

Baedeker's
NORTHERN ITALY.

BAEDEKER'S GUIDE BOOKS.

1 German mark (formerly 10 sgr. Prussian, or 35 kr. S. German) is equivalent to 1 shilling English, 25 cents American, 1 fr. 25 c. French, 50 kr. Austrian, 59 cents Dutch, 31 kopeks Russian.

BELGIUM AND HOLLAND, with 6 Maps and 15 Plans.

Fourth Edition. 1875.

5 marks.

THE RHINE FROM ROTTERDAM TO CONSTANCE (THE

SEVEN MOUNTAINS, VALLEY OF THE AHR, NIEDERWALD, MOSELLE, VOLCANIC EIFEL, VOSGES Mts., PALATINATE, BLACK FOREST, etc.), with 15 Maps and 16 Plans. Fifth Edition. 1873.

5 marks.

NORTHERN GERMANY AS FAR AS THE BAVARIAN AND AUSTRIAN FRONDIERS, with 15 Maps and 27 Plans. Sixth Edition.

Editor 1877

5 marks.

SOUTHERN

EASTERN
and 27

NORTHERN

RAVE
ITALY
and 30

CENTRAL


a Pan

SOUTHERN

LIPAI
AND C

PARIS AND

TO PA
2 Maps and 12 Plans. Fifth Edition.



SYRIA, INCLUDING THE
ARABIA, etc.), with 28 Maps
8 marks.

**ROME, FLORENCE,
CORSIKA, AND ROUTES TO
AND AUSTRIA**, with 8 Maps
6 marks.

**AND 7 Maps, 23 Plans and
1877.** 6 marks.

**EXCURSIONS TO THE
SICILY, SARDINIA, MALTA,
Sixth Edition. 1877.** 6 marks.

**AND ROUTES FROM LONDON
TO SWITZERLAND**, with
1876. 5 marks.

**SWITZERLAND), AND THE ADJACENT PARTS OF ITALY,
SAVOY, AND THE TYROL**, with 24 Maps, 10 Plans and 7 Panoramas.
Seventh Edition. 1877. 7 marks.

**THE EAST. LOWER EGYPT, THE SYDNEY AND THE
PENINSULA OF MOUNT SINAI**, with 16 Maps, 29 Plans, 7 Views
and 76 Woodcuts. In preparation for the autumn.

— **PALESTINE AND SYRIA**, with 18 Maps, 44 Plans,
1 Panorama of Jerusalem and 10 Views. 1876. 20 marks.

**THE TRAVELLER'S MANUAL OF CONVERSATION IN
ENGLISH, GERMAN, FRENCH AND ITALIAN.** Twenty second Edition. 1876.
3 marks.

NORTHERN ITALY.

MONEY - TABLE.
(Comp. p. xii.)


Approximate Equivalents.

Italian.		American.		English.			German.		Austrian.	
<i>Lire.</i>	<i>Cent.</i>	<i>Doll.</i>	<i>Cts.</i>	<i>L.</i>	<i>S.</i>	<i>D.</i>	<i>Mk.</i>	<i>Pfg.</i>	<i>Fl.</i>	<i>Kr.</i>
—	5	—	1	—	—	$1\frac{1}{2}$	—	4	—	2
—	25	—	5	—	—	$2\frac{1}{2}$	—	20	—	10
—	50	—	10	—	—	5	—	40	—	20
—	75	—	15	—	—	$7\frac{1}{4}$	—	60	—	30
1	—	—	20	—	—	$9\frac{3}{4}$	—	80	—	40
2	—	—	40	—	1	$7\frac{1}{4}$	1	60	—	80
3	—	—	60	—	2	5	2	40	1	20
$\frac{1}{4}$	—	—	80	—	3	$2\frac{1}{2}$	3	20	1	60
5	—	1	—	—	4	—	4	—	2	2
6	—	1	20	—	4	$9\frac{3}{4}$	4	80	2	40
7	—	1	40	—	5	$7\frac{1}{2}$	5	60	2	80
8	—	1	60	—	6	5	6	40	3	20
9	—	1	80	—	7	$2\frac{1}{2}$	7	20	3	60
10	—	2	—	—	8	—	8	—	4	—
11	—	2	20	—	8	$9\frac{3}{4}$	8	80	4	40
12	—	2	40	—	9	$7\frac{1}{2}$	9	60	4	80
13	—	2	60	—	10	5	10	40	5	20
14	—	2	80	—	11	$2\frac{1}{2}$	11	20	5	60
15	—	3	—	—	12	—	12	—	6	—
16	—	3	20	—	12	$9\frac{3}{4}$	12	80	6	40
17	—	3	40	—	13	$7\frac{1}{2}$	13	60	6	80
18	—	3	60	—	14	5	14	40	7	20
19	—	3	80	—	15	$2\frac{1}{2}$	15	20	7	60
20	—	4	—	—	16	—	16	—	8	—
25	—	5	—	—	1	—	20	—	10	—
100	—	20	—	—	$\frac{1}{4}$	—	80	—	40	—

DISTANCES. Since the consolidation of the Kingdom of Italy the French *mètre* system has been in use throughout the country, but the old Italian *miglio* (pl. *le miglia*) is still sometimes preferred to the new *kilomètre*. One kilomètre is equal to 0.62138, or nearly $\frac{3}{5}$ ths, of an English mile. The Tuscan *miglio* is equal to 1.65 kilomètre or 1 M. 44 yds.; the Roman *miglio* is equal to 1.49 kilomètre or 1630 yds.

NORTH ITALY

1:1900,000



ITALY.

HANDBOOK FOR TRAVELLERS

BY

K. BAEDER.

FIRST PART:

NORTHERN ITALY,

INCLUDING

LEGHORN, FLORENCE, RAVENNA, THE ISLAND
OF CORSICA,

AND

ROUTES THROUGH FRANCE, SWITZERLAND, AND AUSTRIA.

WITH 8 MAPS AND 30 PLANS.

FOURTH REMODELLED EDITION.

~~~~~

LEIPSIC: KARL BAEDER.  
LONDON: DULAU AND CO. 37 SOHO SQUARE, W.

1877.

*All rights reserved.*

'Go, little book, God send thee good passage,  
And specially let this be thy prayere  
Unto them all that thee will read or hear,  
Where thou art wrong, after their help to call,  
Thee to correct in any part or all.'

CHAUCER.

## P R E F A C E.

---

The objects of the Handbook for Italy, which consists of three volumes, each complete in itself, are to supply the traveller with some information regarding the culture and art of the people he is about to visit, as well as regarding the natural features of the country, to render him as independent as possible of the services of guides and valets-de-place, to protect him against extortion, and in every way to aid him in deriving enjoyment and instruction from his tour in one of the most fascinating countries in the world. The Handbook will also, it is hoped, be the means of saving the traveller many a trial of temper; for there is probably no country in Europe where the patience is more severely taxed than in some parts of Italy.

The Handbook is founded on the Editor's personal acquaintance with the places described, which he periodically revisits for the purpose of obtaining the newest information; and he is indebted to the kindness of a number of his English readers for many valuable suggestions and corrections, of which he has gratefully availed himself. The Editor will as heretofore highly appreciate any new information with which travellers may favour him, but he regrets that he cannot undertake to answer all communications.

The present volume, corresponding to the eighth German edition, has, like its predecessor, been thoroughly revised and considerably augmented. Its contents have been divided into groups of routes arranged historically and geographically (*Piedmont, Liguria, Lombardy, Venetia, The Emilia, and Tuscany*), each section being provided with a prefatory outline of the history of the district. To *Professor A. Springer* the Editor is indebted for the introductory article on Art, which has special reference to Northern Italy and Florence, and for



most of the art-historical notices prefixed to the description of the larger towns and the principal picture-galleries.

The MAPS and PLANS, upon which special care has been bestowed, will abundantly suffice for the use of the ordinary traveller.

HEIGHTS are given in English feet (1 Engl. ft. = 0,3048 mètre), and DISTANCES in English miles (comp. p. ii).

HOTELS (comp. p. xviii). In no country does the treatment which the traveller experiences at hotels vary more than in Italy, and attempts at extortion are perhaps nowhere so outrageous. Besides the modern palatial and expensive establishments, the Handbook also contains a selection of modest, old-fashioned inns, which not unfrequently afford good accommodation at moderate charges. The asterisks indicate those hotels which the Editor has reason to believe from his own experience, as well as from information supplied by numerous travellers, to be respectable, clean, and reasonable. The value of these asterisks, it need hardly be observed, varies according to circumstances, those prefixed to town hotels and village inns signifying respectively that the establishments are good of their kind. At the same time the Editor does not doubt that comfortable quarters may occasionally be obtained at inns which he has not recommended or even mentioned. Although changes frequently take place, and prices generally have an upward tendency, the average charges stated in the Handbook will enable the traveller to form a fair estimate of his probable expenditure.

To hotel proprietors, tradesmen, and others the Editor begs to intimate that a character for fair dealing and courtesy towards travellers forms the sole passport to his commendation.

---

# CONTENTS.

## Introduction.

|                                                            | Page  |
|------------------------------------------------------------|-------|
| I. Travelling Expenses. Money . . . . .                    | xi    |
| II. Period and Plan of Tour . . . . .                      | xiii  |
| III. Language . . . . .                                    | xiv   |
| IV. Passports. Custom-house. Luggage . . . . .             | xv    |
| V. Bandits. Beggars . . . . .                              | xv    |
| VI. Prices and Gratuities . . . . .                        | xvi   |
| VII. Railways . . . . .                                    | xvii  |
| VIII. Hotels . . . . .                                     | xviii |
| IX. Restaurants. Cafés, Osterie . . . . .                  | xix   |
| X. Sights, Theatres, etc. . . . .                          | xxi   |
| XI. Post Office. Telegraph . . . . .                       | xxii  |
| XII. Climate. Health. . . . .                              | xxii  |
| XIII. Dates of Recent Events . . . . .                     | xxiii |
| XIV. History of Art, by <i>Prof. A. Springer</i> . . . . . | xxv   |

(The principal matters and persons mentioned in this article are embraced in the general Index at the end of the volume.)

## I. Routes to Italy.

| Route                                                                                          | Page |
|------------------------------------------------------------------------------------------------|------|
| 1. From Paris to Nice by Lyons and Marseilles . . . . .                                        | 1    |
| 1. From Strassburg (Bâle) to Lyons . . . . .                                                   | 4    |
| 2. From Geneva to Lyons . . . . .                                                              | 5    |
| 3. Vaucluse . . . . .                                                                          | 10   |
| 4. From Tarascon to St. Remy . . . . .                                                         | 12   |
| 5. From Tarascon to Nimes and Montpellier . . . . .                                            | 12   |
| 6. Hyères . . . . .                                                                            | 19   |
| 2. From Paris ( <i>Geneva</i> ) to Turin by Mont Cenis . . . . .                               | 21   |
| 1. From Geneva to Culoz . . . . .                                                              | 22   |
| 2. From Bussoleno to Susa . . . . .                                                            | 24   |
| 3. From Martigny to Arona on the Lago Maggiore ( <i>and Milan</i> ) over the Simplon . . . . . | 25   |
| 4. From Lucerne to Locarno and Lugano ( <i>Milan</i> ) over the St. Gotthard . . . . .         | 27   |
| 5. From Coire to Colico ( <i>and Milan</i> ) over the Splügen . . . . .                        | 33   |
| 6. From Coire to Bellinzona. Bernardino Pass . . . . .                                         | 37   |
| 7. From Innsbruck to Colico ( <i>and Milan</i> ) over the Stelvio . . . . .                    | 38   |
| 8. From Innsbruck to Verona by the Brenner . . . . .                                           | 44   |
| 1. From Trent to Riva on the Lago di Garda . . . . .                                           | 48   |
| 2. From Trent to Venice by the Val Sugana . . . . .                                            | 48   |
| 9. From Vienna to Trieste. Semmering Railway . . . . .                                         | 50   |

| Route                                                                                           | Page |
|-------------------------------------------------------------------------------------------------|------|
| <b>II. Piedmont</b>                                                                             |      |
| 10. Turin . . . . .                                                                             | 60   |
| 1. The Superga . . . . .                                                                        | 71   |
| 2. From Turin to Torre Luserna by Pignerol . . . . .                                            | 72   |
| 11. From Turin to Aosta . . . . .                                                               | 72   |
| 12. From Turin to Milan by Novara . . . . .                                                     | 75   |
| 1. From Santhià to Biella . . . . .                                                             | 75   |
| 2. From Vercelli to Alessandria . . . . .                                                       | 75   |
| 3. From Novara to Gozzano . . . . .                                                             | 76   |
| 13. From Turin to Piacenza by Alessandria . . . . .                                             | 76   |
| From Tortona to Novi . . . . .                                                                  | 76   |
| 14. From Turin to Genoa . . . . .                                                               | 77   |
| a. Vià Alessandria . . . . .                                                                    | 77   |
| 1. From Asti to Mortara (Milan) . . . . .                                                       | 78   |
| 2. From Alessandria to Savona . . . . .                                                         | 78   |
| b. Vià Brà and Savona . . . . .                                                                 | 79   |
| 1. Carignano . . . . .                                                                          | 79   |
| 2. From Cavallermaggiore to Alessandria . . . . .                                               | 80   |
| 3. From Carrù to Mondovì . . . . .                                                              | 80   |
| <b>III. Liguria</b>                                                                             |      |
| 15. Genoa . . . . .                                                                             | 81   |
| 16. From Genoa to Nice. Riviera di Ponente . . . . .                                            | 95   |
| 17. Nice and its Environs . . . . .                                                             | 104  |
| 18. From Nice to Turin by the Col di Tenda . . . . .                                            | 110  |
| 1. Certosa di Val Pesio. Baths of Valdieri . . . . .                                            | 112  |
| 2. From Savigliano to Saluzzo . . . . .                                                         | 112  |
| 19. From Genoa to Pisa. Riviera di Levante . . . . .                                            | 112  |
| From Avenza to Carrara . . . . .                                                                | 116  |
| <b>IV. Lombardy</b>                                                                             |      |
| 20. Milan . . . . .                                                                             | 118  |
| 21. From Milan to Lecco or Como. The Brianza . . . . .                                          | 134  |
| 22. Lake of Como . . . . .                                                                      | 137  |
| The Lake of Lecco. . . . .                                                                      | 144  |
| 23. From the Lake of Como to the Lago Maggiore. Varese. Lugano and the Lake of Lugano . . . . . | 145  |
| 1. From Como to Laveno by Varese . . . . .                                                      | 145  |
| 2. From Como to Luino by Lugano . . . . .                                                       | 147  |
| 3. From Menaggio by Porlezza to Lugano . . . . .                                                | 150  |
| 24. Lago Maggiore. From Arona to Milan and to Genoa . . . . .                                   | 155  |
| 1. From Arona to Milan . . . . .                                                                | 161  |
| 2. From Arona to Genoa . . . . .                                                                | 161  |
| 3. From Milan by Vigevano to Mortara (Genoa) . . . . .                                          | 161  |
| 25. From Stresa to Varallo. Monte Motterone. Lake of Orta . . . . .                             | 162  |
| 26. From Milan to Voghera ( <i>Genoa</i> ) by Pavia. Certosa di Pavia . . . . .                 | 161  |
| 1. From Pavia to Alessandria vià Valenza . . . . .                                              | 164  |
| 2. From Pavia to Brescia vià Cremona . . . . .                                                  | 164  |
| 3. From Pavia to Piacenza vià Codogno . . . . .                                                 | 165  |
| 27. From Milan to Mantua vià Cremona . . . . .                                                  | 165  |
| From Cremona to Piacenza . . . . .                                                              | 166  |

| Route                                                                                | Page          |
|--------------------------------------------------------------------------------------|---------------|
| 28. From Milan to Verona. Bergamo . . . . .                                          | 167           |
| 29. Brescia . . . . .                                                                | 169           |
| 30. From Brescia to Tirano in the Valtellina. Lago d'Iseo.<br>Monte Aprica . . . . . | 174           |
| 31. The Lago di Garda . . . . .                                                      | 177           |
| From Riva to Mori. Excursions from Riva . . . . .                                    | 179           |
| <b>V. Venetia . . . . .</b>                                                          |               |
| 32. Verona . . . . .                                                                 | 182           |
| 33. From Verona to Mantua and Modena . . . . .                                       | 190           |
| 34. From Verona to Venice. Vicenza . . . . .                                         | 195           |
| From Vicenza to Schio. The Baths of Recoaro . . . . .                                | 198           |
| 35. Padua . . . . .                                                                  | 199           |
| 36. Venice . . . . .                                                                 | 204           |
| Murano. Torcello. Chioggia . . . . .                                                 | 244, 245      |
| 37. From Venice to Trieste . . . . .                                                 | 245           |
| a. By Land, viâ Udine . . . . .                                                      | 245           |
| Villa Masèr. Belluno. Aquileia . . . . .                                             | 248, 250      |
| b. Sea Voyage to Trieste . . . . .                                                   | 248           |
| <b>VI. The Emilia . . . . .</b>                                                      |               |
| 38. From Milan to Bologna. Piacenza. Reggio . . . . .                                | 250           |
| Bobbio. Velleia. Correggio. Canossa . . . . .                                        | 252, 254, 255 |
| 39. Parma . . . . .                                                                  | 255           |
| 40. Modena . . . . .                                                                 | 260           |
| Vignôla. Road from Modena to Pistoja . . . . .                                       | 263           |
| 41. From Padua to Bologna . . . . .                                                  | 263           |
| Monti Euganei. Adria. Cento . . . . .                                                | 263, 265      |
| 42. Ferrara . . . . .                                                                | 265           |
| 43. Bologna . . . . .                                                                | 270           |
| 44. From Bologna to Ravenna . . . . .                                                | 284           |
| 45. From Bologna to Florence . . . . .                                               | 294           |
| <b>VII. Tuscany . . . . .</b>                                                        |               |
| 46. From ( <i>Genoa</i> ) Leghorn to Florence by Pisa and Empoli . . . . .           | 299           |
| 47. Pisa . . . . .                                                                   | 302           |
| 48. From Pisa to Florence by Lucca and Pistoja . . . . .                             | 312           |
| The Baths of Lucca . . . . .                                                         | 316           |
| 49. Florence . . . . .                                                               | 323           |
| 50. Environs of Florence . . . . .                                                   | 382           |
| a. Viale dei Colli. Piazzale Michelangelo . . . . .                                  | 383           |
| b. S. Miniato . . . . .                                                              | 383           |
| c. Poggio Imperiale. Torre del Gallo. Villa del Galileo . . . . .                    | 384           |
| d. Certosa in the Val d'Ema . . . . .                                                | 385           |
| e. Bello Sguardo . . . . .                                                           | 386           |
| f. Monte Oliveto . . . . .                                                           | 386           |
| g. The Cascine. Villa Careggi. Villa Petraja . . . . .                               | 387           |
| h. Fiesole . . . . .                                                                 | 387           |
| i. Monastery of S. Salvi . . . . .                                                   | 389           |
| k. Vallombrosa . . . . .                                                             | 390           |
| l. Camaldoli and Alvernia. The Casentino . . . . .                                   | 390           |

| Route                                                                 | Page       |
|-----------------------------------------------------------------------|------------|
| <b>VIII. Corsica . . . . .</b>                                        | <b>394</b> |
| Ajaccio . . . . .                                                     | 396        |
| From Ajaccio to S. Bonifacio, and to Bastia by the E. Coast . . . . . | 398        |
| From Ajaccio to Bastia . . . . .                                      | 399        |
| Corte and the Monte Rotondo . . . . .                                 | 400        |
| Bastia . . . . .                                                      | 401        |
| From Bastia to Capo Corso, S. Fiorenzo and Calvi . . . . .            | 402        |
| Index . . . . .                                                       | 403        |

### Maps and Plans.

1. GENERAL MAP OF N. ITALY: before the title-page.
2. ENVIRONS OF NICE: between pp. 108, 109.
3. LAKES OF COMO AND OF LUGANO: between pp. 138, 139.
4. LAGO MAGGIORE AND LAGO D'ORTA: between pp. 154, 155.
5. LAGO DI GARDA: between pp. 176, 177.
6. ENVIRONS OF FLORENCE: between pp. 382, 383.
7. ISLAND OF CORSICA: between pp. 394, 395.
8. RAILWAY MAP OF N. ITALY: after the Index.

Plans of: —

1. AVIGNON. 2. BERGAMO. 3. BOLOGNA. 4. BRESCIA. 5. CREMONA. 6. FERRARA. 7. FLORENCE. 8. GENOA. 9. LEGHORN. 10. LUCCA. 11. LYONS.
12. MANTUA. 13. MARSEILLES. 14. MILAN. 15. MODENA. 16. NICE.
17. NIMES. 18. PADUA. 19. PARMA. 20. PAVIA. 21. PIACENZA. 22. PISA.
23. PISTOJA. 24. RAVENNA. 25. REGGIO. 26. TRIESTE. 27. TURIN.
28. VENICE. 29. VERONA. 30. VICENZA.

### Abbreviations.

M. = Engl. mile; hr. = hour; min. = minute; r. = right; l. = left; N. = north, northwards, northern; S. = south, etc.; E. = east, etc.; W. = west, etc.; R. = room; B. = breakfast; D. = dinner; A. = attendance; L. = light.

### Asterisks

denote objects deserving of special attention.

---

## INTRODUCTION.

---

'Thou art the garden of the world, the home  
Of all Art yields, and Nature can decree;  
E'en in thy desert, what is like to thee?  
Thy very weeds are beautiful, thy waste  
More rich than other climes' fertility,  
Thy wreck a glory, and thy ruin graced  
With an immaculate charm which cannot be defaced.'

BYRON.

From the earliest ages down to the present time Italy has ever exercised a powerful influence on the denizens of more northern lands, and a journey thither has often been the fondly cherished wish of many an aspiring traveller. That wish may now be gratified with comparative facility. A great network of railways now over-spreads the entire peninsula; and even the more remote towns may be visited with little sacrifice of time. Northern Italy, in particular, with Milan, Venice, and Genoa, is of very easy access from France, Switzerland, or the Tyrol; and although its attractions are doubtless inferior to those of Florence, Rome, and Naples, it is replete with interest and instruction for the ordinary traveller, as well as for the scientific. The facilities for travelling have also been much increased by the recent introduction of various reforms. A single monetary system has superseded the numerous and perplexing varieties of coinage formerly in use; the annoyance inseparable from passport and custom-house formalities, with which the traveller was assailed at every frontier, and even in many an insignificant town, has been greatly mitigated; and energetic measures have been adopted to repress the extortionate practices of vetturini, facchini, and other members of this class.

### I. Travelling Expenses. Money.

**Expenses.** The cost of a tour in Italy depends of course on the traveller's resources and habits, but, as a rule, it need not exceed that incurred in other much frequented parts of the continent. The average expenditure of a single traveller, when in Italy, may be estimated at 25-30 francs per day, or at 12-15 francs when a prolonged stay is made at one place; but persons acquainted with the language and habits of the country may easily restrict their expenses to still narrower limits. Those who travel as members of a party effect a considerable saving by sharing the expense of guides, carriages, and other items. When ladies are of the party, the expenses are generally greater.

**Money.** The French monetary system is now in use throughout the whole of Italy. The franc (*lira* or *franco*) contains 100 *centesimi*: 1 fr. 25 c. = 1 s. = 1 German mark = 50 Austrian *kreuzers*. The precious metals are rarely seen in Italy. In copper (*bronz* or *rame*) there are coins of 1, 2, 5, and 10 *centesimi*. A piece of 5 c. is called a *soldo*, or *sou*, and as the lower classes often keep their accounts in *soldi*, the traveller will find it useful to accustom himself to this mode of reckoning. See also the Money Table opposite the title-page.

**BANKNOTES.** Since the introduction of a paper currency during the war of 1866, at a compulsory rate of exchange, gold and silver have entirely disappeared from ordinary circulation, and bulky bundles of small notes have taken their place. For these the purses used in most other countries are quite unsuitable, but one adapted for the purpose may be bought in Italy for  $1\frac{1}{2}$ -2 fr.; in addition to which a strong pouch for copper will be found useful. By a law passed in 1874 for the regulation of the paper currency, the right of issuing banknotes is restricted to six banks, the *Banca Nazionale*, the *Banca Nazionale Toscana*, the *Banca Toscana Industriale Commerciale*, the *Banca Romana*, the *Banca di Napoli*, and the *Banca di Sicilia*, the notes of which pass in every province where these banks have branch offices. Besides these notes, there are the *Biglietti Consorziati* ( $\frac{1}{2}$ , 1, 2, 5, 10, and 20 *lire*), issued by the above six banks in common, available throughout the whole country, and intended gradually to supersede the others entirely. As the Roman and provincial notes do not often realise their full value beyond the limits of their respective provinces, the traveller should always secure notes of the *Banca Nazionale* or *Biglietti Consorziati* if possible. Besides these, the notes of the Tuscan banks are of course current in Florence and Tuscany. (The *Banca di Napoli* has a branch at Milan, but in ordinary business and at the railway-stations its notes are usually rejected.) The traveller should decline to take soiled or imperfect notes, and be on his guard against the forged imitations which are occasionally met with.

**EXCHANGE.** English circular notes, as well as gold and silver, are worth considerably more than Italian banknotes of nominally the same value. In the spring of 1877 the gain on the exchange averaged 8 per cent (a *napoleon*, for example, realising about  $2\frac{1}{2}$  fr., and a *sovereign* 27 fr.). If the traveller makes a payment in gold he is entitled to decline receiving banknotes in exchange, unless the difference in value be taken into account, but the full rate of exchange is rarely given except by respectable money-changers ('*cambiavaluta*'). As a rule, those money-changers are the most satisfactory who publicly exhibit a list of the current rates of exchange. The traveller should always be provided with an abundant supply of small notes (1, 2, and 5 fr.), as it is often difficult to change those of large amount. When a railway fare has to be paid it is a

wise precaution to be provided with the exact sum beforehand in order that mistakes or imposition may be prevented. Besides the small notes, 1-1½ fr. in copper should also be carried in a separate pocket or pouch.

**BEST MONEY FOR THE TOUR.** *Circular Notes*, obtainable at the principal English banks, form the proper medium for the transport of large sums, and realise the most favourable exchange. English and German banknotes also realise more than their nominal value. A moderate supply of *French Gold*, to be used on the homeward journey from Italy, will also be found desirable. *Sovereigns* are received at the full value (about 27 fr.) by the principal hotel-keepers, but not in out-of-the-way places.

## II. Period and Plan of Tour.

**Season.** As a general rule the spring and autumn months are the best season for a tour in N. Italy, especially May and September, before or after the heat of summer has attained its climax. Winter in Lombardy and Piedmont is generally a much colder season than it is in England, but Nice and the whole of the Riviera, Pisa, and Venice afford pleasant and sheltered quarters. The height of summer can hardly be recommended for travelling. The scenery, indeed, is then in perfection, and the long days are hailed with satisfaction by the enterprising traveller; but the fierce rays of an Italian sun seldom fail to impair the physical and mental energies. This result is not occasioned so much by the intensity as by the protracted duration of the heat, the sky being frequently cloudless and not a drop of rain falling for many weeks in succession. The heat generally moderates about the end of August, when the first showers of autumn begin to refresh the parched atmosphere.

**Plan.** The traveller's movements must of course be regulated in accordance with the objects he has in view, and with the time and money at his command. The chief centres of attraction in N. Italy are Milan, Venice, Genoa, and Florence. The following short itinerary, beginning at Turin and ending at Nice, though very far from exhaustive of the beauties of N. Italy, includes most of the places usually visited, with the time required for a glimpse at each.

|                                                                                                                                  | Days |
|----------------------------------------------------------------------------------------------------------------------------------|------|
| From <i>Turin</i> (R. 10) to the <i>Lago Maggiore</i> , <i>Lago di Lugano</i> ,<br>and <i>Lago di Como</i> (RR. 21-24) . . . . . | 3    |
| To <i>Milan</i> (R. 29) and excursion to <i>Pavia</i> (the Certosa.<br>R. 26) . . . . .                                          | 2    |
| From <i>Milan</i> viâ <i>Bergamo</i> and <i>Brescia</i> to <i>Verona</i> (R. 32) . . . . .                                       | 1    |
| Excursion from <i>Desenzano</i> or <i>Verona</i> to the <i>Lago di Garda</i><br>(R. 31) . . . . .                                | 1    |



|                                                                                                                                              | Days |
|----------------------------------------------------------------------------------------------------------------------------------------------|------|
| From Verona to <i>Padua</i> (R. 34) . . . . .                                                                                                | 1    |
| From <i>Padua</i> to <i>Venice</i> (R. 36) . . . . .                                                                                         | 4    |
| From <i>Venice</i> viâ <i>Ferrara</i> to <i>Bologna</i> (R. 45) . . . . .                                                                    | 2    |
| Excursions from <i>Bologna</i> to <i>Ravenna</i> (R. 44), 1½ day, and<br>to <i>Modena</i> (R. 40) and <i>Parma</i> (R. 39), 1½ day . . . . . | 3    |
| From <i>Bologna</i> to <i>Florence</i> (R. 49) . . . . .                                                                                     | 7    |
| From <i>Florence</i> to <i>Pisa</i> (R. 47) . . . . .                                                                                        | 1    |
| From <i>Pisa</i> to <i>Genoa</i> (R. 15), and excursion to <i>Pegli</i> (Villa<br>Pallavicini, p. 96) . . . . .                              | 2    |
| From <i>Genoa</i> to <i>Nice</i> (R. 16) . . . . .                                                                                           | 1    |

The traveller who enters Italy from Switzerland or Austria, or intends to return through either of these countries, will have no difficulty in framing his itinerary with the aid of the map. The *Simplon*, the *St. Gotthard*, the *Bernardino*, the *Splügen*, the *Stelvio*, and the *Brenner* are all interesting routes, of which the *St. Gotthard* and the *Stelvio* are generally considered the finest in point of scenery, while the *Brenner*, being traversed by a railway, is the most convenient.

The luxurious character of the Italian climate, vegetation, and scenery, the soft richness of the language, and the courtier manners of the upper classes will strike the traveller most forcibly if he approaches Italy for the first time from German Switzerland. the characteristics of which are of a harsher and rougher type. In this case he is recommended to quit the country viâ *Nice* (1 day), *Cannes* (½ day), *Marseilles* (1 day), *Arles* (½ day), *Nimes* (1 day), *Avignon* (1 day), and *Lyons* (R. 1), all of which are worthy of a visit, even after Italy.

### III. Language.

The time and labour which the traveller has bestowed on the study of Italian at home will be amply repaid as he proceeds on his journey. It is quite possible for persons entirely ignorant of Italian and French to travel through Italy with tolerable comfort; but such travellers cannot conveniently deviate from the ordinary track, and are moreover invariably made to pay '*alla Inglese*' by hotel-keepers and others, i. e. considerably more than the ordinary charges. French is very useful, as the Italians are very partial to that language, and it may suffice for Rome and some of the main routes; but for those who desire the utmost possible freedom, and who dislike being imposed upon, a slight acquaintance with the language of the country is indispensable. †

† 'Baedeker's *Manual of Conversation in English, French, German, and Italian, with Vocabulary, etc.*' (22nd Edit., Baedeker, Leipsic), which is specially adapted for the use of travellers, with the addition of a pocket-dictionary, will soon enable the beginner to make himself understood. — A few words on the *pronunciation* may be acceptable to persons unacquainted with the language. *C* before *e* and *i* is pronounced like the

#### IV. Passports. Custom-House. Luggage.

**Passports**, though not required in Italy, are occasionally useful. Registered letters, for example, will not be delivered to strangers, unless they exhibit a passport to prove their identity. In the remote districts, too, where the public safety demands a more rigorous supervision, the traveller is sometimes asked for his credentials. The Italian police authorities are generally civil and obliging.

**Custom-House.** The examination of luggage at the Italian custom-houses is generally lenient. Tobacco and cigars are the articles chiefly sought for. At the gates of most of the Italian towns a tax (*dazio consumo*) is levied on comestibles, but travellers' luggage is passed at the barriers (*limite daziario*) on a simple declaration that it contains no such articles.

**Luggage.** If possible, luggage should never be sent to Italy by goods-train, as it is liable to damage, pilferage, and undue custom-house detention. If the traveller is obliged to forward it in this way, he should employ a trustworthy agent at the frontier and send him the keys. As a rule it is advisable, and often in the end less expensive, never to part from one's luggage, and to superintend the custom-house examination in person.

#### V. Bandits. Beggars.

**Bandits.** Italy is still sometimes regarded as the land of Fra Diavolo's and Rinaldo Rinaldini's, and the impression is fostered by tales of travellers and sensational letters to newspapers; but at the present day travelling in Northern and Central Italy is hardly attended with more hazard than in any of the more northern European countries. For information as to the safety of the roads the traveller should apply to the *Carabinieri*, or *gensdarmes* (who wear a black uniform, with red facings and white shoulder-straps, and cocked hats), a respectable and trustworthy corps, the strength of which was raised in 1874 from 1900 to 3297 men.

**Begging**, which was countenanced and encouraged under the old system of Italian politics, still continues to be one of those national nuisances to which the traveller must habituate himself. The present government has adopted energetic measures for its suppression, but hitherto with only partial success. The average Italian

---

English *ch*; *g* before *e* and *i* like *j*. Before other vowels *c* and *g* are hard. *Ch* and *gh*, which generally precede *e* or *i*, are hard. *Sc* before *e* or *i* is pronounced like *sh*; *gn* and *gl* between vowels like *ny* and *ly*. The vowels *a*, *e*, *i*, *o*, *u* are pronounced *ah*, *ā*, *ee*, *o*, *oo*. — In addressing persons of the educated classes 'Ella' or 'Lei', with the 3rd pers. sing., should always be employed (addressing several at once, 'loro' with the 3rd pers. pl). 'Voi' is used in addressing waiters, drivers, etc., 'tu' by those only who are proficient in the language. 'Voi' is the usual mode of address among the Neapolitans, but is generally regarded as inelegant or uncourteous.

beggar is a mere speculator, and not a deserving object of charity. The traveller should therefore decline to give anything, with the words, 'non c'è niente', or a gesture of refusal. If a donation be bestowed, it should consist of the smallest possible copper coin. A beggar, who on one occasion was presented with 2c. and thanked the donor with the usual benedictions, was on another presented with 50 c., but this act of liberality, instead of being gratefully accepted, only called forth the remark in a half-offended tone: 'Ma. Signore, è molto poco!'

## VI. Prices and Gratuities.

Italian sellers are very apt to demand a much higher price than they will ultimately accept; but a knowledge of the custom, which is based upon the presumed ignorance of one of the contracting parties, practically neutralises its effect. Where tariffs and fixed charges exist, they should be carefully consulted; and when a certain average price is established by custom, the traveller should make a precise bargain with respect to the article to be bought or the service to be rendered, and never rely on the equity of the other party. In cases of dispute the traveller who is not thoroughly acquainted with the language should be careful not to engage in a war of words in which he is necessarily at a great disadvantage.

Many shops now profess to have fixed prices, but even in these cases it is usual to offer two-thirds or three-quarters only of the price demanded. The same rule applies to artizans, drivers, and others. '*Non volete?*' (then you will not?) is a remark which generally has the effect of bringing the matter to a speedy adjustment. Purchases should never be made by the traveller when accompanied by a *valet-de-place*. These individuals, by tacit agreement, receive from the seller at least 10 per cent of the purchase-money, a bonus which of course comes out of the pocket of the purchaser.

The traveller should always be abundantly supplied with copper coin in a country where trifling donations are in constant demand. Drivers, guides, and other persons of the same class invariably expect, and often demand as their right, a gratuity (*buona mano, mancia, da bere, bottiglia, caffè, fumata*) in addition to the hire agreed on, varying according to circumstances from 2-3 sous to a franc or more. The traveller need have no scruple in limiting his donations to the smallest possible sums, as liberality frequently becomes a source of annoyance and embarrassment. Thus, if half-a-franc is bestowed where two sous would have sufficed, the fact speedily becomes known, and the donor is sure to be besieged by numerous other applicants whose demands it is impossible to satisfy.

In Northern Italy the traveller will now find comparatively few causes for complaint, as the system of fixed charges is gradually being introduced at the hotels and the shops. He will generally

find the people with whom he comes in contact civil and obliging, and if he has some acquaintance with the language he will rarely meet with attempts at extortion.

### VII. Railways.

Northern Italy is now overspread with so complete a network of railways that the traveller will seldom use any other conveyance, except on the Alpine routes and on the lakes. The rate of travelling is very moderate, and the trains are often behind time. The first class carriages are tolerably comfortable, the second are inferior to those of the German railways, and resemble the English and French, while the third class is chiefly frequented by the lower orders. Among the expressions with which the railway-traveller will soon become familiar are — '*pronti*' (ready), '*partenza*' (departure), '*si cambia convoglio*' (change carriages), and '*uscita*' (egress).

When about to start from a crowded station, the traveller will find it convenient to have as nearly as possible the exact fare ready before taking tickets. In addition to the fare, a tax of 5 c. is payable on each ticket, and the express fares are 10-12½ per cent higher than the ordinary. It is also very important to be at the station early, as, in accordance with the regulations, the ticket-office closes 5 min., and the luggage-office ¼ hr. before the departure of the train. At the end of the journey tickets are given up at the *uscita*, except in the case of the very large stations, where they are collected before the passengers alight.

The traveller should, if possible, know the weight of his luggage approximately, in order to guard against imposition (1 kilogramme = about 2½ lbs.). No luggage is allowed free, except small articles taken by the passenger into his carriage. Porters who convey luggage to and from the carriages are sufficiently paid with a few sous, where there is no fixed tariff. Those who intend to make only a short stay at a place, especially when the town or village lies at a considerable distance from the railway, had better leave their heavier luggage at the station till their return (*dare in deposito*, or *depositare*; 10 c. per day for each article).

The best collection of time-tables is the '*Indicatore Ufficiale delle Strade Ferrate*', etc. (price 1 fr.; small edition 40 c.), with which every traveller should be provided. The local time-tables of the Tuscan, Roman, and Neapolitan lines, which may be procured at the railway-stations for a few sous, are also useful.

THROUGH TICKETS to various parts of Italy are issued in London (at the principal railway stations; by Messrs. Cook & Son, Fleet Street; etc.), in Paris, and at many of the principal towns in Germany and Switzerland. They are generally available for 30 days,

and each passenger is allowed 56 Engl. lbs. of luggage free. Tickets from Italy to Switzerland, Germany, etc. must be partly paid for in gold. Travellers about to cross the frontier in either direction are strongly recommended to superintend the custom-house examination of luggage in person.

**CIRCULAR TICKETS** (*viaggi circolari*) to the principal towns in Italy, available sometimes for 50 days, may be purchased in London, in France, and in Germany, as well as in Italy, at a reduction of 45 per cent (but without a free allowance of luggage). Farther particulars will be found in the time-tables, or at the '*agenzie*', or railway-offices in the larger towns. For Northern Italy there are upwards of twelve different circular tours, for which 10-30 days are allowed. These tickets require to be stamped at the office at each fresh starting-point. If the traveller quits the prescribed route, intending to rejoin it at point farther on, he should give notice of his intention to the *capostazione* of the place where he leaves the railway.

**RETURN TICKETS** may often be advantageously used for short excursions, but they are generally available for one day only. It should also be observed that if the traveller alights at a station short of his destination he forfeits the *whole* of the rest of his ticket.

### VIII. Hotels.

**FIRST CLASS HOTELS**, comfortably fitted up, are to be found at all the principal resorts of travellers in Northern Italy, most of them having fixed charges: room 2½-5 fr., bougie 75 c. to 1 fr., attendance 1 fr., table d'hôte 5 fr., and so on. Families, for whose reception the hotels are often specially fitted up, should make an agreement with the landlord with regard to pension (8-15 fr. each person per day). Visitors are expected to dine at the table d'hôte; otherwise the charge for rooms is apt to be raised. The cuisine is a mixture of French and Italian.

The **SECOND CLASS HOTELS** are thoroughly Italian in their arrangements, and are rarely very clean or comfortable. The charges are little more than one-half of the above. They have no table d'hôte, but there is generally a trattoria connected with the house, where refreshments *à la carte*, or a dinner a *prezzo fisso*, may be procured at any hour. These inns will often be found convenient and economical by the *voyageur en garçon*, and the better houses of this class may even be visited by ladies. As a rule, it is advisable to make enquiries as to charges beforehand. A dinner, for example at 2-3 fr. may be stipulated for, and in arranging as to the charge for a room the *servizio e candela* should not be forgotten. Exorbitant demands may generally be reduced without difficulty to reasonable limits, and even when no previous agreement has been made an extortionate bill may sometimes be successfully

disputed, though not without lively discussion. At the smaller inns a fee of 1 fr. per day is usually divided between the waiter and the facchino, or less for a prolonged stay. Copper coins are never despised by such recipients.

HÔTELS GARNIS and PRIVATE APARTMENTS are recommended for a prolonged stay. A distinct agreement as to rent should be made beforehand. When a whole suite of apartments is hired, a written contract on stamped paper should be drawn up with the aid of some one acquainted with the language and customs of the place (e. g. a banker), in order that 'misunderstandings' may be prevented. For single travellers a verbal agreement with regard to attendance, linen, stoves and carpets in winter, a receptacle for coal, and other details will generally suffice.

The popular idea of cleanliness in Italy is behind the age, dirt being perhaps neutralised in the opinion of the natives by the brilliancy of their climate. The traveller will rarely suffer from this shortcoming in hotels and lodgings of the best class; but those who quit the beaten track must be prepared for privations. In the villages the pig (*animale nero*) appears as a domestic animal, and the poultry also have free access to the houses. Iron bedsteads should if possible be selected, as they are less likely to harbour the enemies of repose. Insect-powder (*polvere di Persia*, or Keating's) or camphor somewhat repels their advances. The *zanzäre*, or gnats, are a source of great annoyance, and often of suffering, during the autumn months. Windows should always be carefully closed before a light is introduced into the room. Light muslin curtains (*zanzariere*) round the beds, masks for the face, and gloves are employed to ward off the attacks of these pertinacious intruders. The burning of insect powder over a spirit lamp is also recommended, and pastilles may be purchased at the principal chemists' for the same purpose.

### IX. Restaurants, Cafés, Osterie.

**Restaurants** (*trattorie*) are chiefly frequented by Italians and gentlemen travelling alone, but those of the better class may be visited by ladies also. Dinner may be obtained *à la carte*, and sometimes *a prezzo fisso*, at any hour between 12 and 7 or 8 p. m., for 2-5 fr.; the waiters expect a gratuity of 2-5 soldi. The diner who wishes to confine his expenses within reasonable limits should refrain from ordering dishes not mentioned in the bill of fare. Besides the old-fashioned *trattorie* a number of 'restaurants' of a better class have recently been opened in some of the larger towns. The cookery is generally French, and the charges and arrangements are similar to those in other European cities. The waiter is called *camerière*, but the approved way of attracting his attention is by knocking on the table.

A late hour for the chief repast of the day should be chosen in

winter, in order that the daylight may be profitably employed, but an early dinner is preferable in summer when the midday heat precludes exertion.

List of the ordinary dishes at the Italian restaurants.

|                                                                             |                                                                             |
|-----------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| <i>Minestra</i> or <i>Zuppa</i> , soup.                                     | <i>Funghi</i> , mushrooms (often too rich).                                 |
| <i>Consumé</i> , broth or bouillon.                                         | <i>Presciutto</i> , ham.                                                    |
| <i>Zuppa alla Santè</i> , soup with green vegetables and bread.             | <i>Salami</i> , sausage.                                                    |
| <i>Gnocchi</i> , small puddings.                                            | <i>Potto</i> , or <i>pottastro</i> , fowl.                                  |
| <i>Riso con piselli</i> , rice-soup with peas.                              | <i>Galotta</i> , turkey.                                                    |
| <i>Hisotto</i> ( <i>alla Milanese</i> ), a kind of rice pudding (rich).     | <i>Umido</i> , meat with sauce.                                             |
| <i>Maccaroni al burro</i> , with butter; <i>al pomodoro</i> , with tomatas. | <i>Stufatino</i> , ragout.                                                  |
| <i>Manzo</i> , boiled beef.                                                 | <i>Legume</i> , vegetables.                                                 |
| <i>Fritto</i> , fried meat.                                                 | <i>Carciofi</i> , artichokes.                                               |
| <i>Frittura mista</i> , a mixture of fried liver, brains, and artichokes.   | <i>Piselli</i> , peas.                                                      |
| <i>Frittata</i> , omelette.                                                 | <i>Lenticchi</i> , lentils.                                                 |
| <i>Arrosto</i> , roasted meat.                                              | <i>Cavoli fiori</i> , cauliflower.                                          |
| <i>Arrosto di vitello</i> , or <i>di mongana</i> , roast-veal.              | <i>Fave</i> , beans.                                                        |
| <i>Bistecca</i> , beefsteak.                                                | <i>Fagiolini</i> , French beans.                                            |
| <i>Coscietto</i> , loin.                                                    | <i>Mostarda</i> , simple mustard.                                           |
| <i>Testa di vitello</i> , calf's head.                                      | <i>Senape</i> , hot mustard.                                                |
| <i>Fegato di vitello</i> , calf's liver.                                    | <i>Ostriche</i> , oysters (good in winter only).                            |
| <i>Braccioletta di vitello</i> , veal-cutlet.                               | <i>Giardinello</i> or <i>frutta</i> , fruit-desert.                         |
| <i>Costoletta alla minola</i> , veal-cutlet with calves' ears and truffles. | <i>Crostata di frutti</i> , fruit-tart.                                     |
| <i>Patate</i> , potatoes.                                                   | <i>Crostata di pasta sfoglia</i> , a kind of pastry.                        |
| <i>Quaglia</i> , quail.                                                     | <i>Fragole</i> , strawberries.                                              |
| <i>Tordo</i> , field-fare.                                                  | <i>Pera</i> , pear.                                                         |
| <i>Lodola</i> , lark.                                                       | <i>Mele</i> , apples.                                                       |
| <i>Sfoglina</i> , a kind of solc.                                           | <i>Persiche</i> , peaches.                                                  |
| <i>Principi alla tavola</i> , or <i>piattini</i> , hot relishes.            | <i>Uva</i> , bunch of grapes.                                               |
|                                                                             | <i>Limone</i> , lemon.                                                      |
|                                                                             | <i>Arancio</i> or <i>portogallo</i> , orange.                               |
|                                                                             | <i>Finocchio</i> , root of fennel.                                          |
|                                                                             | <i>Pane francese</i> , bread made with yeast (the Italian is made without). |
|                                                                             | <i>Formaggio</i> , cacio, cheese.                                           |

WINE (*nero* or *rosso*, red; *bianco*, white; *dolce*, sweet; *asciutto*, dry; *nazionale*, or *del paese*, wine of the country) is usually placed on the table in large bottles at the Tuscan restaurants and charged for according to the quantity drunk. At Rome and some other places the visitor is asked if he wishes *un mezzo litro* or *un quinto* (1/5th litre).

**Cafés** are frequented for breakfast and lunch, and in the evening by numerous consumers of ices.

*Caffè nero*, or coffee without milk, is usually drunk (10-15 c. per cup). *Caffè latte* is coffee mixed with milk before served (20-30 c.); or *caffè e latte*, i. e. with the milk served separately, may be preferred (35-40 c.). *Mischio*, a mixture of coffee and chocolate (20-30 c.), is considered wholesome and nutritious.

The usual viands for lunch are ham, sausages, cutlets, beefsteaks, and eggs (*nova da bere*, soft; *toste*, hard; *nova al piatto*, fried).

Ices (*sorbetto* or *gelato*) of every possible variety are supplied at the cafés at 30-90 c. per portion; or half a portion (*mezzo*) may be ordered. *Granita*, or half-frozen ice (*timonata*, of lemons; *aranciata* of oranges), is much in vogue in the forenoon. The waiters, who expects a sou or more, according to the amount of the payment, are apt to be inaccurate in changing money.

The principal Parisian newspapers are to be found at all the larger cafés, English rarely.

**Wine Shops** (*osterie*), especially at Rome, are a favourite haunt of the lower classes, who bring their own eatables from the *pizzicarolo*, or dealer in comestibles. The rooms are generally dirty and uninviting, but the wine is often good.

**Cigars** in Italy are a monopoly of Government, and bad; those under 3-4 soldi hardly smokable. Good imported cigars may be bought at the best shops in the large towns for 25-60 c. each.

### X. Sights, Theatres, etc.

**Churches** are open in the morning till 12 or 12. 30, and generally again from 4 to 7 p. m. Visitors may inspect the works of art even during divine service, provided they move about noiselessly, and keep aloof from the altar where the clergy are officiating. On the occasion of festivals the works of art are often entirely concealed by the temporary decorations. The verger (*sagrestano*, or *nonzolo*) receives a fee of  $\frac{1}{2}$  fr. or upwards, if his services are required.

**Museums**, picture-galleries, and other collections are usually open from 10 to 3 o'clock. By a law passed in 1875 all the collections which belong to government are open on week-days at a charge of 1 fr., and on Sundays (and sometimes on Thursdays also) gratis. They are closed on the following public holidays: New Year's Day, Epiphany (6th Jan.), the Monday and Tuesday during the Carnival, Palm Sunday, Easter Sunday, Whitsunday and Whitmonday, Fête de Dieu (Corpus Christi), the Festa dello Statuto (first Sunday in June), Assumption of the Virgin (15th Aug.), and on Christmas Day. A good many other days are also sometimes observed as holidays, such as the Thursday before the Carnival and the day sacred to the local patron saint.

**Valets de Place** (*servitori di piazza*) may be hired at 5-6 fr. per day. They are generally respectable and trustworthy, but, as they are seldom good judges of what is really worth seeing, the traveller should specify to them the places he desires to visit. Their services may generally well be dispensed with by those who are not pressed for time. Purchases should never be made, nor contracts with vetturini or other persons drawn up, in presence or with the aid of a commissionaire, as any such intervention tends considerably to increase the prices.

**Theatres.** Performances in the large theatres begin at 8, 8.30, or 9, and terminate at midnight or later, operas and ballets being exclusively performed. The first act of an opera is usually succeeded by a ballet of three acts or more. Verdi is the most popular composer. The pit (*platēa*) is the usual resort of the men, while the boxes and sometimes the stalls (*scanni chiusi*, *sedie chiuse*, *poltrone*, or *posti distinti*) are frequented by ladies. A box (*palco*) must



always be secured in advance. — A visit to some of the smaller theatres, where dramas and comedies are acted, is recommended for the sake of habituating the ear to the language. Performances in summer take place in the open air, in which case smoking is allowed. — The theatre is the usual evening-resort of the Italians, who never observe strict silence during the performance of the orchestra. The instrumental music is rarely good.

### XI. Post Office. Telegraph.

**Letters** (whether '*poste restante*', Italian '*ferma in posta*', or to the traveller's hotel) should be addressed very distinctly, and the name of the place should be in Italian. When asking for letters the traveller should present his visiting card instead of giving his name orally. Postage-stamps (*francobolli*) are sold at the post-offices and at many of the tobacco-shops. — Letters of 15 grammes ( $\frac{1}{2}$  oz., about the weight of three sous) to any of the states included in the postal union (now comprising the whole of Europe) 30 c.; post-card (*cartolina postale*) 15 c.; book-packets 5 c. and upwards, according to weight; registration-fee (*raccomandazione*) 30 c.

Letters by town-post 5 c.; throughout the kingdom of Italy 20 c. prepaid, or 30 c. unpaid. Post-card 10 c.

In the larger towns the post-office is open daily from 8 or 9 a. m. to 10 p. m. (also on Sundays and holidays); in smaller places it is generally closed in the middle of the day for two or three hours.

**Telegram** of 20 words to London 9 fr., to other parts of Great Britain 10 fr., France 4, Germany 5, Switzerland 3, Austria 3 or 4, Belgium 5, Denmark  $7\frac{1}{2}$ . Russia 11, Sweden 8, Norway  $8\frac{1}{2}$  fr. — To America 10 words 50 fr.

Within the kingdom of Italy, 15 words 1 fr., each additional word 10 c.; telegrams with special haste (*telegrammi urgenti*), which take precedence of all others, whether for inland or foreign places, may be sent at five times the above rates.

### XII. Climate. Health.

**Climate.** Most travellers must in some degree alter their mode of living whilst in Italy, without however implicitly adopting the Italian style. Inhabitants of more northern countries generally become unusually susceptible to cold in Italy, and therefore should not omit to be well supplied with warm clothing for the winter. Carpets and stoves, to the comforts of which the Italians generally appear indifferent, are indispensable in winter. A southern aspect in winter is an absolute essential for delicate persons, and highly desirable for the robust. Colds are most easily caught after sunset, and in rainy weather. Even in summer it is a wise precaution not to wear too light clothing.

Exposure to the summer-sun should be avoided as much as possible. According to a Roman proverb, dogs and foreigners (Ingleſi) alone walk in the sun, Christians in the ſhade. Umbrellas, or ſpectacles of coloured glaſs (grey, concave glaſſes to protect the whole eye are beſt), may be uſed with advantage when a walk in the ſun is unavoidable. Blue veils are recommended to ladies. Reſe during the hotteſt hours is adviſable, and a moderate ſieſta is often reſreſhing. Windows ſhould be cloſed at night.

**Health.** Engliſh and German medical men are to be met with in the larger cities. The Italian therapeutic art does not enjoy a very high reputation in the reſt of Europe. Engliſh and German chemiſts, where available, are recommended in preference to the Italian. It may, however, be wiſe, in the caſe of maladies ariſing from local cauſes, to employ native ſkill. Foreigners frequently ſuffer from diarrhœa in Italy, which is generally occaſioned by the unwonted heat. Ice and rice are two of the commoneſt remedies. The homœopathic tincture of camphor may alſo be mentioned. In ſuch caſes, however, thorough reſe is the chief deſideratum.

### XIII. Chronological Table of Recent Events.

- |       |       |     |                                                                                        |
|-------|-------|-----|----------------------------------------------------------------------------------------|
| 1846. | June  | 16. | Election of Pius IX.                                                                   |
| 1848. | March | 18. | Insurrection at Milan.                                                                 |
|       |       | 22. | Charles Albert enters Milan.                                                           |
|       |       | 22. | Republic proclaimed at Venice.                                                         |
|       | May   | 15. | Insurrection at Naples quelled by Ferdinand II. ('Re Bomba').                          |
|       |       | 29. | Radetzky's victory at Curtatone.                                                       |
|       |       | 30. | Radetzky defeated at Goito; capitulation of Peschiera.                                 |
|       | July  | 25. | Radetzky's victory at Custoza.                                                         |
|       | Aug.  | 6.  | Radetzky's victory at Milan.                                                           |
|       |       | 9.  | Armistice.                                                                             |
|       | Nov.  | 15. | Murder of Count Rossi at Rome.                                                         |
|       |       | 25. | Flight of the Pope to Gaeta.                                                           |
| 1849. | Febr. | 5.  | Republic proclaimed at Rome.                                                           |
|       |       | 17. | Republic proclaimed in Tuscany, under Guerazzi.                                        |
|       | March | 16. | Charles Albert terminates the armistice (ten days' campaign).                          |
|       |       | 23. | Radetzky's victory at Novara.                                                          |
|       |       | 24. | Charles Albert abdicates (d. at Oporto on 26th July); accession of Victor Emmanuel II. |
|       |       | 26. | Armistice; Alessandria occupied by the Austrians.                                      |
|       |       | 31. | Haynau conquers Brescia.                                                               |
|       | April | 5.  | Republic at Genoa overthrown by La Marmora.                                            |
|       |       | 11. | Reaction at Florence.                                                                  |
|       |       | 30. | Garibaldi defeats the French under Oudinot.                                            |
|       | May   | 11. | Leghorn stormed by the Austrians.                                                      |
|       |       | 15. | Subjugation of Sicily.                                                                 |
|       |       | 16. | Bologna stormed by the Austrians.                                                      |
|       | July  | 4.  | Rome capitulates.                                                                      |
|       | Aug.  | 6.  | Peace concluded between Austria and Sardinia.                                          |
|       |       | 22. | Venice capitulates.                                                                    |
| 1850. | April | 4.  | Pius IX. returns to Rome.                                                              |
| 1855. |       |     | Sardinia takes part in the Crimean War.                                                |
| 1856. |       |     | Congress at Paris. Cavour raises the Italian question.                                 |
| 1859. | May   | 20. | Battle of Montebello.                                                                  |
|       | June  | 4.  | Battle of Magenta.                                                                     |

1859. June 24. Battle of Solferino.  
 July 11. Meeting of the emperors at Villafranca.  
 Nov. 10. Peace of Zurich.
1860. March 18. Annexation of the Emilia (Parma, Modena, Romagna).  
 22. Annexation of Tuscany.  
 - 24. Cession of Savoy and Nice.  
 May 11. Garibaldi lands at Marsala.  
 27. Taking of Palermo.  
 July 20. Battle of Melazzo.  
 Sept. 7. Garibaldi enters Naples.  
 - 18. Battle of Castellidardo.  
 - 29. Ancona capitulates.  
 Oct. 1. Battle of the Volturno.  
 21. Plebiscite at Naples.  
 Dec. 17. Annexation of the principalities, Umbria, and the two Sicilies.
1861. Febr. 13. Gaeta capitulates after a four months' siege.  
 March 17. Victor Emmanuel assumes the title of king of Italy.
1864. Sept. 15. Convention between France and Italy.
1866. June 20. Battle of Custoza.  
 July 5. Cession of Venetia.  
 20. Naval battle of Lissa.
1867. Nov. 3. Battle of Mentana.
1870. Sept. 12. Occupation of the States of the Church by Italian troops.  
 20. Occupation of Rome.
-

# Italian Art.

An Historical Sketch by Professor A. Springer.

---

One of the primary objects of the enlightened traveller in Italy is usually to form some acquaintance with its treasures of art. Even those whose usual avocations are of the most prosaic nature unconsciously become admirers of poetry and art in Italy. The traveller here finds them so interwoven with scenes of everyday life, that he encounters their impress at every step, and involuntarily becomes susceptible to their influence. A single visit can hardly suffice to enable any one justly to appreciate the numerous works of art he meets with in the course of his tour, nor can a guide-book teach him to fathom the mysterious depths of Italian creative genius, the past history of which is particularly attractive; but the perusal of a few remarks on this subject will be found materially to enhance the pleasure and facilitate the researches of even the most unpretending lover of art. Works of the highest class, the most perfect creations of genius, lose nothing of their charm by being pointed out as specimens of the best period of art; while those of inferior merit are invested with far higher interest when they are shown to be necessary links in the chain of development, and when, on comparison with earlier or later works, their relative defects or superiority are recognised. The following observations, therefore, will hardly be deemed out of place in a work designed to aid the traveller in deriving the greatest possible amount of enjoyment and instruction from his sojourn in Italy.

The two great epochs in the history of art which principally arrest the attention are those of *Classic Antiquity*, and of the 16th century, the culminating period of the so-called *Renaissance*. The intervening space of more than a thousand years is usually, with much unfairness, almost entirely ignored; for this interval not only continues to exhibit vestiges of the first epoch, but gradually paves the way for the second. It is a common error to suppose that in Italy alone the character of ancient art can be thoroughly appreciated. This idea dates from the period when no precise distinction was made between Greek and Roman art, when the connection of the former with a particular land and nation, and the tendency of the latter to pursue an independent course were alike overlooked. Now, however, that we are acquainted with more numerous Greek originals, and have acquired a

INTRO-  
DUCTORY.

CLASSIC AND  
RENAIS-  
SANCE  
PERIODS.

deeper insight into the development of Hellenic art, an indiscriminate confusion of Greek and Roman styles is no longer to be apprehended. We are now well aware that the highest perfection of ancient architecture is realised in the Hellenic temple alone. The Doric order, in which majestic gravity is expressed by massive proportions and symmetrical decoration, and the Ionic structure, with its lighter and more graceful character, exhibit a creative spirit entirely different from that manifested in the sumptuous Roman edifices. Again, the most valuable collection of ancient sculptures in Italy is incapable of affording so admirable an insight into the development of Greek art as the sculptures of the Parthenon and other fragments of Greek temple-architecture preserved in the British Museum. But, while instruction is afforded more abundantly by other than Italian sources, ancient art is perhaps thoroughly admired in Italy alone, where works of art encounter the eye with more appropriate adjuncts, and where climate, scenery, and people materially contribute to intensify their impressiveness. As long as a visit to Greece and Asia Minor is within the reach of comparatively few travellers, a sojourn in Italy may be recommended as best calculated to afford instruction with respect to the growth of ancient art. An additional facility, moreover, is afforded by the circumstance, that in accordance with an admirable custom of classic antiquity the once perfected type of a plastic figure was not again arbitrarily abandoned, but rigidly adhered to, and continually reproduced. Thus in numerous cases, where the more ancient Greek original had been lost, it was preserved in subsequent copies; and even in the works of the Roman imperial age Hellenic creative talent is still reflected.

The non-scientific traveller will hardly be disposed to devote much attention to the utensils which the earliest Italians used in common with all the Indo-Germanic races, or to the works of the earliest dawn of art, to the so-called *Cyclopean* walls, constructed of polygonal blocks of stone (as those of *Pyrgi*, *Cosa*, *Saturnia*, but more commonly met with in Lower Italy), or to the artistic progress of the mysterious *Etruscan* nation (manifested in their tombs, cinerary urns, implements of metal, and mural paintings); but the eye will not fail to rest with interest upon their magnificent golden ornaments, their beautiful designs engraved on metal (bronze-mirrors; the finest engraved design handed down by antiquity is on the *Ficoronian Cista* in the Museo Kircheriano at Rome), and their numerous painted vases. The latter not only disclose to the observer a wide sphere of ancient artistic ideas, and prove how intimately a love of the beautiful and graceful was associated with the pursuit of a mere trade, but at the same time present one of the earliest instances of artistic industry. Although most of these vases were discovered in Etruscan tombs, they are not all of Italian workmanship, for many of them were imported from

GREEK AND  
ROMAN  
STYLES DIS-  
TINGUISHED.

DAWN OF  
ART.

Greece, where they were systematically manufactured, originally perhaps at Corinth, and subsequently at Athens (vases with red figures).

The artistic dependence of ancient Italy on Greece was not confined to this single and comparatively subordinate branch of art, but gradually extended to every other department, including architecture and sculpture. This supremacy of Greek intellect in Italy was established in a twofold manner. In the first place Greek colonists introduced their ancient native style into their new homes. This is proved by the existence of several Doric temples in Sicily, such as those of *Selinunto* (but not all dating from the same period), and the ruined temples at *Syracuse*, *Girgenti*, and *Segesta*. On the mainland the so-called Temple of Neptune at *Pæstum*, as well as the ruins at *Metapontum*, are striking examples of the fully developed elegance and grandeur of the Doric order. But, in the second place, the art of the Greeks did not attain its universal supremacy in Italy till a later period, when Hellas, nationally ruined, had learned to obey the dictates of her mighty conqueror, and the Romans had begun to combine with their political superiority the refinements of more advanced culture. The ancient scenes of artistic activity in Greece (Athens for example) became re-peopled at the cost of Rome; Greek works of art and Greek artists were introduced into Italy; and ostentatious pride in the magnificence of booty acquired by victory led by an easy transition to a taste for such objects. To surround themselves with artistic decoration thus gradually became the universal custom of the Romans, and the foundation of public monuments came to be regarded as an indispensable duty of government.

Although the Roman works of art of the imperial epoch are deficient in originality compared with the Greek, yet their authors never degenerate into mere copyists, or entirely renounce independent effort. This remark applies especially to their architecture. Independently of the Greeks, the ancient Italian nations, and with them the Romans, had acquired a knowledge of stone-cutting, and discovered the method of constructing arches and vaulting. With this technically and scientifically important art they aimed at combining Greek forms, the column supporting the entablature. The sphere of architecture was then gradually extended. One of the chief requirements was now to construct edifices with spacious interiors, and several stories in height. No precise model was afforded by Greek architecture, and yet the current Greek forms appeared too beautiful to be lightly disregarded. The Romans therefore preferred to combine them with the arch-principle, and apply this combination to their new architectural designs. The individuality of the Greek orders, and their originally unalterable coherence were thereby sacrificed, and divested of much of their importance; that which once possessed a definite organic

significance frequently assumed a superficial and decorative character; but the aggregate effect is always imposing, the skill in blending contrasts, and the directing taste admirable. The lofty gravity of the *Doric Style* † must not be sought for at Rome. The Doric column in the hands of Roman architects lost the finest features of its original character, and was at length entirely disused. The Ionic column also, and corresponding entablature, were regarded with less favour than those of the Corinthian order, the sumptuousness of which was more congenial to the artistic taste of the Romans. As the column in Roman architecture was no longer destined exclusively to support a superstructure, but formed a projecting portion of the wall, or was of a purely ornamental character, the most ornate forms were the most sought after. The graceful Corinthian capital, consisting of slightly drooping acanthus-leaves, was at length regarded as insufficiently enriched, and was superseded by the so-called Roman capital (first used in the arch of Titus), a union of the Corinthian and Ionic. An impartial judgment respecting Roman architecture cannot, however, be formed from a minute inspection of the individual columns,

---

† Those unacquainted with architecture will easily learn to distinguish the different Greek styles. In the Doric the shafts of the columns (without bases) rest immediately on the common pavement, in the Ionic they are separated from it by bases. The flutings of the Doric column immediately adjoin each other, being separated by a sharp ridge, while those of the Ionic are disposed in pairs, separated by broad unfluted intervening spaces. The Doric capital, expanding towards the summit, somewhat resembles a crown of leaves, and was in fact originally adorned with painted representations of wreaths; the Ionic capital is distinguished by the volutes (or scrolls) projecting on either side, which may be regarded rather as an appropriate covering of the capital than as the capital itself. The entablature over the columns begins in the Doric style with the simple, in the Ionic with the threefold architrave; above which in the Doric order are the metopes (originally openings, subsequently receding panels) and triglyphs (tablets with two angular grooves in front, and a half groove at each end, resembling extremities of beams), and in the Ionic the frieze with its sculptured enrichments. In the temples of both orders the front culminates in a pediment. The so-called Tuscan, or early Italian column, approaching most nearly to the Doric, exhibits no decided distinctive marks; the Corinthian, with the rich capital formed of acanthus-leaves, is essentially of a decorative character only. The following technical terms should also be observed. Temples in which the columns are on both sides enclosed by the projecting walls are termed 'in antis' (antæ = end-pilasters); those which have one extremity only adorned by columns, prostyle; those with an additional pediment at the back, supported by columns, amphiprostyle; those entirely surrounded by columns, peripteral. In some temples it was imperative that the image of the god erected in the cella should be exposed to the rays of the sun. In this case an aperture was left in the ceiling and roof, and such temples were termed *hæthral*. Temples are also named tetrastyle, hexastyle, octastyle, etc. according to the number of columns at each end. — A most attractive study is that of architectural mouldings and enrichments, and of those constituent members which respectively indicate superincumbent weight, or a free and independent existence. Research in these matters will enable the traveller more fully to appreciate the strict harmony of ancient architecture.

nor is the highest rank in importance to be assigned to the Roman temples, which, owing to the different (projecting) construction of their roofs, are excluded from comparison with the Greek. Attention must be directed to the several-storied structures, in which the tasteful ascending gradation of the component parts, from the more massive (Doric) to the lighter (Corinthian), chiefly arrests the eye; and the vast and artistically vaulted interiors, as well as the structures of a merely decorative description, must also be examined, in order that the chief merits of Roman art may be understood. In the use of column in front of closed walls (e. g. as members of a façade), in the construction of domes above circular interiors, and of cylindrical and groined vaulting over oblong spaces, the Roman edifices have served as models to posterity, and the imitations have often fallen short of the originals. No dome-building has yet been erected which will bear comparison with the simple and strikingly effective *Pantheon*; nor does there exist any edifice so sumptuous, with so varied an aggregate of structures, and yet so harmonious and monumental in character, as the *Thermae of Caracalla* and *Diocletian* must once have been. Boldness of design, skill in execution, accurate estimation of resources, consistent prosecution of the object in view, and practical utility combined with splendour characterise most of the Roman fabrics, whether destined for public business like the basilicas of the fora, to gratify the popular love of pageantry like the amphitheatres, theatres, and circuses, to commemorate the achievements of the living by means of triumphal arches, or to perpetuate the memory of the dead by monumental tombs. Finally it is worthy of note that architecture resisted degradation longer than any other art, and does not betray palpable signs of declension until the beginning of the 4th century, after having attained its culminating point under the Flavii, considerably earlier.

The history of the art of SCULPTURE among the Romans, which never evidenced their national greatness in the same degree ROMAN as architecture, is of briefer duration. Two different SCULPTURE. methods of investigation may here be pursued. Those who possess sufficient preliminary information, and do not shrink from an arduous although interesting task, should examine the numerous statues of gods and heroes copied from Greek models, of which we possess written records, and compare them with the descriptions. In the *Statue of Zeus from the house of the Verospi*, and in the *Bust of Otricoli* (Vatican), the lineaments of the Olympic Zeus created by Phidias will be sought for, in the *Statues of Hercules* their derivation from the ideal of Lysippus, and in the Juno Ludovisi, and in the head of Hera in the Museum at Naples, their descent from the Juno of Polycletus. Then, for example, the *Dying Gladiator* (in the Capitoline Museum) or the *Group of the Gauls* (in the Villa



Ludovisi) will afford us an idea of the character of the historical sculpture at Pergamus, while the *Discus-throwers of Myron*, the *Amazons of Phidias* and *Ctesilaus*, the *Ares* and *Apollo of Scopas*, the *Statues of Venus by Praxiteles* and others will be recognised in their imitations and slightly varying copies. By these means a correct judgment will be formed with regard to the position of the individual work in the development of ancient art, and the relation of the later sculpture of the Romans to that of the earlier Greeks will be clearly understood. By means of this systematic criticism the science of archæology has of late years led to most interesting results; it has proved that a series of Greek works, once regarded as irrecoverably lost, still survive in their copies, and it has correctly explained several misinterpreted sculptures (e. g. the *Apollo Belvedere*). The amateur, however, will probably prefer to adhere to the course which was formerly pursued by the scientific, and be satisfied with contemplating the mere artistic beauty of the sculptures, irrespective of their historical significance. This æsthetic mode of investigation is justified by the fact that the sculpture of antiquity presents to the eye a harmonious whole, in which the same principles and the same tendency of imagination almost invariably recur. Strongly marked as the distinction is between Greek and Roman views of art, and between the earlier and later development of the art of sculpture, yet the existence of numerous common elements, and the voluntary subordination of the later artists to the once established types cannot be disputed. This will be rendered clearer by an illustration. A universally predominant ideal of the Madonna, on which the images of mediæval and modern art are based, cannot possibly be discovered. Between the Madonnas of Raphael, and Our Lady of the old German and Dutch schools, not the faintest resemblance can be traced; were the former lost, their character could never be divined from the latter. In ancient art, on the contrary, the image of a god, even of the later Roman period, continues to exhibit the distinctive character of the original ideal, and often serves admirably to throw light upon defects in the earlier images; moreover every plastic work of antiquity, whether remote or more recent, faithfully embodies for us the precepts of sculpture, and teaches us the treatment of the nude, the disposition of drapery, and the just standard of expression and movement.

Whether archæological or æsthetic interest be placed in the foreground, opportunities will always present themselves for an

BEST PERIOD OF ROMAN SCULPTURE. examination of the characteristic features of Roman sculpture. (The '*Orestes and Electra*' by Menelaus of Rome in the Villa Ludovisi, of the school of Pasiteles, is probably the best specimen of the Roman sculpture of the close of the Republic.)

This art developed itself most freely between the reigns of Augustus and Hadrian, flourishing contemporaneously with the most brilliant period of the Empire, and constituting its fitting artistic adornment.

Aptitude in imparting a living and attractive character to allegorical representations, as is well exemplified by the charming group of the Nile (Vatican), is not to be regarded as a peculiar feature of Roman art so much as the striking individuality expressed in portrait-busts and statues (marble *Statue of Augustus* in the Vatican, with traces of painting; and *Equestrian Statue of Marcus Aurelius* on the Capitol, which affords an excellent standard of height for monuments of the kind), and the realistic element from which the creation of historical reliefs has emanated. Specimens of this faithful and detailed historical representation, which however occasionally deviates from the plastic standard, are afforded by the *Triumphal Arches of Titus* and *Constantine* (reliefs partly transferred from the arch of Trajan), and the *Columns of Trajan* and *Marcus Aurelius*. As late as the time of Hadrian a new ideal was sought in Antinous, but after that period the art rapidly declined, although even down to the latest era of the Empire great technical skill was still frequently exhibited. The most interesting of these later works are the sarcophagus-sculptures, from their almost encyclopædic richness in representations, and the extensive sphere of ideas which they embrace. They formed the principal school of art for subsequent generations, and are therefore of great historical importance; but the same cannot be said of the later monumental architecture, although it now exhibits the most diversified and attractive picture of the artistic life of antiquity. The ruins of *Herculeaneum* and *Pompeii* prove more forcibly than any record, how universally art was applied in the ancient world, and how even the humblest implements were ennobled by artistic forms; they form an inexhaustible mine of decorative enrichments, and refute the prevailing idea that an entirely subordinate rank is to be assigned to ancient painting. As they were not rescued from oblivion till the 18th century, they exercised no influence on the art of the middle ages or the Renaissance; but, on the other hand, we no longer possess the decorative paintings of the Roman *Thermæ*, which so powerfully stimulated the imagination of artists as lately as the 16th century.

In the 4th century the heathen world, which had long been in a tottering condition, at length became Christianised, and a new period of art began. This is sometimes erroneously re-  
CHRISTIAN  
PERIOD  
OF ART.
garded as the result of a forcible rupture from ancient Roman art, and a sudden and spontaneous invention of a new style. But the eye and the hand adhere to custom more tenaciously than the mind. While new ideas, and altered views of the character of the Deity and the destination of man were entertained, the wonted forms were still necessarily employed in the expression of these thoughts. Moreover the heathen sovereigns had by no means been unremittently hostile to Christianity (the most bitter persecutions did not take place till the 3rd century), and the new doctrines were

permitted to expand, take deeper root, and organise themselves in the midst of heathen society. The consequence was, that the transition from heathen to Christian ideas of art was a gradual one, and that in point of form early Christian art continued to follow up the tasks of the ancient. The best proof of this is afforded by the paintings of the Roman CATACOMBS. These, forming as it were a subterranean belt around the city, but not connected with each other, as formerly supposed, were by no means originally the secret, anxiously concealed places of refuge of the primitive Christians, but constituted their legally recognised, publicly accessible burial-places (e. g. the *Catacombs of Nicomedes* and of *Flavia Domitilla*), and were not enveloped in intentional obscurity until the periodically recurring persecutions of the 3rd century. Reared in the midst of the customs of heathen Rome, the Christian community perceived no necessity to deviate from the artistic principles of antiquity. In the embellishment of the catacombs they adhered to the decorative forms handed down by their ancestors; and in design, choice of colour, grouping of figures, and treatment of subject, they were entirely guided by the customary rules. The various symbols (such as the dove with the olive-branch, the lamb, and the ship) are derived from modern phases of thought, but some of the groups of figures (as the Good Shepherd and Orpheus) are borrowed from antiquity. The earlier the date of the paintings in the catacombs, the more nearly they approach the ancient forms. Even the sarcophagus-sculptures of the 4th and 5th centuries differ in purport only, and not in technical treatment, from the type exhibited in the tomb-reliefs of heathen Rome. Five centuries elapsed before a new artistic style sprang up in the pictorial, and the greatly neglected plastic arts. Meanwhile architecture had developed itself commensurately with the requirements of Christian worship, and, in connection with the new modes of building, painting acquired a different character.

The term **BASILICA-STYLE** is often employed to designate early Christian architecture down to the 10th century. The name is of great antiquity, but it is a mistake to suppose that the early Christian basilicas possessed anything beyond the mere name in common with those of the Roman fora. The latter structures, which are proved to have existed in most of the towns of the Roman empire, and served as courts of judicature and public assembly-halls, differ essentially in their origin and form from the churches of the Christians. The forensic basilicas were neither fitted up for the purposes of Christian worship, nor did they serve as models for the the construction of Christian churches. The latter are rather to be regarded as extensions of the private dwelling-houses of the Romans, where the first assemblies of the community were held, and the component parts of which were reproduced in ecclesiastical edifices. The most faithful representative now extant

CHURCH  
ARCHITECTURE.

of the architectural character and internal arrangements of an early Christian basilica is the church of *S. Clemente* at Rome, although not of earlier origin than the 12th century. A small portico borne by columns leads to the anterior court (atrium), surrounded by colonnades and provided with a fountain (cantharus) in the centre; the eastern colonnade is the approach to the interior of the church, which usually consisted of a nave and two aisles, the latter lower than the former, and separated from it by two rows of columns, the whole terminating in a semicircle (apsis). In front of the apse there was sometimes a transverse space (transept); the altar, surmounted by a columnar structure, occupied a detached position in the apse; the space in front of it, bounded by cancelli or railings, was destined for the choir of officiating priests, and contained the two pulpits (ambones) where the gospel and epistles were read. Unlike the ancient temples, the early Christian basilicas exhibit a neglect of external architecture, the chief importance being attached to the interior, the decorations of which, however, especially in early mediæval times, were often procured by plundering the ancient Roman edifices, and transferring them to the churches with little regard to harmony of style and material. Thus the churches of *S. Maria in Trastevere* and *S. Lorenzo Fuori le Mura* each possess columns of entirely different workmanship and materials. Other instances of a similar transference of columns are afforded by the churches of *S. Sabina* and *S. Maria Maggiore*. The most appropriate ornaments of the churches were the metallic objects, such as crosses and lustres, and the tapestry bestowed on them by papal piety; while the chief decoration of the walls consisted of mosaics, especially those covering the background of the apse and the 'triumphal' arch which separates the apse from the nave. The mosaics, as far at least as the material was concerned, were of a sterling monumental character, and contributed to give rise to a new style of pictorial art; in them ancient tradition was for the first time abandoned, and the harsh and austere style erroneously termed Byzantine gradually introduced. Some of the earliest mosaics (composed of fragments of glass) are in the church of *S. Pudenziana*, dating, like those of *S. Costanza* and the *Baptistry of Naples*, from the 4th century, while those of *S. Maria Maggiore* and *S. Sabina* belong to the 5th. The mosaics in *S. Maria Maggiore* in particular deserve examination, as they mark the period when Christian artists began to display a higher degree of originality, and to endeavour to exchange the symbolical for the historical style. The type of Christ abandons its ideal character (the Good Shepherd) and approaches the portrait style, and the history of his Nativity and Passion are brought more into the foreground. The mosaics (date 526-530) are regarded as the finest compositions of the kind.

Christian art originated at Rome, but its development was actively promoted in other Italian districts, especially at RAVENNA, where during the Ostrogothic supremacy (493-552), as well as under the succeeding Byzantine empire, architecture was zealously cultivated. The basilica-type was there more highly matured, the external architecture enlivened by low arches and projecting buttresses, and the capitals of the columns in the interior appropriately moulded with reference to the superincumbent arches. There, too, the art of mosaic painting was sedulously cultivated, exhibiting in its earlier specimens (in *S. Giovanni in Fonte* and *S. Nazario e Celso*) greater technical excellence and better drawing than the contemporaneous Roman works. At Ravenna the Western style also appears in combination with the Eastern, and the church of *S. Vitale* (dating from 547) may be regarded as a fine example of a Byzantine structure. The term 'BYZANTINE' is, however, often misapplied. Every work of the so-called dark centuries of the middle ages, everything in architecture that intervenes between the ancient and the Gothic, everything in painting which repels by its uncouth, ill-proportioned forms, is apt to be termed Byzantine; and it is commonly supposed that the practice of art in Italy was entrusted exclusively to Byzantine hands from the fall of the Western Empire to an advanced period of the 13th century. This belief in the universal and unqualified prevalence of the Byzantine style, as well as the idea that it is invariably of a clumsy and lifeless character, is entirely unfounded. The forms of Byzantine architecture are at least strongly and clearly defined. While the basilica is a long-extended hall, over which the eye is compelled to range until it finds a natural resting-place in the recess of the apse, every Byzantine structure may be circumscribed with a curved line. The aisles, which in the basilica run parallel with the nave, degenerate in the Byzantine style to narrow and insignificant passages; the apse loses its intimate connection with the nave, being separated from it; the most conspicuous feature in the building consists of the central square space, bounded by four massive pillars which support the dome. These are the essential characteristics of the Byzantine style, which culminates in the magnificent church of *S. Sophia*, and prevails throughout Oriental Christendom, but in the West, including Italy, only occurs sporadically. With the exception of the churches of *S. Vitale* at Ravenna, and *St. Mark* at Venice, the edifices of Lower Italy alone show a frequent application of this style. When baptisteries and mortuary chapels are styled Byzantine on account of their circular form, this is no more justifiable than the popular classification of the whale among the fishes. External points of resemblance must not be confounded with fundamental relationship.

The Byzantine imagination does not appear to have exercised a greater influence on the growth of other branches of Italian art than on architecture. A brisk traffic in works of art was carried on by Venice, Amalfi, and other Italian towns, with the Levant; the position of Constantinople resembled that of the modern Lyons; silk wares, tapestry, and jewellery were most highly valued when imported from the Eastern metropolis. Byzantine artists were always welcome visitors to Italy, Italian connoisseurs ordered works to be executed at Constantinople, chiefly those in metal, and the superiority of Byzantine workmanship was universally acknowledged. All this, however, does not justify the inference that Italian art was quite subordinate to Byzantine. On the contrary, notwithstanding various external influences, it underwent an independent and unbiassed development, and never entirely abandoned its ancient principles. A considerable interval indeed elapsed before the fusion of the original inhabitants with the early mediæval immigrants was complete, before the aggregate of different tribes, languages, customs, and ideas became blended into a single nationality, and before the people attained sufficient concentration and independence of spirit to devote themselves successfully to the cultivation of art. Unproductive in the province of art as this early period is, yet an entire departure from native tradition, or a serious conflict of the latter with extraneous innovation never took place. It may be admitted, that in the massive columns and cumbrous capitals of the churches of Upper Italy, and in the art of vaulting which was developed here at an early period, symptoms of the Germanic character of the inhabitants are manifested, and that in the Lower Italian and especially Sicilian structures, traces of Arabian and Norman influence are unmistakable. The pointed arches of the cathedral of *Amalfi*, and those in the cloisters of the monastery-church of *Ravello*, the interior of the Cappella Palatina at *Palermo*, etc. point to Arabian models; while the façades of the churches at *Cefalu* and *Monreale*, and the enrichments of their portals, recall Norman types. In the essentials, however, the foreigners continue to be the recipients; the might of ancient tradition, and the national idea of form could not be repressed or superseded.

About the middle of the 11th century a zealous and promising artistic movement took place in Italy, and the seeds were sown which three or four centuries later yielded so luxuriant a growth. As yet nothing was matured, nothing completed, the aim was obscure, the resources insufficient; meanwhile architecture alone satisfied artistic requirements, the attempts at painting and sculpture being barbarous in the extreme; these, however, were the germs of the subsequent development of art observable as early as the 11th and 12th centuries. This has been aptly designated the Romanesque period (11th-

GROWTH  
OF ART IN  
ITALY.

ROMAN-  
ESQUE  
STYLE.

13th cent.), and the then prevalent forms of art the **Romanesque Style**. As the Romance languages, notwithstanding alterations, additions, and corruptions, maintain their relation of daughtership to the language of the Romans, so Romanesque art, in spite of its rude and barbarous aspect, reveals its immediate descent from the art of that people. The Tuscan towns were the principal scene of the prosecution of mediæval art. There an industrial population gradually arose, treasures of commerce were collected, independent views of life were acquired in active party-conflicts, loftier common interests became interwoven with those of private life, and education entered a broader and more enlightened track; and thus a taste for art also was awakened, and æsthetic perception developed itself. When Italian architecture of the Romanesque period is examined, the difference between its character and that of contemporaneous northern works is at once apparent. In the latter the principal aim is perfection in the construction of vaulting. French, English, and German churches are unquestionably the more organically conceived, the individual parts are more inseparable and more appropriately arranged. But the subordination of all other aims to that of the secure and accurate formation of the vaulting does not admit of an unrestrained manifestation of the sense of form. The columns are apt to be heavy, symmetry and harmony in the constituent members to be disregarded. On Italian soil new architectural ideas are rarely found, constructive boldness not being here the chief object; on the other hand, the decorative arrangements are richer and more grateful, the sense of rhythm and symmetry more pronounced. The cathedral of Pisa, founded as early as the 11th century, or the church of S. Miniato near Florence, dating from the 12th, may be taken as an example of this. The interior with its rows of columns, the mouldings throughout, and the flat ceiling recall the basilica-type; while the exterior, especially the façade destitute of tower, with the small arcades one above the other, and the variegated colours of the courses of stone, presents a fine decorative effect. At the same time the construction and decoration of the walls already evince a taste for the elegant proportions which we admire in later Italian structures; the formation of the capitals, and the design of the outlines prove that the precepts of antiquity were not entirely forgotten. In the Baptistery of Florence (S. Giovanni) a definite Roman structure (the Pantheon) has even been imitated. A peculiar conservative spirit pervades the mediæval architecture of Italy; artists do not aim at an unknown and remote object; the ideal which they have in view, although perhaps instinctively only, lies in the past; to conjure up this, and bring about a Renaissance of the antique, appears to be the goal of their aspirations. They apply themselves to their task with calmness and concentration, they indulge in no bold or novel schemes, but are content to display their love of form in the execution of details.

What architecture as a whole loses in historical attraction is compensated for by the beauty of the individual edifices. While the North possesses structures of greater importance in the history of the development of art, Italy boasts of a far greater number of pleasing works.

There is hardly a district in Italy which does not boast of interesting examples of Romanesque architecture. At *Verona* we may mention the famous church of St. Zeno with its sculptured portals. In the same style are the cathedrals of *Ferrara*, *Modena*, *Parma*, and *Piacenza*, the church of S. Ambrogio at *Milan*, with its characteristic fore-court and façade, and that of S. Michele at *Pavia*, erroneously attributed to the Lombardi. Tuscany abounds with Romanesque edifices. Among these the palm is due to the cathedral of *Pisa*, a church of spacious dimensions in the interior, superbly embellished with its marble of two colours and the rows of columns on its façade. To the same period also belong the neighbouring Leaning Tower and the Baptistery. The churches of *Lucca* are copies of those at Pisa. Those of *Florence*, however, such as the octagonal, dome-covered baptistery and the charmingly situated church of S. Miniato al Monte, exhibit an independent style. At *Rome* we meet with no edifices strictly belonging to this period, as she was then fully occupied in restoring the ancient basilicas; but she possesses a profusion of decorative works of the 12th cent. (such as altars, ambos, and candelabra in 'Cosmato' work) and a number of specimens of ornamental architecture (chiefly monastery-courts) which exhibit both technical excellence and a partial return to the traditions of antiquity. In Southern Italy we meet with a surprising number of Romanesque churches, among which the cathedrals of *Salerno* and *Amalfi*, the church of S. Nicola at *Bari*, and the cathedrals of *Trani*, *Ruvo*, and above all that of *Troja* are the most notable examples. Mosaic ornamentation, resembling the Roman Cosmato work, has also been largely used in these churches, and notably in *Sicily*, where the mosaics of Palermo present an interesting combination of native and Arabian features, with a preponderance of the latter.

The position occupied by Italy with regard to Gothic architecture is thus rendered obvious. She could not entirely ignore its influence, although incapable of accord-  
ing an unconditional reception to this, the highest development of vault-architecture. Gothic was introduced into Italy in a mature and perfected condition. It did not of necessity, as in France, develop itself from the earlier (Romanesque) style, its progress cannot be traced step by step; it was imported by foreign architects (practised at Assisi by the German master Jacob), and adopted as being in consonance with the tendency of the age; it found numerous admirers among the mendicant orders of monks and the humbler classes of citizens, but could never quite dis-

ROMAN-  
ESQUE  
CHURCHES.

GOthic  
STYLE.



engage itself from Italianising influences. It was so far transformed that the constructive constituents of Gothic are degraded to a decorative office, and the national taste thus became reconciled to it. The cathedral of *Milan* cannot be regarded as a fair specimen of Italian Gothic, but this style must rather be sought for in the mediæval cathedrals of *Florence*, *Siena*, *Orvieto*, and in numerous secular edifices, such as the Loggia dei Lanzi at Florence, the communal palaces of mediæval Italian towns, and the palaces of *Venice*. An acquaintance with true Gothic construction, so contracted notwithstanding all its apparent richness, so exclusively adapted to practical requirements, can certainly not be acquired from these cathedrals. The spacious interior, inviting, as it were, to calm enjoyment, while the cathedrals of the north seem to produce a sense of oppression, the predominance of horizontal lines, the playful application of pointed arches and gables, of finials and canopies, prove that an organic coherence of the different architectural distinguishing members was here but little considered. The characteristics of Gothic architecture, the towers immediately connected with the façade, and the prominent flying buttresses are frequently wanting in Italian Gothic edifices, — whether to their disadvantage, it may be doubted. It is not so much the sumptuousness of the materials which disposes the spectator to pronounce a lenient judgment, as a feeling that Italian architects pursued the only course by which the Gothic style could be reconciled with the atmosphere and light, the climate and natural features of Italy. Gothic lost much of its peculiar character in Italy, but by these deviations from the customary type it there became capable of being nationalised, especially as at the same period the other branches of art also aimed at a greater degree of nationality, and entered into a new combination with the fundamental trait of the Italian character, that of retrospective adherence to the antique.

The apparently sudden and unprepared-for revival of ancient ideals in the 13th century is one of the most interesting phenomena in the history of art. The Italians themselves could only REVIVAL OF ANCIENT ART IDEALS. account for this by attributing it to chance. The popular story was that the sculptor NICCOLÒ PISANO was induced by an inspection of ancient sarcophagi to exchange the prevailing style for the ancient, and indeed in one case we can trace back a work of his to its antique prototype. We refer to a relief on the pulpit in the Baptistery at Pisa, several figures in which are borrowed from a Bacchus vase still preserved in the Campo Santo of that city (pp. 306, 308). Whether Niccolò Pisano was a member of a local school or was trained under foreign influences we are as yet unable to determine. His sculptures on the pulpits in the Baptistery of Pisa and the Cathedral of Siena introduce us at once into a new world. It is not merely their obvious resemblance to the works

of antiquity that arrests the eye; a still higher interest is awakened by their peculiarly fresh and lifelike tone, indicating the enthusiastic concentration with which the master devoted himself to his task. During the succeeding period (Pisan School) ancient characteristics were placed in the background, and importance was attached solely to life and expression (e.g. reliefs on the façade of the Cathedral at Orvieto). Artists now began to impart to their compositions the impress of their own peculiar views, and the public taste for poetry, which had already strongly manifested itself, was now succeeded by a love of art also.

From this period (14th century) therefore the Italians date the origin of their modern art. Contemporaneous writers who observed the change of views, the revolution in sense of form, and the superiority of the more recent works in life and expression, warmly extolled their authors, and zealously proclaimed how greatly they surpassed their ancestors. But succeeding generations began to lose sight of this connection between ancient and modern art. A mere anecdote was deemed sufficient to connect GIOTTO DI BONDONE (1276-1336), the father of modern Italian art, with GIOVANNI CIMABUE (d. after 1302), the most celebrated representative of the earlier style. (Cimabue is said to have watched Giotto, when, as a shepherd-boy, relieving the monotony of his office by tracing the outlines of his sheep in the sand, and to have received him as a pupil in consequence). But it was forgotten that a revolution in artistic ideas and forms had taken place at Rome and Siena still earlier than at Florence, that both Cimabue and his pupil Giotto had numerous professional brethren, and that the composition of mosaics, as well as mural and panel-painting, was still successfully practised. Subsequent investigation has rectified these errors, pointed out the Roman and Tuscan mosaics as works of the transition-period, and restored the Siennese master *Duccio*, who was remarkable for his sense of the beautiful and the expressiveness of his figures, to his merited rank. Giotto, however, is fully entitled to rank in the highest class. The amateur, who before entering Italy has become acquainted with Giotto from insignificant easel-pictures only, often arbitrarily attributed to this master, and even in Italy itself encounters little else than obliquely drawn eyes, clumsy features, and cumbrous masses of drapery as characteristics of his style, will regard Giotto's reputation as ill-founded. He will be at a loss to comprehend why Giotto is regarded as the inaugurator of a new era of art, and why the name of the old Florentine master is only second in popularity to that of Raphael. The fact is that Giotto's celebrity is not due to any single perfect work of art. His indefatigable energy in different spheres of art, the enthusiasm which he kindled in every direction, and the development for which he paved the way, must be taken into consideration,

in order that his place in history may be understood. Even when, in consonance with the poetical sentiments of his age, he embodies allegorical conceptions, as poverty, chastity, obedience, or displays to us a ship as an emblem of the Church of Christ, he shows a masterly acquaintance with the art of converting what is perhaps in itself an ungrateful idea into a speaking, life-like scene. Giotto is an adept in narration, in imparting a faithful reality to his compositions. The individual figures in his pictures may fail to satisfy the expectations, and even earlier masters, such as Duccio, may have surpassed him in execution, but intelligibility of movement and dramatic effect were first naturalised in art by Giotto. This is partly attributable to the luminous colouring employed by him instead of the dark and heavy tones of his predecessors, enabling him to impart the proper expression to his artistic and novel conceptions. On these grounds therefore Giotto, so versatile and so active in the most extended spheres, was accounted the purest type of his century, and succeeding generations founded a regular school of art in his name. As in the case of all the earlier Italian painters, so in that of Giotto and his successors, an opinion of their true merits can be formed from their mural paintings alone. The intimate connection of the picture with the architecture, of which it constituted the living ornament, compelled artists to study the rules of symmetry and harmonious composition, developed their sense of style, and, as extensive spaces were placed at their disposal, admitted of broad and unshackled delineation. Almost every church in Florence boasted of specimens of art in the style of Giotto, and almost every town in Central Italy in the 14th century practised some branch of art akin to Giotto's. The most valuable works of this style are preserved in the churches of *S. Croce* and *S. Maria Novella* at Florence (in the latter the *Cappella degli Spagnuoli* is very important). Beyond the precincts of the Tuscan capital the finest works of Giotto are to be found at *Assisi* and in the *Cappella dell' Arena* at *Padua*, where in 1303 he executed a representation of scenes from the life of the Virgin. The *Campo Santo* of Pisa affords specimens of the handiwork of his pupils and contemporaries. In the works on the walls of this unique national museum the spectator cannot fail to be struck by their finely-conceived, poetical character (e.g. the Triumph of Death), their sublimity (Last Judgment, Trials of Job), or their richness in dramatic effect (History of St. Rainerus, and of the Martyrs Ephesus and Potitus).

In the 15th century, as well as in the 14th, *Florence* continued to take the lead amongst the capitals of Italy in matters of art.

FLORENCE, Vasari attributes this merit to its pure and delicious atmosphere, which he regards as highly conducive to intelligence and refinement. The fact, however, is, that Florence did not itself produce a greater number of eminent artists than other

places. During a long period Siena successfully vied with her in artistic fertility, and Upper Italy in the 14th century gave birth to the two painters D'AVANZO and ALTICHIERI (paintings in the Chapel of *S. Giorgio* in Padua), who far surpass Giotto's ordinary style. On the other hand, no Italian city afforded in its political institutions and public life so many favourable stimulants to artistic imagination, or promoted intellectual activity in so marked a degree, or combined ease and dignity so harmoniously as Florence. What therefore was but obscurely experienced in the rest of Italy, and manifested at irregular intervals only, was generally first realised here with tangible distinctness. Florence became the birthplace of the revolution in art effected by Giotto, and Florence was the home of the art of the Renaissance, which began to prevail soon after the beginning of the 15th century and superseded the style of Giotto.

The word **Renaissance** is commonly understood to designate a revival of the antique; but while ancient art now began to influence artistic taste more powerfully, and its study to be more zealously prosecuted, the essential character of the Renaissance consists by no means exclusively, or even principally, in the imitation of the antique; nor must the term be confined merely to art, as it truly embraces the whole progress of civilisation in Italy during the 15th and 16th centuries. How the Renaissance manifested itself in political life, and the different phases it assumes in the scientific and the social world, cannot here be discussed. It may, however, be observed that the Renaissance in social life was chiefly promoted by the 'humanists', who preferred general culture to great professional attainments, who enthusiastically regarded classical antiquity as the golden age of great men, and who exercised the most extensive influence on the bias of artistic views. In the period of the Renaissance the position of the artist with regard to his work, and the nature and aspect of the latter are changed. The education and taste of the individual leave a more marked impress on the work of the author than was ever before the case; his creations are pre-eminently the reflection of his intellect; his alone is the responsibility, his the reward of success or the mortification of failure. Artists now seek to attain celebrity, they desire their works to be examined and judged as testimonials of their personal endowments. Mere technical skill by no means satisfies them, although they are far from despising the drudgery of a handicraft (many of the most eminent quattrocentists having received the rudiments of their education in the workshop of a goldsmith), the exclusive pursuit of a single sphere of art is regarded by them as an indication of intellectual poverty, and they aim at mastering the principles of each different branch. They work simultaneously as painters and sculptors, and when they devote themselves to architecture, it is deemed nothing unwonted or anomalous. A comprehensive and versatile education,

united with refined personal sentiments, forms their loftiest aim. This they attain in but few instances, but that they eagerly aspired to it is proved by the biography of the illustrious LEON BATTISTA ALBERTI, who is entitled to the same rank in the 15th century, as Leonardo da Vinci in the 16th. Rationally educated, physically and morally healthy, keenly alive to the calm enjoyments of life, and possessing clearly defined ideas and decided tastes, the Renaissance artists necessarily regarded nature and her artistic embodiment with different views from their predecessors. A fresh and joyous love of nature seems to pervade the whole of this period. She not only afforded an unbounded field to the scientific, but artists also strove to approach her at first by a careful study of her various phenomena. Anatomy, geometry, perspective, and the study of drapery and colour are zealously pursued and practically applied. External truth, fidelity to nature, and a correct rendering of real life in its minutest details are among the necessary qualities in a perfect work. The realism of the representation is, however, only the basis for the expression of life-like character and present enjoyment. The earlier artists of the Renaissance rarely exhibit partiality for pathetic scenes, or events which awaken painful emotions and turbulent passions; but, when such incidents are represented, they are apt to be somewhat exaggerated. The preference of these masters obviously inclines to cheerful and joyous subjects. In the works of the 15th century strict faithfulness, in an objective sense, must not be looked for. Whether the topic be derived from the Old or the New Testament, from history or fable, it is always transplanted to the immediate present, and adorned with the colours of actual life. Thus Florentines of the genuine national type are represented as surrounding the patriarchs, visiting Elizabeth after the birth of her son, or witnessing the miracles of Christ. This transference of remote events to the present bears a striking resemblance to the naïve and not displeasing tone of the chronicler. The development of Italian art, however, by no means terminates with mere fidelity to nature, a quality likewise displayed by the contemporaneous art of the North. A superficial glance at the works of the Italian Renaissance enables one to recognise the higher goal of imagination. The carefully selected groups of dignified men, beautiful women, and pleasing children, occasionally without internal necessity placed in the foreground, prove that attractiveness was pre-eminently aimed at. This is also evidenced by the early-awakened enthusiasm for the nude, by the skill in disposition of drapery, and the care devoted to boldness of outline and accuracy of form. This aim is still more obvious from the keen sense of symmetry observable in all the better artists. The individual figures are not coldly and accurately drawn in conformity with systematic rules. They are executed with refined taste and feeling; harshness of expression and displeasing characteristics are

FIDELITY  
OF THE RE-  
NAISSANCE  
ARTISTS TO  
NATURE.

sedulously avoided, while in the art of the North physiognomic fidelity is usually accompanied by extreme rigidity. A taste for symmetry does not prevail in the formation of the individual figure only; obedience to rhythmical precepts is perceptible in the disposition of the groups also, and in the composition of the entire work. The intimate connection between Italian painting (fresco) and architecture naturally leads to the transference of architectural rules to the province of pictorial art, whereby not only the invasion of a mere luxuriant naturalism was obviated, but the fullest scope was afforded to the artist for the execution of his task. For, to discover the most effective proportions, to inspire life into a scene by the very rhythm of the lineaments, are not accomplishments to be acquired by extraneous aid; precise measurement and calculation are here of no avail; a discriminating eye, refined taste, and a creative imagination, which instinctively divines the appropriate forms for its design, can alone excel in this sphere of art. This enthusiasm for external beauty and just and harmonious proportions is the essential characteristic of the art of the Renaissance. Its veneration for the antique is thus also accounted for. At first an ambitious thirst for fame caused the Italians of the 15th and 16th centuries to look back to classical antiquity as the era of illustrious men, and ardently to desire its return. Subsequently, however, they regarded it simply as an excellent and appropriate resource, when the study of actual life did not suffice, and an admirable assistance in perfecting their sense of form and symmetry. They by no means viewed the art of the ancients as a perfect whole, or as the product of a definite historical epoch, which developed itself under peculiar conditions; but their attention was arrested by the individual works of antiquity and their special beauties. Thus ancient ideas were re-admitted into the sphere of Renaissance art. A return to the religious spirit of the Romans and Greeks is not of course to be inferred from the veneration for the ancient gods shown during the humanistic period; belief in the Olympian gods was extinct; but just because no devotional feeling was intermingled, because the forms could only receive life from creative imagination, did they exercise so powerful an influence on the Italian masters. The importance of mythological characters being entirely due to the perfect beauty of their forms, they could not fail on this account pre-eminently to recommend themselves to artists of the Renaissance.

These remarks will, it is hoped, convey to the reader a general idea of the character of the Renaissance. Those who examine the architectural works of the 15th or 16th century should refrain from marring their enjoyment by the not altogether justifiable reflection, that in the Renaissance style no new system was invented, as the architects merely employed the ancient elements, and adhered principally to tradition

STUDY  
OF THE  
ANTIQUE

CHARACTER-  
ISTICS OF  
RENAIS-  
SANCE  
ARCHI-  
TECTURE.

in their constructive principles and selection of component parts. Notwithstanding the apparent want of organisation, however, great beauty of form, the outcome of the most exuberant imagination, will be observed in all these structures.

Throughout the diversified stages of development of the succeeding styles of Renaissance architecture, felicity of proportion is invariably the aim of all the great masters. To appreciate their success in this aim should also be regarded as the principal task of the spectator, who with this object in view will do well to compare a Gothic with a Renaissance structure. This comparison will prove to him that harmony of proportion is not the only effective element in architecture; for, especially in the cathedrals of Germany, the exclusively vertical tendency, the attention to form without regard to measure, the violation of precepts of rhythm, and a disregard of proportion and the proper ratio of the open to the closed cannot fail to strike the eye. Even the unskilled amateur will thus be convinced of the abrupt contrast between the mediæval and the Renaissance styles. Thus prepared, he may, for example, proceed to inspect the *Pitti Palace* at Florence, which, undecorated and unorganised as it is, would scarcely be distinguishable from a rude pile of stones, if a judgment were formed from the mere description. The artistic charm consists in the simplicity of the mass, the justness of proportion in the elevation of the stories, and the tasteful adjustment of the windows in the vast surface of the façade. That the architects thoroughly understood the æsthetical effect of symmetrical proportions is proved by the mode of construction adopted in the somewhat more recent Florentine palaces, in which the roughly hewn blocks (*rustica*) in the successive stories recede in gradations, and by their careful experiments as to whether the cornice surmounting the structure should bear reference to the highest story, or to the entire façade. The same bias manifests itself in Bramante's imagination. The *Cancellaria* is justly considered a beautifully organised structure; and when, after the example of Palladio in church-façades, a single series of columns was substituted for those resting above one another, symmetry of proportion was also the object in view.

From the works of Brunelleschi (p. xlv), the greatest master of the **Early Renaissance**, down to those of Andrea Palladio of Vicenza (p. xlvi), the last great architect of the Renaissance, the works of all the architects of that period will be found to possess many features in common. The style of the 15th century may, however, **EARLY RE-** easily be distinguished from that of the 16th. The Flo-  
**NAISSANCE.** rentine *Pitti*, *Riccardi*, and *Strozzi* palaces are still based on the type of the mediæval castle. A taste for beauty of detail, coeval with the realistic tendency of painting, produces in the architecture of the 15th century an extensive application of graceful and attractive ornaments, which entirely cover the surfaces, and throw the real

organisation of the edifice into the background. For a time the truism of Renaissance art appears to have been departed from; anxious care is devoted to detail instead of to general effect; the re-application of column did not at first admit of spacious structures; the dome rose but timidly above the level of the roof. But this attention to minutiae, this disregard of effect on the part of these architects, was only, as it were, a restraining of their power, in order the more completely to master, the more grandly to develop the art.

There is no doubt that the Renaissance palaces (among which that of Urbino, mentioned in vol. ii. of this Handbook, has always been regarded as pre-eminently typical, are more attractive than the churches. These last, however, though destitute of the venerable associations connected with the mediæval cathedrals, bear ample testimony to the ability of their builders. The churches of Northern Italy in particular are worthy of examination. The first early Renaissance work constructed in this part of the country was the façade of the *Certosa of Pavia*, a superb example of decorative architecture. Besides the marble edifices of this period we also observe structures in brick, in which the vaulting and pillars form prominent features. The favourite form was either circular or that of the Greek cross (with equal arms), the edifice being usually crowned with a dome, and displaying in its interior an exuberant taste for lavish enrichment. Of this type are the church of the *Madonna della Croce* near *Crema* and several others at *Piacenza* and *Parma* (Madonna della Steccata). It was in this region that BRAMANTE (see below) prosecuted the studies of which Rome afterwards reaped the benefit. Among the secular buildings of N. Italy we may mention the *Ospedale Maggiore* at *Milan*, which shows the transition from Gothic to Renaissance. The best survey of the palatial edifices built of brick will be obtained by walking through the streets of *Bologna* (p. 272).

The visitor to *Venice* will have an opportunity of tracing within a very limited space the progress of Renaissance architecture. The church of *S. Zaccaria* is an example of early Renaissance still in conflict with Gothic, while the richly coloured church of *S. Maria dei Miracoli* and the *Scuola di S. Marco* exhibit the style in its perfection. Foremost among the architects of Venice must be mentioned the *Lombardi*, to whom most of the Venetian buildings of the 15th cent. are attributed; but we shall afterwards advert to the farther progress of Venetian architecture (p. xlvii). One of the most famous architects of N. Italy was FRA GIOCONDO of *Verona*, a monk, philologist (the discoverer of the letters of the younger Pliny), a botanist, an engineer, and a thoroughly well trained architect, who at a very advanced age, after the death of Bramante, was summoned to Rome to superintend the building of St. Peter's.

Examples of early Renaissance architecture abound in the towns of Tuscany. At *Florence*, the scene of FILIPPO BRUNELLESCHI'S labours (1377-1446), the attention is chiefly arrested by the church



of *S. Lorenzo* (1425), with its two sacristies (the earlier by Brunelleschi, the later by Michael Angelo, which it is interesting to compare), while the small *Cappella dei Pazzi* near *S. Croce* is also noticeable. The *Palazzo Rucellai* is also important as showing the combination of pilasters with 'rustica', the greatest advance achieved by the early Renaissance. *Siena*, with its numerous palaces, *Pienza*, the model of a Renaissance town, and *Urbino* also afford excellent examples of the art of the Quattrocentists, but are beyond the limits of the present volume. While all these different edifices possess many features in common, they may be classed in a number of groups, differing in material and various other characteristics, and entirely relieving them from any reproach of monotony.

The early Renaissance is succeeded by BRAMANTE'S epoch (1444-1514), with which began the golden age of symmetrical construction. With a wise economy the mere decorative portions of the Renaissance were circumscribed, while greater significance and more marked expression were imparted to the true constituents of the structure, the real exponents of the architectural design. The works of the Bramantine era are less graceful and attractive than those of their predecessors, but superior in their well defined, lofty simplicity and finished character. Had the *Church of St. Peter* been completed in the form originally designed by Bramante, we could have pronounced a more decided opinion as to the ideal of the church-architecture of the Renaissance. The circumstance that the grandest work of this style has been subjected to the most varied alterations (for vastness of dimensions was the principal aim of the architects) teaches us to refrain from the indiscriminate blame which so commonly falls to the lot of Renaissance churches. It must at least be admitted that the favourite form of a Greek cross with rounded extremities, crowned by a dome, possesses concentrated unity, and that the pillar-construction relieved by niches presents a most majestic appearance; nor can it be disputed that in the churches of the Renaissance the same artistic principles are applied as in the universally admired palaces and secular edifices. If the former therefore excite less interest, this is not due to the inferiority of the architects, but to causes beyond their control. The great masters of this culminating period of the Renaissance were RAPHAEL, BALDASSARE PERUZZI, the younger A. DA SANGALLO of Rome, MICHELE SANNICHELHI of Verona (p. 183), JACOPO SANSOVINO of Venice, and lastly MICHAEL ANGELO. The succeeding generation of the 16th century did not adhere to the style introduced by Bramante, but not reduced by him to a finished system. They aim more sedulously at general effect, so that harmony among the individual members begins to be neglected; they endeavour to arrest the eye by boldness of construction and striking contrasts; or they borrow new modes of expression from antiquity, the precepts of which had hitherto been applied in an unsystematic manner only.

The traveller will become acquainted with the works of Bramante and his contemporaries at *Rome* (see vol. ii. of this Handbook), but there are other places also which possess important examples of the 'High Renaissance' style. At *Florence*, for example, are the *Palazzo Pandolfini* and the *Palazzo Uguccioni*, both of which are said to have been designed by RAPHAEL; the *Court of the Pitti Palace* by BART. AMMANATI; the *Palazzo Serristori* and the *Palazzo Bartolini* by BACCIO D'AGNOLO. We must also mention *Mantua* as the scene of the architectural labours of GIULIO ROMANO (p. 191), *Verona* with its numerous buildings by SAMMICHELI (e. g. the *Palazzo Bevilacqua*), and *Padua*, where GIOVANNI MARIA FALCONETTO (1458-1534) and ANDREA RICCIO, or properly BRUSCO (S. Giustina) flourished. At *Venice* the Renaissance culminated in the first half of the 16th cent. in the works of the Florentine JACOPO SANSOVINO (properly TATTI, 1477-1570), and at *Genoa* in those of GALEAZZO ALESSI (1500-72) of Perugia (e.g. S. Maria in Carignano).

In the middle and latter half of the 16th cent, *Venice*, *Genoa*, and *Vicenza* were zealous patrons of art. To this period belongs ANDREA PALLADIO of *Vicenza* (1518-80; p. 196), the last of the great Renaissance architects, whose Venetian churches (*S. Giorgio Maggiore* and *Redentore*) and Vicentine palaces are equally celebrated. The fundamental type of domestic architecture at *Venice* recurs with little variation. The nature of the ground afforded little scope for the caprice of the architect, while the conservative spirit of the inhabitants inclined them to adhere to the style established by custom. Nice distinctions of style are therefore the more observable, and that which emanated from a pure sense of form the more appreciable. Those who have been convinced by careful comparison of the great superiority of the *Biblioteca* (in the *Piazzetta*) of Sansovino over the new *Procurazie* of Scamozzi, although the two edifices exactly correspond in many respects, have made great progress towards an accurate insight into the architecture of the Renaissance.

Much, however, would be lost by the traveller who devoted his attention exclusively to the master-works which have been extolled from time immemorial, or solely to the great monumental structures. As even the insignificant vases (*majolicas*, manufactured at *Pesaro*, *Urbino*, *Gubbio*, and *Castel-Durante*) testify to the taste of the Italians, their partiality for classical models, and their enthusiasm for purity of form, so also in inferior works, some of which fall within the province of a mere handicraft, the peculiar beauties of the Renaissance style are often detected, and charming specimens of architecture are sometimes discovered in remote corners of Italian towns. Nor must the vast domain of decorative sculpture be disregarded, as such works, whether in metal, stone, or stucco, inlaid or carved wood (*intarsii*),

often verge on the sphere of architecture in their designs, drawing, and style of enrichment.

On the whole it may be asserted that the architecture of the Renaissance, which in obedience to the requirements of modern life manifests its greatest excellence in secular structures, cannot SCULPTURE OF THE RENAISSANCE. fail to gratify the taste of the most superficial observer. With the sculpture of the same period, however, the case is different. The Italian architecture of the 15th and 16th centuries still possesses a practical value and is frequently imitated at the present day; and painting undoubtedly attained its highest consummation at the same period; but the sculpture of the Renaissance does not appear to us worthy of revival, and indeed cannot compete with that of antiquity. Yet the plastic art, far from enjoying a lower degree of favour, was rather viewed by the artists of that age as the proper centre of their sphere of activity. Sculpture was the first art in Italy which was launched into the stream of the Renaissance, in its development it was ever a step in advance of the other arts, and in the popular opinion possessed the advantage of most clearly embodying the current ideas of the age, and of affording the most brilliant evidence of the re-awakened love of art. Owing probably to the closeness of the connection between the plastic art of the Renaissance and the peculiar national culture, the former lost much of its value after the decline of the latter, and was less appreciated than pictorial and architectural works, in which adventitious historical origin is obviously less important than general effect. In tracing the progress of the sculpture of the Renaissance, the enquirer at once encounters serious deviations from strict precepts, and numerous infringements of æsthetical rules. The execution of reliefs constitutes by far the widest sphere of action of the Italian sculptors of the 15th century. These, however, contrary to immemorial usage, are executed in a pictorial style. LORENZO Ghiberti (1378-1455), for example, in his celebrated (eastern) door of the Baptistery of Florence, is not satisfied with grouping the figures as in a painting, and placing them in a rich landscape copied from nature. He treats the background in accordance with the rules of perspective; the figures at a distance are smaller and less raised than those in the foreground. He oversteps the limits of the plastic art, and above all violates the laws of the relief-style, according to which the figures are always represented in an imaginary space, and the usual system of a mere design in profile seldom departed from. In like manner the painted reliefs in terracotta by LUCA DELLA Robbia (1400-82) are somewhat inconsistent with purity of plastic form. But if it be borne in mind that the sculptors of the Renaissance did not derive their ideas from a previously defined system, or adhere to abstract rules, the fresh and life-like vigour of their works (especially those of the 15th century) will not be disputed,

and prejudice will be dispelled by the great attractions of the reliefs themselves. The sculpture of the Renaissance adheres as strictly as the other arts to the fundamental principle of representation; scrupulous care is bestowed on the faithful and attractive rendering of the individual objects; the taste is gratified by expressive heads, graceful female figures, and joyous children; the sculptors have a keen appreciation of the beauty of the nude, and the importance of a calm and dignified flow of drapery. In their anxiety for fidelity of representation, however, they do not shrink from harshness of expression or rigidity of form. Their predilection for bronze-casting, an art which was less in vogue in the 16th cent., accords with their love of individualising their characters. In this material, decision and pregnancy of form are expressed without restraint, and almost, as it were, spontaneously. Works in marble also occur, but these generally trench on the province of decoration, and seldom display the bold and unfettered aspirations which are apparent in the works in bronze.

The churches have always afforded the most important field for the labours of the Italian sculptors, some of them, such as *S. Croce* at Florence, *S. Maria del Popolo* at Rome, *Frari* and *S. Giovanni e Paolo* at Venice, and the *Santo* at Padua, forming very museums of Renaissance sculpture. At the same time many of the wealthier families (the *Medici* and others) embellished their mansions with statuary, and the art of the sculptor was frequently invoked with a view to erect a fitting tribute to the memory of some public benefactor (such as the equestrian statues at *Venice* and *Padua*).

At *Florence*, the cradle of Renaissance sculpture, we become acquainted with Ghiberti and Della Robbia, who have been SCULPTORS already mentioned, and with the famous DONATELLO (PRO- OF THE RE- perly DONATO DI NICCOLÒ DI BETTI BARDI, 1386-1466), who NAISSANCE. introduced a naturalistic style, which, though often harsh, is full of life and character. The *Judith Group* in the Loggia de' Lanzi is an exaggerated and unpleasing example of this style, the master having aimed at the utmost possible expressiveness, while the lines and contours are entirely destitute of ease. Among Donatello's most successful works on the other hand are his statue of *St. George* (in Or S. Michele, which also contains his *Peter* and *Mark*; p. 345) and his *Victorious David* in bronze in the Museo Nazionale (p. 353), a collection invaluable to the student of the early Renaissance. The reliefs on the two pulpits in *S. Lorenzo* and the sculptures in the sacristy of that church (p. 366) should also be inspected. Donatello's finest works out of Florence are his numerous sculptures in *S. Antonio* at *Padua*.

The next sculptor of note was ANDREA VERROCCHIO (1435-88). Most of the other masters of this period (ANTONIO ROSELLINO, MINO DA FIESOLE, DESIDERIO DA SETTIGNANO) were chiefly occupied in the execution of tombstones, and do not occupy a

position of much importance; but the life and sense of beauty which characterise the early Renaissance are admirably exemplified in the works of the comparatively unknown MATTEO CIVITALI of *Lucca* (1435-1501; Altar of St. Regulus in the Cathedral, p. 313). Important Florentine masters of the first half of the 16th cent. were GIOV. FRANC. RUSTICI (1474-1550?), who was perhaps inspired by Leonardo, and particularly ANDREA SANSOVINO (1460-1529), the author of the exquisite group of Christ and the Baptist in the Baptistery at *Florence*, of superb monuments at *Rome* (in the choir of S. Maria del Popolo), and of part of the sculptures which adorn the Santa Casa at *Loreto*. Northern Italy also contributed largely to the development of the plastic art. The Certosa at *Pavia*, for example, afforded occupation to numerous artists during several decades; *Venice* gave birth to the famous sculptor ALESSANDRO LEOPARDI (d. 1521); RICCIO or BRISCO wrought at *Padua*; AGOSTINO BUSTI, IL BAMBaja (p. 126) and CRISTOFANO SOLARI, IL GOBBO, were actively engaged at *Milan*; and *Modena* afforded employment to MAZZONI and BEGARELLI (p. 261), artists in terracotta, the latter of whom is sometimes compared with Correggio. Of the various works executed by these masters, *Monumental Tombs* largely predominate, and a perfect museum of such memorials is to be found in the church of S. Giovanni e Paolo at Venice and that of S. Maria del Popolo at Rome. While these monuments are occasionally of a somewhat bombastic character, they afford an excellent illustration of the high value attached to individuality and personal culture during the Renaissance period. We may perhaps also frequently take exception to the monotony of their style, which remained almost unaltered for a whole century, but we cannot fail to derive genuine pleasure from the inexhaustible freshness of imagination displayed within so narrow limits.

As museums cannot convey an adequate idea of the sculpture of the 15th century, so the picture galleries will not afford an accurate insight into the painting of that period. † Sculptures are frequently removed from their original position, many of those belonging to the Florentine churches, for example, having been of late transferred to museums; but mural paintings are of course generally inseparable from the walls which they adorn. Of the frescoes of the 15th century of which a record has been preserved, perhaps one-half have been destroyed or obliterated, but those still extant are the most instructive and attractive examples of the art of this period. The mural paintings in the church *del Carmine* (*Cappella Brancacci*) at Florence are usually spoken of as the earliest specimens of the painting of the Renaissance. This is a chronological mistake, as some of these frescoes were not com-

---

† The best work on this subject is *Crowe & Cavalcaselle's History of Italian Painting*.

pleted before the second half of the 15th century; but on material grounds the classification is justifiable, as this cycle of pictures may be regarded as a programme of the earlier art of the Renaissance, the importance of which it served to maintain, even during the age of Raphael. Here the beauty of the nude was first revealed, and here a calm dignity was for the first time imparted to the individual figures, as well as to the general arrangement; and the transformation of a group of indifferent spectators in the composition into a sympathising choir, forming as it were a frame to the principal actors in the scene, was first successfully effected. It is, therefore, natural that these frescoes should still be regarded as models for imitation, and that, when the attention of connoisseurs was again directed during the last century to the beauties of the pre-Raphaelite period, the works of MASACCIO (b. 1401) and FILIPPINO LIPPI (1458?-1504) should have been eagerly rescued from oblivion.

A visit to the churches of Florence is well calculated to convey an idea of the subsequent rapid development of the art of painting. The most important and extensive works are those of DOMENICO GHIRLANDAJO (1449-94): viz. frescoes in S. Trinità, PAINTING AT FLORENCE. and those in the choir of S. Maria Novella, which in sprightliness of conception are hardly surpassed by any other work of the same period. (The traveller will find it very instructive to compare the former of these works with the mural paintings of Giotto in S. Croce, which also represent the legend of St. Francis, and to draw a parallel between Ghirlandajo's Last Supper in the monasteries of S. Marco and Ognissanti, and the work of Leonardo.) In the Dominican monastery of S. Marco reigns the pious and peaceful genius of FRA GIOVANNI ANGELICO DA FIESOLE (1387-1455), who, though inferior to his contemporaries in dramatic power, vies with the best of them in his depth of sentiment and his sense of beauty, as expressed more particularly by his heads, and who in his old age displayed his well matured art in the frescoes of the chapel of St. Nicholas in the Vatican.

Although the Tuscan painters exhibit their art to its fullest extent in their mural paintings, their easel-pictures are also well worthy of most careful examination; for it was chiefly through these that they gradually attained to perfection in imparting beauty and dignity to the human form. Besides the two great Florentine galleries (Uffizi and Pitti), the collection of the Academy (p. 361) is also well calculated to afford a survey of the progress of Florentine painting.

Beyond the precincts of Florence, BENOZZO GOZZOLI'S charming scenes from the Old Testament on the northern wall of the Campo Santo of Pisa, truly forming biblical genre-pictures, and his PAINTING IN OTHER PARTS OF TUSCANY. FILIPPO LIPPI'S frescoes at Prato (p. 322), PIERO DELLA FRANCESCA'S Finding of the Cross in S. Francesco at Arezzo,

and lastly LUCA SIGNORELLI's representation of the Last Day in the Cathedral at *Orvieto*, afford a most admirable review of the character and development of Renaissance painting in Central Italy. Arezzo and Orvieto should by no means be passed over, not only because the works they contain of Piero della Francesca and Luca Signorelli show how nearly the art even of the 15th century approaches perfection, but because both of these towns afford an immediate and attractive insight into the artistic taste of the mediæval towns of Italy. Those who cannot conveniently visit the provincial towns will find several of the principal masters of the 15th century united in the mural paintings of the Sistine Chapel at *Rome*, where SANDRO BOTICELLI, a pupil of the elder Lippi, COSIMO ROSSELLI, Dom. Ghirlandajo, Signorelli, and Perugino have executed a number of rich compositions from the life of Moses and that of Christ.

But an acquaintance with the Tuscan schools alone can never suffice to enable one to form a judgment respecting the general OTHER progress of art in Italy. Chords which are here but slightly SCHOOLS. touched vibrate powerfully in *Upper Italy*. The works of ANDREA MANTEGNA (1431-1506; at Padua and Mantua) derive much interest from having exercised a marked influence on the German masters Holbein and Dürer, and surpass all the other works of his time in fidelity to nature and excellence of perspective (p. 191). — The earlier masters of the *Venetian School* (VIVARINI, CRIVELLI) were to some extent adherents of the Paduan school, to which Mantegna belonged, but the peculiar Venetian style, mainly founded on local characteristics, and admirably successful in its rich portraiture of noble and dignified personages, was soon afterwards elaborated by GENTILE BELLINI (1424-1507) and his brother GIOVANNI (1426-1516), sons of Giacomo (comp. p. 212). — The Umbrian School also, which originated at Gubbio, and is admirably represented early in the 15th century by OTTAVIANO NELLI, blending with the Tuscan school in GENTILE DA FABRIANO, and culminating in its last masters PIETRO VANNUCCI, surnamed PERUGINO (1446-1524) and BERNARDINO PINTURICCHIO (1454-1513), merits attention, not only because Raphael was one of its adherents during his first period, but because it supplements the broader Florentine style, and notwithstanding its peculiar and limited bias is impressive in its character of lyric sentiment and religious devotion (e. g. Madonnas).

The fact that the various points of excellence were distributed among different local schools showed the necessity of a loftier union. Transcendant talent was requisite in order harmoniously to combine what could hitherto be viewed separately only. UNION OF DIFFERENT SCHOOLS. The 15th century, notwithstanding all its attractiveness, shows that the climax of art was still unattained. The forms employed, graceful and pleasing though they be, are not yet lofty and pure enough to be regarded as embodiments of the highest and

noblest conceptions. The figures still present a local colouring, having been selected by the artists as physically attractive, rather than as characteristic and expressive of their ideas. A portrait style still predominates, the actual representation does not appear always wisely balanced with the internal significance of the event, and the dramatic element is insufficiently emphasised. The most abundant scope was therefore now afforded for the labours of the great triumvirate, LEONARDO DA VINCI, MICHAEL ANGELO BUONARROTI, and RAPHAEL SANTI, by whom an entirely new era was inaugurated.

**Leonardo's** (1452-1519) remarkable character can only be thoroughly understood by means of prolonged study. His comprehensive genius was only partially devoted to art; he also directed LEONARDO DA VINCI. his attention to scientific and practical pursuits of an entirely different nature. Refinement and versatility may be described as the goal of his aspirations; a division of labour, a partition of individual tasks were principles unknown to him. He laid, as it were, his entire personality into the scale in all that he undertook. He regarded careful physical training as scarcely less important than comprehensive culture of the mind; the vigour of his imagination served also to stimulate the exercise of his intellect; and his minute observation of nature developed his artistic taste and organ of form. One is frequently tempted to regard Leonardo's works as mere studies, in which he tested his powers, and which occupied his attention so far only as they gratified his love of investigation and experiment. At all events his personal importance has exercised a greater influence than his productions as an artist, especially as his prejudiced age strenuously sought to obliterate all trace of the latter. Few of Leonardo's works have been preserved in Italy, and these sadly marred by neglect. A reminiscence of his earlier period, when he wrought under ANDREA VERROCCIO at Florence, and was a fellow-pupil of LORENZO DI CREDI, is the fresco (*Madonna and donor*) in S. Onofrio at Rome. Several oil-paintings, portraits, Madonnas, and composed works are attributed to his Milan period, although careful research inclines us to attribute them to his pupils. The following are the most famous of his pictures in the Italian galleries: — in the Ambrosiana of Milan the *Portrait of Isabella of Arragon*, wife of Giov. Galeazzo Sforza; in the Palazzo Pitti the *Goldsmith* and the *Monaca* (both of doubtful authenticity); in the Uffizi the *Portrait of himself* (certainly spurious) and the *Adoration of the Magi*, which last, though little more than a sketch, bears full testimony to the fertility of the artist's imagination; and lastly, in the Vatican Gallery, the *St. Jerome* (in shades of brown). The traveller will also find Leonardo's drawings in the Ambrosiana exceedingly interesting. The best insight into Leonardo's style, and his reforms in the art of colouring, is obtained by an attentive examination of the works



of the Milan school (LUINI, SALAINO ; p. 121), as these are far better preserved than the original works of the master, of which (his battle-cartoon having been unfortunately lost with the exception of a single equestrian group) the Last Supper in S. Maria delle Grazie at Milan is now the only worthy representative. Although now a total wreck, it is still well calculated to convey an idea of the new epoch of Leonardo. The spectator should first examine the delicate equilibrium of the composition, and observe how the individual groups are complete in themselves, and yet simultaneously point to a common centre and impart a monumental character to the work ; then the remarkable physiognomical fidelity which pervades every detail, the psychological distinctness of character, and the dramatic life, together with the calmness of the entire bearing of the picture. He will then comprehend that with Leonardo a new era in Italian painting was inaugurated, that the development of art had attained its perfection.

The accuracy of this assertion will perhaps be doubted by the amateur when he turns from Leonardo to **Michael Angelo** (1474-1563). On the one hand he hears Michael Angelo extolled as the most celebrated artist of the Renaissance, while on the other it is said that he exercised a prejudicial influence on Italian art, and was the precursor of the decline of sculpture and painting. Nor is an inspection of this illustrious master's works calculated to dispel the doubt. Unnatural and arbitrary features often appear in juxtaposition with what is perfect, profoundly significant, and faithfully conceived. As in the case of Leonardo, we shall find that it is only by studying the master's biography that we can obtain an explanation of these anomalies, and reach a true appreciation of Michael Angelo's artistic greatness. Educated as a sculptor, he exhibits partiality to the nude, and treats the drapery in many respects differently from his professional brethren. But, like them, his aim is to inspire his figures with life, and he seeks to attain it by imparting to them an imposing and impressive character. At the same time he occupies an isolated position, at variance with many of the tendencies of his age. Naturally predisposed to melancholy, concealing a gentle and almost effeminate temperament beneath a mask of austerity, Michael Angelo was confirmed in his peculiarities by the political and ecclesiastical circumstances of his time, and wrapped himself up within the depths of his own absorbing thoughts. His sculpture most clearly manifests that profound sentiment to which however he often sacrificed symmetry of form. His figures are therefore anomalous, exhibiting a grand conception, but no distinct or tangible thoughts, and least of all the traditional ideas. It is difficult now to fathom the hidden sentiments which the master intended to embody in his statues and pictures, as they often present nothing but massive and clumsy forms, and appear to degenerate into meaningless mannerism. The decep-

tive effect produced by Michael Angelo's style is best exemplified by some of his later works. His *Moses* in S. Pietro in Vincoli is of impossible proportions; such a man can never have existed; the huge arms and the gigantic torso are utterly disproportionate; the robe which falls over the celebrated knee could not be folded as it is represented. Nevertheless the work is grandly impressive; and so also are the *Monuments of the Medici* in S. Lorenzo at Florence, in spite of the forced attitude and arbitrary moulding of some of the figures. Michael Angelo only sacrifices accuracy of detail in order to enhance the aggregate effect. Had so great and talented a master not presided over the whole, the danger of an inflated style would have been incurred, the forms selected would have been exaggerated, and a professional mannerism would have been the result. Michael Angelo's numerous pupils, in their anxiety to follow the example of his *Last Judgment* in the Sistine, succeeded only in representing complicated groups of unnaturally foreshortened nude figures, while Baccio Bandinelli, thinking even to surpass Michael Angelo, produced in his group of Hercules and Cacus (in the Piazza della Signoria at Florence) a mere caricature of his model.

Amateurs will best be enabled to render justice to Michael Angelo by first devoting their attention to his earlier works, among which in the province of sculpture the group of the *Pietà* in St. Peter's occupies the highest rank. The statues of Bacchus and David (at Florence) likewise do not transgress the customary precepts of the art of the Renaissance. Paintings of Michael Angelo's earlier period are rare; the finest, whether conceived in the midst of his youthful studies, or in his maturer years, is unquestionably the ceiling-painting in the Sistine. The architectural arrangement of the ceiling, and the composition of the several pictures are equally masterly; the taste and discrimination of the painter and sculptor are admirably combined. In *God the Father*, Michael Angelo produced a perfect type of its kind; he understood how to inspire with dramatic life the abstract idea of the act of creation, which he conceived as motion in the prophets and sibyls. Notwithstanding the apparent monotony of the fundamental intention (foreshadowing of the Redemption), a great variety of psychological incidents are displayed and embodied in distinct characters. Lastly, in the so-called *Ancestors of Christ*, the forms represented are the genuine emanations of Michael Angelo's genius, pervaded by his profound and sombre sentiments, and yet by no means destitute of gracefulness and beauty. The decorative figures also which he designed to give life to his architectural framework are wonderfully beautiful and spirited. The *Last Judgment*, which was executed nearly thirty years later (in 1541 according to Vasari), is not nearly so striking as the ceiling-paintings, owing in a great measure to its damaged condi-

tion. — Among Michael Angelo's pupils were SEBASTIAN DEL PIOMBO (the Venetian), MARCELLO VENUSTI, and DANIELE DA VOLTERRA.

Whether the palm be due to Michael Angelo or to **Raphael** (1483-1520) among the artists of Italy is a question which formerly gave rise to vehement discussion among artists and amateurs. **RAPHAEL.** The admirer of Michael Angelo need, however, by no means be precluded from enjoying the works of Raphael. We now know that it is far more advantageous to form an acquaintance with each master in his peculiar province, than anxiously to weigh their respective merits; and the more minutely we examine their works, the more firmly we are persuaded that neither in any way obstructed the progress of the other, and that a so-called higher combination of the two styles was impossible. Michael Angelo's unique position among his contemporaries was such, that no one, Raphael not excepted, was entirely exempt from his influence; but the result of preceding development was turned to the best account, not by him, but by Raphael, whose susceptible and discriminating character enabled him at once to combine different tendencies within himself, and to avoid the faults of his predecessors. Raphael's pictures are replete with indications of profound sentiment, but his imagination was so constituted that he did not distort the ideas which he had to embody in order to accommodate them to his own views, but rather strove to identify himself with them, and to reproduce them with the utmost fidelity. In the case of Raphael, therefore, a knowledge of his works and the enjoyment of them are almost inseparable, and it is difficult to point out any single sphere with which he was especially familiar. He presents to us with equal enthusiasm pictures of the Madonna, and the myth of Cupid and Psyche; in great cyclic compositions he is as brilliant as in the limited sphere of portrait-painting; at one time he appears to attach paramount importance to strictness of style, architectural arrangement, symmetry of groups, etc.; at other times one is tempted to believe that he regarded colour as his most effective auxiliary. His excellence consists in his rendering equal justice to the most varied subjects, and in each case as unhesitatingly pursuing the right course, both in his apprehension of the idea and selection of form, as if he had never followed any other.

Little is known of Raphael's private life, nor is it known by what master he was trained after his father's death (1494). In 1500 he entered the studio of *Perugino* (p. lii), and probably soon assisted in the execution of some of the works of his prolific master. That he rendered some assistance to *Pinturicchio* in the execution of the frescoes at Siena (in 1503, or perhaps as late as 1504) appears certain from their points of resemblance with some of his drawings. Of Raphael's early, or *Umbrian* period there are examples

in the Vatican Gallery (*Coronation of Mary*) and the Brera at Milan (*Sposalizio of the Madonna*, 1504). On settling at Florence (about 1504) Raphael did not at first abandon the style he had learned at Perugia, and which he had carried to greater perfection than any of the other Umbrian masters. Many of the pictures he painted there show that he still followed the precepts of his first master; but he soon yielded to the influence of his Florentine training. After the storm raised by Savonarola had passed over, glorious days were in store for Florence. *Leonardo*, after his return from Milan, and *Michael Angelo* were engaged here on their cartoons for the decoration of the great hall in the Palazzo Vecchio; and it was their example, and more particularly the stimulating influence of *Leonardo*, that awakened the genius and called forth the highest energies of all their younger contemporaries.

The fame of the Florentine school was at this period chiefly maintained by FRA BARTOLOMMEO (1475-1517) and ANDREA DEL SARTO (1487-1531). The only works of Bartolommeo which we know are somewhat spiritless altar-pieces, but they exhibit in a high degree the dignity of character, the tranquillity of expression, and the architectural symmetry of grouping in which he excelled. His finest pictures are the *Christ with the four Saints*, the *Descent from the Cross* (or *Pietà*), the *St. Mark* in the Pitti Gallery, and the *Madonna* in the cathedral at Lucca. The traveller would not do justice to Andrea del Sarto, a master of rich colouring, were he to confine his attention to that artist's works in the two great Florentine galleries. Sarto's *Frescoes* in the *Annunziata* (court and cloisters) and in the *Scalzo* (History of John the Baptist, p. 361) are among the finest creations of the cinquecento. Such, too, was the stimulus given to the artists of this period by their great contemporaries at Florence that even those of subordinate merit have occasionally produced works of the highest excellence, as, for instance, the *Salutation* of ALBERTINELLI and the *Zenobius* pictures of RIDOLFO GHIRLANDAJO in the Uffizi. The last masters of the local Florentine school were PONTORMO and ANGELO BRONZINO.

Raphael's style was more particularly influenced by his relations to Fra Bartolommeo, and the traveller will find it most interesting to compare their works and to determine to what extent each derived suggestions from the other. The best authenticated works in Italy of Raphael's Florentine period are the *Madonna del Granduca* (Pitti), the *Madonna del Cardinello* (Uffizi), the *Entombment* (Gal. Borghese in Rome), the *Predelle* in the Vatican, the portraits of *Angelo* and *Maddalena Doni* (Pitti), and the *Portrait of himself* (Uffizi). The *Portrait of a Lady* in the Pitti gallery is of doubtful origin, and the *Madonna del Baldacchino* in the same gallery was only begun by Raphael.

When Raphael went to Rome in 1508 he found a large circle of notable artists already congregated there. Some of these were

RAPHAEL'S  
FLORENTINE  
CONTEMPORARIES.

deprived of their employment by his arrival, including the Sieneſe master GIOV. ANTONIO BAZZI, ſurnamed IL SODOMA, whoſe frescoes in the Farnesina (unfortunately not now acceſſible) vie with Raphael's works in tendereſs and grace. A ſtill more numerous circle of pupils, however, ſoon aſſembled around Raphael himſelf, ſuch as GIULIO ROMANO, PERINO DEL VAGA, ANDREA DA SALERNO, POLIDORO DA CARAVAGGIO, TIMOTEO DELLA VITE, GAROFALO, FRANC. PENNI, and GIOVANNI DA UDINE. Attended by this diſtinguiſhed retinue, Raphael enjoyed all the honours of a prince, although, in the Roman art world, *Bramante* (p. xlvi) and *Michael Angelo* occupied an equally high rank. The latter did not, however, trench on Raphael's province as a painter ſo much as was formerly ſuppoſed, and the jealousy of each other which they are ſaid to have entertained was probably chiefly confined to their reſpective followers. Raphael had doubtleſs examined the ceiling of the Sistine with the utmoſt care, and was indebted to Michael Angelo for much inſtruction; but it is very important to note that he neither followed in the footſteps, nor ſuffered his native genius to be biassed in the ſlighteſt degree by the example of his great rival. A ſignal proof of this independence is afforded by the *Sibyls* which he painted in the church of S. Maria della Pace in 1514, and which, though conceived in a very different ſpirit from the impoſing figures in the Sistine, are not the leſs admirable. In order duly to appreciate the works produced by Raphael during his Roman period, the traveller ſhould chiefly direct his attention to the maſter's frescoes. The *Stanze* in the Vatican, the programme for which was obviously changed repeatedly during the progreſs of the work, the *Tapeſtry*, the *Loggie*, the fineſt work of decorative art in exiſtence, the *Dome Mosaics* in S. Maria del Popolo (Capp. Chigi), and the *Galatea* and *Myth of Psyche* in the Farnesina together conſtitute the treaſure bequeathed to Rome by the genius of the prince of painters. (Farther particulars as to theſe works will be found in the ſecond vol. of this Handbook.)

Many, and ſome of the beſt, of Raphael's eaſel-pictures of his Roman period are now beyond the Alps. Italy, however, ſtill poſſeſſes the *Madonna della Sedia*, the moſt mundane, but moſt charming of his Madonnas (Pitti), the *Madonna dell' Impannata* (Pitti), the *Madonna col Divino Amore* (Naples), the *Madonna di Foligno* and the *Transfiguration* (in the Vatican), *St. Cecilia* (Bologna), and the *Young St. John* (Uffizi). The fineſt of his portraits are thoſe of *Pope Julius II.* (Pitti; a replica in the Uffizi) and *Leo X. with two Cardinals* (Pitti; a copy by Andrea del Sarto at Naples). Beſides theſe works we muſt alſo mention his *Cardinal Bibbiena* (Pitti), the *Violin-player* (in the Pal. Sciarra at Rome), the *Beatrice* (? perhaps rather a Venetian picture; in the Uffizi), the *Fornarina*, Raphael's miſtreſs (in the Pal. Barberini at Rome), and the *Portrait of a Lady* (Pitti, No. 245), which recalls the Sistine Madonna.

After Raphael's death the progress of art did not merely come to a standstill, but a period of rapid DECLINE set in. The conquest and plundering of Rome in 1527 entirely paralysed all artistic effort for a time. At first this misfortune proved a boon to other parts of Italy. Raphael's pupils migrated from Rome to various provincial towns. GIULIO ROMANO, for example, entered the service of the Duke of Mantua, embellished his palace with paintings, and designed the Palazzo del Tè (p. 194), while PERINO DEL VAGA settled at Genoa (Pal. Doria). These offshoots of Raphael's school, however, soon languished, and ere long ceased to exist. PERIOD OF  
DECLINE.

The NORTHERN SCHOOLS of Italy, on the other hand, retained their vitality and independence for a somewhat longer period. At Bologna the local style, modified by the influence of Raphael, was successfully practised by BART. RAMENGI, sur- SCHOOLS OF  
N. ITALY. named BAGNACAVALLO (1484-1542). Ferrara boasted of LODOVICO MAZZOLINO (1481-1530), a master of some importance, and Dosso Dossi; and at Verona the reputation of the school was maintained by GIANFRANC. CAROTO.

The most important works produced in Northern Italy were those of ANTONIO ALLEGRI, surnamed CORREGGIO (1494?-1534), and of the Venetian masters. Those who visit Parma after Rome and Florence will certainly be disappointed with the pictures of Correggio. They will discover a naturalistic tendency in his works, and they will observe, not only that his treatment of space (as in the perspective painting of domes) is unrefined, but that his individual figures possess little attraction beyond mere natural charms, and that their want of repose is apt to displease and fatigue the eye. The fact is, that Correggio was not a painter of all-embracing genius and far-reaching culture, but merely an adept in chiaroscuro, who left all the other resources of his art undeveloped. CORREGGIO.

In examining the principal works of the VENETIAN SCHOOL, however, the traveller will experience no such dissatisfaction. From the school of Giovanni Bellini (p. lii) emanated the greatest representatives of Venetian painting — GIORGIONE, properly VENETIAN  
SCHOOL. BARBARELLI (1477-1511), whose works have unfortunately not yet been sufficiently well identified, the elder PALMA (1480-1528), and TIZIANO VECELLIO (1477-1575), who for nearly three quarters of a century maintained his native style at its culminating point. These masters are far from being mere colorists; nor do they owe their peculiar attraction to local inspiration alone. The enjoyment of life and pleasure which they so happily pourtray is a theme dictated by the culture of the Renaissance (a culture possessed in an eminent degree by Titian, as indicated by his intimacy with the 'divine' Aretino). Their serene and joyous characters often recall some of the ancient gods, showing the manner in which the artists of the Renaissance had profited by the revived study of the antique. Owing to the soundness of the principles on which the Venetian

school was based, there is no wide gulf between its masters of the highest and those of secondary rank, as is so often the case in the other Italian schools; and we accordingly find that works by LORENZO LOTTO, SEBASTIAN DEL PIOMBO, the BONIFAZIO's, MORETTO (p. 170), PORDENONE, PARIS BORDONE, and TINTORETTO frequently vie in beauty with those of the more renowned chiefs of their school. Even PAOLO CALIARI, surnamed VERONESE (1528-88), the last great master of his school, shows as yet no trace of the approaching period of decline, but continues to delight the beholder with his delicate silvery tints and the spirit and richness of his compositions (comp. p. 212).

Correggio, as well as subsequent Venetian masters, were frequently taken as models by the Italian painters of the 17th century, and the influence they exercised could not fail to be detected even by the amateur, if the entire post-Raphaelite period were not usually overlooked. Those, however, who make the great cinquecentists their principal study will doubtless be loth to examine the works of their successors. Magnificent decorative works are occasionally encountered, but the taste is offended by the undisguised love of pomp and superficial mannerism which they generally display. Artists no longer earnestly identify themselves with the ideas they embody; they mechanically reproduce the customary themes, they lose the desire, and finally the ability to compose independently. They are, moreover, deficient in taste for beauty of form, which, as is well known, is most attractive when most simple and natural. Their technical skill is not the result of mature experience, slowly acquired and justly valued: they came into easy possession of great resources of art, which they frivolously and unworthily squander. The quaint, the extravagant, the piquant alone stimulates their taste; rapidity, not excellence of workmanship, is their aim. Abundant specimens of this mannerism are encountered at Rome and Naples (cupola of the cathedral at Florence by ZUCCARO, frescoes in the Roman churches of S. Maria Maggiore and S. Prassede by D'ARPINO, in S. Stefano by TEMPESTA, etc.). The fact that several works of this class produce a less unfavourable impression does not alter their general position, as it is not want of talent so much as of conscientiousness which is attributed to these artists.

The condition of Italian art, that of painting at least, improved to some extent towards the close of the 16th century, when there was a kind of second efflorescence, known in the schools as the 'revival of good taste', which is said to have chiefly manifested itself in two directions, the eclectic and the naturalistic. But these are terms of little or no moment in the study of art, and the amateur had better disregard them. This period of art also should be studied historically. The principal architectural monuments of the 17th century are the churches of the Jesuits, which

PERIOD OF  
DECLINE.

SECOND RE-  
VIVAL.

unquestionably produce a most imposing effect; but the historical enquirer will not easily be dazzled by their meretricious magnificence. He will perceive the absence of organic forms and the impropriety of combining totally different styles, and he will steel himself against the gorgeous, but monotonous attractions of the paintings and other works of the same period. The bright Renaissance is extinct, simple pleasure in the natural and human is obliterated. A gradual change in the views of the Italian public and in the position of the church did not fail to influence the tendencies of art, and in the 17th century artists again devoted their energies more immediately to the service of the church. Devotional pictures now became more frequent, but at the same time a sensual, naturalistic element gained ground. At one time it veils itself in beauty of form, at another it is manifested in the representation of voluptuous and passionate emotions; classic dignity and noble symmetry are never attained. CRIST. ALLORI's Judith should be compared with the beauties of Titian, and the frescoes of ANNIBALE CARACCI in the Palazzo Farnese with Raphael's ceiling-paintings in the Farnesina, in order that the difference between the 16th and 17th centuries may be clearly understood; and the enquirer will be still farther aided by consulting the coeval Italian poetry, and observing the development of the lyric drama or opera. The poetry of the period thus furnishes a key to the mythological representations of the School of the Caracci. Gems of art, however, were not unfrequently produced during the 17th century, and many of the frescoes of this period are admirable (the Aurora of GUIDO RENI in the Pal. Rospigliosi, Life of St. Cecilia in S. Luigi, Life of St. Nilus in Grottaferrata, paintings on the cupola and vaulting of S. Andrea by DOMENICHINO, etc.). Beautiful oil-paintings by various masters are also preserved in the Italian galleries. Besides the public collections of Bologna (St. Jerome by AGOSTINO CARACCI, Slaughter of the Innocents and Pietà by GUIDO RENI), Naples, and the Vatican (CARAVAGGIO's Entombment) and Capitol (GUERCINO's Petronilla), the private galleries of Rome are of great importance. The so-called gallery-pieces, figures and scenes designated by imposing titles, and painted in the prevailing taste of the 17th century, were readily received, and indeed most appropriately placed in the palaces of the Roman nobles, most of which owe their origin and decoration to that age. This retreat of art to the privacy of the apartments of the great may be regarded as a symptom of the universal withdrawal of the Italians from public life. Artists, too, henceforth occupy an isolated position, unchecked by public opinion, exposed to the caprices of amateurs, and themselves inclined to an arbitrary deportment. Several qualities, however, still exist of which Italian artists are never entirely divested; they retain a certain address in the arrangement of figures, they preserve their reputation as ingenious decorators, and understand the art of occasionally imparting an



ideal impress to their pictures; even down to a late period in the 18th century they excel in effects of colour, and by devoting attention to the province of genre and landscape-painting they may boast of having extended the sphere of their native art. At the same time they cannot conceal the fact that they have lost all faith in the ancient ideals, that they are incapable of new and earnest tasks. They breathe a close, academic atmosphere, they no longer labour like their predecessors in an independent and healthy sphere, and their productions are therefore devoid of absorbing and permanent interest.

This slight outline of the decline of Italian art brings us to the close of our brief and imperfect historical sketch, which, be it again observed, is designed merely to guide the eye of the enlightened traveller, and to aid the uninitiated in independent discrimination and research.

---

#### Contents of Article on Italian Art:

|                                                                  | Page           |
|------------------------------------------------------------------|----------------|
| <i>Art of Antiquity: the Greeks, Etruscans, Romans</i> . . . . . | xxv            |
| Roman Architecture . . . . .                                     | xxvii          |
| Roman Sculpture . . . . .                                        | xxix           |
| <i>The Middle Ages: Early Christian Art</i> . . . . .            | xxxi           |
| Byzantine style . . . . .                                        | xxxiv          |
| Romanesque style. . . . .                                        | xxxv           |
| Gothic style . . . . .                                           | xxxvii         |
| Niccolò Pisano, Giotto . . . . .                                 | xxxviii, xxxix |
| <i>The Renaissance</i> . . . . .                                 | xli            |
| Architecture . . . . .                                           | xliii          |
| Early Renaissance. . . . .                                       | xliv           |
| High Renaissance. . . . .                                        | xlv            |
| Sculpture . . . . .                                              | xlvi           |
| Painting: . . . . .                                              | xlvi           |
| XV. Cent. { Tuscan Schools . . . . .                             | li             |
| { Upper Italian Schools . . . . .                                | lii            |
| { Umbrian School . . . . .                                       | lii            |
| { Leonardo da Vinci . . . . .                                    | liii           |
| { Michael Angelo and his pupils . . . . .                        | liv            |
| XVI. Cent. { Raphael, his contemporaries, and pupils. . . . .    | lvi            |
| { Correggio . . . . .                                            | lix            |
| { Venetian masters . . . . .                                     | lix            |
| XVII. Cent. . Mannerists, Naturalists, Eclectics . . . . .       | Ix             |

# I. Routes to Italy.

## 1. From Paris to Nice by Lyons and Marseilles.

RAILWAY to Marseilles, 536 M., in 24 (express in  $16\frac{1}{4}$  hrs.; fares 106 fr. 30, 79 fr. 75, 58 fr. 45 c. (Express from Paris to Lyons, 318 M., in  $9\frac{1}{4}$ , ordinary trains in  $12\frac{3}{4}$  hrs.; fares 63 fr. 5, 47 fr. 30, 34 fr. 70 c.) — From Lyons to Marseilles, 218 M., express in  $6\frac{3}{4}$ - $8\frac{1}{4}$  hrs., first class only; fare 43 fr. 30 c. From Marseilles to Nice, 140 M., in  $7\frac{1}{2}$  (express in 6 hrs.; fares 27 fr. 70, 20 fr. 75, 15 fr. 20 c.

Soon after quitting Paris the train crosses the *Marne*, near its confluence with the Seine, and near the station of *Charenton*, the lunatic asylum of which is seen on an eminence to the left. To the right and left rise the forts of *Ivry* and *Charenton*, which here command the course of the Seine.  $9\frac{1}{2}$  M. *Villeneuve St. Georges* is picturesquely situated on the slope of a wooded hill. The beautiful green dale of the *Yères* is now traversed. Picturesque country houses, small parks, and thriving mills are passed in rapid succession. Stat. *Montgeron*. The chain of hills to the left, and the plain are studded with innumerable dwellings. Before *Brunoy* is reached the train crosses the *Yères*, and beyond the village passes over a viaduct commanding a beautiful view.

The valley of the *Yères* is now quitted, and the country becomes flatter. Stations *Combes-la-Ville*, *Lieusaint*, and *Cesson*. The Seine is again reached and crossed by a handsome iron bridge at —

28 M. *Melun* (*Hôtel de France*), the capital of the Département de Seine et Marne, an ancient town with 11,400 inhab., the Roman *Methalum*, or *Melodunum*, picturesquely situated on an eminence above the river. The church of Notre Dame, dating from the 11th cent., the church of St. Aspais, of the 14th cent., and the modern Gothic town-hall are fine edifices.

After affording several picturesque glimpses of the Seine valley, the train enters the forest of Fontainebleau. Stat. *Bois-le-Roi*.

37 M. *Fontainebleau* (*Hôtel de Londres*; *Aigle Noir*; *Hôtel de France*) is a quiet place with broad, clean streets (10,500 inhab.). The *\*Palace*, an extensive pile, containing five courts, is almost exclusively indebted for its present form to Francis I. (d. 1547), and abounds in interesting historical reminiscences. It contains a series of handsome saloons and apartments (fee 1 fr.). The *\*Forest* occupies an area of 50,000 acres (60 M. in circumference) and affords many delightful walks. (For farther details, see *Baedeker's Paris*.)

Next stat. *Thomery*, celebrated for its luscious grapes (Chas-

selas de Fontainebleau). The forest is quitted here. 41½ M. *Moret*, a venerable town on the *Loing*, which here falls into the Seine, has a Gothic church of the 12th-15th cent. and a ruined château once occupied by Sully. (Railway hence to Lyons by *Nevers*, *Moulins*, and *Roanne*.)

The line crosses the valley of the Loing by a viaduct of 30 arches. Stat. *St. Mammès*; then (49½ M.) *Montereau* (*Grand Monarque*), picturesquely situated at the confluence of the Seine and *Yonne*. (Branch line to *Flamboin*, a station on the Paris and Troyes line.)

The train ascends the broad and well cultivated valley of the Yonne. Stat. *Villeneuve-la-Guiard*, *Champigny*, *Pont-sur-Yonne*.

72½ M. *Sens* (*Hôtels de l'Écu, de Paris*), the ancient capital of the Senones, who under Brennus plundered Rome in B.C. 389, the *Agedincum* of the Romans, is a quiet town with 11,900 inhab. The early Gothic \**Cathedral* (St. Etienne), dating chiefly from the 13th cent., is an imposing edifice, though somewhat unsymmetrical and destitute of ornament. The stained glass of the 16th cent. and the \**Mausoleum* of the Dauphin, the father of Louis XVI., and his wife, by Coustou, are the chief objects of interest in the interior. The treasury contains many valuables.

Next stations *Villeneuve-sur-Yonne*, *St. Julien du Sault*, *Cézy*. 89½ M. *Joigny* (*Duc de Bourgogne*), the *Joviniacum* of the Romans, is a picturesque and ancient town (6300 inhab.) on the Yonne. Next stat. *La Roche*.

From La Roche by a branch-line in 52 min. to *Auxerre* (*Hôtel du Léopard*), the capital (13,000 inhab.) of the Department of the Yonne, possessing several good churches, especially the late Gothic cathedral. *Chablis*, well known for its wines, lies between Auxerre and Tonnerre (see below), 13½ M. to the E. of the former.

Near La Roche the line crosses the Yonne, into which the *Armançon* here empties itself, and follows the latter river and the *Canal de Bourgogne*, which connects the Seine and Saône.

About 6 M. from *St. Florentin* is the Cistercian *Abbey of Pontigny*, where Thomas à Becket passed two years of his exile. Langton, archbishop of Canterbury, banished by king John, and other English prelates have also sought a retreat within its walls.

122 M. *Tonnerre* (*Hôt. des Courriers*; *Lion d'Or*; \**Rail. Restaurant*), a town with 5000 inhab., picturesquely situated on the Armançon. The church of *St. Pierre*, on an eminence above the town, built in the 12th-16th cent., commands a pleasing prospect.

Stat. *Tanlay* boasts of a fine château in the Renaissance style, founded by the brother of Admiral Coligny. At *Ancy-le-Franc* there is a very handsome château, erected in the 16th cent. from designs by Primaticcio. From stat. *Nuits-sous-Ravières* a branch-line runs to *Châtillon-sur-Seine* and *Chaumont*. *Montbard*, birthplace (1707) of Buffon, the great naturalist (d. at Paris in 1788), contains his château and a monument to his memory.

Beyond *Blaisy-Bas* the line penetrates the watershed (1326 ft.) between the Seine and the Rhone by a tunnel (*Souterrain de Blaisy*), 2½ M. long. Hence to Dijon a succession of viaducts, cuttings, and tunnels. Beyond stat. *Malain*, with its ruined château, the line enters the picturesque valley of the *Ouche*, bounded on the right by the slopes of the Côte d'Or.

197 M. **Dijon** (*Hôtels de la Cloche, de Bourgogne, du Jura; Buffet*), with 39,200 inhab., the ancient *Divio*, once the capital of Burgundy, now that of the Département de la Côte d'Or, is situated at the confluence of the *Ouche* and the *Souzon*. The dukes of Burgundy resided here down to the death of Charles the Bold in 1477. The buildings of that period enhance the interest of the place.

The Rue Guillaume leads from the station to the *Hôtel de Ville*, once the ducal palace, but remodelled in the 17th and 18th cent. The two towers and the Salle des Gardes are almost the only ancient parts. The *Museum*, containing the celebrated \*monuments of the dukes Philip the Bold and Jean sans Peur (14th and 15th cent.), and valuable collections of pictures, antiquities, engravings, etc., is open to the public on Sundays, 12-4, on Thursdays, 12-2, and daily to strangers on payment of a fee.

\**Notre Dame*, to the N. of the Hôtel de Ville, is a Gothic church of the 13th cent., of very picturesque exterior. The principal portal is a beautiful Gothic composition. The interior is also interesting. One of the chapels of the transept contains a black image of the Virgin dating from the 11th or 12th cent.

*St. Bénigne*, the cathedral, to the S. of the Porte Guillaume, an interesting building, was erected in 1271-88. The plan resembles that of Byzantine churches. The two towers in front are covered with conical roofs, and a wooden spire, 300 ft. in height, rises over the transept.

In the vicinity are *St. Philibert*, of the 12th cent., and *St. Jean*, of the 15th cent., the latter now disfigured by modern paintings.

The *Castle*, to the N. of the Porte Guillaume, now in a half-ruined condition, was erected by Louis XI. in 1478-1512, after the union of Burgundy with France, and subsequently employed as a state-prison. On the way to it we pass the modern *Statue of St. Bernard* (d. 1153), who was born at Fontaine, a village near Dijon.

The town contains a number of picturesque buildings of the Renaissance period, chiefly interesting to architects. The old ramparts have been converted into promenades.

Dijon is the junction of the line via *Dôle* and *Mouchard* to *Pontarlier*, where it diverges to the left (N.E.) to *Neuchâtel*, and to the right (S.E.) to *Lausanne* (*Geneva*) and *Sierre*. Comp. R. 3.

The line to Mâcon crosses the *Ouche* and the *Canal de Bourgogne* (p. 2), and skirts the base of the sunny vineyards of the Côte d'Or, which produce the choicest Burgundy wines. At *Vougeot* is the fa-

mous *Clos-Vougeot* vineyard. Near *Nuits-sous-Beaune* a battle was fought between the Germans and the French in Dec. 1870.

218½ M. **Beaune** (*Hôtels de France, de la Poste*), with 11,000 inhab., on the *Bouzoise*, contains several Gothic edifices (e. g. the church of *Notre Dame*, of the 12th and 15th cent., with a fine but mutilated portal) and a monument to the mathematician Monge, who was born here in 1747 (d. 1818).

Stat. *Meursault*. From *Chagny* a branch-line diverges to *Autun*, and by *Le Creuzot* to *Nevers*. The train passes under the *Canal du Centre*, which connects the Saône and the Loire, by means of a tunnel, intersects the *Col de Chagny* (watershed, 725 ft.), and enters the valley of the *Thalie*. Stat. *Fontaines*.

238 M. **Châlon-sur-Saône** (*Hôtels du Chevreuil, du Commerce, de Provence*), with 20,000 inhab., is situated at the junction of the Canal du Centre with the Saône, which is here navigated by steamboats (to Lyons in 5-6 hrs.). The town contains little to detain the traveller. The Gothic church of *St. Vincent*, built in 1386-1440, has recently been restored. The express trains do not touch Châlon, the branch-line to which diverges from the *St. Cosme* junction. Branch-lines hence to *Lons-le-Saulnier* and to *Dôle*.

The line follows the right bank of the Saône; to the left in the distance rises the Jura, and in clear weather the snowy summit of Mont Blanc, 150 M. distant, is visible. 254 M. *Tournus* (5500 inhab.) possesses a fine abbey-church (*St. Philibert*).

274 M. **Mâcon** (*Hôt. des Champs Élysées, de l'Europe; Buffet*), the capital of the Department of the Saône and Loire, with 18,400 inhab., is another great focus of the wine-trade. The remains of the cathedral of *St. Vincent* are partly in the Romanesque style. — The line to *Culoz* (*Geneva, Turin*) diverges here to the left; see R. 2.

The line continues to follow the right bank of the Saône. Scenery pleasing. The stations between Mâcon and Lyons, thirteen in number, present little to interest the traveller.


318 M. **Lyons**, see p. 5.

FROM STRASSBURG (*Bâle*) TO LYONS by *Mülhausen* and *Bourg*, the most direct route between the S.W. of Germany and S. France. (Railway from Strassburg to *Belfort*, 99 M., express in 5¼ hrs.; fares 14 *M* 70, 10 *M* 50 pf. — From *Belfort* to *Lyons*, 208 M., in 12 hrs.; fares 41 fr. 15, 30 fr. 85c.) — From Strassburg (and from *Bâle*) to *Mülhausen*, see *Baedeker's Rhine*. The German frontier station, 89½ M. from Strassburg, is *Altminsterol*, and the French frontier-station is (99 M.) *Belfort*, where the Paris line diverges. *Belfort* (8000 inhab.), a fortress on the *Savoireuse*, erected by Vauban under Louis XIV., was taken by the Germans after a protracted siege in Feb. 1871. The train now traverses a picturesque, undulating district; to the left rise the spurs of the Jura. At *Héricourt*, several engagements took place between Gen. Werder's army and the French under Bourbaki in Jan. 1871. Stat. *Montbéliard* belonged to the German Empire down to 1793. Beyond stat. *Voujaourt* the line follows the *Doubs*, which it crosses several times. Beyond stat. *L'Isle-sur-le-Doubs* the train passes through several tunnels. A number of unimportant stations; then —





# LYON



|                                        |                            |            |    |                             |      |
|----------------------------------------|----------------------------|------------|----|-----------------------------|------|
| 1                                      | Abattoir                   | G. 4. D. 6 | 71 | Poste aux Lettres           | E. 3 |
| 2                                      | Ancêtre                    | C. 2       | 72 | Préfecture (Hôtel de Ville) | D. 3 |
| 3                                      | Antiquaille Hospice        | E. 4       | 73 | Prison St-Joseph            | G. 4 |
| 4                                      | Archevêché                 | E. 4       | 74 | St. Milit.                  | F. 3 |
| 5                                      | Arsenal                    | G. 5       | 75 | Séminaire                   | E. 4 |
| 6                                      | Bibliothèque pub.          | D. 3       | 76 | Théâtre des Célestins       | E. 3 |
|                                        |                            |            | 77 | Eglise anglaise             | C. 3 |
| <b>Casernes</b>                        |                            |            |    |                             |      |
| 7                                      | d'Artillerie               | E. 1. 2    |    |                             |      |
| 8                                      | des Bernardines            | C. 3       |    |                             |      |
| 9                                      | du Bon Pasteur             | C. 4       |    |                             |      |
| 10                                     | Carmes déchaux             | D. 4       |    |                             |      |
| 11                                     | des Colnettes              | C. 3       |    |                             |      |
| 12                                     | de Gendarmerie             | F. 4       |    |                             |      |
| 13                                     | Louis-Napoléon             | F. 4       |    |                             |      |
| 14                                     | de Perrache                | H. 4       |    |                             |      |
| 15                                     | de Serin                   | C. D. 5    |    |                             |      |
| 16                                     | Sergents de Ville          | E. 3       |    |                             |      |
| 17                                     | Verses milit.              | D. 5       |    |                             |      |
| 18                                     | Fourrages milit.           | D. 4       |    |                             |      |
| 19                                     | Charité Hospice            | E. F. 3    |    |                             |      |
| 20                                     | Condition d Soies          | D. 3       |    |                             |      |
| 21                                     | Depot de Médecine          | E. 4       |    |                             |      |
| 22                                     | École d'Artillerie         | D. 2       |    |                             |      |
| 23                                     | École Vétérinaire          | D. 5       |    |                             |      |
| <b>Eglises</b>                         |                            |            |    |                             |      |
| 24                                     | St-Antoine                 | F. 4       |    |                             |      |
| 25                                     | N.D. de Fourvières         | E. 4       |    |                             |      |
| 26                                     | de l'Observance            | D. 5       |    |                             |      |
| 27                                     | St-André                   | F. 3       |    |                             |      |
| 28                                     | St-Augustin                | C. 4       |    |                             |      |
| 29                                     | St-Bernard                 | C. 3       |    |                             |      |
| 30                                     | St-Blandine                | G. 4       |    |                             |      |
| 31                                     | St-Bonaventure             | D. E. 3    |    |                             |      |
| 32                                     | St-Bruno                   | C. 4       |    |                             |      |
| 33                                     | St-Clair                   | H. 2       |    |                             |      |
| 34                                     | St-Denis                   | B. 3       |    |                             |      |
| 35                                     | St-Eucher                  | B. 3       |    |                             |      |
| 36                                     | St-Etienne                 | H. 6       |    |                             |      |
| 37                                     | St-François                | F. 3       |    |                             |      |
| 38                                     | St-Georges                 | E. 4       |    |                             |      |
| 39                                     | St-Irénée                  | F. 5       |    |                             |      |
| 40                                     | St-Just                    | E. F. 4    |    |                             |      |
| 41                                     | St-Jean (Cathédrale)       | E. 4       |    |                             |      |
| 42                                     | N.D. de St-Vincent         | D. 4       |    |                             |      |
| 43                                     | St-Louis-Guillotière       | F. 2       |    |                             |      |
| 44                                     | St-Nizier                  | D. 3       |    |                             |      |
| 45                                     | St-Paul                    | D. 4       |    |                             |      |
| 46                                     | St-Pierre                  | D. 3       |    |                             |      |
| 47                                     | St-Pothin                  | D. 2       |    |                             |      |
| 48                                     | St-Polycarpe               | C. 3       |    |                             |      |
| 49                                     | de Serin                   | C. 5       |    |                             |      |
| 50                                     | de Vaise                   | C. 5. 6    |    |                             |      |
| 51                                     | Temple des Protestants     | D. 4       |    |                             |      |
| <b>Embarcadères des Chemins de Fer</b> |                            |            |    |                             |      |
| 52                                     | de Lyon à St-Etienne       | H. 4       |    |                             |      |
| 53                                     | à Marseille                | G. 2. 3    |    |                             |      |
| 54                                     | à Paris (Stras)            | G. 4       |    |                             |      |
| 55                                     | à Paris (Vaise)            | B. 6       |    |                             |      |
| 56                                     | Grand Hôtel Dieu           | E. 3       |    |                             |      |
| 57                                     | Grand Théâtre              | D. 3       |    |                             |      |
| 58                                     | Grenette                   | D. 5       |    |                             |      |
| 59                                     | Hospices Militaires        | F. 3       |    |                             |      |
| 60                                     | Hôtel de la Divis. Mil.    | E. F. 4    |    |                             |      |
| 61                                     | Hôtel des Monnaies         | F. 3. 4    |    |                             |      |
| 62                                     | Hôtel de Ville             | D. 3       |    |                             |      |
| 63                                     | Jardin des Plantes         | C. 4       |    |                             |      |
| 64                                     | L. J. J.                   | D. 3       |    |                             |      |
| 65                                     | Mans. des Tabacs           | F. 4       |    |                             |      |
| 66                                     | Mant de Piété              | E. 3       |    |                             |      |
| 67                                     | Palais de Justice          | E. 4       |    |                             |      |
| 68                                     | de la Bourne               | D. 3       |    |                             |      |
| 69                                     | des Arts                   | D. 3       |    |                             |      |
| <b>Hôtels:</b>                         |                            |            |    |                             |      |
| a.                                     | Grand Hôtel de Lyon        | D. 3.      |    |                             |      |
| b.                                     | Collet                     | E. 3.      |    |                             |      |
| c.                                     | del'Europe                 | E. 4.      |    |                             |      |
| d.                                     | Hôtel des Beaux Arts       | E. 3.      |    |                             |      |
| e.                                     | Négociant                  | E. 3.      |    |                             |      |
| f.                                     | du Harve                   | E. 3.      |    |                             |      |
| g.                                     | Beauquis                   | E. 3.      |    |                             |      |
| h.                                     | Michel                     | F. 4.      |    |                             |      |
| i.                                     | Angletierre et Deux Mondes | F. 4.      |    |                             |      |
| k.                                     | Milan                      | D. 3.      |    |                             |      |
| l.                                     | de la Bombarde             | E. 4.      |    |                             |      |
| m.                                     | Eau de France              | D. 3.      |    |                             |      |
| n.                                     | de l'Univers               | G. 4.      |    |                             |      |



159 M. **Besançon** (*Hôtel du Nord; Hôtel de Paris*), the ancient *Vesontio*, capital of the Franche Comté, with 47,000 inhab., a strongly fortified place, situated in a wide basin on the Doubs, which flows round the town and once rendered it an important military point, as described by Cæsar (*De Bell. Gall.* i. 38).

The substantial, old-fashioned architecture of the town is interesting, and modern innovations are comparatively rare. The **MUSEUM**, established in a modern building in the *Place de l'Abondance*, contains a Christ on the Cross by Dürer, and a Descent from the Cross by Bronzino. — The **Library**, founded in 1694 by Boiset, contains 100,000 vols., about 1800 MSS., a collection of coins, etc.

In the principal street, the *Grande Rue*, which ascends from the *Pont de la Madeleine* to the citadel, is situated the *Palais Granvelle*, a handsome structure in the Renaissance style (1530-40). Farther on is the *Porte Noire*, a triumphal arch of the late Roman period. The **CATHEDRAL** OF ST. JEAN contains in the 1st chapel on the right near the entrance, the monument of the archdeacon Ferrico Carondelet (d. 1528); above it the Death of Ananias by Seb. del Piombo. In the chapel on the left the Virgin surrounded by angels with SS. Sebastian, John, Dominic, and the two donors of the picture, by Fra Bartolommeo. The street ascends hence to the *Citadel*, constructed by Vauban (permission to visit it must be obtained from the commandant in the town). The summit commands an admirable view. At the base of the citadel (8 min. walk from the *Porte de Rivotte*), on the river, is situated the *Porte Taillée*, originally appertaining to a Roman aqueduct, and subsequently widened so as to form a gateway.

184 M. **Mouchard**, junction of the lines from Dijon and Dôle, and from Pontarlier (Neuchâtel and Lausanne). — At (216 M.) *Lons le Saunier* a line diverges to Châlon.

252 M. **Bourg** (p. 21); scenery thence to (307 M.) *Lyons* uninteresting.

FROM GENEVA TO LYONS, 104 M., railway in 5¼-6½ hrs. (fares 18 fr. 80, 14 fr. 10, 10 fr. 35 c.). From Geneva to *Ambérieu*, see p. 22. The Lyons line diverges here from that to Mâcon and proceeds towards the S.W. Picturesque district, presenting a series of pleasing landscapes. Beyond stat. *Leyment* the train crosses the *Ain*, commanding a beautiful glimpse of the valley of that stream. Then several unimportant places. Near Lyons the line intersects the suburbs of *La Croix Rousse* and *La Guillotière*, and soon reaches the extensive terminus (at Lyon-Perrache).

**Lyons. Arrival.** After stopping at the *St. Clair* and *Des Brotteaux* stations, the train proceeds to the *Gare de Perrache* (Pl. H, 4, 5), the principal station, where hotel omnibuses are in waiting.

**Hotels.** GRAND HÔTEL DE LYON (Pl. a), Rue de Lyon 16, in the Parisian style, with restaurant, café, etc., R. 3, A. 1 fr.; GRAND HÔTEL COLLET (Pl. b), Rue de Lyon 62; HÔTEL DE L'EUROPE (Pl. c), Rue de Bellecour; GR. HÔT. DE TOULOUSE ET DE STRASBOURG, Cours de Midi; GR. HÔT. DE BELLECOUR, Place Bellecour, formerly Louis-le-Grand; GR. HÔT. DE LA POSTE, Rue de la Barre 3; HÔTEL DU GLOBE, Rue Gasparin 21; GRAND HÔTEL DES BEAUX ARTS (Pl. d); HÔTEL DES NÉGOCIANTS (Pl. e); HÔTEL MICHEL (Pl. h); HÔTEL DE MILAN (Pl. k); HÔTEL DE FRANCE, Rue de l'Arbre Sec, near the Muscum.

**Café-Restaurant.** *Maderni*, Rue de Lyon 19, and Place de la Bourse. Cabs, per drive 1 fr. 50 c., 1st hour 2 fr., each following hour 1 fr. 50 c.; from midnight to 7 a.m. per drive 1 fr. 65, per hour 2 fr. 50 c. — Omnibus from the station to the town 50, with luggage 75 c.; hotel-omnibus 1-1½ fr.

**Post Office**, Place Bellecour (open from 7 a.m. to 8 p.m.). — English Church Service, resident chaplain.

Lyons, the ancient *Lugdunum*, which after the time of Augustus gave its name to one-third part of Gaul, is now the second city, and the most important manufacturing place in France, with 326,000



inhab., silk being its great staple commodity. Lyons is an archiepiscopal see. As an episcopal residence it is mentioned as early as the 2nd cent.

The situation of the city at the confluence of the *Rhone* and *Saône* is imposing. The *Saône* is crossed by ten, the *Rhone* by seven bridges. Lyons is one of the best built towns in France. Great alterations have taken place within the last 20 years, so that the general aspect of the city is modern. It consists of three distinct portions, the original town on the tongue of land between the *Rhone* and *Saône*, the suburbs of *Les Brotteaux* and *La Guillotière* on the left bank of the *Rhone*, and the suburb of *Vaise* on the right bank of the *Saône*. The military defences of the city consist of a wide girdle of eighteen forts.

The beauty of the situation and the extent of the city are best appreciated when viewed from the <sup>\*\*</sup>*Height of Fourvières* (Pl. 25; E, 4), crowned by its conspicuous church, to which there are several different ways. The direct route leads between the handsome modern *Palais de Justice* (Pl. 67; E, 4) and the cathedral, through narrow and steep streets, passing the hospital of *Les Antiquailles*, which occupies the site of an ancient Roman palace where *Claudius and Caligula* were born. We now continue to follow the main street; or we may take the '*Passage Abrégé*' (5 c.) to the right, leading past gardens, vineyards, and a number of fragments of Roman masonry, with explanations attached to them, which however are not to be implicitly trusted. This footpath leads to the *Observatoire* on the summit, not far distant from the church of *Notre Dame de Fourvières* (Pl. 25), which contains a highly revered 'miraculous' image of the *Virgin* (visited by upwards of 1½ million pilgrims annually) and numerous votive tablets. The church is a modern structure, surmounted by a gilded statue of the *Madonna*. The tower commands a magnificent *VIEW* (fee 25 c.; visitors may ascend to the statue); and a still finer prospect may be obtained from the neighbouring *Observatory* (fee 50 c.; restaurant). At the feet of the spectator lie the imposing city, with the two rivers and their bridges, and the well cultivated district in the neighbourhood; to the E. in fine weather *Mont Blanc*, 85 M. distant, is sometimes visible; farther S. the *Alps of Dauphiné*, the *Mts. of the Grande Chartreuse* and *Mont Pilat*, and to the W. the *Mts. of Auvergne*.

The *Cathedral of St. Jean Baptiste* (Pl. 41; E, 4) on the right bank of the *Saône*, adjoining the *Palais de Justice*, dates from the 12th-14th cent. The *Bourbon* chapel (1st on the right), erected by *Cardinal Bourbon* and his brother *Pierre de Bourbon*, son-in-law of *Louis XI.*, contains some fine sculptures.

On the left bank of the *Saône*, about ½ M. lower down, is situated the church of the *Abbey d'Ainay* (Pl. 24; E, 4), one of the oldest in France, dating from the 10th cent., the vaulting of which is borne by four antique columns of granite.

In the *Place des Terreaux* (Pl. D, 3), in which the *Hôtel de Ville* and the *Museum* are situated, Richelieu caused the youthful *Marquis de Cinq-Mars*, who for a short period was the favourite of *Louis XIII.*, and his partisan *De Thou* to be executed as traitors, 12th Sept., 1642. Numerous victims of the Revolution perished here by the guillotine in 1794, after which the more wholesale system of drowning and shooting was introduced. The *Hôtel de Ville* (Pl. 62) is a handsome edifice of 1647-55.

The *Palais des Beaux Arts*, or *Museum* (Pl. 69; D, 3), is open to visitors gratis, daily 11-4 (a gratuity is expected; for the different sections 25 c. from each person).

Under the arcades of the spacious COURT, are some remarkable Roman antiquities, a taurobolium (sacrifice of oxen), altars, inscriptions, sculptures, etc.

The *Picture Gallery* is on the first floor. *SALLE DES ANCIENS MAÎTRES*: in the centre four Roman mosaics, representing *Orpheus*, *Cupid and Pan*, and the games of the circus. Among the pictures may be mentioned: *Terburg*, *The Message*; *Palma Giovane*, *Scourging of Christ*; *Pietro Perugino*, *Ascension*, one of this master's finest works, painted in 1495 for the cathedral of Perugia; *Sebastian del Piombo*, *Christ reposing*; *Guercino*, *Circumcision*; *Perugino*, *SS. James and Gregory*; *Dürer*, *Madonna and the Child*, bestowing bouquets of roses on the Emp. *Maximilian* and his consort, a celebrated picture containing numerous figures, painted by the master at Venice in 1506, originally preserved in the *Imperial Gallery* at Vienna, brought to Paris by *Napoleon I.* and presented to Lyons. There are also works by *Rubens* and *Jordaens*, *A. del Sarto*, the *Caracci*, and others. — On the floor above the *GALERIE DES PEINTRES LYONNAIS*: *Bonnefond*, *Portrait of Jacquard*, inventor of the improved loom, born at Lyons in 1752, died 1834; *Paul* and *Hippolyte Plandrin*, and others.

The *MUSÉE ARCHÉOLOGIQUE*, also on the first floor, contains the \*bronz tablets (found in 1528) with the speech delivered by the Emperor *Claudius* before the Senate at Rome in the year 48, in defence of the measure of bestowing citizenship on the Gauls ('*Tables Claudiennes*'); in the central saloon, antique and mediæval bronzes, coins, trinkets, and various curiosities. — There is also a *Musée d'Histoire Naturelle* here, and a *Library*.

The second floor of the *Palais du Commerce et de la Bourse* (Pl. 68; D, 3) contains the *Musée d'Art et d'Industrie*, founded in 1858; the specimens in illustration of the silk-culture are particularly instructive.

The *Civic Library* (Pl. 6; D, 3) possesses 150,000 vols. and 2400 MSS. In the neighbouring *Place Tholozan* rises the bronze *Statue of Marshal Suchet*, '*Duc d'Albufera*' (born at Lyons 1770, d. 1826), and the *Place Sathonay* (Pl. D, 4) is adorned with a statue of *Jacquard* (see above), executed by *Foyatier*.

Two magnificent new streets, the *Rue de Lyon* (formerly *Impériale*) and the *Rue de l'Hôtel de Ville* (formerly *de l'Impératrice*) lead from the *Hôtel de Ville* to the \**Place Bellecour* (formerly *Louis le Grand*; Pl. E, 3), one of the most spacious squares in Europe, and adorned with an *Equestrian Statue of Louis XIV.* by *Lemot*. — The *Rue de Bourbon* leads thence to the *Place Perrache* with the station of that name (formerly *Place* and *Cours Napoléon*; Pl. F, 4).

Beyond the station, and occupying the point of the tongue of

land between the rivers, is the suburb *Perrache*, named after its founder (1770), and rapidly increasing in extent. (From the station to the confluence of the rapid Rhone and sluggish Saône,  $1\frac{1}{4}$  M.)

If time permits, the traveller should visit the \**Parc de la Tête d'Or*, on the left bank of the Rhone (Pl. B, C, 1, 2; 1 M. from the Place des Terreaux), laid out in 1857, and containing rare plants, hothouses, and pleasure-grounds in the style of the Bois de Boulogne at Paris.

The RAILWAY TO MARSEILLES (Gare de Perrache) descends the valley of the Rhone, which flows on our right.


337 M. **Vienna** (*Hôtel du Nord*; *Hôtel de la Poste*), the *Vienna Allobrogum* of the ancients, with 24,800 inhab., lies on the left bank of the Rhone, at the influx of the *Gère*. Several interesting mementoes of its former greatness are still extant. The so-called \**Temple of Augustus*, of the Corinthian order (88 ft. long, 49 ft. wide, 56 ft. high), with 16 columns, and hexastyle portico, is approached from the ancient forum by twelve steps, in the middle of which stands an altar. The temple was used in the middle ages as a church, but has been restored as nearly as possible to its original condition. The ancient abbey-church of \**St. Pierre*, of the 6th cent., altered in the 18th and now restored, contains a museum of Roman antiquities. — The \**Cathedral of St. Maurice* (between the temple of Augustus and the bridge across the Rhone), begun at the close of the 11th cent., but not completed till 1515, possesses a fine façade of the transition period. — On the high road,  $\frac{1}{4}$  M. S. of the town, stands an archway surmounted by an obelisk called the \**Plan de l'Aiguille*, which once served as the meta (goal) of a circus.

Vienna is not visible from the railway, which passes under part of the town by a tunnel. Immediately beyond the town rises the Plan de l'Aiguille, mentioned above. The banks of the Rhone rise in gentle slopes, planted with vines and fruit-trees. On the right bank, at some distance from the river, towers *Mont Pilat* (3750 ft.), a picturesque group of mountains, at the base of which lie the celebrated vineyards of *La Côte Rôtie*. — 356 M. *St. Rambert* (branch-line to Grenoble). — 373 $\frac{1}{2}$  M. *Tain*, where the valley of the Rhone contracts; on the left rises the extensive vineyard of *Ermilage*, where the well known wine of that name is produced. In the distance to the left the indented spurs of the Alps are conspicuous, above which in clear weather the gigantic Mont Blanc is visible. Tain is connected by means of a suspension-bridge with *Tournon*, on the opposite bank, a small town with picturesque old castles of the Counts of Tournon and Dukes of Soubise.

On our left, in the direction of the Little St. Bernard, now opens the broad valley of the turbid *Isère*, which is also traversed by a railway to Grenoble. In September, B. C. 218. Hannibal




# AVIGNON



- |    |                             |                        |
|----|-----------------------------|------------------------|
| 28 | Palais de Justice           | E 4                    |
| 29 | Pénitencier                 | C. 5. 6                |
| 30 | Poste aux Lettres           | E. 3                   |
| 31 | Préfecture                  | C. D. 3                |
| 32 | Séminaire St Charles        | B. 4                   |
| 33 | Statue d'Albin              | E. 1                   |
| 34 | du Grillon                  | D. 3                   |
| 35 | Télégraphe                  | C. 3                   |
| 36 | Théâtre                     | B. 2. 3                |
| 37 | Tombeaux de Loure et Folant | a de l'Europe C. D. 2  |
| 38 | Tour des Abbayes            | b du Louvainbourg E. 4 |
| 39 | Restes de l'Empire romain   | c. du Louvre C. 2      |

### Hôtels



- 1 Anc. Hôtel Grillon D.4
- 2 Anc. Hôtel des Monnaies D.2
- 3 Anc. Palais des Papes E.2.3  
(Caserne du Palais)
- 4 Anc. Palais de la Reine D.2  
Jeanne
- 5 Archevêché D.3
- 6 Banque de France D.2
- 7 Bourse D.3.4
- 8 Collège St. Joseph E.5  
Embarcadere du Chemin  
de fer B.6

- Eglises**
- 9 St. Agricol C.D.3.5
  - 10 Cathédrale N. D. E.2
  - 11 St. Didier D.4
  - 12 de l'Oratoire C.3
  - 13 des Peintures gris E.5
  - 14 . . . . . noirs F.2
  - 15 . . . . . blancs D.4
  - 16 St. Pierre D.E.3
  - 17 St. Saphorien F.3
  - 18 Temple protestant C.D.3.6
  - 19 . . . . . israelite E.4
  - 20 la Glacière
  - 21 Halle et Marche E.4

- 22 Hospice St. Louis B.C.5
- 23 Hotel Dieu G.H.4
- 24 Hotel de Ville D.3
- 25 Lycée C.D.4
- 26 Musée Calvet C.3
- 27 . . . d'Histoire C.A.5  
(Mus. du botanique)



ascended this valley with his army, and crossed the Little St. Bernard into Italy.

384 M. **Valence** (*Hôtel de France*), the *Valentia* of the ancients, once the capital of the Duchy of *Valentinois*, with which the infamous Cæsar Borgia was invested by Louis XII., is now the chief town of the Department of the Drôme, with 20,000 inhab. The situation is picturesque, but there is little else to arrest the traveller's attention. — On the right bank lies *St. Peray*, famous for its wine.

411 M. *Montélimar*. The ancient castle of the once celebrated *Monteît d'Adhémar* family rises on an eminence from the midst of mulberry-trees. The line here quits the Rhone; the plain on the right expands.

443 M. **Orange** (*\*Hôtel de la Poste*), 3 M. from the Rhone, the *Arausio* of the Romans and once a prosperous and important place. In the middle ages it was the capital of a small principality, which, on the death of the last reigning prince without issue in 1531, fell to his nephew the Count of Nassau, and until the death of William III. (d. 1702), king of England, continued subject to the house of Nassau-Orange. By the Peace of Utrecht, Orange was annexed to France, and the house of Nassau retained the title only of princes of Orange. The antiquarian should if possible devote a few hours to the interesting Roman remains at Orange. On the road to Lyons,  $\frac{1}{4}$  M. N. of the town, is a *\*Triumphal Arch*, with three archways and twelve columns, probably dating from the close of the 2nd cent. On the S. side of the town, at the foot of an eminence, lies the *\*Roman Theatre*, 118 ft. in height, 338 ft. in length, with walls 13 ft. in thickness (conceige  $\frac{1}{2}$ -1 fr.). The admirably preserved wall of the stage still contains the three doors by which the actors entered; most of the tiers of seats for the spectators, however, have entirely disappeared. The acoustic arrangement of the structure is admirable. Scanty remnants of a *Circus* adjoin the theatre. The height above the theatre, once occupied by the citadel of Orange which was destroyed by Louis XIV., affords a good survey of the neighbourhood. The promenade is adorned with a statue of the *Comte de Gasparin* (d. 1862).

Beyond Orange the line traverses a plain, at a considerable distance from the Rhone and the mountains, where olives begin to indicate the proximity of a warmer climate. — From (455 M.) *Sorgues* a branch-line runs to *Carpentras* (10 $\frac{1}{2}$  M.; *Hôt. de la Poste*), the Palais de Justice of which contains a *Triumphal Arch* of the 3rd cent.

461 M. **Avignon** (*\*Hôtel de l'Europe*, Pl. a, dear; *Hôtel du Luxembourg*, Pl. b; *Louvre*, Pl. c; all  $\frac{3}{4}$  M. from the station, omnibus 50 c.; best *Cafés* in the Place), the *Avenio* of the Romans. The old city-wall, constructed of massive blocks of stone in 1349-68.



with numerous gates, admirably preserved and affording an interesting example of the fortifications of that period, testify to its ancient importance. In the reign of Louis XIV. it contained 80,000 inhab. (now 36,400). Avignon was once a Roman colony, afterwards belonged to the Burgundians, then to the Franks, became the capital of the County of Venaissin, lost its independence to Louis VIII. in 1226, fell into the hands of Charles of Anjou in 1290, was the residence of the popes from 1309 to 1377, seven of whom, from Clement V. to Gregory XI., reigned here (the latter transferred his seat to Rome in 1377), and continued subject to the pontifical sway until it was annexed to France by the Revolution in 1791.

The town lies on the left bank of the Rhone, a little above the influx of the Durance, and is connected with *Villeneuve* on the opposite bank by a suspension-bridge. It is commanded by the abrupt *Rocher des Doms* (rupes dominorum), 300 ft. in height, which is surmounted by the *Cathedral of Notre Dame*, (Pl. 10), a structure of the 14th cent., recently restored. The portico is of considerably earlier origin. The church contains the handsome \*monument of Pope John XXII. (Euse of Cahors, d. 1334), and that of Benedict XII. (d. 1342) in the left aisle.

In the vicinity of the cathedral rises the \**Papal Palace* (Pl. 3; E. 2), a lofty and gloomy pile, erected by Clement V. and his successors, with huge towers and walls 100 ft. in height. The faded frescoes in the *Chapelle du St. Office* were executed by Simone Memmi of Siena (d. 1339). Rienzi was incarcerated here in 1351 in the *Tour des Oubliettes*, at the same time as Petrarch was entertained in the palace as a guest.

Pleasant grounds have been laid out on the hill near the cathedral. The best point of view is a rocky eminence in the centre. The \*prospect, one of the most beautiful in France, embraces the course of the Rhone and its banks; Villeneuve on the opposite bank with its citadel and ancient towers; in the distance towards the N.W. the Cevennes; N.E. Mont Ventoux; E. the Durance, resembling a silver thread, and beyond it the Alps; below the spectator the tortuous and antiquated streets of Avignon. On the promenade is a statue to *Jean Althen*, erected in 1846, out of gratitude to him for having in 1766 introduced the cultivation of madder, which now forms the staple commodity of the district (used extensively in dyeing the French red military trowsers).

At the base of the Rocher des Doms lies the Place de l'Hôtel de Ville (Pl. D. 3), with a number of handsome modern edifices. In front of the *Theatre* (Pl. 36) are statues of Racine and Molière; the medallions above represent John XXII. and Petrarch. The neighbouring *Hôtel de Ville* (Pl. 24) possesses a quaint clock with figures which strike the hours. In front of it stands a *Statue of Crillon* (Pl. 34), erected in 1858 to this celebrated soldier (d. at Avignon in 1615); the pedestal bears his motto, '*Fais ton devoir*'.

In the Rue Calade is the \**Musée Calvet* (Pl. 26, C. 3; open daily, custodian 1 fr.), containing a few ancient pictures, numerous works of the *Vernet* family who were natives of Avignon (*Joseph*, the painter of sea-pieces, his son *Carle*, and his celebrated grandson *Horace*), several small works of art, coins, etc. — The Library contains 80,000 vols. and 2000 MSS.

In the garden at the back of the Museum a monument was erected in 1823 by Mr. Charles Kensall to the memory of Petrarch's *Laura*. Her tomb was formerly in the Eglise des Cordeliers, but was destroyed with the church during the Revolution.

In 1326, *Francesco Petrarca*, then 22 years of age, visited Avignon, and beheld *Laura de Noves*, who was in her 18th year, at the church of the nunnery of St. Claire. Her beauty impressed the ardent young Italian so profoundly, that, although he never received the slightest token of regard from the object of his romantic attachment, either before or after her marriage with Hugues de Sade, he continued throughout his whole lifetime to celebrate her praises in songs and sonnets. In 1334 he quitted Avignon for Vacluse, travelled in France, Germany, and Italy, and returned to Avignon in 1342 (with his friend Cola di Rienzi), where he found *Laura* the mother of a numerous family. She died in 1348, bowed down by domestic affliction. Petrarch lived till 1374, and long after *Laura's* death dedicated many touching lines to her memory.

The long and intimate connection of Avignon with Rome, as well as its reminiscences of Petrarch, may be said to invest the town with an almost Italian character. The whole of *Provence* indeed recalls the scenery of the south more than any other district in France.

Avignon is a very windy place. The prevailing *Mistral* often blows with great violence, and has given rise to the ancient saying:

*Avenio ventosa,  
Sine vento venenosa,  
Cum vento fastidiosa.*

THE FOUNTAINS OF VAUCLUSE may easily be visited in the course of an afternoon with the aid of the Avignon-Cavaillon branch-railway. After several unimportant stations, the train reaches *L'Isle sur Sorgue* (in 1-1/2 hr.; fares 2 fr. 90, 2 fr. 20, 1 fr. 65 c.). Thence drive or walk up the valley of the Sorgue, following its sinuosities towards Mont Ventoux, to the (3 M.) village of *Vaucluse* (Hôtel de Laure). A footpath leads hence in 1/4 hr. into the *Vaucluse* ravine, a rocky gorge, above which the ruined castle of the Bishops of Cavaillon rises on the right. At its extremity the sources of the Sorgue emerge from a profound grotto, at one time in precipitate haste, at another in gentle ripples. This spot is mentioned by Petrarch in his 14th Canzone, 'Chiarc, fresche e dolci acque.'

Soon after quitting Avignon the train crosses the broad bed of the often impetuous and turbid *Durance*, the Roman *Druentia*, which descends from the Cottian Alps to the Rhone.

474 M. **Tarascon** (*Hôtel des Empereurs*), with 12,400 inhab., once the seat of King René of Anjou, the great patron of minstrelsy, whose lofty old castle and above it the Gothic spire of the church of *St. Marthe* (14th cent.) arrest the traveller's attention. — On the opposite bank, and connected with Tarascon by a bridge, is situated the busy town of *Beaucaire*, commanded by an ancient castle of the Counts of Toulouse.

FROM TARASCON TO ST. RÉMY (10 M., one horse carr. for the excursion 10 fr.). On the site of the ancient *Glanum*,  $\frac{1}{2}$  M. above the small town, are situated two interesting *Roman Monuments*. One of these, 53 ft. in height, resembling the celebrated monument of Igel near Trèves, was erected by the three brothers Sextus, Lucius, and Marcus Julius to the memory of their parents, and is constructed of massive blocks of stone in three different stories. This magnificent relic belongs to the time of Cæsar. Adjacent to it is a half ruined *Triumphal Arch*, also adorned with sculptures.

Continuation of the line to Marseilles, see p. 14.

RAILWAY FROM TARASCON TO NIMES in  $\frac{3}{4}$  hr. (fares 3 fr. 30, 2 fr. 45, 1 fr. 80 c.). The train crosses the Rhone to Beaucaire (p. 11) and passes several unimportant stations.

$16\frac{1}{2}$  M. **Nîmes.** — Omnibus to the hotels  $\frac{1}{2}$  fr., cab 1 fr. — HÔTEL DU LUXEMBOURG (Pl. a), in the Esplanade; CHEVAL BLANC (Pl. b), opposite the Arena, R. 2, A. 1, D.  $3\frac{1}{2}$  fr.; HÔTEL MANIVET (Pl. c), opposite the Maison Carrée, moderate; HÔTEL DU MIDI (Pl. d), Place de la Couronne. Good *Cafés* in the esplanade, opposite the Arena and the Maison Carrée.

Nîmes, the ancient *Nemausus*, capital of the Gallic *Arecomaci*, and one of the most important places in Gallia *Narbonensis*, is now the chief town of the Department of the Gard. The town, which numbers 15,000 Protestants among its present population of 60,000, has several times been the scene of fierce religious struggles, especially during the reign of Louis XIV.


The town is surrounded by pleasant Boulevards, which terminate in the *Esplanade*, adorned with a handsome modern fountain-group (representing the city of Nemausus, with four river-deities below).

The extremely interesting Roman antiquities are not far distant from the station. We first reach the *Arena*, or *Amphitheatre* (Pl. 3, E, 4), consisting of two stories, each with 60 arcades, together 74 ft. in height. The exterior is in excellent preservation. The interior contains 32 tiers of seats (entrance on the W. side, where a notice indicates the dwelling of the concierge; 50 c.), and could accommodate 23,000 spectators; longer axis 148, shorter 112 yds., height 74 ft., inner arena 76 by 42 yds.; upper gallery about  $\frac{1}{4}$  M. in circumference.

The founder is unknown, but is conjectured to have been the emperor Antoninus Pius, about B.C. 140, whose ancestors were natives of Nemausus. The four original entrances are still traceable. Doors in the pavement of the arena lead to the (modern) 'souterrain', the ceiling of which is supported by beams. In the middle ages the Arena was employed by the Visigoths and afterwards by the Saracens as a fortress. Extensive works of restoration are now going on, especially in the interior and on the E. side of the exterior, as the Arena is still used for the exhibition of bull-fights (but of a bloodless character).


The next object of interest is the *Maison Carrée* (Pl. 19; D, 3), a well preserved temple (83 ft. long, 42 ft. wide), with 30 Corinthian columns (10 detached, 20 immured), dating from the reign of Augustus, or, more probably, of Antoninus Pius, employed as a church in the middle ages and subsequently as a town-hall. This





- |    |                           |        |
|----|---------------------------|--------|
| 1  | Abattoir (grand)          | B 4 5  |
| 2  | (petit)                   | D 4    |
| 3  | Arènes                    | E 4    |
| 4  | Caserne                   | F 2    |
| 5  | Collège                   | F 3    |
| 6  | École Mutuelle            | C 3    |
|    | <b>Eglise</b>             |        |
| 7  | Cathédrale (St. Gaster)   | E 3    |
| 8  | St. Charles               | E 2    |
| 9  | St. Beaulé                | F 3    |
| 10 | St. Paul                  | D 3    |
| 11 | St. Perpetue              | F 4    |
| 12 | Grand Temple              | E 3    |
| 13 | Petit Temple              | D 2    |
| 14 | Evêché                    | E 3    |
| 15 | Hôtel Dieu                | D 4    |
| 16 | Hôtel de Ville            | E 3    |
| 17 | Hôpital                   | D 4    |
| 18 | Manufacture               | F 4    |
| 19 | Maison carrée             | D 3    |
| 20 | d'Arrets                  | E 4    |
| 21 | Centrale                  | E 1    |
| 22 | Palais de Justice         | E 4    |
| 23 | Porte d'Auguste           | F 3    |
| 24 | de France                 | F 4 5  |
| 25 | Prefecture                | E 3    |
| 26 | Santaire                  | C 3    |
| 27 | Synagogue                 | F 4    |
| 28 | Temple de Diane (Jupiter) | B. C 2 |
| 29 | Théâtre                   | D 3    |
| 30 | Tour maque                | C 1    |

# NIMES.



## Place

|                        |       |
|------------------------|-------|
| I de la Belle Croix    | E.3   |
| II de la Comédie       | D.3   |
| III de la Couronne     | F.3.4 |
| IV de l'Ecluse         | F.3   |
| V aux Herbes           | E.3   |
| VI de l'Hôtel de Ville | E.3   |
| VII de Marché          | E.3   |
| VIII Marché aux Bœufs  | D.4   |
| IX de Montcalm         | D.5   |
| X S. Paul              | D.3   |
| XI la Placette         | C.4   |
| XII de la Salamandre   | E.3   |

## Hôtels

|                 |     |
|-----------------|-----|
| a de Luxembourg | F.4 |
| b Cheval blanc  | E.4 |
| c Monivret      | E.4 |
| d du Midi       | D.3 |



temple was connected with other buildings, the foundations of which still exist, and in all probability constituted part of the ancient forum, like the similar Temple of Augustus at Vienne (p. 8). It now contains a \**Museum* of antiquities and several good, chiefly modern, French pictures. The concierge lives opposite (1 fr.).

From the Maison Carrée the visitor should next proceed by the Boulevards and the canal to the *Jardin de la Fontaine*, where the \**Nymphæum* (Pl. 28; B, C, 2), formerly supposed to be a *Temple of Diana*, is situated. This fine vaulted structure, with niches for the reception of statues, has partly fallen in; it contains statues, busts, architectural fragments, etc., from the excavations which have been made here. The nature of the extensive ruins behind the Nymphæum cannot now be ascertained. Here, too, are the Roman \**Baths* excavated by Louis XIV. They contain a large peristyle with low columns, a number of niches, a basin for swimming, and the spring by which Nîmes is now supplied with water. Well kept pleasure-grounds in the rococo style adjoin the baths. (The concierge at the E. entrance to the garden keeps the keys of the Nymphæum and the Baths; 1 fr.)

Beyond the spring rises a hill with promenades, surmounted by the \**Tourmagne* (turris magna; Pl. 30; C, 1), a Roman structure, variously conjectured to have been a beacon-tower, a temple, or a treasury (keys at a small red house, to the right on the way from the baths, about 200 paces below the summit). It was more probably a monumental tribute to some illustrious Roman. The tower is of octagonal form, and is ascended by a modern staircase of 140 steps. The \*view from the summit well repays the ascent; it embraces the town and environs, as far as the vicinity of the estuary of the Rhone, and the distant Pyrenees to the W. The extent of the ancient Nemausus is distinctly recognised hence; two of the ancient gates, the *Porta Augusti* (Pl. 23; F, 3) and the *Porte de France* (Pl. 24; D, 4, 5) are still preserved. The former, discovered in 1793, has four entrances and bears the inscription: IMPER. CAESAR. DIVI. F. AVGVSTVS. COS. XI. TRIB. POT. PORTAS. MVROS. QVE. COL. DAT., signifying that Augustus provided the colony of Nemausus with gates and walls in the year B.C. 23. The other gate is of simpler construction, and one arch of it only is preserved.

EXCURSION TO THE PONT DU GARD, 14½ M., uninteresting country, by carr. in 2 hrs. One-horse carr. there and back 12 fr. (from the Hôtel du Luxembourg). Or the traveller may avail himself of one of the omnibuses which run to *Remoulins* several times daily, as far as *La Four*, whence a road on the right bank of the Gard leads to the far-famed 'Pont' (1½ M.), at a small house near which refreshments may be obtained.

The \*\**Pont du Gard*, a bridge and aqueduct over the Gard, which descends from the Cevennes, passing the town of *Alais* with its extensive iron-works, is one of the grandest Roman works in existence. The desolate rocky valley of the Gard is bridged over by a threefold series of arches (the lowest 6, the next 11, and the highest 35 in number) which present a most majestic appearance. Agrippa, the general of Augustus,



is supposed to have been the founder. The object of this structure was to supply Nîmes with water from the springs of Airan near St. Quentin and Ure near Uzès, a distance of 25 M. Several arches are also seen to the N. of the Pont du Gard, and other traces of the aqueduct still exist nearer the town. The bridge for carriages was added to the Roman aqueduct in 1743.

Beyond Nîmes the train traverses the broad and fertile plain on the S. of the Cévennes, and in 1<sup>1</sup> 2-2 hrs. reaches —

**Montpellier** (*Hôtel Nevet*), capital of the Department of the Hérault, an industrial town with 55,600 inhab., and the seat of a university founded in 1196. The finest point in the town is the \**Promenade du Peyrou*, an extensive terrace planted with lime-trees, with an equestrian *Statue of Louis XIV.*, and the *Château d'Eau*. Fine view hence; in clear weather the summit of the Canigou in the Pyrenees is visible. The *Jardin des Plantes* is the oldest in France. The *Musée Favre* contains a picture-gallery of some value, the gem of which is a \**Portrait of Lorenzo de' Medici* by Raphael. The public *Library* possesses a few interesting MSS. and other curiosities.

FROM TARASCON (p. 11) TO ARLES the railway skirts the left bank of the Rhone. The country, which is flat, and planted with the vine and olive, presents a marked southern character. The manners and unintelligible patois of the inhabitants differ materially from those of N. France. The peculiar softness of the old Provençal language employed by the *Troubadours* may still be traced. *S* is pronounced here like *sh* (e. g. *persshonne*), *ch* like *s* (*serser* for *chercher*). These characteristics, as well as the vivacious and excitable temperament of the natives, betoken the gradual transition from France to Italy.

483 M. **Arles** (\**Hôtel du Nord*; *Hôtel du Forum*), the *Arelate* or *Arelas* of the ancients, once one of the most important towns in Gaul, is now a somewhat dull place (26,400 inhab.) on the Rhone, 24 M. from its mouth. It is connected with *Trinquetaille* on the opposite bank by a bridge of boats.

The principal sights of Arles, for which 3-4 hrs. suffice, are all within easy distance from the hotels: to the E. St. Trophime, the extensive Museum, and the Theatre of Augustus; N. the Amphitheatre, and S.E. the Champs-Élysées.

In the Place of the *Hôtel de Ville*, which was erected in 1673, rises an \**Obelisk* of grey granite from the mines of Estrelle near Fréjus (p. 27), an ancient monument of unknown origin, found in the Rhone in 1676.

In the vicinity stands the \**Cathedral of St. Trophime* (Trophimus is said to have been a pupil of St. Paul), founded in the 6th or 7th cent., possessing an interesting Romanesque \**Portal* of the 12th or 13th cent., of semicircular form, supported by twelve columns resting on lions, between which are apostles and saints (St. Trophimus, St. Stephen, etc.); above it Christ as Judge of the world.

The INTERIOR contains little to interest the visitor, with the exception of several sarcophagi and pictures. — On the S. side (entered from the sacristy) are the \**Cloisters*, with round and pointed arches and remarkable capitals, dating from various epochs. The N. side is in the half antique style of the Carlovingian period (9th cent.), the E. side

dates from 1221, the W. side (the most beautiful) from 1389, and the S. side from the 16th cent.

The \**Museum*, established in the old church of St. Anna, contains numerous antiquities found in and near Arles. The following relics deserve special mention: \*head of Diana (or Venus); Augustus (found in 1834); recumbent Silenus with pipe, once used as a fountain-figure; and sarcophagi from the ancient burial-ground (see below), etc.

The \**Theatre* (commonly called that of 'Augustus'), a most picturesque ruin, is in a very dilapidated condition. The most perfect part is the stage-wall, which according to the ancient arrangement had three doors. In front of it was a colonnade, of which two columns, one of African, the other of Carrara marble, are still standing. The opening for the letting down of the curtain is distinctly recognisable. The orchestra, paved with slabs of variegated marble, contained the seats of persons of rank. The lower tiers only of the seats of the ordinary spectators are preserved.

The theatre once possessed a second story, indications of which are observed when the ruin is viewed from the Saracens' Tower (in the direction of the public promenade). The dimensions of the building when perfect were very extensive (breadth from N. to S. 337½ ft.), and the effect it produces is extremely striking.

The \**Amphitheatre* is larger than that of Nîmes (p. 12), but in inferior preservation. It is nearly 500 yds. in circumference; the arena is 75 yds. long and 40 yds. wide. The entrance is on the N. side. It possessed five corridors and tiers of seats for 25,000 spectators. The two stories of 60 arches, the lower being Doric, the upper Corinthian, present a most imposing aspect.

The INTERIOR (the concierge lives opposite the N. entrance) was formerly occupied by a number of dwellings tenanted by poor families, but these have been almost entirely removed since 1846-47. After the Roman period the amphitheatre was employed by the Goths, then by the Saracens, and again by Charles Martel (who expelled the latter in 739), as a stronghold, two of the four towers of which are still standing. A staircase of 103 steps ascends the W. tower, which commands a pleasing survey of the neighbourhood. The vaults beneath the lowest tier of seats served as receptacles for the wild beasts, the gladiators, etc. They communicated with the arena by means of six doors. The spectators of high rank occupied the front seats and were protected from the attacks of the wild animals by a lofty parapet. Bloodless bull-fights are now occasionally exhibited here.

In the *Place du Forum*, the site of the ancient market-place, two granite pillars and fragments of a Corinthian pediment are still seen (near the Hôtel du Nord).

On the S.E. side of the town are the *Champs Elysées* (Aliscamps), originally a Roman burying-ground, consecrated by St. Trophimus and furnished by him with a chapel. In the middle ages this cemetery enjoyed such celebrity that bodies were conveyed hither for sepulture from vast distances. It is mentioned by Dante in his *Inferno* (9, 112): '*Si come ad Arli, ove Rodano stagna, . . . fanno i sepolcri tutto il loco varo*'. ('As at Arles where the Rhone is dammed, . . . the graves make the whole ground uneven'.)

To this day many ancient sarcophagi are still to be seen in the environs of the curious old church, although after the first Revolution great numbers were sold to relic-hunters from all parts of the world.

FROM ARLES TO MONTPELLIER (p. 14) a branch-line runs in 1½ hr. Below Arles begins the flat delta of the estuary of the Rhone called the *Ile de la Camargue*. It is protected against the incursions of the sea by dykes, and is employed partly as arable and partly as pasture land, which supports numerous flocks and herds. The delta encloses the *Etang de Valcarès*, at the mouth of which, on the *Petit Rhône*, near the sea, is situated *Ste. Marie*, the only village on the Camargue. A canal, constructed in 1864-71, admits vessels to the estuary of the Rhone, which had previously been inaccessible.

Between Arles and *Salon* the line intersects the stony plain of *Crau*, which the ancients mention as the scene of the contest of Hercules with the Liguers. Near *St. Chamas* the line skirts the long *Etang de Berre*, an extensive inland lake on the right. From (519 M.) *Rognac*, a branch-line diverges to *Aix*, the ancient *Aquæ Sextiæ*. Beyond (525 M.) *Pas-des-Lanciers* the train traverses the longest tunnel in France, nearly 3 M. in length, on emerging from which it passes some grand rocky scenery. The sea now comes in sight, and the rocky islands of *Château d'If*, *Ratonneau*, etc. are seen rising from the Gulf of Marseilles.

536 M. **Marseilles.** — Arrival. *Hotel Omnibuses* at the station (½-1½ fr.). *Cabs* ('voitures de la gare'), 1 pers. 1 fr. 25, after 10 p. m. 1 fr. 50 c. — Carriages in the town ('voitures de place'), per drive 1 fr. 50, per hour 2 fr. 25 c.

**Hotels.** GRAND HÔTEL DU LOUVRE ET DE LA PAIX (Pl. a), with 250 rooms. principal façade facing the S., GRAND HÔTEL DE MARSEILLE (Pl. b), HÔTEL NOAILLES (Pl. c), all three in the Rue de Noailles, and fitted up in the style of the great Parisian hotels, rooms from 2 fr. upwards, table d'hôte at 6 p. m. 5 fr., B. 1½ fr., A. and L. 1½ fr.; HÔTEL DU PETIT LOUVRE (Pl. d), Rue Cannebière 16, moderate, R. 2 fr.; HÔTEL DU LUXEMBOURG (Pl. e), Rue St. Ferréol 25; HÔTEL DES COLONIES, Rue Vacon; HÔTEL DES PRINCES (Pl. g), Place de la Bourse (formerly Place Royale); HÔTEL D'ITALIE (Pl. i), at the harbour; HÔTEL DE ROME (Pl. k). — *Bouillabaisse*, a good fish. — The white wines usually drunk are *Chablis*, *Graves*, and *Sauterne*.

**Cafés.** The *Cannebière* contains a great number of handsome cafés in the Parisian style.

**Post Office**, Rue de Grignan, 53.

**Steamboats** to *Ajaccio* (Corsica) once weekly in 26 hrs., fare 40 or 25 fr.; to *Algiers* 3 times weekly; to *Genoa* almost daily; to *Civita Vecchia* twice weekly; to *Naples* direct every Thursd.; to *Malta* on the 1st and 15th of every month.

**Sea Baths**, bandsomely fitted up, in the *Ause des Catalans*, on the E. side of the town, below the conspicuous former *Résidence Impériale*, which is now a hospital; also warm seawater-baths, douche, vapour, etc., for gentlemen and ladies. Adjacent, a large HÔTEL, with restaurant. Omnibus to or from the town 30 c.

**English Church Service** performed by a resident chaplain.

*Marseilles*, with upwards of 300,000 inhab., the capital of the Department of the Embouchures of the Rhone, is the principal seaport of France, and the dépôt of a brisk maritime traffic with the East, Italy, and Africa.


*Massilia* was a colony founded about B.C. 600 by Greeks from Phocæa





## Marseille

- |                    |       |                           |       |                          |       |
|--------------------|-------|---------------------------|-------|--------------------------|-------|
| 1. Arc de Triomphe | C. 5. | 8. Conserv. de Musique    | D. 2. | 54. Lycée Impérial       | D. 4. |
| 2. Arsenal         | E. 5. | 9. Douane                 | —     | 55. Manufact. des Tabacs | A. 2. |
| 3. Banque          | E. 5. | 17. Gendarmerie           | C. 4. | 54. Musée                | B. 1. |
| 4. Bibliothèque    | D. 2. | 28. Halle neuve           | D. 5. | 55. Observatoire         | —     |
| 5. Bourse          | D. 3. | 29. Hôpital de la Charité | C. 4. | 56. Palais de Justice    | E. 3. |
| 6. Casernes        | D. 5. | 30. — du St-Esprit        | D. 4. | 57. Poste aux lettres    | E. 3. |
| 7. Casino          | C. 5. | 51. Hôtel de Ville        | D. 4. | 58. Préfecture           | E. 2. |



**Eglises**

|                        |     |
|------------------------|-----|
| 10. du Calvaire        | D 4 |
| 11. Notre Dame du Mont | D 2 |
| 12. " du M. Carmel     | C 4 |
| 13. des Precheurs      | D 3 |
| 14. St Charles         | F 3 |
| 15. St Ferréol         | D 3 |
| 16. St Joseph          | E 2 |
| 17. St Laurent         | D 3 |
| 18. St Lazare          | B 4 |
| 19. St Martin          | C 3 |
| 20. St Michel          | C 1 |
| 21. St Théodore        | C 5 |
| 22. St Victor          | E 4 |
| 23. St Vincent de Paul | C 2 |
| 24. de la Trinité      | D 2 |
| 25. Eglise grecque     | C 2 |
| 26. protestante        | E 3 |

**Hôtels**

|                 |     |
|-----------------|-----|
| a. Louvre       | D 3 |
| b. Marville     | D 3 |
| c. Saittes      | D 3 |
| d. Petit Louvre | D 3 |
| e. Luxembourg   | D 3 |
| f. Ambassadeur  | D 3 |
| g. Prince       | D 3 |
| h. Bero         | D 3 |
| i. Italo        | D 3 |
| k. Catalans     | F 5 |
| l. Victoria     | H 4 |

Lignes de chemins de fer  
 Chemins de fer  
 (grand)  
 du Gymnase  
 Chare  
 F 2  
 E. F. 5  
 D 3  
 C 2  
 D 1

Stat. de Chemins de fer B.C.S.



in Asia Minor, who soon became masters of the sea, defeated the Carthaginians in a naval battle near Corsica, and established new colonies in their neighbourhood, such as *Taurœis* (near Ciotat), *Olbia* (near Hyères), *Antipolis* (Antibes), and *Nicaea* (Nice), all of which, like their founders, adhered to the Greek language, customs, and culture. Massilia maintained this reputation until the imperial period of Rome, and was therefore treated with leniency and respect by Julius Cæsar when conquered by him, B.C. 49. Tacitus informs us that his father-in-law Agricola, a native of the neighbouring Roman colony of Forum Julii (Fréjus), even under Claudius, found ample opportunities for completing his education at Massilia in the Greek manner, for which purpose Athens was usually frequented. The town possessed temples of Diana (on the site of the present cathedral), of Neptune (on the coast), of Apollo, and other gods. Its government was aristocratic. After the fall of the W. Empire Marseilles fell successively into the hands of the Visigoths, the Franks, and Arelate; it was destroyed by the Saracens, restored in the 10th cent. and became subject to the *Vicomtes de Marseille*; in 1218 it became independent, but shortly afterwards succumbed to Charles of Anjou. In 1481 it was united to France, but still adhered to its ancient privileges, as was especially evident in the wars of the Ligue, against Henry IV. In 1660 Louis XIV. divested the town of its privileges, so that it retained its importance as a sea-port only. In 1720 and 1721 it was devastated by a fearful pestilence. During the revolution it remained unshaken in its allegiance to royalty and was therefore severely punished. In 1792 hordes of galley-slaves were sent hence to Paris, where they committed frightful excesses. It was for them that *Rouget de l'Isle*, an officer of engineers, composed the celebrated *Marseillaise*, 'Allons, enfants de la patrie', which subsequently became the battle-hymn of the republican armies.

The docks and quays (comp. plan) are very extensive. The harbour has been extended to four-times its former size since 1850, notwithstanding which there is still a demand for increased accommodation. In 1853 the *Port de la Joliette* was added to the *Ancien Port*, and is now the starting-point of most of the steamboats. The *Bassin du Lazaret* and *d'Arcenc* were added next, in 1856 the *Bassin Napoléon* (now *National*), and recently the *Bassin de la Gare Maritime*. Other extensions are projected.

The old harbour is long and narrow. Its entrance is defended by the forts of *St. Jean* and *St. Nicolas*. — Near the former is the *Consigne* (Pl. 6; D, 5; entrance by the gate, fee 50 c.), or office of the 'Intendance Sanitaire' (quarantine authorities).

The principal hall contains several good pictures: *Horace Vernet*, The cholera on board the frigate Melpomene; *David*, St. Rochus praying to the Virgin for the plague-stricken, painted in Rome. 1780; *Güérin*. The Chevalier Rose directing the sepulture of those who have died of the plague; *Puyet*, The plague at Milan, a relief in marble; *Gérard*, Bishop Belsunce during the plague of 1720; *Tanneurs*. The frigate Justine returning from the East with the plague on board.

A few paces farther N. is the *Cathedral* (Pl. C, D, 5), a new edifice constructed of alternate courses of black and white stone, in a mixed Byzantine and Romanesque style. The towers are surmounted by domes, designed by Vaudoyer. The terrace commands a pleasant survey of the Bassin de la Joliette. — To the E., in front of the old harbour, is the former 'Résidence Impériale', now *Château du Pharo*, a hospital (Pl. E, 5). In the vicinity are the sea-baths (p. 16).

\*LA CANNEBIÈRE (Pl. D, 3), a broad and very handsome street,



intersects the town from W. to E., from the extremity of the *Ancien Port* to the centre of the town where the ground rises. In this street, a few paces from the harbour, stands the *Bourse*, with a portico of Corinthian columns, erected 1854-60.

A short distance further the *Cours* (Pl. C, D, 3) is reached on the left, a shady promenade generally thronged with foot-passengers, at the S. end of which stands the statue of Bishop *Belsunce*, who during the appalling plague in 1720, which carried off 40,000 persons, alone maintained his post and faithfully performed the solemn duties of his calling. — From this point the *Rue d'Aix* ascends to the *Arc de Triomphe* (Pl. 1; C, 3), erected in 1823, and afterwards adorned with representations of Napoleonic battles in relief by *Ramey* and *David d'Angers*.

We now return to the *Cannebière*. Opposite the *Cours* opens the *Cours des Fleurs*, continued by the *Rue de Rome* and the *Cours du Prado*, which is 2½ M. in length. At the S. end of the latter is the *Château des Fleurs*, a small park with fishponds, affording various kinds of entertainments (comp. Pl. G, H, 1).

To the left in the *Cours des Fleurs* at the entrance to the narrow *Rue de la Palud*, is a fountain, adorned with an insignificant bust of *Pierre Puget*, the celebrated sculptor, who was a native of *Marseille* (1622-94).

At the E. end of the *Boulevard de Longchamp* rises the new and handsome \**Musée de Longchamp* (Pl. 34; B, 1), consisting of two extensive buildings connected by a colonnade of the Ionic order, adorned with a fountain in the centre. The right wing contains the *Musée d'Histoire Naturelle*; in the other is the *Musée des Beaux Arts*, containing several good pictures (*Perugino*, *Madonna and Saints*; *Murillo*, *Capuchin Monk*; *Holbein*, portrait, retouched, and others).

The well-kept grounds at the back of the Museum extend to the *Zoological Garden* (adm. 1 fr.), which contains a valuable collection of animals.

\*VIEW. The best survey of the town and environs is afforded by the church of \**NOTRE DAME DE LA GARDE* (Pl. F, 3), situated on an eminence to the S. of the old harbour, an ancient shrine, rebuilt from designs by *Esperandieu* in 1864. The highly ornate interior contains an image of the *Virgin* and innumerable votive tablets presented by those who have been rescued from shipwreck or disease. The terrace in front of the church, and especially the gallery of the tower (154 steps), which contains a huge bell, 10 tons in weight, and is to be crowned with a large figure of the *Virgin*, command an admirable survey of the extensive city, occupying the entire width of the valley, the innumerable white villas (*bastides*) on the surrounding hills, the harbour and the barren group of islands at its entrance, with the *Château d'If*, where *Mirabeau* was once confined (also mentioned in *Dumas' Monte Christo*), and part

of the Mediterranean. Several different paths ascend to this point from the old harbour, terminating in steps, a somewhat fatiguing climb. The full force of the prevailing *Mistral* (see p. 11), or piercing N.W. wind, the scourge of Provence, is often felt here.

The following drive of several hours is recommended. Ascend the *Promenade du Prado* (see above; Pl. F. G, 1), pass the *Château des Fleurs* (Pl. II, 1), descend to the sea, and return to the town by the picturesque *Chemin de Ceinture* (or *la Corniche*), on which lies *Rest. Roubion*, beautifully situated.

RAILWAY FROM MARSEILLES TO NICE (140 M., in 7 hrs.; fares 27 fr. 70, 20 fr. 75, 15 fr. 20 c.). The interesting route at first traverses rocky defiles at some distance from the sea, and, farther on, commands striking views. Several tunnels. — 23 M. *La Ciotat*, charmingly situated on the coast, and the most beautiful point on the whole journey.

42 M. **Toulon** (*Grand Hôtel*, near the station; *Victoria*; *Croix d'Or*), the war-harbour of France for the Mediterranean, with 77,100 inhab., possesses a double harbour, protected by eleven forts which crown the surrounding heights. In 1707 the town was besieged in vain by Prince Eugene, and in 1793 the inhabitants surrendered to the English Admiral Hood. In December of that year it was gallantly defended by a small body of English soldiers against an enemy of tenfold number, but was at last taken by storm. The attack was conducted by *Buonaparte*, lieutenant of artillery, then in his 23rd year. The town contains nothing to detain the traveller except the *War Harbour*, with the *Bagno* (prison of the *forçats*, or galley-convicts). The \*view from the height of *La Malgue*, S.E. of Toulon, is one of the most beautiful in Provence.

Beyond Toulon the train quits the coast and winds through the *Montagnes des Maures* to the N.E. 48½ M. *Hyères*.

The small town of **Hyères** (*Hôtel des Îles d'Or*; *des Hespérides*; *de l'Europe*; *d'Orient*; *du Parc*; *des Ambassadeurs*; *du Louvre*; *des Étrangers*) lies 3 M. from the railway (omnibus) and the same distance from the sea, on the slope of the lofty Mts. des Maures, but not sufficiently protected from the *Mistral* (see p. 11). It is much visited as a winter-residence by persons suffering from pulmonary complaints, and is surrounded by a number of villas, but the town itself is uninviting. Most of the heights in the vicinity are barren. The orange and lemon-trees of which Hyères boasts are generally concealed by garden-walls. The low ground is marshy at places and exhales unwholesome vapours in summer and autumn. The *Islands of Hyères* (the *Stoichades* of the ancients) are a group of rocky islands and cliffs near the coast. The largest of them are the *Île du Levant* or *Titan*, *Porteros*, *Porquerolles*, and *Bagueau*. Some of them are fortified and inhabited, but they do not enjoy so mild a climate as Hyères itself, being more exposed to the wind.

85 M. *Les Arcs*, whence a branch-line runs to *Draquignan*.

98 M. **Fréjus** (*Hôtel du Midi*), a small town with 3000 inhab.. the ancient *Forum Julii*, founded by Julius Cæsar, contains a number of Roman remains, an amphitheatre, archway (*Porte Dorée*), and aqueduct, none of which possess much interest.

101 M. *St. Raphael*, delightfully situated in a ravine on the

coast. At the small harbour of this place Napoleon landed in Oct., 1799, on his return from Egypt. Here, too, after his abdication, he embarked for Elba, 28th April, 1814. The line traverses a romantic, rocky district, occasionally affording charming glimpses of the numerous bays of the coast. Then four tunnels.

123 M. **Cannes.** — **Hotels**, upwards of fifty in number, of which a few only need be mentioned. Near the sea: SPLENDIDE HÔTEL; HÔTEL DE GENEVE, and GRAND HÔTEL DE CANNES (the most handsomely fitted up); HÔTEL GRAY & D'ALBION; BEAU RIVAGE; GONNET; DE LA REINE; DE LA PLAGE; DES PRINCES; DE LA MÉDITERRANÉE; DES QUATRE-SAISONS; HÔTEL-PENS. SUISSE (new). On the road to Fréjus (towards the W., frequented by English visitors): BEAU SITE; DU PAVILLON; DE BELLVUE; D'ESTÉREL; DU SQUARE-BROUGHAM. — In the interior of the town: HÔTEL DU NORD; DE LA POSTE, Rue d'Antibes. — In the Cannet quarter: HÔTEL DE FRANCE; DU PHÉNIX; D'ALSACE-LORRAINE; DE PROVENCE; VICTORIA; DU PARADIS; DE L'EUROPE; DU LOUVRE, near the station. — In the E. quarter: HÔTEL BEAU-SEJOUR.

**Pensions.** Towards the E.: ST. CHARLES; DE LÉRINS; DES ANGÉS. On the Route d'Antibes: THUILLIER; ANNE THÉRÈSE; AUGUSTA. — In the Cannet quarter: RICHMOND; ANGLAISE; BEL-AIR; DE LA PAIX; D'ANGLETERRE; MONTFLEURI; BEAU SEJOUR (pens. 10 fr.), and others. — To the W.: PENSION ITALIENNE; DES ORANGERS; DE LA TERRASSE; DE ST. ROCK (chiefly frequented by English visitors).

The charges at the Pensions vary from 8 to 12 fr. per day, at the hotels 12-20 fr. Private apartments are also easily obtained. Engagements are usually made for the whole season, from October to May, the rent being 1200-2000 fr. and upwards. Cannes is considered a very expensive place.

**Cafés.** *Café des Allées*, in the Cours; *de Paris; de la Rotonde*, in the Boulevard de la Plage.

**Carriages.** One-horse carr. 1 fr. 25, two-horse 1 fr. 50 c. per drive; 2 fr. 50 and 3 fr. per hour; one-horse carr. for two persons only, somewhat less.

#### English Church Service.

*Cannes*, a small but rapidly increasing town with 10,000 inhab., picturesquely situated on the *Golfe de la Napoule*, is indebted to its sheltered situation for its repute as a wintering-place for consumptive and delicate persons. It is protected by the *Estérel Mts.* (see above) from the N. and N.W. winds.

The town consists of a main street, parallel with which, along the coast, runs the *Boulevard de la Plage*, terminating on the W. in the *Cours*, a 'place' with promenades and fountains. The most sheltered situation is the space between the N. side of the town and the village of *Le Cannet*. The W. end of the town is chiefly occupied by English families (the English Church is situated here). The best French society is also well represented.

The old town lies at the foot of the *Mont Chevalier*, on which the parish church rises, and from which the pier closing the S.W. side of the harbour extends. Fine view from the top.

Opposite the *Cap de la Croisette*, the promontory which separates the *Golfe de la Napoule* from the *Golfe de Jouan*, rise the *Iles de Lérins*. On *Sainte Marguerite*, the largest of these, is situated *Fort Montereau* (poor inn), in which 'the man with the iron mask' was kept in close confinement from 1686 to 1698; and

recently well known as the prison of Marshal Bazaine (from 26th Dec. to the night of 9th Aug. 1874 when he effected his escape). The island commands a fine survey of Cannes and the coast. On the island of *St. Honorat* rise the ruins of a fortified monastery and church (boat there and back 10-12 fr.).

The ENVIRONS of Cannes are delightful, and studded with numerous villas. On the Fréjus road (to the W.) is the *Château des Tours*, the property of the Duc de Vallombrosa, with a beautiful \*garden, to which visitors are admitted. Another walk may be made towards the E. to the *Cap de la Croisette*, where the *Jardin des Hespérides*, with its fine orange plantations, is situated. A somewhat more fatiguing excursion is to the *Chapel of St. Antoine* on the road to *Vattauris*, which commands an admirable view. A visit may also be paid to *Mougins*, to the monastery of *St. Cassien*, the ruin of *Napoute*; farther distant, to *Grasse* and *Bar*. The vegetation is luxuriant, but lemon-trees are not common here. Orange-trees are principally cultivated for the sake of the blossoms, which form an important article of commerce.

Beyond Cannes the line passes *Golfe Juan*; a column marks the spot where Napoleon bivouacked on the night after his arrival from Elba, 1st March, 1815.

128 M. **Antibes** (*Hôtel de France*), the ancient *Antipolis*, a colony of the Massilians, is now a small, but busy seaport (6000 inhab.), beautifully situated on a promontory, and commanding a charming view of the sea, the Bay of Nice, and the Alpes Maritimes. A pier constructed by Vauban connects it with several islands in the vicinity. — This portion of the line traverses a remarkably rich and attractive district. It soon crosses the *Var* (*Varus*; station), an impetuous mountain-torrent, which in modern, as well as ancient times formed the boundary between France and Italy, until in 1860 Nice was ceded to France, and the frontier removed farther to the E.

140 M. **Nice**, see p. 104. From Nice to *Genoa*, see R. 16.

## 2. From Paris (*Geneva*) to Turin by Mont Cenis.

498 M. RAILWAY in 22-30½ hrs. (fares 105 fr. 45, 78 fr. 70, 56 fr. 25 c.).

From Paris to *Mâcon* (274 M.), see R. 1. The railway here quits the Lyons line and turns to the left, crosses the Saône, and, at stat. *Pont-de-Veyle*, the *Veyle*. In front and to the left a view of the Jura is obtained. The next place of importance is —

297½ M. **Bourg** (*Hôtels de l'Europe, du Midi, de France*), with 14,000 inhab., the ancient capital of Bresse, situated on the left bank of the *Reyssouze*, ¾ M. from the station. The church of *Notre Dame de Bourg*, erected in the 15th-17th cent., in a variety of styles, contains several pictures, sculptures, and fine wood-carving. On the promenade *Le Bastion* is the \**Monument of*

*Bichat* (d. 1802), who once studied at Bourg, by David d'Angers. The house in which *Lalande* (d. at Paris in 1807) was born is indicated by a tablet with inscription. — Bourg is the junction of the line to Lyons, Mouchard, Besançon, and Mülhausen, which is the direct railway between Lyons and Strassburg (comp. pp. 4, 5).

The celebrated **Church of Brou**, in the florid Gothic style, erected in 1511-36 by Margaret of Austria, Regent of the Netherlands, is situated  $1\frac{1}{2}$  M. from the town. It contains the sumptuous *Monuments* of the foundress, the Duke Philibert of Savoy her husband, and Margaret of Bourbon, her mother-in-law. Her well-known motto '*Fortune infortune forte une*', may be seen in different parts of the church.

The line intersects the forest of *Seillon*. Near Stat. *Pont d'Ain* the *Ain* is crossed.

317 M. **Ambérieu**, a pleasant little town on the *Albarine*, situated at the base of the Jura Mts., is the junction for Lyons (p. 5).

The train now continues to ascend the valley of the *Albarine*. To the left lie the ruined castles of *Vieux-Mont-Ferrand* and *St. Germain*. Beyond *St. Rambert de Joux* the valley becomes wilder and more imposing. The line quits the *Albarine* at stat. *Tenay*, and enters a sequestered valley to the right, where *Les Hôpitaux* is situated. Near *Rossilton* are a few fragments of an ancient stronghold. Beyond a tunnel,  $\frac{1}{3}$  M. in length, the lakes of *Pugieu* are observed on the right. Beyond two small stations the train next reaches the valley of the Rhone near —

348 M. **Culoz** (774 ft.; \**Rail. Restaur.*), at the base of the *Colombier* (5000 ft.), the junction of the Geneva line.

FROM GENEVA TO CULOZ (41 $\frac{1}{2}$  M.) railway in 2 $\frac{1}{2}$  hrs. (fares 7 fr. 50, 5 fr. 65, 4 fr. 15 c.). The line follows the right bank of the Rhone, on the slopes of the Jura Mts. Beyond *Collonges*, the fifth station, the Rhone flows through a narrow rocky valley, confined between the Jura and *Mont Vouache*, and commanded by the *Fort de l'Ecluse*, which rises far above on the right. The line quits the defile by the long *Tunnel du Crêdo* (2 $\frac{1}{3}$  M.), crosses the grand *Valserine Viaduct*, and reaches stat. *Bellegarde* (Poste), at the influx of the Valserine into the Rhone (French custom-house examination). The latter here forms a species of rapid, known as the *Perte du Rhône*, where the water is occasionally lost to view. Stations *Pyrimont*, *Seysel*, and *Culoz*.

The train crosses the Rhone, and at stat. *Châtillon* reaches the *Lac du Bourget* (12 M. in length, 1 $\frac{1}{2}$  M. in breadth), the E. bank of which it follows. Several tunnels and fine views.

363 M. **Aix-les-Bains** (850 ft.; \**Grand Hôtel d'Aix*, the nearest to the station; *Hôtel de l'Univers et des Ambassadeurs*; \**Venat*, with a large garden; *Globe*; *Europe*, D. 4 fr.; *Guilland*; the three last less expensive), the *Aquæ Allobrogum* or *Aquæ Gratianæ* of the Romans, is a celebrated watering-place with 4400 inhab. (5-6000 visitors to the baths annually), possessing sulphur-springs (113° Fahr.), adapted for internal and external use. The large new *Etablissement Thermal*, with baths and pump-room, deserves inspection. In the *place* in front of it rises a Roman triumphal arch of the 3rd or 4th cent.; the other scanty relics of the Roman period (fragments of a temple and of baths) are almost all

within the precincts of private property and not easily accessible. — Pleasant excursion by steamboat to *\*Haute Combe*, a Cistercian Abbey on the N.W. bank of the *Lac du Bourget*. The church contains a number of handsome monuments erected to Princes of Savoy.

The line quits the lake and traverses the broad valley of the *Laisse*; to the left the beautifully wooded slopes of the *Mont d'Azil* and the *Dent de Nivolet* (5025 ft.).

370 M. **Chambéry** (883 ft.; *\*Hôtel de France*; *Hôtel de la Pair*, near the station; *Hôtel de l'Europe*; *Poste*, less expensive; *Hôtel des Princes*) is the capital of the Department of Savoy, with 18,000 inhab., and an archiepiscopal see. A square tower and remnants of the façade of the old palace of the Dukes of Savoy, erected in 1230, still exist. On the Promenade is the *Monument of General de Boigne* (d. 1830), adorned with life-size figures of elephants.

The line traverses a picturesque district, passing the ruined castles of *Bâtie* and *Chignin*. — 377 M. *Les Marches* is the junction for the branch-line to Grenoble, which enters the valley of the *Isère* (or *Valley of Graisivaudan*) to the right. From Grenoble to Marseilles by railway in 12 hrs.

380 M. *Montmélian*. The ancient castle, of which scanty fragments now alone exist, was long the bulwark of Savoy against France. The train crosses the *Isère*. — 385 M. *St. Pierre d'Albigny*; the town lies opposite on the right bank, commanded by the ruins of the *Château of Miolans*. Near (388 M.) *Chamousset* the line turns to the right, and traverses the valley of the *Arc* (*Vallée de Maurienne*), which here joins the *Isère*. Beyond (393 M.) *Aiguebelle*, which is grandly situated, the *Arc* is crossed (in the vicinity, on the left bank, the extensive iron mines of *St. George des Hurtières*). Between stations *Epiierre* and *La Chambre* the train passes through a tunnel.

413 M. *St. Jean de Maurienne*. — 421 M. *St. Michel* (2330 ft.). The train crosses the *Arc* several times. Numerous tunnels (nine between *St. Michel* and *Modane*). — 427 M. *La Prax* (3137 ft.).

431 M. **Modane** (3468 ft.; *Hôtel International*; *Rail. Restaurant*, dear, D. 4½ fr.) is the seat of the French and Italian custom-house authorities (change carriages).

The train (best view on the right) describes a wide curve round the village, and passing through two short tunnels, enters, beyond the small village of *Fourneaux*, the great **\*Mont Cenis Tunnel**, by which the *Col de Fréjus* (8338 ft.) is penetrated in a S.E. direction.

The tunnel (8 M. in length; N. entrance 3802 ft., S. entrance 4163 ft. above the sea-level; height in the centre 4245 ft., depth below the surface of the mountain 4093 ft.) was begun in Jan. 1861 and completed in Dec. 1870, and its total cost amounted to 75 million francs. The ingenious boring-machines, constructed for the purpose, were worked by means of compressed air, by the engineers *Sommeiller*, *Grandis*, and *Grattoni*. From 1500 to 2000 workmen were constantly employed on each side.

The tunnel is 26 ft. wide, 19 ft. high, and almost entirely lined with masonry. It is lighted by lanterns placed at intervals of 500 metres, and the distances are given in kilomètres. The carriages are lighted with gas. The air in the tunnel, although somewhat close, is not unpleasant, even when the windows are left open. The transit occupies 30 minutes.

The now deserted MONT CENIS ROAD, which continues to ascend the valley of the Arc, was constructed by Fabbroni in 1802-5, during the reign of Napoleon I. The culminating point of the Mont Cenis (6950 ft.) lies 17 M. to the E. of the tunnel which was therefore hardly appropriately called after the mountain. The road then descends to Susa (see below), about 40 M. from Modane.

At the S. end of the tunnel is (443 M.) stat. *Bardonecchia* (4127 ft.). Two tunnels. Stat. *Beaulard*. Near stat. *Oulx* (3497 ft.), the Roman *Villa Martis*, the line enters the valley of the *Dora Riparia*. (A road to the S.W. leads hence to *Cesanne* at the confluence of the Dora and Ripa, and over the *Mont Genève* to the French fortress of *Briançon* on the Durance; comp. p. 72.)

The train traverses the picturesque valley of the Dora. Beyond a bridge and two tunnels, we reach stat. *Salbertrand* (3302 ft.). The river again is crossed. Before the next station (*Chiomonte*), nine tunnels are traversed. To the left, between the second and third, a glimpse is obtained of the small town of *Exilles* with the frontier fortress of that name; farther on, a fine waterfall. — 453 M. *Chiomonte*, or *Chaumont* (2526 ft.). Then a number of tunnels and aqueducts. The valley contracts and forms a wild gorge (*Le Gorgie*), of which beautiful views are obtained, with the Mont Cenis road winding up the hill on the farther side, and the *Rochemelon*, *Roche-Michel*, etc. towering above it. When the valley expands, Susa with the arch of Augustus comes in sight on the left (see below). — 456½ M. *Meana* (1949 ft.), 1 M. from Susa, lies 324 ft. higher than the latter. Three tunnels. The train then descends through beautiful chestnut woods, and crosses the Dora. 462 M. *Bussoleno*.

A short branch-line runs hence to *Susa* (1625 ft.; *Hôtel de France: Soleil: Rail. Restaurant*), a small and ancient town, the Roman *Segusio*, situated on the right bank of the Dora. A garden on the W. side of the town contains a Triumphant Arch, 44 ft. in height, 39 ft. in width, and 23 ft. in depth, with projecting Corinthian columns at the corners and sacrificial scenes on the frieze, erected according to the inscription in A.D. 8. There are also a few other Roman relics. The church of *S. Giusto* dates from the 11th century. On the opposite bank of the Dora rises the fort *La Brumette*, which was destroyed by the French in 1798.

Next stations *Borgone* (where the Dora is crossed), *S. Antonino*, *Candore*, and *S. Ambrogio*, high above which, on a rocky eminence to the right, rises the abbey of *S. Michele della Chiusa*, or *La Sagra*, remarkable for a peculiar property of its tombs which convert dead bodies into natural mummies. At stat. *Arigiana* the valley expands into a broad plain. Stations *Rosta*, *Atignano*, *Collegno*.

498 M. *Turin*, see p. 60.

### 3. From Martigny to Arona on the Lago Maggiore (and Milan) over the Simplon.

125 M. RAILWAY from Martigny to Sierre, 25½ M., in 1 hr. 40 min. (fares 4 fr. 90, 3 fr. 35, 2 fr. 50 c.). Thence over the Simplon to Arona, 99½ M., DILIGENCE once daily in 20 hrs. (fare 29 fr. 10, coupé 31 fr. 10 c.). See remarks as to diligence seats and 'Extrapost', p. 27. — Through-tickets from Lausanne to Milan 51 fr. 55, 44 fr. 50, 40 fr. 30 c. (Railway from Lausanne to Martigny in 3 hrs.) — TWO-HORSE CARRIAGE from Brieg to the Lago Maggiore (Baveno, Stresa, Pallanza) about 150 fr. and gratuity (but more in the height of the season). The night is usually spent at Bérisal and at Domo d'Ossola.

**Martigny** (1558 ft. ; \**Hôtel Clerc* ; *Hôtel de la Tour* ; *Grande-Maison-Poste* ; *Hôtel du Mont Blanc*, moderate), is a busy little town in summer, being the starting-point of the Great St. Bernard and Chamorny routes.

The RAILWAY runs in a straight direction past the *Baths of Saxon to Riddes*, where the Rhone is crossed.

15½ M. **Sion** (1709 ft. ; \**Poste* ; *Lion d'Or*), with 4895 inhab., the capital of the *Canton du Valais*, has an important appearance in the distance with the picturesque castles towering above it. Two of these, the *Tourbillon* (\*view) and *Majoria*, were burned down in 1788 ; *Valerin*, the third, erected on the site of an ancient Roman fort, is well preserved.

25½ M. **Sierre** (1765 ft. ; \**Hôtel et Pension Baur* ; *Bellevue* ; *Poste* ; *Mont Bonvin*), picturesquely situated on a hill, is at present the terminus of the railway. Good wine is produced in the environs.

DILIGENCE hence over the Simplon. German begins to be spoken at the small village of *Pfyn*, the boundary between the French and German languages. The picturesque old village of *Leuk*, or *Loèche*, with its castle and towers, rises high above the right bank of the Rhone ; opposite, on the left bank, lies the small hamlet of *Susten* (\**Hôtel*), through which the road passes.

9 M. *Turtman*. To the left, high up in the *Lötschenthal* which opens here, rise the icy slopes of the *Tschingel Glacier* ; to the right in the background, above the Simplon group, is the extensive *Kaltwasser Glacier*. To the left, above *Raron*, rises the snow-clad *Bietschhorn* (12,966 ft.).

17½ M. *Vispach* or *Visp*, French *Viège* (2155 ft. ; \**Sonne* ; *Post*), is a small village with beautiful environs. \**View* from the sluiceway and the cemetery ; in the background rises the *Batfrin* (12,546 ft.).

23½ M. **Brieg**, French *Brigue* (2244 ft. ; \**Trois Couronnes* ; \**Angteterre*), is a small town at the base of the Simplon.

The SIMPLON ROUTE, properly so called, which begins here, was constructed by order of Napoleon in 1800-1806, and, after the Brenner (p. 44), was the first carriage-road across the Alps from Switzerland to Italy. The road quits the valley of the Rhone, as-



ends in numerous windings, and avoids the *Ganterthal* by means of a long circuit to the E.

32 M. *Bérisal* (5006 ft.), the 3rd Refuge, is also a post-station and \*Inn (R. 2 fr., B. 1½ fr.). Above the 4th Refuge a retrospect is obtained in clear weather of the Bernese Alps (to the N.), from which the huge *Aletsch Glacier* descends. The part of the road between the 5th Refuge and the culminating point is the most dangerous during the period of avalanches and storms. Within a distance of less than 3 M. there are no fewer than six houses of refuge and a hospice. The road passes through the *Kaltwasser Glacier Gallery*, over which the stream issuing from the glacier is precipitated into the depths below, forming a waterfall which is visible through a side opening. From the 6th Refuge a splendid final view is enjoyed of the Bernese Alps; far below in the Rhonc Valley lies Brig.

The **Simplon Pass** (6595 ft.) is 6½ M. from Bérisal. About ¾ M. beyond the summit is the *Hospice* (no payment demanded for hospitality, but travellers should contribute at least as much to the poor-box as they would have paid at an hotel), a spacious building founded by Napoleon, but not completed till 1825. A broad, open valley, carpeted at places with Alpine roses, here forms the highest portion of the Simplon Pass, bounded by snow-capped heights and glaciers. The imposing *Raut Glacier* is a conspicuous object on the mountains to the S. The *Old Hospice*, a lofty square tower now tenanted by herdsmen, lies far below the new road.

43½ M. **Simplon** (4856 ft.), Ger. *Simpeln*, Ital. *Sempione* (\**Poste*; \**Hôtel Fletschlhorn*). The road now describes a long curve to the S., which pedestrians may cut off by a rough path regaining the road at the *Algaby Gallery*, where the most interesting part of the Simplon route begins. It leads through the \**Ravine of Gondo*, one of the wildest and grandest in the Alps, becoming narrower and more profound at every step, until its smooth and precipitous walls of mica-slate completely overhang the road, below which rushes the impetuous *Diveria*. The most remarkable of the cuttings by which the road penetrates the rocks is the *Gallery of Gondo*, a tunnel 245 yds. in length, constructed by Napoleon in 1805 and fortified by the Swiss in 1830. At the end of the tunnel the *Fressinone* (or *Alpienbach*) forms a fine waterfall, which is crossed by a slender bridge. On both sides the rocks tower to a dizzy height of 2000 ft. The dark entrance of the tunnel forms a striking contrast to the white foam of the falling torrent. This magnificent Alpine \*scene, especially when viewed at a distance of 40-50 paces, surpasses the *Via Mala*. *Gondo* (2818 ft.) is the last Swiss village; ½ M. beyond it is the Italian boundary-column. *S. Marco* is the first Italian village.

52½ M. **Iselle** (2175 ft.; \**Posta*) is the seat of the Italian custom-house. The valley, although now less wild, continues to be

extremely picturesque. It unites with the broad and fertile valley of the *Tosa* (or *Toce*) at the bridge of *Crevola*, 100 ft. in height, below which it is called the *Val d'Ossola*. The characteristics of the scenery are thoroughly Italian.

64 M. **Domo d'Ossola** (1000 ft.; *Grand Hôtel de la Ville*, or *Ancienne Poste*; *Hôtel d'Espagne*. One horse carr. to Baveno '25. to Brieg 60 fr.; diligence daily to Pallanza on Lago Maggiore, 6 fr.), a small town with 2480 inhab., beautifully situated. Near (4 M.) *Villa*, the *Antrona Valley* opens on the right; then (3 M.) *Pallasceno*, and (3 M.) *Masone*, where the *Anzasca Valley* opens on the right. The *Tosa* is crossed.

71½ M. *Vogogna* (\**Corona*, unpretending), a small town, at the base of precipitous rocks. The next villages are (1½ M.) *Premosello*, *Cuzzago*, and (4½ M.) *Migiandone*, where the *Tosa* is crossed by a five-arched stone bridge.

78 M. *Ornavasso* (Italia; *Croce Bianca*). The marble-quarries in the vicinity yielded the material of which the cathedral of Milan is built. To the S. a road leads through the valley of the *Strona*, which falls into the *Tosa* near *Gravellona* (Europa), to the *Lake of Orta* (p. 159). — Near *Fariòlo* (Leone d'Oro), the next village, situated in a most luxuriant district, covered with olive-groves, maize-fields, vineyards, chestnuts, and fig-trees, the road passes an extensive granite quarry, where the columns (26 ft. in height) of the restored Basilica S. Paolo Fuori le Mura near Rome were hewn, and soon reaches the S.W. bank of *Lago Maggiore* (R. 24), from which in the distance rises the *Isola Madre*, the most N. of the Borromean Islands.

85½ M. **Baveno** (\**Bellevue*; \**Beau-Rivage*; *Simplon*) is a steamboat station. Travellers from the *Simplon* usually visit the Borromean Islands from this point (comp. p. 151). The road, most of which rests on buttresses of granite and solid masonry, skirts the lake and leads by *Stresa* (p. 155), *Belgirate*, *Lesa*, and *Meina*, to—

99½ M. **Arona**, see p. 156. Railway to *Milan*, see p. 157; to *Genoa*, see p. 157; to *Turin* by *Novara*, see p. 157 and R. 12.

#### 4. From Lucerne to Locarno and Lugano (*Milan*) over the St. Gotthard.

126 M. STEAMBOAT from Lucerne to Flüelen (and back) 6-7 times daily in 2¼-2¾ hrs. (fares 4 fr., 2 fr. 30 c.). — From Flüelen to Biasca (station) DILIGENCE three times daily in summer, and once in winter, in 1¾ hrs. (22 fr. 15 c., coupé 25 fr. 45 c.). — RAILWAY (*St. Gotthard Line*) from Biasca to Locarno via Bellinzona in 1¾ hr.; fares 4 fr. 10., 2 fr. 90 c. (steamboat from Locarno to Arona, and railway thence to Milan). — The direct route to Milan is via Lugano, to which the SWISS DILIGENCE will continue to run from Bellinzona until the completion of the Monte Cenero tunnel (4¼ hrs.; fare 4 fr. 90 c., coupé 6 fr.). RAILWAY from Lugano to Como and Milan, see pp. 146-151. Tickets for this route may be procured at the post-office of Lucerne (where coupé-places are most easily secured), or on board the steamboat. Through-tickets are also

issued at the branch-post office of Lucerne (Schweizerhof Quay): to Bellinzona 27 fr. 55 (coupé 31 fr. 10 c.); Locarno 28 fr. 80 (coupé 32 fr. 95 c.); Lugano 32 fr. 35 (coupé 37 fr. 10 c.), and to Florence, Rome, and Naples. Travellers are cautioned against forwarding their luggage across the frontier, but it may be safely transmitted by post or by goods' train within the limits either of Switzerland or Italy. — EXTRA-POST from Flüelen to Biasca, with two horses 125 fr. 10 c., with three horses 212 fr. 50 c., with four horses 272 fr. 90 c.

THE CARRIAGE TARIFF of the Canton Uri, which the drivers are apt to disregard, fixes the following charges: carriage and pair to Airolo 100 fr., to Faido 120 fr., to Biasca 150 fr., to Bellinzona 180 fr., to Lugano 220 fr., and a fee. Application for a carriage had better be made to the innkeeper, but extortionate demands are sometimes made, especially on the Italian side, a spurious tariff even having been sometimes exhibited as an authority. In every contract the number of horses, duration of the journey, stations for the night, amount of driver's fee, etc., should be distinctly specified. The drivers are prohibited to change horses, private posting being illegal. The night is usually spent at Andermatt or Hospenthal.

**St. Gotthard Railway.** The St. Gotthard line, commenced in 1872, will consist of the *Lucerne, Flüelen, Airolo, Bellinzona, and Locarno*, the *Bellinzona, Lugano, and Chiasso (Como)*, and the *Bellinzona, Magadino, and Pino* lines. The great *St. Gotthard Tunnel* will be  $9\frac{1}{4}$  M. in length (i. e. about  $1\frac{1}{4}$  M. longer than the Mont Cenis Tunnel), extending from *Göschenen* (p. 30) on the N. side to *Airolo* (p. 31) on the S. side. From the central point of the tunnel (3779 ft. above the sea-level, i. e. 466 ft. lower than the highest point of the Mont Cenis tunnel) there will be a fall towards Göschenen of 6' per 1000', and towards Airolo of 1' per 1000'. This stupendous work is to be completed in 1880, at a cost of about 50 million fr.

**Lucerne.** — \*SCHWEIZERHOF; \*LUZERNER HOF; \*HÔTEL NATIONAL; ANGLETERRE; \*CYGNE; \*HÔTEL DU RIGI, all near the steamboat-pier. HÔTEL DU LAC, and \*ST. GOTTHARD, both near the station. \*BALANCES; ADLER, RÖSSLI, \*POSTE, HÔTEL DES ALPES, \*MOHR, HIRSCH, all unpretending.

*Lucerne*, the capital of the canton of that name, with 14,500 inhab., is situated at the efflux of the *Reuss* from the Lake of Lucerne. Its well-preserved walls and watch-towers, as well as its palatial modern hotels, impart a handsome appearance to the town. The view from the quay is strikingly beautiful. The celebrated \**Lion of Lucerne*, designed by Thorvaldsen, and the adjacent *Gletscher-Garten*, containing interesting remains of a glacier of the ice period, are the principal attractions in the town. Walks and excursions, see *Baedeker's Switzerland*.

The \***Lake of Lucerne** (1433 ft.), or *Lake of the Four Forest-Cantons* (viz. Uri, Schwyz, Unterwalden, Lucerne), is unsurpassed in Switzerland, and perhaps in Europe, in the beauty and magnificence of its scenery. It is nearly cruciform in shape; length from Lucerne to Flüelen  $26\frac{1}{2}$  M., greatest width about 3 M.

The STEAMBOATS start from the railway station and touch at the piers on the opposite bank, near the hotels, before their final departure. Strikingly picturesque retrospect of the town, as the quay is quitted. As the vessel proceeds, the Rigi on the left, Pilatus on the right, and the Bürgenstock and Stanser Horn opposite the traveller are the most conspicuous mountains. To the left of Pilatus, the Majestic Bernese Alps (Schreckhörner, Mönch, Biger, Jungfrau) gradually become visible.

A view is soon obtained of the *Lake of Küssnacht* to the left, and of the *Alpmacher Sec* to the right. The steamer soon reaches (on the left) *Wäggis*, in a very fertile district, at the foot of the *Rigi* (5906 ft.). The next village is *Vitznau*, the terminus of the Rigi-railway (see *Baedeker's Switzerland*).

Two promontories, aptly termed the *Nasen* (noses), the one a spur of the *Rigi*, the other of the *Bürgenstock*, here extend far into the lake and appear to terminate it. The bay towards the W. beyond this strait takes the name of the *Lake of Buochs*, from the village of *Buochs* on the right, above which rise the *Buochser Horn* (5934 ft.) and *Stanser Horn* (6231 ft.).

To the right *Beckenried* (Mond; Sonne), delightfully situated. Then, on the opposite bank, *Gersau* (\*Hotel Müller).

To the E. rise the bald summits of the two *Mythen* (6244 ft. and 5954 ft.), at the base of which, 3 M. inland, lies the small town of *Schwyz*. To the right, *Treib*. Opposite, on the E. bank of the lake, at the mouth of the *Muotta*, is situated *Brunnen* (\*Waldstätter Hof; \*Adler); on the hill \**Kurhaus Axenstein* and *Hôt. Axenfels*.

Near *Brunnen* begins the S. arm of the lake, called the *Lake of Uri*, the grandest part of the lake, with mountains rising almost perpendicularly on both sides. At the sharp angle which here abuts on the lake, rises the *Mythenstein*, a pyramid of rock, 80 ft. in height, bearing an inscription in honour of Schiller. A little farther on, at the base of the *Seelisberg*, lies the *Rütti*, a meadow, memorable as the spot where on the night of 7th Nov., 1307, the first Swiss league (between Uri, Schwyz, and Unterwalden) was solemnly concluded. A little beyond it, on the opposite bank, rises the *Axenbergl* (3353 ft.), at the base of which nestles the *Chapel of Tett* amid rock and wood. It stands on the *Tetts-Platte*, a ledge of rock on the margin of the lake, where Tell is said to have sprung out of Gessler's boat when overtaken by a storm. Above it runs the \**Axenstrass*, a highly picturesque road, leading from *Brunnen* to *Flüelen*, hewn in many places through the solid rock. Immediately above the chapel, 2½ M. from *Flüelen*, is \**Tell's Platte Hotel* (steamboat-station).

26½ M. (from Lucerne) **Flüelen**, Ital. *Fiora* (\**Urnerhof*; *Flüelerhof*; *Adter*; \**Kreuz*) is beautifully situated at the S. end of the Lake of Lucerne, at the mouth of the *Reuss*.

The St. Gotthard road (omnibus to *Altorf* 50 c.) leads hence to (28½ M.) *Altorf* (1466 ft.; \**Adter*; \**Schlüsset*; *Löwe*), 2 M. from *Flüelen*, the capital (2700 inhab.) of the canton of Uri, where Tell is said to have aimed his arrow at the apple on his son's head.

The road crosses the impetuous *Schächenbach*, and at the *Klus*, opposite *Erstfeld*, approaches the *Reuss*. To the left rise the *Kleine Windgelle* or *Sevelistock* (9846 ft.) and the *Grosse Windgelle* or *Kalkstock* (10,463 ft.). Towards *Silinen*, which lies to the right of the road, a fine view of the *Bristenstock* (10,089 ft.) is obtained.

37½ M. **Amsteg** (1759 ft.; \**Stern or Post*; *Kreuz*; *Hirsch*) lies picturesquely at the foot of the Bristenstock and at the mouth of the *Maleramer Thal*.

The *St. GOTTHARD ROUTE*, properly so called, begins at the new bridge over the Reuss a little beyond Amsteg. It was constructed in 1820-32 by the cantons of Uri and Ticino. The scenery surpasses that of the other great Alpine routes. The road at first gradually ascends on the left bank of the Reuss, which flows in its deep channel far below. Beyond *Insch* (2168 ft.), a village 1½ M. from Amsteg, a fall of the *Inschalpbach* is passed. The road next crosses the rapid *Meienbach*.

45 M. **Wasen** (2779 ft.; \**Hôtel des Alpes*; *Ochs*; *Krone*) is picturesquely situated on a height. To the right of the Reuss bridge is a beautiful fall of the *Rohrbach*, near *Wattigen*. We now cross the fifth bridge, the 'Schönbrücke' (3212 ft.). To the W. of (2½ M.) *Geschenen* (3488 ft.; \**Hôtel Geschenen*; *Rössli*), 2¼ M. from Wasen, opens the valley of the *Geschenen-Reuss*, terminated by the grand *Dammafirn*.

About 1 M. beyond Geschenen, below the *Vordere*, or *Häderti Brücke*, is the N. entrance to the great *St. Gotthard Tunnel* (p. 28), to which visitors are not admitted. Here begins the dark and rocky defile of the \**Schöllenen*. On both sides rise vast and almost perpendicular walls of granite, at the base of which dashes the impetuous Reuss. The road winds upwards and crosses numerous bridges. Pedestrians may cut off most of the curves by the old bridle-path. This part of the road is much exposed to avalanches, and is carried past the most dangerous spot by a gallery or tunnel, 80 yds. in length.

The \***Devil's Bridge** (4593 ft.), in the midst of a scene of wild desolation, is now reached (3½ M. from Geschenen). The Reuss here forms a beautiful fall, about 100 ft. in height, the spray of which bedews the bridge above. The old moss-grown bridge below is disused. In 1799 this spot was the scene of fierce struggles between the French and Austrians, and a month later between French and Russians.

Immediately beyond the bridge the road passes through the *Urner Loch*, a tunnel 70 yds. long, cut through the solid rock in 1707, but not accessible to carriages until it was enlarged when the new road was constructed. The *Valley of Urseren*, which the road enters beyond the tunnel, forms a striking contrast to the bleak region just traversed. This peaceful dale, watered by the Reuss, and surrounded by lofty and partially snow-clad mountains, was probably a lake before the Reuss had forced a passage through the *Schöllenen*.

52½ M. **Andermatt**, or **Urseren**, Ital. *Orsera* (4738 ft.; \**Bellevue*; \**St. Gotthard*; *Drei Könige*; *Oberalp*), 1 M. from the Devil's Bridge, is the principal village in the valley. The Oberalp route to the valley of the Vorder-Rhein and Coire diverges here to the left.

54 $\frac{1}{2}$  M. *Hospenthal* (4800 ft.; \*Meyerhof; \*Löwe), derives its name from a former hospice. The Furca road to Realp and the Rhone Glacier diverges here to the right.

The St. Gotthard road now ascends in numerous windings through a desolate valley, on the left bank of that branch of the Reuss which descends from the *Lake of Lucendro* (6831 ft.; not visible from the road), and crosses the river for the last time by the *Rodont Bridge*, 1 $\frac{1}{4}$  M. from the summit of the **Pass of St. Gotthard** (6936 ft.). It then leads between several small lakes and traverses a dreary valley, enclosed by the barren peaks of the St. Gotthard group.

62 $\frac{1}{2}$  M. *Albergo del S. Gottardo* (6867 ft.),  $\frac{1}{4}$  M. beyond the pass, a large, gloomy Italian inn; opposite is the \**Hôtel du Mont Prosa* (post and telegraph station), adjoining which is the *Hospice* for poor travellers. Pedestrians may descend to Airolo in 1 $\frac{1}{2}$  hr. Snow often lies on the pass throughout the summer.

About  $\frac{1}{2}$  M. below the hospice the road crosses the *Ticino*, which rises in the *Lago di Sella* to the E. (not visible from the road). A little farther, near a large mass of rock lying by the road, an inscription near the old bridle-path commemorates the events of 1799; the words '*Suwarow Victor*' only are now legible. Near the 1st Refuge, *Cantoniera S. Antonio*, the road enters the *Val Tremola*, a dreary valley 1 $\frac{1}{2}$  M. long, into which avalanches are frequently precipitated in winter and spring. Beyond the third *Cantoniera di Val Tremola*, an extensive \*view of the green valley of the *Ticino* (*Valle Leventina*) down to Quinto is obtained. To the right opens the *Val Bedretto*, from which the W. arm of the *Ticino* descends.

70 M. **Airolo** (3868 ft.; \**Posta*; *Hôtel Airolo*, new), the first village where Italian is spoken. On the left opens the *Val Canuria*. The road enters the *Stretto di Stalvedro*, a defile which in 1799 was defended by 600 French against 3000 Russians, and passes by means of rockhewn galleries through four parallel ridges which descend to the *Ticino*. On the right bank, 1 M. below the ravine, is the beautiful waterfall of the *Calcaccia*.

We next pass *Piotta*, *Ambri*, *Fiesso*; 6 M. farther, beyond the poor inn of *Dazio Grande* (3110 ft.), the mouth of a second \*ravine is reached. The *Ticino* has here forced a passage through the *Monte Piottino*, and precipitates itself in a succession of \*cataracts through the gloomy ravine into which the road descends close to the falls. To the right, near *Faido*, where the culture of the vine begins, is a beautiful fall of the *Piumogna*.

81 M. **Faido** (2365 ft.; \**Angelo*; \**Prince of Wales*; *Hôtel Vella*), a village of thoroughly Italian character, is the capital of the *Leventina*. Beautiful scenery, with numerous campanili in the Italian style peeping most picturesquely from the surrounding heights. Cascades on both sides of the road; that of the \**Cribiasca*

resembles a veil in form. Huge masses of rock lie scattered about, interspersed with fine chestnut-trees. Vines and mulberry trees now begin to appear. Where the road descends in windings to the bottom of the valley, the Ticino forms another beautiful fall, spanned by a bridge over which the road passes. Beyond *Giornico* (1325 ft.; Cervo; Corona) is another picturesque waterfall on the right, called *La Cramosina*.

91 M. *Bodio* (1086 ft.; Posta; Aquila). Beyond *Polleggio* the *Brenno* descends from the *Val Blegno* to the Ticino. The valley of the Ticino now expands and takes the name of *Riviera*, or river-valley. Luxuriant vines, chestnuts, walnuts, mulberries, and fig-trees now remind the traveller of his proximity to 'the garden of the earth, fair Italy'. The vines extend their dense foliage over wooden trellis-work supported by stone pillars, 10-12 ft. in height. Frequent inundations render the district unhealthy.

94 M. *Biasca* (942 ft.; \**Grand Hôtel Biasca; Unione*) is at present the terminus of the St. Gotthard line. The station lies 1 M. to the S. of the village. A series of oratories leads hence to the *Petronella Chapel*, which commands a fine view.

The RAILWAY FROM BIASCA TO BELLINZONA AND LOCARNO traverses the very hot and dusty valley of the Ticino close to the base of the richly cultivated E. slopes of the mountains. —  $4\frac{1}{2}$  M. *Osoyna* (965 ft.), at the foot of an abrupt and rocky height. Near *Cresciano*, on the left, are several picturesque waterfalls. —  $7\frac{1}{2}$  M. *Claro* (1017 ft.), at the foot of the mountain of that name (8760 ft.), with the monastery of *S. Maria*, halfway up the hill. — 10 M. *Castione*; on the left, farther on, opens the *Val Mesocco* (Bernardino route, pp. 37, 38), whence the *Moësa* descends which is crossed by the railway.

$12\frac{1}{2}$  M. (106 $\frac{1}{2}$  from Lucerne) *Bellinzona* (777 ft.; \**Posta*, outside the N. gate; *Hôtel de la Ville*, outside the S. gate; *Angelo*), one of the three capitals of the canton of Ticino, with 2600 inhab., presents a strikingly picturesque appearance when viewed from a distance, but the charm is dispelled when the town is entered.

The three picturesque CASTLES were once the residence of the bailiffs of the three ancient confederate cantons. The largest, the *Castello Grande*, on an isolated hill to the W., belonged to Uri; of the other two, towards the E., the lower, *Il Castello di Mezzo*, belonged to Schwyz, and the *Castello Corbario* or *Corbé* (1502 ft.), the upper, now a ruin, to Unterwalden. The *Castello Grande* is now used as an arsenal and prison; visitors are admitted to the court and gardens to see the beautiful view (fee to the guide). Another admirable point is the loftily situated pilgrimage-chapel of *S. Maria dello Salute*.

The lower valley of the Ticino forms a wide plain, enclosed by lofty mountains. Near ( $14\frac{1}{2}$  M.) *Giubiasco* the still unfinished line through the *Monte Cenere* (see below) to Lugano diverges to the left. —  $17\frac{1}{2}$  M. *Cadenazzo*. The high-road to Lugano ascends to the left (see below); the road in a straight direction leads to Magadino (p. 152). — The train crosses the Ticino beyond *Cugnasco*.

21½ M. *Gordola*. It next crosses the *Verzasca*, which dashes forth from a gorge on the right, and, farther on, skirts the Lago Maggiore. — 25½ M. (119½ M. from Lucerne) **Locarno**, see p. 152.

The HIGH ROAD FROM BELLINZONA TO LUGANO descends to *Cadenazzo* (see above) in the same direction as the railway, and then winds upwards for 4½ M. through beautiful chestnut woods on the slopes of *Monte Cenere* (see below), commanding a succession of \*views of Bellinzona and the Ticino Valley, the influx of the latter into the Lago Maggiore, the N. end of that lake, and Locarno. On the summit of the pass (1814 ft.) stands a guard house (*Corpo di Guardia*), and near it the *Osteria Nuova* (inn). The road then descends through a fertile valley.

117 M. *Birònico* (1420 ft.). We then cross the *Vedeggio*, which rises a few miles to the E., at the base of the *Monte Camoghè* (7303 ft.), but is usually dry in summer. M. Camoghè, which may be ascended in 6-7 hrs. from Bellinzona or Bironico, commands a magnificent \*view of the broad plain of Lombardy, the lakes, and the Alps. The summit of *Monte Cenere* (3777 ft.), which may be reached by an easy ascent from the *Osteria Nuova* in 2 hrs., also commands an admirable view. — Beyond Bironico the scenery is picturesque and the country fertile; the double-peaked Mte. Camoghè is kept constantly on the left. 3¾ M. *Taverne Superiori*; ¼ M. \**Taverne Inferiori*; 2½ M. *Cadempino*; 1 M. *Vezia* (view from the church of *Madonna di S. Martino*).

Towards (1½ M.) Lugano, during the descent, the beauty and fertility of the country increase. The hill and shrine of *Monte S. Salvatore* first become visible; then the lake, in the clear green water of which the beautiful outlines of the mountains are reflected. The road passes several handsome villas and soon reaches the town with its flat-roofed houses. In the foreground are the extensive barracks.

126 M. **Lugano** (932 ft.), and thence to *Milan*, see p. 147.

## 5. From Coire to Colico (and Milan) over the Splügen.

75½ M. DILIGENCE from Coire to Colico twice daily in summer in 16¼ hrs. (coupé 27 fr. 90 c., interior 24 fr. 5 c.). Remarks as to diligences-seats, see p. 27. EXTRA POST from Coire to Colico with two horses 160 fr. 10 c., with three horses 235 fr. 75 c. Through-tickets from Coire to Milan, Genoa, Florence, etc.

**Coire**, Ger. *Chur* (1936 ft.; \**Steinbock*; *Freieck*; \**Lukmanier*, near the station; \**Stern*; *Rother Löwe*, near the post-office), situated on the *Plessur*, 1½ M. from its confluence with the Rhine, is the capital of the Canton of the Grisons, or Graubünden, with 7500 inhab., and an episcopal residence. Within the '*Episcopal*



*Court*, which is surrounded by walls and rises above the town, are the *Cathedral of St. Lucius*, the oldest part of which is said to date from the 8th cent. (choir 1208, nave consecrated in 1282), and the mediæval *Episcopal Palace*.

The Diligence Road from Coire (leading to the Splügen, the Bernardino, and the Vorder Rheinthal) ascends the broad valley of the Rhine, and is nearly level as far as Reichenau. On the opposite bank of the river, at the base of the *Calanda*, lies the village of *Felsberg*, which was partly destroyed by a landslide in 1850. The road passes through the thriving village of *Ems*, near the ruins of the old castle of *Hohenems*, and crosses a covered bridge with a single arch, 84 yds. long, and 85 ft. above the Rhine, before reaching —

6 M. **Reichenau** (1936 ft.; \**Adler*), a group of houses at the confluence of the *Vorder* and *Hinter-Rhein*. The château of M. de Planta afforded refuge to Louis Philippe in 1794, then Duke of Chartres.

A second covered wooden bridge crosses the *Vorder-Rhein*, immediately before its confluence with the *Hinter-Rhein*. Through the valley of the *Vorder-Rhein* a post-road, not crossing this bridge, but branching off to the right, on the left bank of the *Vorder-Rhein*, leads to *Dissentis* and *Andermatt* (p. 30). The road soon ascends for a short distance, and passes the villages of *Bonaduz* and *Rhâzüns*. The *Domleschg Valley*, Romansch *Domgiasca*, which we follow as far as Thusis, on the right (E.) bank of the Rhine (the W. side of which is called *Heinzenberg*, or *Montagna*), is remarkable for its fertility and its numerous castles. Some of the villages are quite Romansch, others German; some are Roman Catholic, others Protestant.

Between the *Bridge of Rothenbrunnen* and *Katzis* are the castles of *Juvalta*, *Ortenstein*, *Paspels*, *Canova*, *Rietberg*, and *Fürstenau* on the right, and that of *Realta* on the left bank. Towards *Katzis* (2185 ft.; *Kreuz*) the scenery is particularly fine. To the S. rises the snow-clad summit of the *Piz Curver* (9760 ft.); beyond this, to the left, lies the *Schym Pass*, with the majestic *Piz St. Michël* (10,371 ft.) in the background; to the N. the *Ringelspitz* (10,659 ft.) and the *Trinserhorn* (9934 ft.). Near Thusis, above the village of *Masein*, rises the castle of *Tagstein*.

16 M. **Thusis**, Romansch *Tusaun* (2448 ft.; \**Via Mala*; \**Adler*; \**Hôtel and Pension Rhaetia*), lies at the confluence of the Rhine and the *Nolla*, the turbid water of which tinges the Rhine for a considerable distance. Interesting view from the bridge over the *Nolla*. In the background of the valley towers the barren *Piz Beverin* (9843 ft.).

Beyond Thusis the valley of the Rhine is apparently terminated by lofty mountains. The entrance of the ravine of the Rhine is guarded on the right bank by the ruined castle of *Hohen-Rhätien*,

or *Hoch-Reall*. Prior to 1822 the bridle-path from Thusis ascended the valley of the Nolla on the right bank through forest, and entered the gorge below *Rongellen* (see below). The path through the gorge, the celebrated \**Via Mala*, was then only 4 ft. wide, and followed the left bank. The new road was constructed in 1822. The limestone-rocks rise almost perpendicularly on both sides to a height of 1600 ft. At the *Känzli*, a little way from the entrance of the ravine, there is a fine retrospect. About 1½ M. from Thusis is the *Verlorne Loch*, a tunnel 50 yds. long, penetrating the projecting rock. Before reaching it the road passes beneath a huge overhanging cliff. At the point, beyond the tunnel, where the side-wall ceases and the wooden railings recommence, a view of the brawling torrent is obtained. The retrospective \*view, through the narrow and gloomy defile, of the solitary tower of Hohen-Rhætien and the sunny slopes of the Heinzenberg beyond is very striking.

Near the (¾ M.) post-house of *Rongellen* the gorge expands, but soon again contracts. The road crosses the river three times at short intervals. The scene is most imposing in the vicinity of the \*SECOND BRIDGE (2844 ft.), built in 1738, 1 M. from *Rongellen*. The Rhine, 260 ft. below the road, winds through a ravine so narrow that the precipices above almost meet. At the third bridge, built in 1834, about 1 M. farther, the *Via Mala* ends.

The road now enters the more open *Valley of Schams*, the green meadows and cheerful cottages of which present a pleasant contrast to the sombre defile just quitted. To the S. in the background are the peaks of the *Hirli* (9373 ft.). Above the old bridge the Rhine forms a small waterfall. The first village in the valley of Schams (6 M. from Thusis) is *Zillis*, Roman. *Zirau*n (Inn), with the oldest church in the valley. On the hill to the right, on the left bank of the Rhine, stands the ruined castle of *Fardün*, or *La Turr*. Farther down is the village of *Donat*, above which towers the *Piz Beverin*.

23½ M. *Andeer* (3212 ft.; \**Krone*, or *Hôtel Fravi*) is the principal village in the valley, with 600 inhab. Near it stands the tower of *Castellatsch*. Fine view of the valley from the church, built in 1673.

The road ascends in windings, passes the ruins of the *Bärenburg*, and enters the \**Roffna Ravine*, a gorge 3 M. in length, in which the Rhine forms a series of waterfalls. Near the entrance the *Averser Rhein* descends from the *Ferrera Valley* and joins the *Hinter-Rhein*.

Towards the end of the gorge, an ancient bridge crosses the Rhine. Farther on, a rocky gateway (*Sassa Plana*), 16 yds. in length, is passed. The open Alpine landscape of the *Rheinwaldthal* (*Val Rhein*) is now disclosed; to the right is the village of *Suvers* (4673 ft.); opposite rise the *Pizzo Uccello* (8911 ft.) and the *Einshorn* (9650 ft.); to the left of the *Splügen*, near the Uc-

cello, is the *Tambohorn* (10,748 ft.); to the W. the *Zapporhorn* (9803 ft.), etc.

32½ M. **Splügen**, Roman. *Spluga* (4757 ft.; \**Hôtel Bodenhaus*), the capital of the Rheinwaldthal, is a busy place, owing to its position at the junction of the Splügen and Bernardino routes. The latter (p. 37) here runs towards the W. The Splügen route turns to the left, crosses the Rhine, and ascends in windings, passing through a tunnel 93 yds. in length. Retrospect of the barren *Kalkberg* rising above Splügen. The road then enters a bleak valley and ascends on the W. side by numberless zigzags, passing a solitary Refuge, to the summit of the **Splügen Pass** (*Colmo dell' Orso*; 6946 ft.), lying between the precipitous *Tambohorn*, or *Schneehorn* (10,748 ft.) to the W., and the *Surellahorn* (9925 ft.) to the E. This narrow ridge forms the boundary between Switzerland and Italy. The pass, which was known to the Romans, was traversed down to 1818 by a bridle-path only. The road was constructed by the Austrian government in 1819-21. About ¾ M. beyond the pass is the *Dogana* (6247 ft.), the Italian custom-house, at the head of a bleak valley surrounded by lofty mountains.

The road now descends by numberless zigzags along the E. slope, being protected against avalanches by three long galleries. Beyond the second gallery a beautiful view is obtained of *Isola* and the old road, destroyed by an inundation in 1834. The new road avoids the dangerous *Liro* gorge between *Isola* and *Campo Dolcino*. Beyond *Pianazzo*, near the entrance to a short gallery, the *Madèsimo* forms a magnificent waterfall, about 700 ft. in height, which is best surveyed from a small platform by the road-side.

50 M. **Campo Dolcino** (3457 ft.) consists of two large groups of houses. The first contains the church, surrounded by ash-trees, and the 'Campo Santo'. At the second, ½ M. farther, is the *Croce d'Oro Inn* (moderate). The *Liro Valley* is strewn with fragments of rock, but the wildness of the scene is softened by the luxuriant foliage of the chestnuts lower down, from which rises the slender white campanile of the church of *Madonna di Gallivaggio*. Near *S. Giacōmo* there are whole forests of chestnuts, which extend far up the steep mountain slopes. The vineyards of *Chiavenna* soon begin, and the rich luxuriance of Italian vegetation unfolds itself to the view.

58½ M. **Chiavenna** (1090 ft.; \**Hôtel Conradi*, near the post-office; *Chiave d'Oro*; *Chiavenna* beer is the best in N. Italy), the Roman *Clavenna*, an ancient town with 3800 inhab., is charmingly situated on the *Maira*, at the mouth of the *Val Bregaglia*, through which the road to the Maloja Pass and the Engadine leads. Opposite the post-office, on the road, are the extensive ruins of a castle, formerly the property of the *De Salis* family. Picturesque view from the castle-garden or 'paradiso' (fec ½ fr.), which extends along an isolated vine-clad rock. — *S. Lorenzo*, the principal church,

near the post-office, has an elegant slender clock-tower or campanile, rising from the old Campo Santo, or burial-ground, with its arcades. The *Battisterio* contains an ancient font adorned with reliefs.

The road to Colico at first traverses vineyards; farther on, the effects of the inundations of the *Maira*, and its tributary the *Liro*, which joins it below Chiavenna, become apparent. Near —

65 M. **Riva** the road reaches the *Lago di Riva*, or *di Mezzola*, which, before the construction of the road, travellers were obliged to cross by boat. This piece of water originally formed the N. bay of the Lake of Como, but the deposits of the *Adda* have in the course of ages almost entirely separated the two lakes, and they are now connected by a narrow channel only. The road skirts the E. bank of the lake, in some places supported by embankments and masonry, in others passing through galleries, and crosses the *Adda*. Before the road joins the Stelvio route (p. 44), the ruins of the castle of *Fuentes*, erected by the Spaniards in 1603, and destroyed by the French in 1796, are seen on the right. It was formerly situated on an island, and considered the key of the Val Tellina.

75½ M. **Colico** (722 ft.; *Isola Bella*, *Angelo*, both in the Italian style; *Ristoratore della Posta*, on the lake), is situated at the N.E. extremity of the Lake of Como (R. 22). The Swiss diligence runs on the road mentioned at p. 144 viâ (86½ M.) *Varenna* as far as (101½ M.) *Lecco* (p. 144). — *Diligence* to Sondrio in 5, Tirano 9, Bormio 14 hrs. — From Colico to *Como*, see pp. 139-43; from *Como* to *Milan*, see R. 21.

## 6. From Coire to Bellinzona. S. Bernardino Pass.

76½ M. — *DILIGENCE* from Coire to Bellinzona (76½ M.) twice daily in summer in 15 hrs. (fare 26 fr. 15, coupé 30 fr. 15 c.). Remarks as to diligence-seats, see p. 27. Carriage with two horses 180, to Lugano 210 fr.

From *Coire* to *Splügen*, 32½ M., see pp. 33-36.

The **BERNARDINO-ROAD**, constructed in 1819-23, ascends from the village of *Splügen* (4757 ft.) to the W., in the upper *Rheinwaldthal*, or *Val Rhein*, on the left bank of the *Hinter-Rhein* to —

39 M. **Hinterrhein** (5302 ft.; *Post*), the highest village in the valley. The source of the *Hinter-Rhein* (7270 ft.) may be reached hence in 3½ hrs. About ½ M. beyond the village the road crosses the first bridge (5301 ft.), which spans the Rhine in three arches, and then in sixteen windings ascends a steep slope with a fine view of the valley. On reaching the top it leads through a bleak valley to the **S. Bernardino Pass** (6768 ft.), which was known to the Romans, and was called the *Vogelberg* down to the 15th century. When S. Bernardino of Siena preached the gospel at that period in this region, a chapel was erected on the S. slope and gave its name to the pass. The small *Lago Moësa* (2 hrs. from *Hinter-Rhein*), out of which three rocks project, lies on the summit of the pass (Inn). From the S. end of the lake issues the *Moësa*,

which the road follows down to its confluence with the Ticino above Bellinzona. The new road descends in numerous windings, following the left bank of the Moësa. (On the opposite bank we observe long portions of the old road which was destroyed by an inundation.) The road then crosses the stream by a handsome new bridge, and after another long curve reaches (4 M. from the summit of the pass) —

49 $\frac{1}{2}$  M. **S. Bernardino** (5335 ft.; \**Hotel Brocco*; *Ravizza*; *Desteffanis*), the highest village in the *Val Mesocco*, or *Mesolcina*, with a mineral spring which attracts invalids in summer. Between S. Bernardino and *S. Giacomo* we pass a fall of the Moësa. Near S. Giacomo the road again crosses the river by a bridge commanding a fine view, and then descends rapidly to —

58 M. **Mesocco**, or *Creneo* (2559 ft.; *Toscani*; *Desteffanis*), charmingly situated amidst walnuts, chestnuts, vines, and maize-fields. Numerous brooklets fall from the surrounding mountains. On a rocky eminence to the left of the road,  $\frac{1}{2}$  M. below the village, stand the imposing ruins of the *Château of Mesocco* with its four towers, which was destroyed by the inhabitants of the Grisons in 1526. Beyond (2 M.) *Soazza* (2067 ft.) the bottom of the valley is reached, and the road becomes level. Near the second bridge below Soazza the *Buffalora* forms a fine cascade near the road. Near *Cabbiolo* another waterfall; then *Lostallo* with extensive vineyards. The first figs and mulberries are seen near the Capuchin monastery of —

68 M. *Cima* (1260 ft.). The next villages are *Leggia* and *Grono*, the latter at the entrance to the *Val Calanca*, with the massive tower of *Florentina*.

71 M. **Roveredo** (974 ft.; *Posta*; *Croce*; \**Angelo*), the capital of the lower Val Mesocco, with the ruined castle of the *Trivulzio* family.

*S. Vittore* (882 ft.) is the last village in the Grisons, *Lumino* the first in the Canton Ticino. On this side the bridge over the Moësa the road unites with the St. Gotthard route (p. 32). Below the confluence of the Moësa and the Ticino lies *Arbedo*, where a battle was fought in 1422 between the Milanese and the Swiss, in which 2000 of the latter fell.

76 $\frac{1}{2}$  M. **Bellinzona**, a station on the line to *Locarno*, on the Lago Maggiore, see p. 32; diligence to *Lugano*, see p. 33.

## 7. From Innsbruck to Colico on the Lake of Como (and Milan) over the Stelvio.

210 M. DILIGENCE from Innsbruck to *Landeck* daily (usually in the evening, returning on the following day about noon) in 8 hrs. (fare 6 fl. 60 kr.). STELLWAGEN daily at 5 a.m. (starting from the Adler or Stern). — DILIGENCE from Landeck to *Eys* daily (usually at noon) in 9 $\frac{1}{2}$  hrs. (also a Stellwagen). — DILIGENCE in summer from Eys to the *Baths of Bormio* daily in 11 $\frac{1}{2}$  hrs. (fare 6 fl.). There are also open carriages. If a seat in one of these cannot be procured, it is pleasanter in fine weather

to walk over the pass. Departure from Eys at 6.30 a. m., returning from Bormio at the same hour. MESSAGERIE between Bormio and Sondrio, and between Sondrio and Colico daily (from the Baths of Bormio to Colico in 14 hrs., fare 15 fr. 20 c.). From 1st Oct. to 15th June no diligence from Eys to Sondrio. (Carriage with two horses from Bormio to Sondrio 67 fr., to Colico 102 fr.; from Sondrio to Colico 35 fr.)

The \*STELVIO ROAD, the highest in Europe, 9172 ft. above the sea-level, was constructed by the Austrian government in 1820-25. The bold and skilful construction of the road and the grandeur of the scenery render this one of the most remarkable routes in Europe. The vast glaciers and snow-fields of the Ortler and Monte Cristallo present a striking contrast to the vineclad slopes of the Valtellina, and the luxuriant southern vegetation of the banks of the Lake of Como. Pedestrians are strongly recommended not to take any of the short cuts, as all the finest views are from the road itself. Since the evacuation of Lombardy by the Austrians, the road on the Tyrolese side was much neglected, but has since been repaired.

**Innsbruck** (1870 ft.; *Tyroler Hof*, new; \**Europäischer Hof*, both near the station. In the town: *Goldene Sonne*; *Goldner Adler*, near the bridge; *Stadt München*, moderate; *Hirsch*; *Stern*, on the left bank of the Inn), the capital of the Tyrol, with 16,000 inhab. and a garrison of 1500 men, is charmingly situated on both banks of the *Inn*, in the midst of a broad and fertile valley enclosed by lofty mountains. The chief object of interest in the town is the \**Hofkirche*, or *Franciscan Church*, built at the beginning of the 16th cent., and containing the \*monuments of Emp. Maximilian I. (d. 1519), with the celebrated reliefs by Alex. Colin, and 28 colossal statues in bronze, by P. Vischer, and others. The *Ferdinandeam* contains valuable collections, see *Baedeker's S. Germany and Austria*.

The road ascends on the left bank of the *Inn*, passing the *Martinswand* (3778 ft.), a precipice where the Emp. Maximilian I. nearly lost his life in 1493, while chamois-hunting. Above —

8 M. *Zirl* (2001 ft.; \**Stern*; *Löwe*), rises the ruined castle of *Fragenstein*. Near —

17½ M. *Telfs* (2070 ft.; Post; *Löwe*) the road crosses the *Inn* and passes the considerable (l.) Cistercian monastery of *Stams*. Beyond —

25½ M. *Silz* (2130 ft.; *Steinbock*) rises the wooded *Petersberg* on the left, crowned with the ruined castle of that name, and the new château of *Welfenburg*. Beyond *Haimingen* the road crosses the *Inn* to *Magerbach* (2170 ft.; \**Inn*), and skirts the base of the *Tschürgant* (7766 ft.). A remarkable view is obtained here of the masses of debris with which the *Oetzthaler Ache*, descending from the *Oetzthal*, covers the whole valley. Beyond *Roppen*, where the *Pitzthal* opens to the S., the road quits the *Inn* and ascends gradually to —

38 M. *Imst* (2710 ft.; \**Post*), a well-built village at the base of the *Laggersberg* and the *Platteinkogl*. — The road again descends and approaches the *Inn*. The next villages are *Mils* and *Starkenbach*. The imposing ruins of the *Kronburg* rise on a lofty

eminence on the opposite bank. The bridge over the Inn near *Zams* (2722 ft.) has frequently been the scene of fierce contests.

52 M. **Landeck** (2638 ft.; \**Post*; *Goldner Adler*), a considerable village on both banks of the Inn, is commanded by the old castle of the same name.

The road passes below the castle on the right bank of the river, which here forces its way through a narrow ravine and forms several rapids. The *Pontlatzer Bridge*, 6 M. from Landeck, has on several occasions proved a most disastrous spot to the Bavarian invaders of the Tyrol.

On the right, on a precipitous rock above Prutz, stands the ruin of *Laudegg*. Near it, on the height, is the village of *Ladis*, 1 hr. from Prutz, with sulphur-baths;  $\frac{1}{2}$  hr. higher up are the charmingly situated baths of *Obladis*. *Prutz* (Rose), where the road recrosses the Inn, lies in a swampy plain at the entrance of the *Kaunserthal*.

62 M. **Ried** (2851 ft.; *Post*; *Adler*) is a thriving village, with the castle of *Siegmundsried*, the seat of the local authorities. Farther on is *Tösens* (3045 ft.; *Wilder Mann*), where the Inn is again crossed.

71 M. *Pfunds* (3182 ft.; \**Traube*) consists of two groups of houses, separated by the river. To the S.W. rises the *Mondin-Ferner* (10,378 ft.), one of the N. Engadine chain.

Above Pfunds the road crosses the Inn and gradually ascends on the right bank, hewn at places in the perpendicular rock, or supported by solid masonry, and commanding picturesque views of the narrow valley of the Inn. The finest point is at \***Hoch-Finstermünz** (3730 ft.; \**Inn*), about  $4\frac{1}{2}$  M. from Pfunds, a small group of houses on the road. Far below are the old *Finstermünz* tower (3203 ft.) and a bridge over the Inn. These, with the defile through which the river issues from the Engadine, and the mountains in the background, form a very striking picture.

81 M. **Nauders** (4468 ft.; *Post*; *Mondschein*), with the old castle of *Naudersberg*, which contains the district court of justice.

The road now gradually ascends to the *RESCHEN-SCHNEDECK* (4898 ft.), the watershed between the Black Sea and the Adriatic. Beyond the village of *Reschen* (4888 ft.; *Stern*), near the muddy lake of that name, a very striking \*view is disclosed. The entire background is formed by the snow and ice-fields of the *Ortler* chain. The *Etsch*, Italian *Adige*, rises near Reschen, and flows through the lake, and also through the *Mittersee* and *Heidersee*. Between these is situated —

90 M. *St. Valentin auf der Heide* (4695 ft.; \**Post*), formerly the hospice of the bleak and rocky *Mals* *Heide*. The beauty of the view increases as the road approaches the *Vintschgau* (Val Venosta). The Ortler continues to form the imposing background. As the road descends, the villages of *Mals*, *Glurns*, and *Tartsch*, when

viewed from the height, almost appear to form a single town. To the right, before Mals is reached, is seen the village of *Burgeis*, with its red spire, and the castle of *Fürstenburg*, now occupied by a number of poor families. The Benedictine Abbey of *Marienberg* lies on the hill to the right.

97 M. **Mals** (3430 ft.; \**Post* or *Adler*; \**Hirsch*; *Gans*) is a small town of Roman origin. Beyond it the ancient tower of the *Frölichsburg* is passed. In the distance to the right, on the opposite bank of the Etsch, rises the handsome but dilapidated castle of *Lichtenberg*. To the left of the road, near *Schluderns*, is the *Churburg*, a chateau of Count Trapp. At *Neu-Spondinig* (2855 ft.; \**Hirsch*), 1½ M. before reaching Prad, the Stelvio-road crosses the broad, marshy valley of the Etsch and the river itself by a long bridge, which forms the boundary between the Upper and Lower Vintschgau.

107 M. **Prad** (3100 ft.; \**Post*), or *Bivio di Prad*, or *Brad*, an insignificant village. The road now enters the narrow valley of the *Trafoi-Bach*. On the hill-side to the right lies the village of *Stilfs*, Ital. *Stelvio*, from which this route derives its name.

Near *Gomagoi* (Inn), with its fort, built in 1860, the wild *Suldenthal* opens on the E. To the S. the snow mountains of Trafoi come in sight; to the N. the *Weisskugel*, the second highest of the Oetzthal Alps, long remains visible.

116 M. **Trafoi** (5081 ft.; \**Post*). Pleasant walk of ¾ hr. to the \**Three Holy Springs*, which rise in the valley below at the foot of the Ortler.

The Stelvio now ascends in bold windings, on the left side of the valley. As the best views are obtained from the bends in the road, the short cuts should be avoided. The finest point is the \**Weisse Knott*, 1¼ hr. ascent from Trafoi, a rocky projection with a balustrade commanding a superb view of the magnificent *Madatsch-Glacier*. A little farther on is the *Cantoniera al Bosco*, which was destroyed by the Italians in 1848. At —

123 M. **Franzenhöhe** (7156 ft.; \**Wallnöfer*), the highest peak of the *Ortler* (12,814 ft.) becomes visible for the first time. The road now ascends in numerous windings on slopes of talc-slate. Vegetation gradually disappears, and scanty moss alone is seen clinging to the rocks.

The summit of the **Stelvio Pass** (9172 ft.), Germ. *Stilfser Joch*, about 6½ M. from the *Franzenhöhe*, is the boundary between Austria and Italy. A workmen's house stands at the top, whence a footpath ascends in 20 min. to a rocky height which commands an extensive \*panorama.

Immediately to the left of the road rise the huge icy masses of the *Cristallo* and *Stelvio Glaciers*. The snow here seldom melts except in unusually warm seasons.

132 M. **S. Maria** (8153 ft.; *Inn*), the fourth *Cantoniera* and



the Italian custom-house ( $\frac{1}{2}$  hr. from the summit of the pass), is situated in a bleak mountain basin, almost destitute of vegetation, and surrounded by barren peaks. The interesting ascent of the \**Piz Umbrail* (9918 ft.) may be made from this point in  $1\frac{1}{2}$  hr.

The diligence runs hence to (12 M.) Bormio (see below) in less than 2 hrs. (In the opposite direction it takes  $4\frac{1}{2}$  hrs., and may easily be outstripped by a good walker. From S. Maria to Prad, p. 41, 25 M.)

The road next reaches the *Cantoniera al Pianodel Braulio* (7871 ft.; Inn, tolerable), in a green valley, with a chapel; and then the *Casino dei Rotteri di Spondalunga*, a road-menders' house. The road descends by numerous windings which the pedestrian may generally cut off, crosses the brook descending from the *Val Vitelli*, and reaches the *Cantoniera al Piede di Spondalunga* (6906 ft.), which was destroyed by the Garibaldians in 1859 and has since been a ruin. To the right rises the precipitous *Monte Braulio* (9778 ft.). The road next descends in long windings by a succession of galleries through the narrow defile of the *Wormser Loch* ('*Il Dirocamento*'), and reaches the *Cantoniera di Piatta Martina* (5971 ft.), a refuge for travellers. Farther on, to the right, the Adda emerges from the wild *Val Fraele* (a considerable brook issuing from the rocks below the Val Fraele is sometimes erroneously called the *Source of the Adda*).

Beyond the last gallery but one the valley turns to the S., and a magnificent view is disclosed of the valley of Bormio as far as Ceppina, S.W. the *Piz S. Colombano* (9625 ft.), the *Cima di Piazza* (11,713 ft.), and the *Piz Redasco*, S.E. the *Cime di Gobetta* and the ice pyramid of the *Piz Trezero* (11,604 ft.). On the right, beyond the deep ravine of the Adda, tower the abrupt slopes of the *Monte delle Scalte*. The *Bagni Vecchi*, or Old Baths of Bormio, now come into view, perched on the rocks below the road. Before the last cutting is reached, a road descends to them direct (accommodation unpretending, but good). At the egress of the last tunnel (the *Galleria dei Bagni*) a slab on the rock to the left records that this road was begun in 1820, and completed by the architect Donegani in 1825. The bridge here was blown up by the Austrians in 1859.

The handsome \***New Bath-House** (*Bagni Nuovi*, 4397 ft.),  $\frac{1}{2}$  M. lower down, and 10 M. from S. Maria, situated on a terrace commanding a fine survey of the valley of Bormio and the surrounding mountains, is much frequented in July and August, but is closed about the end of September. The mineral water (containing salt and sulphur, 93-100° Fahr.) is conducted hither by pipes from the springs at the old bath, 1 M. higher up. The windings of the road terminate, about 1 M. lower down, at —

144 M. **Bormio** (4007 ft.; *Posta*; *Cola*, in the market-place), an old-fashioned little town of Italian character, with several dilapidated towers, at the entrance of the *Val Furva*.

The road crosses the muddy *Frodolfo*, which unites with the *Adda* below the bridge, and, turning towards the S., enters a broad green region of the valley called *Piano di Bormio*, extending to the village of *Ceppina*, and enclosed by lofty mountains. Below (3 M.) *Ceppina* is the hamlet of *S. Antonio*. Then (3 M.) *Morignone*. The defile of *La Serra*, 1 M. in length, here separates the '*Paese Freddo*', 'cold region', or district of Bormio, from the *Valtellina*, which belonged to the Grisons down to 1797, then to Austria, and has since 1859 been Italian. The broad valley is watered by the *Adda*, the inundations of which often cause considerable damage. The vineyards on the slopes yield excellent red wine. The climate is considered unhealthy, and cretinism is not infrequent. — The *Ponte del Diavolo* was destroyed by the Austrians in 1859. The valley now expands, and the vegetation of the south gradually develops itself. To the left lies *Le Prese*; farther on, *Mondadizza*.

155½ M. **Bolladore** (2838 ft.; \**Post*). On the hill to the right rises the picturesque church of *Sondalo*. Near the considerable village of (3½ M.) *Grosio* the road crosses the *Adda*, and, below (¾ M.) *Grosotto* (*Leone*), recrosses it at *Mazzo*. To the W. rises the precipitous *Fiz Masuccio* (8740 ft.), a landslip from which in 1807 blocked up the narrow bed of the *Adda* and converted the populous and fertile valley into a vast lake. The road now descends by *Tovo*, *Lovero*, and *Sernio*, passing vineclad hills, to —

167½ M. **Tirano** (1506 ft.; \**Posta*; \**Stelvio*), a small town with old mansions of the *Visconti*, *Pallavicini*, and *Salis* families, which has often suffered from the inundations of the *Adda*.

About ¾ M. farther, on the right bank of the *Adda*, lies **Madonna di Tirano** (\**S. Michele*). — (The road which diverges here to the right leads to *Poschiavo*, and over the *Bernina* to the *Upper Engadine*; see *Baedeker's Switzerland*. The '*Confine Svizzero*' is ¾ M. N. of *Madonna di Tirano*.)

The road next crosses the *Poschiavino*, a stream descending from the *Bernina* glaciers. At *Tresenda* the new road over the *Monte Aprica* diverges (R. 30). About halfway up the N. slope of the valley rises the ancient watch-tower of *Teglio*, whence the valley (*Val Teglino*) derives its name. To the right is *Chiuro*, at the mouth of the *Val Fontana*; near *Sondrio* the churches of *Pendolaseo* and *Montagna* are seen on the hill to the right.

184½ M. **Sondrio** (1139 ft.; \**Posta*; *Maddalena*), the capital of the *Valtellina*, is situated on the *Malero*, an impetuous torrent which has frequently endangered the town, but is now conducted through a broad artificial channel. The Nunnery, a large edifice outside the town, is now a prison; the old castle of the governors is used as a barrack. Interesting excursion hence into the picturesque *Val Matenco*, traversed by the *Malero*.

Farther to the W. rises the church of *Sassella*, built on a rocky eminence and supported by galleries. Vines, mulberries, and

pomegranates flourish luxuriantly in the valley, while in the background tower the snowy peaks of the *Monte della Disgrazia* (12,057 ft.), one of the Bernina range.

200 M. **Morbegno** (853 ft.; \**Regina d'Inghilterra*, or *Posta*) is noted for its silk-culture. The lower part of the Valtellina is rendered unhealthy by the inundations of the Adda. Before reaching Colico the road is joined by the Splügen route from the right (p. 38).

210 M. *Colico* and the *Lake of Como*, see R. 22. Railway from *Como* to *Milan*, see R. 21.

## 8. From Innsbruck to Verona by the Brenner.

164½ M. RAILWAY in 9¼-12 hrs.; express fares 15 fl. 91, 11 fl. 84 kr.; ordinary 13 fl. 32, 9 fl. 99, 6 fl. 66 kr. (these are the fares in silver, to which is added a trifling stamp duty, and, if they are paid in paper, the difference in value between silver and paper). Views on the *right* as far as the summit of the Brenner. Information as to through-tickets, see *Intro.* vii.

The BRENNER, the lowest pass over the principal chain of the Alps, is traversed by the oldest of the Alpine routes, which was used as early as the Roman period, and rendered practicable for carriages in 1772. The railway, opened in 1867, one of the grandest modern works of the kind, affords the most direct communication between Germany and Italy. It ascends for 21 M. with an incline of 1:40 to the culminating point. The descent to Brixen is less rapid. There are 23 tunnels and 60 bridges of various dimensions between Innsbruck and Bozen.

*Innsbruck* (1870 ft.), see p. 39. The train passes the Abbey of *Wilten* (on the right) and penetrates the hill of *Isel* by a tunnel 750 yds. in length. It then passes through another tunnel, and crosses to the right bank of the *Sill* on which it ascends. Five other tunnels are traversed before it reaches (5 M.) *Patsch* (2560 ft.), near which the *Rutzbach*, descending from the *Stubaythal*, is precipitated into the *Sill* from a narrow gorge on the right.

The valley becomes narrower and wilder. Four more tunnels. The *Sill* is crossed twice.

12 M. *Matrei* (3241 ft.), with the château of *Trautson*, the property of Prince Auersperg, is charmingly situated. — 14 M. *Steinach* (3448 ft.); the village lies on the other side of the valley, at the mouth of the *Gschnitzthal*.

The train then passes the village of *Stafflach* in a wide curve, turning into the *Schmirner Thal* (two tunnels), and ascends, high above the profound ravine of the *Sill*, to (19½ M.) *Gries*; then, in another curve, passes the small green *Brennersee*, and reaches —

38 M. Stat. **Brenner** (4485 ft.), on the summit of the pass, the watershed between the Black Sea and the Adriatic. View limited. The *Sill*, which rises on the N. side of the pass, falls into the *Inn*; the *Eisak*, rising on the S. side, descends to the *Adige*. The train follows the course of the *Eisak* and soon stops at (46 M.) *Brennerbad* (4353 ft.), a solitary bath-establishment. It then descends

rapidly by means of a long embankment and through two tunnels to stat. *Schelleberg* (4069 ft.), where it turns into the *Pfersch-Thal*. Here it enters the N. slope of the valley by a curved tunnel, 800 yds. long, from which it emerges in the opposite direction, soon reaching (33 M.) *Gossensass*, which lies 588 ft. below Schelleberg. This is one of the most interesting parts of the line, and is most striking when seen in the reverse direction.

The train now runs high above the Eisak, passing at places through wild rocky scenery.

38 M. **Sterzing** (3107 ft.; *Post*; *Schwarzer Adler*; *Rose*), a clean and picturesque little town with curious old buildings and arcades, deriving its prosperity from mines formerly worked here, lies in the broad *Sterzinger Moos*.

The train now crosses the *Pfitscher Bach*; on the left rises the castle of *Sprechenstein*, and on the right bank of the Eisak, the ruins of *Thumburg* and *Reifenstein* are visible. — 40½ M. *Freienfeld*. The train crosses the Eisak; on the left bank rises the ruined castle of *Welfenstein* (said to be of Roman origin), and the village of *Mauls*. — Beyond (45 M.) *Grasstein* the train enters the narrow defile of *Mittewald*, where the French were defeated in 1809.

The lower end of the defile, called the *Brixener Klause*, near *Unterau* (2703 ft.), is strongly fortified by the **Franzensfeste**, constructed in 1833. These works, which are very conspicuous when seen from the S., command the Brenner route. *Franzensfeste* (47½ M. from Innsbruck) is the junction for the Pusterthal line; the station (*\*Rail. Restaurant*, D. 1 fl. 20 kr.) lies at some distance from the precincts of the fortifications. The vegetation now assumes a more southern character, vineyards and chestnuts gradually appearing.

57 M. **Brixen**, Ital. *Bressanone* (1833 ft.; *\*Elephant*, adjoining the post-office, ½ M. from the station), was for nine centuries the capital of a spiritual principality, which was dissolved in 1803, and is still an episcopal residence. Most of the churches date from the 18th cent., and are unimportant. At the S.W. end of the town is the *Episcopal Palace* with an extensive garden.

The train next crosses the Eisak by a lofty iron bridge; on the right, above, lies *Tschötsch*; on the left, the pleasant village of *Albeins*.

61½ M. **Klausen** (1791 ft.; *Lamm*; *Post*), consisting of a single narrow street, is situated in a defile, as its name imports. The Benedictine monastery of *Seben*, on the right, commands a very striking view. It was once a Rhätian fortress, then a Roman fort under the name of *Sabiona*, afterwards an episcopal residence down to the 10th cent., and finally a baronial castle.

Below Klausen the valley contracts. The line skirts precipitous porphyry cliffs. On the heights above extend fertile plains,

sprinkled with numerous villages. 66½ M. *Waidbruck* (1520 ft. ; *Sonne*), at the mouth of the *Grödener Thal*. On the left, high above, rises the *Trostburg*, the property of Count *Wolkenstein*. This is the most picturesque point in this narrow part of the valley of the *Eisak*.

The train crosses the *Grödenerbach*, and then the *Eisak* in a narrow valley enclosed by abrupt porphyry rocks, called the *Kun- tersweg* after the first constructor of the road. — 71 M. *Atzwang* (1244 ft. ; \**Post*), at the mouth of the *Finsterbach*. Four short tunnels. Stat. *Blumau*, at the mouth of the *Tierser Thal*. On the right bank are the vineclad slopes of the *Bozener Leitach*; another tunnel is passed through, and the train crosses to the right bank of the *Eisak* near the village of *Kardaun*, at the opening of the *Eggenthal*. The train now enters the wide basin of *Bozen*, a district of luxuriant fertility, resembling a vast vineyard.

80 M. **Bozen**, Ital. *Bolzano* (850 ft. ; \**Kaiserkrone*, in the *Musterplatz* ; \**Hôtel Victoria*, near the station ; *Mondschein* ; *Erz- herzog Heinrich* ; *Krüütner* ; *Schwarzer Adler*), with 9400 inhab., the most important commercial town in the Tyrol, is beautifully situated at the confluence of the *Eisak* and the *Talfer*, which descends from the *Sarnthal* on the N. The background towards the E. is formed by the strikingly picturesque dolomite mountains of the *Val di Fassa* ; to the W. rises the long porphyry ridge of the *Mendola*. The Gothic *Parish Church* of the 14th and 15th cent. has a W. Portal, with two lions of red marble, in the Lombard style. Beautiful open tower, completed in 1519. On the E. side a gateway with the inscription '*Resurrecturis*' leads to the *Cemetery*, surrounded by arcades. — The \**Calvarienberg* (25 min. walk ; beyond the *Eisak* bridge cross the railway to the right) commands a fine view of the town and environs. — *Gries* (1 M. from the station), in a sheltered situation on the right bank of the *Talfer*, has of late years become a winter-resort for invalids.

Beyond *Bozen* the train crosses the *Eisak*, which falls into the *Etsch* (or *Adige*) 4 M. below the town. The latter becomes navigable at stat. *Bronzoll* (Ital. *Bronzollo*). In the distance, to the right, rises the dilapidated castle of *Sigmundskron*, and the wooded range of the *Mittelberg*, which separates the vine-covered plain of *Eppan* from the valley of the *Adige*. Beyond stat. *Auer* (Ital. *Ora*), near *Gmundl*, the train crosses the river ; to the right lies the *Kalterer See* ; above it, on the hill, *Kaltern*, with its famous vineyards. — 94½ M. *Neumarkt*, Ital. *Egna*, where the German element still preponderates, lies on the left bank of the *Adige*, and consists of a single street only. On the slopes to the right lie the villages of *Tramin*, *Kurtatsch*, and *Margreid*. — 99½ M. *Saturn* on the left bank of the river, commanded by a ruined castle on an apparently inaccessible rock.

The *Rocchetta Pass* to the right leads to the *Val di Non*. *Mezzo*

*Tedesco* and *Mezzo Lombardo* (or *Deutsch* and *Wälsch-Metz*), situated on different sides of the pass, separated by the *Noce*, are both Italian.

104 M. *S. Michele*, or *Wälsch-Michael*, with a handsome old Augustinian monastery (suppressed), is the station for the Val di Non. The train again crosses the Adige. 109 M. *Lavis* on the *Avasio*, which here descends from the Val Cembra. This impetuous torrent with its different ramifications is crossed above its junction with the Adige by a bridge 1000 yds. in length.

115<sup>1</sup>/<sub>2</sub> M. *Trent*, or *Trento*, Lat. *Tridentum* (715 ft.). — *Hotels*: EUROPA, R. 80, L. 20, B. 50 KR.; HÔTEL DE LA VILLE; HÔTEL TRENTO, new; CORONA; REBECCHINO, next to the Hôtel de la Ville; AQUILA BIANCA; CASTELLO. — *Cafés* Europa und Specchi. — *Carriages* may be hired of F. Gennari, the postmaster: with one horse to Arco, 8 fl., with two horses 14, with three, 20 fl.; to Riva 9, 16, or 22 fl.

*Trent*, with 17,000 inhab., formerly the wealthiest and most important town in the Tyrol, founded according to tradition by the Etruscans, and mentioned by Strabo, Pliny, and Ptolemy, possesses numerous towers, palaces of marble, dilapidated castles, and broad streets, and bears the impress of an important Italian town. The *Piazza del Duomo* in particular presents a very imposing appearance.

The \**Cathedral*, founded in 1048, begun in its present form in 1212, and completed at the beginning of the 15th cent., is a Romanesque church surmounted by two domes. The portal, as at Bozen, is adorned with a pair of lions (p. 46). In the S. transept are several old monuments, half-faded frescoes, and on the wall the porphyry tombstone of the Venetian general Sanseverino, whom the inhabitants of Trent defeated and killed at Calliano (see below) in 1487. In the Piazza of the cathedral, which is embellished with a *Fountain*, are the *Archiepiscopal Palace*, and the *Torre di Piazza*.

*S. Maria Maggiore*, where the celebrated Council of Trent sat in 1545-63, contains a picture, on the N. wall of the choir, with portraits of the members of the council, and an excellent organ. Adjoining the S. side of the choir is a column dedicated to the Virgin, erected in 1855 on the 300th anniversary of the meeting of the Council.

To the E. of the town, and N. of the large Piazza d'Armi, is situated the extensive chateau of *Buon Consiglio*, formerly the seat of the Prince-Bishops of Trent, and now a barrack, which contains remains of ancient frescoes. The colossal, circular *Torre di Augusto* is supposed to date from the time of the Romans.

Among the numerous old palaces, the painted façades of which ill conceal the poverty within, may be mentioned *Palazzo Zambelli*, opposite the Hôtel Europa, dating from the 16th cent. (fine view from the garden), and *Palazzo Tabarelli*, in the Contrada del Teatro, said to have been built from designs by Bramante.

The rocky eminence of *Verruca*, or *Dos Trento*, on the right

bank of the Adige, was fortified in 1857, and affords a fine point of view (permission from the commandant necessary). The terrace of the *Capuchin Church* on the E. side of the town also commands a good view.

FROM TRENT TO RIVA ON THE LAGO DI GARDA, a walk of 9 hrs., very fatiguing in hot weather. Omnibus once daily, usually at 9 a.m., fare 2 fl.; carriage, see p. 47.

This route is far preferable to the direct railway-journey to Verona (see p. 49) on account of the charming scenery of the Lago di Garda. The traveller from Bozen, whose time is limited, may shorten the route by taking the railway as far as stat. *Mori*, and driving thence to (10 M.) *Riva* (see p. 50).

The road crosses the Adige, traverses the suburb *Piè di Castello*, and winds round the S. slope of the Dos Trento (p. 47). A wild and rocky defile (*Bucco di Vela*) is now entered, the upper end of which (3 M.) is closed by a newly erected fort. Traversing the bleak mountain ridge, the road reaches (1½ M.) the small village of *Cadine* (1620 ft.); to the right in the valley lies the village of *Terlago* with its small lake (1320 ft.), at the base of the precipitous *Monte Gazza* (6695 ft.). The road now descends to (1½ M.) *Vigolo-Baselga* and (3 M.) *Vezzano (Corona)*, the principal place between Trent and Arco. At (1½ M.) *Padernone*, at the mouth of the *Val Cavedine*, where we observe the first olive trees, the *Lake of Toblino* becomes visible. The road crosses the narrowest part of it by a bridge, and skirts the N. bank; to the left, on a promontory, rises the picturesque castle of *Toblino*, the property of Count Wolkenstein. Below (1½ M.) *Le Sarche* (Inn unpretending), where the Sarca emerges from a gorge, and the road to *Giudicaria* diverges, the Sarca is crossed by a bridge. Next (1½ M.) *Pietra Murata*. Near (1½ M.) *Drò* is the ruined *Castello di Drena* on an eminence to the left. The road, which has hitherto led through a bleak and rocky wilderness, now traverses a more fertile district. (3 M.) *Arco* (288 ft.; \**Corona*; *Olivo*; *Pension Kirchlechner*, 3 fl. per day), with a handsome parish-church with metal-clad domes, has of late gained a reputation as a winter resort for invalids, owing to its sheltered situation. New château belonging to Archduke Albrecht of Austria. To the N., on a precipitous rock, rises the *Château of Arco*, which during the Spanish War of Succession was destroyed by the French. — Interesting excursion from Arco towards the W. to *Tenno*, see p. 179. — The road now leads through the broad, beautiful valley (to the left the *Monte Brione*, to the right *Tenno*) to (3¾ M.) *Riva* (comp. p. 178).

FROM TRENT TO TREVISO (Venice) BY THE VAL SUGANA, 105 M. Diligence three times daily in 4 hrs. from Trent to Borgo (1 fl. 50 kr.); twice daily from Borgo by Primolano to Bassano in 7 hrs. (2½ fl.); from Bassano to Padua, to Treviso, or to Vicenza in 6-7 hrs. This direct route to Venice (although not the most expeditious) traverses the beautiful *Venetian Mountains*. The road, which ascends immediately beyond Trent, enters the narrow valley of the *Fersina*, and is partially hewn in the rocks or supported by buttresses of masonry.

7½ M. *Pergine* (288 ft.), a considerable market town, commanded by the handsome castle of that name. To the right lies the picturesque lake of *Caldonazzo*, which is drained by the *Brenta*. Farther on is the smaller lake of *Lerico*, in which *Monte Scanupia* (7050 ft.) is reflected. The *Val Sugana* begins at *Levico*, its capital being —

22 M. *Borgo* (411 ft.; \**Croce*), on the N. side of which rises the ruined castle of *Telvaux*, with the remains of a second castle high above it. Below the town is the beautiful château of *Ivano*, belonging to Count Wolkenstein-Trostburg.

Near *Grigno* the valley of *Tesino* opens to the N., watered by the *Grigno*. Beyond Grigno the valley is confined between lofty cliffs which barely leave room for the road. The Austrian custom-house is at *Le Tesse*, the Italian ¾ M. beyond it. In a rocky cavity beyond —

38 M. *Primolano*, is situated the ruined castle of *Covelo*, a mediæval stronghold. About 1 M. farther the *Cismone* descends from the *Val Pri-miero*. *Valstagna* is inhabited chiefly by straw-hat makers.

Near *Solagna* the ravine of the *Brenta* expands, the road turns a corner, and a view is obtained of a broad plain with large olive-plantations in which lies the picturesque town of —

57½ M. **Bassano** (*Mondo*; *S. Antonio*), with 15,000 inhab., and surrounded by lofty old ivy-clad walls. In the centre of the town rises the once fortified tower of the tyrant *Ezzelino*. Bassano possesses no fewer than 35 churches, the chief of which is the *Cathedral*, containing good pictures, the finest by *Giacomo da Ponte*, surnamed *Bassano*, this town having been his birthplace. His best work, a *Nativity*, is in the *Oratorio S. Giuseppe*. In the piazza are to be seen some interesting remains of the façade painting which was common in the towns of the Venetian Terra Ferma (comp. p. 246).

The *Villa Rezzonica*, 1½ M. from the town, contains, amongst other works of art, an oil-painting by *Canova*, representing the *Death of Socrates*. In the suburb of *Borgo Leone* lies the *Villa Parolini*, with a beautiful park.

[*Possagno*, *Canova's* birthplace, is beautifully situated at the base of the *Monte Grappa*, 12 M. N.E. of Bassano. A good road to it leads by *Romano*, the birthplace of *Ezzelino*, and *Crespano*. The church, in the form of a circular temple, designed by *Canova*, contains his tomb, an altar-piece painted by him, and a handsome bronze relief of the *Entombment*. The church and the bridge at *Crespano* (see above), which spans the river by a single arch, were built with funds bequeathed by *Canova* for the purpose. The *Palazzo*, as his house is called, contains models and casts of his works. — Those who wish to proceed direct from *Possagno* to *Treviso*, may go by *Villa Masèr* (p. 246).]

At (66½ M.) *Cittadella* the roads to (85 M.) *Padua* (p. 199) and *Treviso* diverge.

71 M. **Castelfranco**, an ancient town surrounded by walls and towers, was the birthplace of the painter *G. Barbarelli*, surnamed *Il Giorgione* (about 1477-1511). The principal church contains a *Madonna* with *SS. Francis and Liberale* by that master; in the sacristy is a fresco by *Paolo Veronese*, representing *Justice*. *Dr. Luigi Tescari* possesses an interesting collection of Venetian pictures.

87 M. *Treviso*, and railway thence to (105 M.) *Venice*, see R. 37.

Beyond *Trent* the railway continues to traverse the broad and fertile valley of the *Adige*. To the S.W. of *Trent*, on the right bank, is the village of *Sardagna*, with a considerable waterfall. *Stat. Matarello*. On a height near *stat. Calliano* rises the extensive castle of *Beseno*, the property of *Count Trapp*. The rocky debris here are the result of a landslip.

130 M. **Roveredo** (*Cervo*; *Corona*), a town with 11,000 inhab., is noted for its silk-culture. The most remarkable building is the old *Castello* in the *Piazza del Podestà*. — A road leads hence up the valley of the *Leno* and over the *Fugazze Pass* to *Schio* (31 M.), the terminus of a branch-line from *Vicenza* (p. 198).

The lower part of the valley of the *Adige*, down to the Italian frontier, which yields abundance of fruit and good red wine, is called the *Val Lagarina*. On the right bank lies *Isera*, with vineyards, numerous villas, and a waterfall. On the left bank, to the E. of the railway, near *Lizzana*, is a castle, which about the year 1302 was visited by *Dante* when banished from *Florence*.

The train follows the left bank of the *Adige*. — 132 M. **Mori**;



the village lies in a ravine on the opposite bank, on the road leading to Riva, and is famed for its asparagus. — Omnibus to Riva twice daily (usually at 9.45 a. m. and 6.45 p. m.) in 2½ hrs., fare 65 or 75 kr.; one-horse carr. 4, two-horse 7 fl. (comp. p. 179).

Near *S. Marco* the line intersects the traces of a vast landslip, which is said to have buried a town here in 833, and is described by Dante (*Inferno* xii. 4-9). At *Serravalle*, a fort which once guarded the defile, the valley contracts.

141½ M. *Alà* (*Vapore*, ½ M. from the station), a place of some importance, possesses velvet-manufactories which once enjoyed a high reputation, and is the seat of the Italian and Austrian custom-house authorities. Those who have forwarded luggage by this route to or from Italy should take the precaution to enquire for it at the custom-house here. Halt of ½ hr. — *Avio* is the last station in the Austrian dominions. The village, with a well preserved chateau of Count Castelbarco, lies on the right bank of the Adige.

*Peri* is the first Italian station. The *Monte Baldo* (6942 ft.) on the W. separates the valley of the Adige from the Lago di Garda. Stat. *Ceraino*. The train now enters the celebrated *Chiusa di Verona*, a rocky defile which was defended against the Veronese in 1155 by the German army under Otho of Wittelsbach, in the reign of Frederick Barbarossa. On an eminence on the right bank lies *Rivoli*, which was stormed several times by the French in 1796 and 1797 under Masséna, and afterwards furnished him with his ducal title.

Next stations *Domegliard*, *Pescantina*, and *Parona*. The train crosses the Adige, reaches the Verona and Milan line at *S. Lucia* (p. 169), and then the station of —

164½ M. *Verona*, see p. 182.

## 9. From Vienna to Trieste. Semmering Railway.

371 M. AUSTRIAN S. RAILWAY. Express (1st, in winter 1st and 2nd class) in 14¾ hrs., ordinary trains in 22-23 hrs.; fares 28 fl. 26, 21 fl. 20, 14 fl. 13 kr. (express ½ 5th more). 50 lbs. of luggage free, provided it is at the station at least ½ hr. before the departure of the train; otherwise the whole is liable to be charged for. — Best views generally on the left. For farther particulars, see *Baedeker's S. Germany and Austria*.

The station of the S. Railway is between the Belvedere and the Favorite 'Lines', or boundaries of the city. The train, soon after starting, affords a good survey of Vienna, and the broad plain with its innumerable villas and villages, as far as the hills of the Leitha, to the S. Station *Hetzendorf*, with an imperial chateau. On the hills to the right, near stat. *Brunn*, are several artificial ruins. — Near (10 M.) *Mödling*, the *Brühl*, a picturesque rocky valley, opens on the W., and a branch-line diverges to the E. to the imperial chateau and park of *Laxenburg*. Stations *Guntramsdorf* and *Gumpoldskirchen*, famous for its wines.

17 M. **Baden** (*Hôtel Munsch; Stadt Wien*), with handsome villas, celebrated for its warm mineral springs, the Roman *Thermae Pannonicae*. A beautiful view is obtained from the *Calvarienberg*. A pleasant excursion may be made from Baden to the \**Helenenthal*, commanded by the ruins of *Rauhenstein* and *Rauheneck*, and the handsome château of *Weilburg*, belonging to Archduke Albrecht.

19½ M. **Vöslau** (\**Hôtel Back*), which yields the best Austrian wine, is also frequented as a watering-place (74° Fahr.). The next stations are *Kottingbrunn*, *Leobersdorf* (where the barren *Schneeberg*, 6808 ft., rises on the right), *Felixdorf*, and *Theresienfeld*.

31 M. **Neustadt**, or *Wienerisch-Neustadt* (*Hirsch; Kreuz*), with 20,000 inhab., is an important manufacturing town. On the E. side lies the old ducal *Castle* of the Babenberg family, converted in 1752 into a military academy.

On the right beyond Neustadt the *Schneeberg* is visible almost from base to summit; on the left rises the *Leitha* range. On the hills to the right, in the distance, stands the well-preserved castle of *Sebenstein*, the property of Prince Liechtenstein. Stations *St. Egyden*, *Neunkirchen*, a manufacturing place, *Ternitz*, and *Pötschach*. On the height to the left, near *Gloggnitz*, rises the castle of *Wartenstein*. *Schloss Gloggnitz* on the hill, with its numerous windows, was a Benedictine Abbey down to 1803.

At (47½ M.) *Gloggnitz* (1378 ft.) begins the imposing \***Semmering Railway**, one of the most interesting lines in Europe (best views on the left), and the train now ascends. In the valley lies the green *Schwarzau*, with the imperial paper-factory of *Schleglmühl*. On the left the three-peaked *Semmering*; to the W. in the background the *Raxalp*. The line describes a wide circuit round the N. side of the valley to (55 M.) **Payerbach** (1513 ft.; *Mader; Rail. Restaurant*), and crosses the *Valley of Reichenau* by a viaduct with 13 arches, 300 yds. long. The train now ascends rapidly on the S. slope of the valley (gradient 1:40). Beyond two short tunnels, it skirts the *Gotschakogel*, and beyond two more tunnels reaches stat. *Klamm* (2254 ft.), with a half-ruined castle of Prince Liechtenstein, on a rocky pinnacle, once the key of Styria. Far below runs the old Semmering road; several factories, and the white houses of *Schottwien*, nestling in a narrow gorge, are visible. The train now skirts the *Weinzettelwand* by a long gallery and reaches stat. *Breitenstein* (2555 ft.). Two more tunnels are traversed, and the ravines of the *Kalte Rinne* and the *Untere Adlitzgraben* crossed by lofty viaducts. After three more tunnels the train reaches —

74 M. **Semmering** (2884 ft.; \**Obermayer*), the culminating point of the line. In order to avoid the remaining part (360 ft.) of the ascent, the line penetrates the highest part of the Semmering, the boundary between Austria and Styria, by means of a tunnel nearly 1 M. in length, and then descends rapidly on the N. slope of the peaceful dale of the *Fröschnitz* to stat. *Spital* and (83 M.)

**Mürzzuschlag** (2178 ft.; \**Bräuhaus*; \**Elephant*; *Rail. Restaurant*), an old town on the *Mürz*.

The train now follows the picturesque, pine-clad valley of the *Mürz*, containing numerous forges. Stations *Krieglach* and *Mitterdorf*, the latter with extensive gun-manufactories. On the right rises the château of *Püchl*, with its four towers, and beyond, the ruins of *Lichtenegg*. Stations *Kindberg* and *Kapfenberg* with the castles of these names. Near stat. *Bruck* rises the ancient castle of *Landskron*.

109 M. **Bruck** (1589 ft.; *Bernauer*, at the station; *Adler*) is a small town at the confluence of the *Mürz* and the *Mur*, with an old castle. The train now enters the narrow valley of the *Mur*. 116 M. *Pernegg*, with a large château. Near *Mixnitz* there are interesting stalactite caves. The forges of *Frohnleiten* on the right bank and the castle of *Pfannberg* on the left belong to Prince Lobkowitz. *Schloss Rabenstein* on the right bank is the property of Prince Liechtenstein. The train next passes the *Badelwand*, and skirts the river by means of a rocky gallery of 35 arches, above which runs the high road. Stat. *Peggau* possesses silver and lead mines.

The train crosses the *Mur* and passes stations *Klein-Stübing*, with a handsome château, and *Gratwein*. Near *Judendorf*, on an eminence to the W., rises the picturesque Gothic pilgrimage-church of *Strassengel* with handsome towers. The train now skirts a height, at the foot of which rises the castle of *Gösting*, the property of Count Attems, a favourite resort of the Gratzers, and enters the fertile basin in which Gratz is situated. In the foreground rises the *Schlossberg*.

141 M. **Gratz** (1068 ft.). — HOTELS on the right bank of the *Mur*: \*ELEPHANT; \*OESTERREICHISCHER HOF; \*GOLDNES ROSS; \*FLORIAN; \*GOLDNER LÖWE; DREI RABEN. — On the left bank: \*ERZHERZOG JOHANN; KAISERKRONE.

*Gratz*, the capital of Styria, picturesquely situated on both banks of the *Mur*, which is here crossed by four bridges, with nearly 90,000 inhab., is one of the pleasantest provincial capitals of Austria. The fortifications have recently been removed, and their site is now occupied by the handsome *Ringstrasse* and the *Stadtpark*. — The \**Schlossberg*, which rises about 400 ft. above the river, commands one of the finest \*views in Germany, embracing the course of the *Mur* and the populous valley, enclosed by picturesque mountains. On the S. side of the hill rises the handsome *Clock-Tower*, and in front of the Swiss house the *Statue of Fieldmarshal Baron v. Welden* (d. 1853), in bronze, by Gasser. — The Gothic *Cathedral* dates from 1446, and the copper-clad dome was added in 1663. In front of the *Theatre* rises a bronze *Statue of Emperor Francis I.*, designed by Marchesi.

The train proceeds through the broad valley of the *Mur*, at some distance from the river. Stat. *Puntigam*; on the hills to the right rises the castle of *Premstetten*; on the left, beyond stat.

*Kalsdorf*, the castle of *Weisseneck*. Near *Wildon* the *Kainach* is crossed by a wooden bridge; on the height above rise the ruins of *Ober-Wildon*; to the right are the outskirts of the *Schwanberg Alps*. Stat. *Lebring*. To the right, near *Leibnitz*, is the archiepiscopal chateau of *Seckau*; farther on, the castle of *Labeck* to the left. The train next crosses the *Sulm* by an iron chain-bridge and approaches the *Mur*. 168½ M. *Ehrenhausen*, with the chateau of the same name, and the mausoleum of the princes of *Eggenberg* on a wooded height to the right. 170½ M. *Spielfeld*, with a handsome chateau of Count *Attems*.

The line quits the *Mur* and enters the mountainous district which separates the *Mur* from the *Drau*. On the watershed a tunnel, 700 yds. in length, and near *Pössnitz* a viaduct of equal length are traversed.

182½ M. **Marburg** (895 ft.; \* *Wohlschlager*; *Stadt Wien*; *Stadt Meran*; *Rail. Restaurant*) is an important town with 11,000 inhab., picturesquely situated on the *Drau*, and the junction of the lines to *Villach* and *Franzensfeste*. To the S.W. extends the long vine and forest-clad *Bacher-Gebirge*. A pleasing view is obtained from the train as it crosses the *Drau*; on the right bank are the extensive locomotive works of the S. Railway. Traversing a broad plain, with the slopes of the *Bacher Mts.* on the right, we next reach (189 M.) *Kranichsfeld*, with an old chateau, and (193 M.) *Pragerhof*, the junction for the line to *Kanisza* and *Ofen*. The train now enters a region of lower hills, and traverses two tunnels. 204 M. *Pölttschach*, at the foot of the *Botsch* (3230 ft.), on the N. slope of which are situated the picturesque ruins of the Carthusian monastery of *Seitz*.

The German language is now replaced by a Slavonic or *Wend* dialect. The train winds through a sparsely peopled district. The valleys are generally narrow and picturesque, the mountains richly wooded, with occasional vineyards and fields of maize. Several small stations and foundries are passed, and an extensive view of the *Sannthal*, a populous and undulating plain, bounded by the *Sutzbach Alps*, is at length suddenly disclosed.

224½ M. **Cilli** (787 ft.; *Erzherzog Johann*; *Kaiserkrone*), an ancient town of some importance, founded by Emp. *Claudius (Claudia Cellaia)*, contains several Roman reliefs and memorial slabs on the town-walls. On a wooded height in the vicinity stands the ruined castle of *Obercilli*; on the slope to the N.E. lies the Lazarist monastery of *St. Joseph*, with its two towers.

The train crosses the green *Sann*, and enters the narrow and wooded valley of that stream. The most picturesque part of the whole line is between *Cilli* and *Sava*. Stations *Markt Tüffer*, with a ruined castle, and (229 M.) *Römerbad* (which memorial stones prove to have been known to the Romans), also called *Teplitza* (i. e. 'warm bath'), a beautifully situated watering-place with attractive grounds and promenades.

241 M. *Steinbrück* (\*Rail. Restaurant; 25 min. allowed for express passengers to dine), a thriving village on the *Save*, or *Sau*, which here unites with the *Sann*, is the junction for the line to Agram and Karlstadt. The train now runs for 1 hr. in the narrow valley of the *Save*, enclosed by lofty limestone cliffs, which often barely afford space for the river and railway. Stations *Hrastnig* (with valuable coal-mines), *Trifail*, *Sagor* (the first place in Carniola), and *Sava*.

The valley now expands. At *Littai* the *Save* is crossed. Scenery still very picturesque. Stations *Kressnitz*, *Laase*. At the influx of the *Laibach* into the *Save*, the line quits the latter and enters the valley of the former. The lofty mountain-range to the N.W. is that of the *Julian* or *Carnian Alps*. 274 M. *Salloch*.

279 M. **Laibach** (994 ft.; *Stadt Wien*; *Elephant*; *Europa*; \*Rail. Restaurant), Slav. *Ljubljana*, on the *Laibach*, the capital of Carniola, with 23,000 inhab., is situated in an extensive plain enclosed by mountains of various heights. An old *Castle*, now used as a prison, rises above the town. The *Cathedral*, an edifice in the Italian style, is decorated with stucco and numerous frescoes of the 18th cent.

The line now traverses the marshy *Laibacher Moos* by means of an embankment,  $1\frac{3}{4}$  M. in length, and crosses the *Laibach*, which becomes navigable here, although hardly 3 M. below the point where it issues from the rocks near Oberlaibach. Near stat. *Franzdorf* the line is carried past *Oberlaibach* by a viaduct 625 yds. long, 120 ft. high in the centre, and supported by a double row of arches (25 in number), and enters a more mountainous district with beautiful pine-forest. — 301 $\frac{1}{2}$  M. *Loitsch* (1555 ft.; Post or Stadt Trieste). About 15 M. to the N.W. of Loitsch are the rich quicksilver mines of *Idria*. — 308 M. *Rakek*,  $3\frac{1}{2}$  M. to the S.E. of which is the *Zirknitzer See*, enclosed by lofty mountains. Then (319 M.) **Adelsberg** (1798 ft.; *Adelsberger Hof*; *Krone*), Slav. *Postójna*.


The celebrated \*STALACTITE CAVERNS, known in the middle ages and accidentally re-discovered in 1816, are  $\frac{3}{4}$  M. W. of Adelsberg. All the fees are fixed by tariff, and are somewhat high for a single visitor (from 2 fl. 30 kr. to 21 fl., according to the illumination), but less when shared by a party. Brilliant illumination is necessary in order to produce a satisfactory effect. A visit to the grotto occupies  $2\frac{1}{2}$ -3 hrs., or if prolonged to the Belvedere 4 hrs. Temperature 48° Fahr. Entrance 1 M. from the station. Fuller particulars, see *Baedeker's Austria*.

The train now traverses a dreary, inhospitable plain, strewn with blocks of limestone, called the **Karst** (Ital. *Carso*, Slav. *Gabrek*), extending from Fiume to Gorizia (p. 247). The train (2 hrs. by express from Adelsberg to Trieste) threads its way through this wilderness of stones, crosses the *Poik* at stat. *Prestranek*, and beyond (326 M.) *St. Peter* (branch-line to *Fiume*) passes through six tunnels. Stations *Lesece*, *Divazza* ( $2\frac{1}{2}$  M. to the S.E. are the grottoes of *S. Canzian*), *Sessana* (1627 ft.). The train descends to *Prosecco* and *Nabresina* (Hôtel Daniel), where the line to Venice by Udine



# TRIESTE.



1:16700



- 1 *Accademia reale di Musica con Biblioteca civica e Museo Ferdinando Massimo* G5  
 2 *Arco di Riccardo* F4  
 3 *Arenale del Lloyd austriaco* H6  
 4 *Borsa* E4  
 5 *Canale grande* D34  
 6 *Cabinetto letterario di Minerva con propria biblioteca* E4

## Chiese

- 7 *S. Antonio nuovo* D3  
 8 *Cattedrale S. Giusto* F3  
 9 *S. Maria Maggiore* F4  
 10 *S. Vito dei Greci* E4  
 11 *Municipio* E4  
 12 *Duomo nuovo* CD4  
 13 *Edificio della Sanità* F5  
 14 *Lazzaretto nuovo* A6  
 15 *occhio* H6  
 16 *Museo municipale di antichità e Monumento Winkelmann* F3  
 17 *Ospedale civile* D1  
 18 *Praterhof* D4  
 19 *Porchera* E5  
 20 *Stazione della Strada ferrata* B5



## Alberghi:

- a. *Hotel de Ville* E. 4  
 b. *Locanda grande* E. 4  
 c. *Europa* C. 3  
 d. *de France* E. 4  
 e. *Daniel* E. 4

21. *Finca*  
 22. *Morone*  
 23. *Andromeda*  
 24. *Armenia*  
 25. *Argentea*  
 26. *Flora d'Italia*  
 27. *Italia*  
 28. *Villa Virginia*







diverges (R. 37), and affords a magnificent \*view of the blue Adriatic, Trieste, and the Istrian coast (views to the right). The slopes are planted with olives, fig-trees, and trellised vines. *Grignano*, the last station, is not above 1½ M. below Prosecco in a straight direction. On the *Punta Grignana*, which here projects into the sea, is situated the handsome chateau of *Miramar* (p. 57; station). Before reaching (371 M.) Trieste the train enters a tunnel, 906 ft. in length, which terminates at the station.

**Trieste.** — **Hotels.** \*HÔTEL DE LA VILLE (Pl. a), R. 1½-5 fl.; \*HÔTEL DELORME, opposite the Exchange, R. 2 fl., B. 60 kr., D. 2 fl.; AQUILA NERA, with a good restaurant (beer); EUROPA, nearest the station; ALBERGO DANIEL (Pl. E), good restaurant on the ground-floor; LOCANDA GRANDE, in the Pescheria; HÔTEL GARNI, Piazza Grande 5, R. 1 fl. 75, with baths.

**Cafés.** *Hôtel de la Ville* (see above); *Degli Specchi*, Piazza Grande; *All' Europa Felice*, in the Pescheria; *Stella Polare*; *Caffè Adriatico*, near the post-office, and others.

**Restaurants.** *Alla Borsa Vecchia*; *Berger*, in the old town below the castle, good view from the garden; *Alte und Neue Bierhalle*, near the Boschetto, with gardens; beer-garden in the *Boschetto* (p. 57), and many others with gardens in which concerts are frequently given.

**Osterie** in the Italian style: *All' Adriatico*, Via di Vienna; *Ai Due Tamburini*, adjoining the *Caffè Adriatico*; *Anderno de Piero*, in the Piazza Gadola.

**Fiacres.** From the station to the town, one-horse 60 kr., two-horse 1½ fl.; from the town to the station 40 kr. or 1 fl.; drive in the town, ¼ hr. 30 or 45 kr., ½ hr. 50 or 80, ¾ hr. 75 kr. or 1 fl. 10 kr., 1 hr. 1 fl. or 1 fl. 80 kr., each additional ¼ hr. 20 or 30 kr., at night 5 kr. more per ¼ hr.; luggage 15 kr. per box. — *Omnibus* from the station to all the hotels 20, at night 30 kr. — *Porter's* charge, up to 100 lbs. 20 kr.

**Steamboats** to Muggia, Capodistria, and Pirano, several times daily; small vessels to Parenzo, Rovigno, and Pola, daily. Steamboats of the Austrian Lloyd to Venice (see p. 248) three times weekly, viâ Istria and Dalmatia; to Fiume twice weekly, etc.

**Telegraph Office**, Via della Dogana, No. 926.

**Baths.** *Oesterreicher*, near the Artillery Arsenal; *Hôtel de la Ville*; warm salt and fresh-water baths at both. Turkish baths at the *Bagni Russi*, near the public gardens. — Sea-baths at the *Bagno Maria*, opposite the *Hôtel de la Ville*; *Bagno Boscaglia*, to the right of the last; *Military Swimming Bath*, below the lighthouse, to the left. Ferry to the baths 3 kr. each way. — *Boats* 1-1½ fl. per hour.

**Public Gardens.** One in the Piazza Lipsia; another in the Piazza Grande; also the pleasant *Giardino Pubblico* by the Boschetto (Café).

**Theatres.** *Teatro Grande* (Pl. 21), opposite the Tergesteo; *Teatro Filodrammatico* (Pl. 23); *Armonia* (Pl. 24). The *Teatro Mauroner* was burnt down in 1876. Italian plays and operas are usually performed at all these.

**Railway Station**, a handsome structure, 1 M. from the Exchange, near the quay.

**English Church Service** performed by a resident chaplain.

*Trieste*, the *Tergeste* of the Romans, situated at the N.E. extremity of the Adriatic, is the capital of Illyria and the most important seaport of Austria (pop. 70,000, incl. villages 123,000). It was constituted a free harbour by Emp. Charles VI. in 1719, and may be termed the Hamburg of S. Germany. Every European nation has a consul here. The population is very heterogeneous, but the Italian element predominates in the city.

The *Harbour* is the centre of business. It is entered and quitted

by 15,000 vessels annually, of an aggregate burden of one million tons. The quays have been greatly extended within the last few years to meet the increasing requirements of the shipping trade. A lofty *Lighthouse* rises on the S.W. Molo.

The *New Town*, or *Theresienstadt*, adjoining the harbour, is laid out in broad, well-paved streets with handsome houses, and is intersected by the *Canal Grande* (Pl. 5; D, 3, 4), which enables vessels to discharge their cargoes close to the warehouses. At the end of the Canal is the church of *S. Antonio Nuovo* (Pl. 7; D, 3), built in 1830 by Nobile in the Greek style.

Adjacent to the Hôtel de la Ville towards the S. is the *Greek Church* (*S. Niccolò dei Greci*, Pl. 10; E, 4; divine service 6-8.30 a.m. and 5-7 p.m.), with its two green towers, sumptuously fitted up. To the left of the Hôtel de la Ville is the *Palazzo Carciotti*, with a green dome, and in the vicinity, near the Ponte Rosso, a new *Servian Church*.

A few paces farther, in a S.E. direction, is the *\*Tergesteo* (Pl. 25; E, 4), an extensive pile of buildings, on the outside of which are shops, and in the interior a glass gallery in the form of a cross, where the *Exchange* (12-2 o'clock) is situated. The *Reading Room* of the exchange is well stocked with newspapers (visitors admitted). The principal part of the edifice is occupied by the offices of the '*Austrian Lloyd*', a steamboat-company established in 1833.

In the Piazza della Borsa (Pl. E, 4), where the old Exchange is situated, stands a Neptune group in marble, and a *Statue of Leopold I.*, erected in 1660. — In the Piazza Grande is the new *Municipio* (Pl. 11; E, 4), containing the handsome hall of the provincial diet.

The *Corso*, the principal street of Trieste, together with the two piazzas just mentioned, separate the new town from the old. The latter, nestling round the hill on which the castle rises, consists of narrow and steep streets, not passable for carriages. To the left on the route to the cathedral and the castle is situated the *Jesuits' Church* (*S. Maria Maggiore*, Pl. 9; F, 4), containing a large modern fresco by Sante. To the W., a few paces higher up, is the *Piazzetta di Riccardo*, named after Richard Cœur de Lion, who is said to have been imprisoned here after his return from Palestine. The *Arco di Riccardo* (Pl. 2) is believed by some to be a Roman triumphal arch, but probably belonged to an aqueduct.

The *\*Cattedrale S. Giusto* (Pl. 8; F, 3) consisted originally of a basilica, a baptistery, and a small Byzantine church, dating from the 6th cent., which in the 14th cent. were united so as to form a whole. The tower contains Roman columns, and six Roman tombstones (busts in relief) with inscriptions are immured in the portal. The façade is adorned with three busts of bishops in bronze. The altar-niches of the interior contain two ancient mosaics, representing Christ and Mary. The Apostles in the left bay,

under the Madonna, are Byzantine (6th cent.). Some of the capitals are antique, others Romanesque.

A disused burial-ground adjoining the church is now an open-air *Museum of Roman Antiquities* (Pl. 16) of no great value, those on the upper terrace having been found at Trieste, those on the lower at Aquileia (key kept by the sacristan of the cathedral, 50 kr.). Winckelmann, the eminent German archæologist, who was robbed and murdered by an Italian at the Locanda Grande in 1768, is interred here, and a monument was erected to him in 1832.

*Fouché, Duc d'Otranto*, once the powerful minister of police of Napoleon I., died at Trieste in 1820, and was interred on the *Terrace* in front of the church. Fine view thence of the town and sea; still more extensive from the height on which the *Castle* stands.

On the slope of the hill opposite the Cathedral rises the *Armenian Catholic Church*, a Byzantine edifice. — The new *Protestant Church*, in the Piazza Carradori, was completed in 1874.

In the Piazza Lipsia is the *Nautical Academy* (Pl. 1; G, 5), containing the *Municipal Museum*, the chief attraction of which is a complete collection of the fauna of the Adriatic. In the same piazza is the sumptuously furnished *Palazzo Revoltella* (visitors admitted). — The Piazza Giuseppe, which opens towards the Molo of that name (Pl. F, G, 5, 6), is embellished with a \**Monument to Emperor Maximilian of Mexico* (d. 1867), in bronze, designed by Schilling, and erected in 1875. The unfortunate prince, who was a contre-admiral in the Austrian navy, generally resided at Trieste before he undertook his ill-starred expedition to Mexico.

A long avenue, skirting the coast and commanding a succession of beautiful views, leads on the E. side of the town, past the *Villa Murat*, the *Lloyd Arsenal*, and the *Gas-Works*, to *Servola* (comp. Plan, I, 7-4).

The extensive *Wharves of the Lloyd Co.*, opposite Servola (4 M.), may be visited daily, except holidays, Saturdays, and between 11 and 1 o'clock (guide  $\frac{1}{2}$  - 1 fl.).

On the road to *Zaule*, famous for its oyster-beds, are the handsome *Cemeteries*.

Another pleasant walk is along the *Acquedotto* through a pretty valley to the *Boschetto*, a favourite resort (large brewery). From the *Boschetto* a shady road leads to the *Villa Ferdinandiana* (restaurant), adjoining which is the *Villa Revoltella*, with park and chapel, commanding a charming view of the town, the sea, and the coast.

A very pleasant excursion (railway station, see p. 55; carr. 3 fl., boat 4 fl.) may be made to the château of \**Mirammar*, formerly the property of Emp. Maximilian of Mexico (see above), charmingly situated to the N.W. near *Grignano*, and commanding a fine view of Trieste, the sea, and the coast. The park is open to the public.

daily. The sumptuously furnished \*Château is shown to visitors on application to the steward. — *Barcola* (restaurant) is a favourite resort, halfway between Trieste and the château.

Excursions. To *Opitschina* (3 M.; Hôtel all' Obelisco), commanding a beautiful view of the town and the sea; *Servola* (see above); *S. Giovanni*; the grotto of *Corniale*, 9 M. to the E.; to *Lipizza* (imperial stables), etc. — A very interesting excursion, occupying one day (starting early in the morning), is by steamer (p. 55) to *Muggia*; over the hill on foot (beautiful view from the top) to *Oltre* (1 hr.), thence by boat (15 kr.) to **Capo d'Istria** (*Città di Trieste*; *Radetzky*; Caffè in the principal Piazza). The town itself, situated on an island, with 7500 inhab., is the *Justinopolis* of the Romans, and is connected with the mainland by a stone embankment. The chief objects of interest are the *Cathedral*, the *Palazzo Pubblico*, occupying the site of a temple of Cybele, and the extensive salt-works. We now proceed by the road on the shore, passing *Semedella*, to (3 M.) *Isola* (good Refosco wine), and (6 M. farther) *Pirano*, and return to Trieste by steamer in the evening. — About 2 M. from Pirano lies the sea-bathing place of *S. Lorenzo*, established in 1864, a handsome building in an extensive park.

From Trieste to *Venice*, see p. 245; to *Pola*, *Fiume*, and *Dalmatia*, see *Baedeker's S. Germany and Austria*.

## II. Piedmont.

This district 'at the foot of the mountains', enclosed on three sides by the Alps and Apennines, and separated from Lombardy by the Ticino, embraces, according to the present division, the provinces of *Turin*, *Novara*, *Cuneo*, and *Alessandria*, with 2,899,564 inhab., and an area of about 11,400 sq. M. It consists of lowlands flanking the banks of the Po and its tributaries, which yield rice and maize, and of highlands where excellent wine and silk are produced, and lastly of a bleaker mountain region of forests and pastures. The earliest INHABITANTS were Celtic and Ligurian tribes, who were but slowly influenced by Roman culture; and it was not till the reign of Augustus that the subjugation of the higher valleys was completed. The DIALECT of the people still retains traces of their ancient affinity with the French; thus, *pieuve*, instead of the Italian *piovere*, *om* for *uomo*, *coeur* for *cuore*, *sità* for *città*, *rason* for *ragione*, *plassa* for *piazza*. This patois is universally spoken, even by the higher classes, and is unintelligible to strangers. Throughout Piedmont the traveller will find that French will carry him quite as far as Italian.

The HISTORY of the country is closely interwoven with that of its dynasty. The *House of Savoy* (or *Casa Sabauda*), a family of German origin, professing even to trace their descent from the Saxon Duke Wittekind, the opponent of Charlemagne, first became conspicuous among the nobles of Upper Burgundy about the year 1000. *Humber I.* (d. about 1050) is generally regarded as the founder of the dynasty. In 1101 his descendants were created imperial counts of Savoy by Henry IV., and by judiciously espousing the cause of the pope and the emperor alternately, they gradually succeeded in extending their supremacy over Turin, Aosta, Susa, Ivrea, and Nice. In consequence of a law passed by *Amadeus V., the Great*, in 1367, which settled the succession on the male line in the order of primogeniture, and constituted Chambéry the seat of government, the subdivisions of the country were at length united. In 1416, during the reign of *Amadeus VIII.*, the counts became Dukes of Savoy. Situated between the two great mediæval powers of France on one side, and Austria and Spain on the other, the princes of Savoy frequently changed sides, and although sometimes overtaken by terrible disasters, they contrived to maintain, and even to extend their territory. At one period the greater part of the Duchy was annexed to France, but *Emmanuel Philibert* ('Testa di Ferro', 1553-80) restored it to its original extent, being, as regards internal organisation also, its second founder. Under his son *Charles Emmanuel I.* (1580-1630) the Duchy again became dependent on France. From the sons of this prince is descended the elder branch of the family, which became extinct in 1831, and the younger Carignano line, which succeeded to the throne in the person of Carlo Alberto. The following dukes were *Vittorio Amadeo I.* (1630-37), *Francesco Giacinto* (1637-38), *Carlo Emanuele II.* (1638-75), and *Vittorio Amadeo II.* (1675-1730). The last of these having boldly allied himself with Austria during the Spanish War of Succession, thus managed to throw off the French suzerainty (1703); he obtained Sicily as his reward, which island, however, he was afterwards obliged to exchange for Sardinia (1720), and in 1713 assumed the title of KING, which was subsequently coupled with the name of the latter island. His successors were *Carlo Emanuele III.* (1730-73) and *Vittorio Amadeo III.* (1773-96). After the battle of Turin (p. 71) the Piedmontese princes directed their attention to Prussia, which served as a model for the organisation of their kingdom. In both countries the

military and feudal element preponderated, and both were obliged to succumb to the new powers evolved by the French revolution. *Carlo Emanuele IV.* (1796-1802) was deprived of all his continental possessions by the French in 1798, and restricted to the island of Sardinia, which was protected by the English fleet. *Vittorio Emanuele I.* (1802-21) was at length reinstated in his dominions with the addition of Genoa by the Congress of Vienna. The Napoleonic period had swept away the feudal institutions of Piedmont, and had bequeathed in their stead many of the benefits of modern legislation, and high military renown. It is therefore intelligible that the clerical reaction, which set in with the king's return, gave rise to an insurrection which caused the king to abdicate, and which had to be quelled by Austrian troops. His brother *Carlo Felice* (1821-31) adhered faithfully to Jesuitical principles, and lived on the whole in accordance with his motto, 'Non sono re per essere seccato'. With him the older line of the House of Savoy became extinct, and was succeeded by the collateral line of Carignano (p. 59; 27th April, 1831). *Carlo Alberto* (b. 1798), who had been educated at a French military school, and had headed the insurrection of 1821, was protected by France and Russia against the attempts of Austria to deprive him of his claims to the throne. His own experiences, and the force of circumstances, rendered him an implacable enemy of Austria. With him began the national development of Piedmont, although his efforts were not always consistent. The liberals called him the 'Re Tentenna' (the vacillating), while in 1843 he himself described his position as being 'between the daggers of the Carbonari and the chocolate of the Jesuits'. On 6th Jan. 1848 *Count Cavour* made the first public demand for the establishment of a constitution, and on the 7th Feb. the king, half in despair, yielded to the popular desires. The insurrection in Lombardy at length induced him to become the champion of national independence, and to give vent to his old enmity against Austria (23rd March), but one year later his career terminated with his defeat at Novara (23rd March, 1849). He then abdicated and retired to Oporto, where he died in a few months (26th July). For his son *Vittorio Emanuele II.* (b. 14th March, 1820) it was reserved finally to give effect to the national wishes of Italy.


## 10. Turin, Ital. *Torino.*

**Arrival.** The principal railway-station at Turin is the *Stazione Centrale*, or *Porta Nuova* (Pl. G, 7, 8), in the Piazza Carlo Felice, at the end of the Via Roma, a handsome edifice with waiting-rooms adorned with frescoes, and the terminus of all the lines. — Travellers to Milan may take the train at the *Stazione Porta Susa* (Pl. C, 5, 6), at the end of the Via della Cernaia, the first stopping place of all the trains of the Novara-Milan line (omnibuses and carriages meet every train), or at the *Stazione Succursale*, on the left bank of the Dora. — Station of the branch line to Rivoli in the Piazza dello Statuto (Pl. C, 4); of that to *Cirié* between the Piazza Emanuele Filiberto and the Pontc Mosca (Pl. F, 1).

**Hotels.** EUROPA (Pl. a), Piazza Castello 19; GRAND HÔTEL DE TURIN (Pl. d), opposite the central station; HÔTEL DE LA LIGURIE (Pl. k), Via Carlo Alberto; HÔTEL FEDER (Pl. e), Via S. Francesco di Paola 8; HÔTEL TROMBETTA (Pl. c), Via Roma 29, Piazza S. Carlo; GRAND HÔTEL D'ANGLETERRE (Pl. b), Via Roma 31, and Via Cavour 2. All these are of the first class, with similar charges: R. from 3, B. 1½-2, D. generally at 5 o'clock 4-5, L. 1, A. 1, omnibus 1½ fr. — The following are more in the Italian style, and have trattorie connected with them: ALBERGO CENTRALE (Pl. h), Via delle Finanze; BONNE FEMME (Pl. f), Via Barharoux 1; HÔTEL SWISS, Via Sacchi 2, near the central station; these three well spoken of. CACCIA REALE (Pl. g), Piazza Castello 18; HÔTEL DE FRANCE ET DE LA CONCORDE, Via di Po 20, R. 2, A. 1½; TRE CORONE (Pl. k), Via S. Tommaso, R. 2, D. 3, L. 1½ fr., B. 60 c.; DOGANA VECCHIA (Pl. i), Via Corte d'Appello 4, near the Palazzo di Città. — The *Grisini*, a kind of bread in long,







# Turin Torino

## Chiese.

- |                |                     |      |
|----------------|---------------------|------|
| 1              | Basilica Magistrale | F 3. |
| 2              | S. Carlo            | G 6. |
| 3              | Cattedrale          | E 3. |
| 4              | Consolata           | E 3. |
| 5              | Corpus Domini       | F 4. |
| 6              | Francoese di Sales  | F 4. |
| 7              | Madre di Dio        | M 5. |
| 8              | Tempio Valdese      | H 8. |
| 8 <sup>a</sup> | Sinagoga            | I 4. |

- |    |                      |      |
|----|----------------------|------|
| 9  | Accademia Belle Arti | I 4. |
| 10 | Accademia Scienze    | G 5. |
| 11 | Armeria Reale        | G 3. |
| 12 | Arsenale             | F 6. |
| 13 | Borsa di Commercio   | H 6. |
| 14 | Casa Carour          | G 6. |

## Monumenti.

- |      |                      |      |
|------|----------------------|------|
| 15   | All' Esercito Sardo  | G 4. |
| 16   | Andreo               | F 4. |
| 17   | Carour               | I 5. |
| 18   | Carlo Alberto        | H 2. |
| 19   | Emanuele Filiberto   | G 5. |
| 20   | Gioberti (Piazzoni)  | G 4. |
| 21   | Lagrange (Luigi)     | G 7. |
| 22   | Palazzo              | G 7. |
| 23   | Siccardi             | E 3. |
| 24   | Monte de' Cappuccini | M 6. |
| 25   | Museo civico         | I 3. |
| 25 a | Museo industriale    | H 6. |

## Palazzi principali


- |    |                      |        |
|----|----------------------|--------|
| 26 | Casignano            | G H 5. |
| 27 | de' Pitta            | F 4.   |
| 28 | del Duca di Genova   | G 3.   |
| 29 | Madama (Pinacoteca)  | G 4.   |
| 30 | de' Magistrati Supr. | E 3.   |
| 31 | de' Riti             | O 3.   |
| 32 | delle Torri          | F 3.   |
| 33 | Posta delle Lettere  | H 5.   |

## Teatri

- |    |                            |        |
|----|----------------------------|--------|
| 34 | d'Ingegneri                | I 5.   |
| 35 | Carignano                  | G 4 5. |
| 36 | Royal                      | H 4.   |
| 37 | Nazionale                  | H 7.   |
| 38 | Veneto (Museo Capitolario) | H 1.   |

## Alberghi

- |      |                   |      |
|------|-------------------|------|
| G 4. | f. Bonne Fosse    | G 4. |
| G 6. | g. Caccia Reale   | G 4. |
| H 4. | h. Centrale       | G 4. |
| G 8. | i. Dogana vecchia | F 3. |
| G 6. | k. Liguria        | H 6. |



1:20 000

Wagner & Debes, Leipzig



thin, and crisp sticks, form a speciality of the place. Best wines: *Barbera*, *Barolo*, *Nebbiolo*, and *Grignolino*.

**Restaurants.** *Cambio*, Piazza Carignano 2, much frequented in the morning, best Italian wines; *Paris*, Via di Po 21; *Biffo*, Via Roma 13; *Trattoria di Piazza S. Carlo*, D. 3 fr., in a room on the upper floor; *Meridiana*, Via S. Teresa 7; *Due Indie*, Via Guasco 4; in the two latter Italian, in the others French cuisine. Good Restaurant also at the *Stazione Centrale*. — Good *Piedmontese Wine* (Barbera and Barolo) at the *Trattoria d'Oriente*, Via Lagrange, and at the *Coccania*, Via Dora Grossa.

**Cafés.** *Café de Paris*, Via di Po 21, 1st floor; *S. Carlo*, handsomely fitted up, Piazza S. Carlo 2; *Nazionale*, Via di Po 20; *Madera*, Via Lagrange 10; *Romano*, by the Galleria dell'Industria Subalpina, in the Piazza Castello, with an extensive 'Birreria' on the sunk floor; *Caffè della Borsa*, Via Roma 25; *Liguria*, Corso del Re, near the station. — Iccs everywhere, *sorbetti* and *pezzi duri* (the former half the latter quite frozen), comp. Introd. IX. A favourite morning beverage is a mixture of coffee, milk, and chocolate, 'un *bicchierino*' 20 c.; a cup of coffee 20 c., in summer always with iced water. — **Confectioner.** *Bass*, Piazza Castello, S. side. — **Beer.** At the above mentioned *Caffè Romano*; *Lump*, at the corner of Via dell'Arsenale and Via Alfieri; in the *Birreria*, Via di Dora Grossa 5.

**Cabs**, or *Cittadine*, stand in most of the piazzas and in the streets leading out of the Via di Po. Per drive (*corsa*) 1 fr., at night (12-6 a. m.) 1 fr. 20 c.; first  $\frac{1}{2}$  hr. 1 fr., first hour (*ora*) 1 fr. 50 c., each following  $\frac{1}{2}$  hr. 75 c., at night  $\frac{1}{2}$  fr. and 2 fr.; each trunk 20 c. — Two-horse carriage 50 c. more in each case. — *Omnibuses* run frequently from the Piazza Castello to each of the four gates, and to the Via della Rocca, fare 10 c. — *Tramway* from the Piazza Castello by the Via Lagrange to the Barriera di Nizza, 10 c.

**Consuls.** *British*, Via di S. Filippo 20. *American*, Via de' Fiori 19.

**Post Office** (*Posta Lettere*), Via d'Angennes 10. **Telegraph Office**, at the same place.

**Booksellers.** *Loescher*, Via di Po 19, with circulating library of English, French, German, and other books; *Beuf*, Via dell'Accademia delle Scienze 2. — *Fine Arts Warehouse*: Dom. Cerruti, in the Galleria Subalpina (p. 62).

**Military Music** in front of the Royal Palace (Pl. 31) daily, in winter at 4, in summer at 5 o'clock; on Sundays 12-2, in summer in the Giardino Reale, in winter in the Piazza Vittorio Emanuele; in the evening in the Piazza d'Armi daily, in summer during the Corso. — The chief promenades are the avenues of the Piazza d'Armi.

**Baths**, Via di Po 51, and Via della Consolata. — *Swimming Bath* (scuola di nuoto) above the old bridge over the Po (Pl. L, 5).

**Theatres.** *Teatro Regio* (P. 36), in the Piazza Castello, with seats for 2500, generally open during the Carnival only; *Carignano* (Pl. 35), in the Piazza of that name, open the greater part of the year; *D'Angennes* (Pl. 34); *Nazionale*, for operas, Via Borgo Nuovo (these two generally closed); *Rossini*, Via di Po 24; *Scribe*, Via Zecca 29, French; *Gerbino*, corner of Via Plana and Via del Soccorso, Italian comedies; *Vittorio Emanuele*, Via Rossini 11, a circus, etc.

**English Church Service** performed in a chapel at the back of the Tempio Valdese (Pl. 8).

**Principal Attractions**: Armoury (p. 63), Picture Gallery (p. 65) and Museum of Antiquities (p. 65), monuments in the cathedral (p. 67), view from the Capuchin monastery (p. 71).

*Turin* (820 ft.), the Roman *Augusta Taurinorum*, founded by the Taurini, a Ligurian tribe, destroyed by Hannibal B.C. 218, and subsequently re-erected, was the capital of the County of Piedmont in the middle ages, and in 1418 became subject to the Dukes of Savoy, who frequently resided here. From 1859 to 1865 it was the capital of Italy and residence of the king. *Turin*.

the seat of a university, and of a military academy, is situated in an extensive plain on the *Po*, which receives the waters of the *Dora Riparia* below the city. The plain of the *Po* is bounded on the W. by the *Graian* and *Cottian Alps*, and on the E. by a range of hills rising on the right bank, opposite the city (hill of the *Capuchins*, p. 71; *Superga*, p. 71). Turin has always been the focus of the national struggles for unity, and by the industry and perseverance of its citizens has recovered from the severe losses consequent on the removal of the court. The population in 1871, including surrounding villages, was 212,644, the town itself 192,443 (in 1377, 4,200; in 1631, 36,447; in 1799, 80,752; and in 1848, 130,849).

Turin is conspicuous among the principal cities of Italy for the regularity of its construction. Its plan presents rectangular blocks of houses (*Isote*), long, broad, straight streets (formerly called *Contrade*, now *Vie*), wide squares, and numerous gardens. Its history explains this. The plan of the old town, with slight variations, is ascertained to be the same as that of the colony founded by the Emperor Augustus. It formed a rectangle of 1370 ft. in length, and 2210 ft. in breadth, and is now intersected by the *Via di Dora Grossa*, which runs between the *Piazza Castello* and the *Via della Consolata*. It had four principal gates, of which the *Porta Palatina*, to the N. (in the *Palazzo delle Torri*, Pl. 32) still exists. The whole town was comprised within this circumference during the middle ages, until in the 17th cent., under the princes of Savoy, a systematic extension of the city was begun in accordance with the original plan. The fortifications constructed by Francis I. in 1536, and finally the siege of 1706 cleared away most of the old buildings, and gave the town its present appearance. The fortifications were demolished by the French when in possession of the city and environs in 1801, and the citadel had to give place to the railway in 1857.

The spacious **PIAZZA CASTELLO** (Pl. G, 4), with the Royal Palace, forms the centre of the town. From this point the busiest streets diverge: — the *Via Roma* between the *Piazza Carlo Felice* and the *Piazza Castello*, the *Via di Dora Grossa* between the *Piazza Castello* and the *Piazza dello Statuto*, and the broad and handsome **VIA DI PO**, leading to the bridge over the *Po*, and flanked by arcades (*Portici*), containing shops, the handsomest of which are near the *Piazza Castello* (those in the direction of the *Po*, towards the *Piazza Vittorio Emanuele*, being inferior). These arcades present a busy and brilliant scene in the evening, when lighted by gas. The University in the *Via di Po*, see p. 69. — In the S. E. angle of the *Piazza Castello* is the new *Galleria dell' Industria Subalpina*, containing cafés, a large birreria, and concert rooms, which is worthy of a visit, though inferior to the arcade at Milan. The other end of the arcade is in the *Piazza Carlo Alberto* (p. 64).

The **Palazzo Madama** (Pl. 29; G, 4), the ancient castle, a lofty and cumbrous pile in the centre of the *Piazza Castello*, is the only mediæval structure of which Turin boasts, and was erected by William of Monferrat, when master of the town in the latter half of the 13th cent. It owes its present name to the mother of King Victor Amadeus II., who as Dowager Duchess (*'Madama Reale'*)

occupied the building, and embellished it in 1718 by the addition of a handsome double flight of steps and the façade with marble columns on the W. side. The two original towers on the E. side are still standing; two others on the W. side, one of which is intended for an observatory, are concealed by the façade. Down to 1865 the Palazzo Madama was the seat of the Italian senate, and it now contains several institutions. — In front of the Palace stands a *Monument to the Sardinian Army* (Pl. 15) by *Vinc. Vela*, erected by the Milanese in 1859, and representing a warrior in white marble defending a banner with his sword. In relief, Victor Emmanuel on horseback at the head of his troops.

On the N. side of the Piazza Castello is situated the **Palazzo Reale**, or *Royal Palace* (Pl. 31; G, 3), erected about the middle of the 17th cent., a plain edifice of brick, sumptuously fitted up in the interior. The palace-yard is separated from the Piazza by a gate, the pillars of which are decorated with two groups in bronze of Castor and Pollux, designed by *Abbondio Sangiorgio* in 1842. To the left in the hall of the palace, to which the public are admitted, in a niche near the staircase, is the '*Cavallo di Marmo*', an equestrian statue of Duke Victor Amadeus I. (d. 1637); the statue is of bronze, the horse in marble; below the latter are two slaves. The steps have recently been magnificently embellished; among the statues those of Emmanuel Philibert, by *Varni*, and Carlo Alberto, by *Vela*, deserve special notice. The royal apartments are generally accessible in the absence of the king.

The long S.E. wing of the edifice (*Galleria Beaumont*) contains the \***ROYAL ARMOURY** (*Armeria Reale*; Pl. 11; G, 3; entered from the arcade, first door to the right when approached from the palace), opposite and to the N.E. of the Palazzo Madama. It is open to the public on Sundays, 11-3 o'clock, and daily at the same hours by tickets (obtained between 11 and 3 o'clock at the office of the secretary of the Armoury, on the ground-floor). The collection is very choice and in admirable order (custodian  $\frac{1}{2}$ -1 fr.).

In the centre of ROOM I. is a handsome modern marble group by *Finelli*, representing St. Michael with raised sword keeping down Satan in fetters, presented in 1844 by '*M. Cristina di Borbone vedova del Re Carlo Felice*'. By the pedestal are two French regimental eagles and the sword worn by Napoleon I. at the battle of Marengo. Numerous models of modern weapons; in a cabinet near the window, Prussian helmets; then Japanese and Indian weapons and armour. A cabinet on the right contains gifts presented to the king by Italian towns, a sword presented by Rome in 1859, a gilded wreath of laurel by Turin 1860, and a sword in 1865, on the occasion of the Dante Festival; in the centre, the favourite horse of Charles Albert; Piedmontese flags from the wars of 1848-49 over the cabinets. The long HALL contains, on the right, a gigantic suit of armour worn at the Battle of Pavia by an equerry of Francis I. of France; beyond it, in front of the chimney-piece, a choice and very valuable collection of 32 battle-axes. In the middle of the saloon, in the glass cabinet P, No. 949, at the top, is a sword executed by *Benvenuto Cellini*. The finest suits of armour are those of the Brescian family Martinengo, three on the left, and one on the right. Then, armour of Duke Emmanuel Philibert; saddle of Emp. Charles V in red velvet. At the end, the armour

of Prince Eugene worn at the battle of Turin. Under glass, a \*Shield by *Benvenuto Cellini* (?), embossed, and inlaid with gilding, representing scenes from the war of Marius against Jugurtha. Over the door a bust of King Charles Albert (d. 1849), between two Austrian flags captured in 1848 at the battle of Somma Campagna (p. 169). (A small adjacent room is occupied by a very valuable *Collection of Coins*, trinkets, mosaics, carved ivory, etc.) On the right, as the long hall is re-entered, we observe, under glass, the sword of St. Maurice, the sabre of Tipoo Sahib, etc. In the cabinet A are Roman weapons, helmets, and the eagle of a legion. In the cabinet F, at the top, the sword of the Imperial General Johann v. Werth (d. 1652), bearing a German inscription in verse.

On the floor above is the KING'S PRIVATE LIBRARY (shown daily 9-4; director Signor *Promis*), in which historical and genealogical works are particularly well represented. It also contains a valuable collection of drawings (by *Leonardo*, *Michael Angelo*, and *Venetian* masters).

The **Palace Garden** (*Giardino Reale*; Pl. G, H, 3), entered from the arcade opposite the Palazzo Madama, is open daily in summer (1st May to 1st Oct.) 11-3, on Sundays and festivals 12-2; military music, see p. 61. — Connected with the Giardino Reale is a well-stocked *Zoological Garden* (open to the public Mon. and Thurs.; to strangers daily on application at the palace). — The Cathedral, which adjoins the palace on the W., see p. 67.

In the PIAZZA CARIGNANO, near the Piazza Castello, to the S., rises the **Palazzo Carignano** (Pl. 26; G, H, 4), with its curious brick ornamentation, erected in 1680. From 1848 to 1860 the Sardinian Chamber of Deputies met here, and the Italian Chamber from 1860 to 1865. A new façade has been built at the back, towards the Piazza Carlo Alberto, and part of the collections of the Academy will be transferred to this palace. — In the Piazza Carignano, in front of the palace, stands the finely-executed marble statue of the philosopher and patriot *Gioberti* (Pl. 20), by *Albertoni*, erected in 1859. — The PIAZZA CARLO ALBERTO (E. side of the Palazzo Carignano) is embellished with a bronze monument of *King Charles Albert* (Pl. 18), designed by *Marochetti*, and cast in London. The pedestal stands on four steps of Scottish granite; at the corners below are four colossal statues of Sardinian soldiers; above them are four allegorical female figures, representing Martyrdom, Freedom, Justice, and Independence. The Piazza Carlo Alberto is connected with the Piazza Castello by the Galleria Subalpina, mentioned at p. 62.

In the vicinity, at the corner of the Piazza Carignano and the Via dell' Accademia No. 4, is the **Palazzo dell' Accademia delle Scienze** (Pl. 10; G, 5), containing a picture-gallery and museums of natural history and antiquities. To the right on the GROUND-FLOOR are the Egyptian, Roman, and Greek sculptures; on the FIRST FLOOR the natural history collection; on the SECOND FLOOR (98 steps), smaller Egyptian antiquities and the picture gallery. The first and third of these collections are open daily 9-4, adm. 1 fr.; on Sund. 9-3, gratis.

The **Natural History Museum** (open to the public on week-days, 10-4; from May to Oct. on Sundays also, 1-3, gratis), contains fossil impressions

of fish; a cabinet with fossil teeth and bones of an antediluvian '*Tetralopodon Arvernensis*', found during the construction of the railway; a gigantic '*Glyptodon Clavipes*' from the La Plata district; also a '*Megatherium Cuvieri*' and a valuable collection of stuffed animals. — The *Mineralogical Collection* is also worthy of a visit.

The **Museum of Antiquities** (*Museo Egizio e di Antichità Greco-Romane*) consists of two sections. An ante-room on the ground-floor, to the right, contains the complete skeleton of a whale. The door leads to HALL I., containing large Egyptian sphynxes, figures of idols and kings, sarcophagi, reliefs; over the sitting figure of Sesostris is an inscription in honour of the celebrated Parisian antiquarian Champollion. HALL II.: Egyptian statues and late Greek works found in Egypt; on the right a good torso, on the left four figures placed round a column, bearing the name of Protys the sculptor. Minerva, over life-size. In the centre of the room °mosaics found at Stampacci in Sardinia, representing Orpheus with his lyre, and a lion, goat, and ass, probably the animals listening to him. — The visitor now enters the — I. GALLERY to the left. In the centre, statue of a youth, Hercules killing the snakes (in Greek marble). Posterior wall, colossal female head (Venus), found at Alba in 1839, used as a fountain-jet; Antinous; replica of Marsyas and Olympus. On the 1st pillar, Athlete offering sacrifice (a relief). — II. GALLERY. Window-wall, head of basalt with Coptic inscription; two rows of busts of emperors. On the 2nd pillar, works in ivory and wood: Judgment of Solomon and Abraham's Sacrifice, by Simon Troger of Munich, 1741. The cabinets contain statuettes and busts in marble and bronze, many of them modern. By the 3rd pillar, under glass, a °Faun, found near Turin. Along the window-wall, busts of philosophers and poets. — Last Room: Vases; by the pillar dishes and terracottas (°head of Medusa, Mercury and a youth, Olympus from the group already mentioned, graceful dancing nymphs). By the wall opposite, a °statuette of Minerva in bronze, found in the Versa near Stradella in 1829; a tripod.

The SMALL ANTIQUITIES are on the *Second Floor* (visitors ring a bell on the right), consisting of mummies, papyrus writings, scarabees, statuettes, trinkets, vases, etc. In the centre of the second room is the formerly celebrated *Tabula Isiaca*, found in the pontificate of Pope Paul III. (d. 1549) in the Villa Caffarelli at Rome, a tablet of bronze with hieroglyphics and figures partially inlaid with silver. Attempts to decipher the characters elicited the most profound and erudite explanations and conjectures from the savants of three centuries, but it has been recently proved that the tablet is spurious, having been manufactured at Rome in the reign of Hadrian. The celebrated papyrus with the annals of Manetho, discovered by Champollion, is also preserved here. Finally a number of Roman and early Christian antiquities, at present in disorder.

The °**Picture Gallery** (*Pinacoteca*) consists of 15 rooms containing upwards of 514 paintings. This collection, being of recent date, cannot boast of a very distinct character like most of the other Italian galleries; but it affords the traveller an excellent opportunity of becoming better acquainted with the works of *Gaudenzio Ferrari* (1484-1549), in which we can distinctly trace Leonardo's inspiration, coupled with the influence of the Umbrian school (Nos. 49, and 54). *Sodoma* (*Giovanni Antonio Bassi*, 1477-1549), who originally belonged to the Loubard school, is also well represented by three pictures. *Lorenzo di Credi's* (1439-1537) *Madonna*. No. 103, of this master's best period, shows that he was influenced by Leonardo. The *Madonna della Tenda* was not painted by *Raphael* himself, and the *Madonna by Titian* is also a copy, like so many other pictures in this gallery. Numerous and important works of the old Netherlandish school, such as: 359. *Petrus Cristus*; 358. *Memling*; 340. Sketch by *Rubens*: 338, 351, 363, 384, by *Van Dyck*. (Catalogue 1 fr. 25 c.)

I. ROOM. Princes of the House of Savoy and battle-pieces. Beginning on the right: ten of the battles fought by Prince Eugene, by *Huchtenburgh*; thirteen portraits of members of the House of Savoy; No. 28 is by



*Horace Vernet*; 29, 31. *Clouet*; 26, 30. *Van Dyck*; 4. *Van Schuppen*, Prince Eugene on horseback.

II., III., IV. Rooms contain works of the school of Vercelli and Monferrato, of no great value. Room II.: \*49. *Gaudenzio Ferrari*, St. Peter and donor; 50. *Sodoma*, Holy Family; 50 bis. *Macrino d'Alba*, Madonna and saints (1492); 54. *Ferrari*, Descent from the Cross. Room III.: \*55. *Sodoma*, Madonna and saints. Room IV.: 90. Landscape by *Massimo d'Azeglio* (d. 1866).

V. Room. 93. *Fra Angelico da Fiesole* (?), Madonna; 94, 96. Adoring angels, by the same; 97. *Pollajuolo*, Tobias and the angel; 98. *Sandro Botticelli*, Same subject; 99. Madonna, with Christ and angels, by the same; 101. *Fr. Francia*, Entombment; 103. *Lorenzo di Credi*, Madonna and Child; 106. *Bugiardini*, Holy Family; 108 bis. After Raphael, Portrait of Pope Julius II. in the Palazzo Pitti at Florence; 111. *School of Leonardo da Vinci*, Madonna and John the Baptist; 118. *Girolamo Savoldo*, Holy Family; 121. *Franciabigio*, Annunciation; 122. *Franc. Penni*, Good copy (1518) of Raphael's Entombment in the Palazzo Borghese at Rome; 127 bis. *Clovio*, Entombment; 129. After Titian, an old copy; Pope Paul III.; 130. *Paris Bordone*, Portrait of a lady.

VI. Room. 132. *Bonifazio*, Holy Family; 137, 138, 142, 143. *Andrea Schiarone*, Mythological scenes; 140. *Antonio Badile*, Presentation in the Temple; 152. *Rinaldo Mantovano*, God the Father; 157. *Paolo Veronese*, The Queen of Sheba before Solomon; 158. *Annibale Caracci*, St. Peter; 161. *Caravaggio*, Musician.

VII. Room. 163. *Guido Reni*, John the Baptist; 166. *Badalocchio*, St. Jerome with the skull; 162. *Tintoretto*, The Trinity; 174. *Spagnoletto*, St. Jerome; 177, 178. *Albani*, Salmacis and the hermaphrodite; 189 bis. Christ at Emmaus, after Titian.

VIII. Room. Porcelain-paintings by *Constantin* of Geneva, copied from celebrated originals.

IX. Room. Fruit and flower-pieces; 227. by *Mignon*. 228. by *De Heem*. — Then a corridor with inferior works.

X. Room. \*234. *Paolo Veronese*, Mary Magdalene washing the Saviour's feet; 236. *Guido Reni*, Group of Cupids; 237, 238. *Poussin*, Waterfall, Cascades of Tivoli; 239, 242. *Guercino*, S. Francesca, Ecce Homo; 244. *Orazio Gentileschi*, Annunciation; 251. *Strozzi*, Homer.

XI. Room. 257, 258. *Sassoferrato*, Madonnas, the first called 'della Rosa'; 260, 264, 271, 274. *Albani*, The four Elements; 276. *Carlo Dolce*, Madonna; 284, 288. *Bernardo Bellotti*, Views of Turin; 293. *Tiepolo*, Allegory, a sketch; 295. *Maratta*, Madonna; 299, 300. *Angelica Kauffmann*, Sibyls.

XII. Room. Netherlands and German school: 306. *Engelbrechtseu*, Passion; 309. Adoration of the Magi in the style of *Hieron. Bosch* (15th cent.); 318. *Bruun*, Portrait of Calvin (?); 322. *Paul Bril*, Landscape; 325. *Goltz*, Warriors; \*388. *Van Dyck*, Children of Charles I. of England; 340. *Rubens*, Sketch of his apotheosis of Henry IV. in the Uffizi; 351. *Van Dyck*, Princess Isabella of Spain.

XIII. Room, containing the gems of the collection: 355. *Mantegna*, Madonna and saints; \*358. *Hans Memling*, Seven Sorrows of Mary, forming the counterpart of the Seven Joys of Mary at Munich; 359. *Petrus Cristus*, Madonna; \*363. *Van Dyck*, Prince Thomas of Savoy; 364. *D. Teniers*, Tavern; 366. *Wouwerman*, Cavalry attacking a bridge; 368. *D. Teniers*, Younger, The music-lesson; 369. *Sandro Botticelli*, Triumph of Chastity; 373. *Raphael*, Madonna della Tenda (a very fine picture, but the original is at Munich); 375. *Donatello*, Madonna (relief); 376. *Sodoma*, Lucretia killing herself; \*377. *Paul Potter* (1649), Cattle grazing; 377 bis. *Jan Liens*, Man asleep; 378. *Jan Breughel*, Landscape with accessories; 379. *Frans Mieris*, Portrait of himself; 360. *Felret Breughel*, Quay; 383 bis. *Murillo*, Capuchin; 384. *Van Dyck*, Holy Family; 385. *Honthorst* (*Gherardo delle Notti*). Samson overcome by the Philistines; \*386. *H. Holbein*, Portrait of Erasmus; 389. *J. Ruyssdael*, Landscape; 391. *Gerard Dow*, Girl plucking grapes; 392. *Velasquez*, Philip IV. of Spain; 393. *Rubens* (?), Holy Family; 394. *C. Netscher*, Scissors-grinder.

XIV. Room. 410. *Floris*, Adoration of the Magi; 417. *School of Rubens*, Soldier and girl; 420. *Wouwerman*, Horse-market; 435. *Gerard Dow*, Por-

trait; 434 bis. *Jacob Ruysdael*, Landscape; 428. *Teniers*, *Younger*, *Carl-Players*; 450. *School of Rembrandt*, Portrait of a Rabbi; 458. *Schalcken*, Old woman; 470 bis. *Murillo*, Portrait of a boy.

XV. Room. 478, 483. *Claude Lorrain*, Landscapes; 481. *Bourguignon*, Battle; 484 bis. *Netscher*, Portrait of Molière.

The spacious PIAZZA S. CARLO (Pl. G, 5; 587 ft. long, and 264 ft. wide), which adjoins the Academy, is embellished with the equestrian \***Statue of Emmanuel Philibert** (Pl. 19), Duke of Savoy (d. 1580), surnamed '*Tête de Fer*', in bronze, designed by *Marcchetti*, and placed on a pedestal of granite, with reliefs at the sides. On the W. side the Battle of St. Quentin, gained by the duke under Philip II. of Spain against the French in 1557; on the E. side the Peace of Cateau-Cambrésis (1558), by which the duchy was restored to the House of Savoy. The duke as '*pacem redditurus*' is in the act of sheathing his sword (his armour preserved at the armoury is placed in the same attitude).

The VIA ROMA leads from the Piazza S. Carlo to (N.) the Piazza Castello (p. 62), and (S.) to the Piazza Carlo Felice (p. 69) and the railway-station. — To the left in the Via dell' Ospedale is the *Exchange* (Pl. 13; H. 6), and adjoining it, No. 36, a *Museo Industriale Italiano*, with a technological collection. Farther on, No. 36, is the large *Ospedale S. Giovanni Battista*, with 557 beds. — The cross-street leads in a N. direction to the PIAZZA CARLO EMANUELE II. (Pl. I. 5), with a handsome \***Monument to Cavour** (Pl. 17), by *Dupré* of Florence, erected in 1873: grateful Italy presenting to Cavour, who holds a scroll in his left hand with the famous words '*libera chiesa in libero stato*', the civic crown; the pedestal is adorned with allegorical figures of Justice, Duty, Policy, and Independence; the reliefs represent the return of the Sardinian troops from the Crimea, and the Paris Congress. — In the Via Cavour, at the corner of the Via Lagrange, is the house in which Count Cavour was born in 1810 (d. 1861), with a memorial tablet.

Adjoining the Palazzo Reale (p. 63) on the W. side rises the **Cathedral** of *S. Giovanni Battista* (Pl. 3; G. 3), occupying the site of three ancient churches erected in 1492-98 by *Meo del Caprino* (of Florence, from Baccio Pintelli's design?), with a marble façade in the Renaissance style.

The **Interior** consists of a nave and aisles, a transept, and an octagonal dome in the centre. Over the W. Portal is a copy of Leonardo da Vinci's Last Supper (p. 129). Over the second altar on the right are 18 small pictures, blackened with age, by *Deferrari* (not Alb. Durer). Frescoes on the ceiling modern. The seats of the royal family are on the left of the high altar.

Behind the high altar is situated the \***Cappella del SS. Sudario** (open during morning mass till 9 o'clock), approached by 37 steps to the right of the high altar, constructed in the 17th cent. by the Theatine monk *Guarini*. It is a lofty circular chapel of dark brown marble, contrasting strongly with the white monuments, separated from the choir by a glass partition, and covered with a curiously shaped dome. This is the burial-chapel of the Dukes of Savoy, and was embellished by King Charles

Albert in 1842 with statues in white marble and symbolical figures to the memory of the most illustrious members of his family: (r.) *Emmanuel Philibert* (d. 1580), 'restitutor imperii', by Marchesi; Prince *Thomas* (d. 1656) 'qui magno animo italicam libertatem armis adseruit nec prius dimicare destitit quam vivere', by Gaggini; *Charles Emmanuel II.* (d. 1675), by Fraccaroli; *Amadeus VIII.* (d. 1451), by Cacciatori. The chapel also contains the marble monument of the late Queen of Sardinia *Maria Adelaide*, consort of Victor Emmanuel (d. 1855), by Revelli. The peculiar light from above enhances the effect. In a kind of urn over the altar is preserved the *SS. Sudario*, or part of the linen cloth in which the body of the Saviour is said to have been wrapped. — The door in the centre leads to the upper corridors of the royal palace, which are used as a public thoroughfare.

**Corpus Domini** (Pl. 5; E, F, 4), not far from the cathedral, was erected in 1607 by *Vitozzi*, and derived its name from a miracle of the Host in 1453. The church was restored in 1753 by Count *Alfiéri*, then 'decurione' of the city, and lavishly decorated with marble, gilding, and paintings. — In the adjacent church of *S. Spirito*, Rousseau, when an exile from Geneva, at the age of 16, was admitted within the pale of the Roman Catholic Church in 1728, but again professed himself a convert to Calvinism at Geneva in 1754.

The **Palazzo di Città** (Pl. 27; F, 4), the seat of the municipality, and containing a library, was erected in 1659. The Piazza in front of it is adorned with a monument to *Amadeus VI.* (Pl. 16), surnamed the '*conte verde*', the conqueror of the Turks and restorer of the imperial throne of Greece (d. 1383), a bronze group designed by *Palagi*, and erected in 1853. The marble statues in front of the portico of the Palazzo di Città (town-hall) of (l.) *Prince Eugene* (p. 71; d. 1756) and (r.) *Prince Ferdinand* (d. 1855), Duke of Genoa and brother of Victor Emmanuel, were erected in 1858; that of *King Charles Albert* (d. 1849) in the colonnade to the left was erected in 1859; that of the present king, to the right, in 1860. Opposite these statues are several *Memorial Tablets* bearing reference to the late wars and annexations.

In the **Piazza Savoia** (Pl. E, 3, 4) rises the '*Monumento Siccardi*' (Pl. 23), an obelisk 75 ft. in height, erected in 1854 to commemorate the abolition of ecclesiastical jurisdiction, named after *Siccardi*, minister of justice, on whose suggestion it was erected with the consent of the king and Chambers. The names of all the towns which contributed to the erection of the monument, are inscribed on the column.

The Via della Consolata leads hence to the church of —

**La Consolata** (Pl. 4; E, 3), containing a highly revered Madonna, and formed by the union of three churches; the present structure in the 'baroque' style of the 17th cent., was erected by *Guirini* in 1679, and decorated by *Juvara* in 1714. The chapel to the left below the dome contains the kneeling statues of *Maria Theresa*, Queen of Charles Albert, and *Maria Adelaide*, Queen of Victor Emmanuel (both of whom died in 1855), erected in 1861.

The passage to the right of the church is hung with votive pictures. — The piazza adjoining the church is adorned with a granite column surmounted with a statue of the Virgin, erected in 1835 to commemorate the cessation of the cholera.

Returning to the Piazza Savoia and crossing the Corso Siccardi, we reach the new **Giardino della Cittadella** (Pl. D, 5), where statues were erected in 1871 to *Brofferio* (d. 1866), the poet and orator, and in 1873, on the opposite corner, to the jurist *J. B. Cassini*. — Farther on, in the triangular Piazza Pietro Micca (Pl. G, 5), at the corner of the Via della Cernaja, is a monument in bronze, erected in 1864 in memory of *Pietro Micca*, the brave 'soldato minatore', who at the sacrifice of his own life saved the citadel of Turin, on 30th Aug., 1706, by springing a mine when the French grenadiers had already advanced to the very gates. Nearly opposite rises the statue of Count *Alex. Lamarmora* (d. 1855 in the Crimea).

The spacious *Arsenal* (Pl. 12; F, 6), containing the *Museo Nazionale d'Artigleria*, etc., is only shown to visitors by special permission of the minister of war.

In front of the imposing *Central Station* (p. 60; Pl. G, 7, 8) extends the **PIAZZA CARLO FELICE**, in which it is intended to erect a colossal monument in memory of the completion of the Mont Cenis tunnel. The bronze statue of *Massimo d'Azeglio*, the patriot, poet, and painter (d. 1866), by Balzico, was cast at Munich, and erected in 1873. This large piazza is adjoined by two smaller ones, the *Piazza Paleocapa* to the W., adorned with the statue of the minister of the same name (Pl. 22), and the *Piazza Lagrange*, with the statue of Count Lagrange, the mathematician (d. 1813 at Paris; Pl. 21).

In the **VIA DI PO** (p. 62) which leads to the S. E. from the Piazza Castello, on the left, is the **University** (Pl. 38; H, 4), with a handsome court in the late Renaissance style, with two arcades, one above the other. It contains a *Museo Lapidario* of Roman antiquities, chiefly inscriptions. Marble statues have been erected here to *Carlo Emanuele III.*, and to *Vittorio Amadeo II.* (at the entrance), to Prof. *Riberi* (d. 1861), and Dr. *L. Gallo* (d. 1857). On the corridor of the first floor are busts of celebrated professors and a large allegorical group presented by Victor Emmanuel. The *Library* (open to the public daily, 8 a.m. to 6 p.m. in summer, and 9-4 and 7-10 p.m. in winter; closed in Sept.), numbers 200,000 vols. and contains a number of valuable manuscripts from Bobbio and rare editions (Aldi). The University (founded in 1404) has at present a staff of 85 professors, and numbers about 1500 students.

No. 6, to the right in the Via dell' *Accademia Albertina*, is the **Accademia Albertina delle Belle Arti** (Pl. 9; I, 4; shown on weekdays on payment of a fee). It contains a small collection of pic-

tures; among them a Madonna ascribed to Raphael, a cartoon by Leonardo Vinci, and 24 cartoons by Gaudenzio Ferrari.

The Via Montebello, the next cross-street, leads to the new **Synagogue** (Pl. Sa; I, 3, 4), built by Antonelli in 1863, a square building resembling a tower, and the loftiest in the city (354 ft.), with a singular façade consisting of several rows of columns.

In the Via di Gaudenzio Ferrari, No. 1, is situated the **Museo Civico** (Pl. 25: I, 3), containing the civic collections (open to the public on Sun. and Thurs. 11-3, on other days by paying a fee of 1 fr.). These collections comprise three sections, an Ethnological and Pre-historic, another for mediæval objects, and a third for paintings. The latter numbers about 150 modern pictures, many by Massimo d'Azeglio, and several ancient.

The former *Giardino dei Ripari*, on the site of the old fortifications, is now superseded by new streets and squares in course of construction. The squares in this new quarter are adorned with several monuments, such as that to the Dictator of Venice, *Danielle Manin* (d. 1857), representing the Republic Venice, holding in her right hand a palm-branch, and leaning, with her left, on the medallion portrait of Manin. Also statues of *Cesare Balbo* (d. 1853), the minister and historian, of *Bava*, the Piedmontese general, and of general *Gugl. Pepe* (d. 1853), the brave defender of Venice in 1849.

An avenue leads from the Piazza Vittorio Emanuele, along the bank of the river, to the chain-bridge (Pl. L, 7), constructed in 1840. In the Via S. Lazzaro, diverging to the right, is situated the church of —

**S. Massimo** (Pl. I, 6, 7), built in 1849-54 in the style of a Roman temple, surmounted by a dome. The façade is adorned with statues of the Four Evangelists. Good modern frescoes in the interior, and several statues by Albertoni.

In the Corso del Re, which leads from the iron bridge to the Piazza Carlo Felice, on the left, is the handsome *Protestant Church* (*Tempio Valdese*, p. 72; Pl. 8; II, I, 7, 8), completed in 1854. The first erected at Turin since the establishment of religious toleration in 1848.

A favourite promenade, especially in the evening, is the **\*Nuovo Giardino Pubblico**, (Pl. K, 8, 9), above the iron bridge on the left bank of the Po (Café). It comprises the *Botanical Garden*, and extends beyond the royal château *Il Valentino*, a turreted building of the 17th cent., now occupied by the *Polytechnic School* ('Scuola superiore d'applicazione degli Ingegneri').

Opposite the spacious Piazza Vittorio Emanuele (see p. 62; Pl. K, L, 4, 5) the Po is crossed by a *Bridge* of five arches, constructed of granite in 1810. (Above the bridge are the swimming-baths, p. 61.) Beyond the bridge, on the right bank of the river is a flight of 32 steps ascending to the spacious dome-church of **Gran Madre di Dio** (Pl. 7; M, 5), erected in 1818 in imitation of the Pantheon at Rome, to commemorate the return of King Victor Emmanuel I. in 1814. The groups sculptured in stone on the flight of steps are

emblematical of Faith and Charity. The lofty columns of the portico are monoliths of granite. — A few hundred yards farther is the *Villa della Regina*, now a school for the daughters of officers who fell in battle, commanding a fine view of the town.

On the wooded hill to the right rises the **Capuchin Monastery, Il Monte** (Pl. 24; M, 6),  $\frac{1}{4}$  hr. walk from the bridge, approached by broad paths on the S. and N. sides. The latter is to be preferred, being shady and unpaved. The terrace in front of the church (which should be visited in the morning, as the evening light is dazzling) commands a fine \*survey of the river, city, plain, and the chain of the Alps in the background, above which (right) the snowy summit of Monte Rosa (15,217 ft.) is prominent, then the Grand-Paradis (13,780 ft.), and Monte Levanna (12,075 ft.); farther W. the valley of Susa (p. 24), S. Michele della Chiusa (p. 24), rising conspicuously on a hill (1042 ft.), above it the Roche-Melon (11,660 ft.) to the right of Mont Cenis, and farther S.W. Monte Viso (12,670 ft.). This hill of the Capuchins has always been a point of great importance in the military history of Turin, and was fortified down to 1802.

The **Cemetery (Cimitèro, or Campo Santo, open 12-4 o'cl. in winter in fine weather; in March and April 1-5; in summer 3-8; in Sept. and Oct. 2-4 only; single cab fare),  $\frac{1}{2}$  M. N.E. of Turin, on the road to Chivasso (see p. 75), is superior in extent and arrangement to most of the Italian burial-grounds, but contains few monuments worthy of note. The front part is enclosed by a wall with arches, while the more interesting portion beyond is surrounded by arcades covered with small domes. To the left by the wall in the first section is the tomb of *Silvio Pellico* (d. 1854); in the other section we observe the names of many celebrated modern Italians, such as *d'Azeglio, Bava, Brofferio, Gioberti, Pepe, and Pinelli*. A separate space on the N. side is reserved for the interment of non-Romanists.**

The **\*Superga (2555 ft.), the royal burial-church, a handsome edifice with a colonnade in front, and surmounted by a dome, conspicuously situated on a hill to the E. of Turin, is well worthy of a visit, and commands a splendid view. The building was begun in 1718, from designs by *Juvara*, and was completed in 1731 (closed 12-1). Adjacent are a seminary for priests and a trattoria. — It was near the Superga that the famous battle of Turin between the Italians and French was fought, 7th Sept. 1706, in which the latter were signally defeated, and by which the House of Savoy regained the Duchy, which was created a kingdom in the Peace of Utrecht, 1713. It is said that Prince Eugene reconnoitred the hostile camp from this height before the commencement of the battle, and that, observing symptoms of irresolution in their movements, he observed to Duke Amadeus II. '*Il me semble, que ces gens-là sont à demi battus*'. The latter, it is said, on this occasion vowed to erect a church here in honour of the Virgin, in case of his success in the battle. An annual thanksgiving still takes place in the church on 8th Sept.**

Pedestrians require three good hours to reach the Superga. The pleasantest way is to take a boat (*barchetta*) near the Po-bridge, to the left, as far as the *Madonna del Pilone*, about 1 M. below Turin, where donkeys (*somarelli*, 1-3 fr.) may be engaged for the ascent of the hill.

Or the omnibus, starting from Piazza Castello every  $\frac{1}{2}$  hr., may be taken to where the road ascends to the Superga in  $2\frac{1}{4}$  hrs.

EXCURSION from Turin to the VALLEYS OF THE WALDENSES (*Vallées Valdaises*), extending along the French frontier, about 30 M. to the S.W. The well-known and interesting Protestant communities (about 25,000 souls) who have occupied these valleys for 600 years, have steadily adhered to the faith for which they were formerly so cruelly persecuted. Their language is French. Railway from Turin to **Pignerol** (Ital. *Pinerolo*) in  $1\frac{1}{2}$  hr. (fares 3 fr. 45, 2 fr. 60, 1 fr. 75 c.); omnibus thence in 1 hr. (fare 1 fr.) to **La Tour**, Ital. *Torre Luserna (L'Ours; Lion d'Or)*, the chief of these communities, which possesses excellent schools. — From Pignerol a road ascends the valley of the *Clusone* by *Perosa* and *Fenestrelle*, a strongly fortified place, to the *Mont Genève* and the French fortress of *Briançon* in the lofty valley of the *Durance*. At *Cesanne* this road unites with that from *Susa* (p. 24).

### 11. From Turin to Aosta.

81 M. RAILWAY to Ivrea (39 M.) in 2 hrs. (fares 7 fr. 5, 4 fr. 95, 3 fr. 45 c.). DILIGENCE thence to Aosta (42 M.) in 9 hrs.

From Turin to (18 M.) *Chivasso*, see p. 75. Between the depressions of the lower mountains the snowy summits of the Grand-Paradis are conspicuous; farther to the E., Monte Rosa is visible.

At Chivasso carriages are changed. — 22 M. *Montanaro*, 27 M. *Caluso*, and 27 M. *Strambino*, villages of some importance.

39 M. **Ivrēa** (768 ft.; \**Europa*, in the Dora promenade; \**Universo*), a town with 9600 inhab., is picturesquely situated on the *Dora Baltea* (French *Doire*), on the slope of a hill crowned by an extensive and well-preserved ancient *Castle*, with three lofty towers of brick, now a prison. Adjacent is the modern *Cathedral*, the interior of which was restored in 1855. An ancient sarcophagus adorns the adjoining Piazza. Ivrea was the ancient *Eporedia*, which was colonised by the Romans, B.C. 100, in order to command the Alpine routes over the Great and Little St. Bernard. Pleasant walk to the *Madonna del Monte* (pilgrimage church) and the lake of *S. Giuseppe* with a ruined monastery (1 hr.).

Ivrea may be regarded as one of the S. gateways to the Alps. The luxuriantly fertile valley, here  $1\frac{1}{2}$  M. in breadth, is flanked with mountains of considerable height. The ROAD skirts the *Dora Baltea* the whole way to Aosta. On a height to the right stands the well-preserved, pinnacled castle of *Montalto* (a waterfall near it); several other ruins crown the hills farther on. The vines which clothe the slopes are carefully cultivated. The road leads through the villages of *Settimo-Vittone* and *Carema*. At —

11 M. (from Ivrea) **Pont St. Martin** (*Rosa Rossa*) the road crosses the *Lys* torrent, which descends from Monte Rosa. The bold and slender bridge which crosses the brook higher up is a Roman structure. This and the ruined castle here are most picturesque features in the landscape. Several forges are situated on the bank of the Dora.

Beyond *Donnaz* the road ascends rapidly through a profound defile. On the left flows the river, on the right rises a precipitous rock. The pass is terminated by the picturesque \***Fort Bard** (1019 ft.), which stands on a huge mass of rock in a most commanding position. The fort is of very ancient origin. In 1052 it was taken by Duke Anadeus of Savoy after a long and determined siege.

In May, 1800, three weeks before the battle of Marengo, an Austrian garrison of 400 men here kept the whole French army in check for a week after their passage of the St. Bernard. The French, however, succeeded in conveying a small field-piece to the summit of *Monte Albarredo*, which overtops the fort, and thus to silence the Austrian batteries.

The new road, hewn in the solid rock, no longer leads by the village of *Bard*, but follows the course of the *Dora*, below the fort. On the left opens the *Val di Camporciro*, or *Champorcher*.

19 M. **Verrex** (1279 ft.; *Ecu de France*, or *Poste*; \**Couronne*) lies at the entrance of the (r.) *Val de Challant*.

The valleys of Aosta and Susa (p. 24) were alternately occupied by the Franks and the Lombards, and belonged for a considerable period to the Franconian Empire, in consequence of which the French language still predominates in these Italian districts. Bard is the point of transition from Italian to French, while at Verrex the latter is spoken almost exclusively.

Above Verrex the valley expands. The ruined castle of *St. Germain*, loftily situated, soon comes into view. The road ascends through the long and steep \**Defile of Montjovet*. The rock-hewn passage is supposed to have been originally constructed by the Romans. The *Doire* forms a succession of waterfalls in its rugged channel far below. The small village of *Montjovet*, on the roofs of which the traveller looks down from the road, appears to cling precariously to the rocks. The castle of *St. Germain* is again visible from several different points of view.

As soon as the region of the valley in which Aosta is situated is entered, a grand and picturesque landscape, enhanced by the richest vegetation, is disclosed. The *Pont des Salassins* (see below), a bridge crossing a profound ravine, commands a magnificent view. On the left rises the castle of *Usselle*.

Near *St. Vincent* (Lion d'Or; *Ecu de France*) is a mineral spring and bath-establishment. Then (1½ M. farther) —

27½ M. **Châtillon** (1738 ft.; *Hôtel de Londres*; *Lion d'Or*, poor), the capital of this district, possessing a number of forges and handsome houses. To the N. opens the *Val Tournanche*, through which a bridle-path leads to the Theodule Pass (10,899 ft.), Zermatt, etc. (see *Baedeker's Switzerland*).

The road is shaded by walnut and chestnut-trees and trellised vines. The wine of *Chambave*, about 3 M. from Châtillon, is one of the best in Piedmont. A slight eminence here commands an imposing retrospect; to the E. rise several of the snowy summits of *Monte Rosa*, on the right the *Castor and Pollux* (*Les Jumeaux*), on



the left the bold peak of the Matterhorn and the Theodule Pass (see above). The whole of the background towards the W. is formed by the Mont Blanc chain.

To the left, at the entrance of the valley, stands the picturesque castle of *Fenis*. The poor village of *Nus*, with fragments of an old castle, lies midway between Châtillon and Aosta.

A footpath leads from *Villefranche* to the castle of *Quart* on the hill above (now a hospital) and descends on the other side. Beautiful view from the summit.

42 M. **Aosta** (1912 ft.; \**Hôtel du Montblanc*, at the upper end of the town, on the road to Courmayeur, R. 2, D. 4, B. 1 fr.: *Couronne*, in the market-place), the *Augusta Praetoria Salassorum* of the Romans, now the capital (7760 inhab.) of the Italian province of that name, lies at the confluence of the *Buttier* and the *Doire*, or *Dora Baltea*. The valley was anciently inhabited by the Salassi, a Celtic race, who commanded the passage of the Great and the Little St. Bernard, the two most important routes from Italy to Gaul. They frequently harassed the Romans in various ways, and on one occasion plundered the coffers of Cæsar himself. After protracted struggles the tribe was finally extirpated by Augustus, who is said to have captured the whole of the survivors, 36,000 in number, and to have sold them as slaves at Eporædia. He then founded Aosta to protect the high roads, named it after himself, and garrisoned it with 3000 soldiers of the Prætorian cohorts. The antiquities which still testify to its ancient importance are the *Town Walls*, flanked with strong towers, the double *S. Gate*, resembling the Porta Nigra of Trèves in miniature, a magnificent *Triumphal Arch* constructed of huge blocks and adorned with ten Corinthian half-columns, the half-buried arch of a bridge, the ruins of a basilica, etc. The principal relics may be seen in 1/2 hr. (follow the principal street towards the E. leading to the Roman Gate and the Triumphal Arch; 200 paces straight beyond the latter, bearing to the left, is the narrow Rue du Pont Romain crossing the Roman bridge, the construction of which is seen by descending a few paces to the left).

The modern *Cathedral* possesses a singular Portal, with frescoes: above it the Last Supper in terracotta, gaudily painted. Near the church of *St. Ours* are cloisters with handsome early Romanesque columns. Modern *Town Hall* in the spacious Piazza Carlo Alberto, or market-place.

The **Becca di Nona** (10,354 ft.), which rises to the S. of Aosta, commands a superb view of the Alps. Good bridle-path to the summit (6 1/2 hrs.; refuge hut three-quarters of the way up).

From Aosta over the *Great St. Bernard to Martigny* (p. 25), and from Aosta to *Courmayeur* and round Mont Blanc to *Chamonix*, and excursions to the *Great Alps*, see *Baedeker's Switzerland*. One-horse carr. to St. Remy (near the Great St. Bernard) 15, to Courmayeur 20, to Châtillon (p. 73) 12 fr. — Diligence to Courmayeur and Pré St. Didier.

## 12. From Turin to Milan by Novara.

94 M. RAILWAY in  $3\frac{3}{4}$ - $5\frac{1}{2}$  hrs. (fares 17 fr., 11 fr. 90, 8 fr. 55 c.). — The seats on the left afford occasional glimpses of the Alps. — Stations at Turin, see p. 60.

The *Dora Riparia* is crossed, then the *Stura* between stations *Succursale di Torino* and *Settimo* (whence a tramway runs towards the N. to *Rivarolo*), and beyond it the *Mulon* and *Orco*, all tributaries of the *Po*. — 15 M. *Brandizzo*.

18 M. *Chivasso* (*Moro*) lies near the influx of the *Orco* into the *Po*. Branch-line hence to *Ivrea*, see p. 72. Beyond stat. *Torrazza di Verolan* the *Dora Baltea* (p. 72), a torrent descending from Mont Blanc, is crossed. Stations *Saluggia*, *Livorno*, *Bianzè*, and *Tronzano*.

37 M. *Santhià* possesses a church, restored with taste in 1862, and containing a picture by Gaud. Ferrari in ten sections.

BRANCH-LINE TO BIELLA,  $37\frac{1}{2}$  M., in 1 hr., by *Salussola*, *Vergnasco*, *Sandigliano*, and *Candelo*. — *Biella* (*Albergo della Testa Grigia*), an industrial town and seat of a bishop, possesses streets with arcades and a fine cathedral in a spacious Piazza, where the episcopal palace and seminary are also situated. The palaces of the old town, rising picturesquely on the hill, are now tenanted by the lower classes. Celebrated pilgrimage-church of the *Madonna d'Oropa*, 8 M. farther up the valley (omnibus thither). On the way to it two finely situated hydropathic establishments are passed.

The train skirts the high road. —  $40\frac{1}{2}$  M. *S. Germano*.

$49\frac{1}{2}$  M. *Vercelli* (*Tre Re*; *Leone d'Oro*), an episcopal residence with 20,000 inhab. The church of *S. Cristoforo* contains pictures by G. Ferrari and B. Lanini, by the former a \**Madonna* and donors in an orchard. *S. Caterina* also contains a work of Ferrari. The library of the cathedral contains a number of rare and ancient MSS. A statue of *Cavour* was erected in the market-place in 1864.

BRANCH-LINE TO ALESSANDRIA, 35 M., in 2 hrs. (fares 6 fr. 35, 4 fr. 45. 3 fr. 20 c.). Stations *Asigliano*, *Pertengo*, *Balzola*, beyond which the *Po* is crossed. —  $14\frac{1}{2}$  M. *Casale* (*Albergo dell' Angelo*, *Leone d'Oro*) the ancient capital of the Duchy of Monferrato, which afterwards belonged to the Gonzagas. The interesting Romanesque *Cathedral* contains several good paintings (by G. Ferrari and others), and sculptures by Lombard masters. The church of *S. Domenico*, in the Renaissance style, the *Palazzo di Città*, with its handsome colonnade, and other palaces are also worthy of inspection. *Casale* is the junction of the Asti and Mortara line (see p. 78). — The following stations are *Borgo S. Martino*, *Giarole*, *Valenza* (see p. 158), *Valmadonna*, and *Alessandria* (see p. 78).

The train crosses the *Sesia* (p. 160); to the left rise the Alps, among which the magnificent Monte Rosa group is most conspicuous.  $52\frac{1}{2}$  M. *Borgo Vercelli*, 57 M. *Ponzana*.

63 M. *Novara* (\**Rail. Restaurant*; *Albergo d'Italia*; *Tre Re*), an episcopal residence and formerly a fortress with 14,400 inhab., commanded by the stately tower of the church of *S. Gaudenzio*, which was erected by Pellegrini about 1560 and contains several good pictures by Gaudenzio Ferrari (2nd chapel on the left). The tower, ascended by 300 steps, commands a very extensive prospect, most picturesque in the direction of the Alps. The *Cathedral*, a

Renaissance structure with nave and aisles, connected with the Baptistery by an atrium or entrance-court, is a picturesque pile. The market-place is surrounded by colonnades. The whole town, with its Italian architecture and numerous shops, is attractive and interesting. In the Corso Cavour, at the entrance to the town from the station, stands a *Monument of Cavour*, by Dini, erected in 1863; near the Porta Mortara is another to *Charles Albert*. Novara was the scene of a victory gained by the Austrians under Radetzky over the Piedmontese in 1849, in consequence of which Charles Albert abdicated.

The celebrated philosopher *Petrus Lombardus* (d. 1164 as Bishop of Paris), surnamed the 'Magister Sententiarum' and a pupil of Abelard, was born near Novara about 1120.

BRANCH-LINE TO GOZZANO, 22½ M., in 1¼ hr. (fares 4 fr. 10, 2 fr. 85 c., 2 fr. 5 c.). Stations *Callignaga*, *Momo*, *Borgomanèro* (a thriving town), *Gozzano* (near it *Bolzano*, an episcopal chateau with a church and seminary); diligence hence to Orta and Omega (see p. 159).

At Novara the Turin and Milan line is crossed by that from Arona to Genoa (p. 157). Frequent changes of carriage.

69 M. *Trecale*. Near *S. Martino* the line crosses the Ticino by a broad and handsome stone bridge of eleven arches, which the Austrians partially destroyed before the battle of Magenta.

Farther on, the *Naviglio Grande*, a canal connecting Milan with the Ticino and the Lago Maggiore, is crossed (comp. p. 120). On the right, before (77 M.) *Magenta* is reached, stands a monument erected to Napoleon III. in 1862, to commemorate the victory gained by the French and Sardinians over the Austrians on 4th June, 1859, in consequence of which the latter were compelled to evacuate the whole of Lombardy. A number of mounds with crosses in a low-lying field opposite the station mark the graves of those who fell in the struggle. A small chapel has been erected on an eminence in the burial-ground, and adjoining it a charnel-house.

The line intersects numerous fields of rice, which are kept under water during two months in the year. The next stations are *Vittuone* and *Rhò* (p. 157), where the line unites with that from Lago Maggiore.

93½ M. *Milan* (see p. 118).

### 13. From Turin to Piacenza by Alessandria.

117 M. RAILWAY in 4-8 hrs.; fares 21 fr. 35, 14 fr. 90, 10 fr. 60 c.

From Turin to *Alessandria*, 57 M., see R. 14. Beyond *Alessandria* the train traverses the *Battle-field of Marengo* (p. 78). 62 M. *Spinetta*, a little to the N.W. of Marengo. — 65 M. *S. Giuliano*. The train then crosses the *Scrvia*, and reaches (70 M.) the small town of *Tortona* (*Croce Bianca*), the ancient *Dertona*, with a *Cathedral* erected by Philip II. in 1584, containing a remarkably fine ancient sarcophagus.

BRANCH-LINE TO NOVI (p. 79), 11½ M., by stat. *Pozzuolo*, in 35-45 min. (2 fr. 15, 1 fr. 55, 1 fr. 10 c.).

The train traverses a fertile district, and near stat. *Pontecurone* crosses the impetuous *Curone*. — 81 M. **Voghĕra** (*Italia*; *Albergo det Popoto*), a town with 10,000 inhab., on the left bank of the *Staffora* (perhaps the ancient *Iria*), was once fortified by Giov. Galeazzo Visconti. The old church of *S. Lorenzo*, founded in the 11th cent., was remodelled in 1600. From Voghera to Milan viâ Pavia, see R. 26.

On the high road from Voghera to the next station *Casteggio*, to the S. of the railway, is situated *Montebello*, where the well known battle of 9th June, 1800 (five days before the battle of Marengo), took place, and on 20th May, 1859, the first serious encounter between the Austrians and the united French and Sardinian armies. *Casteggio*, a village on the *Coppa*, is believed to be identical with the *Clastidium* so frequently mentioned in the annals of the wars of the Romans against the Gauls.

The train skirts the base of the N. spurs of the *Apennines*. Stations *S. Giuletta*, *Broni*, *Stradella*. At (98½ M.) *Arena-Po* it enters the plain of the Po. — 103 M. *Castel S. Giovanni* is situated in the ex-Duchy of Parma. The last stations are *Sarmato*, *Rottofreno*, and *S. Niccolò*. The last, in the plain of the *Trebia*, is memorable for the victory gained by Hannibal, B. C. 218, over the Romans, whom he had shortly before defeated near Somma.

117 M. *Piacenza*, see p. 251.

## 14. From Turin to Genoa.

### a. Viâ Alessandria.

108 M. RAILWAY in 4¼-5¾ hrs.; fares 18 fr. 80, 13 fr. 50, 9 fr. 40 c.

The line, the construction of which was zealously promoted by Count Cavour in order to bring Genoa into closer relations with Turin (opened in 1853), at first proceeds towards the S., at some distance from the left bank of the *Po*. Near (5 M.) *Moncalieri*, where the line turns to the E., the river is crossed by a bridge of seven arches. On a height above Moncalieri, which is picturesquely situated on the hill-side, rises the handsome royal châteâu, where Victor Emmanuel I. died in 1823. A final retrospect is now obtained of the hills of Turin, and, to the left, of the principal snowy summits of the Alps. At (8 M.) *Trofarello* the line to *Savona* (p. 79) and *Cuneo* (p. 111) diverges to the right (S.). Stations—*Cambiano*, *Pessione*, *Villanuova*, *Villafranca*, *Baldichieri*, *S. Damiano*. The line then crosses the *Borbone*, and reaches the valley of the *Tanaro*, on the left bank of which it runs to Alessandria.

35½ M. **Asti** (*Leone d'Oro*; *Albergo Reale*), the ancient *Asta*, with 20,000 inhab. and numerous towers, the birthplace of the dramatist *Alfieri* (d. 1803), is famous for its wine and its horticulture. The left aisle of the Gothic *Cathedral*, erected in 1348, contains (in the 2nd chapel) a *Madonna* with four saints by a master

of the school of Vercelli, and (in the 3rd chapel) a Sposalizio, probably by the same. — The adjacent church of *S. Giovanni* (the sacristan of the cathedral keeps the key) is built above an ancient Christian basilica, part of which has again been rendered accessible, and is borne by monolithic columns with capitals bearing Christian symbols (6th cent.). The Piazza is adorned with a *Statue of Alfieri*, by Viui, erected in 1862. Near Porta Alessandria is the small Baptistery of *S. Pietro* (11th cent.), an octagonal structure, borne by short columns with square capitals, and surrounded by a low, polygonal gallery. On the right and left, at some distance from the town, rise vine-clad hills which yield the excellent wine of Asti.

FROM ASTI TO MORTARA (Milan) 46 M., in 3 $\frac{1}{2}$ -4 hrs. — Stations unimportant: (29 M.) *Casale*, see p. 74; *Mortara*, see p. 157. — FROM ASTI TO CASTAGNOLE (p. 80), 13 M., in  $\frac{3}{4}$  hr.

Next stations *Annone*, *Cerro*, *Felizzano*, *Solero*. The country is flat and fertile. Before Alessandria is reached, the line to Arona (p. 157) diverges to the N. The train now crosses the Tanaro by a bridge of 15 arches, skirts the fortifications, and reaches —

56 $\frac{1}{2}$  M. **Alessandria** (*Hôtel de l'Univers*, R. 2, B. 1 $\frac{1}{2}$  fr.; *Europa*; *Italia*; \**Railway Restaurant*), a town with 54,000 inhab., situated on the *Tanaro* in a marshy district, and only remarkable as a fortified place. It was founded in 1168 by the Lombard towns allied against the Emp. Frederick Barbarossa, and named after Pope Alexander III., with the addition of *della paglia*, i. e. of straw, perhaps because the first houses were thatched with straw. — Alessandria being a junction of several lines, carriages are generally changed here. Railway to Vercelli by Valenza, p. 75; to Novara and Arona, p. 157; to Milan by Mortara and Vigevano, see p. 157; to Pavia by Valenza, see p. 164; to Piacenza, Parma, Bologna, etc., see RR. 13 and 38; to Cavaller maggiore, see p. 80.

FROM ALESSANDRIA TO SAVONA (viâ Acqui), 65 M., in 4 $\frac{1}{4}$ -4 $\frac{3}{4}$  hrs. (fares 11 fr. 94. 8 fr. 40 c., 6 fr.). — As far as *Cantalupo* the line is the same as to Brâ and Cavallermaggiore (see p. 80). — 21 M. **Acqui** (*Albergo del Moro*), the *Aquæ Statielæ* of the Romans, an episcopal town on the *Bormida* with 8600 inhab., is well known for its mineral waters, which resemble those of Aix-la-Chapelle in their ingredients and effects. The *Cathedral*, with its double aisles, dates from the 12th cent. Near Acqui the Austrians and Piedmontese were defeated by the French in 1794. Good wine is produced in the vicinity. — The line ascends the valley of the Bormida, passing through ten tunnels. Stations *Terzo*, *Bistagno*, *Ponti*, *Montechiario*, *Spigno* (with silk and wool factories), *Merana*, *Dego*, *Rocchetta*, and *Cairo*. — 52 M. *S. Giuseppe di Cairo*, see p. 80. — 65 M. *Savona*, see p. 97.

The line crosses the *Bormida*, which a short distance below Alessandria falls into the Tanaro. About 1 $\frac{1}{4}$  M. E. of the bridge, in the broad plain between the Bormida and the *Scriveria*, is situated the small village of *Marengo*, near which, on 14th June, 1800, was fought a battle which influenced the destinies of the whole of Europe. The French were commanded by Napoleon, the Austrians by Melas. The battle lasted 12 hrs., and the French lost Desaix, one of their best generals. — 63 M. *Fruarîolo*.

70 M. **Novi** (\**La Sirena*; branch-line to Pavia and Milan via Tortona and Voghera, see p. 76, and R. 26; to Piacenza, see R. 13), situated on the hills to the right, commanded by a lofty square tower, was the scene of the victory gained by the Austrians and Russians under Suwarow over the French on 15th Aug., 1799. At (75 M.) *Serravalle* the train enters a mountainous district. — 79 M. *Arquata*, with a ruined castle on the height. Between this point and Genoa there are eleven tunnels. The train threads its way through profound rocky ravines (*la Bocchetta*), traversing lofty embankments, and several times crossing the mountain-brook (*Serria*). The scenery is imposing and beautiful. — 83 M. *Isola del Cantone*; on the height to the right the ruins of an old castle.

89½ M. *Busalla* (1192 ft.), the culminating point of the line, is the watershed between the Adriatic and the Mediterranean.

The last long tunnel, the *Galleria dei Giori*, is upwards of 2 M. in length, and descends towards the S. Then several short cuttings. The landscape becomes more smiling; the hills, planted with vines and corn, are sprinkled with the villas of the Genoese.

To the right, on the loftiest summit of the mountain near (95½ M.) *Pontedecimo* (282 ft.), rises the white church of the *Madonna della Guardia*. 98 M. *Bolzaneto*, and (100 M.) *Rivarolo*. The railway now crosses the *Polcevera*, the stony channel of which is occasionally filled with an impetuous torrent, by a handsome new bridge with 9 arches. On the summits of the heights to the left are towers belonging to the old fortifications of Genoa. The last stat. (101¼ M.) *S. Piër d'Arèna* is a suburb of Genoa (p. 94), where travellers provided with through-tickets to or from Nice change carriages (\*Rail. Restaurant). On the right are the lighthouse and citadel, below which the train enters the town by a tunnel. On the right, before the station is entered, is the *Palazzo del Principe Doria*.

103 M. *Genoa*, see p. 82.

### b. Vià Brà and Savona.

FROM TURIN TO SAVONA. 97 M., in 5¾-7 hrs. (fares 16 fr. 70. 11 fr. 70. 8 fr. 45 c.); thence to GENOA. 27½ M., in 1¼-2 hrs. (fares 5 fr., 3 fr. 50. 2 fr. 50 c.). Finest views to the right.

From Turin to *Trofarello*, 8 M., see p. 77. — 121½ M. *Villastellone*.

A road crossing the *Po* leads hence to the W. to (4½ M.) *Carignano*, a town with 7800 inhab., and several handsome churches, situated on the high road from Turin to Nice. *S. Giovanni Battista* was erected by Count Alfieri: *S. Maria delle Grazie* contains a monument to Bianca Paleologus, daughter of Guglielmo IV., Marquis of Montferrat, and wife of Duke Charles I., at whose court the 'Chevalier Bayard' was brought up. — Carignano, with the title of a principality, was given as an appanage to Thomas Francis (d. 1656), fourth son of Charles Emmanuel I., from whom the present royal family is descended.

18 M. *Carmagnola*, with 12,800 inhab.

Carmagnola was the birthplace (1390) of the celebrated Condottiere *Franesco Bussone*, son of a swine-herd, usually called Count of Carmagnola, who reconquered a considerable part of Lombardy for Duke Filippo

Maria Visconti, and afterwards, as Generalissimo of the Republic of Venice conquered Brescia and Bergauo, and won the battle of Macalo (1427). At length his fidelity was suspected by the Council of Ten, and he was beheaded between the two columns in the Piazzetta (p. 218) on 5th May, 1432. Bussoni's fate is the subject of a tragedy by Mauzoni.

A direct line hence to Brà is projected, with a view to cut off the circuit by Cavallermaggiore. — 23½ M. *Racconigi*, with a royal château and park, laid out in 1755 by Le Nôtre, the favourite residence of Carlo Alberto (d. 1849).

28 M. *Cavallermaggiore* (Italia; Buoi Rossi), with 5000 inhab., is the junction of the lines to Saluzzo and Cuneo (p. 112).

31 M. *Madonna del Pilone*. — 36 M. *Brà*, the largest place on the line, with 13,000 inhab., is the junction for Alessandria.

FROM CAVALLERMAGGIORE TO ALESSANDRIA, 61 M., in 2¼ hrs. (fares 11 fr. 15, 7 fr. 80, 5 fr. 60c.). — 8 M. *Brà*, see above. — 12½ M. *Vittoria*, whence a pleasant excursion to the royal palace of *Pollenzo* may be made. — 19½ M. *Alba*, with 9600 inhab. The cathedral of *S. Lorenzo* dates from the 15th cent. — Next stations *Neive*, *Castagnole* (p. 78), *Costigliole*, *S. Stefano Belbo*, on the *Belbo*, the valley of which the train traverses for a considerable distance; *Cinelli*, *Calamandrana*, and *Nizza di Monferrato*, whence a good road leads to *Acqui* (p. 78). Stat. *Incisa*, situated on the *Belbo*, a considerable distance from the railway. Then *Castelnuovo*, *Bruno*, *Bergamasco*, *Oviglio*, *Cantalupo*, and (61 M.) *Alessandria*, see p. 78.

41 M. *Cherasco*, not visible from the line, lies at the confluence of the *Tanaro* and the *Stura*. The train ascends the course of the former. Stations *Narzole*, *Monchierro*, *Farigliano*. — 89 M. *Carrù*.

BRANCH-LINE TO MONDOVI, 9 M., in 40 min. (fares 1 fr. 65, 1 fr. 15, 85c.). — **MONDOVI** (*Croce di Malta*; *Tre Limoni d'Oro*), a town with 18,000 inhab., on the *Ellero*, with a cathedral of the 15th cent., and a loftily situated old tower, is the best starting point for a visit to the imposing *Cavern of Bossèa*, in the *Valle di Corsaglia*. A carriage may be hired at one of the inns at Mondovi for *Erabosa*, 9½ M. to the S. of Mondovi, whence a lighter 'calessa' conveys travellers to the cavern (each member of a party 7-8 fr. for the whole drive). The cavern is shown from the beginning of June to the end of October (admission 2¼ fr.; no gratuities).

62 M. *Niella*. — 68 M. *Ceva*, on the *Tanaro*, an industrial place with an old castle under which the train passes by a tunnel.

The train now begins to cross the Maritime Alps, and reaches the most imposing part of the line. Between this point and Savona are numerous viaducts and no fewer than 28 tunnels. The train quits the valley of the *Tanaro* and ascends. Beyond (72 M.) *Sale* it passes through the *Galleria del Belbo*, a tunnel upwards of 3 M. in length, and the longest on the line. — 79 M. *Millesimo*, in the valley of the *Bormida di Millesimo*.

84½ M. *S. Giuseppe di Cairo*, on the *Bormida di Spigno*, through the valley of which the train descends to *Acqui* (p. 78).

Tunnels and viaducts now follow each other in rapid succession, the loftiest of the latter being 137 ft. high. — 93 M. *Santuariò di Savona*, a pilgrimage church with a large hospice for poor devotees, founded in 1537.

97 M. *Savona*, see p. 97.

### III. Liguria.

The *Maritime Alps* and the immediately contiguous *Apennines* (the boundary between which is near Savona, about 20 M. to the W. of Genoa) slope gently northwards to the Po in the form of an extensive rolling country, and descend abruptly towards the sea to the S. The narrow RIVIERA, or coast-district, expands at a few points only into small plains. The cultivated land climbs up the hill-sides in terraces, sheltered from the N. wind, and enjoying a fine sunny aspect. While the mean temperature at Trin is  $53\frac{1}{3}^{\circ}$  Fahr., it is no less than  $61^{\circ}$  at Genoa; and again, while the temperature of January averages  $31^{\circ}$  at the former, and occasionally falls below zero, it averages  $46^{\circ}$  at the latter, and is rarely lower than  $23^{\circ}$ . — The climate of the Riviera is therefore milder than that of Rome, and is even favourable to the growth of the palm.

As the country differs in many respects from Piedmont, so also do its INHABITANTS, while their Genoese dialect, which is difficult for foreigners to understand, occupies a middle place between the Gallic patois of Upper Italy and that of Sardinia. The *historical* development of the two countries has also been widely different. The natural resource of the *Ligurians*, or the inhabitants of the Riviera, was the sea, and they were accordingly known to the Greeks at a very early period as pirates and freebooters. To what race the Ligurians belong has not yet been ascertained. As the Greek Massalia formed the centre of trade in S. France, with Nice as its extreme outpost towards the E., so *Genoa* constituted the natural outlet for the traffic of the Riviera. During the 3rd cent. B.C. Genoa became subject to the Romans, who in subsequent centuries had to wage long and obstinate wars with the Ligurians, in order to secure the possession of the military coast-road to Spain. As late as the reign of Augustus the Roman culture had made little progress here. At that period the inhabitants exported timber, cattle, hides, wool, and honey, receiving wine and oil in exchange. In the 7th cent. the *Lombards* gained a footing here, and thenceforth the political state of the country was gradually altered. The W. part with Nice belonged to the Provence, but in 1388 came into the possession of the Counts of Savoy, forming their only access to the sea down to the period when they acquired Genoa (1815).

The *Var*, which the Emp. Augustus had declared to be the boundary between Italy and Gaul, continued to be so down to 1860, when, as a reward for services rendered by Napoleon III., Italy ceded to France the districts of Savoy (4316 sq. M.) and Nice (1436 sq. M.). While the loss of Savoy, though the cradle of the dynasty, was not severely felt owing to the notorious French sympathies and clerical propensities of the inhabitants, the cession of Nice was regarded by the Italians as a national injury. The E. part of the Riviera now forms the *Province of Porto Maurizio*, 488 sq. M. in area, with 127,053 inhab., adjoining which is the *Province of Genoa*, 1669 sq. M. in area, with 716,759 inhab. These provinces once constituted the REPUBLIC OF GENOA, which in the 13th cent. became the mistress of the W. part of the Mediterranean, and afterwards fought against Venice for the supremacy in the Levant. Genoa's greatness was founded on the ruin of Pisa. The Tuscan hatred of the Genoese was embodied in the saying — 'Mare senza pesce, montagna senza alberi, uomini senza fede, e donne senza vergogna', and *Dante* (Inf. xxxiii. 151-53) addresses them with the words —



Ahi, Genovesi, uomini diversi  
 D'ogni costume, e pien d'ogni magagna;  
 Perchè non siete voi del mondo spersi?

Modern historians describe the character of the Genoese in the middle-ages in a similar strain. The whole energy of the Genoese seems indeed to have been concentrated on commerce and the pursuit of gain. Notwithstanding their proud naval supremacy, they participated little in the intellectual development of Italy, and neither possessed a school of art, nor produced any scholars of eminence. When at length the effete republic was incorporated with Piedmont, it became the representative of radical principles as contrasted with the conservatism of the royalist territory. *Giuseppe Mazzini*, the chief leader of the national revolutionary party, was born at Genoa in 1808, and *Garibaldi*, though born at Nice (1807), was the son of a Genoese of Chiavari. The rivalry of the once far-famed republic with the upstart Turin, and of the restless harbour population with the stolid Piedmontese, have of recent years been productive of very notable results. Modern Genoa has, moreover, regained its ancient mercantile importance, and it is in the possession of the Ligurian coast that the maritime power of Italy chiefly lies.

## 15. Genoa, Italian *Genova*, French *Gènes*.

**Arrival.** There are two stations at Genoa. The *Stazione Piazza Principe*, or principal station (for Alessandria, Turin, Spezia, Pisa, and for Savona and Nice), is in the Piazza Acquaverde (Pl. D, 1, 2; the goods-station only is in the Piazza del Principe). The arrangements are admirable. A long row of omnibuses in the covered hall awaits the arrival of the trains. — The second station, called *Stazione Piazza Brignole* (Pl. H, 4), at the end of the Via Serra, and connected with the first by means of a tunnel below the higher parts of the town, is the first place where the Spezia and Pisa trains stop. — Travellers arriving at Genoa by sea, and wishing to continue their journey by rail without delay, may immediately after the custom-house examination, which takes place on the quay, book their luggage there for their destination (taking care to entrust it to a *facchino* of the dogana, fee 20 c., and not to an unauthorised bystander), and thus save much trouble.

**Hotels**, all of unattractive exterior. \*HÔTEL TROMBETTA, formerly *Feder* (Pl. a), once the Palace of the Admiralty, entrance Via Bogina 9; HÔTEL DE LA VILLE (Pl. c), both kept by Sign. *Trombetta*; HÔTEL D'ITALIE & CROIX DE MALTE (Pl. b); \*HÔTEL DES QUATRE NATIONS, in the Palazzo Serra (Pl. d). Average charges at these: R. from 3, B. 1½, L. and A. 2, omnibus 1-1½ fr. — \*ALBERGO DI GENOVA (Pl. h), near the Teatro Carlo Felice, quiet; \*HÔTEL DE FRANCE (Pl. g), R. 2½ fr.; HÔTEL DE LONDRES, near the principal station, R. 2½, D. 4½ fr.; VITTORIA, Piazza dell' Annunziata 16, R. 2½ fr.; REBECCHINO, Via Nuovissima, well spoken of, with trattoria; \*HÔTEL SMITH (English landlord), near the exchange Via Ponte Reale, unpretending.

**Cafés.** *Café Roma*, the newest and most attractive, by the Teatro Carlo Felice, at the corner of the new Via Roma; \**Concordia*, Via Nuova, opposite the Palazzo Rosso (Pl. 25; p. 90), handsomely fitted up, with a cool garden and a fountain, music frequently in the evening; \**Café d'Italie*, with a brilliantly illuminated garden, open in summer only, at Acqua Sola (p. 94); *Café de France*, Via Carlo Felice; *Café Rossini*, opposite the post-office; *Café d'Europe*, Via Giulia; *Café Costanza*, Via degli Orefici, near the exchange; *Café del Centro*, Via Nuova, and others. — The larger cafés are also restaurants, and some of them give dinners at a fixed charge (Concordia 4-5, Italie 4, France 2½ fr.).

**Restaurants:** *Unione*, Piazza Campetto 9. — **Beer:** *Birreria Müller*, Via Caffaro, cold viands; *Monsch*, nearly opposite the post-office, Munich beer; *Klainguti*, opposite the Teatro Carlo Felice, Vienna beer.







# GENOVA.

- |                 |                                             |                              |
|-----------------|---------------------------------------------|------------------------------|
| 1               | Accademia di Belle Arti e Biblioteca civica | F.4                          |
| 2               | Archivio Governativo                        | Via al Arcovescovato 14. F.4 |
| 3               | Archivio di S. Giorgio e Dogana             | Via del Commercio 4. E.3.    |
| 4               | Arcovescovato                               | E.F.4                        |
| 5               | Banca Nazionale                             | Via S. Lorenzo 12. E.4       |
| 6               | Biblioteca Franzoniana                      | Via Gustiniani 11. E.4       |
| 7               | Borsa o Loggia                              | E.3                          |
| 8               | Camera di Commercio                         | Piazza Sanregola 1. E.3      |
| <b>Chiese :</b> |                                             |                              |
| 9               | S. Maria della Vigna                        | E.4                          |
| 10              | S. Annunziata                               | E.2                          |
| 11              | S. Stefano                                  | G.4                          |
| 12              | S. Ambrogio                                 | F.4                          |
| 13              | S. Maria di Carignano                       | F.5                          |
| 14              | S. Matteo                                   | F.4                          |
| 15              | S. Filippo Forti                            | Via Lomellini. E.2.3         |
| 16              | S. Maria di Castello                        | Via S.M. di Castello. E.4    |

- |                  |                                 |                             |
|------------------|---------------------------------|-----------------------------|
| 17               | S. Maria delle Vigne            | E.3                         |
| 18               | S. Siro, Piazza S. Siro         | E.3                         |
| <b>Palazzi :</b> |                                 |                             |
| 19               | Balbi                           | E.2                         |
| 20               | Durazzo, Marcello o delle Scale | E.2                         |
| 21               | Reale                           | E.2                         |
| 22               | Ducale                          | F.4                         |
| 23               | del Municipio                   | F.3                         |
| 24               | Andrea Doria                    | C.12                        |
| 25               | Brignole o Rosso                | F.3                         |
| 26               | Pallavicini                     | F.3                         |
| 33               | Durazzo Girapallo               | Piazza dello Zerbino 12. H. |

- |                 |                                                   |                               |
|-----------------|---------------------------------------------------|-------------------------------|
| 29              | Imperiale, Piazza Campetto 8.                     | E. F. 3. 4                    |
| 30              | Pallavicini, Salita S. Bartolomeo degli Armeni 3. | H.3                           |
| 31              | Pallavicini, Piazza Fontane Morose 27.            | F.3.                          |
| 33              | Serra, Via Nuova 12                               | F.3.                          |
| 34              | Spinola, Via Nuova 5.                             | F.3                           |
| 35              | Spinola, Via all'Acquasola.                       | F. G. 4                       |
| <b>Teatri :</b> |                                                   |                               |
| 36              | Carlo Felice                                      | F.4.                          |
| 37              | Andrea Doria                                      | G.5                           |
| 38              | Apollo                                            | F.5                           |
| 39              | Colombo                                           | F.2.                          |
| 40              | Nazionale                                         | E.2.                          |
| 41              | Politeama (Anfiteatro)                            | Salita dei Cappuccini 19.     |
| 42              | Paganini, Via Caffaro 10.                         | E. F. 2. 3.                   |
| 44              | Legio (Palconi) Via Balbi 10.                     | E.2.                          |
| 45              | Vigne (Marionette)                                | Vico del Teatro delle Vigne 1 |
| 46              | Villa Negro                                       | F.3                           |
| 47              | Monumento di Cristof. Colombo                     | D.1.                          |
| 48              | Musica Istituto di                                | Via Mascherona 9.             |
| 49              | Posta delle lettere                               | F.4                           |
| 50              | R. Prefettura e Palaz. Ducale (22)                | F.3                           |
| 51              | Sicurezza Pubblica e Palaz. Ducale (22)           | F.2.                          |
| 54              | Tribunale di Commercio                            | Via S. Massimo                |
| 55              | R. Università                                     | E.2.                          |
| 56              | Zecca, Piazza dei Forni 5.                        | E. F. 2. 3.                   |

- Alberghi principali :**
- |                           |         |
|---------------------------|---------|
| a. Fider                  | E. 3.   |
| b. Italia                 | E. 3.   |
| c. Hotel de la Ville      | E. 3.   |
| d. Quattro Nazioni        | E. 3.   |
| f. Croce di Malta         | E. 3.   |
| g. Hotel de France        | E. 3. 6 |
| h. Albergo di Genova.     | F. 4.   |
| k. Albergo della Vittoria | E. 2.   |

1:13,500  
0 100 200 300 400 metri



| Cabs (a tariff in each) in the town : | One-h. | Two-h. | At night. |
|---------------------------------------|--------|--------|-----------|
| Per drive . . . . .                   | 1 —    | 1.50   | 2 —       |
| Per hour . . . . .                    | 1.50   | 2 —    | 2.50      |
| Each additional half-hour . . . . .   | — 75   | 1 —    | 1.50      |

Small articles of luggage are free; trunk 20 c. — The night-fares, beginning on the lighting up of the lighthouse, are the same for the one horse and two-horse cabs.

**Omnibuses** traverse the town in every direction, fare 10 c. From the Piazza Carlo Felice to the two stations, 20 c. — Smaller omnibuses run to places in the environs, but they are often crowded.

**Steamboats:** to *Leghorn* every week-day in 9 hrs.; to *Spezia* twice a week in 5-6 hrs.; to *Ortù Vecchia* and *Naples* 4 times weekly in 32-42 hrs.; to *Marseilles* every week-day in 18-20 hrs.; to *Nice* (p. 95) 5 times weekly in 9-10 hrs.; to *Sardinia* by *Leghorn* 3 times weekly. Embarcation in each case 1 fr. for each person, including luggage.

**Baths.** At the *Palazzo Spinola*, Salita S. Caterina, adjoining Bossola's music shop, handsomely fitted up; others at Via delle Grazie 11, and Piazza Sarzano 51. — **SEA BATHS** by the Molo Vecchio (Pl. D. E. 4): by the Cava and the Strega (Pl. F. G. 6), farther S.; also by the lighthouse (Lanterna; Pl. A. 4), but in July and August only, poorly fitted up. Swimmers are recommended to bathe from a boat. Sea-bathing places on the Riviera, see p. 96.

**Post Office** (Pl. 19), Piazza delle Fontane Morose, open 8 a.m. to 8 p.m. — **Telegraph Office** in the Palazzo Ducale (Pl. 22).

**Theatres.** *Carlo Felice* (Pl. 36), built in 1827, one of the largest in Italy, with five tiers of boxes, holding nearly 3000 persons; parterre 2, fauteuil 5 fr.; operas performed here. — *Paganini* (Pl. 42), Strada Caffaro 10. — *Potiteama* (Pl. 41), by the Villa Negro.

**Military Music** in the park of *Acqua Sola* (p. 94), daily in summer, 7-8 p.m., and on Sundays at 2 p.m. also, except during the great heat. In winter, during three months, the band plays in the evening in the *Piazza Deferrari* (p. 88).

**Photographs.** *Alfred Noack*, Vico del Filo 1, upstairs, not far from the cathedral of S. Lorenzo, good selection of views of N. Italy; *Arnulf*, Via Nuovissima 12; *Mangiagalli*, Via Nuovissima 7.

**Consulates.** *English*, Salita di S. Caterina; *American*, Salita de' Cappuccini, near the Acqua Sola.

**Physician:** *Dr. Breiting*, corner of the Salita Sta. Maria della Sanità (Pl. G. 3, 2), to be found in the morning in the *Protestant Hospital*, Vico Barnabiti 14, at the back of S. Bartolomeo. This institution is recommended to travellers overtaken by illness (a few private rooms). — **Dentist:** *Mr. Charles S. Bright*, Via Assarotti 14, 1st floor.

**Bookseller:** *Hermann Steneberg*, Via Roma 4. — **Goods-Agents:** *C. Jung-hans*, Salita S. Matteo 19; *C. Ruepprecht*, at the back of the church of S. Luca.

**English Church Service** in an apartment in the Via Assarotti (Pl. H. 3), *Presbyterian* at the Waldensian Church in the same street.

**Principal Attractions.** Walk in the morning on the *Gran Terrazzo* (p. 86); walk through the Via S. Lorenzo past the *Cathedral* (p. 86) to the Piazza Nuova; ascend to the *Madonna di Carignano* (p. 88) and return to the Piazza Fontane Morose. Then through the Via Nuova (p. 89), and visit the *Palazzi Rosso* (p. 90), *Durazzo* (p. 91), and *Balbi* (p. 92) (the mansions of the Genoese noblesse are generally shown between 11 and 4 o'clock, and probably earlier in summer), the *Monument of Columbus* (p. 93), and the *Palazzo Doria* (p. 93), and devote the afternoon to a drive to the *Campo Santo* (p. 95), after which the evening may be spent in the park of *Acqua Sola* (p. 94). \**Villa Pallavicini*, see p. 96.

The situation of Genoa, rising above the sea in a wide semi-circle, and its numerous palaces, justly entitle it to the epithet of 'La Superba'. The city is surrounded by extensive fortifications, dating from the beginning of the 17th cent., which have recently

been strengthened. From the lighthouse on the W. side, where the large barrack of *S. Benigno* affords quarters for 10,000 men, a broad rampart extends at some distance from the town up the hill, past the *Forte Begato* (1618 ft.) to the *Forte dello Sperone* (1693 ft.), the highest point, and then descends past the *Forte Castellaccio* (1253 ft.) to the mouth of the *Bisagno* which falls into the sea to the E. of Genoa, a circuit of about 9½ M. in all. The heights around the town are crowned with ten detached forts.

Genoa is the chief commercial town in Italy, and contains 130,000 inhab., or with the neighbouring suburbs 180,000. The annual imports are valued at 300 million fr., the exports at 120 million. Of the imports about one-third is from England, and the rest chiefly from France and North America.

From a very early period Genoa has been famous as a sea-port, and even in the time of the Romans it formed an outlet for the products of the extensive Ligurian coast-district. The town is believed to derive its name from the fact that the sea penetrates into the land here somewhat in the shape of a knee (*genu*). The most flourishing period of Genoa began in the middle ages, when the citizens successfully defended themselves against the Saracens. In 1119 they waged a victorious war against *Pisa*, which was then the mistress of the Tyrrhenian Sea. From that date the rival cities were almost permanently at war down to 1284, when a terrible naval battle took place between them at Meloria, on which occasion the Genoese captured 29 Pisan galleys, and sank 7 others. From that disaster Pisa never recovered, and Genoa now obtained the supremacy over the W. islands, Corsica, and nominally over Sardinia also. At a still earlier period she had participated in the Crusades, and secured to herself a busy trade with the Levant. She also possessed settlements at Constantinople and in the Crimea, in Syria and Cyprus, at Tunis and Majorca. The rivalry of the Genoese and *Venetians* was a fruitful source of wars and feuds during the 12-14th centuries, which at length were terminated by a decisive victory gained by the latter in 1380.

The internal history of the city was no less chequered than the external. The party conflicts between the great families of the *Doria* and *Spinola* (Ghibellines) on one side, and the *Grimaldi* and *Fieschi* (Guelphs) on the other, led to some extraordinary results. The defeated party used, at the expense of their own independence, to invoke the aid of some foreign prince, and accordingly we find that after the 14th cent. the kings of Naples and France, the counts of Monferrat, and the dukes of Milan, were alternately masters of Genoa. Nor was this state of matters materially altered by the revolution of 1339, by which the exclusive sway of the nobility was overthrown, and a *Doge* invested with the supreme power. In the midst of all this confusion the only stable element was the mercantile *Banco di S. Giorgio*, which had acquired extensive possessions, chiefly in Corsica, and would have eventually absorbed the whole of the republic and converted it into a commercial aristocracy, had not Genoa lost its power of independent development by becoming involved in the wars of the great powers. *Andrea Doria* (p. 94), the admiral of Emperor Charles V., at length restored peace by the establishment of a new oligarchic constitution, and the unsuccessful conspiracy of Fieschi in 1547 was one of the last instances of an attempt to make the supreme power dependent on unbridled personal ambition. The power of Genoa was, however, already on the wane. The Turks conquered its Oriental possessions one after another, and the city was subjected to severe humiliations by its powerful Italian rivals, as well as by the French, who took Genoa in 1684, and by the Imperial troops by whom Genoa was occupied for a few days in 1746. In 1736 the ambition of *Theodore de Neuhof*, a Westphalian nobleman, occasioned great disquietude to the republic. He was created king by the inhabitants of

Corsica, who had been subjects of Genoa, but now threw off their yoke. The Genoese pronounced the newly elected king guilty of treason, in consequence of which the usurper fled, and, with the aid of the French, they succeeded in re-establishing their supremacy over Corsica, but were soon afterwards (1768) obliged to cede the island to their new ally. After the battle of Marengo (1800) Genoa was taken possession of by the French. In 1805 it was formally annexed to the Empire of France, and in 1815 to the Kingdom of Sardinia.

The beauty of its situation, and the interesting reminiscences of its ancient magnificence, render a visit to Genoa very attractive, especially to the traveller who is visiting Italy for the first time. To the historian of art the Renaissance palaces of the Genoese nobility are objects of extreme interest, surpassing in number and magnificence those of any other city in Italy.

Many of these buildings were erected by *Galeazzo Alessi* (a pupil of Michael Angelo, born at Perugia 1500, d. 1672), whose example was generally followed by subsequent architects. In spite of occasional defects, the architecture of the city is of an imposing and uniform character, and great ingenuity has been displayed in employing an unfavourable and limited site to the best advantage. The palaces moreover contain a considerable number of works of art, while *Rubens*, who resided at Genoa in 1606-8, and *Van Dyck* at a later period, have contributed to preserve the memory of many members of the noblesse. The native school of art, however, never rose to importance, and was far from being benefited by the zeal of its artists in painting façades. The chief painters were *Luca Cambiaso* (1527-85), *Bernardo Strozzi*, surnamed *Il Cappuccino* or *Prete Genovese* (1581-1644), *Giov. Batt. Paggi*, and *Benedetto Castiglione*.

The \***Harbour** (*Porto*) consists of a semicircular bay, about 2 M. in diameter, which is protected from the open sea by two long and substantial piers. That on the E. is the *Molo Vecchio*, with the small old lighthouse and the *Porta del Molo*, erected by Galeazzo Alessi in 1550; that on the W. the *Molo Nuovo*, adjoining which rises the new lighthouse, or *Lanterna*, with its dazzling reflectors 410 ft. above the sea-level. The summit, reached by 375 steps, commands a fine view, especially by evening light (fee 1 fr.), and the arrangements of the interior may also be inspected.

The Duke of Galliera (d. 1876) having presented 20 million francs for the improvement of the harbour, on condition that the government and the city would advance the remainder of the required sum, extensive alterations will probably soon take place here. On the Cava, below Carignano (Pl. F, 5, 6), a large new Molo is to be constructed, while the present Molo Nuovo is to be so lengthened that it will continue to be the outer pier. Extensive quays connected by rails with the main line are also projected, with a view to enable the largest vessels to unload without lighters.

On the E. side of the present harbour, near the Piazza Cavour and the Via Vittorio Emanuele (Pl. E. 4), lies the enclosed *Porto Franco* with its extensive bonded warehouses (visitors admitted). The *Dogana* (Pl. 3, E. 3) occupies the building of the former *Banco di S. Giorgio* (p. 84). The large hall is embellished with statues of men who have deserved well of the town, some of them of the 15th cent. On the upper floor are the Archives.

The central part of the harbour is bordered by a lofty wall with arcades. the marble platform of which, called the \**Terrazzo di Marmo*. 20 paces in width, affords an excellent promenade, especially early in the morning. There are two approaches to the terrace, one opposite the Hôtel de la Ville (Pl. c; E. 3; known as the 'Scala della Rotonda'), and another to the N., opposite the Hôtel des Quatre Nations (Pl. d; E. 2, 3), both of which are closed at dusk. — A row in the harbour, for which numerous boatmen offer their services, is also recommended (2 fr. per hour for 1-4 persons, but a bargain should be made).

Near the S. end of the Via Vittorio Emanuele, on the E. side, is the small PIAZZA CATTANEO, with the palace of that name, a room in which contains eight pictures by *Van Dyck*. — Not far from this point is the church of *Sa. Maria di Castello* (Pl. 16; E. 4), occupying the site of an ancient Roman castle, and mentioned in history as far back as 1042. It contains several pictures by Genoese painters; in the transept is a Madonna by *Justus d'Allamagna*, 1451.

Instead of walking through the noisy and bustling streets near the Terrazzo di Marmo, the traveller is recommended to take the following route. Leaving the piazza of the station, we descend by a lane opposite the corner of the Hôtel de Londres to the *Via di Prè* (Pl. D, E, 2), which we follow. We then cross the *Piazza della Darsena*, from which the *Via della Fontana* leads, to the left, to the *Annunziata* (p. 91), and follow the *Via del Campo* (Pl. E, 2, 3). An inscription at the back of the fountain in the small *Piazza Vacchero*, obliquely opposite the Hôtel d'Italie (Pl. b; E. 3), records that Giulio Cesare Vacchero was executed here for high treason in 1628, while his children were banished, and his house razed to the ground. From the *Piazza Fossatello* (Pl. E, 3) the *Via Lomellini* leads to the left to the *Annunziata* (p. 91). — Following the *Via di Fossatello* and the *Via S. Luca*, — in a side street to the left of which is the church of *S. Siro* (Pl. 18; E. 3), erected in 1576, modernised in 1820, containing statues by *Taddeo*, and frescoes by *Giov. Batt. Carlone*, — we next reach the PIAZZA BANCHI, in which is situated the **Exchange** (*Loggia de' Banchi, Borsa*, Pl. 7; E. 3), erected at the end of the 16th cent. from plans by *Alessi*, and adorned with a sitting figure of *Cavour* in marble by *Vinc. Vela*. — The narrow but handsome \**Via degli Orefici* (Pl. E, F, 3; at the beginning of which, on the right, is a door with an interesting Adoration of the Magi in relief, of the middle of the 15th cent.), and then the *Via Luccoli*, lead to the *Piazza delle Fontane Morose* (p. 89). To the S. of the Exchange we traverse the *Via S. Pietro della Porta* to the *Via S. Lorenzo*, and the PIAZZA S. LORENZO, in which rise the new *Banca Nazionale* (Pl. 5), and the cathedral of—

\***S. Lorenzo** (Pl. 9; E, F, 4), erected in 1100 on the site of an earlier edifice, and subsequently so much altered, that it now presents three distinct styles, the Romanesque, the French Gothic, and the Renaissance. The lower part of the façade, which consists of alternate courses of black and white marble, was constructed in

the 13th cent. in the style peculiar to the French churches; the two lower of the recumbent lions with which it is adorned on the right and left of the steps, are modern. The sides of the principal portal are decorated with good reliefs representing the early history of Christ (end of 13th cent.); the sculptures in the lunette, (Christ and the emblems of the four evangelists, with the martyrdom of St. Lawrence below them, are inferior works of the same period. The sculptures at the entrances to the aisles are of the 12th century.

The INTERIOR, constructed in 1307, is borne by the columns of the earlier church. Beyond the massive substructure of the towers, which forms a kind of atrium, lies the nave with its aisles, covered with cylindrical vaulting and a dome (which last was constructed by Alessi in 1567), and borne by sixteen Corinthian columns of coloured marble and four buttresses, above which is another series of columns alternating with pillars. On the right, over the second side-portal, is the monument of a bishop of 1336 with reliefs and statues, the sarcophagus being supported by four lions. In the chapel to the right of the choir a Crucifixion by *Fed. Baroccio*, and statues by *P. Francavilla*. In the choir, handsome stalls with inlaid-work by *Franc. Zabello*. In the chapel to the left of the choir a statue and six pictures by *L. Cambiaso*. In the left transept, seven statues by *Gugl. della Porta*. — The second chapel to the left of the entrance, that of °S. GIOVANNI BATTISTA, erected in 1451-96, contains in a stone area of the 13th cent. relics of John the Baptist, brought from Palestine during the Crusades. The six statues at the sides and the reliefs above them are by *Matteo Civitani* (d. 1501); the Madonna and John the Baptist by *Andrea Sansovino* (15' 3); the canopy and the other sculptures by *Giacomo* and *Guglielmo della Porta* (d. 1532). The external decoration of the chapel is in the Gothic style, with admirable reliefs above (not easily seen; best light in the afternoon). — In the sacristy is preserved the *Vaso Catino*, the vessel out of which the Saviour and his disciples are said to have partaken of the paschal lamb, and in which Joseph of Arimathea is said to have caught some drops of the blood of the Crucified (a fine glass vessel, captured by the Genoese at Cesarea during the Crusades, shown by permission of the municipio only), and other precious relics.

Farther on in the PIAZZA NUOVA is **S. Ambrogio** (Pl. 12; F. 4), a church of the Jesuits founded by Genoese nobles, and overladen with showy decorations of the close of the 16th cent.

3rd Altar on the right: Assumption by *Guido Reni*. High-altar-piece, the Circumcision, by *Rubens*. The four black monolith columns are from Porto Venere (p. 115). First chapel on the left, Martyrdom of St. Andrew, by *Semino*, the Elder. 2nd Altar on the left: *Rubens*, St. Ignatius healing a man possessed of an evil spirit.

In the same piazza is situated the **Palazzo Ducale** (Pl. 22; F. 4), now *Palazzo della Prefettura*; on the upper part of the façade are six statues of captives, above which are trophies. This edifice, the ancient residence of the doges, was founded at the close of the 13th cent., but was entirely remodelled in the 16th, and modernised in 1777 after a great fire. The handsome flight of steps is by *Rocca Pennone* (1550).

This is the best starting point for a visit to the church of S. Maria in Carignano, situated on one of the highest points at the S. E. end of the city, and affording the best general survey of Genoa. Opposite the Palazzo Ducale we follow the Salita Pollajuoli, ascend



the Stradone Agostino to the right, cross the Piazza Sarzano to the left, and proceed to the right through the Via al Ponte Carignano to the *Ponte Carignano*, a bridge across a street nearly 100 ft. below, leading direct to the church.

**S. Maria in Carignano** (Pl. 13; F, 5; 174 ft. above the sea-level), begun in accordance with designs by *Galeazzo Alessi* in 1555, but not completed till 1603, is an imitation of Bramante's original plan of St. Peter's at Rome, and is remarkable for its harmonious proportions, especially in the interior. The baroque statues below the dome are by *Puget*, *Parodi*, and *David*: the paintings by *Piola*, *Maratta*, *Guercino*, *Procaccini*, and *Cambiaso*. The \*VIEW from the highest gallery of the dome (368 ft. above the sea; 119 steps to the first gallery, thence to the top 130, ascended by an easy and well-lighted staircase) embraces the city, harbour, and fortifications, and the well peopled coast (W. the *Riviera di Ponente*, E. the *Riviera di Levante*), bounded on the E. by the picturesque promontory of S. Martino d'Albaro, and the bold Montefino beyond it (p. 113), and to the S. by the vast blue expanse of the Mediterranean. (Sacristan 25 c.; his attendance for the ascent is unnecessary; best light in the morning.)

A little to the W. is the *Villa Mylius*, containing numerous pictures and sculptures, chiefly by modern masters.

From the Piazza Nuova we proceed to the left through the Via Sellai (Pl. F, 4) to the PIAZZA DEFERRARI (with a palace of that name, of the 18th cent., on the left), formerly Piazza S. Domenico (79 ft. above the sea).

From this piazza the Salita di S. Matteo, the second side-street to the left, leads to the small church of **S. Matteo** (Pl. 14), originally Gothic (1278), which contains numerous reminiscences of the Doria family, the façade being covered with inscriptions to their memory. The interior was altered in 1530 by the Florentine *Gianantonio Montorsoli*, who was invited to Genoa by Andrea Doria, and who, with his assistants, executed the whole of the fine sculptures with which the church is embellished. Above the high-altar is Doria's sword. To the left of the church are handsome cloisters with double columns, dating from 1308, with 17 ancient inscriptions relating to the Dorias, and remains of two statues of Andrea Doria (by Montorsoli, 1548) and one of Gianetto Doria (1577), which were mutilated during the Revolution in 1797. — A palazzo opposite, the lower half of which is covered with black and yellow marble, bears the inscription, '*Senat. Cons. Andreae de Oria, patriae liberatori munus publicum*'.

To the right in the Piazza Deferrari is situated the *Teatro Carlo Felice* (Pl. 36), built in 1826-28 (see p. 83). Adjacent is the —

**Accademia delle Belle Arti** (Pl. 1; F, 4). The vestibule below contains mediæval sculptures from the suppressed church of S. Domenico. On the first floor is the *Biblioteca Civica*, well stocked with modern works (about 40,000 vols.; open daily), and on the second floor a *Picture Gallery* (shown by the custodian).

The copying-room leads to a large saloon with ancient pictures, still unarranged, some of them only being numbered, chiefly by German and early Netherlands masters. The finest are: 69. Last Supper; 19. St. An-

tony; \*20. Two saints; 68, 97. 99. Miracles of St. Philip. Then 28 (9). *Manfredino da Pistoja* (1292), Annunciation, Christ in the house of Martha; \*21. *Umbrian School*, Crucifixion; *Ant. Scarini*, Entombment; *L. Cambiaso*, Holy Family. In the centre modern statues. Next a circular room and a saloon with large pictures by Genoese painters (*Piola, Deferrari, Ferrari, Fiasella*, etc.), and lastly two rooms with sculptures, chiefly modern (MUSEO PRINCIPE ODONE), and several others containing casts.

The Via Giulia leads from the academy towards the E. to the Porta degli Archi. On a terrace to the left of the gate stands **S. Stefano** (Pl. 11; G, 4), a Gothic church, the oldest parts of which date from the end of the 12th century. Above the high altar the \*Stoning of Stephen by *Giulio Romano*, one of his best works, taken (1530) to Paris by Napoleon in 1811, but restored in 1815. From the back of the church we may proceed to the left to the Acquasola (p. 94), or to Carignano to the right (p. 88).

Two broad streets lead towards the N.E. from the Piazza Deferrari: to the right the new *Via Roma*, leading straight to the Acquasola promenade (see p. 94); and to the left the VIA CARLO FELICE. On the left side of the latter, No. 12, is the *Palazzo Pallavicini* (Pl. 26; F, 3), now the property of the Durazzo family (p. 91). — We next come to the PIAZZA DELLE FONTANE MOROSE (Pl. F, 3). No. 17 in the piazza is the *Palazzo della Casa*, originally Spinola, adorned with five honorary statues in niches, of the 15th cent.; No. 27 is *Palazzo Lud. Stef. Pallavicini*, sumptuously fitted up in a modern style. — [In the Via Caterina, which leads from this piazza to Acquasola, No. 14, is the *Palazzo Spinola*, dating from the 14th and 16th centuries, and one of the finest older palaces of Genoa.]

Near the Piazza Fontane Morose begins a broad line of streets built in the 16th cent., extending to the Piazza dell' Acquaverde near the railway-station, under the names of *Via Nuova*, *Via Nuovissima*, and *Via Balbi*, and forming one of the chief arteries of modern traffic. In these streets are situated the most important palaces and several churches; some of the former should be visited for the sake of their magnificent staircases, which are among the most remarkable objects in Genoa. — On each side of these loftily situated streets a complete labyrinth of narrow lanes, occupied by the lower classes, descend to the left to the harbour, and ascend the hill on the right; here, too, the traveller will observe many interesting buildings.

The first of these main streets is the \***Via Nuova** (Pl. F, 3), which is flanked by a succession of palaces on both sides. On the right, No. 1, is the *Palazzo Ces. Cambiaso*, with a few pictures of the 16th and 17th cent. of the Italian and Netherlands schools. On the left, No. 2, *Palazzo Gambaro*, formerly Cambiaso. Right, No. 3, *Palazzo Parodi*, erected in 1567-81 by Gal. Alessi for Franco Lerario, containing frescoes by Luca Cambiaso, and others. Left, No. 4, \**Palazzo Cataldi*, formerly Carega, erected about 1560 for Tobia Pallavicini. Right, No. 5, *Palazzo Spinola*, by Gal. Alessi, possess-

ing an imposing vestibule, staircase, and colonnaded court, and a few pictures, chiefly of the Genoese (Luca Cambiosa) and Bologna schools, an equestrian portrait, and a Madonna by Van Dyck. Left, No. 6, *Palazzo Giorgio Doria*, containing several frescoes by Luca Cambiosa and other pictures (Castiglione, Shepherd and shepherdess; Van Dyck, Portrait of a lady).

Left, No. 10, *Palazzo Adorno*, also by Gal. Alessi (?), contains several good pictures, but is not always shown to visitors.

I. ROOM: *Rubens*, Hercules with the apples of the Hesperides, and Dejanira with an old woman holding the poisoned garment; *Guido Reni*, Judith; also works by *Guercino*, and others. — II. ROOM: *Bassano*, Holy Family; *Palma Vecchio*, Madonna and saints; *Paris Bordone*, Venus and Cupid; *Sebastian del Piombo*, Raising of the brazen serpent; *Rubens*, Madonna, and St. Francis receiving the stigmata. — III. GALLERY: *Andrea Mantegna* (?), Judith, Triumph over Jugurtha, and two scenes with Cupids; *Perino del Vaga*, Nativity of Mary; *Pellegrino Piola* (a Genoese who died young, 1630), Frieze with children.

Left, No. 12, *Palazzo Serra*, by Alessi, remodelled in the interior by De Wailly (d. 1798) and Tagliafico, contains a fine hall.

Right, No. 9, **Palazzo del Municipio** (Pl. 23), formerly *Doria Tursi*, erected by *Rocco Lurago* (16th cent.), has a handsome staircase and court, ingeniously adapted to the rising ground on which it stands.

The *Vestibule* is adorned with five frescoes from the life of the Doge Grimaldi, and a statue of Mazzini in marble. — In the large COUNCIL CHAMBER on the upper floor are portraits of Columbus and Marco Polo in mosaic. In the adjacent room a Madonna between two saints, by *Gerard David of Bruges* (not Van Eyck), and a Crucifixion with SS. Mary and John, by a good early Netherlands master (not Dürer); two other pictures inferior. Two letters of Columbus; large bronze tablet of A.D. 117, recording the judgment of Roman arbiters in a dispute between Genoa and a neighbouring castle. A cabinet to the left contains the violin of Paganini.

Left, No. 18, \***Palazzo Rosso** (Pl. 28), so named from its red colour, of the 17th cent., formerly the property of the *Brignole-Sale* family, with its valuable contents, a library, and \**Picture Gallery*, was presented to the city of Genoa in 1874 by the Marchesa Maria Brignole-Sale, wife of the Marchese Ferrarini, Duke of Galliera (p. 85), and by their son Filippo.

Ascending the handsome staircase, we pass through an *Antisala*, or ante-chamber, into the CAMERA DELLE ARTI LIBERALI, which, like the following rooms, derives its name from the subject of the ceiling paintings (by *Carlone*, *Parodi*, *De Ferrari*, and others), and contains three portraits of Doges of the Brignole family, of the 17th and 18th cent. — Traversing a small room (*Alcova*), we enter the principal saloons. I. STANZA DELLA GIOVENTÙ: \**Guercino*, Cleopatra; *Andrea del Sarto*, Holy Family, a replica of the picture in the Palazzo Pitti at Florence (No. 81; p. 378). — II. SALONE, the ceiling adorned with family armorial bearings; pictures by Genoese masters. — III. STANZA DELLA PRIMAVERA: *Paris Bordone*, Portrait of a Venetian lady; *Titian*, Portrait of an old man; *Dürer* (?), Portrait; \**Moretto*, Portrait of a botanist (1533); \**Van Dyck*, Marchese Giulio Brignole-Sale on horseback; *Tintoretto*, Doge; *Van Dyck*, Prince of Orange; *Titian*, Philip II. of Spain; \**Van Dyck*, Marchesa Paola Brignole-Sale; *Jac. Bassano*, Father and son; *Van Dyck*, Bearing of the Cross; *Paris Bordone*, Portrait of a man. — IV. STANZA D'ESTATE: *Luca Giordano*, Chlorinda liberating Olyntho and Sophronia; *Paolo Veronese*, Adoration of the shepherds (a sketch); *Lucas of Leyden* (?), \*Portrait, and St.

Jerome; *Caravaggio*, Raising of Lazarus; *Guido Reni*, St. Sebastian; *Lanfranco*, Bearing of the Cross. — V. STANZA D'AUTUNNO: *Leandro Bassano*, Portrait; *Bonifazio*, Adoration of the Magi; *Guido Reni*, Madonna; *Guercino*, Madonna enthroned; *Giov. Bellini* (more probably *Bernardino Licinio da Pordenone*, brother of the more celebrated master), Portrait of Franciscus Philetus. — VI. STANZA DELL' INVERNO: *Paolo Veronese*, Judith; *Jac. Bassano*, Penitent thief on the Cross; *Paris Bordone*, Portrait of a lady; *Van Dyck*, The tribute-money; *Rubens*, Portrait of an old man; *School of Leonardo da Vinci*, John the Baptist; *Procaccini*, 'Santa Conversazione'; *Murillo* (?), Holy Family; *Paris Bordone*, Holy Family; *Pellegrino Piola*, Holy Family. — VII. STANZA DELLA VITA DELL' UOMO: *Van Dyck*, Portrait; *Van Dyck*, The Marchesa Geronima Brignole-Sale with her daughter; *Paolo Veronese*, Portrait of a lady, Annunciation; *Garofalo*, Madonna and saints. — Catalogues for the use of visitors.

No. 13, opposite the Palazzo Rosso, is the **Palazzo Bianco**, erected in 1565-69, which was also for a long period the property of the *Brignole-Sale* family, but was afterwards inherited by the *Marchese De Ferrari*. The name has been given to it by way of contrast to the 'red palace' opposite.

In the CORRIDOR on the ground-floor, Janus and Jupiter, statues by *P. Francavilla*, a follower of *Giov. da Bologna*, both failures (1585). — On the FIRST FLOOR is the MARCHESA C. DONGHU's valuable collection of smaller works of art, chiefly cameos, and several pictures. — Here, also, is a PICTURE GALLERY, formed by the zealous collector *Dr. Giacomo Peirano*, and containing about 200 works, many of them dating from the 17th cent., several of which are interesting, although the celebrated names attached to some of the works may be questionable. The gem of the collection is a variation of *Raphael's* Madonna of the Alva family (now in St. Petersburg), and named 'Madonna della Rovere', from the oak under the shade of which the holy family is reposing; the probability that the work is genuine is thought to be strengthened by the fact that it was originally at Savona, the birthplace of Pope Julius II. (Rovere); *Dürer's* Adam and Eve is painted from the famous engraving executed by that master in 1504. A Madonna by *Giov. Bellini*, a Lucrezia by *Marco d'Oggiono*, and several works by *Francia*, *Murillo*, *Zurbaran*, *Rembrandt*, and the pictures of *Cambiaso*, *Strozzi*, and other Genoese masters also deserve notice. The gallery is open daily, 11-4, except on Sundays and festivals.

Crossing the small piazza in front of these palaces, we enter the VIA NUOVISSIMA (Pl. E, 3). At the end of this street to the left, No. 13, is the *\*Palazzo Balbi*, by Gregorio Petroni (18th cent.), through which a fine view is obtained of the lower lying Via Lomellini. — In the *Piazza dei Forni*, obliquely opposite, are the old *Zecca* or mint, an old Palazzo Lomellini, now the *Istituto Tecnico*, and the *Palazzo Centurioni*, richly embellished with marble, and containing several pictures.

In the Piazza dell' Annunziata (Pl. E, 2) is the Capuchin church of **\*S. Annunziata** (Pl. 10), erected in 1587, with a portal borne by marble columns, the brick façade being otherwise unfinished. It is a cruciform structure with a dome, the vaulting being supported by twelve fluted and inlaid columns of white marble, richly gilded and painted. This is the most sumptuous church at Genoa.

In the broad and handsome VIA BALBI (Pl. E, 3), on the right, No. 1, is the **\*Palazzo Marcello Durazzo** (Pl. 20), formerly *Filippo Durazzo*, or *della Scala*, erected in the 17th cent. by *Bartolommeo*

*Bianco* of Como for the Balbi family. This edifice is remarkable for its handsome façade with an imposing gateway and balcony, its fine vestibule, and the superb staircase (on the left), added by *Andrea Tagliafico* at the close of the 18th cent. On the first floor is the \**Galleria Durazzo-Pallavicini*, formed by uniting a collection formerly here with another from the Palazzo Pallavicini (p. 89), and shown daily, 11-4.

Crossing the *Antisala*, which contains modern busts of the Durazzo-Pallavicini family, we first enter the SALONE, a hall with Bolognese works of the 18th cent. representing scenes from the life of Achilles. The gallery also possesses numerous paintings of the 17th cent. by the *Caracci*, *Guido Reni*, *Domenichino*, and other masters of the Bologna school, of which we enumerate the most interesting only. We proceed to the right, W. wing. I. Room: *Van Dyck*, Two portraits of children; *Rubens*, Philip IV. of Spain; *Titian*, Ceres and Bacchus; *Caravaggio*, Cupid and Psyche. — II. Room: Genoese works of inferior value. — III. Room: *Bern. Strozzi*, surnamed *Il Cappuccino*, Mater Dolorosa; *Lucas of Leyden*, Entombment and Virgin with saints and the donor and his wife, a winged picture; *A. Dürer*, Repose on the Flight to Egypt; *Jac. Ruysdael*, Landscape, with figures by *Wouverman*. — IV. Room: *Andrea del Sarto*, The Magi; *Perino del Vaga*, Caritas; *Rubens*, Portrait of Ambrogio Spinola. We next visit the rooms in the E. wing. V. Room: School of *Andrea del Sarto*, Madonna and Child; *Paolo Veronese*, Betrothal of St. Catharine; *Perino del Vaga*, Holy Family; *Van Dyck*, Portrait; *Tintoretto*, Portrait of the Marchese Agostino Durazzo; *Rubens*, Portrait of himself. — VI. Room: Genoese masters, such as: *Il Cappuccino*, Portrait of a prelate; also, *Titian*, Mary Magdalene. — VII. Room: *Guercino*, Mucius Scaevola; *Lucas of Leyden*, Descent from the Cross; *Dürer* (?), Holy Family; *Van Dyck*, James I. of England with his family. — VIII. Room: *Schidone*, Madonna; *After Raphael*, Madonna (original in Naples). — The other rooms, which also contain several pictures, are generally closed. Two silver vases by *Benvenuto Cellini* are likewise worthy of inspection. — The library contains 7000 vols., including many specimens of early printing.

To the right, in the corner of the colonnaded court, is the approach to the office, where *permessi* for the Villa Pallavicini at Pegli are issued (comp. also p. 96).

On the right side of the street, No. 5, is the \**Palazzo dell' Università* (Pl. 54), begun as a Jesuit college by *Bart. Bianco* in 1623, and erected into a university in 1812. The rich court and staircase are probably the finest structures of the kind at Genoa. The building contains a library, a natural history museum, a small botanical garden, and several bronzes by *Giovanni da Bologna*.

The second palace on the left side, No. 4, is the \**Palazzo Balbi-Senarega* (Pl. 19), begun early in the 17th cent. by *Bart. Bianco*, and afterwards enlarged by *Pier Ant. Corradi*. It still belongs to the family who built it, and after whom the street is named. The superb court, surrounded by Doric colonnades, affords a beautiful glimpse of the orangery. The *Picture Gallery* on the first floor is worthy of a visit; admission daily, 2-4.

I. Room, adorned like the others with ceiling paintings by Genoese artists. *Van Dyck*, Francesco Maria Balbi on horseback; *Bern. Strozzi*, Joseph explaining the dream. — II. Room. *Titian*, St. Jerome; *Rubens*, Christ and St. John as children; *Titian* (more probably *Giov. Ant.* or *Bernardino Licinio da Pordenone*), Madonna with St. Catharine, St. Dominicus, and the donors; *Guid. Ferrari*, Holy Family; *Van Dyck*, Madonna with the pomegranate (della Melagrana); *Michael Angelo* (?), Gethsemane. —

III. ROOM. Three portraits of the Balbi family by *Van Dyck* (the head of Philip IV. in the equestrian piece is said to have been substituted by *Velasquez* for that of the Balbi, who had meanwhile been banished). — IV. ROOM. *Caravaggio*, Conversion of St. Paul; portraits by *Tintoretto*, *Allori*, *Van Dyck*, and *Holbein* (?); then, *Lucas of Leyden* (?), Madonna and Nativity. — V. ROOM. Four children, sketches by *Perino del Vaga*; small pictures by *Schiavone*; market-place, by one of the *Bassanos*. — VI. GALLERY. *Perino del Vaga*, Holy Family; *Van Dyck*, Holy Family; *Mening* (?), Christ on the Cross; *Fra Filippo Lippi* (?), Communion of St. Jerome; *Titian* (?), Portrait of himself.

Next, on the left, No. 6, *Pal. Durazzo*, with a simple colonnade.

Left, No. 10, **Palazzo Reale** (Pl. 21; E, 2), erected in the 17th cent. by the Lombard architects *Franc. Cantone* and *Giov. Ang. Falcone* for the Durazzo family, and extended by *Carlo Fontana* of Rome at the beginning of the 18th cent., was purchased in 1815 by the royal family, and restored by Carlo Alberto in 1842. It contains handsome staircases and balconies and sumptuously furnished apartments (shown daily, except when the royal family is in residence). The pictures and antiquities are of no great value.

Ante-Chamber: Battle-pieces by *Burrasca*. Room on the right: *Van Dyck*, Portrait of a lady; good portrait of the Lombard school, attributed to *Leon. da Vinci*; *Perino del Vaga*, Holy Family. To the right a handsome gallery with rococo-painting and a few ancient and modern statues: on the right, Apollo and Apollino, on the left, Mercury; at the end, Rape of Proserpine by *Schiaffino*. On the left are three small rooms; the second contains a Crucifixion by *Van Dyck*; the third, *Adulteress* by *Moretto*. The throne-room is adorned with two large pictures by *Luca Giordano*.

The terrace commands a fine view of the city and harbour.

In the PIAZZA ACQUAVERDE (Pl. 47; D, 1) rises the **Statue of Columbus**, who is said to have been born at *Cogoleto* (p. 97) in 1459. It was erected in 1862, and stands on a pedestal adorned with ships' prows. At the feet of the statue, which rests on an anchor, kneels the figure of America. The monument, which consists entirely of white marble, is surrounded by allegorical figures in a sitting posture, representing Religion, Geography, Strength, and Wisdom.

Between these are reliefs of scenes from the history of Columbus, with the inscription of dedication: 'A *Cristoforo Colombo la Patria*', and '*divinato un mondo lo avvinse di perenni benefizi all' antico*'. — [On the house No. 9, Via Carlo Alberto, near the Piazza della Darsena (p. 86; Pl. E, 2), a niche contains a small *Statue of Columbus*, with the inscription, '*Dissi, volli, credi, ecco un secondo sorgere nuovo dall' onde ignote mondo*'.]

Opposite the monument is the *Palazzo Furrigiana*, with a marble frieze representing scenes from the life of Columbus and an inscription. — The Via di Circonvallazione (p. 95), now in course of construction, will eventually terminate in the Piazza Acquaverde, as shown by our Plan.

In the PIAZZA DEL PRINCIPE (Pl. C, D, 1, 2), to the W. of the station, No. 4, is situated the long **\*Palazzo Doria** (Pl. 24), presented in 1522 to *Andrea Doria*, the 'padre della patria' (d. 1560, at the age of 95). It was remodelled in 1529 from designs by *Giov. Ang. Montorsoli*, and adorned with frescoes by *Perino del Vaga*, a pupil of Raphael.

The long Latin inscription on the side next the street records that *Andrea d'Orta*, admiral of the Papal, Imperial, French, and native fleets, in order to close his eventful career in honourable repose, caused the palace to be rebuilt for the use of himself and his successors. His praises were thus sung by Ariosto — 'questo è quel Doria, che fa dai pirati sicuro il vostro mar per tutti i lati'. — The finest of the FÆSCOEES by *Perino del Vaga* (restored in 1845), which in many respects recall the paintings of Raphael, are those on the ceiling, vaulting, and lunettes of the great-entrance hall, representing scenes from Roman history; a corridor hung with portraits of the Doria family, a saloon with a large ceiling-painting representing Jupiter overthrowing the Titans, and a room with the love adventures of Jupiter. The Titan saloon also contains a portrait of the aged prince with his favourite cat, and a superb chimney-piece. The elder branch of the Doria family, to whom the palace now belongs, generally resides at Rome.

The garden of the palace, extending towards the harbour, contains an extensive Loggia with arcades. The gardens on the hill opposite, with a statue of Hercules (*'Il Gigante'*) in a niche, also belong to the estate.

Farther on, in the direction of the Molo Nuovo, stretches the new and shadeless *Passo Nuovo* promenade, which, together with the *Via Milano* (Pl. C, B, 2), runs above the extensive railway magazines (*Magazzini Generali*), and commands a fine \*view. — In this road, beyond the railway, lies the *Palazzo dello Scoglietto*, the property of Sign. Vitale Rosazza, the charming gardens of which also command a fine view (gardener, 1 fr.).

The *Molo Nuovo* and the *Lighthouse*, see p. 85.

On the coast, farther to the W., lies the suburb of *Sampierdarena*, or *S. Pier d'Arèna* (cab with one horse 2, with two horses 2½ fr.), with 1700 inhab. and numerous palaces and gardens, including the *Palazzo Spinola*, and the *Palazzo Scassi*, formerly Imperiali, with a pleasant garden, both probably erected by Gal. Alessi. The church of *S. Maria della Cella* contains frescoes of the Genoese school. Railway station, see p. 96.

The most favourite promenade is the small park of \***Acqua Sola** (Pl. G, 3, 4; 137 ft. above the sea), adorned with a fountain, situated on an eminence at the N.E. end of the town (approached most conveniently from the Piazza delle Fontane Morose by the Salita S. Caterina. The grounds were laid out in their present form on part of the old ramparts of the town in 1837. During the military concerts (p. 83) on Sunday afternoons the grounds are crowded. Pleasant views to the E. and S., finest towards the sea. Adjoining the promenades of Acqua Sola on the N. is the \***Villa Negro** (Pl. 46; reached direct by the Salita delle Battistine, to the right of the Via Nuova), the property of the city, and open to the public, with a well-kept garden, a small museum of Natural History (open on Sundays), and the beginnings of a Zoological garden. Winding promenades ascend hence to a bastion at the back of the villa, about 150 ft. above Acqua Sola, commanding a fine survey of the city, the harbour, and environs. — The walk may be pleasantly extended thus: from Acqua Sola proceed to the S. by *Mura S. Stefano*, then by *Mura Sta. Chiara* (turn to the left and follow the town walls), *Mura del Prato* (to the left, below, is the *Manicomio*,

or lunatic asylum), and then by *Mura delle Cappuccine*, and *Mura della Strega*, to the *Piazza della Cava* (Pl. F, 6). From this point we may proceed either to *S. Maria in Carignano* (p. 88), or to the *Molo Vecchio* (p. 85).

The **Via di Circonvallazione**, a magnificent route, which will vie in beauty with the Corso Vittorio Emanuele at Naples, is now in course of construction on the hills at the back of the town. It is to begin at the Piazza Acquaverde (p. 93; Pl. D, 1, 2; 66 ft. above the sea-level); and is to ascend gradually to the *Albergo dei Poveri* (Pl. E, F, 1, 2; 318 ft. above the sea), a hospital founded in the 17th cent., and last extended in 1835, accommodating 1300 persons. It will then lead along the slope in long windings, and across a viaduct, to the *Piazza Manin* (Pl. H, 3; 329 ft.). The latter half is now completed. Near the Piazza Manin is situated the *Palazzo Gropallo* (Pl. 28) in a large garden.

The **\*Campo Santo** (*Cimitero di Staglieno*, opened at 10 a.m.) situated on the slope of the valley of the *Bisagno*,  $1\frac{1}{2}$  M. from the town, is reached from the Piazza Deferrari (p. 88) by the Via Giulia, Via S. Vincenzo, and *Porta Romana* (Pl. H, 4; cab there and back 5 fr.). It was laid out with considerable taste in 1867, and contains several good \*monuments. One of the finest is that of March. Tagliacarne in the lower row on the right, above No. 359. The whole arrangement of the cemetery is interesting, as also the rotunda in the upper row, the internal gallery of which is borne by monolithic columns of black marble. The large pipes which are seen crossing the valley in the vicinity belong to the water-works of the city. — The cemeteries of the non-Romanists are shortly to be transferred hither.

**Excursions.** To the W. to *Pegli* (=Villa Pallavicini), a station on the railway. see p. 96, or reached in  $1\frac{1}{4}$  hr. by carriage (with two horses 7 fr.). To the E. to *S. Margherita* (by railway), and thence to *Portofino*, see p. 42.

## 16. From Genoa to Nice. Riviera di Ponente.

116 M. RAILWAY in  $6\frac{1}{2}$ -8 hrs.; fares 21 fr. 5, 14 fr. 90, 10 fr. 65 c. *in gold*. A slight saving is effected by booking to the frontier-station Ventimiglia only (fares 17 fr. 20, 12 fr. 5, 8 fr. 60 c. *in paper*), where there is ample time to procure a new ticket. — STEAMBOAT 5 times weekly in 9-10 hrs.; vessels of the Italian *Peirano Danovaro Comp.* on Friday at 8 p.m., returning from Nice on Wed. at 9 a.m., reaching Genoa at 6 or 7 p.m.; fares, including dinner, 1st class 32<sup>1</sup>/<sub>2</sub>, 2nd 22<sup>1</sup>/<sub>2</sub>, 3rd 12 fr.

The **\*CARRIAGE ROAD** along the charming *Riviera di Ponente*, the famous *Route de la Corniche*, will however still be preferred by many travellers, if not for the whole distance, at least for the most beautiful parts of the route, especially where the view is lost in passing through the numerous railway-tunnels, as between Savona and Loano, and between San Remo and Nice. This journey is very attractive. The road affords a delightful succession of varied landscapes, traversing bold and lofty promontories, wooded hills, and richly cultivated plains near the coast. At some places it passes precipitous and frowning cliffs, the bases of which are washed by the surf of the Mediterranean, while the summits are crowned with



the venerable ruins of towers, erected in bygone ages for protection against pirates. At other places extensive plantations of olives, with their grotesque and gnarled stems, bright green pine-forests, and luxuriant growths of figs, vines, citrons, oranges, oleanders, myrtles, and aloes meet the view, and even palms are occasionally seen (at S. Remo and Bordighera). Many of the towns are picturesquely situated on gently sloping heights (Porto Maurizio, S. Remo, Bordighera, Ventimiglia); others, commanded by ancient strongholds and castles, are perched like nests among the rocks (Roccabruna, Eza). Small churches and chapels peering from the sombre foliage of cypresses, and gigantic grey pinnacles of rock rising proudly above the smiling plains, frequently enhance the charms of the scenery. Finally, the vast expanse of the sea, with its ever varying hues, forms one of the chief attractions. At one time it is bathed in a flood of sunshine, at another its beautiful blue colour arrests the eye; or while the shore immediately below the spectator is lashed with wild breakers, the snowy crests of the waves are gradually softened to view in the purple distance.

The railway skirts the coast, and runs parallel with the high road as far as Savona. The numerous promontories are penetrated by tunnels. 2½ M. S. *Pier d'Arena*, see p. 94; 3½ M. *Cornigliano* (\**Hôtel Beau Séjour*), with numerous villas, well adapted for a prolonged stay in the months of April and May.

5 M. *Sestri Ponente* (11,000 inhab.) also possesses a number of villas, a church adorned with frescoes, and busy wharves. The *Grotta* of Sestri has been known for 200 centuries. The hotel is recommended for a visit of some duration (pension 8 fr.).

6 M. **Pegli** (\**Grand Hôtel de Pegli*, formerly *Palazzo Lomelli*, with garden, pension 9-11 fr.; *permessi* for the *Villa Pallavicini* obtained here, see below; *Hôtel Gargini*; these two on the coast; \**Hôtel d'Angleterre*, opposite the station), a small sea-bathing place, which attracts numerous visitors from Genoa, is adapted, like *Cornigliano* and *Sestri*, as a resting-place on the way to the favourite wintering places on the Riviera. A number of pleasant villas are also situated here, such as the *Villa Rostan*, *Elena Doria*, and particularly the beautiful \**Villa Pallavicini*, which forms a favourite object for an excursion from Genoa (comp. p. 95; *permesso*, see p. 92; no admittance after 3 p.m.).

The villa is immediately to the left on leaving the station. One of the gardeners (fee 1-2 fr. for 1 person, more for a party) of the *Marchesa* conducts visitors through the grounds and park, which extend to a considerable height on the slopes rising from the coast, and display a rich profusion of oleanders, azaleas, camellias, etc. Several points of view afford delightful prospects of Genoa, the sea, coast, and mountains. On the highest of these points stands a castle in the mediæval style with a tower, which affords an extensive and magnificent panorama. Around it are indications of a simulated siege, the mausoleum of the fallen commandant, and the ruin-strewn burial-place of his heroes. Farther on is a stalactite grotto with a subterranean piece of water, over which visitors are ferried, and a striking glimpse under the bridge of the lighthouse of Genoa and the sea; kiosques in the Pompeian, Turkish, and Chinese style, obelisk, fountains, etc. may also be inspected. The gardens also contain examples of the coffee, vanilla, cinnamon, pepper, sugar-cane, camphor, and other tropical plants, some of them remarkably fine.

8 M. *Prà*, another small ship-building place; 9 M. *Voltri* (Al-

bergo Svizzero), with 11,000 inhab., which carries on a considerable traffic in 'confitures', situated at the mouth of the *Ceruso* in a fertile plain sprinkled with villas.

Beyond Voltri numerous tunnels and bridges. 13½ M. *Arenzano*; beautiful retrospect of the coast as far as Genoa. 16 M. *Cogoleto*, the supposed birthplace of Columbus (p. 93). The house in which he is said to have been born, now a poor tavern, bears the inscription:—

*Hospes, siste gradum. Fuit hic lux prima Colombo;*  
*Orbe viro majori heu nimis arcta domus!*  
*Unus erat mundus. 'Duo sunt', ait ille. Fuere.*

20½ M. *Varazze*, or *Voragine*, a town with 8000 inhab., is a considerable ship-building place. The coast on both sides of it is rocky, and there are numerous cuttings and tunnels.

23 M. *Celle*; 25 M. *Albissola*, at the mouth of the *Sansobbia*, and —

27½ M. *Savona* (*Rail. Restaurant; Albergo Svizzero; Roma; Italia*), a town with 20,000 inhab., the capital of the Montcotte department under Napoleon I., is charmingly situated amidst lemon and orange gardens. The harbour, commanded by a fort, presents a busy scene. The *Cathedral* of 1604 contains several good pictures. The handsome theatre, erected in 1853, is dedicated to the poet *Chiabrera* (1552-1637), a native of the place. Savona was the birthplace of the popes Sixtus IV. and Julius II. (della Rovere). Pius VII. was once detained as a prisoner here for some time.

31 M. *Vado*. On this side of the extensive *Capo Bergeggi* a fine \*retrospect of the Riviera as far as Genoa is enjoyed. Then a tunnel and galleries, through the arches of which the sea and the small island of *Bergeggi* are seen. The construction of the line was attended with much difficulty here, and several long tunnels are traversed. 35 M. *Spotorno*; 37 M. *Noli*, a small town shaded by dense olive-groves, with the ruins of a castle.

42 M. *Finalmarina* (*Hôtel de Venise*) is the seaport and principal part of the town of *Finale*, which consists of three different villages. To the right lies *Borgo*, the oldest part, with a castle and a cathedral with double columns of white marble, a dome, and rich gilding; and farther to the E. is *Finalpia*. — 45½ M. *Pietraligure*, with the ruins of a castle in the middle of the village. 48 M. *Loano* (*Europa*); to the right of the line are two suppressed monasteries, of which *Monte Carmelo*, the higher, erected by the Dorias in 1609, commands a fine view. The large twelve-sided church of the village was also erected by the Dorias. Beyond (50 M.) *Ceriale*, with its ancient fortifications, the mountains recede. The line now quits the coast and traverses olive groves, vineyards, and orchards.

53 M. *Albenga* (*Albergo Reale*), the *Albigaunum* of the Romans, an ancient town and episcopal residence. About ¼ M. to the E. of the town are extensive remains of the *Ponte Lungo*,

a Roman bridge. Several châteaux of the old noblesse with lofty towers; cathedral with towers and elegant façade, all of brick. — To the left, from the sea, rises the rocky island of *Gallinara*, crowned with a tower.

The train crosses the *Centa* and skirts the promontory of *S. Croce*. Several tunnels. 57 M. *Alassio* (Hôtel de Londres; 4000 inhab.), a seaport, with orangeries containing palm-trees. 59½ M. *Laiqueglia*; beautiful retrospect of the wild *Capo della Croce*. The train penetrates the prominent *Capo delle Mele* by means of a long tunnel, and enters a valley thickly planted with olives. 62 M. *Pigna-Andora*; the village of Andora lies on the hill to the right; then several tunnels. 64½ M. *Cervo*, picturesquely situated on the slope; then (66 M.) *Diano Marina*, in a fertile plain; to the right, inland, *Diano Castello*. — The train enters a more extensive coast district, in which *Oneglia* and *Porto Maurizio* are situated.

69½ M. *Oneglia* (*Rail. Restaurant; Albergo del Vapore*), a beautifully situated town, with 8000 inhab. and a shallow harbour. The prison near the station somewhat resembles a church.

The train crosses the broad stony bed of the *Impero*, which the road crosses to the left by a neat suspension-bridge. — 71 M. *Porto Maurizio* (*Hôtel de France*), a town with 7000 inhab. and a good harbour, most picturesquely situated in the midst of dense olive-groves, and frequented of late as a winter residence. This town is the seat of the authorities of the district.

74 M. *S. Lorenzo*. The low, massive towers which now rise at intervals along the coast to the right of the line, some of which have been converted into dwelling-houses (others were removed on the construction of the railway), were erected for the defence of the country against Saracen marauders in the 9th and 10th centuries. 78½ M. *Rivaligure*. To the right on the hill stands the fortified *S. Stefano*, beyond which the broad *Val Taggia* is entered. The train crosses the *Taggia* and stops at (79½ M.) the station of that name (the village lies 3 M. up the valley). Beyond the next short tunnel a valley opens on the right commanding a charming view of *Bussana*, romantically perched on a rock. The village opposite to it is *Poggio*, which first becomes visible. The train now passes through the *Capo Verde* by means of a tunnel and reaches —

85 M. *San Remo*. — *Hotels and Pensions*. On the *W. Side of the Town*: GRAND HÔTEL DE LA PAIX, near the station, in a fine open situation (pension 10-15 fr.); \*GRAND HÔTEL DE LONDRES; \*HÔTEL DI SAN REMO, near the station; \*HÔTEL BELLEVUE, expensive; HÔTEL DE NICE; GRAND HÔTEL ROYAL, a handsome new building, finely situated; HÔTEL PARADIS, also new; \*PENSION ROSE, recently enlarged (10-15 fr.), and behind it, HÔTEL PENSION MARNER (new), both with pleasant gardens; PENSION JOLY, opposite the Hôtel de Londres, somewhat exposed, but well spoken of. — In the principal street of the lower town (*Via Vittorio Emanuele*): HÔTEL GRANDE BRETAGNE (Italian style); HÔTEL DE RUSSIE; ALBERGO DEL COMMERCIO, commercial; PENSION SUISSE, from 6 fr., well spoken of; VILLA QUAGLIA, a pension in the *Via Gioberti*. — On the *E. Side of the Town*:

<sup>1</sup> **HÔTEL VICTORIA**, farthest from the station, but with S. aspect and a pleasant garden extending down to the sea, D. 5, B. 1½ fr.; nearer the town, <sup>2</sup> **HÔTEL D'ANGLETERRE**; **PENSION MOLINARI** (formerly *Anglaise*); **PENSION BEAU SÉJOUR**, smaller, all with gardens and well spoken of. — The charges at San Remo are now generally as high as at Mentone. Payment cannot be legally exacted in *gold* unless previously stipulated (comp. *Introd.*, p. xii).

**Apartments.** The choice of small suites of private apartments is annually increasing. They are to be found in the Via Gioberti, Vittorio Emanuele (Casa Escoffier, Casa del Circolo Internazionale, and in the former Hôtel Royal), and in the new Via Feraldi. Others may be hired in the interior of the town, but these are less desirable, owing to the coldness of the street. **VILLAS** abound; rent for the winter 1000-7000 fr. (list at Mr. W. Congreve's, the English vice-consul, Via Gioberti), including furniture and the other requisites for housekeeping (with regard to which, however, a distinct bargain is necessary). A more moderate rent than that advertised is generally taken. Situation should be carefully considered where invalids are concerned, and a S. aspect is essential.

**Restaurant.** *Brianzi*, Via Vitt. Emanuele, where regular diners may subscribe. — **Cafés.** <sup>2</sup> *Garibaldi*, cup of coffee 20, beer 30 c.; *Européen* (Vienna beer), both in the Via Vitt. Emanuele.

**Reading Room** at the *Circolo Internazionale*, where balls and concerts are also given; subscription for the winter 50, per quarter 30, per month 12 fr.

**Physicians.** English, *Drs. Daubeny, Freeman, and Whitley*; German, *Drs. Bröking, v. Brunn, Goltz, and Biermann*; Italian, *Drs. Ajcardi, Ameglio, Onetti, and Panizzi*. — English Chemist, *Squire*, Via Vittorio Emanuele, Casa Rubino; *Pharmacie Internationale*, at the corner of the Via Vitt. Emanuele and Via Feraldi; Italian, *Panizzi* (a good botanist), Via Palazzo. — *Warm Baths*, Via Gioberti 5.

**Post Office** in the Via Vitt. Emanuele 9, in the Pension Suisse. **Telegraph Office**, Corso Garibaldi 7, at the E. end of the town.

**Bankers.** *Asquasciati, Rubino*, both in the Via Vitt. Emanuele.

**Shops.** *Gandolfo*, bookseller, in the Via Palazzo, the old main street of the town, where the shops are often better and less expensive, although less showy, than those in the Via Vitt. Emanuele, the new main street. Among the specialties of the place are inlaid wood (depôt of *Mlle. Nicolas*) and the perfumes manufactured by *Ajcardi*.

**English Vice-Consul.** Mr. Walter Congreve, Via Gioberti.

**Music:** alternately in the Giardino Pubblico and the Giardino dell'Imperatrice, 3 times weekly. — **TEATRO AMEDEO.** Operas are performed from 1st Jan. to Easter.

**Carriages.** Per drive in the town, with one horse 1 fr., with two horses 1 fr. 50 c.; per hour 2 or 3 fr.; if luggage over 40 lbs., each box 50 c. — **Donkey** per day 5, half-day 3 fr., and gratuity. — **Boat** per hour for 1 person 1 fr., for several 2 fr. and gratuity.

**English Church Service** during the season.

*San Remo*, although apparently a small place, contains 11,000 inhab., densely crowded in the older parts of the town, which consist of a labyrinth of quaint and narrow lanes, flights of steps, archways, lofty and sombre houses, and mouldering walls. The arches by which the houses are connected high above the streets are intended to give them stability in case of earthquakes. The town, which was formerly fortified, stands on a hill between two short valleys, and the houses rising one above another receive their modicum of light and air from the back only. *Castigliuoli*, a smaller quarter on the W. side, is similarly situated.

The E. part of the town terminates in an eminence approached by broad roads shaded by cypresses, commanding charming views

of the bay and mountains, and crowned with the white dome-covered church of the *Madonna della Cosla*, in front of which there is a large hospital for lepers. On a more prominent point stands the Villa Carbone, with a low octagonal tower (fee  $1\frac{1}{2}$  fr.), the panorama from which conveys a good idea of the peculiarities of the situation. The island of Corsica is visible in the distance to the S.

Another walk may be taken to the W. pier of the small harbour, which is defended by the fort of *St. Tecla*, erected by the Genoese, and now used as a prison. A survey from the upper platform of the Molo will convey an idea of the sheltered position of the town, which renders the climate as genial as that of Mentone and has brought the place into notice as a winter residence for invalids. In front of the spectator rises a hill in an almost regular semicircle around the town, sloping upwards from the Capo Nero by La Colla to its culminating point in the Piano Carparo and Monte Bignone, which attain a height of nearly 4000 ft., and descending thence to the Capo Verde, the summit of this barrier being nowhere more than 4 M. distant in a straight line. The N. winds are therefore entirely excluded from this favoured spot, especially as a double range of Alps rises behind the town a little farther back, while at the same time the violence of the E. and W. winds is much broken. In the rich vegetation of this nook the olive predominates, and the hills above are chiefly clothed with pines. Country-houses and churches peep from amidst the olive groves in every direction, the highest being at *San Romolo* at the foot of the Bignone, to which the few visitors who remain throughout the summer resort in order to escape from the heat. Several fine palms rise in the principal street of the lower and modern part of the town, and others in the 'palm-quarter' of the old town, and other places (comp. p. 101).

WALKS numerous and pleasant, but occasionally rough. Near the station are the *Giardino Pubblico*, containing palms, eucalyptus, etc., and a small fountain, and the *Corso Mezzogiorno*, which terminates towards the W. in the *Giardino dell' Imperatrice*, a garden recently laid out under the auspices of the Empress of Russia. The most sheltered walk higher up in the basin is the *Berigo Road*. — A beautiful point of view easily reached is the *Madonna della Guardia* on the *Capo Verde*, returning by *Foggio*. — To *S. Romolo* 3 hrs., an excursion for which a donkey may be hired. About 2 hrs. higher rises the *Monte Bignone* (4235 ft.), which commands a beautiful panorama of the sea to the S. and the Maritime Alps to the N., on the way back from which the *Piano del Re*, a celebrated point of view, may also be visited. — Good roads lead to *Ceriana* and to *Taggia*. — To *La Colla* by *Ospedaletti* (see below) 2 hrs.; or direct, by a very ancient road, 3 M.

The train passes through a tunnel under the *Capo Nero*, while the road winds over the promontory at a considerable height. —  $88\frac{1}{2}$  M. *Ospedaletti* is also the station for the loftily situated (1 hr.) *La Colla*, the town-hall of which contains a valuable picture-gallery. A view is now soon obtained of the palm-groves of —

$9\frac{1}{2}$  M. **Bordighera** (\**Hôtel d'Anoletterre: Hôtel Bordighera*,

pension at both 10-12 fr.; *Pension Anglaise*; *Pension Victoria*. 7-8 fr. — Physicians, Dr. Schmitz and Dr. Christeller), situated on a hill projecting into the sea, and consisting of an upper and a lower quarter. Beautiful \*view from the top of the hill (from the terrace of the small *Café Cadama*, pension 5-6 fr., to the left as the picturesque upper part of the town is entered), embracing the bay of Ventimiglia, Mentone, and Monaco as far as the Estérels, with groves of palms in the foreground (*Phoenix dactylifera*, the fruit of which does not ripen sufficiently here to be edible). A considerable trade is carried on here in palm branches and young palm-trees. The palm-garden of Sign. Moreno is worthy of a visit. The climate is almost as mild as that of Mentone and San Remo, but is more bracing, and invalids frequently come here for change of air, and even to spend the whole winter. Excursion to the neighbouring *Dolceaqua* with the ancestral château of the Dorias of Genoa, and to *Pigna*.

Farther on, to the right of the line, is the Protestant school of *Vallecrosia*, immediately beyond which a brook is crossed, and a glimpse of the Maritime Alps is obtained. 94½ M. *Ventimiglia* (\**Rail. Restaurant*; *Hôtel de l'Europe*), where passengers' luggage is examined at the French custom-house. The town, which is an Italian frontier-fortress, lies very picturesquely on a hill beyond the *Roja*, a stream whose broad stony channel the line crosses farther on. The train passes through a tunnel and approaches the sea. View limited. — [On this part of the route the scenery is much finer on the road than on the railway. The road ascends gradually and is guarded by forts at the highest point. In descending it commands an extensive view of the French coast, and passes through several villages with picturesque and venerable groups of olive-trees, affording several fine retrospects. On a hill to the right are the ruins of a Roman fort. *Mortola*, with its church, farther on, stands picturesquely on a rocky eminence. The road then skirts a gorge and ascends to the last height, where a view of Mentone is disclosed. Immediately beyond this point is the Italian dogana. On the hill to the right lies *Grimaldi*. Charming country-houses with lemon and orange-gardens and luxuriant vegetation are now passed. The deep gorge crossed by the *Pont St. Louis* forms the boundary of France.] —

101½ M. **Mentone**, French *Menton*. — **Hotels and Pensions.** *On the W. Bay.* (1.) At some distance from the sea: \**HÔTEL DES ILES BRITANNIQUES*, new and well fitted up; \**HÔTEL DU LOUVRE*, pension on the 1st floor 15, 2nd floor 13 fr.; \**HÔTEL DE VENISE*; \**HÔTEL D'ORIENT*, finely situated; \**HÔTEL DE TURIN*; \**HÔTEL DES ÉTRANGERS*, much frequented; \**HÔTEL MÉDITERRANÉE*. Near the station: \**HÔTEL SPLENDIDE* and \**HÔTEL DU PARC*, the latter convenient for a short stay. *PENSION DES ORANGERS*, on the Turin road, with a large garden; *PENSION SUÉDOISE*. — (2.) On the Promenade du Midi, near the sea: \**HÔTEL DU PAVILLON*, patronised by English and Americans; *HÔTEL DE RUSSIE*; \**PENSION CAMOUS*; *PENSION ALLEMANDE*; *PENSION DE LONDRES*; *PENSION AMÉRICAINNE*; *HÔTEL WESTMINSTER*; \**HÔTEL VICTORIA*, a large establishment; *GRAND HÔTEL DE MENTON*.

R. 3. D. 5 fr.; <sup>2</sup>HÔTEL DU MIDI; HÔTEL BRISTOL; PENSION DU NORD, patronised by Scandinavians; PENSION SUISSE; HÔTEL ROYAL. — *In the Town*: HÔTEL DE FRANCE, for a short stay. — *On the E. Bay*: <sup>2</sup>HÔTEL DE LA GRANDE BRETAGNE; <sup>2</sup>HÔTEL D'ITALIE, with pleasant garden, patronised by the English, and <sup>2</sup>HÔTEL BELLEVUE, both near the Pont St. Louis; <sup>2</sup>GRAND HÔTEL DE LA PAIX; <sup>2</sup>HÔTEL DES ANGLAIS, frequented chiefly by English; <sup>2</sup>GRAND HÔTEL QUARTIER GARAVANT, with large garden; PENSION DE L'UNIVERS, unpretending; <sup>2</sup>PENSION GABRELE, in the *Villa Marina*; PENSION SCANDINAVE, in the Gorbio valley. and many others. Pension 8-15 fr. per day, exclusive of fires and lights.

In both bays there are also numerous (150) charmingly situated and sometimes handsomely furnished villas, a list of which may be obtained of the agent *Amaranthe*, who draws up contracts for a lease, takes inventories of furnishings, and compares them again when the visitor leaves. The rents vary from 1000 to 7000 fr. and upwards for the season. Private apartments for the season, from 400 fr. upwards, are also to be had, where the visitor may have his own 'menage', and live less expensively than at a pension. Choice of situation, comp. p. 99.

The *Cercle Philharmonique* contains a reading-room, and frequently gives halls and concerts; subscription 60 fr. for the season, ladies 48 fr.; per month 15 fr., ladies 12 fr.

**Restaurants.** *London Tavern*; *Café de la Victoire*; *Café de Paris*; *Restaurant du Cercle*.

**Physicians.** *Drs. Bennet, Marriott, and Siordet*, English; *Drs. Bottini and Farina*, Italian; *Drs. Stiege and v. Cube*, German. — **Chemists:** *Albertotti, Gras, and Farraud*, who make up English and German prescriptions during the winter.

**Post Office,** Rue Guvini. — **Telegraph Office:** Avenue Victor Emmanuel 19.

**Bankers:** *Viale (Biòvès & Co.)*; *Franc Palmaro* (Engl. vice-consul); *Adamin Bottini*. — **Booksellers:** *Papy; Giordan*. — **Photographers:** *Astroga, Anfossi*, both in the Avenue Victor Emanuel.

**Omnibuses** through the town during the season from the Quartier Garavant to the Quartier Madonna, every hour, 50c.

**Carriages.** Drive in the town, with one horse, 1¼ fr., with two horses 1¾ fr.; per hour 2½ or 3½ fr.; for half-a-day one-horse 8-10, per day 12-15 fr., two-horse 25 fr. — **Donkeys** 5 fr. per day, 2½ fr. for half-a-day, and gratuity.

**English Church Service** during the season.

*Mentone*, a small town with 5600 inhab., formerly belonging to the principality of Monaco, and afterwards under the Sardinian supremacy, was annexed to France in 1860. It is charmingly situated on the Bay of Mentone, which is divided into the *Baie de l'Est* and the *Baie de l'Ouest* by a rocky promontory, and being protected by a girdle of rocky mountains from the N. winds, is considered one of the most favourable spots for a winter-residence on the Riviera di Ponente (mean temperature about 3° Fahr. higher than at Nice; a cold wind, however, generally prevails towards noon, especially at the point where the valley opens towards the W. bay). The vegetation is luxuriant, consisting chiefly of orange and lemon groves interspersed with gnarled carob-trees (*ceratonia siliqua*), figs, olives, etc. The *Promenade du Midi* and the *Jardin Public* are favourite walks in the afternoon. The ruined castle on the above mentioned rocky promontory, which has been converted into a burial-ground, affords a fine view, embracing S. Agnese on a lofty hill, erected for defence against the Saracens. Another picturesque point is the monastery of *S. Annunziata*, to

which a tolerable path ascends (in  $\frac{1}{2}$  hr.) from the Turin road (to the left immediately beyond the railway). Pleasant and sheltered walks may also be taken to the *Vallée Cabrole*, *Vallée Gorbio*, and *Vallée de Menton*, and to the *Cap Martin*, which bounds the Bay of Mentone on the W.; another to *Grimaldi* (p. 101), to the E., immediately beyond the frontier bridge, where a tower in Dr. Bennet's garden commands a fine view.

Attractive excursions from Mentone to *Monti* and the *Cascades*, and thence to *Castiglione* and *Sospello* (p. 110). — Also by (4 M.) *Castellaro* to the summit of the *Berceau* (3-4 hrs.); magnificent prospect embracing the mountains of the coast, the blue expanse of the Mediterranean, and Corsica in the distance. — To *S. Agnese*, situated on a serrated ridge of rock (*Locanda*, bad), 2 hrs., returning by (2 hrs.) *Gorbio* and *Roccabruna* to Mentone (in 4-5 hrs. more). From *S. Agnese* the '*Aiguille*' may be ascended in 2-2½ hrs., a higher point than the *Berceau*, also commanding a fine view. — To *Camporosso*, situated 3½ M., and *Dolce Acqua*, 7 M. inland from *Ventimiglia* (p. 101). — Comp. also p. 109.

The ROAD FROM MENTONE TO NICE, 19 M. (by carr. in 4 hrs.; 25-30 fr., 2-3 fr. gratuity), the so-called '*Route de la Corniche*', traverses the most beautiful part of the Riviera, and is far preferable to the railway. It ascends through the most luxuriant vegetation, and commands a charming retrospect of Mentone and the coast as far as *Bordighera*. Then a view of *Monaco* (see below), to which a road descends to the left beyond the highest point of the road. To the right of the road, higher up, *Roccabruna* (see below) is visible. Then *Turbia* with its huge Roman tower, now a mere shell, the remains of the *Tropæa Augusti* (whence the name '*Turbia*'), erected to commemorate the subjugation of the Ligurian tribes (A.D. 13). Another very beautiful view is enjoyed here. To the E. the wild mountains and the entire coast from *Ventimiglia* to *Bordighera*; W. (view in this direction from a point a few steps above the tower) the Mediterranean, the French coast near *Antibes*, the island of *St. Marguerite*, the *Montagnes de l'Estérel*, and other distant coast-hills. The road attains its culminating point in a bleak mountain-district  $\frac{3}{4}$  M. beyond *Turbia*. On the left is *Eza* (p. 104), a group of grey and venerable houses with a white campanile, perched on an isolated rock rising abruptly from the valley. Farther on, the wooded promontory of *St. Hospice* (p. 110), *Beaulieu* (p. 110), and *Villafranca* (p. 109), beyond which a view is obtained of the beautiful valley of *Nice* (p. 104), with its villas, monasteries, villages, and green hills.

The RAILWAY from Mentone to Nice skirts the coast the whole way, and affords very inferior views to the magnificent and lofty carriage-road. It crosses the *Borigli*, penetrates *Capo Martino* (see above) by means of a tunnel, and stops at stat. *Abbe-Roquebrune*. The village (Ital. *Roccabruna*) lies on the hill to the right, in the midst of orange and lemon groves, commanded by a ruined castle. Next stat. *Monte Carlo* (station for the *Casino* of *Monaco*).

107 M. *Monaco* (*Hôtel de Paris*, on a grand scale, adjoining the *Casino*; *Hôtel Suisse* and *du Louvre*, both smaller; *Angleterre* and *des Bains*, both near the station; all these near the sea; *Prince Albert*, in the town above. *Carriage* from station to town  $\frac{1}{2}$ , per hr. 3 fr.), picturesquely situated on a bold and prominent rock, the capital (1500 inhab.) of the diminutive principality of that name, to which Mentone and *Roccabruna* also belonged down to 1848, was mediatised by France in 1860, the princes, who were anciently renowned for their naval exploits, retaining but few



of their former privileges. The palace (shown on Tuesd., 2-5 p. m.) contains a suite of sumptuously furnished apartments. Pleasant promenades extend round the rocky point. Visitors are attracted to Monaco by the mildness of the climate in winter, and by the sea-bathing in summer, but the chief inducement to many is the 'tapis vert' at the *Casino*, which stands on a promontory to the E. of the town, surrounded by beautiful grounds (café, music twice daily; classical concerts on Thursdays), and commanding a fine view (*Casino* station, see p. 103).

Beyond Monaco the train passes through three long and several shorter tunnels. 111 M. Stat. *Eza*; the village, situated on an isolated rock on the right, high above the line, was once a stronghold of Saracen freebooters, who levied contributions on the surrounding district.

112½ M. *Beaulieu* (p. 110). — 113½ M. *Villafranca* (p. 109). The train now enters the valley of the *Paglione* by means of a tunnel nearly 1 M. in length, crosses the stream, passes through another tunnel, and reaches the station of (116 M.) **Nice** on the right bank of the river.


## 17. Nice and its Environs.

*Comp. Map, p. 108.*

**Hotels.** In the Promenade des Anglais: <sup>1</sup>HÔTEL DES ANGLAIS, <sup>2</sup>DU LUXEMBOURG, <sup>3</sup>DE LA MÉDITERRANÉE, DE ROME, all first class. — By the Jardin Public: <sup>4</sup>GRANDE BRETAGNE, <sup>5</sup>ANGLETERRE. — On the Quai Masséna (Quai des Palmiers): <sup>6</sup>HÔTEL DE FRANCE. — Quai St. Jean Baptiste: <sup>7</sup>HÔTEL CHAUVAIN, HÔTEL DE LA PAIX, <sup>8</sup>GRAND HÔTEL. — In the Boulevard Carabacel: HÔTEL DE PARIS; EUROPE ET AMÉRIQUE; PERINO; <sup>9</sup>HÔTEL FISCHER, new; <sup>10</sup>HÔTEL DE NICE, well situated, good cuisine; HÔTEL ET PENSION CARABACEL. — In the Boulevard Bouchage: <sup>11</sup>HÔTEL WINDSOR, HÔTEL JULIEN; HÔTEL STEIMEL. — In the Avenue Beaulieu: <sup>12</sup>HÔTEL ET PENSION RAISSAN. — Avenue de la Gare: <sup>13</sup>ILES BRITANNIQUES; HÔTEL DES EMPEREURS; HÔTEL HELVÉTIQUE; HÔTEL DES DEUX MONDES; MAISON DORÉE. — In the Boulevard Longchamp: <sup>14</sup>HÔTEL PARADIS. — Rue St. Etienne: HÔTEL DU LOUVRE. — Avenue Delphine: HÔTEL ET RESTAURANT DU MIDI, near the station; BEAU-SITE. — Rue Grimaldi: HÔTEL ROYAL. — Place Masséna: HÔTEL MEUBLE. Rue des Ponchettes: <sup>15</sup>HÔTEL ET PENSION SUISSE, beautifully situated on the sea, one of the best and cheapest pensions, open throughout the summer. — On the Quai du Midi: HÔTEL VICTORIA. In the old town: <sup>16</sup>HÔTEL DES PRINCES, Rue des Ponchettes; <sup>17</sup>HÔTEL DE L'UNIVERS, Place St. Dominique; <sup>18</sup>HÔTEL DES ÉTRANGERS, Rue du Pont-neuf, well spoken of; these two open throughout the summer. — In the Rue de France: HÔTEL DU PARC and HÔTEL CROIX DE MARBRE. — The larger hotels are closed from the beginning of summer till the end of September. — In resisting the exorbitant demands sometimes made by the innkeepers on the death of one of their guests, the traveller will receive efficient aid from the local authorities.

**Pensions.** In the Promenade des Anglais: *Pension Rivoir*, *Pension Anglaise*. In the Rue de France: *P. de la Métropole*, *Pension Torelli*. Rue Longchamp: <sup>19</sup>*P. St. Etienne*. Rue St. Etienne: <sup>20</sup>*Pension Millet*, 10-12 fr. Petite Rue St. Etienne: <sup>21</sup>*Pension Internationale*. Avenue Delphine: <sup>22</sup>*P. Royale*. Boulevard Carabacel: *Pension Genève*. At Cimiez: <sup>23</sup>*P. Anglaise* (Villa Garin), *P. Cimiez*. — The usual charge at these houses is 7-12 fr. per day.

**Restaurants.** In the Avenue de la Gare: <sup>24</sup>*Restaurant Français*; *Restaurant des Deux Mondes*; *Maison Dorée*; <sup>25</sup>*Restaurant Suisse*, <sup>26</sup>*Américain*.



# NIZZA. NICE.

- |    |                       |       |    |                   |      |
|----|-----------------------|-------|----|-------------------|------|
| 1  | Banque de France      | BE.6. | 12 | Temple Anglais    | C4.  |
| 2  | Bibliothèque publique | E.2.  | 13 | Rosse             | D.3. |
| 3  | Quartier              | DE.3. | 14 | Fontaines         | E.3. |
| 4  | Église Mamma          | D.3.  | 15 | Hôpital civil     | E.2. |
| 5  | Quai de Napoléon      | C.4.  | 16 | Lycee             | E.3. |
| 6  | Quai de Napoléon      | E.4.  | 17 | Mairie            | E.3. |
| 7  | Cathédrale            | D.4.  | 18 | Poste aux Lettres | E.4. |
| 8  | Opéra de Nizza        | E.4.  | 19 | Préfecture        | E.4. |
| 9  | Église                | E.4.  | 20 | Palais de Justice | E.4. |
| 10 | Place de Nizza        | D.2.  | 21 | Théâtre National  | E.4. |
| 11 | Église de Nizza       | E.4.  | 22 | Théâtre Français  | D.3. |

- Hôtels.**
- |    |                          |      |
|----|--------------------------|------|
| a. | Hôtel des Anglais        | D.4. |
| b. | Grand Hôtel              | E.3. |
| c. | Hôtel de Nizza           | E.2. |
| d. | Hôtel de la Méditerranée | C.4. |
| e. | Hôtel de la Côte d'Azur  | D.4. |
| f. | Hôtel de la France       | D.4. |



Rue Croix de Marbre: *London House*. Rue Macarani: *Trois Suisses*. In the Corso: *Restaurant du Cours, du Commerce*. — **Cafés**. Place Masséna: *de la Victoire*; *Grand Café*, in the Grand Hôtel; *Café Américain*, in the Corso. *Ices*: the best at *Rumpelmeier's*; also at the *Maison Dorée* and *Deux Mondes* (see above). — *Preserved Fruits*: *Müller*, Place St. Dominique; *Fea*, Avenue de la Gare; *Escoffier*, Place Masséna. — The *Beer* is seldom good; best at the *Brasserie Centrale*, and in the *Brasserie de Strasbourg*, both in the Rue du Temple. Also in most of the restaurants and cafés; glass 30-40 c.

**Bakers**. *Renz*, Rue Paradis, German. *Diedrich*, Place Grimaldi.

**Cabs** are stationed in the Place Charles Albert, Place Masséna, Boulevard du Pont Vieux, and other places.

|                                                                                                                                             | One-horse.<br>with 2 seats. |       | One-horse.<br>with 4 seats. |       | Two-horse.<br>with 4 seats. |       |
|---------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|-------|-----------------------------|-------|-----------------------------|-------|
|                                                                                                                                             | day                         | night | day                         | night | day                         | night |
| Per <i>Drive</i> in the town (exclusive of some villas) . . . . .                                                                           | 1—                          | 1.50  | 1.25                        | 1.75  | 1.75                        | 2.25  |
| From the station to the town the following charges are for 1 pers. in the smallest cabs, and for 2 pers. in the others, without luggage . . | 1—                          | 1.50  | 1.50                        | 2—    | 1.75                        | 2.25  |
| Each additional pers., as also each larger article of luggage, or drive from one hotel to another . . . . .                                 | —25                         | —25   | —25                         | —25   | —25                         | —25   |
| Per hour . . . . .                                                                                                                          | 1.75                        | 2.25  | 2.25                        | 2.75  | 2.75                        | 3.25  |
| To <i>Villafranca, Grotte St. André</i> , there and back with a stay of ½ hr. . . . .                                                       | 5—                          | 6—    | 6—                          | 7—    | 7—                          | 8—    |

**Omnibuses** cross the town in several directions (25 c.); from the station to the town 30 c.; trunk 25, hat-box 10 c.; to Villafranca and Beaulieu every 2 hrs., 30 c., starting from the Pont Vieux, left bank of the Paillon.

**Horses** may be hired of *Nigio*, Boulevard Charles-Albert 2, and Rue St. François de Paule; *Mouton*, Rue Pastorelli, etc.; 6-10 fr. for a ride of 3-4 hrs. In winter a horse may be hired by the month for 250-350 fr., in summer for less.

**Donkeys** generally 4 fr. (but in the height of the season sometimes 5 fr.) per day, and 1 fr. for the attendant; half-day 2 fr.

**Markets** in the Cours, adjoining the cathedral, and in the Place St. François, 8-11 a.m., sale of flowers. — Fish-market at the back of the Cours.

**Booksellers**. *Librairie Etrangère de Barbéry Frères*, with circulating library, Jardin Public 7. *Visconti's* reading-room, well supplied with newspapers, Rue du Cours, with garden; *Fleurdelys*, Avenue de la Gare 5; *Jougla*, Rue Gioffredo 1.

**Post Office**, Rue St. François de Paule, 7 a.m. to 6, in summer to 7 p.m.; Sund. 7-12, 4-6 only. — **Telegraph Office**, Rue du Pont Neuf, adjoining the Préfecture.

**Physicians**. *Drs. Travis, Gurney, Marcet, Crothers, Crossby*, and *Blest*, English. *Drs. Zürcher, Lippert, Rehberg*, and *Bode*; *Drs. Jantzen*, and *Pröll*, homeopaths, all German. — **Dentists**: *Hall* (American), *Préferve*, both in the Place Masséna; *Fieux*, Quai Masséna; *Ninçh*, Rue Masséna 30. — **Chemists**: *Pharmacie Anglaise*, Quai Masséna; *Draghi*, Rue de France; *Fouque*, Boulevard du Pont Vieux; *Leoncini*, Place St. Etienne; *Vigon*, Rue Gioffredo; *Pharmacie Alsacienne*, Rue Gioffredo 1.

**Bankers**. *Lacroix*, Rue du Cours; *Caisse de Crédit*, Rue Gubernatis.

**Baths**. Warm Baths: *Bains des Quatre Saisons*, Place du Jardin Public; *Bains de Macarani*, Place Grimaldi; *Bains Masséna*, Rue Masséna. Turkish Baths: *Hammam de Nice*, Place Grimaldi and Rue de la Buffa. *Sea-baths* opposite the Promenade des Anglais, 1 fr.

**Shops**. The best are on the Quai St. Jean Baptiste and the Quai Mas-

séna. 'Marqueterie' (inlaid wood-work): *Gimelle Fils, & Co.*, Quai St. Jean Baptiste 9; *Rueger*, Rue du Pont Neuf 3, and others. Photographers: *Blanc*, Promenade des Anglais; *Ferret*, Rue Gioffredo.

**Casinos.** *Cercle Masséna*, Place Masséna; *Cercle Méditerranée*, formerly the Casino, a new building on the Promenade des Anglais, embellished with the armorial bearings of different states, both French; *Cercle Philharmonique*, Rue Pont Neuf.

**Theatres.** *Théâtre National*, Rue St. François de Paule, Italian opera; *Théâtre Français*, Rue du Temple, operas, comedies, etc.

**Military Music** several times weekly in the Jardin Public, 2-4 o'clock.

**Steamboats** (companies: *Fraissinet*, Place Bellevue 6, on the quay; *Peirano, Danovaro & Co.*, office in the Corso, to the right of the flight of steps ascending to the terrace; *Valery Frères et Fils*, Quai Lunel 14): to *Genoa* 5 times weekly in 9-10 hrs., 32½ or 22½ fr., cabin on the deck 12½ fr. — To *Marseilles* on Tues. in 12 hrs., 30, 12, 8 fr. — To *Corsica* (Bastia, see p. 394) on Wed. in 12 hrs., 30, 20, 15 fr.

**House Agents**, *Samaritani, Lattes, Dalgoutte*, and *Jougla*, to whom a percentage is paid by the proprietors. A more advantageous bargain may therefore be made without their intervention. Houses and apartments to let are indicated by tickets. A single visitor may procure 1-2 furnished rooms for the winter in the town for 300-700 fr.; suites of apartments are let for 2000-5000 fr., villas for 5000-8000 fr. and upwards.

The hirer should not take possession until a contract on stamped paper has been signed by both parties, containing stipulations with regard to damage done to furniture and linen, compensation for breakages, etc. This is the only way to avoid the disputes which are apt to arise on the termination of the contract. Nice has the reputation of being an expensive place, but it is not much dearer than Switzerland in the height of the season, while at the pensions situated at a distance from the sea, but in well sheltered spots, the charges are moderate compared with those at other favourite wintering places on the Riviera.

**English Church** in the Rue de France, service also at Carabacel. *Scotch Church*, Rue Masséna 5.

**Climate.** The bay of Nice is sheltered from the N., N.E., and N.W. winds by the lower terraces of the Maritime Alps (culminating in *Mont Chauve*, Italian *Monte Calvo*, 2672 ft.), a natural barrier to which it owes its European reputation for mildness of climate. The mean winter temperature is 10-15° Fahr. higher than that of Paris, summer temperature 5-10° lower. Frost is rare. The *Mistral*, or N.W. wind, the scourge of Provence, is seldom felt, being intercepted by the *Montagnes du Var* and de l'*Estérel*. The E. wind, however, which generally prevails in spring, is trying to delicate persons. The most sheltered situations are the Boulevard Carabacel and the Quartiers Brancolar and Cimiès, in the last of which the air is generally pure and free from dust. Sunset is a critical period. As the sun disappears, a sensation is often felt as if a damp mantle were being placed on the shoulders, but this moisture lasts 1-2 hours only. — The rainy season usually begins early in October and lasts about a month.

*Nice*. Ital. *Nizza*, the capital (50,000 inhab.) of the French Département des Alpes Maritimes, was founded by the Phocian inhabitants of Marseilles in the 5th cent. B.C., and named *Nicaea*. Down to 1388 it belonged to the County of Provence, and afterwards to the Dukes of Savoy; in 1792 it was occupied by the French, in 1814 restored to Sardinia, and in 1860 finally annexed to France together with Savoy. Nice was the birthplace of the French general Masséna (in 1758) and of Giuseppe Garibaldi (in 1807). The dialect of the natives is a mixture of Provençal and Italian.

In winter Nice is the rendezvous of invalids as well as persons in robust health from all parts of Europe, especially from England,

Russia, and Germany, who assemble here to escape from the rigours of a northerly winter. The annual number of visitors is still on the increase, and living becomes dearer in proportion. In summer the town is deserted.

Nice is beautifully situated on the broad *Baie des Anges*, which opens towards the S., at the mouth of the *Paglione*, or *Paillon* (a small stream, frequently dried up). The broad and stony bed of the river, with handsome quays on each bank, bisects the town. On the left bank is the OLD TOWN, with its narrow, dirty lanes, which however have been superseded by better streets near the shore (Boulevard du Midi and Promenade du Cours). On the right bank is the STRANGERS' QUARTER, which already surpasses the old town in extent, and is intended to occupy the entire space bounded on the W. by the brook *Magnan*, and on the N. by the railway (the Quartier de la Croix de Marbre stretches along the coast to the W., the Boulevard Carabacel and the Quartiers Brançolar and Cimiès to the N.E. along the bank of the Paillon).

In the Avenue de la Gare, leading from the station to the town, rises the still unfinished church of *Notre Dame*, erected by Lenormant of Paris in the Gothic style. — A *Marble Cross* in the Rue de France, commemorating the meeting of Charles V. and Francis I. in 1538, which was effected through the intervention of Pope Paul III., has given its name (Croix de Marbre) to this quarter of the town. — The SQUARE, a broad space formed by covering in the Paillon between the Pont Vieux and Pont Neuf, is embellished by a *Statue of Masséna* (p. 106) in bronze, erected in 1867; in front Clio is represented on the pedestal writing his name on the page of history; at the sides are reliefs. — The *Town Library* (40,000 vols., open daily 10-3, on Sundays 10-12 o'clock), Rue St. François de Paule 2, contains a few Roman antiquities (milestones, etc.), and a natural history cabinet.

The **Jardin Public** (Pl. D, 4; military music, see p. 106) at the embouchure of the Paillon, and the **\*Promenade des Anglais** adjoining it on the W., which was laid out by English residents in 1822-24, and greatly extended in 1862, are the principal resorts of visitors. These grounds stretch along the coast for  $1\frac{1}{2}$  M., as far as the brook *Magnan*, and are bordered with handsome hotels and villas (at the beginning of the promenades is the Cercle Méditerranée, mentioned p. 106). On the left bank of the Paillon, which is crossed here by the Pont Napoléon, they are continued by the *Boulevard du Midi* (see above).

To the E. of the town rises the **Castle Hill**, 320 ft. in height (Pl. F, 4; ascent from the N. or E. side, 20 min.), crowned by the ruins of a castle destroyed by the Duke of Berwick under Louis XIV. in 1706, now converted into beautiful grounds, where palms, oranges, cypresses, and aloes flourish in profusion. The platform on the summit, erected in honour of Napoleon III., commands an admirable

view in every direction: S. the Mediterranean; W. the French coast, the promontory of Antibes, the two Iles de Lérins, the month of the Var (which down to 1860 formed the boundary between France and Sardinia), below the spectator Nice itself; N. the valley of the Paglione, the monasteries of Cimella, or Cimiès, and St. Pons, in the distance the castle of S. André, Mont Chauve, the Aspremont, and the Alps: E. the harbour, the mountains and Fort Montalban, and the promontory of Montboron which separates the roadsteads of Villafranca (p. 109) and Nice. The S. slope of the castle-hill, which descends precipitously towards the sea, is called the *Raubacapeu* ('hat-robber', owing to the prevalence of sudden gusts). — The *Cemeteries*, with the exception of the English, are on the N. side of the castle-hill.

At the base of the castle-hill on the E., where a house opposite the dogana was destroyed by a landslip in the winter of 1871, lies the small **Harbour** (Pl. F. 4), called *Limpia* from an excellent spring (*limpida*) which rises near the E. pier. It is accessible to small vessels only; those of large tonnage cast anchor in the bay of Villafranca (p. 109). The Place Bellevue adjoining the harbour, is embellished with a *Statue of Charles Felix, King of Sardinia*, in marble, erected in 1830.

To the N. of the town are the villas *Château Neuf* and *Orangini*, both in the Quartier Brancolar.

The ENVIRONS of Nice, with their attractive villas and luxuriant vegetation, afford a variety of beautiful excursions.

The Franciscan monastery of **Cimiès**, Ital. *Cimella*, is situated 3 M. to the N. of Nice. The best, although not the shortest route to it is by the new road ascending to the E. from the Boulevard Carabacel (Pl. E, 2), which on the top of the hill intersects the site of a Roman *Amphitheatre* (210 ft. long, 175 ft. wide). About  $\frac{1}{4}$  M. to the right from the cross-road, immediately beyond the amphitheatre, we reach the monastery (two pictures by Bréa in the chapel), re-erected in 1543 after its destruction by the Turks. It stands on the site of the Roman town of *Cemenelium*, to which the above-mentioned amphitheatre and a quadrangular structure, commonly called a '*Temple of Apollo*', belonged. Traces of baths and other buildings have also been discovered.

The *Vittu Clary*, to which the public are admitted, below Cimiès, on the road to St. André, possesses the finest orange and lemon-trees at Nice and many rare plants.

A good carriage-road ascends on the right bank of the Paglione to the (40 min.) monastery of **St. Pons**, founded in 775 on the spot where St. Pontius, a Roman senator, suffered martyrdom in 261. It was destroyed by the Saracens in 890, and the present edifice erected in 999. The treaty by which the County of Nice was annexed to the Duchy of Savoy was concluded here in 1388. The










Environs de Nice.

1: 220,000 d. N

Miglia di Piemonte di 45 per grado





château of **St. André** (restaurant, closed in summer), which is reached in  $\frac{1}{2}$  hr. more, built in the 17th cent., is now unoccupied. About  $\frac{1}{4}$  hr. farther up the valley is the grotto *Les Cluses de St. André*, or rather a natural bridge over a brook, crossed by the road. An avenue of cypresses leads from the château to the grotto ( $\frac{1}{4}$  hr.).

The excursion may be extended still farther in this direction. From the Grotto of St. André we follow the Torretta road in the desolate rocky ravine a little farther, and then ascend to the left by the new road in several windings to the village of **Falicon**, the highest point of which affords an admirable view. — From Falicon we may either return by the road to the S. to Nice (or by the less beautiful and very steep, but shorter path *via Cimiers*), or proceed farther towards the N. to **\*Aspremont**,  $9\frac{1}{2}$  M. from Nice. The road is good the whole way, and commands a fine view. Near Aspremont we obtain an excellent \*survey of the valley of the Var and of the Alps.

Farther up the valley of St. André, 7 M. from Nice, lies the antiquated village of **Torretta**, with the picturesque ruin of that name (Fr. *La Tourette*). The tower of the castle commands a very singular survey of the sterile mountain scene, especially of Mont Chauve, the Aspremont, and the deserted village of Château Neuf, perched on a barren ridge of rock; to the S. Montalban and the sea.

About  $1\frac{1}{2}$  M. farther is the dilapidated village of **Château Neuf**, founded on the ruins of old fortifications, and probably used in the 15th and 16th cent. by the inhabitants of Nice as a refuge from Turkish invaders. It has recently been abandoned by most of its inhabitants on account of the want of water. It is 5 M. distant from Torretta, and affords another fine view.

To the E. of the harbour La Linpia rises the **Montboron**, a promontory 890 ft. in height, which separates Nice from Villafranca. The summit, which is reached in  $1\frac{1}{2}$  hr., commands an extensive prospect. The mountains of Corsica are visible towards the S. in clear weather.

The **ROAD TO VILLAFRANCA** (2 M.; comp. Pl. G, 4), constructed by the French government, leads round the promontory of Montboron and passes a number of villas, the most conspicuous of which is the *Villa Smith*, a red building in the Oriental style. Near this village the new 'Route Forestière de Montboron' ascends to the left, commanding a superb view of Nice and the numerous villas of the environs; it traverses the whole of the hill of Montboron, leads round the *Fort Montalban*, and at length unites with the old road to Villafranca. — **\*Villafranca**, Fr. *Villefranche* (carr. from Nice, see p. 105; rowing-boat 10 fr.), very beautifully situated on the *Bay of Villafranca*, which is enclosed by olive-clad heights, founded in 1295 by Charles II. of Anjou, king of Sicily, is now a station of the Mediterranean squadron of the French fleet. Railway station at Villafranca (see p. 104) close to the sea.

If we follow the road for  $1\frac{1}{2}$  M. farther, a road to the right, crossing the railway by a stone bridge, will lead us to ( $\frac{3}{4}$  M.) **Beaulieu** (rail. stat. to the left of the bridge, see p. 104), an insignificant village situated in the midst of rich plantations of olives, figs, carob-trees (p. 102), lemons, and oranges. Many of the olive-trees are remarkably large, one of them measuring 22 ft. in circumference. Beaulieu lies in a wide bay, bounded on the S. by the long peninsula of **St. Jean**. At the foot of the latter lies the village of *S. Giovanni*, or *St. Jean* (dear inn),  $1\frac{3}{4}$  M. from Beaulieu, a favourite resort of excursionists from Nice. Tunny fishing is successfully carried on here in February, March, and April. At the extremity of the peninsula are the ruins of an old Saracenic castle, destroyed in 1706 in the reign of Louis XIV. (see p. 107), and the ruined chapel of *St. Hospice*. Instead of proceeding to St. Jean by the above route, the traveller may be ferried across the bay to the creek of *Passable* (60 c.), and thence cross the peninsula on foot to St. Jean.

On the W. SIDE of Nice pleasant walks may be taken in the valley of the **Magnan** (p. 101), in which a road ascends to (2 M.) the church of *La Madeleine*. The beautiful, sheltered banks of the **Var**, which falls into the Baie des Anes  $3\frac{3}{4}$  M. to the W. of Nice, are also worthy of a visit (one day; carr. with two horses, 20-25 fr.; also a railway station, comp. p. 21).

## 18. From Nice to Turin by the Col di Tenda.

$140\frac{1}{2}$  M. — MESSAGERIES to Cuneo ( $86\frac{1}{2}$  M.) in 18-22 hrs.; RAILWAY from Cuneo to Turin (54 M.) in  $2\frac{1}{2}$  hrs. — *Office at Nice* in the Hôtel de l'Univers (p. 104), not far from the French theatre; at *Turin*, in the Via Cavour.

This is a very attractive route, especially for those coming from Turin. The views during the descent from the Col di Tenda to the Mediterranean are strikingly beautiful. In winter the road is often impassable for a considerable time.

The road leads from Nice, on the bank of the Paglione, through the villages of *La Trinità-Vittoria* and *Drappo*, beyond which it crosses and quits the river.

12 M. (from Nice) **Scarena**, Fr. *Escarène*. The road hence to Sospello traverses a sterile and unattractive district. The barren rocks which enclose the bleak valley are curiously stratified at places. The road ascends to the *Col di Braus* (4232 ft.). To the S., on a lofty rock to the right, is seen the castle of *Châtillon*, or *Castiglione*. At the foot of the pass on the E. lies —

$25\frac{1}{2}$  M. **Sospello**, French *Sospel* (1174 ft.; *Hôtel Carengo*), situated in the valley of the *Berera* (affluent of the Roja, see below), in the midst of olive-plantations, and surrounded by lofty mountains. A new road leads from Sospello to Mentone. The road now ascends to the *Col di Brouis* (2871 ft.). Near the summit of

the pass a final view is obtained of the Mediterranean. Scenery unattractive, mountains bleak and barren. Then a descent to —

38 M. *Giandola* (1250 ft.; Hôtel des Etrangers; Poste), in a grand situation at the base of lofty rocks. *Breglio*, a town with 2500 inh. and the ruined castle of *Trivella*, lies lower down on the right.

The road now ascends the narrow valley of the *Roja*, which falls into the sea near *Ventimiglia* (p. 101). *Saorgio*, rising in terraces on a lofty rock on the right, with the ruins of a castle in the Oriental style, destroyed by the French in 1792, commands the road. On the opposite side is a monastery of considerable extent. The valley contracts, so as barely to leave room for the river and the road between the perpendicular rocks. Several small villages are situated at the points where the valley expands. Beyond (43 M.) *Fontana* the road crosses the Italian frontier. The southern character of the vegetation now disappears. 48 M. *S. Dalmaszo*, where an old abbey is fitted up as a hydropathic establishment, frequented in summer by some of the winter residents of Nice.

50½ M. *Tenda* (Hôtel Royal; Hôtel Impérial) lies at the S. base of the Col di Tenda. A few fragments of the castle of the unfortunate *Beatrice di Tenda* (comp. *Binasco*, p. 161) are picturesquely situated on a rock here.

The road traverses a dreary valley by the side of the *Roja* and ascends by 69 zigzags on the barren mountain, passing several refuges, to the summit of the *Col di Tenda*, or *di Cornio* (6145 ft.), where the Maritime Alps (W.) terminate and the Apennines (E.) begin. The view embraces the chain of the Alps from *Mont Iséran* to *Monte Rosa*; *Monte Viso* is not visible from the pass itself, but is seen a little beyond it, near the 4th Refuge. The descent is very steep. The road follows the course of the *Vermanagna* to —

75½ M. *Limone* (3668 ft.; Hôtel de la Poste), an Italian excise-station, and then becomes more level. The valley of the *Vermanagna*, which is now traversed, is at some places enclosed by wooded heights, at others by precipitous limestone cliffs. To the left rises the magnificent pyramid of the *Monte Viso* (12,670 ft.).

Stations *Robillante*, *Roccavione*, *Borgo S. Dalmaszo*, and —

86½ M. *Cuneo*, or *Coni* (1499 ft.; *Albergo della Barra di Ferro*), a town with 13,000 inhab., at the confluence of the *Stura* and the *Gesso*, once strongly fortified. After the battle of *Marengo* the works were dismantled in accordance with a decree of the three consuls and were converted into pleasure-grounds. The *Franciscan Church*, like most churches of this order beyond the Alps, is in the Gothic style (12th cent.). Pleasant walk to the *Madonna degli Angeli*, at the confluence of the *Gesso* and the *Stura*.

About 7 M. S.E. of Cuneo, in the *VAL PÉSTO*, is the romantically situated *Certosa di Val Pésio*, now used as a hydropathic establishment, also frequented as quarters for the summer by persons in search of retirement. — In the *Val di Gesso*, about 15 M. S.W. of Cuneo, are the *Baths of Valdieri*.



The RAILWAY to Turin intersects the fertile plain, bounded on the W. by the Maritime Alps, and, farther distant, the Cottian Alps, and on the E. by the Apennines. *Centallo*, the first station, with 4900 inhab., possesses remains of mediæval walls and towers. Next station *La Maddalena*; then (101 M.) *Fossano*, an episcopal residence, on the left bank of the *Stura*, beautifully situated on an eminence, with ramparts and a mediæval castle.

108½ M. *Savigliano* (*Corona*) is a pleasant town on the *Mucra*, enclosed by old fortifications. The principal church contains pictures by *Mulinari* (1721-93), a native of Savigliano, surnamed *Caraccino*, as an imitator of Caracci.

BRANCH-LINE TO SALUZZO, 10 M. (halfway station *Lagnasco*), in ½ hr. (fares 1 fr. 85, 1 fr. 30, 95 c.). *Saluzzo* is the capital of the province (formerly a marquiseate) of that name, with 16,000 inhab. The higher part of the town, with its precipitous streets, affords a fine prospect over the Piedmontese plain. A monument was erected here in 1863 to *Silvio Pellico*, the poet (d. 1854), who was born here in 1788.

At (114 M.) *Cavallermaggiore* the line unites with the Turin and Savona railway, see p. 80. — 140½ M. *Turin*, see p. 60.

### 19. From Genoa to Pisa. Riviera di Levante.

104½ M. RAILWAY in 4½-7¼ hrs. (fares 18 fr. 15, 13 fr. 60 c., 10 fr.). — Some of the trains start from the *Stazione Piazza Principe* at Genoa, stopping, with the exception of the express, at the *Stazione Piazza Brignole*, while others start from the latter station. — The finest views are from the side of the train opposite that on which passengers enter at *Stazione Piazza Principe*.

*Genoa*, see p. 82. The train backs out of the *Stazione Piazza Principe*, and then starts in the opposite (E.) direction, passing through a long tunnel under the higher parts of the town (transit of 4-5 min.).

2 M. *Stazione Piazza Brignole*, where there is generally a prolonged stoppage. — To the left we obtain a view of the fortress-crowned heights around Genoa (comp. p. 84).

The train, which at places runs parallel with the road, now follows the \*RIVIERA DI LEVANTE, which is less remarkable for luxuriant vegetation than the Riviera di Ponente (p. 95), but presents almost more striking scenery. The line is carried through the numerous promontories by means of cuttings and tunnels, of which last there are no fewer than eighty, some of them of considerable length. The villages generally present a townlike appearance, with their narrow streets and lofty and substantial houses, closely built on the narrow plain of the coast, or in short and confined valleys, and mostly painted externally as at Genoa.

The train crosses the *Bisagno*, generally an insignificant brook, and passes through the hill on which *S. Francesco d'Albaro* is situated by means of a tunnel. — 4 M. *Sturla*. To the right stretches the beautiful expanse of the Mediterranean; to the left we enjoy a view of the olive-clad slopes of the Apennines, sprinkled with country houses. Two tunnels. — 6 M. *Quinto*, with numerous

villas, and dense lemon plantations, among which rise several fine palm-trees. Three tunnels.

7 $\frac{1}{2}$  M. **Nervi** (*Hôtel Oriental*, near the station; \**Pension Anglaise*, recently enlarged), a small town with 5000 inhab., surrounded by lemon-groves, has of late come into notice as a winter residence, owing to its sheltered situation and mild climate. Nervi, Quinto, and Sturla, are frequented by Italians in summer for the sake of the sea-bathing. Among the handsome villas the finest are *Villa Serra* and *Villa Gropallo*.

Many of the beauties of the scenery are lost to railway travellers owing to the numerous tunnels through which the train now passes. 9 M. *Bogliasco*; 10 M. *Pieve di Sorì*; 11 M. *Sorì*, where we obtain a noble survey of the sea and the valley from the viaduct (in three stories) which passes high above the town and the rivulet. — 21 M. *Recco*; 14 $\frac{1}{2}$  M. *Camogli*, on the coast to the right. The train passes through the long *Tunnel of Ruta*, which penetrates the promontory of *S. Margherita* (the village of Ruta, situated on the height, and commanding an admirable view towards Genoa, is about 2 M. from Camogli by the road), and reaches the fertile plain with its numerous villas, and the bay of Rapallo.

17 $\frac{1}{2}$  M. *S. Margherita* lies on the coast below.

A beautiful Excursion may be made hence by boat, or by walking along the coast, to (3 M.) *Portofino*, a small seaport concealed behind the *Montefino*, with two old castles, now the property of Mr. Brown, the English consul. Halfway to Portofino is the suppressed monastery of *Cervara*, where, after the battle of Pavia, Francis I. of France, when detained here by contrary winds on the journey from Genoa to Madrid, was once imprisoned.

19 $\frac{1}{2}$  M. **Rapallo** (*Hôtel de l'Europe*, well spoken of, pension 7-10 fr.), a small seaport with 10,000 inhab., who carry on a brisk trade in olive-oil. Near it is the pilgrimage church of the *Madonna di Montallegro*. — 21 M. *Zoagli*.

24 $\frac{1}{2}$  M. **Chiavari** (\**Venezia*; *Fenice*), a town with 11,500 inhab., is charmingly situated at the influx of the *Sturla* into the *Bay of Rapallo*, where the mountains recede in a wide semicircle. Chiavari manufactures lace and light chairs (*sedie di Chiavari*), and possesses silk factories and ship-building yards.

25 $\frac{1}{2}$  M. *Lavagna*, a ship-building place, is the ancestral seat of the Counts Fieschi. *Sinibaldo de' Fieschi*, professor of law at Bologna, and afterwards elevated to the papal throne as Pope Innocent IV. (1243-54), the powerful opponent of Emp. Frederick II., was born here. Count *Giovanni Luigi de' Fieschi*, well known in history as the conspirator against the power of the Doria family (1547) at Genoa, was also a native of Lavagna. The train passes through a long tunnel and reaches —

28 $\frac{1}{2}$  M. **Sestri Levante** (*Albergo dell' Europa*; *Italia*), picturesquely situated on a bay which is terminated by a promontory.

The HIGH ROAD FROM SESTRI TO SPEZIA is far superior to the railway in point of scenery. (A carriage and pair for the journey, costing about



45 fr., may be ordered before leaving Genoa through one of the agents who may be heard of at the hotels.) The road turns inland and ascends the scantily wooded mountains in long windings, affording fine retrospects of the peninsula and valley (the village in the latter is *Casarza*). Farther on, the village of *Bracco* becomes visible on the left; then to the right a view is again disclosed of the sea, near which the road leads. The village on the coast below is *Moneglia* (see below). Then a gradual ascent through a somewhat bleak district to the *Osteria Baracca* (2286 ft.), whence the road descends into a pleasant valley in which lies the village of *Baracca*. After a slight ascent it next traverses a well cultivated district to *Pogliaseca* (Europa), in the valley of the impetuous *Vara*, an affluent of the *Magra*, which falls into the sea near Sarzana. The road skirts the broad, gravelly channel of the river for some distance, then diverges to the left and enters a wooded tract, in which beautiful chestnuts predominate. Beyond Baracca the sea does not again come into view, until the last height before Spezia is attained, whence a magnificent prospect is enjoyed of the bay and the precipitous mountains of Carrara, or *Alpi Apuane*, as the whole range is called.

Beyond Sestri the mountains recede from the sea, which the train also leaves for a short time. A great number of tunnels are now passed through in rapid succession; several fine views of the sea and the coast to the right. 35½ M. *Moneglia* lies close to the sea; 37½ M. *Deiva*, a village at the entrance to a side-valley; 40 M. *Framura*; 41½ M. *Bonassola*; 43 M. *Levanto* (4000 inhab.), with partially preserved fortifications, and a small Giardino Pubblico. Again a succession of tunnels. 46 M. *Monterosso*; 48 M. *Vernazza*; 50 M. *Corniglia*; 51 M. *Munarola*; 51½ M. *Riomaggiore*. Before reaching Spezia the train passes through four more tunnels, the last of which is very long (transit of 7 min.).

57½ M. **La Spezia.** — **Hotels.** \*CROCE DI MALTA, close to the sea, new and handsomely furnished, pens. 10-12 fr.; \*ITALIA, with a large garden, R. 2-5, B. 1½, déj. 2½, D. 4 fr., pension in winter 7-9 fr. including light and attendance. \*VILLE DE MILAN and PENSION ANGLAISE, in the Giardino Pubblico in the Palazzo Doria, R. 3, D. 4½ fr. — ALBERGO NAZIONALE, in the Giardino Pubblico, with restaurant, Italian, good cuisine; ALBERGO VICTORIA, Piazza del Teatro Civico, also with restaurant; POSTA, Corso Cavour.

**Cafés.** \*Café del Corso, near the Giardino Pubblico; \*Elretico, near the Teatro Civico.

**Physician.** Dr. Thomas (German) resides here in winter. Chemist, *Fossati*, Via del Prione.

**Baths.** Warm baths at the two first named hotels, and adjoining the Hotel Italia. — *Sea-baths* in summer on the beach to the N., 50 c.

**Post Office** in the Corso Cavour (8-12 a. m. and 2-6 p. m.). — *Telegraph Office:* Piazza Vittorio Emanuele, and Via Fossi 7 (open till midnight).

**Boat** with one rower, 1 fr. per hour.

*La Spezia*, a town with 20,000 inhab., is charmingly situated at the N.W. angle of the *Golfo della Spezia*, between two rocks crowned with forts, and possesses one of the largest, safest, and most convenient harbours in Europe, the *Lunai Portus* of the Romans. Since 1861 La Spezia has been the chief war harbour of Italy, and extensive improvements are now being carried out. The *Royal Dockyard* on the S.W. side of the town is a large establishment covering an area of 150 acres. Spezia is also a trading place of some importance. In summer the sea-baths, and in winter the

mildness of the climate attract numerous visitors. The air is genial and humid, and the vegetation of a southern character. The olive-oil of the environs is esteemed. Pleasant walks on the coast.

A delightful excursion may be made to **Porto Venere** on the W. side of the bay (two-horse carriage in  $1\frac{1}{2}$  hr., 10 fr.; boat in  $2\frac{1}{2}$  hrs., 8-10 fr.; the former preferable), on the site of the ancient *Portus Veneris*. A most charming prospect is enjoyed from the ruins of the church of *S. Pietro*, rising above the sea, and supposed to occupy the site of the old temple of Venus. The opposite island of *Palmaria* with a small fortress, is used as a penal establishment for brigands. Beautiful excursions may also be taken on the E. side of the bay, to *S. Terenzo* and *Lerici*, to which a screw-steamer runs once daily (1 fr.), starting from the Molo of the bay.

Four tunnels. —  $6\frac{1}{2}$  M. *Arcola*, with a conspicuous campanile. The train passes through another long tunnel, and crosses the broad *Magra*, which in ancient times formed the boundary between Italy and Liguria.

$67\frac{1}{2}$  M. **Sarzana** (*New York; Lunigiana*), Rom. *Sergiana*, or *Luna Nova*, from its having superseded the ancient Luna, with the picturesque fortification of *Sarzanella*, constructed by *Castruccio Castracani*, and a handsome *Cathedral* in the Italian Gothic style, begun in 1355.

In 1467 the place fell into the hands of the Florentines under Lorenzo de' Medici, from whom it was again wrested by Charles VIII. of France; it subsequently belonged to the Genoese, and then to the Sardinians. Sarzana was the birthplace of Pope Nicholas V. (Tommaso Parentucelli, 1447-55), a great patron of learning, and the founder of the library of the Vatican. The *Buonaparte* family is also said to have been settled in the Lunigiana, near Sarzana, before they transferred their residence to Corsica.

The environs are very fertile. Among the mountains to the left the white rocks and gorges of the neighbouring marble-quarries are visible. To the right a fine retrospect of the Bay of La Spezia.

Between Sarzana and the next stat. Avenza are the ruins of *Luna*, situated on the coast. This old Etruscan town fell to decay under the Roman emperors, and was destroyed by the Arabs in 1016; its episcopal see was transferred to Sarzana in 1465. The site of the ancient town is still marked by the ruins of an amphitheatre and circus. From the town of Luna the district derives its name of *La Lunigiana*.

$74\frac{1}{2}$  M. *Avenza* is a small town on the brook of that name, above which rises an old castle of *Castruccio Castracani*, of 1322, with bold round towers and pinnacles. On the coast to the right is a small harbour for the shipment of the Carrara marble.

BRANCH RAILWAY from Avenza, 12 min. (3 M.; fares 60, 45, 35c.) to — **Carrara** (*Loranda Nazionale*, with the *Trattoria del Giardinetto*, in the principal street on the right; travellers are cautioned against spending the night here, as the mosquitoes are insufferable). A visit to the celebrated and interesting quarries requires 3 hrs. at least. Guides demand 5 fr., but will generally reduce their charge to 2-3 fr.; for a mere superficial survey their services may be dispensed with. Leaving the station, we turn to the right and follow the street in a straight direction, past the theatre, to the Piazza, which is adorned with a statue of the grand-duchess Maria Beatrice, over life-size, erected in 1861. The bridge to the left at the end of the piazza should then be crossed, and the road

with deep ruts, ascending on the right bank of the *Torano*, followed. At (1/4 M.) a group of houses a path diverges to the right to extensive quarries of an inferior kind of marble, but we continue to follow the road, passing numerous marble cutting and polishing works. Beyond the village of *Torano*, round which the road leads, the first mines, recognisable by broad heaps of rubbish, are situated on both sides of the valley. The blocks are detached, drawn out by oxen, and rolled down the hill. The finer description is called *marmo statuario*. About 400 miners with 6000 workmen are at present in operation. The working hours are from 5 a. m. to 2 or 3 p. m.; the forenoon is therefore the best time for a visit (a supply of copper coins is desirable). A horn is blown as a signal when the rock is about to be blasted. The mines of *Monte Crestola* and *M. Sagro* yield the best and largest blocks. The mines of *Fantiscritti*, 3 M. from Carrara, were worked by the ancient Romans.

The town of Carrara contains the studios of numerous sculptors (*Lazzarini, Franchi, Pelliccia, Bonanni*, etc.), some of which should be visited. Most of the inhabitants obtain their livelihood by working the marble. The following churches should also be inspected: *S. Andrea*, in a half-Germanic style of the 13th cent., like the cathedral of Monza, with interesting façade and good sculptures; *Madonna delle Grazie*, with sumptuous decorations in marble. The *Accademia delle Belle Arti* contains many copies from antiques, as well as works by sculptors of Carrara and several Roman antiquities found in the mines of *Fantiscritti*, e.g. a bas-relief of Jupiter with Bacchus.

78 1/2 M. *Massa (Quattro Nazioni)*, formerly the capital of the Duchy of Massa-Carrara which was united with Modena in 1829, with 10,000 inhab., is pleasantly situated amidst mountains, and enjoys a mild climate. The *Palace* was once occupied by Napoleon's sister Elisa Bacciocchi when duchess. The marble-quarries here are very valuable, rivalling those of Carrara.

Country fertile and well cultivated. The picturesque ruins of the castle of *Montignoso* become visible on an abrupt height to the left. — 83 M. *Querceta*; 3 M. to the left is the village of *Serravezza*, frequented as a summer-resort, with marble-quarries.

85 M. *Pietrasanta (Unione; Europa)*, a small town with ancient walls, beautifully situated among gentle slopes, was besieged and taken by Lorenzo de' Medici in 1482. The church of *S. Martino (Il Duomo)*, begun in the 13th cent., with additions extending down to the 16th cent., contains a pulpit and sculptures by *Staggio Stagi*. Ancient font and bronzes by *Donatello* in the *Battisterio*. *Campanile* of 1380. *S. Agostino*, an unfinished Gothic church of the 14th cent., contains a painting by *Taddeo Zacchia*, of 1519. The pinnacled *Town Hall* is situated in the *Piazza*, between these two churches. Quicksilver mines in the vicinity of *Pietrasanta*.

Near (91 M.) *Viareggio* (Hôtel Anglo-Américain; Albergo del Commercio), a small town on the coast, and a favourite sea-bathing place, the line enters the marshy plain of the *Serchio*, crosses the river beyond (94 M.) *Torre di Lago*, and reaches —

104 1/2 M. *Pisa* (p. 302). To the left at the entrance are seen the cathedral, the baptistery, and the campanile. The station is on the left bank of the Arno.

## IV. Lombardy.

The name of the Germanic tribe which invaded Italy in 568, is now applied to the country between the Alps and the Po, which is separated from Piedmont by the Ticino, and from Venetia by the Mincio. It is divided into the eight provinces of *Como, Milano, Pavia, Sondrio, Bergamo, Cremona, Brescia, and Mantova*, covering an area of about 9000 sq. M., and containing 3,460,824 inhab. The name was formerly applied to a much larger tract. Lombardy has not inaptly been likened to an artichoke, the leaves of which were eaten off in succession by the lords of Piedmont; thus in 1427 they appropriated Vercelli, in 1531 Asti, in 1703 Val Sesia, in 1736 Alessandria, Tortona, and Novara, and in 1743 Domo d'Ossola. The heart of the country, if we continue to use the simile, would then be the DISTRICT OF MILAN, or the tract lying between the Ticino, Po, and Adda. The three zones of cultivation are the same as in Piedmont, viz. the region of pastures among the mountains, that of the vine, fruit-trees, and the silk-culture on the lower undulating country and the slopes adjoining the lakes, and that of wheat, maize, and meadows in the plains, the yield of these last being, however, far more abundant than in Piedmont. The summers are hot and dry, rain being rare beyond the lower Alps, and falling more frequently when the wind is from the E. than from the W., as the moisture of the latter is absorbed by the Maritime Alps and the Apennines. The land, however, is more thoroughly irrigated than that of any other district in Europe, and the servitude of *aquae ductus*, or right to conduct water across the property of others, has been very prevalent here for centuries. A failure of the crops indeed is hardly possible, except when the summer is unusually cold. Meadows yield as many as twelve crops in the year, their growth being unretarded by the winter. The so-called Parmesan cheese is one of the well-known products of Lombardy. In the middle ages the importance of Milan was due to its woollen industries, but sheep-breeding has in modern times been superseded by the silk-culture, an industry which has so materially increased the wealth of the country, that it used to be said during the Austrian régime, that the army and the officers lived on mulberry leaves, as their produce alone sufficed to pay the land taxes. Under these circumstances the population is unusually dense (about 700 persons to the sq. mile, exclusive of the capital), being nowhere greater in Italy except in the province of Naples.

The central situation, and the wealth of the country, have ever rendered it an apple of discord to the different European nations. In the earliest period known to us, it was occupied by the *Etruscans*, an Italian race, which about the 6th cent. B.C. was subjugated or expelled by *Celts* from the W. These immigrants founded *Mediolanum* (Milan), and traces of their language still survive in the modern dialect of the country. It was but slowly that the Italians subdued or assimilated these foreigners, and it was not till B.C. 220 that the *Romans* extended their supremacy to the banks of the Po. In the following century they constituted *Gallia Cisalpina* a province, on which Caesar conferred the rights of citizenship in B.C. 46. Throughout the whole of the imperial epoch these regions of Northern Italy formed the chief buttress of the power of Rome. Since the 4th cent. Milan has surpassed Rome in extent, and, in many respects, in importance also. It became an imperial residence.


and the church founded here by St. Ambrosius (who became bishop in 374), long maintained its independence of the popes. The *Goths*, and afterwards the *Lombards*, made Pavia their capital, but their domination, after lasting for two centuries, was overthrown by *Charlemagne* in 774. The Lombard dialect also contains a good many words derived from the German (thus. *bron. gast, grà, piò, smessor, storà, stosà*, etc., from the German *Brunnen. Gast, Greis. Pflug, Messer, stören, and stossen*). The crown of Lombardy was worn successively by the *Franconian* and by the *German Kings*, the latter of whom, particularly the *Othos*, did much to promote the prosperity of the towns. When the rupture between the emperor and the pope converted the whole of Italy into a Guelph and Ghibelline camp, Milan formed the headquarters of the former, and Cremona those of the latter party, and the power of the *Hohenstaufen* proved to be no match for the Lombard walls. The internal dissensions between the nobles and the townspeople, however, led to the creation of several new principalities. In 1287 *Matteo degli Visconti* of Milan (whose family was so called from their former office of 'viccomites', or archiepiscopal judges) was nominated 'Capitano del Popolo', and in 1294 appointed governor of Lombardy by the German King. Although banished for a time by the Guelph family Della Torre, both he and his sons and their posterity contrived to assert their right to the Signoria. The greatest of this family was *Giovanni Galeazzo*, who wrested the reins of government from his uncle in 1385, and extended his duchy to Pisa and Bologna, and even as far as Perugia and Spoleto. Just, however, as he was preparing at Florence to be crowned king of Italy, he died of the plague in 1402, in the 55th year of his age. On the extinction of the *Visconti* family in 1447, the condottiere *Francesco Sforza* ascended the throne, and under his descendants was developed to the utmost that despotism which Leo describes as 'a state in which the noblest institutions prosper when the prince is a good man; in which the greatest horrors are possible when the prince cannot govern himself; a state which has everywhere thriven in Mohammedan countries, but rarely in the middle ages in other Christian countries besides this'. In 1494 when *Lodovico il Moro* induced Charles VIII. of France to undertake a campaign against Naples, he inaugurated a new period in the history of Italy. Since that time Italy has at once been the battlefield and the prey of the great powers of Europe. *Lodovico* himself, after having revolted against France and been defeated at Novara in 1500, terminated his career in a French dungeon. In 1525 the battle of Pavia constituted *Charles V.* arbiter of the fortunes of Italy. In 1535, after the death of the last *Sforza*, he invested his son, Philip II. of Spain, with the duchy of Milan. In 1713 the Spanish supremacy was followed by the *Austrian* in consequence of the War of Succession. On four occasions (1733, 1745, 1796, and 1800) the French took possession of Milan, and the Napoleonic period at length swept away the last relics of its mediæval institutions. Although *Napoleon* annexed the whole of Piedmont, Genoa, Parma, Tuscany, and Rome (about 36,000 sq. M. of Italian territory) to France, the erection of a kingdom of Italy contributed materially to arouse a national spirit of patriotism. This kingdom embraced Lombardy, Venice, S. Tyrol, Istria, the greater part of the Emilia, and the Marches (about 32,000 sq. M.). Milan was the capital, and *Napoleon* was king, but was represented by his stepson *Eugene Beauharnais*. The *Austrian Supremacy*, which was restored in 1815, proved irreconcilable with the national aspirations of the people. By the Peace of Zurich (10th Nov. 1859), Lombardy, with the exception of the district of Mantua, was ceded to *Napoleon III.*, and by him to Piedmont.

## 20. Milan, Ital. *Milano*.

**Arrival.** The *Railway-Station*, a handsome and well arranged structure, is decorated with frescoes by Pagliano, Induno and Casnedi, and with sculptures by Vela, Strazza, Magni, and Tabacchi. Omnibuses from most of the hotels are in waiting (fare 1-1½ fr.). Fiacre from the station to any part of the town 1½ fr. (also at night), each article of luggage




# MILANO.



- A.**
1. Area della Pace (del Serpione)
  2. Area
  3. Biblioteca Ambrosiana
  4. Casa di Papa
- B.**
- Chiese principali**
5. Cattedrale
  6. S. Ambrogio
  7. S. Andrea
  8. S. Angelo
  9. S. Antonia
  10. S. Babila
  11. S. Calisto
  12. S. Carlo
  13. S. Eufemia
  14. S. Felice
  15. S. Gerardo
  16. S. Francesco di Paola
  17. S. Gerardo
  18. S. Lorenzo
  19. S. Marco
  20. S. Maria del Carmine presso S. Celso delle Grazie
  21. S. Maria delle Grazie
  22. S. Maria della Spina
  23. S. Maria della Pace

- F.**
24. S. Maria della Passione alla Torre
  25. S. Maria della Pace
  26. S. Maria della Spina
  27. S. Marziano ad Ossone
  28. S. Michele ad Ossone
  29. S. Nazario
  30. S. Pietro in Formosa
  31. S. Ruffino
  32. S. Siro
  33. S. Siro
  34. S. Siro
  35. S. Siro
  36. S. Vittore
  37. Comunità Protestante
  38. Collegio Militare
  39. Conservatorio di Musica
  40. Università di Milano
  41. Università di Milano
  42. Università di Milano
  43. Università di Milano
  44. Università di Milano
  45. Università di Milano
  46. Università di Milano
  47. Università di Milano
  48. Università di Milano
  49. Università di Milano
  50. Università di Milano
  51. Università di Milano
  52. Università di Milano
  53. Università di Milano
  54. Università di Milano
  55. Università di Milano
  56. Università di Milano
  57. Università di Milano
  58. Università di Milano
  59. Università di Milano
  60. Università di Milano
  61. Università di Milano
  62. Università di Milano
  63. Università di Milano
  64. Università di Milano
  65. Università di Milano
  66. Università di Milano
  67. Università di Milano
  68. Università di Milano
  69. Università di Milano
  70. Università di Milano
  71. Università di Milano
  72. Università di Milano
  73. Università di Milano
  74. Università di Milano
  75. Università di Milano
  76. Università di Milano
  77. Università di Milano
  78. Università di Milano
  79. Università di Milano
  80. Università di Milano
  81. Università di Milano
  82. Università di Milano
  83. Università di Milano
  84. Università di Milano
  85. Università di Milano
  86. Università di Milano
  87. Università di Milano
  88. Università di Milano
  89. Università di Milano
  90. Università di Milano
  91. Università di Milano
  92. Università di Milano
  93. Università di Milano
  94. Università di Milano
  95. Università di Milano
  96. Università di Milano
  97. Università di Milano
  98. Università di Milano
  99. Università di Milano
  100. Università di Milano



- |                                         |         |                                |         |                                      |      |                   |      |
|-----------------------------------------|---------|--------------------------------|---------|--------------------------------------|------|-------------------|------|
| 18. Palazzo Reale                       | F. 6    | St. Antonio di S. Lorenzo      | C. 7    | 66. S. Raderonda, Teatro             | E. 6 | Alberghi.         | F. 6 |
| 19. Acquasanti.                         | E. 6    | 38. Palazzo                    | F. 6    | 67. Tribunale Civile e Conservatorio | F. 6 | Hotel de la ville | F. 6 |
| 20. Chiesa di Santissima di bella unit. | F. 6    | 39. Scuola di Musica Veneranda | G. 4    | 68. (Pia) Pontale                    | D. 6 | Grand Hotel Royal | D. 6 |
| 21. del Comandante (Marsa)              | D. 4    | 40. Seminario Arcivesc.        | F. 5    | 69. Villa Reale                      | F. 4 | Hotel Bacciniana  | D. 6 |
| 22. Municipio (Marsa)                   | E. 5    | 41. Teatri.                    | F. 5    | 70. Villa Reale                      | F. 4 | Grand Hotel       | D. 6 |
| 23. della Pevetara                      | F. C. 5 | 62. Scala                      | D. E. 5 | 71. Leone                            | F. 4 | Hotel Bacciniana  | D. 6 |
| 24. Piani                               | F. 5    | 63. Cronobianca                | F. 6    |                                      | F. 4 | Hotel Bacciniana  | D. 6 |
| 25. Lilla                               | C. 5    | 64. Marsani                    | F. 7    |                                      | F. 4 | Hotel Bacciniana  | D. 6 |
| 26. Rover Saporiti                      | G. 1    | 65. Di. Terme                  | C. 5    |                                      | F. 4 | Hotel Bacciniana  | D. 6 |
|                                         |         | 66. S. Gerardo                 | C. 5    |                                      | F. 4 | Hotel Bacciniana  | D. 6 |

Geograph. Anst. v. W. Ernst, Debes, Leipzig





25 c. — Omnibus to the cathedral 25 c. — Porterage to the town for luggage under 100 lbs. 50 c., according to tariff.

**Hotels.** \*GRAND HÔTEL DE LA VILLE (Pl. a), CORSO Vittorio Emanuele, opposite the church of S. Carlo, D. 6 fr.; \*HÔTEL CAVOUR, in the Piazza Cavour, near the station, expensive; \*GRAND HÔTEL CONFORTABLE, Via Carlo Alberto, near the Piazza del Duomo, new, the largest and handsomest of the hotels of Milan; \*GRAND HÔTEL DE MILAN (Pl. h), Via del Giardino 29; HÔTEL REICHMANN & \*GRAN BRETAGNA (Pl. d), Via Torino; HÔTEL ROYAL (Pl. b), Via Tre Re. All these are of the first class; average charges: R. 3 fr. and upwards, B. 1½, D. 5, L. and A. 2, omnibus 1½ fr. — The following are good second-class hotels: \*EUROPA (Pl. e), CORSO Vittorio Emanuele 9; HÔTEL MANIN, Via Manin, near the Giardini Pubblici, R. 2½, D. 4½ fr.; \*ROMA, CORSO Vittorio Emanuele 7 (with restaurant, no table d'hôte), omnibus 1 fr.; \*POZZO, Via Torino, near the Ambrosiana; \*FRANCIA, CORSO Vittorio Emanuele 19; \*S. MARCO (Pl. f), Via del Pesce; \*BELLA VENEZIA (Pl. g), Piazza S. Fedele; \*ANCORA, Via Agnello and Corso Vitt. Emanuele; \*LEONE, CORSO Vitt. Emanuele, at the corner of the Via Durini. Italian hotels, with restaurants: \*TROISSUISSES, Via Larga 16, R. 2 fr.; HÔTEL PENSION SUISSE, commercial; FALCONE, well spoken of; REBECCHINO, Via S. Margherita; ALBERGO FIRENZE, Via Principe Umberto, near the station; BORSA, Via S. Giuseppe; AQUILA, Via S. Margherita, moderate; PASSERELLA; CORONA D'ITALIA; BISCIONE; AGNELLO, CORSO Vitt. Emanuele 4.

**Restaurants (Trattorie).** \*Cova, with a garden, Via S. Giuseppe, near the Scala, concerts in the evening (10 c. added to the charge on each refreshment, except on Sundays when the charge of admission is 50 c.); *Trattoria della Borsa (Canetta)*, Via S. Giuseppe, near the Scala; \*Biffi, *Gnocchi*, in the Galleria Vittorio Emanuele (see below); \*Rebecchino, Via S. Margherita, near the Piazza del Duomo, an old established house, founded in 1699. The above-mentioned second-class hotels are also restaurants. *Isola Botta*, outside the town, by the Triumphal Arch (p. 133), a favourite resort on holidays. *Fiaschetta Toscana*, opposite the Rebecchino, near the W. branch of the Galleria Vittorio Emanuele; good Tuscan wine.

**Cafés.** \*Biffi and \*Gnocchi, both in the Galleria Vitt. Emanuele, concerts in the evening; *Cova* (see above); *Martini*, Piazza della Scala; \*Europa, CORSO Vitt. Emanuele, near the Hôtel de la Ville (concerts every evening); several cafés in the *Giardini Pubblici* (p. 132); *delle Colonne*, CORSO Venezia 1. Déjeuner à la fourchette may be procured at most of the cafés; also good beer in glasses (tazza, 30 c.; tazza-grande, 50 c.). — Ices (*sorbetto*, and '*pezzi duri*' or ices frozen hard) are not to be had before 4 p.m.; at an earlier hour, '*granita*', or half-frozen, is in vogue. — *Panetone* is a favourite kind of cake, especially at the time of the Carnival.

**Beer.** *Birreria Nazionale*, a large establishment in the Via Carlo Alberto, on the W. side of the Piazza del Duomo (Vienna beer); *Birreria Mazzola*, CORSO Vittorio Emanuele (Bavarian and Vienna beer); \**Trenk*, Galleria de' Cristoforis (p. 132).

**Baths.** CORSO Vittorio Emanuele 17, clean and not expensive; Via Pasquirolo 11, etc. — Swimming-Baths: \**Bagno di Diana* (Pl. 60), outside the Porta Venezia; *Bagno Nazionale*, outside the Porta Ticinese.

**Cabs ('Broughams';** a tariff in each vehicle). Per drive by day or night 1 fr.; from the station to the town, 1¼ fr.; half-hour 1 fr., per hour 1½ fr.; each article of luggage 25 c.

**Omnibuses** from the Piazza del Duomo to the different gates, the names of which are painted on the omnibus, 10 c., to the railway-station 25 c.; the most frequented are the '*Porta Ticinese*' and the '*Porta Garibaldi*' lines. A saving of time is often effected by using these vehicles.

**Post Office** (Pl. 68), Via Rastrelli 20, near the cathedral, at the back of the Palazzo Reale, open from 8 a.m. to 9 p.m. — **Telegraph Office** (Pl. 69), near the *Borsa*, Piazza dei Mercanti 19, first floor.

**Theatres.** The *Teatro della Scala* (Pl. 62), the largest in Italy after the S. Carlo theatre at Naples, was built in 1778, and holds 3600 spectators. The opera and ballet are excellent, but performances take place during the Carnival only; the interior is worthy of inspection (1 fr.). *Teatro*

*alla Canobbiana* (during the Carnival only; Pl. 63), with ballet; *Teatro Manzoni* (Pl. 64), near the Piazza della Scala, elegantly fitted up, performances sometimes in French. *Teatro dal Verme* (Pl. 65), operas in summer and autumn, dramas and comedies during the Carnival. The arrangements at the new *Teatro Castelli*, Via Palermo (Pl. D.4), are similar; at both theatres the ballet is admirable, and there are occasionally equestrian performances. *S. Radegonda* (Pl. 66), operas, etc.

**Bankers.** *Finck & Scherbius*, Via Andegari; *Mack, Wiegel & Keutzer*, Via Orso 16; *Mylius & Co.*, Via Clerici 4; *Ulrich & Co.*, Via Bigli 21; *Weill, Schott Figli, & Co.*, Via Pietro Verri 7.

**Booksellers.** *F. Sacchi & Figli* (formerly *Artaria*), Via S. Margherita; *Hoepli*, Galleria de' Cristoforis (p. 132); *G. Brigola*, Corso Vittorio Emanuele 26; *A. Vallardi*, Via S. Margherita.

**Shops.** The best are in the Corso and the Galleria Vittorio Emanuele. The *Silk Industry* of Milan, in which upwards of 200 considerable firms are engaged, is very important. The following are noted retail dealers: *Vernazzi*, Corso Vittorio Emanuele, adjoining the Hôtel de la Ville; *Osnaggi*, Via S. Radegonda, a little to the N. of the Cathedral. — Marbles; *Bianchi*, Via Rastrelli 12. — Optician: *Fries*, Via S. Margherita 7. — Chemist: *Zambelletti*, Piazza S. Carlo, opposite the Hôtel de la Ville.

**Cigars.** The Spaccio Normale, or government shop, is No. 18, Corso Vitt. Emanuele, where genuine havanas are also sold.

**Permanent Art Exhibition:** Via S. Primo, open daily.

**English Church Service,** Vicolo San Giovanni della Conca 12.

**Principal Attractions:** Cathedral, ascend tower; Galleria Vittorio Emanuele; Brera (picture-gallery); Arco della Pace; S. Maria delle Grazie and Leonardo da Vinci's Last Supper; S. Ambrogio, the oldest, and S. Alessandro, the most sumptuous of the churches; Piazza de' Mercanti; the new cemetery; between 6 and 7 p.m. walk through Corso Vittorio Emanuele to and beyond the Porta Venezia.

*Milan* (390 ft.), surnamed '*la grande*', the *Mediolanum* of the Romans, which was rebuilt after its total destruction in 1162 by the Emp. Frederick Barbarossa, is the capital of Lombardy, the seat of an archbishop and one of the wealthiest manufacturing towns in Italy, silk and woollen goods being the staple commodities. It is situated on the small river *Olon*, which however is navigable and is connected by means of the *Naviglio Grande* (p. 76) with the *Ticino* and *Lago Maggiore*, by the *Naviglio di Pavia* with the *Ticino* and the *Po*, and by the *Naviglio della Martesana* with the *Adda*, the *Lake of Como*, and the *Po*. The town is 7 M. in circumference, and contains 200,500 inhab., or, including the suburbs, about 300,000.

The favourable situation of Milan in the centre of Lombardy has always secured for it a high degree of prosperity. Under the *Romans* it was one of the largest cities in Italy (p. 117), but owing to its repeated destruction hardly a trace of that period has been left. Its heroic struggles against the German emperors are well known. With the exception of S. Ambrogio and a few other churches, the city was totally destroyed in 1162 by the emperor *Frederick Barbarossa*, but in 1167 rebuilt by the allied cities of Brescia, Bergamo, Mantua, and Verona. It was subsequently governed by the *Visconti* (1312-1447), then by the *Sforza* family (1447-1535). Under the supremacy of the latter it attained the zenith of its reputation as a patron of art, having been the residence of *Bramante* from 1476 to 1500, and of *Leonardo da Vinci* from 1494 to 1516. The most eminent of Leonardo's pupils who flourished here were *Bernardino Luini*, *Cesare da Sesto*, *Giov. Ant. Beltraccio*, *Marco da Oggiono*, *Andrea Salaino*, and *Giulio Ferrari*. — Milan with the rest of Lombardy afterwards fell into the hands of the *Spaniards*, and in 1714 fell to *Austria*. In 1796

it became the capital of the '*Cisalpine Republic*', and then (down to 1815) that of the *Kingdom of Italy*. The bloody insurrection of 17th May, 1848 compelled the *Austrians* to evacuate the city, and after they regained possession of it their unpopularity gave rise to frequent disturbances.

No town in Italy has undergone such marked improvement as Milan since the events of 1859. — In the province of Arr it has raised itself to the highest rank in the kingdom. Sculpture is here carried on to such an extent as to have become almost a special industry. The Milanese SCULPTORS take great pride in their technical skill, and in effective imitations of nature. Among the best known sculptors are *Magni, Peduzzi, Tandardini, Barzaghi, Argenti, Calvi, and Baccaglia*. — PAINTING is represented by *Fr. Hayez, Anduno, Bianchi, Mussini, Passini*, and others, but most of these artists seem to cultivate the modern Parisian style, and to be entirely oblivious of their glorious old national traditions.

The old part of the town, a portion of which consists of narrow and irregular streets, is enclosed by canals, beyond which suburbs (*borghi*), named after the different gates, have sprung up. Of the latter, thirteen in number, the principal are the *Porta Venesia* at the extremity of the handsome new *Corso Venezia*, the prolongation of which, the *Corso Vittorio Emanuele*, the principal street of Milan, leads to the cathedral; the *Porta Sempione* (p. 133), and between these the *Porta Garibaldi* (formerly *Comasina*, i.e. Gate of Como), erected in 1828.

The focus of the commercial and public life of Milan is the \**Piazza del Duomo* (Pl. D, E, 6), which was formerly cooped up between insignificant lanes, but has recently been much extended, and is now enclosed by imposing edifices designed by *Giuseppe Mengoni*, and still partly unfinished, forming with the cathedral a striking architectural whole.

The celebrated \*\**Cathedral* (Pl. 5), dedicated '*Mariæ Nascenti*', as the inscription on the façade announces, and as the gilded statue on the tower over the dome also indicates, erected in the Gothic style, is regarded by the Milanese as the eighth wonder of the world, and is, next to St. Peter's at Rome and the cathedral at Seville, the largest church in Europe. The interior is 159 yds. in length, 61 yds. in breadth; nave 155 ft. in height, 17 yds. in breadth. The dome is 220 ft. in height, the tower 360 ft. above the pavement. The roof is adorned with 98 Gothic turrets, and the exterior with upwards of 2000 statues in marble. The structure, which was founded by the splendour-loving *Gian Galeazzo Visconti* in 1386, apparently after the model of the Cologne cathedral, progressed but slowly owing to the dissensions and jealousies of the Italian and Northern architects, whereby it was impossible to attain uniformity in the execution. *Enrico di Gamodia* (Heinrich von Gmünd), one of the numerous competing architects from France and Germany, has erroneously been called the builder of the cathedral. The whole was finished in its principal parts at the close of the 15th century in accordance with the designs of *Francesco di Giorgio* (dome), and *Giov. Ant. Omodeo*, excepting the ornamentation of the façade (doors and windows), which was executed in the Renaissance style by *Pellegrino Tibaldi* in the middle of the 16th cent.

In 1805 Napoleon caused the works to be resumed, and the tower over the dome to be added, and at the present day additions and repairs are constantly in progress.

The church is cruciform in shape, with double aisles, and a transept also flanked with aisles. The INTERIOR is supported by 52 pillars, each 12 ft. in diameter, the summits of which are adorned with canopied niches with statues instead of capitals. The pavement consists entirely of mosaic in marble of different colours. The vaulting is skilfully painted in imitation of perforated stone-work.

INTERIOR. By the principal inner portal are two huge monolith columns of granite from the quarries of Baveno (see p. 27). The band of brass in the pavement close to the entrance indicates the line of the meridian. SOUTH AISLE: Sarcophagus of Bishop Heribertus Antimianus (d. 1045), with crucifix. Gothic monument of Bishop Marcus Corellus. SOUTH TRANSEPT (W. wall): Monument of the brothers Giacomo and Gabriele de' Medici, erected by their brother Pope Pius IV. (1564), the three bronze statues by *Leone Leoni* (Aretius). Tickets for the roof (25 c., see below) are obtained near this monument; the staircase leading to the dome is in the corner of the side-wall. The altar of the Offering of Mary (E. wall of S. transept) is adorned with fine Reliefs by *Agostino Busti* (*Bambaja*; p. 126); adjacent is the Statue of St. Bartholomew by *Marcus a Grate* (end of 16th cent.), anatomically remarkable, as the saint is represented flayed, with his skin on his shoulder, and bearing the modest inscription 'non me Praxiteles sed Marcus finxit Agratus'.

The door of the S. SACRISTY (to the right, in the choir) is remarkable for its richly sculptured Gothic decorations. (The *Treasury* here may be inspected, fee 1 fr.; among other valuables it contains life-size statues in silver of S. Ambrogio and S. Carlo Borromeo, and the ring and staff of the latter.) — A little farther on is the marble Monument of Cardinal Marino Carraccioli (d. 1538), by whom Emp. Charles V. was crowned at Aix-la-Chapelle in 1520. The fourth of the handsome new Gothic confessionals is for the German, French, and English languages. The stained glass in the three vast choir windows, comprising 350 representations of scriptural subjects, were executed by *Alois* and *Giov. Bertini* of Guastalla during the present century; most of them are copies from old pictures. Before the N. SACRISTY is reached, the Statue of Pius IV. is seen above, in a sitting posture, by *Angelo Siciliano*. The door of this sacristy is also adorned with fine sculptures in marble.

By the E. wall of the N. TRANSEPT is an altar with the Crucifixion in high relief, by *Ant. Prestinari*. In the centre of this transept, in front of the altar, is a valuable bronze *Candelabrum*, in the form of a tree, executed in the 13th cent., and decorated with jewels, presented by *Giov. Batt. Trivulzio*, in 1562.

NORTH AISLE: Altar-piece, painted in 1600 by *Fed. Baroccio*, representing S. Ambrogio releasing Emp. Theodosius from ecclesiastical penalties. Upon the adjoining altar of St. Joseph, the Nuptials of Mary, by *F. Zuccherò*. The following chapel contains the old wooden *Crucifix* which S. Carlo Borromeo bore in 1576, when engaged, barefooted, in his missions of mercy during the plague. Under the next window is a Monument, with a relief of the Virgin in the centre, by *Marchesi*: on the right and left the two SS. John by *Monti*. Not far from the N. side door is the *Font*, consisting of a sarcophagus of S. Dionysius, but appropriated to its present use by S. Carlo Borromeo. The canopy is by *Pellegrini*.

In front of the choir, below the dome, is the subterranean *Cappella S. Carlo Borromeo* (p. 156), with the tomb of the saint; entrance opposite the doors to the sacristy, to the N. and S. of the choir (open in summer 5-10, in winter 7-10 a.m.; at other times 1 fr.; for showing the relics of the saint 5 fr.).

The traveller should not omit to ascend to the \*Roof and Tower of the Cathedral. The staircase ascends from the corner of the right transept (ticket 25 c.; map of town and environs 1½ fr.). As single visitors are not now admitted, a party of two or more must be made up (comp. p. 306). The visitor should mount at once to the highest gallery of the tower (by 194 steps inside and 300 outside the edifice). A watchman, generally stationed at the top, possesses a good telescope. The cathedral is opened at 5 a.m. in summer; no visitors admitted after an hour before sunset. The finest views of the Alps are obtained early. To the extreme left (S.W.), Monte Viso, then Mont Cenis (p. 24); farther distant, between these two, the Superga (p. 74) near Turin; Mont Blanc, Great St. Bernard; Monte Rosa, the most conspicuous of all; to the left of the last the prominent Matterhorn; then the Cima di Jazi, Strahlhorn, and Mischabel; N.W. the Monte Leone near the Simplon; the Bernese Alps; N. the summits of the St. Gotthard and Splügen, and E. in the distance the peak of the Ortler. S. the Certosa of Pavia (p. 161) is visible, farther E. the towers and domes of Pavia itself, in the background the Apennines.

To the S., opposite the cathedral, is situated the *Palazzo Reale* (Pl. 48), built on the site of a palace of the Visconti in 1772, adorned with frescoes by A. Appiani, B. Luini, and Hayez, and a handsome ballroom (Sala delle Cariatide), etc. — Adjoining it, on the E., is the large *Archiepiscopal Palace* (*Arcivescovado*; Pl. 49), erected by Pellegrini in 1565, containing a handsome court with a double colonnade and marble statues (Moses and Aaron) by Tandardini.

The W. side of the Piazza del Duomo is skirted by the *Via Carlo Alberto* (see p. 131), beyond which, to the N.W., lies the *Piazza de' Mercanti* (see p. 127).

On the N. side is the imposing new palatial façade which forms the entrance to the \**Galleria Vittorio Emanuele* (Pl. 40; E, 5, 6), connecting the Piazza del Duomo with the Scala. This is the most spacious and attractive structure of the kind in Europe. It was built in 1865-67 by the architect *Gius. Mengoni*, and is said to have cost 8 million fr. (320,000 l.). Length 320 yds., breadth 16 yds., height 94 ft. The form is that of a Latin cross, with an octagon in the centre, over which rises a cupola 180 ft. in height. The decorations are well-executed and bear testimony to the good taste of the Milanese. The octagon is adorned with frescoes, representing Europe, Asia, Africa, and America, while the frescoes on the entrance-arches are emblematic of Science, Industry, Art, and Agriculture. The gallery contains handsome shops, and is lighted in the evening by 2000 gas-jets. The circle of gas-jets in the dome is lighted by a small engine set in motion by clockwork, which does its work in 1½ min., and attracts numerous spectators. The gallery is adorned with 24 statues of celebrated Italians: at

the entrance from the Piazza del Duomo, Arnold of Brescia and G. B. Vico; in the octagon, on the right, Cavour, Emmanuel Philibert (p. 67), Vittore Pisano, Gian Galeazzo Visconti (p. 118); Romagnosi, Pier Capponi, Macchiavelli, Marco Polo; Raphael, Galileo, Dante, Michael Angelo; Volta, Lanzone, Giov. da Procida, Beccaria; at the right lateral outlet Beno de' Gozzadini and Columbus, at the left lateral outlet Ferruccio and Monti; at the entrance from the Scala, Savonarola and Ugo Foscolo.

The PIAZZA DELLA SCALA (Pl. E, 5) is embellished with the \**Monument of Leonardo da Vinci* (1452-1519) by Magni, erected in 1872. The statue of the master in Carrara marble, over life-size, stands on a lofty pedestal, surrounded by Marco d'Oggiono, Cesare da Sesto, Salaino, and Beltraffio, four of his pupils, and adorned with copies of his principal works in relief. — In the piazza, to the W. of the statue, is the *Teatro della Scala* (p. 119), to the E. is the large *Palazzo del Marino*, in which the *Municipio* (Pl. 52) has been established since 1861, erected in 1555 from designs by Galeazzo Alessi, with a massive façade (S.E. side) and interesting court.

Beyond it is the Jesuit church of *S. Fedele* (Pl. 15) in the Piazza of that name, erected by S. Carlo Borromeo in 1569 from designs by *Pellegrini*, containing a sumptuous high altar. The adjoining *Palazzo del Censo ed Archivio*, formerly the Jesuit college, contains part of the government archives, chiefly documents relating to the history of Milan.

We next proceed from the Piazza della Scala to the N. by the Via S. Giuseppe (Pl. E, D, 5) and Via di Brera to the Brera. In the Via del Monte di Pietà, the second side-street on the left, is the handsome new *Cassa di Risparmio*, or savings-bank, an imitation of the Palazzo Strozzi at Florence.

The \**Brera* (Pl. 50; D, 4; Via di Brera 28), or *Palazzo delle Scienze ed Arti*, formerly a Jesuits' College, contains the *Picture Gallery*, the *Library of the Academy* founded in 1170 (200,000 vols.; open daily), a *Collection of Coins* (50,000), the *Observatory*, a collection of *Casts* from the antique, and an *Archaeological Museum*.

The handsome COURT by Ricchini contains statues in marble of the political economist Count *Pietro Verri*, the architect Marchese *Luigi Cagnola* (d. 1833), *Tommaso Grossi*, the mathematicians *Gabrio Piola* and *Fra Bonaventura Cavalieri* (d. 1647), and of *Carlo Ottavio Castiglione*. In the centre of the court is a bronze statue of *Napoleon I.*, as a Roman emperor, with a long staff in his left hand and in his right a statue of Victory, by *Canova*, considered one of his finest works. By the staircase, to the left, the statue of the celebrated jurist *Beccaria* (d. 1794), who in his treatise '*dei delitti e delle pene*' was the first to call in question the justice of capital punishment; to the right, that of the satirist *Gius. Parini* (d. 1799), professor of rhetoric at the college of the Brera.

The \*PICTURE GALLERY (*Pinacotēca*) contains upwards of 800 works arranged in thirteen rooms. (Admission daily, 9-4, in winter 9-3 o'clock, 1 fr.; Sundays gratis, but not open till 12.)

The gem of the collection is *Raphael's Spozalizio* (No. 334), the chief work of his first or Umbrian period. The numerous pictures of the Lombard school, and particularly the frescoes sawn out of churches, are also very valuable. The drawing of the head of Christ for the last Supper (No. 328) shows with what beauty *Leonardo* could invest his figures. Among the oil-paintings, No. 329 by *Bernardino Luini* is a very meritorious work, and among the frescoes, Nos. 45 and 50, by the same master. The most interesting works of the early Italian school are No. 147 by *Gentile da Fabriano*, and No. 168 by *Mantegna*. The collection also affords an instructive survey of the progress of *Carlo Crivelli* (who flourished in 1468-93; 3rd and 8th rooms), a master who connects the Paduan school with that of Venice. The most notable works of the latter school are No. 155 by *Gentile Bellini*, Nos. 220 and 312 by *Giovanni Bellini*, and No. 287 by *Cima da Conegliano*; and of a later period No. 363 by *Bonifazio*, No. 75 by *Titian*, and Nos. 369, 370, 371 by *Lorenzo Lotto*. No. 94 by *Domenichino*, and No. 319 by *Guercino*, represent the Italian masters of the 17th cent. The most important works of foreign schools are No. 91 by *Rubens*, Nos. 81 and 385 by *Van Dyck*, and No. 330 by *Rembrandt*. Each picture bears the name of the painter. Catalogue 1 fr.

The numbers of the pictures are frequently altered. The following are from the *Catalogue of 1874*.

I. and II. ANTE-CHAMBERS: 1-70. Frescoes by *Ferrari*, *Bramantino*, *Foppa*, *Marco da Oggiono*, and particularly by *Bernardino Luini*, some of them approaching the genre style (Nos. 12, 62), scenes from the life of Mary (40, 41, 51, \*67), \*Madonna with St. Anthony and St. Barbara (45), Angels (13, 25, 47, 52, 66), and St. Catharine borne by angels (50); *Gaudenzio Ferrari*, Adoration of the Magi (24).

ROOM I.: \*75. *Titian*, St. Jerome; 79. *Palma Vecchio* (?), a picture in three sections, Constantine and Helena, St. Rochus and St. Sebastian; \*81. *Van Dyck*, Madonna and St. Anthony of Padua; \*91. *Rubens*, The sacrament; \*94. *Domenichino*, Madonna enthroned, with the Child, and SS. John the Evangelist and Petronius; 96. *Paris Bordone*, Baptism of Christ; 115. *Tintoretto*, Pietà.

ROOM II.: (on the left) 120. *Giacono Francia*, Madonna in the clouds and saints (1544); 124-126. *Paolo Veronese*, Adoration of the Magi, (left) St. Gregory and St. Jerome, (right) St. Ambrose and St. Augustine; 129. *Moretto*, Madonna on clouds and three saints; 134. *Palma Vecchio*, Adoration of the Magi; 142. *Girolamo Savoldo*, Madonna and four saints; 144. *Paolo Veronese*, SS. Cornelius, Antonius Abbas, Cyprian, and a monk with a page.

ROOM III.: 147. \**Gentile da Fabriano*, Coronation of Mary; 149. *Carlo Crivelli*, Madonna and four saints; \*155. *Gentile Bellini*, Preaching of St. Mark at Alexandria; 158. *Bartolommeo Montagna*, Madonna enthroned, angels playing on instruments, and four saints (1499); 164. *Timoteo della Vite*, Annunciation and two saints; \*168. *Andrea Mantegna*, Picture in twelve sections; 173. *Giovanni Santi* (father of Raphael), Annunciation; 179. *Antonio* and *Giovanni da Murano*, Altar-piece in fourteen sections; 184. *Paolo Veronese*, Christ in the house of the Pharisee; 185. *Martino da Udine*, St. Ursula and her virgin attendants (1507); 187. *Garofalo*, The Maries at the Cross; 189. *Carlo Crivelli*, Crucifixion; 192. *Giotto*, Madonna and child (from S. Maria degli Angeli at Bologna, p. 282); 195. *Stefano da Ferrara*, Madonna; 199. *Crivelli*, Madonna enthroned.

ROOM IV.: 212. *Affer Correggio*, Madonna and Child, with two saints; \*220. *Giovanni Bellini*, Pietà; 234. *Vittore Carpaccio*, St. Stephen and the scribes (1514); 205, 206. *Canaletto*, Landscapes; 282. *Jan Breughel*, Genre-picture.

ROOM V.: 258. *Liberale da Verona*, St. Sebastian.

ROOM VI.: 287. *Cima da Conegliano*, John the Baptist, St. Peter, and St. Paul; 292, 293. *Giov. Bellini* (?), Madonnas; 296. *Francesco Albani*,



Cupids dancing; 313. *Garofalo*, Madonna; \*312. (*Gior. Bellini*), Madonna (1510).

ROOM VII.: 315. 'Il Bersaglio de' Dei' (shooting-match of the gods), a sketch attributed to Raphael, but apparently marked as a work of Michael Angelo by Raphael's own hand; \*319. *Guercino*, Abraham and Hagar; 323. *Cesare da Cesto*, Madonna; 324. *Signorelli*, Scourging of Christ; \*326. *Velasquez*, Monk asleep; \*328. *Leonardo da Vinci*, Study for the head of Christ in the Last Supper; 329. *Bern. Luini*, Madonna in an arbour of roses; \*330. *Rembrandt*, Portrait of a lady; \*334. *Raphael's* far-famed Spozalizio, or the Nuptials of the Virgin, an early work of the master (1504), with a considerable resemblance to Perugino's Spozalizio which is now at Caen.

ROOM VIII.: 343. *Francesco Francia*, Annunciation; 358. *Crivelli*, St. Antonio Abbate, St. Jerome, and St. Andrew; 349. The same, St. James with St. Bernardino and Pellegrino; 351. *Civetta (Herri met de Bles?)*, Nativity, Adoration, Flight into Egypt; \*350. *Andrea Mantegna*, Pietà, 'a tempera' on canvas; 353. *Vitt. Carpaccio*, Presentation in the Temple; 355. *Guido Reni*, Peter and Paul.

ROOM IX.: \*363. *Bonifazio*, Finding of Moses; \*371, \*369, \*370. *Lorenzo Loto*, Portraits; 381. *Sassoferrato*, Madonna and Child; 384. *Moretto*, Assumption of the Virgin; \*385. *Van Dyck*, Portrait of a lady.

ROOM X.: 388. *Gaspard Poussin*, John the Baptist in the forest; 395. *Pietro da Cortona*, Madonna enthroned, with four saints; 427. *Bonifazio*, Christ at Emmaus; 441. *Salvator Rosa*, Forest scene with Peter the Hermit.

ROOM XI. (copying-room): 445. *Marco d'Oggiono*, Fall of Lucifer; 447. *Gaud. Ferrari*, Martyrdom of St. Catharine; 455. *Benedetto Crespini*, Circumcision of Christ; 459. *Cesare da Sesto*, Holy Family; 479. *Ambrogio Borgognone*, Assumption and Coronation of Mary.

To the left, farther on, are several rooms containing modern pictures, sketches of academicians, casts from the antique, Renaissance and modern sculptures. (An annual exhibition of art takes place in these rooms, generally in September.) — ROOM XIII.: *Canova*, Vestal Virgin; \**Thorvaldsen*, Monument of Andrea Appiani, Three Graces, and Cupid. — ROOM XXIV. (the last) contains two copies of *Leonardo da Vinci's* Last Supper, that 'al fresco' by *Marco d'Oggiono* being the best. — Returning hence to the ante-chamber, the visitor enters the GALLERIA OGGIONI to the right: 813. *Luini*, Holy Family; 762. *Crivelli*, Coronation of Mary (1493); 797. *Guido Reni* (?), St. Jerome.

The *Museo Archeologico* on the ground-floor (admission daily 10-3, Sundays 2-4; entrance in the small Piazza di Brera, or through a passage to the right on the ground-floor) contains a small collection, imperfectly arranged, of antique, mediæval, and Renaissance sculptures and ancient frescoes, chiefly found at Milan, or collected from churches now destroyed. The finest works are those of *Agostino Busti*, with the enigmatical surname of *Il Bambaja* (born about 1470). Nothing is known about this master, except that he was one of the best Italian sculptors of the 16th cent., and his skill seems to have been inherited by the Milanese statuary of the present day (p. 121).

I. Room. Wall of the door (right): I. Tomb-relief (Greek workmanship); adjoining it a Renaissance 'putto' between inscriptions and sculptures. Window-wall: Mediæval sculpture from the tympanum of a church; Gothic bell of 1352. Next wall: Roman and mediæval architectural fragments, ancient head in terracotta. Fourth wall: Portions of the monument of Gaston de Foix (who fell at the battle of Ravenna in 1512, see p. 294), from the monastery of S. Marta, the most important being (Æ.) a recumbent figure of the hero by *Bambaja*. D. Monument of Lancesio Curzio (d. 1513), by the same master. F. Marble framework of a door from the Casa Medici, attributed to *Michelozzo*. In the corner, C. Monument of Bishop Bagareto by *Bambaja*. — By the pillars to the right, and between them: Ancient Roman sarcophagus; T. Roman cippus. Last pillar: Fragment of a cippus, a youth leaning on a staff (Greek). By the pillars on the left, and between them: Head of

Zeus (nose modern). H. Torso of Venus with the dolphin. B. Monument of Regina della Scala, wife of Bernabò Visconti. In the centre: A. Large monument of Bernabò Visconti (d. 1385), from S. Giovanni in Conca, erected during his lifetime (1354), resting on twelve columns, and richly gilded; on the sarcophagus are reliefs, in front the four evangelists, at the back the coronation of Mary; at the sides the Crucifixion and a Pietà; above, the equestrian statue of the deceased. — II. Room. On the right, suits of armour and bronze implements from the graves of Gauls discovered near Sestri Calende in 1867; in the cabinets, relics from tombs excavated in the Nuovo Giardino Pubblico, terracottas, crystal, objects in ivory, etc.; also vases and Assyrian antiquities. On the walls are nine ancient frescoes, one of them in the style of Giotto.

A little to the W., in the Piazza del Carmine, is the Gothic church of **S. Maria del Carmine** (Pl. 20; D, 5) of the 15th cent., now modernised, containing a Madonna in fresco by *Luini*.

To the W. of the Piazza del Duomo, beyond the *Via Carlo Alberto* (p. 123), lies the interesting \***Piazza de' Mercanti** (Pl. 69; D, 6), the central point of the mediæval city, and formerly provided with five gates. In the centre of the Piazza is the building which was formerly the *Palazzo della Ragione*, a large hall erected in 1228-33 by the podestà (or mayor) Tresseno, to whom an equestrian statue was erected on the S. side with the inscription, 'qui solium struxit, Catharos ut debuit nssit' (the Cathari were a heretical sect). The ground-floor is now the corn-exchange, above which is the Archivio Notarile. On the N. side of the piazza is the ancient *Palazzo della Città* with a tower, erected in the 16th century, with the exchange on the ground-floor; on the S. side is the *Loggia degli Osii*, erected in 1315, adjoining which is the telegraph office.

We proceed hence to the S.W. (by the *Via degli Orefici* to the left) to the *Via* and *Piazza della Rosa*.

The celebrated \***Biblioteca Ambrosiana** (Pl. 3; D, 6), open daily 10-3 o'clock (fee 1 fr.; picture-gallery, or *Pinacoteca*, open to the public on Wed., 10-2½, but a fee expected, entrance from the reading-room to the right in the court), contains 140,000 vols. of printed books, and 20,000 MSS. and palimpsests, or *codices rescripti*, some of them very valuable. Director: *Cav. Gatta*. The library was founded in 1609 by the archbishop Cardinal *Federigo Borromeo*, to whom a statue was erected in front of the building in 1865.

The Court contains ancient inscriptions and a statue of *G. D. Romagnosi* (d. 1835), the teacher of constitutional law, and author of the criminal code for the Napoleonic Kingdom of Italy (1806).

The *Biblioteca* contains among other treasures the *Codice Atlantico*, being a collection of original drawings and MSS. of *Leonardo da Vinci*; Virgil with marginal notes by Petrarch; fragments of a MS. of Homer illuminated, of the end of the 4th cent.; a number of miniatures; letters of S. Carlo Borromeo, Tasso, Galileo, Liguori, etc. Then, Christ crowned with thorns, *al fresco*, *Bernardino Luini*; Cupid in marble, *R. Schadow*; several reliefs and bust of Byron by *Thorvaldsen*; mosaics, coins, old woodcuts, and drawings by celebrated masters. — *First Floor*. First door on the left: **Cabinet of Bronzes**, containing busts of Canova and Thorvaldsen, the latter by the master himself, and pictures of no great value:

46. *Rafael Mengs*, Pope Clement XIII.; without a number, *Marco Basaiti*, The risen Christ; 60. *Carlo Dolce*, John the Baptist; Adoration of the Magi, attributed to *Luca d'Olanda (Lucas of Leyden)*; models of Trajan's column and the obelisks at Rome. — Second door to the left: entrance to the — **Pinacoteca**. I. and II. Room, Engravings. — III. Room: without a number, *Annibale Carracci*, A colossal Mary from the Assunta of Correggio; 80. *Ambrogio Borgognone*, Madonna enthroned and saints; without a number, a small picture groundlessly attributed to Raphael; 82. *Girol. Mazzola*, Annunciation; without a number. *Botticelli*, Madonna with angels; *Rubens*, Lot's Daughters; *Dosso Dossi*, Washing of the feet; 96. *Lower Rhenish Master*, Madonna and Child. — The space to the right contains four landscapes, carefully painted by 'Velvet-Breughel' by order of Cardinal Federigo Borromeo. — The first door to the left leads to the — IV. Room of the DRAWINGS: immediately to the left, 'pen-and-ink sketches by A. Dürer (Samson and the Philistines, 1510; Coronation of Mary). In the 5th frame, sketches by *Leonardo da Vinci*, the finest the \*female head at the top to the left: Maria Sforza, second wife of Maximilian. By the window: A. *Mantegna*, Triumpb of Cæsar. Opposite wall: drawings by and after *Michael Angelo* (a frame with drawings for the Sistine Chapel). 4th wall, above: part of Raphael's cartoon of the Battle of Constantine, unfortunately half obliterated. — V. Room: Copy of *Leonardo da Vinci's* Last Supper by *Andrea Banchi*; 137. *Bernardino Luini*, Portrait-head; without number, \**Raphael*, Cartoon of the 'School of Athens'; 170. *Titian*, Adoration of the Shepherds (the other Titians are probably copies); 165. Holy Family with the young Tobias, attributed to *Giorgione*, but probably by *Girolamo Romanino*; between the windows, drawings by *Raphael*; 4th wall, under glass, \**Leonardo da Vinci*, Portrait of Isabella of Arragon (one of the few pictures by the master's own hand that have been preserved); 153. Portrait of her husband Galeazzo Sforza, also attributed to *Leonardo*; *Andrea Salaino*, John the Baptist. In the court are Roman inscriptions; stained glass by *Giov. Bertini* (p. 122); adjoining the porter's lodge, the Mocking of Christ, a fresco by *Bern. Luini*.

At the back of the library is the venerable church of *S. Sepolero* (Pl. 32; D, 6), dating from the 11th cent. The Via del Bollo leads hence to the W. to the Piazza S. Borromeo, in which are situated the *Palazzo Borromeo*, the small church of *S. Maria Podone*, and a statue of S. Carlo Borromeo. — The Via S. Borromeo and the Via S. Maria alla Porta next lead to the CORSO MAGENTA, on the left side of which rises the small church of *S. Maurizio* (Pl. 27; C, 5, 6), or *Monastero Maggiore*, erected in 1503-1519 by *Giov. Dolcebuono*, a pupil of Bramante, containing \*frescoes by *Luini*, the best of which are near the high altar. — Opposite, to the right, is the *Palace of the Duca Litta* (Pl. 55), whose picture gallery was sold in 1866, with a handsome court.

Farther on in the Corso Magenta, not far from the *Porta Magenta* (formerly *Vercellina*), on the right, is situated the church of —

\***S. Maria delle Grazie** (Pl. 22; B, 5, 6), an abbey-church of the 15th cent., the Gothic nave of which alone belongs to the original structure; the choir, transept, and dome were erected by *Bramante* in the early Renaissance style, partly in stone, and partly in brick, with curious enrichments in terracotta.

The 4th chapel on the right contains frescoes by *Gaudenzio Ferrari* (on the right the Crucifixion, on the left Christ crowned with thorns, Christ scourged), executed in 1542, his last works, and an altar-piece (Descent from the Cross) by *Caravaggio*. In the 6th chapel frescoes by *Piamingo*. To the right, on the organ above, a Madonna by *Luini*. In

the N. aisle John the Baptist by *Bugiardini*; the sacristy contains two frescoes by *Luini*, and good wood paintings on the cabinets.

In the S.E. angle of the small piazza to the N. of this church is the entrance to the refectory of the suppressed monastery of *Sta. Maria delle Grazie* (now a cavalry-barrack), containing the celebrated \*\*LAST SUPPER OF LEONARDO DA VINCI (shown daily 9-4, admission 1 fr.; on Sundays and Thursdays gratis; visitors knock at the door to the right; the 'custode del cenacolo', who is generally to be found in the refectory, supplies them with a printed explanation). The picture is unfortunately in bad preservation, chiefly from having been painted on the wall in oils. A fresco by *Donato Montorfano* (Crucifixion) of 1495, opposite the Last Supper, is in much better condition.

Deplorable as is the condition of the Last Supper, the chief work executed by Leonardo during his stay at Milan, the original alone exhibits to its full extent the emotions which the master intended to express, and which even the best copies fail to reproduce. The motive of the work has been well explained by *Goethe*: 'The shock by which the artist represents the company at the sacred repast as deeply agitated has been produced by the Master's words, One of you shall betray me. They have been pronounced; the whole party is in dismay, while he himself bows his head with downcast eyes. His whole attitude, the motion of his arms and hands, all seem to repeat with heavenly resignation, and his silence to confirm, the mournful words — It cannot be otherwise. One of you shall betray me.'

The Via delle Oche and the Via S. Vittore lead hence to the S.E. to the PIAZZA S. AMBROGIO, with the church of —

\***S. Ambrogio** (Pl. 7; B, C, 6), founded by St. Ambrose in the 4th cent. on the ruins of a temple of Bacchus, and dating in its present Romanesque form, with its peculiar galleries, from the 12th century. In front of the church is a fine atrium of the 9th cent., surrounded by arcades with ancient tombstones, inscriptions, and half-obliterated frescoes of the 12th century and earlier. The gates of this church are said to be those which St. Ambrose closed against the Emp. Theodosius after the cruel massacre of Thessalonica. There is a portrait of the saint on the left side of the principal entrance. The Lombard kings and German emperors formerly caused themselves to be crowned here with the iron crown, which since the time of Frederick Barbarossa has been preserved at Monza (p. 134).

INTERIOR. On the right and left of the side entrance on the right: frescoes by *Gaudenzio Ferrari*, representing the Bearing of the Cross, the three Mariæ, and the Descent from the Cross. 2nd Chapel on the right (Cappella delle Dame): a kneeling statue of St. Marcellina, by *Pacetti*. 5th Chapel on the right: Legend of St. George, frescoes by *Bernardino Lanini*. In the entrance to the sacristy is the Cappella S. Satiro with mosaics of the 5th century. 6th Chapel: Madonna with St. John and Jerome, by *Luini*. Below the pulpit is an early Christian sarcophagus of the 6th cent., said to be that of Stilicho. The canopy over the high altar, which is adorned with reliefs of the 8th cent., recently gilded, is borne by four columns of porphyry. The high altar still retains its original decoration intact, consisting of reliefs on silver and gold ground (in front), enriched with enamel and gems, executed in the Carolingian period by Volfoinus, a German (covered, shown only on payment of 3 fr.). In front of the high altar is the tombstone of Emp. Lewis II. (d. 875). The choir

contains an ancient episcopal throne. By the high altar is an "Ecce Homo, al fresco, by *Luini*, under glass. In the Tribuna "mosaics of the 9th cent., earlier than those of St. Mark's at Venice: Christ in the centre, at the sides the history of St. Ambrose. — At the entrance to the Crypt Christ among the scribes, a fresco by *Borgognone*. The modernised crypt contains the tombs of SS. Ambrose, Protasius, and Gervasius. The brazen serpent on a column in the nave is said to be the one which was raised by Moses in the wilderness.

A little to the S.E. is situated the spacious *Macello Pubblico* or slaughter house (Pl. A, B, 7).

The Via Lanzzone (with the *Palazzo Visconti* on the left) leads hence to the CORSO DI PORTA TICINESE, in which we proceed to the right in the direction of the gate. On the left we soon perceive a large ancient \*COLONNADE (Pl. 57; C, 7) of sixteen Corinthian columns, standing detached from other buildings, the most important relic of the Roman Mediolanum, near which is the entrance to —

\***S. Lorenzo** (Pl. 18), the most ancient church in Milan. Although it is uncertain whether the handsome interior once formed the principal hall of the thermæ, or of a palace of Maximian (4th cent.) to which the above mentioned colonnade belonged, or to a very ancient Christian place of worship, like S. Vitale at Ravenna, and although it was subsequently altered at least three times (the last time by *Martino Bassi*), it is still an object of great interest to architects. It is octagonal in form, and covered with a dome. On the four principal sides are large semicircular apses in two stories, each borne by four columns alternately octagonal and round, and the whole structure is simple and dignified. At the back of the high altar is the Cappella S. Ippolito, containing the tomb of Maria Visconti. To the right of the church is the *Chapel of St. Aquilinus*, containing mosaics of the 6th and 7th cent. (Christ and the apostles), and an ancient Christian sarcophagus supposed to be that of the founder, the Gothic king Ataulph (411-16). The entrance to the chapel is adorned with an antique marble coping.

By the *Porta Ticinese*, farther S., rises the ancient church of **S. Eustorgio** (Pl. 14; C, 8), founded in the 4th cent., re-erected in the Gothic style by *Tosano Lombardo* in 1278, and restored in the bad taste of the 17th cent. by *Richini*. The 'bones of the Magi', to whom the church is dedicated, were formerly deposited here, but were presented to the city of Cologne by Frederick Barbarossa after the conquest of Milan in 1162. At the back of the choir is a chapel in the best Renaissance style by *Michetozzo* (after 1462), containing the tomb of St. Peter the Martyr by *G. Balduccio* of Siena; the frescoes on the high altar, representing scenes from the life of the Magi (1347), and from the Passion, and also the monument of Stefano Visconti, are by the same master.

**S. Maria presso S. Celso** (Pl. 21; D, 8), near the *Porta Lodovica*, possesses a handsome atrium attributed to *Brumante*, and a façade of which the upper part was constructed by *Gateazzo Alessi*. On the right and left of the portal are Adam and Eve by *Stoldo Lorenzi*.

In the INTERIOR is a picture by *Paris Bordone*, St. Jerome adoring the Child (2nd altar on the right); *Gaudenzio Ferrari*, Baptism of Christ (behind the high altar); *Borgognone*, Madonna adoring the Child, surrounded by John the Baptist, St. Rochus, and the donors of the picture (1st chapel on the left); above it, *Sassoferrato*, Madonna. The 2nd chapel on the left contains a sarcophagus with the relics of St. Celsus.

Adjacent to this church is *S. Celso*, a Romanesque edifice, partially removed in 1826.

The CORSO S. CELSO (Pl. D, 7, 8) leads back from this point to the interior of the city. To the right in the *Piazza S. Eufemia* is the church of that name (Pl. 13; D, 7), dating from the 5th cent., but entirely modernised in the 17th, with an Ionic colonnade. Farther towards the N. is situated —

**S. Alessandro** (Pl. 6; D, 6; in the Via Amedei, to the right) erected in 1602, the most sumptuously decorated church in Milan, but destitute of works of art. High altar adorned with precious stones.

We return by the Via Lupetta and the Via di Torino to the Piazza del Duomo. To the right in the Via Carlo Alberto (p. 123) is the small church of **S. Satiro** (Pl. 31; D, 6), founded in 829, and re-erected by *Bramante* and his pupil *Suardi* in the 15th cent.; the octagonal \*Sacristy contains a handsome frieze halfway up the wall, with a gallery above it, and niches by *Bramante* below.

To the S. in the Piazza del Duomo, opposite the cathedral, is the Palazzo Reale and the Archiepiscopal Palace, both already mentioned (p. 123). Adjacent is the PIAZZA FONTANA (Pl. E, 6), with a fountain in red granite. Beyond it, in front of the *Palazzo di Giustizia* (Pl. 67; E, 6) is the statue of *Beccaria* (d. 1794; comp. p. 124) by *Grandi*, erected in 1871.

The Via Brolo leads hence to the S. to the *Piazza S. Stefano*, with the simple Renaissance church of that name (Pl. 34; E, F, 6). The Via dell' Ospedale leads S.W. to the Corso di Porta Romana.

The \***Ospedale Maggiore** (Pl. 46; E, 7), a vast and remarkably fine Gothic brick structure, begun in 1457 by *Antonio Filarete* of Florence, is one of the largest hospitals in existence, and contains no fewer than nine courts. The extensive principal court, surrounded by arcades, is by *Richini* (17th cent.); the court to the right of it is ascribed to *Bramante*. The edifice is entirely covered externally with terracotta, in a style frequently observed in other Milanese buildings, but its façade, with its rich window-mouldings, is superior to any other structure of the kind at Milan.

Farther on, to the S. (entrance in the Corso Porta Romana), is the church of *S. Nazaro* (Pl. 29; E, 7), with pictures by *Bern. Lanini* (\*martyrdom of St. Catharine), and a handsome carved altar.

---

On the N.E. side of the cathedral begins the broad and bustling \***Corso Vittorio Emanuele** (Pl. E, F, 6, 5), which, with its pro-

longation the Corso Porta Venezia, leads to the Giardini Pubblici and the station. This is the principal business street in Milan, containing the best shops. On the left side is the church of —

**S. Carlo Borromeo** (Pl. 12; F, 6), a rotunda in the style of the Pantheon at Rome, 156 ft. in height, consecrated in 1847. It contains two groups in marble by *Pompeo Marchesi*, and modern stained glass by *Jose Bertini* (the finest on the right of the entrance: S. Carlo Borromeo visiting persons sick of the plague).

The adjacent *Galleria de Cristoforis*, now occupied with shops, was erected by Pizzala in 1830-32.

To the right, farther on, at the corner of the Via Monforte, is the small church of *S. Babila* (Pl. 10; F, 5), which is supposed to occupy the site of an ancient temple of the sun. In the Via Monforte is situated the *Palazzo di Prefettura* (Pl. 53; F, G, 5), with a modern façade. — To the S. of this point, in the Via del Conservatorio, is the church of **S. Maria della Passione** (Pl. 24; G, 6), of the 15th cent., with a spacious dome by *Crist. Solari*, surnamed *Il Gobbo* (1530), and paintings by *B. Luini*, *Gaud. Ferrari*, etc. The *Conservatoire of Music* occupies the old monastery buildings.

The Corso Vittorio Emanuele is prolonged to the Porta Venezia by the CORSO DI PORTA VENEZIA (Pl. F, G, 5, 4). On the left, on this side of the canal, is the *Archiepiscopal Seminary* (Pl. 61) with a fine court by *Gius. Meda* (16th cent.), with double colonnades, the lower Doric, the upper Ionic. Then, more to the left, Nos. 59-61, the *Pal. Ciani* (Pl. 54), completed in 1861, with rich ornamentation in terracotta. Opposite, on the right, is the *Pal. Saporiti* (Pl. 56), another modern building, with Ionic columns, reliefs by *Marchesi*, etc.

The \***Giardini Pubblici** (Pl. 44; F, 4), between the Porta Venezia and the Porta Nuova, recently much extended, and containing fine avenues and several sheets of water, are the favourite promenade of the Milanese, especially on Sunday afternoons. The broad chestnut avenue on the N. side, extending between these two gates, and planted on the old ramparts (*Bastione*), is a fashionable drive towards sunset. A broad flight of steps ascends to the older part of the gardens, opened in 1785, in the centre of which is a square building containing a large and handsome saloon used for concerts and balls. The *New Giardino Pubblico* between the Via Palestro, Via Manin, and the above mentioned bastions, opened in 1861, contains a small zoological garden, and is adorned with a statue of the Milanese poet *Carlo Porta* and an *Italia* by *Puttinati*. — In the Piazza Cavour, outside the S.W. entrance, rises a bronze statue of *Cavour* by *Tabacchi* on a lofty pedestal of granite. Clio is represented in front registering his name in her tablets, and at the back is the date 1865. — The *Villa Reale* (Pl. 70; F, 4), a plain modern building in the Via Palestro, containing a few works of art, is the property of the crown-prince of Italy.

In the Via Manin, to the W., is the **Museo Civico** (Pl. 43; F. 4; admission on Tues., Wed., and Sat., 11-3 o'clock,  $\frac{1}{2}$  fr.; on Thurs. gratis), containing natural history collections: on the 1st floor palæontology and ethnography (also a phrenological collection); on the 2nd floor zoology, comprising one of the finest collections of reptiles in Europe, founded by Jan (d. 1866). At the entrance are busts of *Jan* and *Cristoforis*, former directors.

At the N.W. angle of the city lies the spacious **PIAZZA D'ARMI** (Pl. B, C, 4), or drilling-ground, 783 yds. long and 748 yds. wide, with the **Castello**, once the seat of the Visconti and the Sforza, and now a barrack. The corner-towers and part of the walls connecting them on the S.W. side are the sole remains of the original building. The adjoining **Arena** (Pl. 2; C, 3, 4), a kind of circus for races, etc., constructed under Napoleon I., can accommodate 30,000 spectators (fee  $\frac{1}{2}$  fr.).

Opposite the castle, on the N.W. side of the Piazza is the **\*Arco del Sempione**, or *Arco della Pace* (Pl. 1; B, 3, 4), a triumphal arch in the Roman style constructed entirely of white marble from designs by *L. Cagnola*, begun in 1804 by Napoleon as a termination to the Simplon route (p. 25), and completed by the Emp. Francis in 1833, when the dedication and decorations were altered.

For the Latin inscriptions formerly placed on the side next the town in honour of the Emperor Francis, the following have been substituted. On the town side: 'Alle speranze del regno italico auspice Napoleone I. i Milanesi dedicarono l'anno 1807 e francati da servitù felicemente restituirono l'anno 1859'. On the outer side: 'Entrando coll' armi gloriose Napoleone III. e Vittorio Emanuele II. liberatori, Milano esultante cancellò da questi marmi le impronte servili e vi scrisse l'indipendenza d'Italia 1859'.

On the platform is the goddess of Peace in a chariot with six horses, by *Sangiorgio*; at the corners Victories on horseback. *Side towards the Town*: on the right and left of the inscription, the river-gods of the Po and Ticino. On the left under the cornice, the entrance of Emp. Francis into Milan in 1825, above it the battle of Kulm, below it the surrender of Dresden. On the right the foundation of the Lombard and Venetian kingdom, above it the passage of the Rhine, below it the taking of Lyons, all by *Pompeo Marchesi*. Below the great arch the conclusion of the 'Holy Alliance' in two reliefs. On the W. side the battle of Arcis-sur-Aube, E. the victory of Lyons, by *Marchesi*. *Side towards the Country*: river-gods of the Tagliamento and Adige, by *Marchesi*. Under the cornice on the left the Congress of Vienna, Institution of the order of the Iron Crown, Taking of Paris; right, Peace of Paris, Entry of the Allies into Paris, Entry of General Scipperg into Milan 1814.

To the N.W. of the city lies the new **\*Cemetery (Cimiltèro Monumentale)**; Pl. C, 1, 2), designed by *C. Macciachini*, 500 acres in area, enclosed by colonnades, and one of the finest 'campi santi' in Italy. The numerous and handsome monuments, among which those of the *Sonzogno*, *Turati*, *Branrilla*, and *Cicogna* families deserve special mention, form an admirable museum of modern Milanese sculpture. In the last section is situated the '*Tempio di Cremazione*', for the burning of dead bodies, presented to the town in 1876. Fine view of the Alps.



## 21. From Milan to Lecco or Como.

## The Brianza.

RAILWAY FROM MILAN TO COMO, 30 M., in  $1\frac{1}{4}$ - $1\frac{3}{4}$  hr. (fares 5 fr., 3 fr. 85, 2 fr. 55 c.). Through-tickets may be obtained at the railway station of Milan for Como, Tremezzina, Cadenabbia, Bellagio, Menaggio, and Colico. — FROM MILAN TO LECCO, 32 M., railway in 2- $\frac{21}{2}$  hrs. (fares 5 fr. 85, 4 fr. 10, 2 fr. 95 c.). — *From Milan to Monza* a tramway-car also runs hourly, starting from outside the Porta Venezia (Pl. G, 4; fare inside 1 fr., outside 60 c.).

The lines to Como and Lecco follow the same direction as far as Monza, traversing a fertile plain, luxuriantly clothed with vineyards, mulberry-plantations, and fields of maize, and intersected by innumerable canals and cuttings for purposes of irrigation.  $4\frac{1}{2}$  M. *Sesto*.

8 M. **Monza** (*Falcone; Albergo del Castello*, near the station) is a town with 15,600 inhab. Leaving the station and following the Via Italia to the right, we reach the \*CATHEDRAL, the chief object of interest. It was erected in the 14th cent. in the Lombard Gothic style by *Marco di Campione* on the site of a church founded in 595 by the Lombard queen Theodolinda, and contains double aisles and transept, flanked with chapels on both sides.

INTERIOR. In the left transept is the plain sarcophagus of Queen Theodolinda; in the E. transept reliefs of the 13th cent., supposed to represent the coronation of Emp. Otho III., or that of Henry III. — In a casket forming the centre of a richly decorated cross over the altar, to the right of the choir, is preserved the celebrated IRON CROWN, with which 34 Lombard kings were crowned. This venerable relic was last used at the coronation of the Emp. Charles V., of Napoleon in 1805, and of Emp. Ferdinand I. in 1838. It consists of a broad hoop of gold adorned with precious stones, round the interior of which is a thin strip of iron, said to have been made from a nail of the true Cross brought by the empress Helena from Palestine. In 1859 it was carried off by the Austrians, but after the peace of 1866 was restored to its former repository. — The TREASURY contains several objects of historical interest: a hen with seven chickens in gold, representing Lombardy and its seven provinces, executed by order of Queen Theodolinda; the queen's crown, fan, and comb; two silver loaves, presented by Napoleon I. after his coronation; the cross which was placed on the breast of the Lombard kings at the moment of their coronation; goblet of Berengarius; diptychs (ivory tablets with reliefs), etc.; then, in a cabinet outside the treasury, the mummy of one of the Visconti, who died in 1413. The treasury is shown for a fee of 1 fr. for 1-2 pers.; it also contains a model of the iron crown.

The *Broletto*, or town-hall, of the 13th cent., with round arched windows and tower, is believed to be part of a palace of the Emp. Frederick I. and the Lombard kings. The royal *Summer Palace* near Monza is a large building with an extensive and beautiful park, traversed by the Lambro. The church of the *Madonna di Tirano* contains frescoes by Luini, Gaudenzio Ferrari, and Cesare da Sesto.

The lines to Como and Lecco divide at Monza. The latter line skirts the S.E. slopes of the beautiful range of hills of the *Brianza* (p. 136), studded with numerous villas of the wealthy Milanese. —  $12\frac{1}{2}$  M. *Arcore*;  $15\frac{1}{2}$  M. *Usmate*. From (19 M.) *Cernusco-Merate* a pleasant excursion may be taken to the lofty *Montevecchia*, situated

towards the N.W. ( $1\frac{1}{2}$  hr.; the church of Monteverchia commands an excellent view of the Lombard plain, Milan, Cremona, Novara, and part of the Brianza, etc.; good wine, but a poor inn; pleasant return route by Missaglia, with a guide,  $1\frac{1}{4}$  hr.; thence by carriage to Merate; fine views). The village of *Merate* (Albergo del Sole), situated 1 M. from the station, was formerly fortified; pretty villas. — 21 M. *Olgiate-Molgora*; then a tunnel, beyond which a pleasing view of the valley of the *Adda* is obtained. The train descends, crosses the stream by an iron bridge, joins the Lecco and Bergamo line at ( $27\frac{1}{2}$  M.) station *Calolzio*, and reaches (32 M.) *Lecco* in 10 min., see p. 144.

The railway from **MONZA** to **COMO** runs to the N.W., affording pleasant views, to the right, of the fertile Brianza (p. 136), with its numerous country-residences. The train passes through several tunnels.  $12\frac{1}{2}$  M. *Desio*;  $14\frac{1}{2}$  M. *Seregno*, a town with 5000 inhab., the starting point for an excursion to the Brianza, see p. 136.

Farther on, the long, indented *Monte Resegone* rises on the right. — 18 M. *Camnago*,  $24\frac{1}{2}$  M. *Cucciago*. Above (28 M.) *Camerlata* rises the lofty old tower of the *Castello Baradello*, which was occasionally occupied by Frederick Barbarossa. — 30 M. *Como*; omnibus from the station to the quay 30 c. included in through tickets. (Continuation of the railway to Lugano, see p. 146.)

**Como.** — \*HÔTEL VOLTA, R. 3, B. 2, L. and A.  $1\frac{1}{2}$  fr.; **ITALIA**, R. from 2 fr., both at the harbour, with cafés and restaurant; another Café opposite the cathedral in the market-place. — *Café Cavour*, near the quay; \**Trattoria di Frasconi*, at the end of the street leading straight from the harbour; *Baths* in the lake by the *Giardino Pubblico*, to the left, outside the pier.

*Como* (705 ft.), the capital of a province, with 20,000 inhab. and considerable silk factories, the birthplace of the elder and younger Pliny and of the electrician and philosopher Volta (d. 1826; whose *Statue* by P. Marchesi is on the W. side of the town near the quay), lies at the S. end of the S.W. arm of the Lake of Como, and is enclosed by an amphitheatre of mountains.

The \***CATHEDRAL**, begun in the Lombard Gothic style in 1396, and altered in the Renaissance style by *Tommaso Rodari* (choir, transept, outside of nave) in 1513-21, is built entirely of marble, and is one of the best in N. Italy. Over the beautiful N. portal are reliefs (adoration of the Magi) and statuettes (Mary with S. Abbondio, St. Protus, etc.). At the sides of the principal entrance are statues of the elder and the younger Pliny, erected in 1498.

**INTERIOR.** The gaudy vaulting, restored in 1838 at a cost of 600,000 fr., destroys the effect of the fine proportions, which resemble those of the Certosa near Pavia (p. 161). The windows of the portal contain good modern stained glass, representing the history of S. Abbondio; there are others to the right of the entrance and in the choir. — To the right of the entrance is the monument of Cardinal *Tolomeo Gallo*, a benefactor of the town, erected in 1861. Farther on, to the right, 3rd

Altar, di S. Abbondio, with handsome wood-carving, and scenes from the life of the saint; adjoining the Adoration of the Magi, by *Bern. Luini*, and the Flight into Egypt, by *Guid. Ferrari*. Over the altar of St. Jerome a Madonna by *B. Luini*. In the N. TRANSEPT the Altare del Crocifisso of 1498, with a fine statue of St. Sebastian. In the CHOR the Apostles, by *Pompeo Marchesi*. The SACRISTY contains pictures by *Guido Reni*, *Paolo Veronese*, etc. In the LEFT AISLE, the altar of the Mater Dolorosa with an Entombment by *Tommaso Rodari* (1498). At the Altare di S. Giuseppe: *G. Ferrari*, Nuptials of the Virgin, in style resembling Raphael; *B. Luini*, Nativity; St. Joseph, a statue by *P. Marchesi*, and a basrelief below, the last work of this master; at the entrance the busts of Pope Innocent XI. (Odescalchi) and Carlo Ravelli, bishop of Como.

Adjoining the church is the *Town Hall (Broletto)*, constructed of alternate courses of different-coloured stones, and completed in 1215. Behind the cathedral is the handsome *Theatre*, erected in 1813. The old church of *S. Fedele*, of the 10th cent., is in a remote part of the town. The *Porta del Torre*, a massive five-storied structure, is also worthy of note.

On the promenade outside the town is the church *Del Crocifisso*, richly decorated with marble and gold, of the 17th cent.; beyond it, to the left, on the slope of the mountain about 1 M. from the town, is the fine old *Basilica S. Abbondio* of the 11th cent.

WALK on the E. bank of the lake. Two roads lead from Como along the slopes on the E. bank. The lower passes several hamlets and villas. The upper (after 40 min.) affords a view of magnificent snow-mountains towards the W., and leads by *Capo-Vico*, *Sopra-Villa*, and *Cazzanore* (all in the parish of *Blevio*), leaving the *Villa Pliniana* (p. 139) far below, to (3 M.) *Riva di Palanzo* (osteria on the lake), whence the traveller may cross to the steamboat-station *Carate* on the opposite bank. Or the walk may be shortened by descending to (2½ hrs.) *Torno* (steamboat-station).

A carriage-road from Como to Torno is in course of construction.

### The Brianza.

*Brianza* is the name of the undulating, grassy, partially wooded, and extremely fertile tract, 12 M. in length, 6 M. in breadth, extending between the *Sevso* and the *Adda*, and stretching to the N. to the triangular peninsula which divides the Como and Lecco lakes. The soil is very fertile, and the whole district studded with villas peeping out from vines, orchards, and mulberry plantations. In the centre are several small lakes (*Lago d'Annone*, *Pusiano*, *Alserio*, *Segrino*, and *Montorfano*). Two main roads traverse the Brianza; from S. to N. the road from Seregno to Bellagio, from W. to E. another from Como to Lecco, both of which meet at Incino, not far from Erba.

FROM SEREGNO (p. 135) to BELLAGIO, about 25 M. It is advisable to take a carriage as far as Canzo (12 M.; an omnibus runs from Seregno to Canzo every evening; one-horse carriage 5-7 fr.), to pass the night there, and to walk to Bellagio next morning. The road leads by *Paino*, and *Villa Romanò*, to the pretty village of *Inverigo*; on an eminence rises the *Rotonda*, one of the prettiest villas in the Brianza, with a park and admirably kept garden, and commanding an extensive view. The *Villa Cricelli* is famous for its cypresses. Farther on, the villages of *Tregolo* with a new church, *Tabiago*, with the ruins of a castle, and *Monguzzo*, with the *Villa Mondolfo*, once a fortified castle belonging to the Medici.

Where this road crosses that from Lecco to Como at *Incino*, near *Erba* (p. 137), are situated the lakes mentioned above, W. the *Lago d'Alserio*, E. the *Lago di Pusiano*. The road now enters a more mountainous district, and the scenery becomes more attractive. *Castino*, possessing considerable silk-factories (*filatoje*), rises picturesquely on the slope of the hill. The road follows the course of the small river *Lambro*.

**Canzo** (*Croce di Malta*, the first house on the left; a pleasant liqueur, called *Vespetro*, is manufactured at Canzo) is almost contiguous to *Asso*, 1 $\frac{1}{4}$  M. beyond, numbering together 3000 inhah. At the entrance of *Asso* is a large silk-manufactory (*Casa Versa*).

The road now gradually ascends for a considerable distance in the picturesque valley of the *Lambro*, the *VALL' ASSINA*, the slopes of which are well wooded; it passes through several villages, (2 M.) *Lasnigo*, (2 M.) *Barni*, and *Magreglio*, where the ascent becomes more rapid; first view of both arms of the Lake of Como from the eminence near the (1 $\frac{1}{4}$  M.) *Chapel*.

Delightful survey of the entire E. arm to *Lecco* and far beyond, from the back of the first church of (1 $\frac{1}{4}$  M.) *Civenna*, with its graceful tower. The road now runs for 2 $\frac{1}{4}$  M. along the shady brow of the mountain, which extends into the lake at *Bellagio*; beyond the chapel the following striking views are obtained: the W. arm of the lake (of *Como*), the *Tremezzina* with the *Villa Carlotta* and *Cadenabbia*, the E. arm (Lake of *Lecco*), a large portion of the road on the E. bank, the entire lake from the promontory of *Bellagio* to *Domaso* (p. 134), and the rising ground with the *Serbelloni* park.

The road winds downwards for about 3 M., passing the *Villa Giulia* (p. 142) on the right, and,  $\frac{1}{2}$  M. from *Bellagio*, the churchyard of that place, containing the monument of the painter *Carlo Bellosio*, several of whose pictures are to be seen at *Bellagio*. From *Civenna* to the hotels at *Bellagio* on the lake (p. 140) 2 hrs. walk.

A longer route, which will reward the pedestrian, is by the **Monte S. Primo** (5586 ft.). Ascent from *Canzo* with a guide in 4.5 hrs., descent to *Bellagio* 3 hrs. Magnificent panorama from the summit, comprising the *Brianza* as far as *Milan*, and the *Lake of Como* to the N. as far as the *Alps* from *Monte Rosa* to the *Splügen*.

FROM *COMO* TO *ERBA* AND *LECCO*, diligence daily in 3 hrs. (steamer see p. 144). The road quits *Como* by the *Porta Milanese* and ascends the hills to the E. The view of the lake is concealed by the beautifully wooded *Monte S. Maurizio*; to the S. a survey is obtained of the district towards *Milan* and the *Brianza*. The church of *Cannago*, a village to the N. of the road, contains the tomb of *Volta* (p. 135). Farther on, to the S. of the road, is the sharp ridge of *Montorfano* near a small lake. Near *Cassano* is a curious leaning campanile. Beyond *Albesio* a view is disclosed of the plain of *Erba* (*Pian d'Erba*) and the lakes of *Alserio*, *Pusiano*, and *Annone*, above which the *Corni di Canzo* (4512 ft.) and the *Resegone di Lecco* (6161 ft.) rise on the E.

Near (10 $\frac{1}{2}$  M.) *Erba* (1017 ft.; *Inn*), a small town in the luxuriantly fertile '*Pian d'Erba*', are several handsome villas; the *Villa Amalia* on the W. side commands a charming view of the *Brianza*. Near *Incino*, with its lofty Lombard campanile, once stood the *Forum Licini* of the Romans, mentioned by *Pliny* together with *Como* and *Bergamo*.

Before the road crosses the *Lambro*, which is here conducted by an artificial channel to the *Lago di Pusiano*, the road from *Resegno* to *Bellagio* diverges to the right. *Penzano* on the N. bank of the *Lago di Pusiano* is next reached, and then *Pusiano* itself. To the N. a beautiful glimpse of the *Vall' Assina* (see below) and the *Corni di Canzo*, and, to the S., of the *Brianza*. Near *Civate* is the double *Lago d'Annone* (E. rises the *Resegone di Lecco*), connected by the *Ritorto*, which the road follows, with the *Lake of Lecco*. The latter is reached at *Malgrate*, on the W. bank, a place with numerous silk-factories. Opposite to it lies *Lecco* (see p. 144).

## 22. Lake of Como.

**Plan of Excursion.** The most beautiful point on the *Lake of Como* is *Bellagio* (p. 140), which is admirably situated for a stay of several days and for short excursions. — The *Lakes of Como* and *Lugano* (p. 147) and the *Lago Maggiore* (p. 151) may be visited from *Milan* most expeditiously as follows: train in 2 hrs. to *Como* (Cathedral); proceed by steamboat in









20 lbs. weight are occasionally captured. The 'Agoni' are small, but palatable.

The prospect from the quay at Como is limited, but as soon as the steamer has passed the first promontory on the E. the beauty of the lake is disclosed to view.

### Lake of Como.

#### W. BANK.

*Borgo Vico*, the N.W. suburb of Como, with the Villas *Saporiti*, *Salazar*, and *Mondolfo*. At the N. end of the Borgo rises the large *Villa Raimondi*.

*Villa Tavernola*, beyond the mouth of the *Breggia*. *Villa Cima*, in a beautiful park.

*Cernobbio* (Iun) is a considerable village, with the villas *Belinzaghi*, *Baroggi*, etc.

The *Villa d'Este* was opened in 1876 as a \*Hotel on a large scale, connected with which is the former Hôtel de la Reine d'Angleterre (pension 9-10 fr.). A pleasant park extends up the hill. — High above lies the church of *Rovenna*. — *Villa Pizzo*.

*Villa Passalacqua*, with its numerous windows, resembles a manufactory.

Near *Moltrasio* is a picturesque waterfall.

*Urio*; then *Carate*, with the *Monte Bisbino* (4390 ft.) in the background. — *Villa Colobiano*, a green and red building. The lofty pyramid was erected to the memory of Dr. Frank, a professor of Pavia (d. 1851), with money left by him for the purpose. — *Laglio*, with *Villa Antongina*, formerly *Gaggi*.

*Villa Galbiati*, completed in 1855, gaily painted; then *Torrigia*.

Next, *Brienno*, embosomed in laurels.

#### E. BANK.

*Borgo S. Agostino*, the N.E. suburb of Como. On the hill above is the village of *Brunato*, commanding a fine view.

Beyond the promontory (with the *Villa Cornaggia*) we obtain a view of **Blevio**, with its numerous villas, including those of *Mylius*, *Ricordi*, and *Taglioni*, with a Swiss cottage, formerly the property of the famous danseuse, now belonging to her son-in-law Prince Trubetzkoi. *Villa Pasta* was the residence of the celebrated singer (d. 1865).

*Villa Taverna*, formerly *Tanzi*.

**Torno** is surrounded by villas.

*Villa Pliniana* at the end of the bay, at the entrance of a narrow gorge, a gloomy square edifice, erected in 1570 by Count Anguissola, one of the four conspirators who assassinated Duke Farnese at Piacenza, is now the property of the princess Belgiojoso. It derives its name of *Pliniana* from a neighbouring spring which daily changes its level, a peculiarity mentioned by Pliny. Extracts from his works (Epist. iv. 30; Hist. Nat.



## W. BANK.

*Argegno*, at the mouth of the *Intelvi Valley*.

*Sala*, with the small island of *S. Giovanni*, or *Comacina*, frequently mentioned in the annals of mediæval warfare, once fortified, and now occupied by a small church. *Monte Legnone*, and *Monte Legnoncino* (p. 144) are distinctly visible towards the N.E.

*Campo* lies in a bay formed by the promontory of *Lavedo*, which here projects far into the lake. On its extremity glitters the *Villa Balbianello*, with its colonnade, the property of Count Arcomati.

*Tremezzo* (\**Albergo Bazzoni*) is nearly contiguous to *Cadenabbia*; between the two places stands the *Villa Carlotta*. This district, called the *Tremezzina*, is not inaptly called the garden of Lombardy.

**Cadenabbia** (\**Bellevue*, with restaurant; \**Belle-Ile*; *Ville de Milan*, formerly *Majolica*; *Caffè Lazzerari*), halfway between *Como* and *Colico*. In the vicinity (S.W.), in a garden sloping down to the lake, stands the celebrated \**Villa Carlotta*, or *Sommariwa*, from the Count of that name to whom it formerly belonged. In 1843 it came into the possession of Princess Albert of Prussia, from whose daughter *Charlotte*

## E. BANK.

ii. 206) are inscribed on the walls of the court.

*Quarsano* and *Careno*.

*Nesso*, at the foot of the *Piano del Tivano* (3742 ft.), *Nesso Sopra*, and *Nesso Sotto*; near the latter in a rocky gorge is a waterfall of considerable height, frequently dry in summer.

Near *Lezzeno* is one of the deepest parts of the lake.

*Villa Besenna*.

*S. Giovanni*, with the *Villa Trotti*.

*Villa Poldi*, bearing the family name of the *Gonzagas*, contains the mausoleum of the last of the race, in the form of a round Romanesque temple. Fine view.

*Villa Melsi*, see p. 141.

**Bellagio**. — \*GRANDE BRÉTAGNE, and GRAND HÔTEL BELLAGIO, formerly *Villa Frizzoni*, both well fitted up, and the property of companies: †GENAZZINI; these three beautifully situated on the lake; R. 3 fr. and upwards, B. 13/4, D. 5, omnibus 1 fr.; pension according to agreement, even for a few days. 10-12 fr., or at Genazzini's somewhat less; †GRAND HÔTEL & PENSION VILLA SERBELLONI, on the hill in the beautiful park mentioned at p. 142, commanding a fine view, a dépendance of the Grande Bretagne, with the same charges, but inferior in comfort. — Of less pretension: HÔTEL ET PENSION

## W. BANK.

(d. 1855) it derives its present appellation. The widower of the latter, Duke George of Saxe-Meiningen, is the present proprietor. Visitors ring at the entrance to the garden and ascend the broad flight of steps, where they are received by the intendant (1 fr., but more for a party).

INTERIOR. The MARBLE HALL contains a frieze decorated with celebrated Reliefs by *Thorvaldsen*, representing the Triumph of Alexander (for which a sum of nearly 375,000 fr. was once paid by Count Sommariva); also several statues by *Canova* (Cupid and Psyche, Magdalene, Palamedes, Venus); Paris by *Fontana*; bust of Count Sommariva; Mars and Venus, by *Acquisti*; Cupid giving water to pigeons, by *Bienaimé*, etc. The BILLIARD ROOM contains casts, and a small frieze in marble on the chimney-piece representing a Bacchanalian procession, said to be an early work of *Thorvaldsen*. — In the GARDEN SALOON several modern pictures (*Hagar*, *Romeo and Juliet*; *Sordon*, *Athalie*), and a marble relief of Napoleon when consul, by *Lazzarini*.

The GARDEN, which stretches to the S. to Tremezzo, and to the N. towards the Hôtel de Bellevue, contains the most luxuriant vegetation; on the S. side of the Villa is a splendid magnolia; pleasant view towards Bellagio (attendant 1/2 fr.).

Behind the 'Milan' hotel rises *Il Sasso S. Martino*, a rock on which stands the *Madonna di S. Martino*, a small church, commanding a beautiful view; ascent 1 1/2 hr., path destroyed by torrents at places.

The *Monte Cotaiga* or *Crocione*, a more lofty mountain to the W., commands a striking view of the Monte Rosa chain, the Bernese Alps and Mont Blanc, the lakes and the plain of Lombardy (a fatiguing ascent of 6-7 hrs.; guide 5 fr.; in order to avoid the heat the traveller should start at 2 or 3 a.m.).

## E. BANK.

SUISSE; HÔTEL FLORENCE, well spoken of; both on the lake. ALBERGO DEL VAPORE, moderate. — *Rowing Boats*, see p. 138.

*Bellagio* (708 ft.), at the W. base of the promontory which separates the two arms of the lake, is perhaps the most delightful point among the lakes of Upper Italy. About 1/2 M. to the S. of the village is the \**Villa Melzi*, erected by *Albertoli* in 1810-15, for Count *Melzi d'Erile*, who was vice-president of the Italian Republic in 1802, and was made Duke of Lodi by Napoleon in 1807. It now belongs to his grandson the Duca di Melzi (attendant 1 fr., more for a party; gardener 1/2 fr.).

INTERIOR. In the vestibule, copies of ancient busts in marble by *Canova*; bust of the present proprietor by *Vela*; statue of the son of the duca, by *Pessina*; David, by *Fraccaroli*; Innocence, by *Paudiani*, etc. The walls of the following rooms are embellished with appropriate frescoes. In the 2nd Room a bust of Michael Angelo by *Canova*. 3rd R.: Bust of Michael Angelo by himself (?); *Madonna* by *Bern. Luini*. 4th R.: *Comolli*. Eugene Beauharnais, viceroy of Italy; *Appiani*, Napoleon I. as president of the Italian Republic. 5th R.: Ceiling frescoes by *Bossi*, representing Parnassus; statuettes by *Marchesi*; chimney-piece by *Thorvaldsen* with medallion-portraits of celebrated Italians. 5th R. (Flower-Room): *Canova*, Bacchante.

The GARDEN (attendant 1/2 fr.) exhibits all the luxuriance and fragrance of southern vegetation (magnificent magnolias, camellias, cedars, Chinese pines, gigantic aloes, etc.). The CHAPEL contains monuments in marble to the two former proprietors, and to the mother of the present duke, by *Nessi*. In another part of the garden, Dante and Beatrice, by *Comolli*; colossal busts of Madame Lætitia, mother of Napoleon I., and the empress Josephine, by *Canova*.

## W. BANK.

Here, at the *Punta di Bellagio*, the two arms of the lake, the *Lago di Como* and the *Lago di Lecco* (p. 144), unite.

**Menaggio** (\**Grand Hôtel Vittoria*), beautifully situated, R. 3 fr., pleasant Italian hotel, with a special steamboat station; *Corona* possesses an extensive silk manufactory, to which visitors are admitted. On the lake, S. of the village, is the handsome *Villa Mylius*. A road leads hence to *Porlezza* on the Lake of Lugano (9 M.; omnibus daily, 11 a.m., see p. 150).

On an eminence ( $\frac{1}{2}$  hr.), near the church of *Loveno* (\**Inn*), stands the **Villa Vigoni**, formerly *Mylius*, commanding a magnificent \**View* of *Bellagio*, *Menaggio*, and of the three arms of the lake.

The villa contains some admirable works in marble by modern Italian sculptors, reliefs by *Thorvaldsen* (Nc-

## E. BANK.

Higher up stands the \***Villa Serbelloni** (now *Hôtel and Pension*), the park of which commands an exquisite *View*, especially of the Lake of Lecco, probably the finest on the lake (admission  $\frac{1}{2}$  fr.). Charming glimpses of *Varenna*, *Villa Balbianello*, *Carlotta*, etc. Beautiful flowers and plants in the garden of the hotel, and a grove of palm trees. — The belvedere of the *Villa Belmonte*, the property of an Englishman, commands another fine view (admission  $\frac{1}{2}$  fr.). — A little to the S., in the direction of the Lake of Lecco, is the *Villa Giulia*, the property of Count Blome (visitors not admitted). — Excursion to the *Monte S. Primo*, an ascent of 4 hrs., see p. 137.

**Varenna** (\**Albergo Reale*) is charmingly situated on a promontory, surrounded by gardens (*Isimbardi*, *Lelia*, *Venini*), at the mouth of the *Val d'Esino*, commanded by the lofty ruins of the *Torre di Vezio*, with a small village and a beautiful view. In the vicinity, especially towards the N., some remarkable galleries have been hewn in the rock for the passage of the *Stelvio* road. Most of the marble quarried in the neighbourhood is cut and polished in the town.

About  $\frac{3}{4}$  M. to the S. of *Varenna* the *Fiume Latte* ('milk brook', from its colour) is precipitated in several leaps from a height of 1000 ft., forming an imposing cascade in spring, but

## W. BANK.

mesia) and *Marchesi*; in the garden-saloon a \*group by *Argenti*, the proprietress with her children.

The steamer next passes a wild, yellowish-brown cliff, *Il Sasso Rancio* ('the orange-rock'), which is traversed by a dangerous footpath. This route was undertaken in 1799 by the Russians under General Bellegarde, on which occasion many lives were lost.

*S. Abbondio* is the next village.

*Rexzonico* with *Villa Litta*, and the picturesque ruins of a fortress of the 13th cent.

*Cremia* with the handsome church of *S. Michele* (altar-piece \**St. Michael*, by Paolo Veronese); then *Pianello*.

On rocks rising precipitously above *Musso* are situated the ruins of three castles, *Rocca di Musso*, the residence of *Giov. Giac. de' Medici* in 1525-31, 'the castellan of *Musso*', who from this castle ruled over the entire Lake of Como. Then *Dongo*, with a monastery. Above it, on the height to the right, lies *Garzeno*, whence a somewhat neglected path crosses the *Passo di S. Jorio* to (9 hrs.) *Bellinzona*.

*Gravedona* (*Albergo del Sasso*), the most populous village on the lake (1700 inhab.), is picturesquely situated at the mouth of a gorge. The handsome *Palazzo*

## E. BANK.

generally dried up at other seasons.

*Gittana* is the station for the hydropathic establishment of *Regoledo*, situated 500 ft. above the lake.

**Bellāno** (*Roma*) lies at the base of *Monte Grigna* (7254 ft.), at the mouth of the industrial *Val Sussina*, which is traversed by a road to *Lecco* (28 M.) via *Introbbio*. The *Pioverna* forms a waterfall (197 ft.) before reaching the lake (*Orrido di Bellano*; 50 c.). A monument to *Tom. Grossi*, the poet, who was born at Bellano in 1790 (d. 1853), by *Tandardini*, was unveiled here in 1876.

*Dervio*, at the mouth of the *Varrone*, is situated at the base of the abrupt *Monte Legnone* (8566 ft.) and its spur *Monte Legnoncino* (4951 ft.).

*Corenno*, *Dorio*, and *Ogliasca* are the following villages.

## W. BANK.

*del Pero* with four towers, at the upper end, was built by the Milanese Cardinal Gallio. Adjoining the venerable church of *S. Vincenzo* rises the *Baptisterium*, an interesting building of the 12th cent., containing two Christian inscriptions of the 5th cent.

*Domāso*, charmingly situated, possesses several handsome villas, particularly the *Villa Calderara* and *Villa Velasquez*.

## E. BANK.

**Colico** (*Angelo; Isola Bella*; both in the Italian style; \**Restaurant* on the lake adjoining the former), comp. pp. 37, 44. The *Monte Legnone*, mentioned above, may be ascended hence without difficulty in 7-9 hrs.

FROM COLICO TO CHIAVENNA Swiss diligence (also an omnibus, 2l 2 fr.) twice daily in 3 hrs.; thence daily (twice in summer) over the Splügen to COIRE (R. 5) in 13½ hrs. — FROM COLICO TO SONDRIO in the Valtellina diligence once daily in 5 hrs. (comp. p. 44).

## Lake of Lecco.

FROM COMO TO LECCO by Bellagio steamboat twice daily; FROM COLICO TO LECCO, twice daily, see p. 138.

The S.E. arm of the Lake of Como is worthy of a visit, although inferior in attraction to the other parts. Lecco is charmingly situated. The precipitous and formerly almost inaccessible E. bank of the lake is traversed by a road (continuation of the Stelvio Road, p. 39) constructed in 1832 and carried along the rocks at places with the aid of embankments, tunnels, and galleries. Three of the latter near *Olcio* are together 1000 yds. in length. It affords admirable views of the lake.

The steamboat rounds the *Punta di Bellagio*; on the height above is situated the garden of the *Villa Serbelloni*, and adjoining it are the *Villa Giulia* (p. 142) and the village of *Visgnola*. Then *Limonta*, and opposite to it (left) *Lierna* and *Sornico*, (right) *Vassena Onno*, (left) *Olcio*, and *Mandello* on a flat promontory. On the opposite bank (right) lies the small town of *Parè*, separated from *Malgrate* by the promontory of *S. Dionigio*. *Malgrate* itself lies at the entrance of the *Val Madrera*, through which a road to Como leads by *Erba* (p. 137). The lake gradually contracts into the river *Adda*, by which it is drained, and is crossed by the *Ponte Grande*, a stone bridge of ten arches, constructed in 1335 by *Azzone Visconti*, and furnished with fortified towers at the extremities.

**Lecco** (\**Albergo d'Italia*; \**Croce di Malta*, both in the Italian style; *Corona*), an industrial town with 5200 inhab., situated at the S. end of the E. arm of the Lake of Como, is admirably described in Manzoni's 'I Promessi Sposi'. Pleasant walks to the hill of *Castello* and the pilgrimage-church on the *Monte Baro*.

A little below Lecco the *Adda* again expands into the *Lago di Garlate*, and further down, into the small *Lago di Olgirate*. A navigable canal connects *Trezzo* with Milan. — Railway from LECCO TO MILAN, see p. 134.

FROM LECCO TO BERGAMO. 20½ M. in 1¼ hr. (fares 3 fr. 75, 2 fr. 65, 1 fr. 90 c.). — 4½ M. *Calotzio*, see p. 135; 9½ M. *Cisano*; 14 M. *Mapello*; 16 M. *Ponte S. Pietro*, with a pleasing church and old castle; 20½ M. *Bergamo*. see p. 167.

## 23. From the Lake of Como to the Lago Maggiore.

### Varese. Lugano and the Lake of Lugano.

*Comp. Maps, pp. 138, 150.*

#### I. FROM COMO TO LAVENO BY VARESE.

31 M. DILIGENCE (not recommended) between Como and Varese (18½ M., in about 4 hrs.) twice, between Varese and Laveno (12½ M., in 2½ hrs.) once daily. The road does not quit the Italian territory.

RAILWAY from *Milan to Varese*, 37½ M., in 2¼ hrs. (fares 6 fr. 80, 4 fr. 80, 3 fr. 45 c.). As far as Gallarate, see p. 157; the following stations are Albizzate and Gazzada..

*Como*, see p. 135. The road ascends through the long S. suburb of *S. Bartolommeo*, skirts the base of an eminence surmounted by the ruins of the *Castello Baradello*, and leads to *Camerlata* (p. 135). It then turns E. to *Rebbio*, *Lucino*, and *Lurate Abbate*, traversing a luxuriantly fertile district with numerous villas of the aristocracy of Milan. At *Olgiate* the road attains its culminating point (900 ft. above the Lake of Como), whence a view of Monte Rosa, the Simplon chain, and other Alps is obtained. The road next passes the villages of *Solbiate* and *Binago*, descends rapidly by *Malnate*, and crosses the *Lanza*, near its influx into the *Olona*, and farther on, the *Olona* itself.

**Varese.** — **Hotels.** \*GRAND HÔTEL VARESE (*Excelsior*), a large new establishment, formerly the *Villa Recalcati*, in an open situation outside the town, with fine views, omnibus at the station. — In the town. EUROPA; ANGELO; STELLA; LEON D'ORO.

**Cafés.** *Siberia, Pini.*

**Diligences** to Como and Laveno, see above; to Mendrisio (p. 146) the *Impresa Varesina* (an establishment where carriages may also be hired); to Porto (in connection with the steamboats to Lugano and Ponte Tresa); to Milan by Tradate and Saronno (starting from the Angelo), all once daily.

**Railway** to Milan, see above.

*Varese* (1306 ft. above the sea-level) is a thriving place with 12,000 inhab. and silk, paper, furniture, and other manufactories. In summer the pleasant environs attract a number of wealthy Milanese families, who possess villas here and in the neighbourhood. The principal church of *S. Vittore*, which was rebuilt about 1600, with a tower 246 ft. in height, contains a St. George by Crespi, and a Magdalene by Morazzone. Among the villas may be mentioned: *Palazzo Veratti*, known as *La Corte*, on the Laveno road; *Villa Ducale Litta*, on the road to Biume Superiore; *Villa Ponti*, to the N.E., on the road to Biume Inferiore; then, near the latter village, *Villa Litta Modignani*, which still bears traces of a skirmish fought here on 26th May, 1859; *Villa Taccioli*, *Poggi*, and others.

**WALKS.** To the *Colle Campiglio*, 1½ M. to the S., on the road to Masnago and Laveno, commanding a fine view; to *S. Albino*, 1¾ M. to the S. of Varese, with a view of the lake; to the *Lago di Varese* (Osteria della Schiranna), 2½ M.; then, skirting the lake, to *Gropello*, *Otrona*, *Voltorre* (where there is an old monastery of the Canonici Lateranensi containing interesting Romanesque cloisters), and *Gavirate*, 7½ M. (see p. 146).

The most interesting excursion, however, is by *S. Ambrogio* and *Fogliardi* to the \**Madonna del Monte*, a celebrated resort of pilgrims, 8½ M.

to the N.W. (carriage-road to Fogliardi, then a bridle-path). Fourteen chapels or stations of various forms, adorned with frescoes and groups in stucco, have been erected along the broad path, by which the monastery and church on the mountain (2841 ft.) are attained. The view hence is not less celebrated than the peculiar sanctity of the spot. The small lakes of Comabbio, Biandrone, and Monate, that of Varese, two arms of the Lago Maggiore, part of the Lake of Como, and the expansive and fruitful plain as far as Milan are visible. — A far more comprehensive view, including the glacier-world also, is obtained (best by morning-light) from the *Tre Croci* (3966 ft.), 1 hr. N.W. of the Madonna. Several taverns adjoin the monastery. Donkeys and guides (unnecessary) are to be found at the foot of the mountain. Comp. map, p. 150.

About 6½ M. to the S.E. of Varese, not far from the road to *Bizzozero* and *Tradate* (Saronno and Milan; diligence, see above), lies *Castiglione d'Olona*, with 1300 inhab. (no tolerable inn). The Collegiate church and the adjacent Baptistery contain frescoes by *Masolino* (1428); those in the former represent scenes from the lives of Mary and SS. Stephen and Laurence; those in the latter, from the life of John the Baptist. These frescoes are interesting in the history of art, as several frescoes in the Cappella Brancacci in the Chiesa del Carmine at Florence (p. 374) have been ascribed to Masolino and his pupil Masaccio.

The road to Laveno leads by *Masnago* and *Casciago*, and ascends to *Lunate*, whence a beautiful view S.W. is obtained of the *Lake of Varese* and the small adjacent *Lake of Biandrone*, and also of the farther distant lakes of *Monate* and *Comabbio*. The next villages are *Barrasso* and *Comerio*, the latter with a number of pleasant villas, whence the road, passing near the N.W. extremity of the Lago di Varese, gradually descends to *Gavirate*. In the vicinity of the latter are quarries of the 'marmo majolica', a kind of marble used for decorative purposes. For a short distance the road commands a view of Monte Rosa. *Cocquio* and *Gemonio* are situated to the right of the road. Farther on, the *Boesio*, which flows through the *Val Cuvio*, is crossed, and, beyond *Cittiglio*, its right bank skirted. The road then leads past the S. base of the *Sasso del Ferro* to —

*Laveno* (p. 153), a steamboat station. — Small boat to the Borromeo Islands and *Pallanza* with 3 rowers 10-12 fr.; to *Isola Bella* 1½ hr., thence to *Isola Madre* in 20 min., to *Pallanza* in 20 min. more.

## 2. FROM COMO TO LUINO BY LUGANO.

From *Como* to *LUGANO*, 20½ M., railway in 1¼ hr. (fares 3 fr. 30, 2 fr. 35, 1 fr. 65 c.). — From *Lugano* to *LUINO*, about 15 M., Swiss diligence once daily in 2¾ hrs. (fare 3 fr. 15, coupé 3 fr. 70 c.); or steamboat to *Ponte-Tresa* (in 1½ hr., p. 148), and omnibus thence to *Luino*. Carriage and pair from *Lugano* to *Luino* 20, with one horse 10-12 fr.; in the reverse direction a return carriage (from *Luino*) may often be hired at a cheaper rate. The Italian custom-houses are at *Chiasso* and *Fornasette* (p. 150).

The traveller should note that *Italian Paper* is not taken on Swiss territory.

*Como*, see p. 135. The railway, which was opened in September 1876, runs behind the *Borgo Vico* (p. 139), and through a tunnel under the *Monte Olimpino* (comp. Map, p. 138). 4½ M. *Chiasso* (*Angelo* or *Posta*) is the first Swiss village. 6½ M. *Balerna*.

9½ M. *Mendrisio* (1191 ft.; \**Hôtel Mendrisio*, R. 2½ fr.), a

small town with 2400 inhab., in a luxuriantly fertile district, with large wine-cellar and a handsome hospital.

The **\*Monte Generoso** (5561 ft.; *Monte Gionnero*, or *Monte Calvaggione*), the Rigi of Italian Switzerland, is frequently ascended from Mendrisio (where horses and guides may be hired, the latter unnecessary); to the hotel in 2½ hrs., thence to the summit in 1½ hr. more. The bridle-path, passing the wine-cellar of the village of *Salorino*, ascends in zigzags — (pedestrians may take the path to the left, 20 min. beyond Mendrisio, pass the church on the terrace, and proceed to *Sommazzo*, keeping the valley on the right) — to a dale, at the upper extremity of which (1¼ hr., halfway to the hotel) there is a spring in the rock. The path then leads through a grove of chestnuts, and farther on through a beech-wood to the (1¼ hr.) *\*Hôtel du Gènéroso*, the property of *Dr. Pasta* of Mendrisio, a comfortable house with post and telegraph offices, and well adapted for a prolonged stay; ¼ hr. farther, beyond the ridge, are the chalets of *Cassina* where a fine breed of cattle is reared. From the hotel to the summit a steep ascent of 1½ hr., past several peaks of the Generoso. The view embraces the lakes of Lugano, Como, Varese, and the Lago Maggiore, the populous plains of Lombardy, and to the N. the entire Alpine chain from the Monte Viso to the Bernina. At the foot of the mountain, figs and grapes thrive luxuriantly; higher up are dense forests of chestnuts and beeches, and beyond these, broom and scanty herbage. The mountain abounds in rare plants. — The Monte Generoso may also be ascended from *Maroggia* (see below); pleasant bridle-path by *Rovio* (\*Hotel Rovio, where horses and guides may be hired) to the top in 4 hrs.; or from *Balerna* by *Muggio* (to which there is a carriage-road) and *Scudellate* to the summit in 4¼ hrs.

At (12 M.) *Capolago* (Inn on the lake) the line reaches the **\*Lake of Lugano**, or *Lago Ceresio* (892 ft.), the scenery of which is little inferior to that of its more celebrated neighbours Como and Maggiore. In the vicinity of Lugano the banks are picturesquely studded with villas and chapels, and planted with the vine, fig, olive, and walnut. The W. side of the S. arm also presents several delightful points of view. The scenery of the E. arm of the lake (p. 151) is wild and deserted.

The train now skirts the lake, at first on the E. bank, affording charming views. — 14½ M. *Maroggia*. Near *Bissone* the lake is crossed from E. to W. by means of an unsightly stone dyke, ½ M. in length, 26 ft. in width, completed in 1846, along which the line is constructed; at each end is an arch for the passage of vessels. — 16½ M. *Melide* is situated on a promontory on the W. bank of the lake. The white dolomite, of which the mountains chiefly consist here, changes near Melide to dark porphyry, and as *S. Martino* is approached, there is a gradual transition to shell-limestone. — 20½ M. *Lugano* is at present the terminus, but the line is being continued to Bellinzona (p. 33). The station is beautifully situated above the town.

**Lugano.**—**Hotels.** *\*HÔTEL DU PARC*, in the suppressed monastery of *S. Maria degli Angioli*, on the S. side of the town, with a pleasant garden and several dependencies, R. 3-5, L. 1, B. 1½, D. 5, A. 1, music 1 fr.; pension in summer 9 fr. and upwards, but less in winter; attendance complained of; *\*GRAND HÔTEL SUISSE*; *HÔTEL DE LA COURONNE*, cheaper, well spoken of; *\*BELLEVUE*, on the lake. — *Post* and *Telegraph* offices at the Gov. Buildings (see below).

**Restaurants.** *Concordia* and *Americana*, both on the lake; *Café Fè-*



*rini, Jacchini, and del Teatro* in the Piazza della Riforma, at the back of the Gov. Buildings.

**Lake Baths** of the *Società Salvatore* adjoining the Hôtel Bellevue, and *Bagni Galleggianti* by the Hôtel du Parc (for swimmers, 1 fr. with towels).

**Diligence** to *Luino* once daily in 2½ hrs.; steamboat-tickets for *Lago Maggiore* are also issued at the office; to *Bellinzona* (railway to *Biasca*, and diligence thence to *Lucerne* by the St. Gotthard) three times daily; to *Coire* by the *Bernardino* once daily.

**Steamboat** to *Porlezza* twice daily in 1 hr.; to *Ponte Tresa* twice daily in ¼ hr. round the *Monte S. Salvatore* (a pleasant trip; stations *Campione, Bissone, Melide, Brusino, Marcote, Porto, Brusin-Piano, and Ponte Tresa*, p. 150).

**Boats** to *Porlezza* (p. 142) with one rower 7 fr., two 12 fr., three 16½ fr.; to *Osteno* 6, 10, or 12 fr., incl. fec. At the hotels, one rower 2 fr., two rowers 3 fr. for the first hour, each additional, 1½ and 2 fr. respectively.

**Carriages.** To *Luino* with one horse 12, two horses 20 fr., *Bellinzona* 16 or 30, *Magadino* 16 or 30, *Varese* 16 or 30, *Baveno* 22 or 40, *Fluelen* with two horses 220 fr. (driver's fee extra).

**English Church Service** at the Hôtel du Parc.

*Lugano* (932 ft.), the capital of the Swiss canton of *Ticino*, with 6024 inhab., is charmingly situated on the lake of the same name, and enjoys quite an Italian climate (the aloe blooming here in the open air). It is a very pleasant place for a lengthened stay; the environs possess all the charms of Italian mountain scenery; numerous villages and country-seats are scattered along the margin of the lake, and the lower hills are covered with vineyards and gardens, contrasting beautifully with the dark foliage of the chestnuts and walnuts in the background. To the S., immediately above the town, rises the *Monte S. Salvatore*, wooded to its summit; among the mountains towards the N. the double peak of the *Monte Camoghè* (7303 ft.; p. 33) is conspicuous.

The interior of the town with its arcades, workshops, in the open air, and granite-paved streets, is also thoroughly Italian in character. On market-day (Tuesday) a variety of picturesque Italian costumes and characteristic scenes may be observed here.

The once numerous monasteries of *Lugano* have been suppressed with the exception of two. The most important was that of *S. Maria degli Angioli*, now the Hôtel du Parc. The adjacent church contains beautiful \*Frescoes by *Bern. Luini*.

The painting on the wall of the screen, one of the largest and finest ever executed by *Luini*, represents the \**Passion of Christ*, and contains several hundred figures, arranged according to the antiquated style in two rows. In the foreground, occupying the upper part of the wall, stand three huge crosses, at the foot of which we perceive Roman warriors, the groups of the holy women, and St. John, and the executioners casting lots for the garments. Above, on a diminished scale, from left to right, are Christ on the Mount of Olives, Christ taken prisoner, the Scourging, the Bearing of the Cross, the Entombment, and the Ascension, all immediately adjacent. Although the style of the composition strikes one as old-fashioned, especially after seeing *Leonardo's* works, the eye cannot fail to be gratified by the numerous beautiful details. The St. Sebastian and St. Rochus, below, between the arches, are particularly fine. To the left, on the wall of the church, is the *Last Supper*, a picture in three sections, formerly in the Lyceum, and in the 1st Chapel on the right is a *Madonna*, both also by *Luini*.

*S. Lorenzo*, the principal church, on an eminence (fine view

from the terrace), probably erected by *Tommaso Rodari* at the end of the 15th cent., has a tastefully adorned marble façade.

Adjoining the Theatre are the *Government Buildings*, with a cool and pleasant colonnaded court. The hall contains a monument to the architect *Canonico di Tesserete*, and a marble bust of *General Dufour*.

A small temple at the *Villa Tanzina*, where suites of apartments may be hired,  $\frac{1}{4}$  M. S. of the *Hôtel du Parc*, contains a bust of Washington, '*magnum saeculorum decus*'. — The *Villa Vusalli*, charmingly situated near the *Hôtel du Parc*, of which it is now a dépendance, has a beautiful and very extensive garden, containing fine cedars, magnolias, camellias, etc. — Superb view from the tower in the garden of the *Villa Endertin*, to which access is permitted by the proprietor.

The beautiful \**Park of M. Ciani*, extending along the N. bay of the lake about  $\frac{1}{2}$  M. from the *Hôtel du Parc*, is always open to visitors (gardener 1 fr.).

On the broad quay opposite the *Hôtel du Parc* is a *Fountain* with a *Statue of William Tell*, 8 ft. in height, in white sandstone, designed by *Vinc. Vela*, and erected in 1856.

Delightful excursion to \**Monte S. Salvatore* (2982 ft.), ascent 2 hrs., descent  $1\frac{1}{2}$  hr., guide (4 fr.) superfluous (comp. Map, p. 138); horse 9 fr., mule 8 fr., incl. fee. About 10 min from the *Hôtel du Parc*, between a detached house and the wall of a garden, a good paved path diverges to the right from the road to *Melide* (p. 147); 2 min. farther, where the path divides, we go not to the right, but straight on to the houses; between these the road ascends, past the handsome and conspicuous (25 min.) *Villa Marchino*, to (5 min.) the village of *Pazzallo*, from which *Monte Rosa* is visible through a mountain-gorge. Here the path diverges to the left from the broad road, passes through the gateway of the fourth house, and leads to the left by a stony but easy ascent in  $1\frac{1}{2}$  hr. to the *Pilgrimage Chapel* on the summit (milk is sometimes obtainable at the small house near the top, but no other refreshment). The \**View* embraces all the arms of the Lake of Lugano, the mountains and their wooded slopes, especially those above Lugano, sprinkled with numerous villas. To the E. above *Porlezza* is *Monte Legnone* (p. 144), to the left of which, in the extreme distance, are the snow-peaks of the *Bernina*; N. above Lugano the double peak of *Monte Camoghè* (p. 33), to the left of this the distant mountains of *St. Gotthard*; W. the chain of *Monte Rosa*, with the *Matterhorn* and other Alps of the *Valais*. This view is seen to best advantage in the morning, when *Monte Rosa* gleams in the sunshine. The construction of a carriage-road and of a hotel on the summit is projected. In descending, the route through *Carona* and *Melide* (somewhat longer) may be chosen.

A DRIVE (or *Steamboat Journey*, p. 148) ROUND THE MONTE S. SALVATORE ( $4\frac{1}{2}$  hrs.) is much recommended. We proceed by ( $\frac{1}{2}$  hr.) *Pambio*, where a monument by *Vela* has been erected near the church of *S. Pietro* to *Capt. Carloni*, who fell at *Somma Campagna* in 1848, to (1 hr.) *Figino*, where we approach the W. arm of the lake. The road then skirts the lake and passes round the *Monte Arbostora* to ( $\frac{3}{4}$  hr.) *Morcote*, charmingly situated and commanded by a ruined castle (view from the top), and to (1 hr.) *Melide*. Thence to *Lugano*, by the high road. — The churchyard of *S. Abbondio*, 1 M. to the W. of *Pambio* (see above), contains a fine monument of the *Torriani* family, a woman praying, by *Vela*.

The ascent of \**Monte Brè* (3100 ft.), to the N.E. of Lugano, is another easy excursion, scarcely less interesting than that to *Mte. S. Salvatore*.

(It is advisable to take a guide from Brè.) A road runs inland towards several mills at the foot of the mountain. Thence a broad and well-constructed path winds upwards to the right to the small village of *Desago*, passing a few groups of houses. Above *Desago* the path divides; both routes are broad, and well-constructed, leading round the mountain to the village of *Brè* on its farther side (Inn, bread and wine only). The route to the right, above the lake, is very beautiful, while that to the left commands a fine inland view. Near the church of *Brè* a narrow forest-path ascends to the summit of the mountain. This path also divides; the branch to the right traverses the highest crest of the hill, that to the left leads to a spur of the mountain in the direction of *Lugano*. The summit may be attained by either. The view of the several arms of the Lake of *Lugano*, especially in the direction of *Porlezza*, and the surrounding mountains, is remarkably fine. *Lugano* itself is not visible from the summit, but from the above-mentioned spur a good view of it may be obtained. From *Lugano* to *Brè* about 1½ hr.; from *Brè* to the summit by the longest way about 1 hr.

**Monte Caprino**, opposite *Lugano*, on the E. bank of the lake, is much frequented on holidays by the townspeople, who possess wine-cellars (*cantine*) in the numerous cool grottoes by which the side of the mountain is honeycombed. These receptacles are guarded by numerous huts, which from a distance present the appearance of a village. Good wine of icy coolness may be obtained here ('*Asti*' recommended), and there is also a brewery.

Excursion to the *Grotto of Osteno*, see p. 151; — to *Bellinzona*, see p. 33.

Beyond *Lugano* the road gradually winds upwards to the W., turns S. past the small *Lake of Muzzano*, crosses the *Agno*, leads through the village of that name (967 ft.), and a short distance farther reaches the W. arm of the Lake of *Lugano*. Near *Magliaso*, with an ancient castle of the *Beroldingen* family, the lake is quitted, but another of its bays is touched near (6 M.) *Ponte Tresa* (steamboat to *Lugano*, see p. 148). This bay, which is so completely enclosed by mountains as apparently to form a distinct lake; is connected with the Lake of *Lugano* by a narrow channel only. The *Tresa*, which here emerges from the lake, falls into the *Lago Maggiore*, ¾ M. S.W. of *Luino*. The road follows its course as far as the Italian frontier at *Fornace* and *Fornasette*, where luggage is examined; it then descends, and soon affords a view of the *Lago Maggiore*.

15 M. *Luino*, see p. 153.

### 3. FROM MENAGGIO BY PORLEZZA TO LUGANO.

OMNIBUS from *Menaggio* to *Porlezza* in 2 hrs. (fare 3 fr. 60 c.); one-horse carriage 6-8 fr.; two-horse 12 fr. From *Porlezza* to *Lugano* STEAMBOAT (twice daily there and back; Tuesdays three times) in one hour (fare 2½ or 1 fr. in *silver*); boat with one rower 7, with two 12, with three 16½ fr.; bargaining necessary. A railway from *Tremezzo* to *Luino* by *Menaggio*, *Porlezza*, and *Lugano* is projected.

The journey from *Menaggio* to *Porlezza* (9 M.) is also recommended to pedestrians, as the road leads through a succession of imposing and attractive mountain-scenes. The *Villa Vigoni* (p. 142) lies to the right of the road (N.). The retrospect from the height near *Croce*, 2 M. from *Menaggio*, is delightful. Towards the W., on the left the *Monte Crocione*, and opposite to us the *Monte Gal-*

*biya* (5630 ft.) rise precipitously from the lake. The road then descends to the small *Lago del Piano* and the village of *Tavordo*. Thence to Porlezza  $1\frac{1}{4}$  M. more.

**Porlezza** (*Inn* on the lake), with 12,000 inhab., is situated at the N. end of the Lake of Lugano. Attempts at extortion are frequently made here by the fraternity who prey upon travellers.

Soon after Porlezza is quitted, the Monte S. Salvatore (p. 149) becomes conspicuous to the S.W. The steamer touches at *Osteno* (*Inn* on the lake), on the left.

The interesting \**Grotto of Osteno* may easily be visited from Lugano with the aid of the steamboat bound for Porlezza (disembarking at Osteno, and returning by the next boat). The grotto is 7 min. from the landing-place; the boatman is to be found in the village. The mouth of the gorge, in which there are two small waterfalls, is near a projecting rock. Visitors embark in a small boat and enter the grotto, the bottom of which is entirely occupied by the brook. The narrow ravine, through which the boat now threads its way, is curiously hollowed out by the action of the water. Far above, the roof is formed by overhanging bushes, between which an occasional glimpse of blue sky is obtained. The gorge, which is terminated by a waterfall, resembles that of Pfäfers, and is equally imposing, although shorter.

Opposite, on the N. bank, are the villages of *Cima*, *Cresogno*, and *Albogasio*; farther on, at the foot of *Monte Brè* (p. 149), *Gandria*, beautifully situated, with hanging gardens, lofty arcades, vine-terraces, etc. The S. arm of the lake now opens; to the left lies *Monte Caprino* with its wine-cellars; the steamer rounds the promontory of *Castagnola* and reaches *Lugano* (p. 147).

## 24. Lago Maggiore.

### From Arona to Milan and to Genoa.

**Steamboats** ply on the lake 3 times daily during the summer: from *Magadino* to *Arona* in  $5\frac{1}{2}$  hrs., from *Luino* to *Isola Bella* in  $2\frac{1}{4}$  hrs., from *Isola Bella* to *Arona* in  $1\frac{1}{4}$  hr.; fares from *Magadino* to *Arona* 4 fr. 80 and 2 fr. 65 c., from *Luino* to *Isola Bella* 1 fr. 85 and 1 fr. 15 c., from *Isola Bella* to *Arona* 1 fr. 70 and 90 c., *landing and embarking included*. The **STRAMBOATS** are the best and cheapest conveyance to *ISOLA BELLA*, especially for a single traveller (from *Pallanza* 60, from *Baveno* 50, from *Stresa* 40 c.); and as they touch at the island 4-6 times daily, frequent opportunities are afforded for the excursion. — **STATIONS** (those at which the steamers do not touch regularly are printed in *Italics*): *Magadino*, *Locarno*, *Ascona* (small boat station), *Brissago*, *Cannobbio*, *Maccugno*, *Luino*, *Cannero*, *OGGEBBIO*, *Ghiffa* (small boat station), *Porto Valtravaglia*, *Laveno* (touched at on every trip but one), *Intra*, *Pallanza*, *Suna* and *Fariolo* (small boat stations), *Baveno*, *Isola Bella* (small boat station), *Stresa*, *Belgirate*, *Lesa*, *Meina*, *Angera*, *Arona*. Restaurants on board all the steamers.

**Boats.** Travellers coming from the Simplon usually take a boat at *BAVENO* (pp. 27, 154) to visit the Borromean Islands. The charge for an excursion not exceeding 2 hrs. is fixed for each rower at  $2\frac{1}{2}$  fr.; for 1-3 pers. 2 rowers, for 4-6 pers. 3, more than 6 pers. 4 rowers, so that the half-hour's passage to *Isola Bella* is somewhat expensive. — Half-way between *Stresa* and *Baveno*, opposite the island, there is a ferry, where 1-2 fr. is exacted for a passage of scarcely 10 min.; the other boatmen demand 5 fr. The passage from *Stresa* for 1-2 pers. costs 2 fr., for 3 or more with 2 rowers 4 fr., according to tariff. For the return from the island to the

mainland, to Baveno, Stresa, etc., the boatmen demand 5 fr., but they reduce their terms as the time for the departure of the steambot approaches. From Isola Bella to Isola Madre and back, incl. stay, 5 fr. with two rowers.

RAILWAY FROM ARONA TO MILAN, see p. 157; to *Novara* and *Genoa*, see p. 157. — FROM LOCARNO to *Bellinzona* and *Biasca*, see pp. 32, 33; in correspondence with which a diligence crosses the St. Gotthard to Lucerne in 16 hrs. (R. 4); from Bellinzona to Coire over the Bernardino, see R. 6.

Diligence from ARONA twice daily in 6 hrs. to *Domo d'Ossola* (p. 27), in correspondence with the diligence over the Simplon (R. 3). — From *Luino* Swiss diligence daily in 2¾ hrs. to *Lugano* (R. 23). — Tickets issued on board the steamers.

The \**Lago Maggiore* (646 ft., greatest depth 2800 ft.), the *Lacus Verbanus* of the Romans, is 37 M. in length and averages 4½ M. in width. The canton of Ticino possesses only the N. bank for a distance of 9 M.; this portion of the lake is also called the *Lake of Locarno*. The W. bank beyond the brook *Valmara*, and the E. bank from *Zenna* belong to Italy. Its principal tributaries are on the N. the *Ticino* (*Tessin*), on the W. the *Tosa*, on the E. the *Tresa*, flowing from the Lake of Lugano. The river issuing from the S. end of the lake retains the name of *Ticino*. The N. banks are bounded by lofty mountains, for the most part wooded, whilst the E. shore towards the lower end slopes gradually away to the level of the plains of Lombardy. The W. bank affords a succession of charming landscapes. The water is of a green colour in its N. arm, and deep blue towards the S.

At the N.W. angle of the lake, at the influx of the Ticino, lies *Magadino* (Bellevue, on the lake), consisting of Upper and Lower Magadino, at which, since the opening of the railway to Locarno (p. 32), the steamers only touch once daily. — Opposite to it, on the W. bank, lies —

**Locarno** (682 ft.; \**Grand Hôtel Locarno*, a large new house with pleasant grounds, and \**Corona*, both on the lake; \**Albergo Svizzero*, in the piazza, moderate; *Caffè del S. Gottardo*, adjoining the Corona), with 2700 inhab., the terminus of the railway mentioned at p. 33, and one of the three capitals of the Canton of Ticino, situated at the mouth of the *Maggia*, the deposits of which have formed a considerable delta. Politically Locarno is Swiss, but the character of the scenery and population is thoroughly Italian. The *Collegiate Church* contains a few good pictures. The handsome *Governmnte Buildings* are situated in a large 'piazza' and public garden. The pilgrimage-church of \**Madonna del Sasso* (1168 ft.), on a wooded eminence above the town, commands a remarkably fine view. The busy market held at Locarno every alternate Thursday affords the visitor an opportunity of observing a variety of costumes of the peasantry of the neighbourhood. Great national festival on 8th Sept., the Nativity of the Virgin.

The W. bank of the lake, to the S. of Locarno, is studded with country-houses, villages, and campanili. On the bank of

the lake runs the new carriage-road from Locarno to Pallanza; in the angle lies *Ascōna* with its castle and seminary; higher up, on the slope, *Ronco*. Passing two small islands, we next reach *Brisago* (\**Albergo Antico*), a delightful spot, with picturesque white houses conspicuous from a great distance, and an avenue of cypresses leading to the church. The slopes above the village are covered with fig-trees, olives, and pomegranates, and even the myrtle flourishes in the open air. — On the E. bank, opposite, is situated *Pino*, on a grassy slope.

*S. Agāta* and *Canobbio* (\**Albergo del Bissone*; *Pension Villa Badia*, 7 fr.) are on Italian territory. The latter is one of the oldest and most prosperous villages on the lake, situated on a plateau at the entrance of the *Val Canobbino*, and overshadowed by richly-wooded mountains. The high altar-piece of the church *Della Pietà*, the dome of which is ascribed to Bramante, is a Crucifixion by Gaud. Ferrari.

Pleasant walk of 1/2 hr. up the beautiful Val Canobbino to the hydro-pathic establishment of *La Salute* (at present closed), and thence to the (20 min.) *Orrido*, a wild rocky scene with a bridge and in spring a waterfall.

The boat now steers for the E. bank, and touches at *Maccagno*, whence a walk of 2 hrs. may be taken to the loftily situated *Lago Delio* (new inn; extensive view). — Farther on, *Casnedù*, in a wooded ravine; then —

**Luino** (\**Hôtel du Simplon*, R. 3, D. 5, pension 8 fr.; *Vittoria*; *Posta*), with the *Palazzo Crivelli* surrounded by pines, the station for Lugano (p. 150), and a favourite summer resort on account of the beauty of its environs. The Piazza Garibaldi is adorned with a statue of that hero. — About 1/2 M. to the S., at the mouth of the *Margorabbia*, lies *Germignaga*, with the large silk-spinning (filanda) and silk-winding (filatoja) factories of Cesare Bozotti and Co. of Milan.

On the W. bank rise two grotesque-looking castles (*Castelli di Cannero*), half in ruins, the property of Count Borromeo. In the 15th cent. they harboured the five brothers Mazzarda, notorious brigands, the terror of the district. — **Cannero** is beautifully situated in the midst of vineyards and olive-groves, which extend far up the slopes of the mountain. The W. bank is clothed with the richest vegetation, and studded with innumerable white houses and a succession of picturesque villages.

The small villages of *Oggebbio* and *Ghiffa* on the W. bank, and *Porto Valtravaglia* on the E., are only touched at by some of the steamers. In a wooded bay beyond the last lies *Calde*, with the ancient tower of the *Castello di Calde* on an eminence. Then, to the E., —

**Laveno** (\**Posta*; *Moro*; *Stella*), a village of some importance, beautifully situated in a bay at the mouth of the *Boesio*, formerly a strongly fortified harbour for the Austrian gunboats (to Varese

see p. 146). *Fort Garibaldi*,  $1\frac{1}{2}$  M. from Laveno, commands a charming view of the lake and the mountains beyond. — Behind Laveno rises **Il Sasso del Ferro** (5918 ft.), the most beautiful mountain on the lake, commanding a magnificent view of the lake, the plain as far as Milan, and the Monte Rosa chain. The five-peaked summit of Monte Rosa is also visible from this part of the lake.

As the boat approaches Intra, a rotunda with a statue, belonging to the *Villa Prina*, becomes visible. The valley, which here opens to the W., suddenly discloses a strikingly picturesque view of the N. neighbours of Monte Rosa: first the Strahlhorn, then the Mischabel and Simplon. They are lost to view as the steamboat turns the point between Intra and Pallanza, but soon re-appear and remain visible until Isola Bella is reached. From the island itself they are hidden by the mountains of the valley of the Tosa.

**Intra** (*Vitello d'Oro; Leone*), a flourishing town (4300 inhab.) with manufactories, chiefly belonging to Swiss proprietors, is situated on an alluvial soil, between the mouths of two mountain-streams, the *S. Giovanni* and *S. Bernardino*. Omnibus daily between Intra, Pallanza, and Orta; comp. R. 25.

On the promontory of *S. Remigio*, which here juts into the lake, stands a church on the site of an ancient Roman temple of Venus. This is the widest part of the lake. The little *Isola S. Giovanni*, one of the Borromean group, with its chapel, house, and gardens, is the property of Count Borromeo.

**Pallanza.** — **Hotels.** \*GRAND HÔTEL PALLANZA, a large house, beautifully situated; R. 3 fr. and upwards, B.  $1\frac{3}{4}$ , D. 5, L. 1, A. 1 fr.; also a pension. — POSTA; ITALIA.

*Boat* with one rower to the Isola Madre  $1\frac{1}{2}$ , with two 3 fr., to Isola Bella  $2\frac{1}{2}$  or  $4\frac{1}{2}$ ; to both islands  $3\frac{1}{2}$  or 6, to Stresa  $2\frac{1}{2}$  or 4, to Laveno  $2\frac{1}{2}$  or  $4\frac{1}{2}$ , to Luino 6 or 10 fr., etc.

*Diligence* to Domo d'Ossola in 5 hrs., once daily, on the arrival of the steamboat from Magadino.

*Omnibus* to Orta (p. 159) once daily.

*Pallanza*, a thriving little town with 4000 inhab., delightfully situated opposite the Borromean Islands, commands a beautiful view of them, the lake, and the Alps to the N. The nursery gardens of *Rovelli*, *Cerutti*, and others deserve a visit (fee  $\frac{1}{2}$ -1 fr.). Pleasant walk by the new road round the *Monte Rosso*, ascending by the brook *S. Bernardino* as far as (3 M.) the old Roman bridge of *Santino*.

The lake here forms an extensive bay,  $4\frac{1}{2}$  M. long and  $2\frac{1}{4}$  M. wide, running in a N.W. direction, at the N. extremity of which is the influx of the impetuous *Tosa* (*Toce*). On its N.E. bank lies *Suna*, on the S.W. *Fariolo* (*Leone d'Oro*), where the Simplon route (p. 27) quits the lake; the steamboat does not always touch at these two stations. — Then **Baveno** (\*Grand Hôtel Bellevue; \**Beaurivage*, pension 9-10 fr.; *Sempione*), a small town with













1300 inhab., the usual starting-point of travellers from the Simplon for a visit to the —

**\*Borromean Islands.** The steamers touch only at the most S. of these, the *Isola Bella*, which with the *Isola Madre* is the property of the Borromeo family. Between these lies (W.) the *Isola dei Pescatori*, or *Superiore*, the property of the fishermen who inhabit it; to the N. is the *Isola S. Giovanni* mentioned above.

In the 17th cent. Count *Vitalio Borromeo* (d. 1690) erected a château on **\*Isola Bella** and converted the barren rock into beautiful gardens, rising on ten terraces 100 ft. above the lake, and stocked with lemon-trees, cedars, magnolias, cypresses, orange-trees, laurels, magnificent oleanders, and other luxuriant products of the south. The view is very beautiful (evening light most favourable). Shell-grottoes, fountains (dry), mosaics, and statues meet the eye in profusion, but in questionable taste. The *Château*, which is quite disproportionate to the size of the island, is richly decorated, and contains a collection of pictures more numerous than valuable. The N. wing is in ruins. The view through the arches of the long galleries under the château is very striking. A domestic hurries visitors through the apartments (fee  $\frac{1}{2}$ -1 fr. for each pers., a party in proportion), and consigns them to a gardener, who shows the garden with equal dispatch for a similar fee. Adjoining the château is the *\*Hôtel du Dauphin*, or *Delfino* (R. 2 fr. and upwards, D. at 4 p. m. 4 fr., B. 75 c.; also pension, 8-9 fr.). For a boat with two rowers from *Isola Bella* to the other islands (2 hrs.) a charge of 5 fr. is made.

The **\*Isola Madre** on its S. side resembles the *Isola Bella*, and is laid out in seven terraces with lemon and orange-trellises; on the upper terrace is an uninhabited 'Palazzo' (beautiful view). On the N. side, there are charming walks in the English style, with most luxuriant vegetation (fee 1 fr.). — The **Isola dei Pescatori** is entirely occupied by a small fishing-village, the single open space being just sufficient for drying the nets.

The scenery around the Borromean Islands rivals that of the Lake of Como in grandeur, and perhaps surpasses it in softness of character. Monte Rosa is not visible; the snow-mountains to the N.W. are the glaciers and peaks of the Simplon; of the nearer mountains the most conspicuous are the white granite-rocks near Baveno (p. 27). The traveller coming from the N. cannot fail to be struck with the loveliness of these banks, studded with innumerable habitations, and clothed with southern vegetation (chest-nuts, mulberries, vines, figs, olives); the extensive lake with its deep blue waters and beautiful girdle of snowy mountains combining the stern grandeur of the High Alps with the charms of a southern clime. Rousseau at one time intended to make the Borromean Islands the scene of his 'Nouvelle Héloïse', but considered them too artificial for his romance, in which human nature is portrayed with such a masterly hand.

The steamboat now steers S. to —

**Stresa.** — **Hotels:** **\*HÔTEL DES ILES BORROMÉES**, a handsome establishment with diligence office,  $\frac{1}{2}$  M. from the landing-place, R.  $3\frac{1}{2}$ -4, B.  $1\frac{1}{2}$ , A.  $\frac{3}{4}$ , D. 5 fr., pension (room 2-3 fr. extra) in summer  $7\frac{1}{2}$ , in winter 6-7 fr.; **\*HÔTEL DE MILAN**, with garden, near the steamboat-

pier, R. 2, D.  $4\frac{1}{2}$ , B.  $\frac{3}{4}$ , L.  $\frac{1}{2}$ , pension 7-8 fr. — **HÔTEL DU SIMPLON**, pension  $6\frac{1}{2}$ -7 fr.; **ALBERGO REALE**, Italian inn, tolerable.

**Boat** (barca) with one rower  $1\frac{1}{2}$  fr. for the first, and 1 fr. for each additional hour. Comp. p. 151.

**Carriage.** To Domo d'Ossola with one horse 15-20 fr., with two horses 30-35 fr.; to Arona with one horse 6 fr.; carriages for the Simplon route to Sion may also be procured. No supplementary carriages provided when the diligence is full.

*Stresa* is situated on the coast, opposite the *Isola Bella*. The handsome *Rosminian Monastery* halfway up the mountain is now a college. Beautiful cypresses in the *Churchyard*. Among the finest villas in the environs are that of the *Duchess of Genoa*, and the *Villas Casanova, Imperatori, Collegno, Durazzo*, and others. — Ascent of Monte Motterone, see p. 158.

As the boat steers its course along the W. bank, the construction of the high-road, in many places supported by piers of masonry, attracts attention owing to the difficulties which had to be overcome. The banks gradually become flatter, and Monte Rosa makes its appearance in the W. The next place on the W. bank is **Belgirate** (*\*Hôtel and Pension Belgirate*, formerly *Borromeo*, a large new establishment), with about 700 inhab., surrounded by the villas *Fontana, Principessa Matilda, Pallavicini*, and others. — Then follow *Lesà* and *Meina* (*Albergo Zanetta*), and, on the E. bank, *Angera*, where the boat touches once a day only. The handsome chateau above the village belongs to Count Borromeo. The steamer finally stops at the station beyond Arona.

**Arona** (738 ft.; *\*Italia*, or *Posta*, diligence-office; *\*Albergo Reale*, both on the quay, R. 2, A.  $\frac{3}{4}$  fr.; *Café* adjoining the *Albergo Reale*; *Café du Lac*, near the quay), an ancient town on the W. bank, about 3 M. from its S. extremity, with 3200 inhab., extends upwards on the slope of the hill. In the principal church of *S. Maria*, the chapel of the Borromean family, to the right of the high altar, contains the *\*Holy Family* as an altar-piece, by *Gaudenzio Vinci* (1511), a master rarely met with; it is surrounded by five smaller pictures, the upper representing God the Father, at the sides eight saints and the donatrix.

On a height overlooking the entire district,  $\frac{1}{2}$  hr. N. of the station and pier, is a colossal *\*Statue of S. Carlo*, 70 ft. in height, resting on a pedestal 42 ft. high, erected in 1697 in honour of the celebrated Cardinal, Count Carlo Borromeo, Archbishop of Milan (born here in 1538, died 1584, canonised 1610).

The head, hands, and feet of the statue are of bronze, the robe of wrought copper. Notwithstanding its enormous dimensions, the statue is not devoid of artistic merit. The various parts are held together by iron cramps attached to a pillar of masonry in the interior. By means of ladders, kept in readiness in the neighbourhood (fee), the lower part of the robe can be reached on the W. side, and the interior entered. The visitor may now climb by means of iron bars to the head of the statue, which will hold three persons, but the ascent is far from pleasant.

The adjacent church contains a few relics of *S. Carlo*. The extensive building in the vicinity is an *Ecclesiastical Seminary*.

## FROM ARONA TO MILAN.

42 M. RAILWAY in  $2\frac{1}{4}$ - $2\frac{1}{2}$  hrs.; fares 7 fr. 65, 5 fr. 35, 3 fr. 85 c.

The line follows the S. bank of the lake, crosses the *Ticino* (*Tessin*), the boundary between Piedmont and Lombardy, and, down to 1859, also the boundary between Sardinia and Austria. —  $5\frac{1}{2}$  M. *Sesto-Calende* (Posta), at the S.E. extremity of the Lago Maggiore, at the efflux of the Ticino; 10 M. *Vergiate*; 12 M. *Somma*, where P. Corn. Scipio was defeated by Hannibal, B.C. 218.

17 M. *Gallarate* (the junction of the Varese line, p. 145), a town with 5200 inhab., at the S.E. base of a range of hills which form the limit of the vast and fruitful Lombard plain, planted with maize, mulberries, and vines. 21 M. *Busto Arsizio*, the church of which, designed by Bramante, contains frescoes by Gaudenzio Ferrari. 24 M. *Legnano*, where Frederick Barbarossa was defeated by the Milanese in 1176; the principal church contains a fine altar-piece, one of the best works of Luini. —  $27\frac{1}{2}$  M. *Parabiago*; 33 M. *Rhò* (p. 76), with the church of the Madonna dei Miracoli by Pellegrini. — 38 M. *Musocco*.

42 M. *Milan*, see p. 118.

## FROM ARONA TO GENOA.

111 M. Railway in  $5\frac{1}{2}$ - $7\frac{1}{2}$  hrs.; fares 20 fr. 20, 14 fr. 15, 10 fr. 15 c. At the Mortara station this line is joined by another coming from Milan, on which the through trains from Milan to Genoa run: FROM MILAN TO GENOA,  $104\frac{1}{2}$  M., in  $5\text{--}7\frac{1}{2}$  hrs.; fares 17 fr. 30, 12 fr. 10, 8 fr. 70 c. (Railway by Voghera, see R. 26.)

6 M. *Borgo-Ticino*; 8 M. *Varallo-Pombia*; 13 M. *Oleggio* (to the right a fine glimpse of the Monte Rosa chain). The line traverses a flat district. —  $15\frac{1}{2}$  M. *Bellinzago*.

23 M. *Novara* (p. 75), where the Arona and Genoa line is crossed by that from Milan to Turin (R. 12); from Novara to *Turin*,  $2\frac{1}{4}$ -4 hrs.

31 M. *Vespolate*;  $33\frac{1}{2}$  M. *Borgo-Lavezzaro*. — 39 M. *Mortara*, a town with 6000 inhab. The church of *S. Lorenzo* contains several pictures by Crespi, Lanini, Procaccini, and Gaud. Ferrari (Madonna with SS. Rochus and Sebastian). — To the right and left are numerous fields of rice, which are laid under water during two months in the year, intercepted here and there by maize fields and mulberry trees.

At Mortara a direct line to Milan diverges. FROM MILAN TO MORTARA,  $32\frac{1}{2}$  M., in  $1\text{--}1\frac{3}{4}$  hr. (fares 6 fr., 4 fr. 20, 3 fr. 5 c.). Stations *Corsico*, *Gaggiano*, and *Abbiategrasso*. Crossing the Ticino, the train reaches *Vigevano* (*Albergo Reale*), with 15,000 inhab., a town of some importance in the silk-trade, and possessing a spacious market-place surrounded by arcades. Then ( $32\frac{1}{2}$  M.) *Mortara*, see above.

41 M. *Olevano*;  $45\frac{1}{2}$  M. *Valle*; 47 M. *Sartirana*; 51 M. *Torre-Beretti* (railway to Pavia, see p. 164).

To the left the long chain of the *Apennines* forms a blue line in the distance. The line crosses the *Po* by means of a bridge of twenty-one arches.

53½ M. **Valenza**, a town with 9000 inhab., formerly fortified, containing a cathedral of the 16th cent. (route to Pavia, see p. 164; to Vercelli, see p. 75). — The train next passes through a tunnel 1⅓ M. in length. — 57½ M. *Val Madonna*; several picturesquely situated small towns lie on the chain of hills to the right. The *Tanñiro* is then crossed.

63½ M. *Alessandria*; thence to Genoa, see pp. 78, 79.

## 25. From Stresa to Varallo.

### Monte Motterone. Lake of Orta.

Three days suffice for a visit to this district, which, though seldom visited, is one of the most beautiful of the S. Alps. Travellers from the Simplon (R. 3) should, after visiting the Borromean Islands, begin this excursion at STRESA (p. 155) and terminate it at ARONA; or GRAVELLONA (p. 27) may be taken as the starting-point, and STRESA the termination, in which case the portion between Orta and Varallo must be traversed twice. From Stresa or Isola Bella by the Motterone to Orta 9, from Orta (or rather from Pella) to Varallo 4½ hrs. walking; from Varallo to Arona 5, to Novara 6 hrs. drive.

A GUIDE (to the summit of Monte Motterone 5-6, to Orta 8 fr.; donkey and attendant to Orta 12 fr. and fee) can hardly be dispensed with. Mules at Orta at high charges. — The ascent of the Motterone is fatiguing, as the descent must be made the same day, but presents no difficulty and is very attractive.

The Lago Maggiore is separated from the Lake of Orta by a long mountain ridge, which is crossed by a footpath from *Stresa* (p. 155) in 5-6 hrs. via *Gignese*, *Coiro*, and *Armeno* (where the high road is reached) to Orta (see below). — Farther to the N. this mountain culminates in the grassy MONTE MOTTERONE. The path from *Stresa* (guide desirable, see above) ascends opposite the *Isola Bella*, at first through a chestnut grove; then, above the village of *Someraro*, over fern-clad and grassy slopes, passing several chalets shaded by lofty trees, and leading to the W. to a small church, where it turns to the right. Thence to the summit 1 hr. more.

The extensive prospect commanded by the summit of \***Monte Motterone** (4891 ft.), or *Margozzoto*, which may be called the Rigi of the S. Alps, embraces the entire amphitheatre of mountains from Monte Rosa to the Ortler in the Tyrol. A panorama may be bought at *Stresa* or *Orta* for 3½ fr.

To the right of Monte Rosa appear the snow-mountains of Monte Moro, Pizzo di Bottarello, Simplon, Monte Leone, Gries, and St. Gotthard; farther E. the conical *Stella* above *Chiavenna*, and the long, imposing ice-range of the *Bernina*, which separates the *Val Bregaglia* from the *Valtellina*. At the spectator's feet lie six different lakes, the Lake of Orta, Lago Maggiore, Lago di Monate, Lago di Comabbio, Lago di Biandrone, and Lago di Varese; farther to the right stretch the extensive plains of Lombardy and Piedmont, in the centre of which rises the lofty cathedral of Milan. The Ticino and the *Scsia* meander like silver threads through the plains, and by a singular optical delusion frequently appear to traverse a lofty tableland. The simultaneous view of the *Isola Madre* in Lago Maggiore and the *Isola S. Giulio* in the Lake of Orta has a remarkably picturesque effect. — The mountain itself consists of a number of barren summits, studded with occasional chalets, shaded by trees. At its base it is encircled by

chestnut-trees, and the foliage and luxuriant vegetation of the landscape far and wide impart a peculiar charm to the picture.

In descending from Monte Motterone to Orta we soon reach a broad bridle-path, which (guide now unnecessary) leads in 2½ hrs. to *Armeno* (Inn), situated on the high road. We now follow the road to (2 M.) *Miasino*, and (1½ M.) to *Ronchetti's* Pension (Posta), near which a path ascends to the right in 10 min. to the *Sacro Monte* (see below), and (¾ M.) *Orta*.

**Orta** (1220 ft.; *Hôtel S. Giulio*, in the market-place and on the lake, bargaining necessary; *Leon d'Oro*, also on the lake; *Due Spade*, at the back of the piazza, on the road to the *Sacro Monte*; one-horse carr. to *Gravellona* 8 fr.), a small town with narrow streets, paved with marble slabs, is most picturesquely situated on a promontory extending into the lake, at the base of a precipitous cliff. At the S. entrance to the town is the handsome villa of the Marquis Natta of Novara. The *Town-Hall* is situated on the quay.

OMNIBUS and DILIGENCE from Orta daily to *Omegna* (Posta), at the N. end of the Lago d'Orta, and by *Gravellona* (p. 27) to *Pallanza* (p. 154); also from Orta by *Bricione*, a village at the S. end of the Lago d'Orta, commanded by the old *Castello di Cuccione*, to station *Gozzano* (p. 76).

Above Orta rises the **Sacro Monte** (ascent from the principal piazza, or through the garden of Villa Natta, on which route a fee is expected for the opening of the upper gate), a beautifully wooded eminence, laid out as a park, on which 20 chapels were erected in the 16th cent. in honour of S. Francis of Assisi, each containing a scene from the life of the saint. The life-size figures are composed of terracotta, highly coloured, with a background *al fresco*; as a whole, though destitute of artistic worth, the representations are spirited and effective. The best groups are in the 13th, 16th, and 20th chapels, the last representing the canonization of the saint and the assembly of cardinals. The *Tower* on the summit of the hill commands an admirable panorama; the snowy peak of Monte Rosa rises to the W. above the lower intervening mountains. The *'Eremita del Monte'* expects a fee of 1 fr., for showing the above-mentioned three chapels.

In the **Lake of Orta** (9 M. in length, 1½ M. in width), opposite to Orta, rises the rocky island of *S. Giulio*, covered with trees and groups of houses (boat there and back 1 fr.). The Church, founded by St. Julius, who came from Greece in 379 to convert the inhabitants of this district to Christianity, has been frequently restored; it contains several good reliefs, some ancient frescoes, a handsome pulpit in the Romanesque style, and in the sacristy a Madonna by *Gaudenzio Ferrari*.

On the W. bank of the lake, opposite the island, the white houses of the village of **Pella** (*Albergo del Club Alpino*, R. 1, D. 3 fr.) peep from the midst of vineyards and groves of chestnut and walnut-trees. Boat from Orta to Pella 1 fr. with one rower.

A path towards the S. winds upwards from Pella, through a grove of chestnut and fruit trees, in 1½ hr. to the *Madonna del Sasso*, the picturesque church of the village of *Boletto*. An open space by the church, on the brink of a precipice several hundred feet above the lake, commands a fine prospect.

From Pella over the Colma to Varallo 5 hrs. (donkey 7, or, to the Colma only, 3½ fr.; guide unnecessary). A steep path ascends the hill to the W., traversing luxuriant gardens (vines, figs, pump-



kins, and fruit-trees); after 12 min. we avoid the ascent to the right. In 1 hr. (from Pella) we reach *Arola*, at a small chapel beyond which we must again avoid the ascent to the right; the path pursues a straight direction and soon descends. The *Pellino*, a mountain-torrent, descending from the Colma, forms (5 min.) a picturesque waterfall. Beautiful retrospective views of the lake. The path now ascends through a shady wood, between disintegrated blocks of granite which crumble beneath the touch, to the **Col di Colma** (2½ hrs. from Pella), a ridge connecting *Monte Pizzigone* with *Monte Ginistrella*. The prospect of the Alps is beautiful, embracing Monte Rosa, the lakes of Orta and Varese, and the plain of Lombardy. The whole route is attractive. In descending on the W. side (to the right) the traveller overlooks the fruitful *Val Sesia*, with its numerous villages. The path, again traversing groves of chestnut and walnut-trees, carpeted with turf and wild-flowers, now leads through the *Val Duggia* to (1 hr.) *Civiasco* and (1 hr.) —

**Varallo** (1515 ft.; \**Itatia*; \**Posta*; \**Croce Bianca*, moderate; *Falcone Nero*), the principal village (3200 inhab.) in the valley of the *Sesia*, a stream rising on the Monte Rosa, and one of the chief tributaries of the Po, into which it flows beyond Casale (p. 75), but frequently dry in summer. A bridge with three arches crosses the river. The old town and the *Sacro Monte* are very picturesque when seen through the arches of the bridge. — The collegiate church contains an altar-piece representing the Nuptials of St. Catharine by *Gaudenzio Ferrari*, who was born here in 1484 (d. 1549; p. 65). The churches of \*S. Maria delle Grazie (in the choir), S. Maria di Loreto, and S. Marco also contain frescoes by this master (those in the last being of his earlier period).

The *Sacro Monte*, the object of numerous pilgrimages, rises in the immediate vicinity of the town. It is attained in ¼ hr. by a path shaded by beautiful trees, but the enjoyment is somewhat marred by the importunities of beggars. The summit, surmounted by a chapel and crucifix, commands a magnificent view of the surrounding mountains towering one above another. Besides the church there are a great number of CHAPELS or ORATORIES on the summit and slopes of the *Sacro Monte*, many of them buried among the trees, containing scenes from the life of the Saviour, in terracotta, with life-size figures arranged in groups. Each chapel is devoted to a different subject; the 1st, for example, to the Fall, the 2nd to the Annunciation, and so on to the 46th, containing the Entombment of the Virgin. Some of the frescoes by *Pellegrino Tibaldi* and *Gaudenzio Ferrari* are worthy of inspection. This '*Nuova Gerusalemme nel Sacro Monte di Varallo*' was founded by Bernardino Caloto, a Milanese nobleman, with the sanction of Pope Innocent VIII. As a resort of pilgrims, it did not come into vogue until after the visits of Cardinal Borromeo (p. 156) in 1578 and 1583, from which period most of the chapels date.

Varallo is admirably adapted as head-quarters for excursions to the neighbouring valleys, which are very attractive and easily accessible (comp. *Baedeker's Switzerland*).

A carriage-road (omnibus twice daily) descends the picturesque valley of the *Sesia* to (6 M.) *Borgo Sesia*, (7½ M.) *Romagnano* (Posta); then, quitting the *Val Sesia*, by *Sizzano*, *Fara*, and *Briona* to *Novara* (p. 75).

## 26. From Milan to Voghera (*Genoa*) by Pavia.

### Certosa di Pavia.

110 M. RAILWAY in 6-8 hrs.; fares 20 fr. 10, 14 fr. 10, 10 fr. 10 c. (to Pavia only, 22½ M., in 1 hr.; fares 4 fr. 10, 2 fr. 85, 2 fr. 5 c.). No express-trains between Milan and Genoa, except on the Vigevano, Alessandria, and Genoa line, see p. 157.

A visit to the Certosa and the town of Pavia may be conveniently combined with the journey to Genoa by taking the early train to the Certosa, visiting Pavia in the afternoon, and proceeding to Alessandria in the evening. The striking scenery of the Apennines on the line between Novi and Genoa should, if possible, be traversed by daylight.

Those who desire to visit both the Certosa and Pavia from Milan are recommended to take a return-ticket to Pavia, inspect the town (in about 3 hrs.), and then drive (one-horse carriage 4-5, there and back 6 fr.) to the Certosa, a pleasant journey of 50 min., skirting a canal. A visit to the Certosa occupies 1½-2 hrs.; thence to stat. Certosa a walk of ¼ hr. The return-ticket is of course not available for the journey from Pavia to the Certosa and thence to Milan, as the journey cannot be broken without the ticket being given up (comp. Railways, *Intro.* vii).

*Milan*, see p. 118. The train to Pavia at first follows the Piacenza line, and then diverges to the S.W. before stat. *Rogoredo* is reached. The country is flat; underwood and rice-fields are traversed alternately. — 9½ M. *Locate*; 12½ M. *Villamaggiore*.

On the road, to the W. of the line, lies *Binasco*, a small town with an ancient castle, in which, on 13th Sept., 1418, the jealous and tyrannical Duke Fil. Maria Visconti caused his noble and innocent wife Beatrice di Tenda (p. 111) to be executed.

17½ M. *Guinzano*, or *della Certosa* (a plain breakfast may be obtained at the *Ristoratore*, 2 min. from the stat.), whence we follow the path planted with willows, and skirt the long garden-wall of the monastery towards the right (walk of ¼ hr.).

The \***Certosa di Pavia**, or Carthusian monastery, the splendid memorial of the Milan dynasties (p. 118), founded in 1396 by Gian Galeazzo Visconti, and suppressed under Emperor Joseph II., was restored to its original destination in 1844 and presented to the Carthusians, several of whom have been left here after the recent suppression of the Italian monasteries for the sake of control and the guidance of visitors (30-50 c.). A vestibule, embellished with sadly damaged frescoes by *Bern. Luini* (SS. Sebastian and Christopher) leads to a large inner court, at the farther end of which rises the celebrated façade of the church.

The \*\***FAÇADE**, begun in 1473 by *Ambrogio Boryognone*, an example of the richest Renaissance style, is entirely covered with marble of different colours and most tastefully decorated; below are medallions of Roman emperors, above them scenes from sacred history, and from the life of Gian Galeazzo; then heads of angels, beyond them the magnificent windows, and above these numerous niches filled with statues. Thirty of the most distinguished Lombard masters from the 15th to the 17th cent. have had a share in its embellishment, the most eminent of whom are: *Ant. Amadeo* and *Andr. Fusina* (15th cent.); *Giacomo della Porta* and *Agostino Busti*, surnamed *Il Bambaja* (p. 126, to whom the principal portal

is ascribed), and *Cristofano Solari*, surnamed *Il Gobbo*. This is unquestionably the finest decorative work of the kind in N. Italy, although inferior to the façades of the cathedrals of Orvieto and Siena, especially as the upper part has never been completed.

The body of the church, begun in 1396 by *Marco di Campione* in the Gothic style, consists of a nave with aisles and 14 chapels, and is surmounted by a dome, borne by ten slender columns. The interior (to which ladies are now admitted) is sumptuously and tastefully fitted up. The handsome coloured enrichments were probably designed by *Borgognone*, and the pavement of modern mosaic is also worthy of notice.

The CHAPELS and altars are richly adorned with valuable columns and precious stones. 2nd Chapel on the right: good altar-piece in six sections by *Maerico d'Alba* (1496); 4th Chapel on the right, Crucifixion by *Ambrogio Borgognone*; 5th Chapel on the right, St. Sirus with four saints, by the same. The 2nd Chapel on the left (counting from the entrance) formerly contained a picture by *Perugino* in six sections, of which the central part, above, representing God the Father, is alone original, the other parts being now in France and England. The other frescoes and paintings by *Borgognone*, *Procaccini*, *Guercino*, *Bianchi*, *Crespi*, father and son, and others are of no great value.

The transept and choir are separated from the rest of the church by a beautiful *Screen* of iron and bronze. RIGHT TRANSEPT: magnificent Monument of *Giangaleazzo Visconti*, designed in 1490 by *Galeazzo Pellegrini*, but executed chiefly by *Antonio da Amadeo* and *Giacomo della Porta*, and not completed till 1562. LEFT TRANSEPT: Monuments of *Lodovico Moro* and his wife *Beatrice d'Este* (d. 1497), by *Crist. Solari*. — The CHOIR contains a fine altar with carving of the 16th century. The choir-stalls are adorned with figures of apostles and saints, from drawings by *Borgognone*. The four handsome bronze candelabra in front of them are by *Liberio Fontana*. The old sacristy to the left of the choir contains a beautifully carved ivory altar-piece in upwards of 60 sections by *Leonardo degli Ubbriachi* of Florence (16th cent.).

The door to the right of the choir, handsomely framed in marble, leads to the LAVATORY, which contains a richly adorned fountain and (on the left) the Madonna and child in fresco by *Bern. Luini*. To the right of the lavatory is a small burial-place.

The SAGRESTIA NUOVA, or ORATORIO, is entered from the S. end of the transept: Altar-piece, an Assumption by *Andrea Solario*, but the upper part is said to have been painted by *Giulio Campi* of Cremona. Over the door, Madonna enthroned, by *Bart. Montagna*; the side pictures by *Borgognone*.


The front part of the CLOISTERS (della Fontana) possesses slender marble columns and charming decorations in terracotta. Fine view hence of the side of the church and the right transept with its trilateral end. The REFECTORY is also situated here. — Around the large CLOISTERS, farther back, are situated the 24 small houses occupied by the few remaining monks, each consisting of three rooms with a small garden.

The battle of Pavia, at which Francis I. of France was taken prisoner by Lannoy, a general of Charles V., took place near the Certosa on 24th Feb. 1525.

22½ M. *Pavia*, junction of different lines (see p. 164).

**Pavia.** — *CROCE BIANCA* (Pl. a), bargaining necessary, R. 2, omnibus 1½ fr.; *LOMBARDIA* (Pl. b); *Pozzo* (Pl. c), near the bridge over the Ticino; *TRE RE* (Pl. d). — *Cafè Demetrio*, Corso Vittorio Emanuele.

*Cab per drive* 80 c., per hour 1½ fr. — *Omnibus* to the town 25 c.





*Pavia*, with 27,900 inhab., situated near the confluence of the Ticino and the Po, the *Ticinum* of the ancients, subsequently *Papia*, was also known as the *Città di Cento Torri* from its hundred towers, nine of which still exist. In the middle ages it was the faithful ally of the German emperors, until it was subjugated by the Milanese, and it is still partly surrounded by the walls and fortifications of that period. At the N. end of the town is situated the *Castle*, erected by the Visconti in 1360-69, now used as a barrack.

Leaving the railway-station, we enter the CORSO CAVOUR (Pl. A, 4) through the Porta Borgorato or Marengo (in a wall to the right is the statue of a Roman magistrate), and following the Via S. Giuseppe to the right reach the Piazza del Duomo.

The CATHEDRAL (Pl. 4; B, 4), rising on the site of an ancient basilica, begun in accordance with a design by *Brumante*, and continued by *Cristoforo Rocchi* in 1486, but never completed, is a vast circular structure with four arms.

In the INTERIOR, on the right, is the sumptuous *Arca di S. Agostino*, adorned with 290 figures (of saints, and allegorical), begun, it is supposed, in 1362 by *Bonino da Campiglione*, by whom the figures on the tombs of the Scaliger family at Verona (p. 185) were executed. To the right of the entrance is a large model in wood of the church as originally projected.

The gateway to the left of the church is in the early Romanesque style. Adjoining it rises a massive Campanile.

We may now proceed to the CORSO VITTORIO EMANUELE, a street intersecting the town in a straight direction from N. to S., from the Porta di Milano to the Porta Ticinese, and leading to the covered Bridge (a pleasant promenade with picturesque view) over the *Ticino*, which is here navigated by barges and steamboats. A chapel stands on the bridge, halfway across.

S. MICHELE (Pl. 7; B, 5), to which the third side-street to the right leads (coming from the bridge), a Romanesque church erroneously ascribed to the Lombard kings, belongs to the latter part of the 11th cent., and is now undergoing restoration. The façade is adorned with numerous very ancient reliefs in sandstone, in ribbon-like stripes, and a curious gabled gallery. The nave and aisles are supported by eight pillars, from which rise double round arches. The short choir, under which there is a crypt, terminates in an apse. Over the centre of the transept rises a dome. The pillars of the nave bear traces of ancient frescoes.

The traveller may now ascend the Corso Vitt. Emanuele to the UNIVERSITY (Pl. 31; B, 4), the oldest in Europe, said to have been founded by Charlemagne. The building is much handsomer than that of Padua; the quadrangles of the interior are surrounded by handsome arcades and embellished with numerous memorial-tablets, busts, and monuments of celebrated professors and students. In the first court is a marble statue of the mathematician *Antonio*

*Bordoni* (d. 1864), in the second three monuments to professors attended by students.

The Corso next leads in a N. direction, past the *Theatre*, to the *Castle* mentioned at p. 163 (Pl. C, 3), containing a handsome court of the 14th cent.

At the back of the university lies the *Ospedale Civico*, and farther E., in the Contrada Canepanova the church of *S. Maria Incoronata di Canepanova* (Pl. 15; C, 4), a small dome-covered structure designed by Bramante (1492). — More to the N., at the corner of the Contrada del Collegio Germanico, is the Romanesque church of *S. Francesco* (Pl. 8; C, 4), dating from the 14th cent., with aisles and choir in the pointed style.

In the Contrada del Gesù, to the W. of the university, to the right, is the *Jesuits' Church* (Pl. 11; B, 4). — In the Contrada Malaspina is the *Casa Malaspina*, at the entrance to the court of which are busts of *Boëthius* and *Petrarch*. The interior contains a small collection of engravings and paintings.

*Boëthius*, when confined here by the Emperor Theodoric, composed his work on the 'Consolation of Philosophy', and *Petrarch* once spent an autumn here with his daughter and son-in-law. His grandson, who died at the Casa Malaspina, was interred in the neighbouring church of S. Zeno. A short poem of *Petrarch* in allusion to this event, in six Latin distiches, is one of the many inscriptions on the wall opposite the entrance.

The Contrada del Gesù terminates in the Piazza del Carmine, in which is situated the church of *S. Maria del Carmine* (Pl. 6), a brick edifice of fine proportions, flanked with chapels, and dating from 1375.

FROM PAVIA TO ALESSANDRIA VIÀ VALENZA, 40½ M., by railway in 3 hrs. (fares 7 fr. 40, 5 fr. 20, 3 fr. 75 c.). The line crosses the Ticino and intersects the *Lomellina*, or broad plain of the Po, in a S.W. direction. Stations *Cava*, *Zinasco*, *Pieve*, *Sannazzaro*, *Ferrera*, *Lomello*, *Mede*, *Castellaro*, *Torre-Beretti*, *Valenza*; see p. 158. Hence to *Alessandria* and *Genoa*. see p. 158, and pp. 75, 78 and 79.

FROM PAVIA TO BRESCIA VIÀ CREMONA, 77½ M., railway in 5 hrs. (fares 14 fr. 5, 9 fr. 85, 7 fr. 5 c.). — None of the stations are worthy of note except Cremona itself, but this line affords the most direct communication between Genoa and Verona (on the Brenner Railway).

The line intersects the fertile plain watered by the Po and the Olona. Stations *Motta San Damiano*, *Belgiojoso*, with a handsome chateau; near *Corteolona* the Olona is crossed. Then *Miradolo*, *Chignolo* on a small tributary of the Po, *Ospedaletto*, and *Casalpusterlengo*, where the line unites with that from Piacenza to Milan (R. 38). — 29½ M. *Codogno* possesses large cheese manufactories; the line to Piacenza diverges here to the S. (p. 251). Near *Pizzighettone*, a fortified place, the *Adda*, which is here navigable, is crossed. This district is considered unhealthy. Stations *Acquanegra* and *Cava Tigozzi*.

47 M. *Cremona* (see below) is a terminus. from which the train backs out. To *Treviglio* (Milan and Bergamo) and *Mantua*, see R. 27.


From *Cremona* to *Brescia* the line proceeds due N., following the direction of the high road, through a flat district. Stations *Olimeneta*, *Robecco-Ponterico*, beyond which the *Oglio*, a considerable affluent of the Po, is crossed. *Verotanuova*, *Manerbio*; then across the *Mella* to *Bagnolo* and *S. Zeno Gotzano*.

77½ M. *Brescia*, see p. 169.





# CREMONA.



Stazione

Stazione  
 Porta Milano  
 Piazza S. Felice  
 Piazza S. Giovanni  
 Piazza S. Maria  
 Piazza S. Spirito  
 Piazza S. Vito  
 Piazza S. Zenone  
 Piazza S. Andrea  
 Piazza S. Eusebio  
 Piazza S. Felice  
 Piazza S. Giovanni  
 Piazza S. Maria  
 Piazza S. Spirito  
 Piazza S. Vito  
 Piazza S. Zenone  
 Piazza S. Andrea  
 Piazza S. Eusebio

Piazza  
 d'Armi  
 S. Agostino  
 S. Michele  
 S. Pietro al Po  
 S. Felice  
 S. Giovanni  
 S. Maria  
 S. Spirito  
 S. Vito  
 S. Zenone  
 S. Andrea  
 S. Eusebio

**Chiese**

- 1. Battistero F. 4
- 2. Campo santo E. 4
- 3. Duomo F. 4
- 4. S. Abbondio G. 2
- 5. S. Agata D. 2
- 6. S. Agostino D. 3
- 7. S. Alario C. 2
- 8. S. Emidio G. 5
- 9. S. Michele H. 2
- 10. S. Pietro al Po D. E. 5
- 11. S. Felice E. 3
- 12. Palazzo pubbl. F. 4
- 13. Pellegrino E. 4

- Alberghi
- F. 3
  - E. 3
  - E. 4

1:15,000  
 0 200 400 600 800 1000 metri

FROM PAVIA TO PIACENZA *vià* CODOGNO (p. 251), 37½ M., railway in 2 hrs., if no delay takes place in Codogno (fares 6 fr. 85, 4 fr. 80, 3 fr. 45 c.). *Piacenza*, see p. 251.

FROM PAVIA TO VOGHERA, 19 M., in ¾ hr. (fares 3 fr. 10, 2 fr. 20, 1 fr. 60 c.). The train crosses the Ticino, the Po, and a small tributary of the latter. Stations *Cava Manara*, *Bressana*, *Calcababbio*.

*Voghera*, and journey to Tortona, see pp. 76, 77; Novi, and journey to Genoa, see p. 79.

## 27. From Milan to Mantua *vià* Cremona.

100 M. RAILWAY in 5-6 hrs.; fares 18 fr. 35, 12 fr. 85, 8 fr. 20 c.

From Milan to (20 M.) *Treviglio*, see p. 167. Our train diverges here from the main line to the S.E. — 2¼ M. *Caravaggio*, birthplace of the painter Michael Angelo Amerighi da Caravaggio (1569-1609), with the pilgrimage-church of the *Madonna di Caravaggio*. — 30 M. *Casaletto-Vaprio*; 3¼ M. *Crema*, an industrial town (9000 inhab.), and episcopal residence, with an ancient castle and two Renaissance churches.

40 M. *Castelleone*; 45 M. *Soresina*; 50½ M. *Casalbuttano*; 54½ M. *Olmeneta*; 61 M. *Cremona*, the station of which is outside the Porta Milanese.

**Cremona.** — SOLE D'ORO (Pl. a); °ITALIA (Pl. b); CAPPELLO (Pl. c). — *Cab per drive* ½ fr., for ½ hr. 1 fr., for each additional ½ hr. ½ fr.

*Cremona*, the capital of a province and an episcopal see, with 28,600 inhab., is situated in a fertile plain on the left bank of the Po. The spacious streets and piazzas bear testimony to its ancient importance.

The original town was wrested by the Romans from the Gallic Cenomani and colonised by them at various periods, the first of which was at the beginning of the second Punic war (B.C. 218). It suffered seriously during the civil wars, and was several times reduced to ruins, but was restored by the Emp. Vespasian. The Goths and Lombards, especially King Agilulf, as well as the subsequent conflicts between Guelphs and Ghibellines, occasioned great damage to the town. Cremona espoused the cause of Frederick Barbarossa against Milan and Crema, and afterwards came into the possession of the Visconti and of Francesco Sforza, after which it belonged to Milan. On 1st Feb., 1702, Prince Eugene surprised the French marshal Villeroi here and took him prisoner. In 1799 also the Austrians defeated the French here.

The manufacturers of the far-famed VIOLINS and VIOLAS of Cremona were *Amati* (1590-1620), the two *Guarneri* (1552-80 and 1717-40), and *Stradivari* (1670-1728).

Cremona was the birthplace of *Sofonisbe Angussola* (1535-1626), who, like her five sisters, practised the art of painting, and was highly esteemed by her contemporaries. She afterwards retired to Genoa, and even in her old age attracted the admiration of Van Dyck. In the 16th cent. Cremona possessed a school of art of its own, which appears to have been influenced by Romanino especially, and also by Giulio Romano.

In the PIAZZA GRANDE (Pl. F, 4) rises the *Torrazzo*, a tower 397 ft. in height, said to be the loftiest in Italy, erected in 1261-84, connected with the cathedral by a series of logge. The sum-

mit commands an extensive prospect. — Opposite the tower is the Gothic \**Palazzo Pubblico* (Pl. 12) of 1245 (restored), containing a few pictures by masters of the Cremona school, and a richly decorated chimney-piece in marble by *G. C. Pedone* (1502). Adjacent is the \**Palazzo de' Giureconsulti*, of 1292, now a school.

The \**Cathedral* (Pl. 3; F, 4), of 1107, in the German-Lombard style, has a rich façade embellished with columns.

The INTERIOR with its aisles and transept, also flanked with aisles, is covered with frescoes executed by the chief representatives of the school of Cremona, such as *Boccaccino* (1500), father and son, and the later masters *Campi*, *Altobello*, *Bembo*, and *Gatti*. The best, however, are by *Gior. Ant. da Pordenone* of Venice, particularly on the wall of the entrance and the right wall of the nave.

In the vicinity are the octagonal *Battistero* (Pl. 1; F, 4) of 1167, and the *Campo Santo* (Pl. 2), with curious and very ancient mosaics; among these are Hercules and Nessus; Piety wounded by Cruelty; Faith tearing out the tongue of Discord, etc. (entrance to the right of the cathedral, No. 10).

From the *Palazzo Pubblico* to the W. the Contrada *Ariberti* leads to the *Palazzo Reale* (formerly *Ala di Ponzone*), which contains natural history and other collections, a cabinet of coins, and a few pictures (open daily 9-3, except Sundays). Farther up the Corso *Vittorio Emanuele*, in the second cross-street to the left, is the church of *S. Pietro al Po* (Pl. 10; D, E, 5), designed by *Ripari* in 1549-70, and containing pictures by *Ant. Campi*, *Bern. Gatti*, and others. — We then return by the Contrada *Bassa* to *S. Agostino e Giacõmo in Braida* (Pl. 6; D, 3) of the 14th cent., with paintings by *Perugino* (6th chapel on the right, \**Madonna* and two saints, 1494) and *Galeazzo Campi*.

We next walk through the Contrada *S. Margherita* (passing on the right the small church of that name, with frescoes by *Giulio Campi*) to the *PIAZZA GARIBALDI* (Pl. C, D, 2) with the church of *S. Agata* (Pl. 5), whence the Corso di *Porta Milano* leads in a N.W. direction to the gate of that name and to the station.

Among the numerous handsome palaces of Cremona may be mentioned the *Pal. S. Secondo* in the Corso di *Porta Milano*, with a sculptured portal by *Sacchi* (a copy in terracotta, the original sculptures having recently been removed); the *Palazzo Crotti* (formerly *Raimondi*), containing sculptures by *Pedone*, and the *Pal. Stanga a S. Vincenzo*.

About 1½ M. to the E. of the town, not far from the Mantua road, is the church of *S. Sigismondo*, containing frescoes and pictures by *Campi*, *Boccaccino*, and other Cremona masters; \**Altarpiece* by *Giulio Campi*, representing the *Madonna* with saints, and below, *Francesco Sforza* and his wife, the founders of the church. — Near the village of *Le Torri* lies the beautiful *Villa Sacerdoti*.

FROM CREMONA TO BRESCIA OR PAVIA, SEE p. 164.

FROM CREMONA TO PLACENZA (diligence daily in 5 hrs.). The road intersects the plain on the right bank of the *Po*, after having crossed the river





with its numerous islands, and leads by *Monticelli*, *S. Nazaro*, and *Caorso*, where the river formed by the *Chiareina* and *Riglio* is crossed. Near *Roucaglia* we cross the *Nure* and soon reach *Piacenza* (p. 251) to the W.

66 M. *Villetta-Malagnino*; 70 M. *Gazzo* and *Pieve S. Giacomo*; 75 M. *Torre de' Pienardi*; 79 M. *Piadena*; 84 M. *Bozzolo*, with 4300 inhab. and an old castle belonging to the Gonzaga family. Before reaching (88 M.) *Marcaria*, a town with 7500 inhab., the train crosses the *Oglio*. — 93½ M. *Castellucchio*.

About 2½ M. to the E. of Castellucchio, and 5 M. from Mantua, is situated the church of *S. Maria delle Grazie*, founded in 1399, a famous resort of pilgrims, and containing a number of curious votive offerings in the form of life-size figures in wax, bearing the names of 'Charles V', 'Ferdinand I', 'Pope Pius II', the 'Connétable de Bourbon', and others. Also a few monuments.

The train now crosses the *Mincio*. — 100 M. *Mantua*, see p. 191.

## 28. From Milan to Verona.

105½ M. RAILWAY in 3¼-5½ hrs. (fares 19 fr. 65, 13 fr. 85, 9 fr. 90 c.). Finest views to the left.

*Milan*, see p. 118. — 7 M. *Limite*, 12 M. *Melzo*. At (16 M.) *Cassano*, a considerable village, with a number of palatial looking houses, the train crosses the blue *Adda*. 20 M. *Treviglio* (branch-line to Cremona, see R. 27). 26 M. *Verdello*, 32½ M. *Bergamo*.

**Bergamo** (1246 ft.; \**Albergo d'Italia*, R. from 2 fr.; *Venezia*; *Cappello d'Oro*; *Caffè Centrale*), the ancient *Bergomum*, which belonged to the republic of Venice from 1428 to 1797, is now a provincial capital with 22,600 inhab., and one of the busiest of the smaller trading and manufacturing towns in Italy. The once far-famed fair (*Fiera di S. Alessandro*, lasting from the middle of August to the middle of September) has now lost its importance. The town consists of two distinct parts, the old and the new. The **NEW TOWN** (*Borgo S. Leonardo* and *Borgo S. Tomaso*), with its woollen, silk, and other manufactories, the Corso, the piazza where the fair is held, the new Prefettura, and a recently completed Protestant church, lies in the plain.

The **OLD TOWN** (*Città*), beautifully situated on the hills, is connected with the lower town by the *Strada Vittorio Emanuele*. The *Promenade* affords a fine view of the richly cultivated plain and the beautiful amphitheatre formed by the surrounding mountains, particularly those to the N.E. The *Castle* (Pl. A, 1), rising on the hill to the N.W. above the town, commands a still finer prospect.

In the market-place (1¼ M. from the railway-station), now the *Piazza Garibaldi*, is situated the *Palazzo Nuovo* (Pl. 8; C, 2), the seat of the municipal authorities, erected in the Renaissance style by Scamozzi, but unfinished. Opposite to it is the library in the Gothic *Palazzo Vecchio*, or *Brotetto*, the ground-floor of which

consists of an open hall supported by pillars and columns. Near it is the *Monument of Torquato Tasso* (whose father *Bernardo* was born at Bergamo in 1493), and a handsome fountain.

At the back of the Broletto rises the church of **S. Maria Maggiore** (Pl. 6; B, C, 2, 3), erected in 1173 in the Romanesque style, with ancient portals supported by lions on the N. and S. sides. Adjoining the N. portal is the rich Renaissance façade of the chapel of the Colleoni.

The INTERIOR (entrance on the S. side) contains some ancient pictures, fine carved work on the choir-stalls by the Bergamasque *Gior. Franc. Capo Ferrato*, and admirable inlaid wood (intarsia) by *Fra Damiano*. This church also contains the monument of the celebrated composer *Donizetti* of Bergamo (d. 1848), by *Vinc. Vela*, and, opposite, that of his teacher *Gior. Simone Mayr* (d. 1845). — The adjoining **Cappella Colleoni** (shown by the sagrestano of the church), in the early Renaissance style, contains the monument of the founder Bart. Colleoni (d. 1475; p. 241), by *G. Ant. Amadeo*, which is deservedly considered one of the best Renaissance sculptures in Lombardy. The reliefs represent the Bearing of the Cross, Crucifixion, and Descent from the Cross; below runs a frieze of Cupids, above which are the Annunciation, the Nativity, and the Magi; and on the summit is the gilded equestrian statue of Colleoni; adjacent, the much smaller, but beautifully executed monument of his daughter Medea.

The adjoining *Cathedral* (Pl. C, 2, 3) is a handsome, modern building. *S. Spirito*, *S. Bernardino*, and *S. Bartolommeo* contain pictures by *Lor. Lotto* (*S. Spirito* also has paintings by *A. Previtali*, and *Sgr. F. Frizzoni* possesses a few by *Gior. da Udine*). — On the slope of the hill, in the street leading to the lower town, is situated the **Accademia Carrara** (Pl. 11; E, 2), a school of art containing a picture-gallery (*Pinacoteca Lochis*; open to the public daily from 30th Aug. to 18th Sept.; during the rest of the year on the 1st Sund. and 3rd Thursd. of each month; shown at other times on application to the custodian).

I. Room: 28. *Velasquez*, Portrait. — II. R.: 79. *Leandro Bassano*, Monk praying; 95. *Moretto*, Holy Family; 97. *Paolo Veronese*, St. Christina; 75. *Civetta*, St. Christopher. — III. R.: 200. *Mantegna*, Resurrection; 218. *Bart. Vicarini*, Madonna; 204. *Gior. Bellini*, Portrait; 205. *Caroto*, Adoration of the Magi; 213. *Boltraffio*, Madonna; 212. *Antonello da Messina*, St. Sebastian; 194. *Crivelli*, Madonna; 210. *Gior. Bellini*, Madonna; 87. *Titian*, Sketch; 192. *Mantegna*, Portrait; \*190. *B. Luini*, Madonna and Child; 187. *Giorgione* (?), Portrait; 154. *Lor. Lotto*, Holy Family; 83. *Vittore Belliniano*, Crucifixion; 146. *A. Previtali*, Madonna; \*135. *Raphael* (?), St. Sebastian (with clothes, contrary to the tradition); this interesting picture is supposed to be an early work of Raphael, but is more probably by *Eusebio di S. Giorgio*, a pupil of Perugino; 128. *Cina*, Saints; 111. *Titian*, The prodigal son; 104. *Fr. Francia*, Bearing of the Cross; \*106. *Dürer*, same subject in grisaille, with lights in white. — GALLERIA CARRARA: I. R.: Indifferent pictures. — II. R.: 222. *Lor. Lotto*, Marriage of St. Catharine; 201. *Bonifazio*, The Magi. — III. R., on the right: 237. *A. Palmezzano*, Presentation in the Temple; 128. *Previtali*, Madonna; \*187. *Mantegna*, Madonna. In the last Room: *Beonino*, Last Supper.

From Bergamo to LECCO, see p. 144.

The RAILWAY to VERONA now describes a wide curve towards the S.E., and at (35½ M.) *Seriate* crosses the *Serio*. — 40 M. *Gior-*





# Brescia



- 1 S. Miro E.5
- 2 Broletto o Palazzo Vecchio D.3
- 3 S. Barnaba E.5
- 4 Garzate C.2
- 5 Duomo nuovo D.7
- 6 Duomo vecchio D.4
- 7 S. Eudonia F.4
- 8 S. Francesco B.1
- 9 S. Faustino mag. C.1
- 10 Giardini pubblici F.3
- 11 S. Giovanni Eboli. C.3
- 12 Mercato Grande F.4
- 13 S. Massimo e C. Leo B.5
- 14 S. Pietro all'Orto F.2
- 15 Piazza de' Orsabbili C.4
- 16 Palazzo Municipale C.3
- 17 Tempio di S. Spiridione N
- 18 Teatro Grande D.4
- 19 S. Maria delle Grazie A.2
- 20 Biblioteca Quiriniana D.4
- 21 S. Costanzo E.4
- 22 Galleria Teat. E.4
- 23 Madonna dei miracoli B.5
- 24 P. Torlunga N
- 25 S. Maria delle Grazie A.2

- Alberghi
- a Fenice D.8
  - b d'Orto D.5
  - c Gambero D.5

Geograph. Anwalt von Wagner & Debra Leipzig

1: 10000 0 100 200 300 400 500 600 metri

Stazione

P. S. Vescovani

P. S. Alessandro

*lago* and *Grumello* (branch-line to Sarnico, see p. 175). — At (42½ M.) *Palazzolo* the *Oglio*, descending from the *Lago d'Isèo*, is crossed. Picturesque glimpse of the village in the valley to the left with its slender towers. — 46 M. *Coccaglio*, with the monastery of *Mont' Orfano* on a height; 51 M. *Ospedaletto*.

63 M. *Brescia* (see below).

The slopes near *Brescia* are sprinkled with villas. The red colour of the mountains is due to the presence of abundant iron-ore (comp. p. 170). — The line soon quits the hilly district. — 69 M. *Rezzato*, beyond which the *Chiese* is crossed; 74 M. *Ponte S. Marco*. Beyond *Lonato* a short tunnel and a long cutting.

A long viaduct now carries the line to (80 M.) *Desenzano* (p. 177). The train affords an admirable survey of the *Lago di Garda* and the peninsula of *Sermione* (p. 178).

In this district, extending from the banks of the lake to a point considerably beyond *Guidizzolo* (on the road from *Brescia* to *Mantua*), the fiercely contested BATTLE OF SOLFERINO was fought on 24th June, 1859, between the united French and Italian armies and the Austrians. The defeat of the latter led shortly afterwards to the Peace of *Villafranca* (p. 190). The village of *Solferino* (Inn, good red wine; guides) lies on the heights to the S., about 5 M. from the railway; carriage from stat. *Desenzano*, there and back, 15 fr.

90 M. *Peschiera* (\**Railway Restaurant*; station ¾ M. from the town, comp. p. 180) lies at the S.E. end of the *Lago di Garda*, at the efflux of the *Mincio*, which the train crosses. On 30th May, 1848, the place was taken by the Piedmontese after a gallant defence by the Austrian General *Rath* (d. 1852).

93 M. *Castelnuovo*; the village is picturesquely situated on the left. 97 M. *Somma-Campagna*; then *S. Lucia* (to the right a campanile covered with zinc, and a churchyard with cypresses, which was gallantly defended by the 10th Austrian rifle battalion in 1848).

105½ M. *Verona*, see p. 182.

## 29. Brescia.

**Hotels.** ALBERGO D'ITALIA; ALBERGO REALE; FENICE, in the *Piazza del Duomo*; TORRE DI LONDRA; GAMBERO; CAPPELLO.

**Cafés.** Several adjacent to the theatre and in the *Piazza del Duomo*. — Beer at *Währer's*, near *S. Clemente* (Pl. 20; E, 4).

**Cabs (Cittadine):** 85 c. per drive, ¼ fr. per hour.

**Diligences:** to *Edolo* once daily (comp. p. 174); to *Salò* and *Gargnano* twice daily (see p. 178). — **Railway** from *Brescia* by *Cremona* to *Pavia*, see p. 164; to *Verona* and to *Milan*, see above.

*Brescia* (515 ft.), the ancient *Brixia*, which was conquered by the Gauls and afterwards became a Roman colony, vied with *Milan* at the beginning of the 16th cent. as one of the wealthiest cities of Lombardy, but in 1512 was sacked and burned by the French under *Gaston de Foix*, after an obstinate defence. Five years later it was restored to the dominions of *Venice*, to which it belonged till 1797, but it has never recovered its ancient impor-

tance. On 1st April, 1849, the town was bombarded and taken by the Austrians under *Haynau*, and some of the buildings still bear traces of damage done on that occasion.

Brescia is charmingly situated at the foot of the Alps. It is now a manufacturing place with 38,900 inhab., the capital of a province, and the residence of a bishop. Iron wares, and particularly weapons (hence 'Brescia armata') form the staple commodities, and a considerable number of the firearms used by the Italian army are made here. The woollen, linen, and silk manufactures are also worthy of mention.

Brescia occupies a place of no little importance in the history of art from having given birth to ALESSANDRO BUONVICINO, surnamed IL MORETTO (1498-1555), who appears to have studied exclusively at his native place, and whose teacher is said to have been *Floriano Ferramola* of Brescia. It has been asserted that he was influenced by Titian and the Roman school, but for this there is no reason. Like the Veronese masters, he is distinguished from the Venetian school, with which he has generally been classed, by the comparative soberness of his colouring, notwithstanding which he vies with the Venetians in richness and brilliancy. Buonvicino began his career as a painter in his 18th year. He rarely extended the sphere of his labours beyond his native place, and Brescia is therefore abundantly stored with his works. The churches here (such as S. Clemente, p. 173) display his fertility, both as a painter 'al fresco' and in oils, forming quite a museum of his pictures. S. Giovanni Evangelista (p. 172) contains his principal works; and the Coronation of Mary in S. Nazaro e Celso, and the high altar-piece in S. Clemente are also excellent. Another eminent master of the school of Brescia, and a contemporary of Buonvicino, was *Girol. Romano* (1485-1566). — Brescia also contains several interesting antiquities (p. 172).

From the station the town is entered at its S.W. corner by the *Porta S. Nazaro* (Pl. A, 6), whence the *Corso Vittorio Emanuele* leads N.E. to the *Piazza Vecchia* and the *Piazza del Duomo*.

The \***Duomo Nuovo** (Pl. 5; D, 4), or episcopal cathedral, begun in 1604 by *Lattanzio Gambara* (but the dome not finally completed till 1825), is one of the best churches of that period.

INTERIOR. By the first pillar on the right is the large \*Monument of Bishop Nava (d. 1831), with groups in marble and a relief by *Mouti* of Ravenna; by the first pillar on the left the monument of Bishop Ferrari. The second altar on the right is adorned with modern statues in marble of Faith by *Selaroni*, and Hope, by *Emanuelli*, and a modern painting, Christ healing the sick, by *Gregoletti*. Then (3rd altar on the right) a sarcophagus with small \*high-reliefs, date about 1500, containing '*Corpora D. D. Apollonii et Philastri*', transferred hither in 1674 from the crypt of the old cathedral. — High altar-piece an Assumption by *Zoboli*, designed by *Conca*. In the dome the four Evangelists, high reliefs in marble.

Passing through a door between the 2nd and 3rd altar, we descend by 25 steps to the *Duomo Vecchio* (Pl. 6; D, 4), generally called **La Rotonda**, situated on the low ground to the S. of the *Duomo Nuovo* (shown by the sacristan of the new cathedral who lives at the back of the choir of the latter). This massive structure is circular, as its name imports, with a passage round it, surmounted by a dome, and resting on eight short pillars in the interior. The substructure is very ancient (9th cent.), while the dome and cupola (Romanesque) date from the 12th century. The transept

and choir with lateral chapels at the back were added at a very early period. On both sides of the pulpit are statues by *Alessandro Vittoria*. At the second altar on the right is the monument of Bishop Lambertino (d. 1349) with reliefs. Altar-piece, an \*Assumption by *Moretto*. — Below the dome is the crypt, or *Basilica di S. Filastro*, supported by 42 columns (not at present accessible).

Opposite the E. side of the Duomo Nuovo is the entrance to the \**Biblioteca Quiriniana* (*Biblioteca Comunale*, Pl. 19; D, 4; fee 1½ fr.), comprising 40,000 vols., bequeathed to the town in 1750 by Cardinal *Quirini*. Several curiosities are preserved in a separate cabinet. (Admission daily, except Wed. and Sund., 11-3, in winter 10-3; vacation from 24th Dec. to 1st Jan. and from 1st Oct. to 2nd Nov.; closed on high festivals, and during the carnival.)

A Book of the Gospels of the 9th cent. with gold letters on purple vellum; a Koran in 12 vols. adorned with miniatures and gilding; a cross 4 ft. in height (*Croce Magna*), of gold, decorated with cameos and jewels and portraits of the Empress Galla Placidia and her children Honoria and Valentinian III., resembling modern miniatures, the whole a most valuable specimen of the workmanship of the 4th cent.; a small cross adorned with gold and pearls and a fragment of the 'True Cross', said to have been worn by St. Helena. The *Lipsanoteca*, carved in ivory, a cross composed of the sides of an ancient reliquary, with scriptural scenes, of the 4th or 5th cent. The *Dittico Quiriniano*, carved in ivory, presented by Pope Paul II., and other diptychs (ivory tablets with reliefs). Several calendars carved on a staff. Two caskets containing letters which passed between Napoleon and Canova. — In a separate room old Books of the Gospels with miniatures; a MS. of *Dante* on parchment, with miniatures; a *Petrarch* of 1470 with various illustrations (*'Petraarca figurato'*) and written annotations; a *Dante* with notes, printed at Brescia in 1487; the *Codice Eusebiano*, a concordance of the 11th cent. with miniatures; *Madonna* painted on lapis lazuli by *Titian*.

The **Broletto** (Pl. 2; D, 3), adjoining the cathedral on the N., is a massive and spacious building of the 12th cent., but was afterwards so much altered that its original form has been almost entirely obliterated. It was anciently the seat of the municipal authorities, and now contains the courts of justice. Part of it is used as a prison. The campanile on the S. side, called *La Torre del Popolo*, belongs to the original edifice. — A well preserved fragment of Romanesque architecture in the street ascending hence, with circular windows and brick mouldings, is also interesting.

To the W., not far from the Broletto, extends the interesting PIAZZA VECCHIA, in which rises the \***Palazzo Comunale** (Pl. 16; C, 3), usually called **La Loggia**, the town-hall of Brescia, erected by *Formentone* of Brescia in 1508 on the ruins of a temple of Vulcan, with a 'putto' frieze by *Jacopo Sunsovino* and window mouldings by *Palladio*, of the latter half of the 16th century. The interior was half destroyed by a fire in 1575. The exterior of this imposing structure is almost overladen with enrichments. On the ground floor is a deep hall resting on columns; in front are pillars with columns in the wall. In the angles of the arches is a series of busts of Roman emperors as medallions. The upper floor recedes

considerably. The handsome adjacent building on the right, the *Archivio e Camera Notarile*, is probably also by Formentone. (The traveller should walk round the whole building.)

On the opposite side of the Piazza, above the arcade, rises the **Torre dell' Orologio**, or clock-tower, with a large dial marking the hours according to the Italian computation (twice 1 to 12). The bell is struck by two iron figures as at Venice (p. 217). — To the left rises a *Monument*, erected by the king in 1864 to the natives of Brescia who fell during the gallant defence of their town against the Austrians in the insurrection of 1849. — The third side of the piazza is occupied by the *Monte di Pietà* (formerly the *Prigioni*), a plain Renaissance building with a handsome loggia.

Not far from the Piazza Vecchia is the church of \***S. Giovanni Evangelista** (Pl. 11; C. 3), containing several admirable pictures.

We begin on the right. 3rd Altar: \**Moretto*, Massacre of the Innocents. High-Altar: \*\**Moretto*, John the Baptist, Zacharias, St. Augustine, and St. Agnes; in the centre the Madonna; above, God the Father and a prophet. These are two of the master's most excellent works. — At the next Altar: *Giov. Bellini*, Pietà; the frescoes on the right are by *Moretto*: Collecting the manna, Elijah, the Last Supper, Two Evangelists, and prophets above; those on the left are by *Romanino*: Raising of Lazarus, Mary Magdalene before Christ, the Sacrament, two Evangelists, and prophets above. At the next altar: *Romanino*, Nuptials of Mary. In the Battistero: \**Francesco Francia*, The Trinity adored by saints.

Proceeding to the E. from the Piazza Vecchia, and straight past the N. side of the Broletto, we come to a small piazza, to the left in which is the entrance to the \***Museo Patrio** (Pl. 17; E. 3; shown daily, 11-3, on payment of a fee; open to the public during the August fair, 12-4; visitors knock at the door), established in a Corinthian temple of Hercules(?), which was excavated in 1822. The temple, which, according to inscriptions, was erected by Vespasian in A. D. 72 (*Tempio di Vespasiano*), stands on a lofty substructure with a projecting colonnade of ten columns and four pillars to which the steps ascend. The substructions, portions of the steps, and the bases and parts of the shafts of the columns, in white marble, are still well preserved. The Cella consists of three sections, each of which was dedicated to a different god (perhaps Jupiter, Juno, and Minerva).

The pavement of the PRINCIPAL HALL has been restored with the aid of the original remains. An ancient mosaic has also been placed here. By the walls are altars and Roman inscriptions from the province. The Room on the right contains mediæval and other curiosities, ornaments, the monument of Count Pitigliano, weapons, medals (those of the Napoleonic period very numerous). In the Room on the left are ancient sculptures, the most valuable of which is a fine statue of \*\**VICTORY*, excavated in 1826, a bronze figure about 6 ft. in height, with a silver-plated wreath of laurel round her head, a (restored) shield, on which she is about to write, in her left hand, and a (restored) helmet under her left foot. This is one of the most admirable specimens of the ancient plastic art now in existence. Also a number of coins and medals, ornaments, busts in gilded bronze, fragments of a colossal figure from a temple, portions of sarcophagi, decorated breastplate of a horse, etc.

The street opposite the museum descends to a small piazza.

from which a street to the left leads to S. Clemente. Remains of an ancient edifice are built into the wall of the house No. 285 in the small piazza.

**S. Clemente** (Pl. 20; E, 4) is a small church containing the tomb of *Moretto* (p. 170; immediately to the left) and five of his works: right, 2nd altar, SS. Cecilia, Barbara, Agnes, Agatha, and Lucia; left, 1st altar, St. Ursula; 2nd altar, St. Jerome praying; 3rd altar, Abraham and Melchisedech; \*high altar-piece, Madonna with St. Clement and other saints.

The \***Galleria Tosi** (or *Museo Civico*, Pl. 21; E, 4), situated a little to the S. of S. Clemente, in the Contrada Tosi, Quartiere VIII., No. 596 (shown daily, 11-3, on payment of a fee; open to the public during the August fair), bequeathed with the palace to the town by Count Tosi, contains a number of ancient and modern pictures, drawings, engravings, modern sculptures, etc. in a series of a small apartments.

In a room on the ground-floor the Laocoon, a group in marble by *Ferrari*; bust of Galileo by *Monti*; copies of Canova's colossal busts of himself and Napoleon, by *Gandolfi*; *Moretto* (*Buonvicino*), Virgin and Saints, from the church of St. Afra. — In the ante-chamber on the first floor a bust of Count Tosi by *Monti*, drawings, and frescoes by *Romanino*. Handsome inlaid reading desk by *Fra Raffaele da Brescia* (16th cent.). — I. Room (immediately to the left of the entrance): 2. *Fra Bartolommeo*, Holy Family; 3. *Moretto*, Annunciation; 6. *Moretto*, Portrait; 13. *Caravaggio*, Lute player; 16. Portrait in the style of Giorgione; miniatures and drawings. — II. Room: 1. *Monbello*, Presentation in the Temple; 2. *Moretto*, St. Sebastian (a copy of the picture in S. Nazaro e Celso, p. 174); 4. *Moroni*, Portrait (1560); 13. *Francesco Francia*, Madonna; 10. *Lor. Lotto*, Nativity; *Moretto*, 14. Herodias, \*16. The disciples at Emmaus. — III. Room: 1. *Andrea del Sarto*, Holy Family (sadly damaged); 39. *Civerchio*, Adoration of the Child; 75. *Albano*, Venus and Graces ('la toilette de Venus'); 18. *Moretto*, Descent of the Holy Ghost; \*22. *Raphael*, Christ with the crown of thorns and stigmata, teaching (1505); 21. *Ann. Caracci*, St. Francis; 84. *Cesare da Sesto* (?), Youthful Christ. — The cabinets contain interesting engravings, old woodcuts, and drawings (*A. Dürer*). — IV. Room: Modern pictures. 2. *Migliara*, La Certosa near Pavia; 3. *Borsato*, Winter at Venice; 7. *Vernet*, Night; 20. *Domenico Presenti*, Church of St. Celso at Milan, in water-colours; 13. *Basiletti*, Bay of Baiae; 17. *Canella*, Washerwomen at Roano. — In the passage a bust of Eleonora d'Este, by *Canova*; drawings; in the adjacent cabinet, a boy treading out grapes, by *Bartolini*. — Corridor with engravings. — In the CHAPEL a statue of the youthful Saviour, by *Marchesi*. — V. Room: *Baruzzi*, Silvia, statue in marble, from Tasso. — VI. Room: 2. *Canella*, Night, and other pictures by the same master; 11. *Azeglio*, Episode from Ariosto. — VIII. Room: 1. Day, \*2. Night, by *Thorvaldsen*, probably the most popular reliefs by this master. — IX. Room. Sculptures: 1. *Franceschetti*, Dant's Beatrice; 4. *Same master*, Flora; *Gheardo of Obstal*, Sacrifice of Isaac; *Gandolfi*, Genius of music; \*8. *Thorvaldsen*, Ganymede; 9. *Pampaloni*, Boy praying. — VII. Room: *Basiletti*, *Renica*, and *Bisi*. Landscapes. — X. Room: Modern pictures. 1. *Hayez*, Jacob and Esau; 6. *Apptani*, Madonna. — XI. Room: 10. *Palagi*, Newton discovering the law of refraction. — XII. Room: 1. *Belzuoli*, Copy of Raphael's Disputa. — XIII. Room: 1. *Podesti*, Tasso at the court of Ferrara; 2. *Diotti*, Death of Ugolino; 3. *Schiavoni*, Raphael and the Fornarina; 4. *Hayez*, Departure of the Greeks.

\***S. Afra** (Pl. 1; E, 5), situated in the street descending from

the Museo Patrio, was erected in 1580 on the site of a temple of Saturn, but has been entirely modernised.

1st altar on the right, *Bagnadore*, Nativity of Mary; 2nd altar, *Franc. Bassano*, Baptism of S. Afra; 3rd, *Passerotti*, Assumption; above the S. door: *Brusasorci*, Martyrdom of several saints; 4th altar, *Procaccini*, Virgin, S. Latinus, S. Carlo, and many other saints, a confused crowd of figures, all of the same size. High altar-piece, by *Tintoretto*, Ascension, in which the blue of the sky is the predominant colour. Over the N. door, *Titian*, Christ and the adulteress (generally covered). Over the N. altars: *Alessandro Maganza*, Christ in the house of Simon the Pharisee; *P. Veronese*, Martyrdom of St. Afra (in the foreground, among the be-headed martyrs, is the head of the painter); *Palma Giovine*, Brescian martyrs.

**S. Nazaro e Celso** (Pl. 13; B, 5), near the gate leading to the railway-station, erected in 1780, contains several good pictures.

High altar-piece by *Titian*, in five sections, the Resurrection being the principal subject, on the right St. Sebastian, on the left St. Nazarus and St. Celsum with the portrait of the donor of the picture; above these the Annunciation (1522). Over the 2nd altar on the left, Coronation of the Virgin, by *Moretto*; over the 3rd altar on the right, Ascension of Christ; over the 4th altar on the left, Nativity, with S. Nazaro and S. Celso, also by *Moretto*.

**Madonna dei Miracoli** (Pl. 22; B, 5), near S. Nazaro, a small church with four domes and richly decorated façade in the early Renaissance style, was erected at the end of the 15th cent.; 1st altar on the right, a \*Madonna and Child, with St. Nicholas, by *Moretto* (1539).

**S. Maria delle Grazie** (Pl. 23; A, 2), near the Porta S. Giovanni, contains two good works by *Moretto*: over the 4th altar on the right St. Antony of Padua and St. Antoninus the Hermit, and over the high altar a Nativity of Christ. — The churches of *S. Eufemia* (Pl. 7; high altar-piece), *S. Maria Calchera*, *S. Francesco*, and *S. Pietro in Oliveto*, also contain pictures by *Moretto*.

About  $\frac{1}{2}$  M. from the Porta S. Giovanni (Pl. A, 3) lies the pretty *Campo Santo*, to which an avenue of cypresses leads from the high road.

## 30. From Brescia to Tirano in the Valtellina.

### Lago d'Isèo. Monte Aprica.

Distance about 51 M. From Brescia a post-omnibus daily at an early hour, halting at *Pisogne* (1 hr.) and at *Breno* (1 hr.), and arriving at *Edölo* in the evening. Diligence from *Edölo* to *Tirano* also daily in 6 hrs.

This route is recommended to travellers who are already acquainted with the Lake of Como, and who desire to reach the upper Val Tellina and the Stelvio or Bernina (R. 6). The scenery from Isèo onwards is beautiful the whole way.

The road quits Brescia by the Porta S. Giovanni; after  $\frac{1}{2}$  hr. it diverges to the right from the Milan road, through a flat country, to *Camignone*, and near *Provaoglio* reaches the mountains.

$\frac{1}{2}$  M. **Isèo** (*Leone*), situated on the lake of that name, is a busy little town. STEAMBOAT twice daily from *Sarnico* (Leone d'Oro), at the S W end of the lake, to Isèo and Lovère (see below)

and back, in correspondence with the railway between Grumello (p. 168) and Sarnico, and the diligences between Brescia and Iseo, and Lovere and Edolo; from Sarnico to Lovere, 2½ hrs.

The \***Lago d'Isèo** (*Lacus Sebinius*, 620 ft. above the sea-level), about 15 M. in length from N. to S., about 1000 ft. deep in the centre, and averaging 1½ M. in breadth, somewhat resembles an S in form. The *Oglio* enters the lake between Pisogne and Lovere and emerges from it near Sarnico. The scenery vies in beauty with that of the Lago di Garda, the soil is admirably cultivated, and the vegetation of a luxuriant, southern character. The *Mezz-Isola*, an island 1½ M. in length, consisting of a lofty ridge descending precipitously on the E. side (at the S. E. base of which lies *Peschiera d'Iseo*, and at the N.W. base *Siviano*, two fishing-villages), rises picturesquely and boldly in the middle of the lake. Opposite *Peschiera* lies the islet of *S. Paolo*.

The new rock-hewn \*Road on the E. bank, beginning at *Sale Marazzino* and terminating at *Pisogne*, a distance of 6 M., is little inferior in boldness to that on the banks of the Lake of Como. It is carried through number of galleries and supported by solid masonry. Immediately to the left lies the lake, while the rocks rise precipitously on the right overhanging the road at places. From Iseo it winds through a succession of vineyards which cover the valley and its slopes, and reaches the bank of the lake at *Sulzano*, opposite the island mentioned above. On the mountain, far above, is seen the white church of *S. Rocco*; then the ruins of the monastery of *S. Loretto* on a rock in the lake. *Sale Marazzino* (*Albergo della Posta*), consisting of a long row of houses, is the largest village on the road. Next *Marone*, at the W. base of *Monte Guglielmo* (6414 ft.; ascent 4 hrs., beautiful view), and—

24 M. *Pisogne* (*Albergo Grisoni*), at the N. E. end of the lake. Towards the end of this part of the route the scenery is strikingly beautiful, especially where the lake terminates in a rounded bay, and where **Lovere** (*S. Antonio*, or *Posta*; *Leone d'Oro*; *Roma*), with its busy harbour, which before the construction of the road afforded the sole outlet to the industry of the Val Camonica, lies picturesquely on the N. bank. The church of the *Madonna dell'Assunta* contains several pictures by Moroni, and a monument by Canova. The long and handsome *Palazzo Tadini*, a conspicuous point in the distance, contains a collection of antiquities, pictures, and natural history specimens. — Omnibuses between Lovere and Edolo, and Lovere and Bergamo (p. 167).

The road now quits the lake and traverses a fertile, alluvial tract. To the left flows the *Oglio*, a considerable river, which is crossed at *Darfo*. The road skirts the W. side of the valley, which presents the usual characteristics of the valleys of the S. Alps, yielding rich crops of maize, grapes, mulberries, etc., and enclosed by lofty, wooded mountains. The dark rocks (ver-



rucano) here contrast peculiarly with the light triassic formations.

At *Cividate* the Oglio is crossed by two bridges. On the height a very picturesque deserted monastery. Near Breno a broad hill, planted in numerous terraces with vines and mulberries, and surmounted by a ruined castle, rises from the valley.

38 M. **Breno** (*Pellegrino; Italia*, poor) is the capital of the *Val Camonica*, which is 36 M. in length, extends from Lovere and Pisogne to the *Monte Tonale* (see below), and produces a considerable quantity of silk and iron.

The road now crosses a mountain-torrent descending from *Monte Pizzo*, the indented crest of which peeps from an opening on the right. A massive mountain of basalt here extends towards the road, and columnar basalt is visible at places near the summit. Beyond *Capo di Ponte* (1374 ft.) the character of the scenery gradually changes. The valley contracts, maize and mulberries become rarer, while numerous chestnut-trees flourish on the slopes and in the valley itself. The road ascends slightly.

54½ M. **Edolo** (2287 ft.; \**Posta; Due Mori; Leone*), a mountain-village possessing iron-works, lies in a basin on the *Oglio*, which descends from the rocks here. (Diligence to *Tirano*, 8 hrs.; one-horse carriage in 6 hrs., 10 fr.; to *Lovere* in 9 hrs., 15 fr.)

The TONALE ROUTE, diverging here to the N. E. to the **Monte Tonale** (6345 ft.), leads on the E. side of the *Monte Tonale*, which forms the boundary between Lombardy and the Tyrol, through the *Val di Sole* (*Sulzberg*) and *Val di Non* (*Nonsberg*), which descend to *S. Michele* (or *Walsch-Michael*), a station on the railway from *Bozen* to *Verona* (p. 47), in the valley of the *Adige*.

The new road to *Tirano*, which crosses numerous bridges and rests almost entirely on masonry, gradually ascends from *Edolo* on the N. slope of the *Val di Corteno*, affording pleasant retrospects of the *Val Camonica*, and the snow-peaks of the *Adamello* in the background. 4½ M. *Cortenedolo* (the village opposite, on the right bank of the *Corteno*, is *Santicolo*), then (2½ M.) *Galleno*, whence a path to the N. leads over the *Monte Padrio* in 3 hrs. to *Tirano*. The road next crosses to the right bank of the *Corteno*, and re-crosses it again at the small village of *S. Pietro*, not far from the summit of the (6 M.) **Passo d'Aprica** (4049 ft.). About ¾ M. beyond the pass, near the poor village of *Aprica*, stands the new \**Albergo dell' Aprica*.

A view of the *Val Tellina*, with *Sondrio* in the background, is now soon disclosed. The broad, gravelly bed of the *Adda* (p. 43) and the devastations frequently caused by the stream are well surveyed hence. Several of the snowy peaks of the *Bernina* come in view to the N.; lower down, above *Tresenda*, rises the square watch-tower of *Teglio* (p. 43). On the road is the *Belvedere* (Inn), 1½ M. from *Aprica*. Fine \*view of the valley of the *Adda*.





**ICONTORNI DI RIVA.**  
 Scala di 1: 250 000.



The admirably constructed road now descends through plantations of chestnuts, in a long curve, to *La Motta*; it finally reaches the bottom of the valley of the Adda by means of two tunnels, and crosses the river near *Tresenda* (p. 43).

In tolerably dry seasons, when no inundation of the Adda need be apprehended, pedestrians are recommended to quit the high road, a few paces from the point where it turns to the W., by a footpath to the right, at first somewhat steep, which near the village of *Stazione* crosses a brook, passes through an opening in the wall, and reaches *Madonna di Tirano* (p. 43) in 1½ hr. A saving of 4 M. is thus effected.

From *Tresenda* to *Tirano* about 6 M. more. *Tirano* (1413 ft.), see p. 43. Those whose destination is *Sondrio* (p. 43) need not proceed first to *Tirano*, but carriages are seldom to be obtained at *Tresenda*.

### 31. The Lago di Garda.

**Steamboat.** W. BANK, between *Desenzano* and *Riva*: dep. from *Desenzano* daily at 1. 50 p.m., arr. at *Riva* at 6. 30 p.m.; dep. from *Riva* on Tuesdays at 5 a.m., but every other day at 6 a.m., (fares 4 fr. 35, 2 fr. 40 c.). Stations *Salò*, *Maderno*, *Gargnano*, *Tignale*, *Tremosine*, *Limone*, *Riva*. — E. BANK, between *Riva* and *Peschiera*: dep. from *Riva* on Fridays at 5. 20 a.m., but every other day at 11. 50 a.m.; dep. from *Peschiera* on Fridays at 1. 20 p.m., every other day at 6. 15 a.m. (a trip of 4 hrs.; fares 4½, 2½ fr.). Stations *Torbole*, *Malcesine*, *Assenza*, *Castelletto*, *Torri*, *Garda*, *Bardolino*, *Lazise*, *Peschiera*. — Poor restaurant on board the steamers; payment to be made in Italian money.

The *Lago di Garda* (226 ft.), the *Lacus Benacus* of the Romans, the largest of the N. Italian lakes, is 37 M. in length, and 1½-10 M. broad at the widest part; area 189 sq. M., depth in many places upwards of 1000 ft. The whole lake belongs to Italy, except the N. extremity with *Riva*, which is Austrian.

The lake is rarely perfectly calm, and in stormy weather is almost as rough as the sea, a circumstance recorded by *Virgil* (*Georg.* ii. 160). The blue water, like that of all the Alpine lakes, is remarkably clear. The *carpione*, or salmon-trout, which attains a weight of 25 lbs., the *trutta*, or trout, 1-1½ lb., the *lagone*, and the *sardene* are excellent fish.

The banks, although inferior in attraction to those of the Lake of *Como*, present a great variety of beautiful landscapes, enhanced by the imposing expanse of the water. The shores of the S. half are flat and well cultivated, but they become bolder between *Capo S. Vigilio* and a point to the N. of *Salò*, where the lake contracts. The vegetation is luxuriant, especially on the more sheltered W. bank. Even the sensitive lemon arrives at maturity here, but the trees require to be carefully covered in winter. This is accomplished with the aid of numerous white pillars of brick, 8-20 ft. in height, erected at regular intervals, and united by transverse beams at the top. The fruit is more bitter and aromatic than that of Sicily, suffers less from carriage, and keeps longer. Price in plentiful seasons 3-4 fr. per hundred, but frequently as high as 10 fr.

**Desenzano** (*Mayer's Hôtel*, R. 2½, B. 1½ fr.; *Posta Vecchia*, both indifferent; *Vittoria*; *Aquila*), a thriving little town with 4000 inhab., at the S.W. angle of the lake, is a railway station (p. 169). Omnibus from the steamboat to the train 50 c., luggage 25 c.

To the E., not quite half-way to *Peschiera* (p. 169), is the narrow promontory of *Sermione*, projecting 3 M. into the lake, which here attains its greatest breadth.

A pleasant excursion may be made thither by boat or by carriage (6 M. from Desenzano), but the road is not recommended to walkers. The fishing village (poor *locanda*) adjoins the handsome ruin of a castle of the Scaligers (p. 185). We then cross the olive-clad height, past the little church of S. Pietro, to (1 M.) the extremity of the peninsula, where we obtain a charming view. On the hill are remains of baths, and on the promontory are relics of a building extending out into the lake, which are said to have belonged to the country house of Catullus, who wrote his poems here ('Sirmio peninsularum insularumque ocellus').

The STEAMBOAT steers near the W. bank, but does not touch at the small villages of *Moniga* and *Manerba*. Opposite the promontory of *S. Vigilio* (p. 180) it next passes the small *Isola di S. Biagio* and the beautiful crescent-shaped *Isola di Garda*, or *dei Frati*, the property of the Marchese Scotti of Bergamo. The latter was fortified by the Italians in 1859, but the works have since been removed. The steamer now steers to the W. and enters the bay of *Salò* (*Gambèro*; *Sirenî*), a delightfully situated town with 3400 inhab., surrounded with terraces of fragrant lemon-groves. The *Monte S. Bartolommeo*, at the foot of which the town lies, affords a charming view, especially by evening light. (Diligence to Brescia, see below.) *Gardone* is the next village; then *Maderno*, on a promontory extending far into the lake, beyond which rises the *Monte Pizzocolo*. Farther on are *Toscolano*, *Cecina*, and *Bogliaco*, with a large country-residence of Count Bettuno. Most of the lemon-gardens belong to members of the Italian noblesse. Then *Gargnano* (\**Cervo*), an important looking place (4000 inhab.) in the midst of lemon and olive plantations, and one of the most attractive points on the lake (diligence twice daily to Brescia by *Salò*, *Gavardo*, and *Rezzata*).

The mountains now become loftier. The small villages of *Muslone*, *Piovere*, *Tignate*, and *Oldese* are almost adjacent. Then *Tremosine*, on the hill, scarcely visible from the lake, to which a steep path ascends on the precipitous and rocky bank. In a bay farther on are seen the white houses of *Limone*, another lemon and olive producing village. The Austrian frontier is passed a little beyond *La Nova*, and a view is soon obtained of the *Fall of the Ponale* (see below).

**Riva.** — ALBERGO TRAFFELLINI AL SOLE D'ORO, beautifully situated on the lake, R. from 80 kr., D. 1½ fl., B. 50, L. and A. 50 kr.; \*GIARDINO, R. 1 fl., D. 1½ fl., B. 35, A. 25 kr.; \*HOTEL KERN, on the lake, pension 3 fl. *Café Andreis*, and *Café Tschurtschenthaler*, both under the arcades on the quay. — Beer in the gardens outside the *Porta S. Marco* and the *Porta S. Michele*.

*Baths* in the lake to the W., beyond the barrack.

*Omnibus* to Mori, see p. 179, starting from the *Café Andreis*.

*Riva*, a busy harbour with 5000 inhab., is charmingly situated at the N. end of the lake, at the base of the precipitous *Monte Giunella*. The *Church of the Minorites*, outside the *Porta S. Michele*, erected in the 16th cent. and adorned with gilding and stucco mouldings, contains several altar-pieces by Guido Reni, Palma Vecchio, and others. The *Parish Church* in the town possesses

several modern pictures and frescoes. The watch-tower of *La Rocca* on the lake, fortified anew since 1850, at present a barrack, and the old *Castello*, high on the mountain to the W., erected by the Scaligers, greatly enhance the picturesqueness of the place. The situation of Riva is sheltered and healthy, the heat of summer being tempered by the lake. Private apartments may be procured on moderate terms. — Luggage is examined at Riva on the arrival and departure of the steamboats by Austrian and Italian officials respectively.

From RIVA TO MORI (p. 49), a station on the Trent and Verona line, omnibus twice daily in 2½ hrs. (fare 65, coupé 75 kr.), two-horse carriage 7½ fl. The road leads through *Torbolo* (= Bertolini; <sup>3</sup>Olivo), a harbour on the N.E. bank of the lake, and then ascends to the left to *Nago*, whence, before entering the fort, a magnificent retrospect of the lake is obtained. The road next traverses a wild and stony mountain ridge, skirts the picturesque little *Lake of Loppio* (928 ft.), and reaches the village of *Loppio*. The village of *Mori* is at some distance from the station.

Excursions. To the *Fall of the Ponale* (2 hrs.). The waterfall itself, which is formed by the Ponale shortly before it flows from the Val di Ledro into the lake, is hardly worth a visit, especially as it is difficult to find a good point of view (best by boat, 2 fl. and fee), but a walk on the new ROAD to the Val di Ledro, which is carried along the rocks of the W. Bank at a considerable height by means of tunnels and cuttings, and commands beautiful views, will repay the traveller (shade in the afternoon). A path to the waterfall diverges from the road to the left at the point where it turns into the Val di Ledro. Limone (p. 178) lies 4½ M. to the S. of the waterfall.

The *Monte Brione* (1224 ft.), a hill between Riva and *Torbolo* (see above). 1 hr. to the N.E., affords a fine survey of the valley and almost the entire lake. The easiest ascent is from the N. side. The small village of *La Grotta*, at the foot of the Monte Brione, 1½ M. from Riva (by S. Alessandro), is a favourite afternoon resort. — Pleasant excursion to the N.W., via *Varrone* (with a waterfall) and *Cologna*, to (4 M.) *Tenno*, with an old castle. The road then traverses richly cultivated uplands, at a considerable height, commanding a succession of views, and leads by *Varignano* to (4½ M.) *Arco* (p. 48).

The *Monte Baldo*, a range 45 M. in length, which separates the Lake of Garda from the valley of the Adige, is best ascended from *Nago*, (see above). The *Allissimo di Nago* (6811 ft.), the summit towards the N. and the most beautiful point, is reached hence in 4½ hrs. (with guide). Extensive panorama, comprising a great portion of Upper Italy, the lake, the valley of the Adige, and the snow-mountains of the Adamello, Presanella, and the Ortler. — The ascent of the *Monte Maggiore*, or *Telegrafo* (6942 ft.), the central point, from *Torri* or *Garda* (p. 180), via *Caprino*, in 7 hrs., is fatiguing.

The *Valle di Ledro* affords another interesting excursion. Beginning of the route the same as to the Fall of the Ponale (see above). The road turns to the W. and enters the green valley. It leads by *Biacesa*, *Brè*, *Barcesine*, the pretty *Lago di Ledro* (2135 ft.), and *Mezzolago* on its N. bank, to (7½ M. from Riva) *Pieve di Ledro* (= Albergo della Torre). A pleasant afternoon's excursion from Riva may be made by taking the diligence at l. 15 as far as the beginning of the Lago di Ledro (about 2½ M. from Pieve), and returning thence on foot (6 M.); fine view by evening light. — At *Bezzeca*, ¾ M. farther, opens the *Val Conzei*, with the villages of (¼ hr.) *Enguiso* and (¼ hr.) *Lenzuno* (thence back to Riva direct, by the *Mte. Tratta* and *Campi*, in 3½ hrs.). From *Bezzeca* the road leads by *Tiarno*, and through the sequestered *Val Ampola*, to (9 M.) *Storo* (Cavallo Bianco) in the *Val Bona*, or *Chiese*, in which, 3 M. higher, lies *Condino* (Torre), the capital of S. Giudicaria.

Beyond *Storo*, and about 1½ M. below the bridge over the Chiese, the

road crosses the *Caffaro* near *Lodrone* (Austrian and Italian frontier), and reaches (1 $\frac{1}{2}$  M.) the **Lago d'Idro**, 6 M. long,  $\frac{1}{2}$  M. broad, the W. bank of which it skirts. Opposite (3 $\frac{1}{4}$  M.) *Anfo*, with the mountain-castle *Rocca d'Anfo*, lies the small village of *Idro*. At (3 M.) *Lavenone*, at the S. end of the lake, begins the picturesque *Val Sabbia*, of which the capital is (3 M.) *Vestone* (Tre Spade). At (3 M.) *Barghe* the road divides; that to the E. leads by *Sabbio*, *Vobarno*, and *Volciano* to (12 M.) *Satò* on the Lago di Garda (p. 178); that to the W. to *Preseglie* and through the *Val Garza* to (15 M.) *Brescia* (p. 169).

About 10 min. after the steamboat (p. 178) has quitted Riva, the fall of the Ponale, mentioned p. 179, comes in view. *Torbote* (p. 179) lies to the left. The steamer now steers S. to **Malcesine** (2000 inhab.), a good harbour on the E. bank, with an old castle of Charlemagne, which was afterwards a robbers' stronghold. Goethe, while sketching this ruin, narrowly escaped being arrested as a spy by the Venetian government. The castle has since been restored. Beyond it is the rock of *Isoletto*, then *Cassone*, and a little farther the small island of *Tremelone*. The next places of importance are *Castello*, *S. Giovanni*, *Castelletto*, *Montagna*, and, somewhat inland, *Torri*. The banks gradually become flatter. The promontory of *San Vigilio*, sheltered from the N. wind by the *Monte Baldo* (p. 179), extends far into the lake, and is the most beautiful point of view on the E. bank. The surrounding hills are planted with vines, olives, and fig-trees. The village of **Garda** (1100 inhab.), beautifully situated in a bay at the influx of the *Tesino*, which descends from the Monte Baldo, gives its name to the lake. The chateau belongs to Count Albertini of Verona. To the S. in the distance is the peninsula of *Sermione* (p. 178). The next places are *Bardolino* (2000 inhab.) with a harbour, *Cisano*, and *Lazise* (2600 inhab.), another harbour.

*Peschiera* (see p. 169), at the efflux of the *Mincio* from the lake, is a station on the Milan and Verona railway. The station (\*Buffet) is on the E. side of the town, not far from the landing place.

---

## V. Venetia.

The N.E. part of Italy, named *IL VENETO* after the ancient *Veneti*, is divided into the nine provinces of *Verona*, *Vicenza*, *Padova*, *Rovigo*, *Venezia*, *Treviso*, *Belluno*, and *Udine*. Its area, 9059 sq. M., is nearly equal to that of Lombardy, while its population of 2,642,837 souls is considerably smaller. The western and larger portion of the country, between the *Mincio* and *Piave*, is indeed about as thickly peopled as the eastern and less prosperous part of Lombardy between the *Adda* and the *Mincio*; but the *Friuli*, or ancient county of *Forum Julii*, the border-land to the E. of the *Piave*, consists of very inferior soil, owing to the debris brought down by the Alpine streams. The *Furlanians*, the poor inhabitants of the *Friuli*, speak a patois of their own.

The *VENETIAN DIALECT* no longer contains traces of the Gallic element like that of the districts from Piedmont to the Romagna, which were once conquered by the Celts. It boasts, however, of having been frequently used by men of letters, as for example by Goldoni in his comedies, and is the softest of all the Italian dialects, the flattening and elision of the consonants being very common. Thus *nerode* for *nipote*, *suar* for *sudare*, *fogo* for *fuoco*, *signor* for *signore*; and another characteristic is the conversion of *g* into *z*, as *zente* for *gente*, *zorno* for *giorno*, *mazore* for *maggiore*. The history of the country has always been influenced by the proximity of the sea, and the peculiar formation of the coast. In the lower part of its course the *Po* differs widely from all the other rivers in Europe. Its fall is very gradual, being for a considerable distance 2 $\frac{3}{4}$  inches only, and latterly little more than  $\frac{1}{4}$  inch per English mile. Towards the end of its course, moreover, it receives numerous tributaries. The result is that the adjacent districts are much exposed to inundations, a danger which has to be averted by the construction of huge dykes; and these works frequently require to be raised, as the bed of the river is constantly rising. The *Po*, together with the *Adige*, *Bacchiglione*, *Brenta*, and other coast rivers, terminate in a vast delta which extends along the whole coast of Venetia. The quantity of alluvial deposit is so great, that the beds of these streams are continually undergoing change and subdivision. Thus the ancient seaport of *Hatria* now lies 15 $\frac{1}{2}$  M. from the coast, and while the *Po* formerly flowed towards the S., it has formed its present embouchure since 1150. The extensive lagoons (*lagune*), separated from the sea by narrow strips of land (*lidi*), and connected with it by outlets, would render the whole coast uninhabitable, were it not for the slight ebb and flow of the tide (mean difference 1 $\frac{1}{2}$  ft.), which is perceptible in the Adriatic, and prevents malarious exhalations. This extensive alluvial territory, which reminds one of Holland, called into activity the ingenuity and enterprise of its inhabitants at an early period, and a temperate and conservative character has thus been imparted to their history.

The *Veneti*, with whose language and nationality we are unacquainted, kept entirely aloof from the immigrating Celtic tribes. The seaports of *Hatria* and *Spina*, at the mouths of the *Po*, carried on a considerable trade at an early period, and several canals on a large scale were constructed as early as B.C. 380. In the 3rd cent. the *Veneti* together with the *Cenomani*, a Celtic tribe which occupied Brescia and Verona, entered into an alliance with *Rome*. While the Romanisation of Lombardy and Piedmont was attended with violent struggles, it was rapidly effected here without opposition. The Roman colony of *Aquileia* was founded as early as 181 B.C., and the boundary of Italy was thus laid down at the point to which it still extends. Owing to its industries, cattle breeding, and agriculture, Venetia prospered greatly under the emperors. *Padua* was the wealthiest town in Italy next to Rome, and was rivalled in W. Europe by Cadiz alone, as it numbered during the reign of Augustus no fewer than 500 citizens of knightly fortune (i. e. upwards of about 4500 l). The city was afterwards destroyed by Attila, and then razed to the ground by the Lombards, and a similar fate befel *Allium*, an important com-




mercial town in the Lagoons, and *Aquileia*, which in ancient times was of a similar importance as the modern Trieste. The Romans sought refuge from their Lombard conquerors in the islands of the Lagoons. Removed from Teutonic influences, and under the protection of the Byzantine Empire, the most famous of mediæval states took its rise here from apparently insignificant beginnings. Its earliest history is involved in obscurity. The first *Dux* or *Doge* is said to have been *Paulucius Anafestus* (d. 716). In 809 the islands warded off an attack of King Pepin, the son of Charlemagne, and virtually threw off the yoke of the Eastern emperors. At this period the inhabitants were crowded together in the islands of *Rivolto*, *Malamocco*, and *Torcello*, which were the most secure. *Rivolto* was selected as the seat of government, and here accordingly the city of **Venice** was founded. *Angelus Participotus* (819) is said to have been the first doge, whose residence occupied the site of the present Palace of the Doges. Situated between the Byzantine and Franconian empires, Venice became a connecting link between the trade of both, and the great depôt of the traffic between the East and the West. In 828 a Venetian fleet brought the body of *St. Mark* to Venice, and thenceforth the Venetians revered him as their tutelary saint, using his emblem, the lion (Rev. iv. 7) as their cognizance, and his name as synonymous with the republic, while their supreme official functionary was styled 'Procurator of St. Mark'. In the interests of her commerce Venice was at length induced to make foreign conquests. These were at first confined to the Istrian and Dalmatian coasts for the purpose of procuring timber and suppressing piracy. The rivalry that sprang up with Genoa during the Crusade led the Venetians to obtain a footing in the Levant, and to establish extensive colonies. At the same time the constitution of the state developed into a rigorous oligarchy, which with terrible impartiality contrived to keep both the nobility and people in check, and effectually to curb the national desire for liberty. In the neighbouring towns the supreme power rested on a foundation altogether different. The republics had been overthrown by the despots, who, supported by mercenary troops and the favour of the lower classes, had founded principalities in the modern sense of the word. Such were the Visconti in *Milan*, the Scala in *Verona*, the Carrara in *Padua*, the Gonzaga in *Mantua*, and the Este in *Ferrara*. The danger of collision with warlike princes, and the support they afforded to every attempt to overthrow the Venetian constitution, led to their own downfall. Venice, having made conquests on the mainland (*terra ferma*) for the sake of her own safety, soon became one of the chief Italian powers, and was thus involved in all the interminable wars caused by the rivalry of the different states. She obtained permanent possession of *Treviso* in 1339, *Vicenza* in 1404, *Padua* and *Verona* in 1405, *Udine* in 1420, *Brescia* in 1426, *Bergamo* in 1428, *Crema* in 1454, and *Rovigo* in 1484. In the market-places of these towns the lion of St. Mark was erected as a token of their subjugation, and Venetian nobles were appointed their governors. The district thus conquered extended to about 13,200 sq. M., besides the Dalmatian possessions (4250 sq. M.) and the settlements in the Levant. *Napoleon* at length overthrew the Republic, which had long been in a tottering condition. On 15th and 16th May, 1797, Venice was occupied by French troops under *Baragney d'Hilliers*, this being the first occasion on which it had ever been captured by an enemy. In the Peace of Campoformio (1797) it was adjudged to *Austria*, but by the Peace of Pressburg in 1805, the Austrians were compelled to cede it to the Kingdom of *Italy*. On the fall of *Napoleon* it was again awarded to *Austria*, to which it belonged down to 1866, when in consequence of the events of that year it was finally incorporated with the Kingdom of *Italy*.

### 32. Verona.

**Arrival.** There are two stations at Verona: (1) The *Stazione Porta Vecova* (Pl. II. 6. 7), the central station for the trains of all the lines, about



Verona



- |     |                                |       |
|-----|--------------------------------|-------|
| 24  | Arena                          | D.4   |
| 25  | Accademia agricolt.            | D.5   |
| 26  | Asenale                        | F.5   |
| 27  | Dogana                         | E.4.3 |
| 28  | Comando Generale               | F.4   |
| 29  | Muséo Lapidario                | C.D.4 |
| 30  | Orto botanico                  | F.3   |
| 31  | Ospitale nuovo milit.          | A.4   |
| 32  | Ospitale civile                | E.4   |
| 33  | Posta delle lettere            | F.4   |
| 34  | Palazzo del Consiglio          | E.3   |
| 35  | - - - della Gran Guardia       | D.4   |
| 36  | - - - della Gran Guardia nuova | D.4   |
| 36½ | Palazzo Rompi                  | F.5   |

- |     |                       |     |
|-----|-----------------------|-----|
| 37  | Teatro Antico         | F.2 |
| 38  | "    Nuovo            | E.3 |
| 38½ | Ristori               | C.4 |
| 39  | della Acad. vecchia   | F.3 |
| 40  | "    Morando          | B.3 |
| 41  | "    Filarmonico      | C.4 |
| 42  | "    della Valle      | C.4 |
| 43  | Ufficio della Polizia | F.3 |
| 44  | "    della Posta      | E.3 |
| 45  | Il Vescovado          | E.2 |

- Alberghi**
- |    |                        |     |
|----|------------------------|-----|
| 46 | Albergo alle due Torri | E.3 |
| 47 | "    Torre di Loro     | E.3 |
| 48 | "    Colomba d'oro     | E.3 |
| 49 | "    S. Lorenzo        | E.3 |





1½ M. to the E. of the Piazza Brà; (2) The *Stazione Porta Nuova* (Pl. B. 6), where the ordinary trains only stop, ¾ M. to the S. of the Piazza Brà. — The traveller about to leave the country should provide himself in good time with *gold* (comp. *Introd.* vii., *Railways*), as the money changers at the station exact an exorbitant premium.

**Hotels.** DUE TORRI (Pl. 46), R. from 3 D. 5. B. 1½, omn. 1-1½ fr. (lately complained of); HÔTEL DE LONDRES (*Torre di Londra*; Pl. 47), D. 5 fr.; HÔTEL RAINER AL GRAN PARIGI, R. from 3 fr. — Italian houses: ALBERGO COLA, with trattoria, prettily situated on the Adige, Riva di S. Lorenzo, in the third narrow street W. of the Porta Borsari, R. 2-3. L. ½ fr., B. 75 c., omnibus 75 c.-1 fr.; COLOMBA D'ORO (Pl. 48), in the street of that name, close to the Piazza Brà, tolerable; ACQUILA NERA, same proprietor; REGINA D'UNGERIA, near the Piazza d'Erbe; ALB. DELLA POSTA, near the post-office; ALB. D'ITALIA, near the Porta Vescovo.

**Restaurants.** *Birreria Bauer al Giardino S. Luca* (with baths), to the S.W. of the Piazza Vittorio Emanuele, on the right, outside the gate; *Trattoria Cola*, and the other Italian inns; *Crespi*, near the Ponte delle Navi (p. 188). — **Cafés.** *Europa* and *Vittorio Emanuele* in the Piazza Brà, where a military band plays every evening. *Caffè Dante*, Piazza de' Signori.

**Fiacres**, called 'Broughams'. Per drive 75 c., per hour 1½ fr., each additional hr. 1 fr. 25 c.; in the evening 30 c. per hr. more. From the station to the town and vice-versà 1 fr. These fares are for 1-2 pers.; for each additional pers. one-third more. — *Omnibus* from the station to the town 30 c.

**Bookseller.** *H. F. Münster*, in the Via Nuova (p. 184).

The **Sights** of Verona may be seen in one day: begin with the *Arena* and *Piazza Brà*, then cross the Adige to the *Palazzo Pompei* (on the way to which is *S. Fermo Maggiore*, p. 188), return by the *Via Leoni* to the *Piazza de' Signori*, with the tombs of the *Scaligers*; see *S. Anastasia*, and the *Cathedral*, and cross the *Ponte di Ferro* to *S. Giorgio*; drive along the *Corso*, from the *Porta Borsari* to the *Porta Stuppa* and *S. Zeno*, and finally to the *Giardino Giusti*.

**Verona** (157 ft.), an ancient town founded by the Gauls, afterwards a Roman colony, the *Bern* of old German traditions, was the residence of the Lombard princes in the middle ages, and afterwards suffered severely from the contests of the Guelphs and Ghibellines, until a happier era dawned under the auspices of the illustrious *Scaligers*. They were followed by *Giugaleazzo Visconti*, through whose widow Verona came into the possession of Venice, to which, with short interruptions, it remained subject down to the end of the Republic. The town, which has a somewhat poverty-stricken appearance, with 60,000 inhab. and a garrison of 6000, situated at the base of the Alps, on the rapid *Adige*, which is crossed by five bridges, is the most important fortress, and next to Venice the most considerable town in Venetia.

In the history of ARCHITECTURE Verona is a place of considerable importance, not only on account of its mediæval buildings, but as the birthplace of *Michele Sammicheli* (1484-1554), the most famous military architect of Upper Italy, who imparted to the palaces some of the features of fortified castles, and of *Fra Giocondo* (1435-1514), one of the most typical masters of the Renaissance, whose works are to be found at Venice, Paris, and Rome. In judging of the Verona palaces, we must bear in mind that it was customary here, as at Genoa and other towns to adorn the façades with paintings. The painted façades of houses near *S. Fermo*, the *Porta Borsari*, *Piazza delle Erbe* (p. 184), the *Palazzo Tedescchi* (p. 188) and others, recall the style of Paduan masters of the 15th cent., and are perhaps traceable to the influence of Mantegna. — The most distinguished Veronese PAINTERS of the 15th cent. were *Vittore Pisano* (*Pisanello*), *Li-*

*berale da Verona*, *Fr. Morone*, and particularly *Girolamo dai Libri* (1472-1555). The artists of a later period, such as *Paolo Cagliari*, surnamed *Veronese* (1532-88), belong more properly to the Venetian school.

The \***Arena** (Pl. 24; D, 4; entrance from the W. side by the arcade No. V; fee 25 c.) bounds on the N.E. side the **Piazza Brà** (*Prædium*), or *Vittorio Emanuele*, the principal square of Verona. This celebrated amphitheatre, probably erected under Diocletian (A. D. 284), is 106 ft. in height, 182 yds. long, 146 yds. wide (the arena itself 80 yds. long, 47 yds. wide), circumference 528 yds. Around the amphitheatre rise 45 tiers of steps, 18 inches in height, 26 inches in width, of grey marble (modern), on which it is calculated that 25,000 spectators could sit, and 70,000 stand. Of the external wall a fragment only, which appears never to have been completed, is still standing. It is an interesting fact that the pillars, which were probably left rough undesignedly, afterwards became a model for the favourite 'rustica' pillars of the Renaissance. The arcades, 72 in number, are let by the town at high rents to traders of every description. In the interior of the Arena a small theatre is usually established. — The *Via Nuova*, terminating near the Arena, and paved with massive blocks of stone is one of the principal thoroughfares of the town, leading N.E. to the *Piazza delle Erbe* (see below).

The S. side of the Brà is bounded by the *Gran Guardia Antica* (Pl. 35; D, 4; now a corn-magazine), or old guard-house, and the *Gran Guardia Nuova* (Pl. 36; D, 4), now the *Municipio*, erected in 1840. To the W., in the arcades of the spacious *Palazzo Guastaverza* (by Saminicheli) are the cafés mentioned at p. 183. — By the *Portone*, or principal gate, is an ancient tower of the Scaligers. The W. corner is occupied by the *Teatro Filarmonico* (Pl. 41; C, 4). In the court towards the Piazza Brà, under the arcades erected by Pompei in 1745, is situated the valuable *Museo Lapidario* (Pl. 29), collected and described by Scipione Maffei, containing Roman, Greek, and Arabic inscriptions, Roman and Greek bas-reliefs and statues, ancient Christian sarcophagi, and a bust of Maffei. The museum is shown by the custodian of the Teatro Filarmonico, who lives in a side-street at the back of the theatre, No. 1.

Several streets lead from the Piazza Brà towards the N. to the *Corso CAVOUR* (Pl. C, D, E, 3), the principal street of the town, in which a number of handsome palaces are situated (see p. 186). In the Corso, about midway, rises the **Porta de' Borsari** (Pl. D, 3), an ancient triumphal arch or town gate, occupying the whole breadth of the street, consisting of two entrance-archways, with two galleries above them, and a façade towards the outside of the town, erected under the Emperor Gallienus in A. D. 265.

The Corso leads to the N.E., straight to the once busy centre of mediæval life. On the right it first reaches the **Piazza delle Erbe** (Pl. E, 3), the fruit and vegetable market, formerly the forum of the Republic, and one of the most picturesque piazzas in Italy. At the upper end of it rises a *Marble Column*, which bore the lion of

St. Mark down to 1797 to indicate the supremacy of the Republic of Venice. Opposite is the *Palazzo Maffei*, now *Trezza*, with a façade overlaid with enrichment, and a curious spiral staircase in the interior. The *Fountain* is adorned with a statue of 'Verona', part of which is ancient. The *Tribuna*, with its canopy supported by four columns, in the centre of the Piazza, was anciently used as a seat of judgment. Many of the surrounding houses are adorned with frescoes in the old Veronese style, recently restored, such as the *Casa Mazzanti* near the column, and the *Casa dei Mercanti* of the 14th cent., adorned with a statue of the Madonna. — With regard to the Via S. Sebastiano and Via Leoni, see p. 188.

Opposite the Casa Mazzanti rises the *Tower of the Municipio*, about 320 ft. in height. A short street to the left of the latter leads to the **\*Piazza dei Signori** (Pl. E, 3), a small square paved with flag-stones, and surrounded by imposing edifices. — Immediately to the right is the former *Municipio*, or *Town Hall*, with an interesting and very picturesque court, founded, according to the inscription, as a *Palazzo della Ragione* in 1183.

In the angle diagonally opposite is situated the *Old Town Hall*, or **\*Palazzo del Consiglio** (Pl. 34), usually called *La Loggia*, erected at the beginning of the 16th cent. by *Fra Giocondo da Verona* (p. 183), and restored in 1873, with coloured and gilt ornaments; above are five statues of celebrated natives of ancient Verona: Cornelius Nepos, Catullus ('Mantua Virgilio gaudet Verona Catullo': *Ovid.* — 'Tantum magna suo debet Verona Catullo, quantum parva suo Mantua Virgilio': *Martial.* Vitruvius, the younger Pliny, and Æmilius Macer, the poet and friend of Virgil.

In the middle of the piazza rises a marble *Statue of Dante*, who, as recorded by the inscriptions on the monument and on the palace adjoining the Loggia at a right angle, found an asylum here with the Scaligers after his banishment from Florence in 1316, by Zanoni, erected in 1865. — Opposite is the *Pal. de' Giureconsulti*, erected in 1263, but altered in the 16th century. A small adjacent side-street contains a picturesque fountain.

The passage opposite the entrance to the Piazza delle Erbe leads direct to the modernised Romanesque church of *S. Maria Antica* (Pl. 11), and the imposing Gothic **\*Tombs of the Scaligers**, or *della Scala* family, who for upwards of a century (1262-1389) were presidents of the republic of Verona. The ladder, which forms their crest, recurs frequently on the elaborately executed railings.

The largest of the monuments, that at the corner of the street, was executed by *Bonino da Campiglione* for *Can Signorio* (d. 1375) during his life-time. It consists of a sarcophagus resting on a pedestal supported by columns of moderate height, over which rises a canopy crowned with an equestrian statue of the prince. On the square columns in the middle are six Christian heroes. in niches higher up are the Christian virtues. On the other side next to the Piazza dei Signori, is the monument of  *Mastino II.* (d. 1351), another sarcophagus with canopy and equestrian statue. Between these two principal monuments are four large *Sarcophagi*, the three first dating from 1311. The last is that of *Can Grande II.*, who was assassinated



in the public streets by his brother Can Signorio in 1359. Over the church-door the sarcophagus and equestrian statue of *Can Grande (Francesco della Scala, d. 1329)*, the patron of Dante; adjoining it, also on the church wall, that of *Giovanni della Scala (d. 1350)*; lastly that of  *Mastino I. (d. 1277)* (the custodian lives in a house to the right of the entrance to the church, fee 30 c.).

In the vicinity, at the E. end of the Corso Cavour, rises \***S. Anastasia** (Pl. 1; F, 3), a fine Gothic church begun about 1261, with a brick façade, a portal subsequently covered with marble, ancient sculptures in the lunette, and a fresco of the 14th century.

The INTERIOR, borne by 12 circular columns, is remarkable for boldness and symmetry of proportion; the vaulting is painted in the late Gothic style. On the two first pillars, as supporters of the basin for consecrated water, are two beggars (*I Gobbi*) in white and grey marble, that on the left executed by *Gabriele Caviari*, father of Paolo Veronese, that on the right by *Aless. Rossi* in 1591. The chapel of the Pellegrini, on the right by the high altar, is adorned with reliefs of the 14th cent., representing the history of Christ from the Nativity to the Resurrection, and contains two monuments of the Pellegrini in red marble. In the choir, to the left, is the monument of General Sarega (1432). The chapels on the right and left of the choir contain good frescoes of the 14th and 15th centuries.

To the left of the church, over a gateway adjoining the small church of *S. Pietro Martire* (Pl. 15), is the dark marble sarcophagus of a Count Castelbarco, and in the gateway three others, the third of which is adorned with a good relief of the Madonna.

The **Cathedral** (Pl. 4; E, 2) is an imposing Gothic structure of the 14th cent., with choir and Romanesque façade of the 12th cent. Behind the columns of the handsome portal are Roland and Oliver, the two paladins of Charlemagne, in half-relief. In the interior, over the 1st altar on the left, is an \*Assumption by *Titian*, and an elegantly wrought roodloft of marble, designed by *Sammicheli*. — The arches of the handsome *Cloisters* rest on double columns of red marble in two stories, one above the other (entrance to the left of the façade, then turn to the left again opposite the side-entrance).

To the N. of the choir rises *S. Giovanni in Fonte*, the ancient Baptistery, of the 12th cent. The adjacent *Vescovado* (Pl. 45) contains the *Biblioteca Capitolare* with its valuable MSS. (palimpsests), among which Niebuhr discovered the Institutions of Gaius.

On the left bank of the Adige, to which the Ponte Garibaldi leads (toll 2 c.), is situated **S. Giorgio in Braida** (Pl. 10; E, 1, 2), completed in 1604 from designs attributed to *Sammicheli*, surmounted by a dome, and containing some admirable pictures.

On the W. wall, over the door, Baptism of Christ, by *Tintoretto*; 1st altar on the left, St. Ursula and her companions, the Saviour above, painted in 1545 by *Franc. Caroto*; 4th altar on the left, Madonna with two saints, God the Father above, three angels with musical instruments below, by *Girolamo dai Libri*; 5th altar on the left, St. Cecilia, by *Moretto*. To the right in the choir the Miracle of the Five Thousand, by *Paolo Farinati*; to the left, the Shower of mannah, by *Fel. Brusasorci*, both painted in 1603. High altar-piece, Martyrdom of St. George, by *P. Veronese* (generally covered).

Following the CORSO CAVOUR (Pl. D, C, 3) from the Porta Borsari (p. 184) in a S.W. direction, we observe on the left, No. 19, the \**Palazzo Bevilacqua* by *Sammicheli*: then on the right, No. 38,

the *Palazzo Portalupi*, and, on the same side, No. 44, the *Palazzo Canossa*, also by *Sammicheli*, but with an attica added in 1770. On the right we then reach the *Castello Vecchio* (Pl. C, 3), the ancient palace of the Scaligers, now an arsenal, connected with the opposite bank of the Adige by a handsome bridge (not accessible) constructed in the 14th century. — The street called *Rigasta S. Zeno* diverges here to the right. (S. Zeno, see below.)

At the end of the W. continuation of the Corso is the *\*Porta Stuppa* (or *Palio*; Pl. A, 4), the finest of the gates of Verona created by *Sammicheli*.

The Via S. Bernardino (Pl. B, 3) leads to the monastery and church of **S. Bernardino** (Pl. 3; entrance from the E. corner, through a pleasing monastery-court; if the church-door is closed, ring in the corner to the left, adjoining the church). To the right of the high altar is the entrance to the beautiful *\*Cappella dei Pettegrini*, an elegant circular structure by *Sammicheli*, with four niches and four arches, borne by columns, some of them spiral, others fluted, and remarkable for the chaste and simple style of its enrichments.

**\*S. Zeno Maggiore** (Pl. 23; B, 2) is a Romanesque church of noble proportions. The nave in its present form was begun in 1139; the choir dates from the 13th cent.; the projecting portal rests on lions of red marble. The church was lately restored.

The PORTAL is embellished with marble reliefs of scriptural subjects executed about 1178, from the creation of woman and the Fall to the Betrayal by Judas and the Crucifixion. The hunting-scene to the right in one of the lower sections is known as the 'Chase of Theodoric', an allusion to his having embraced the heretical Arian doctrines. Then representations from the life of St. Zeno, and of the months, beginning with March. The doors, of the same or a still earlier period, consisting of a number of small brazen plates with reliefs (the oldest very rudely executed), are said to have been presented by Dukes of Cleve (on the Rhine).

The INTERIOR is borne by alternate pillars and columns, and has an open roof. To the left of the entrance is a large ancient vase of porphyry, 28 ft. in circumference. — On the choir screen are statues of Christ and the 12 Apostles, in marble, some of them painted, supposed to be coeval with the reliefs on the portal. — The walls are covered with remains of ancient frescoes; behind those of the 14th cent., which have peeled off at places, are traces of others of the 12th. — The approach to the spacious CRYPT, in accordance with the ancient plan which has been followed in the restoration of the building, occupies the entire width of the church. It contains the tomb of St. Zeno and ancient sculptures and frescoes; the capitals of the 40 columns are mediæval, some of them bearing the name of the sculptor. The steps to the choir on the right are flanked with columns of brown marble, resting on lions and bulls, each in one block. — To the right in the *Choir*, above the crypt, is the very ancient painted marble figure of St. Zeno, Bishop of Verona (about 9th cent.), holding his episcopal staff and (as patron-saint of fishermen) a fishing-rod with a silver fish. — Behind the high altar is a fine picture (covered) by *Mantegna*, in excellent preservation, but unfortunately hung too high. On a throne of stone in the middle of a colonnade sits the Madonna with the Infant Christ, with angels playing on instruments at her side and on the steps. In the left wing are SS. Peter, Paul, John, and Augustine; in the right wing are SS. John the Baptist, Gregory, Laurence, and Benedict. The striking effect of this great work is enhanced by remarkably rich accessories. (The three lower pictures are copies.)

A door in the N. aisle leads to the admirably preserved Cloisters,

with elegant double columns and a projecting structure, restored (according to an old inscription) as early as 1123. Immediately to the right two tombstones are recognised as pertaining to the Scaliger family by the ladder represented on them. — On the S. side of the church is a small disused *Churchyard*, whence a general view of the church with its campanile of 1045 (restored in 1120) is best obtained. At the entrance to a disused Mausoleum, with a sarcophagus and two columns (descent by 12 steps), a stone bears the inscription, '*Pipini Italiae regis, Magni Caroli imperatoris filii piissimi sepulcrum*'. Adjacent is a very large Roman sarcophagus.

We next visit the S. E. QUARTERS of the town. To the S. E. of the Piazza delle Erbe (p. 184) runs the VIA S. SEBASTIANO or *Cappello* (Pl. E, 4), in which a hat over the gateway of a court opposite the Palazzo Sambonifazi is said to indicate the house of Juliet's parents (Capuletti; p. 190). — Farther on, the Via Scala diverges to the right, leading to the church of *S. Maria della Scala* (Pl. 20, E, 4), founded by Can Grande in 1324, and containing the tomb of Scipione Maffei (d. 1755), the learned antiquarian. Adjoining the church is the *Palazzo Tedeschi*, with a painted façade.

The VIA LEONI, the S. prolongation of the Via S. Sebastiano, leads to the Ponte delle Navi. In this street, on the left, at the corner of the Corticella Leoni, and built into the side of a house rises the \**Arco de' Leoni*, the half of a Roman double gateway, coeval with the Porta de' Borsari, but more delicately executed, and bearing an inscription partially preserved.

A little farther is the Gothic church of *S. Fermo Maggiore* (Pl. 6; E, 4), erected at the beginning of the 14th cent. The architecture of the exterior, with its façade of brick, enriched with marble, is worthy of inspection.

The INTERIOR is modernised; beautiful old ceiling in walnut-wood, and remains of good frescoes of the 14th cent. by *Zevio, Fra Martino*, and *Pisanello*, the finest being a Crucifixion over the left side entrance. To the left of the entrance is a Resurrection carved in wood; the chapel adjoining the left transept contains the monument of the physician Girolamo della Torre by *Riccio* (the originals of the bronze reliefs were carried off by the French, and are in the Louvre); in the chapel to the left of the choir a Madonna with saints, by *Franc. Buonsignori* (1484). The Cappella del Sacramento contains (left) an altarpiece by *Caroto*, painted in 1528; above are the Virgin and St. Anna, below are John the Baptist, St. Sebastian, and other saints.

The *Ponte delle Navi* (Pl. E, 4) in the vicinity, which commands a good survey of S. Fermo, was erected to replace a bridge across the Adige, which was destroyed by an inundation in 1757.

Immediately to the right beyond it, at the beginning of the promenade, is the \**Palazzo Pompei alla Vittoria* (Pl. 36<sup>1</sup>/<sub>2</sub>; E, 5), an interesting edifice by *Sammicheli*, presented by the family to the town, and now containing the *Museo Civico* (fee 1 fr.).

On the GROUND FLOOR are several rooms containing casts, antiquities, chiefly from excavations in the old theatre near the Porta Pietra, and fossils from the Monte Bolca; in the 4th, a drawing by *Andrea Mantegna*. — The *Pinacoteca* or picture-gallery, on the first floor, contains works principally of the Veronese school. The first and second rooms contain the *Galleria Bernasconi*, presented to the town by Dr. Bernasconi. 1. Room: 31 *Paolo Veronese*, Baptism of Christ; 50. *Tintoretto*, Portrait of a doge;

52. Madonna and Child with the infant John, attributed to *Titian*; 71. Copy of the Baptism of Christ (original at Dresden) by *Giulio Romano*; 13. *C. Crivelli*, Madonna and angels. — II. Room: (right) 148. *Franc. Buonsignori*, Madonna; 138. (above the door) *Girolamo dai Libri*, Madonna; 147. *Vinc. Catena*, The Magi; 155. *Fr. Francia*, Madonna with two saints; 115. *M. Basaiti*, St. Stephen; 122. *Cima*, Madonna; 113. *Tintoretto*, The plague at Venice; 90. *Vitt. Pisanello*, Madonna and Christ; 87. *Mantegna*, Madonna; 104. *Amberger*, Portrait of the 'Scholar Faith'; 95. Adoration of the Shepherds, attributed to *Raphael*, a charming picture of the Umbrian school; \*94. *Fra Bartolommeo*, Head of Christ; 93. *Correggio*, Head of a child; 79. *B. Montagna*, Two bishops. — III. Room: Four pictures by *Andrea Schiavone*; \*12. *Giovanni Bellini*, Madonna; without number, \*Moretto, Madonna; 182. *Morone*, Madonna; 202. Copy of the picture by *P. Veronese* in S. Giorgio (p. 186). — IV. Room (to the left of the 1st): 252. *Girolamo*, Madonna; 257. *Paolo Veronese*, Entombment; 259. *School of Raphael*, Holy Family; 272. *Franc. Caroto*, Adoration of the Child; \*240. *Paolo Veronese*, Portrait of Gualtieri, 1556. — V. Room: \*293. *Girolamo dai Libri*, Adoration of the Child; 296. *Paolo Moranda*, surnamed *Cavazzola*, Christ and St. Thomas; 307. *Cima*, Madonna and saints; 274. *Paolo Veronese*, Music, a fresco transferred to canvass; 275. *Cavazzola*, Madonna with two saints, 1522; 276. *Girolamo dai Libri*, Madonna and saints, 1530; 278. Same, Madonna and saints in a landscape. — VI. Room: 334. *C. Crivelli*, Madonna and Christ; 331. *Turone*, Altar-piece, of 1360; 339. *Turone*, Scenes from the Old Testament in thirty pictures on a golden ground; 344. *Giacomo Bellini* (father of Giovanni), Large Crucifixion; 347. *Benaglio*, Altar-piece; \*318-320. *Cavazzola*, Passion. — We return hence through the 5th and 6th rooms, and enter (to the right) the — VII. Room: Nothing noteworthy. — VIII. CORRIDOR with engravings, some of them by *Agostino Caracci*, *Rembrandt*, and *Dürer*. — IX., X., XI., and XII. R.: Nothing of importance. — An adjacent room without a number contains two large pictures of scenes from the history of Verona: 220. *P. Farinati*, Battle of the Veronese against Fred. Barbarossa at Vigasi in 1164; 224. *F. Brusasorci*, Victory of the Veronese over the inhabitants of the banks of the Lago di Garda in 849. — XIV., XV., XVI. R.: Nothing important.

Outside the *Porta S. Vittoria* (Pl. F, 5, 6) is the large new *Cimitero*, enclosed by a Doric colonnade, which connects a lofty church with two temples. The summit of the pediment is adorned with a marble group of Faith, Hope, and Charity, by *Spazzi*.

**S. Maria in Organo** (Pl. 12; F, G, 3), situated near the island in the Adige, was erected from designs by *Sammicheli* in 1481; the façade of 1592 is unfinished.

To the right of the entrance: Madonna with saints under a laurel tree, by *Girolamo dai Libri*. The chapel on the right of the choir contains frescoes by *Giulfino*; a wooden \*Candelabrum, by *Fra Giovanni da Verona*, who belonged to the monastery of this church. The \*Choir-stalls in the Choir with intarsia (views of the town above, arabesques below), of 1499, and the reading-desk, are by the same master. The seats in front of the high-altar contain landscapes by *Cavazzola* and *Brusasorci*. Similar works by the same master are in the SACRISTY on the right wall. The left wall is adorned with paintings in a more elaborate style, by *Fra Giovanni*; the ceiling contains frescoes by *Francesco Morone*.

**S. Nazario e Celso** (Pl. 13; G, 4) is built in the Renaissance style, with traces of the Gothic. The Cappella di S. Biagio contains damaged frescoes by *Bart. Montagna* of Vicenza (end of 15th cent.); the two pictures on the 1st altar to the left, representing SS. John the Baptist and Benedictus, Nazarus and Celsus, are by the same master.

A fine \*VIEW of Verona and its environs, the Alps and the distant Apennines, is obtained from the **Giardino Giusti** on the left bank of the Adige (Pl. G, 4; always accessible; ring at a gate on the right; fee 50 c.), containing a few Roman antiquities, but chiefly noted for its numerous and venerable cypresses, some of which are 400-500 years old and 120 ft. in height. The campanili of S. Lucia and S. Massimo are conspicuous.

The view is still finer from the **Castello S. Pietro** (Pl. G, 2); ascent near the *Ponte della Pietra* (p. 183), built by *Fra Giocondo* (permission obtained at the commandant's office at the entrance), the ancient castle of Theodoric the Great, the 'Dietrich of Bern' of German lore. It was entirely remodelled by *Galeazzo Visconti* in 1393, destroyed by the French in 1801, and refortified by the Austrians in 1849. At its base, immediately below the bridge, are the remains of a semicircular antique *Theatre* (Pl. 37), excavated in the court of a private house, and interesting to antiquarians.

Within a closed garden (visitors ring at the gate facing them, 2-3 soldi) in the *Vicolo Franceschine*, a side-street of the *Via Cappuccini* (Pl. D, 6), is situated the suppressed Franciscan Monastery, where a partially restored chapel contains a rude sarcophagus in red Verona marble, called without the slightest authority the *Tomba di Giulietta*, or '*Tomb of Juliet*' (fee 25 c.). The whole scene is prosaic and unattractive. Shakespeare's play of '*Romeo and Juliet*' is founded on events which actually occurred at Verona. 'Escalus, Prince of Verona' was Bartolommeo della Scala (d. 1303). The house of Juliet's parents, see p. 188.

### 33. From Verona to Mantua and Modena.

63 M. RAILWAY in 2 $\frac{1}{3}$ -3 $\frac{3}{4}$  hrs. (fares 11 fr. 85, 8 fr. 45, 6 fr. 5 c.); to Mantua (25 M.) in 1 $\frac{1}{3}$  hr. (fares 5 fr., 3 fr. 65, 2 fr. 60 c.). — This is the most direct line between Germany and Central Italy, and is the route traversed by the express trains to Florence and Rome.

*Verona*, see p. 182. The line traverses a richly cultivated plain, varied occasionally with wood. Fields of rice are passed near Mantua. — 6 M. *Dossobuono*; 10 $\frac{1}{2}$  M. *Villafranca*, with an ancient castle, where the preliminaries of a peace between France and Austria were concluded on 11th July, 1859, after the battle of Solferino. About 5 M. to the N.W. lies *Custoza*, where the Italians were defeated by the Austrians in 1848 and 1866.


14 M. *Mozzecane*; 18 M. *Roverbella*; 22 $\frac{1}{2}$  M. *Sant. Antonio*.

40 M. *Mantua*. The station lies to the N. of the town (a drive of 35 min.); omnibus (1 fr.) and cabs (2 fr.) are in waiting. — Halfway to the town rises the *Citadel of Mantua*, where *Andreas Hofer*, the Tyrolese patriot, was shot by order of Napoleon on 20th Feb., 1810; a block of marble with an inscription has been erected to his memory (his tomb is in the Franciscan church at Innsbruck). — The citadel and the town are connected by the *Argine Mulino* (a bridge constructed in 1257), which divides the lakes, formed here by the Mincio, into the *Lago Superiore* (W.), and the *Lago di Mezzo* (E.).



Mantova.

Mantua.



- |    |                                  |                                |                              |    |   |
|----|----------------------------------|--------------------------------|------------------------------|----|---|
|    | A                                | alla Stazione d Strada ferrata | C                            | D  | E |
| 1  | Academia                         | D4                             | 15 Teatro della Società      | C4 |   |
| 2  | Archivio                         | E3                             | 16 " " Virgiliano            | D2 |   |
| 3  | Camera di Commercio              | D3                             | 17 Torre della Gabbia        | D3 |   |
| 4  | Comman do di Città ed i Fortezza | E4                             | 18 " " del pubblico Orologio | D4 |   |
| 5  | Corte Imperiale                  | D E 3                          | 19. Ufficio della Posta      | C4 |   |
| 6  | Ginnas, Bibliot. Museo Liceo     | D4                             |                              |    |   |
| 7  | Orto botanico                    | A6                             |                              |    |   |
| 8  | Aspedal civile                   | A B 4                          |                              |    |   |
| 9  | " " milit.                       | C 2                            |                              |    |   |
| 10 | Palazza Municipale               | C4                             |                              |    |   |
| 11 | " " del Te                       | E7                             |                              |    |   |
| 12 | " " Vescooile                    | D3                             |                              |    |   |
| 13 | Teatro Regio                     | E3                             |                              |    |   |
| 14 | " " Scientifico                  | D4                             |                              |    |   |

- Chiese**
- |                         |      |
|-------------------------|------|
| a. s. Andrea            | D 34 |
| b. s. Apollonia         | D 56 |
| c. Barbara              | E 3  |
| d. Barnaba              | B 5  |
| e. Cattedrale s. Pietro | D 3  |
| f. s. Egidio            | D 5  |
| g. Maurizio             | B 4  |
| h. Sebastiano           | B 6  |

**Mantua.** — AQUILA d'ORO; CROCE VERDE, or FENICE, R. 2 fr., both in the *Contrada Croce Verde*, in the centre of the town.

*Café Partenope*, opposite the Croce Verde.

*Cab per drive* 50 c., first hr. 1 fr. 50 c., each following  $\frac{1}{2}$  hr. 50 c.

*Mantua*, Ital. *Mantova*, a very ancient town founded by the Etruscans, with 26,700 inhab. (3000 Jews), is a strongly fortified place, bounded on the N.W. by the *Lago Superiore*, on the N.E. by the *Lago di Mezzo*, on the E. by the *Lago Inferiore*, and on the S. and S.W. by marshy land, which in case of a siege is capable of being laid under water.

Mantua is mentioned in ancient times as the home of Virgil, who is said to have been born at the village of *Pietole* (the ancient Andes?), 3 M. to the S.E., but it was not till the middle ages that it became a place of importance. In the conflicts of the Hohenstaufen period the town embraced the cause of the Guelphs. In 1328 the citizens elected *Luigi, Lord of Gonzaga*, as the 'Capitano del Popolo', and to him the town was indebted for its prosperity. The Gonzagas fought successfully against Milan and Venice, and succeeded in extending their territory, while they were the liberal patrons of art and science. In 1530 *Federigo II.* was raised to the rank of duke by Charles V., and in 1536 was invested with the county of Monteferrato (d. 1540); the chief monument of his reign is the *Palazzo del Tè* (p. 194). In 1627, when Charles de Nevers, a member of a French collateral line, took possession of the throne, the Mantuan war of succession broke out, and the Emperor Ferdinand II. declared the fief forfeited. On 15th July, 1630, Mantua was taken by storm and sacked by the Austrians. Although the emperor, being hard pressed by the Swedes, was obliged to conclude a peace in 1631, the town never recovered from this blow. *Carlo IV.*, the last duke, having taken the French side in the Spanish war of succession, was declared an outlaw in 1703, and Monteferrato was awarded to Piedmont, while Mantua was annexed to *Austria*, and afterwards became the chief support of the Imperial domination in Italy. After a long and obstinate defence by General Wurmser, the fortress capitulated to the French on 2nd February 1797. In accordance with the Peace of Villafranca the Austrians retained Mantua, although deprived of the rest of Lombardy, but they were compelled to cede it to Italy in 1866.

Mantua was the scene of the labours of two great RENAISSANCE PAINTERS. One of these was ANDREA MANTEGNA, who was born at Padua in 1431, and entered into the service of Lodovico Gonzaga in 1460. The principal work of his earlier period is preserved in the church of the *Eremitani* at Padua. In the life of his compositions, and in the fidelity of his characters, he rivals the best of his contemporaries, while he surpasses them in accuracy of perspective, and in his refined taste for beauty of landscape. He died at Mantua in 1506. When Raphael's pupils were dispersed after his death, GIULIO ROMANO (1492-1546), the most eminent of them, established himself at Mantua, where he attained so high a reputation as an architect and painter, that Mantua has been called the 'town of Giulio Romano'. In imitation of Raphael's work in the *Farnesina*, he here composed mythological decorative paintings, which, though far inferior to their prototype, are attractive from the richness of the motives and the sensuous magnificence of the composition, and are important owing to the influence which they exercised on later art. *Primaticcio*, and *Niccolò dell' Abbate*, pupils of Giulio Romano who were educated here, were afterwards summoned to Fontainebleau, and thus formed a connecting link between the French and the Italian Renaissance. Giulio Romano's works must also have exercised no slight influence on the style of *Rubens*, who spent several years at Mantua.

The appearance of the town is dull and unattractive, though it contains a number of large palaces. The traffic of the place is chiefly confined to the arcades of the *Contrada Croce Verde* (Pl. C.



4) and the *Piazza delle Erbe* (Pl. D, 4), near S. Andrea. Beyond the latter, in a small piazza in front of the Camera di Commercio (Pl. 3), is a *Statue of Dante*, erected in 1870.

A little farther on is the **PIAZZA S. PIETRO** (Pl. D, 3), in the centre of which rises a monument to the political martyrs of the year 1851. Here are situated the Cathedral, the Palazzo Vescovile (Pl. 12), and, on the right, the former palace of the Gonzagas.

The **Cathedral of S. Pietro** (Pl. e), a church with double aisles, and a transept covered with a dome, and flanked with two rows of chapels, possesses an unpleasing façade and a huge unfinished tower of much earlier origin. The interior was remodelled from designs by *Giulio Romano*. The nave has a fine fretted ceiling. On the left of the passage leading to the \*Cappella dell' Inconornata is a bust of Aut. Capriano, 1574.

The N.E. angle of the piazza is occupied by the old ducal palace of the Gonzagas, now called the \***Corte Reale** (Pl. 5), and partly used as barracks. The building was begun in 1302 by *Guido Buonacolsi*, and was afterwards altered and embellished with frescoes by *Giulio Romano* by order of Federigo II.

The custodian's room (second large gate on the right), the **UFFIZIO DELLA SCALCHERIA**, is adorned with hunting-scenes by pupils of *Giulio Romano*, but the Diana over the chimney-piece is by himself (d. 1546). — On the **UPPER FLOOR** is a large saloon containing portraits of the Gonzagas by *Bibbiena*. Then the **STANZE DELL' IMPERATRICE**, a suite of apartments in which Raphael's tapestry, now at Vienna, was formerly preserved. The **Dining-Room** is adorned with allegorical figures of the rivers and lakes around Mantua; adjoining it is a garden with a casino. The **SALA DELLO ZODIACO**, with allegorical and mythological representations of the signs of the zodiac by *Giulio Romano* (Napoleon I. once slept in this room); then three **STANZE DELL' IMPERATORE**, containing copies of the tapestry formerly here, painted on the walls by *Canepi*. The **PICTURE GALLERY** contains nothing worthy of note; to the left, by the door, a good bust of a Gonzaga by *Bernini*. The so-called **PARADISO** has a charming ceiling. We now pass through several dilapidated rooms into the **STANZA DELL' ILLIADÉ**, with four scenes from the Iliad by *Giulio Romano*. Then the four **STANZE VICEREALI** (named after the viceroy Eugene Beauharnais), with fine ceilings. The **BALL ROOM** contains three ceiling-paintings, Night, Olympus, and Day; the last, and the 5th medallion to the left of it, are by *Giulio Romano*, the rest by his pupils. — A staircase descends to a remote part of the palace containing the **APPARTAMENTO AND SALA DI TROJA**, decorated by *Giulio Romano*, and a dilapidated but handsome gallery (view of the lake), and lastly two small rooms with frescoes in the style of Raphael.

On the N.E. side of the palace is the *R. Teatro di Corte* (Pl. 13). The vaulted passage between the two leads to the Piazza della Fiera, in which rises the **Castello di Corte** (Pl. E, 3), the old castle of the Gonzagas. The church of *S. Barbara* (Pl. c) to the S. also belongs to this imposing mass of buildings.

Part of the castle is now used as **ARCHIVES** (open during office hours only), and part of it was a prison during the Austrian supremacy. Most of the frescoes by *Andrea Mantegna* (1474) which once adorned the rooms, are now obliterated. The **CAMERA DEGLI SPOSI**, a dining-room, contains the family portraits of the Gonzagas, including *Ludovico Gonzaga* with his wife *Barbara* of *Holenzollern*, with a numerous train. At the sides

are mythological scenes, and in the centre an illusive painting, consisting of an apparent opening, at which Cupids and girls are listening.

\***S. Andrea** (Pl. a; C, D, 3, 4), in the Piazza delle Erbe, a church of very imposing proportions, the finest in Mantua, was erected in 1472 from designs by the Florentine *Leon Battista Alberti*, but the dome was not added till 1782. The white marble façade, with its spacious portico, resembles that of an ancient temple; adjoining it is a square tower, built of red brick, and surmounted by an elegant octagonal superstructure with a Gothic spire. The summit affords a good survey.

The INTERIOR, 110 yds. in length, is covered with massive barrel vaulting, the panels of which are partly painted. *1st Chapel* on the right: *Arrivabene*, St. Antony admonishing the tyrant Ezzelino (painted in 1844). At the sides are frescoes representing Hell, Purgatory, and Paradise according to Dante. — *3rd, Cappella S. Longino*: on the left, Sarcophagus with the inscription: 'Longini ejus, qui latus Christi percussit, ossa'. To the right is the sarcophagus of Gregorius of Nazianzus. The frescoes, designed by *Giulio Romano*, represent the Crucifixion; below is Longinus; on the opposite side the finding of the sacred blood. The saint is said to have brought hither some drops of the blood of Christ, which were preserved in an altar (destroyed by Hungarian soldiers in 1848) in the *Crypt*, beneath the high altar. — The RIGHT TRANSEPT contains the monument of Bishop Andreasi (d. 1549), executed in 1551 by *Clementi*, a pupil of Michael Angelo. The swan is the heraldic emblem in the armorial bearings of Mantua. — CHoir, Martyrdom of St. Andrew, a fresco by *Anselmi*, a pupil of Paolo Veronese. In the corner to the left by the high altar is the marble figure of Duke Guglielmo Gonzaga, founder of the church, in a kneeling posture. — LEFT TRANSEPT. Chapel on the left: Monument of Pietro Strozzi, with caryatides, designed by *Giulio Romano* (best seen from the middle of the nave). Another monument with the recumbent figure of a Count Andreasi, was also designed by *G. Romano*. — The first small chapel to the left of the W. portal contains the tomb of the painter Andrea Mantegna (d. 1506), with his bust in bronze. — The frescos on the walls and dome, which exhibit rare harmony of colouring, are of the 18th cent., most of them by *Campi*.

In the vicinity to the N.W. is a very extensive space, planted with trees and bounded by the Lago di Mezzo on the N. (drill-ground), called the PIAZZA VIRGILIANA (Pl. C, D, 2, 3), adorned with a bust of Virgil (p. 191), and containing an arena, the *Teatro Virgiliano* (Pl. 16), which is used for open-air performances on summer evenings. Beyond the theatre, from the parapet towards the Lago di Mezzo, a superb view of the Tyrolese Alps is enjoyed in clear weather.

The *Accademia Virgiliana di Scienze e Belle Arti* (Pl. 1; D, 4) contains frescoes, sculptures, and casts of little value. Behind it is the *Liceo* (Pl. 6; D, 4) with a *Library* (a room of which contains, above the doors, the portraits of the Gonzaga family, and a Trinity, by *Rubens*, cut into two parts) and the **Museum**.

The museum contains some very valuable antiques. Near the entrance, 326. Bust of Euripides and that of an unknown Greek poet, erroneously called Virgil. To the right of the entrance, torso of a Minerva; busts of emperors; 16. Sarcophagus with the myth of Medea; 31. Funeral, an archaic relief; 36. Torso of Venus; 39. Sarcophagus with a battle of the Amazons; 198. in the centre (opposite), Torso of Venus in Greek marble; Bacchic figures on a square pedestal; 69. Relief, perhaps from a Roman triumphal arch; in the centre, opposite, \*176. Sleeping Cupid,

by *Michael Angelo*. In the adjoining room, on the right, the so-called 'seat of Virgil' and inscriptions. We now return to the galleries. Window-wall, 148. Greek cippus; votive feet. Wall on the left, 171. Sarco-phagus with Selene and Endymion; 180. Torso of a gladiator; 187. Large Bacchic relief; Medea. Opposite, \*210. Archaic Apollo; at the end of the galleries, by the window, 276. Roman tomb-relief, father and son. On the side-wall, \*281. Colossal head of Juno; warriors sacrificing, in relief; in the centre, 237. Youthful Mercury.

A short distance hence, immediately beyond the *Porta Pusterla*, the S.W. gate, is situated the \**Palazzo del Tè* (Pl. II; B, 7; contracted from *Tajetto*), erected by *Giulio Romano*, and containing in comparatively small apartments some of that master's largest frescoes. Antechamber, to the right of the entrance, the sun and moon. 1st Room to the left, the favourite horses of Duke Frederick Gonzaga; 2nd Room: myth of Psyche and Bacchanalians; 3rd Room: representation of the zodiac; 4th Room: fall of Phaeton and numerous smaller pictures; then several rooms with beautiful friezes in stucco; fine open loggia; at the back of the latter the celebrated \**Sala de' Giganti*, with the fall of the giants, whose figures are 14 ft. in height.

*Vasari's* interesting description of this room may be freely rendered as follows. — 'Eccentric and talented, Giulio wished to show here what he could do. He accordingly determined to adapt the walls of a corner room in the palace for his painting, and thereby to deceive the human eye as much as possible. After he had given to this part of the palace, which stands on marshy ground, foundations of double the usual height, he caused a large round chamber with thick walls to be built upon them, the four corners outside being strong enough to bear a heavy vaulting. He then caused doors, windows, and chimney-pieces to be erected so much out of the perpendicular, that they really seemed as if they would fall, and after he had built the room in this strange fashion, he began to paint it in the most singular conception imaginable, representing Jupiter hurling his lightnings at the giants'. The execution of these paintings is chiefly due to *Rinaldo Mantovano*.

*Giulio Romano's House*, and the *Palazzo Colloredo*, built by him, are in the *Contrada Larga* (Pl. B, 5).

FROM MANTUA TO CREMONA, see p. 167.


The train crosses the Lago Superiore by a long bridge to the W. of the Argine Mulino (p. 190; view of the Citadel to the left). It reaches the Po at (32 M.) *Borgoforte*, once an important tête-de-pont, the fortifications of which were blown up by the Austrians in 1866, and crosses the river by an iron bridge.

37 M. *Suzzara*; 42 M. *Reggiolo-Gonzaga*.

About 6 M. to the W., on the road from Mantua to Reggiolo, lies *Gua-stalla (Pasta)*, a small town not far from the Po, with 9500 inhab., which in the 16th cent. gave its name to a principality of the Gonzagas, Dukes of Mantua. These princes became extinct in 1746, and their territory fell to Parma. In the market-place is the bronze Statue of Ferdinand I. Gonzaga (d. 1557 at Brussels), by *Leone Leoni*. — At about the same distance from the station, to the E., on the old road from Verona to Bologna, is situated *Mirandóla*, once the capital of a duchy which belonged to the *Pico* family, a town with broad streets and picturesque, antiquated buildings. It was originally under the jurisdiction of the abbey of *Nonantola* and







|                                             |       |                                     |       |                                       |       |
|---------------------------------------------|-------|-------------------------------------|-------|---------------------------------------|-------|
| 1. <i>Insediamento Vicariale</i>            | D 3   | 30. <i>Cimitero</i>                 | F 1   | 14. <i>Vico</i>                       | E 3 4 |
| 2. <i>Rivera Nazionale</i>                  | C 3   | 31. <i>Vallaggio Cavallotti</i>     | C 3   | 15. <i>Vico Caccotti</i>              | D 3   |
| 3. <i>Palazzo</i>                           | D 3   | 32. <i>Piano inglesi</i>            | C D 2 | 16. <i>Vico Bassino</i>               | D 3   |
| 4. <i>Palazzo di Commercio</i>              | B 3   | 33. <i>Inti ora Piodi</i>           | D 4   | 17. <i>Prefettura/Loggia del Duca</i> | D 3   |
| 5. <i>Casa Federale</i>                     | F 5   | 34. <i>Barbarano</i>                | D 4   | 18. <i>Barbato Piacere</i>            | D 3   |
| 6. <i>Casa Santi</i>                        | F 4 5 | 35. <i>Barbarano</i>                | C 3   | 19. <i>Barbarano</i>                  | D 3   |
| 7. <i>Milan Vassari</i>                     | E 4   | 36. <i>Barbarano</i>                | D 3 4 | 20. <i>Barbarano</i>                  | D 3   |
| 8. <i>di Polladio</i>                       | E 3   | 37. <i>Capidoglio</i>               | D 3 4 | 21. <i>Barbarano</i>                  | D 3   |
| 9. <i>Sabri</i>                             | D E 3 | 38. <i>Capra via Rai</i>            | C D 3 | 22. <i>Barbarano</i>                  | D 4   |
| 10. <i>Duomo/Annosi di S. Maria Vergine</i> | D 4   | 39. <i>Chiosgati/Livorno (Vico)</i> | E 3 4 | 23. <i>Barbarano</i>                  | D 4   |
| 11. <i>S. Feltrina e S. Silvestro</i>       | E 5   | 40. <i>di Gavigli/Basilica</i>      | D 3 4 | 24. <i>Barbarano</i>                  | D 4   |
| 12. <i>S. Teonina</i>                       | E 3   | 41. <i>Carabinieri</i>              | E 3 4 | 25. <i>Barbarano</i>                  | D 4   |
| 13. <i>S. Croce</i>                         | B 2   | 42. <i>Falco</i>                    | D 3 4 | 26. <i>Barbarano</i>                  | D 4   |
| 14. <i>S. Faustino</i>                      | E 3   | 43. <i>Laschi</i>                   | D 2   | 27. <i>Barbarano</i>                  | C 4   |
|                                             |       |                                     | C D 4 | 28. <i>Barbarano</i>                  |       |
|                                             |       |                                     |       | 29. <i>Barbarano</i>                  |       |



the Countess Matilda, and after many vicissitudes came into possession of the Counts of Pico, who retained their supremacy for upwards of three centuries. Count Giovanni Pico (1463-94) was remarkable for his ability and learning. Alexander I. (1619) was the first of the family who bore the title of Duke of Mirandöla and Concordia. Francesco Maria, the last duke, sold his dominions to Modena in 1710. The old *Palace* of the dukes, the *Cathedral*, and the church of *Gesù* should be visited.

46 M. *Rolo-Noni*; 53½ M. *Carpi*, with 5000 inhab., possessing a Cathedral attributed to Bramante, an old castle, a modern palace, and broad streets.

58 M. *Soliera*; 65 M. *Modena* (p. 260).

### 34. From Verona to Venice. Vicenza.

72 M. RAILWAY in 3-5 hrs. (fares 14 fr. 30, 10 fr. 40, 7 fr. 45 c.). Finest views generally to the left.

*Verona*, see p. 182. The train crosses the *Adige*, and traverses an extremely fertile district at the foot of the Alps, covered with vineyards, mulberry trees, and fields of maize, and intersected with irrigation trenches.

Near *S. Michèle*, on the left, stands the pinnacled castle of *Montorio*, formerly the property of the Scaliger family (p. 185). — 4 M. *S. Martino*. The mineral springs of (7½ M.) *Caldiero*, which attract many visitors, were known to the Romans. *Villanuova*, with the castle of *Soave*, once belonging to the Scaligers, on the height to the left, presents a good picture of a mediæval fortified town.

13 M. *S. Bonifacio*. *Arcöle*, 3½ M. to the S., was the scene of the battle of 15th-17th Nov., 1796, between the Austrians and the French under Bonaparte, Masséna, Augereau, and Lannes. — 16 M. *Lonigo*; the village lies 4½ M. S.E., at the W. base of the *Monti Berici*, a chain of volcanic, wooded hills, between which and the spurs of the Alps the train now runs to Vicenza. — 20 M. *Montebello*. Beautiful view towards the mountains; the handsome chateau belongs to Count Arrighi. To the left, on the hill, the castles of the *Montecchi*; then stat. *Tavernelle*.

30 M. **Vicenza.** — HÔTEL DE LA VILLE (*Albergo Reale*; Pl. a), in the Corso Principe Umberto, near the Porta Castello, R. from 2 fr.; ROMA, opposite, with a beer-garden; STELLA D'ORO, in the Corso; DUE MORI E GRAN PARIGI, good cuisine; AI TRE GAROFANI, both in the Contrada delle Due Ruote, a side-street of the Corso.

*Caffè Principe Umberto* and *Caffè Nazionale*, in the Corso; *Garibaldi*, Piazza de' Signori; *Beibay Restaurant*.

*Vicenza*, the *Vicetia* of the ancients, the capital of a province, with 27,000 inhab., lies at the N. base of the *Monti Berici* (p. 198), on both sides of the *Bacchiglione*, near its confluence with the *Retrone*. Though the houses for the most part are crowded, the town possesses many interesting palaces, to which half a day may profitably be devoted.

Vicenza, like all larger towns of N. Italy, boasted in the 15th cent. of a SCHOOL OF PAINTING, which, though it was influenced by Mantegna,



and never produced masters of the highest rank, yielded results of considerable importance. The earliest master of note was *Giovanni Speranza*, who, however, was soon surpassed by *Barlotomæo Montagna* (who flourished here in 1484-1523). The gallery and the churches (the Cathedral, S. Corona, and S. Lorenzo) of Vicenza contain works by the latter, and he is represented at Padua and Verona also. His compositions are strongly realistic, and he shows a predilection for muscular figures, and for colouring of a rich brownish tint. His drapery is ungraceful, but, like that of Dürer, boldly defined. His son, *Benedetto Montagna*, was unimportant, but his contemporary *Giovanni Buonconsiglio* (d. 1530), a follower of Antonello da Messina, has produced some pleasing works. In the 16th cent. Vicenza lost its importance in the history of painting, but attained a high reputation in the province of ARCHITECTURE, having given birth to *Andrea Palladio* (1518-1560), the last great architect of the Renaissance, the chief sphere of whose operations was his native town. By his study of the antique in Rome he was enabled to effect a revival of what may be termed the ancient language of forms, and he made it his endeavour to exhibit in his buildings the organic connection between the different members. The chief characteristic of his school consists in a studious adherence to impressive simplicity of form, and a very sparing indulgence in the lavish enrichments in which the early Renaissance was too apt to revel. His finest churches are at Venice, but his most numerous palaces are at Vicenza, to which they impart a uniform and handsome appearance.

The town is entered by the W. gate, the *Porta del Castello* (Pl. C, 4). Immediately by the entrance, on the right, is the *Palazzo Gusano* (now Hôtel de la Ville); adjacent, to the right, in the S.W. angle of the Piazza Castello is the *Casa del Diavolo* (*Pal. Giulio-Porta*), a large unfinished palace by Palladio. We next follow the long *Corso Principe Umberto*. On the left the new church of *S. Filippo Neri* (Pl. 16). — A short cross-street opposite, on the right, leads to the *Duomo* (Pl. 10; D, 4), consisting of a broad and low nave with wide vaulted arches, the aisles having been converted into chapels, a choir considerably raised above the rest of the church and covered with a dome, and a crypt below it. To the left in the piazza is the *Vescovado* or episcopal palace, the court of which to the left contains beautiful, but uncompleted arcades. Opposite to it is the *Casino*.

The Via Garibaldi, or the short Contrada del Monte, to the right of the Corso (opposite which is the Contrada Porto with numerous palaces), leads to the handsome PIAZZA DE' SIGNORI, with two columns of the Venetian period. Here rises the \**Palazzo del Consiglio*, or *Basilica* (Pl. 40; D, 3, 4), with a double series of grand and beautiful open arcades, the lower with Doric, the upper with Ionic columns, surrounding the *Palazzo della Ragione* (town-hall). These arcades, begun in 1549, are one of Palladio's earliest works. The lofty and slender red tower is of later date; adjacent is the *Tribunale*. — Opposite the Basilica is the unfinished *Loggia del Delegato*, or *Palazzo Prefettizio* (Pl. 47), also by Palladio (1571), adjacent to which is the *Monte di Pietà*. In the Piazza, near the Basilica, stands a good *Statue of Palladio* in marble, by *Gajassi*, erected in 1859.

On the left, at the E. end of the Corso, is the small *Casa di Palladio* (Pl. 8; E, 3), the façade of which was once painted; then to the right, in the Piazza *Vittorio Emanuele*, the —

\***Museo Civico** (Pl. 39; E, 3), established in the *Palazzo Chiericati*, one of Palladio's finest edifices, which was seriously injured in 1848, but restored in accordance with the original plan in 1855 (open daily 9-5, 1/2 fr.).

On the **GROUND FLOOR**, Roman antiquities from an ancient theatre, among which two female statues only deserve mention.—The **UPPER FLOOR** contains the '**Pinacoteca**' (the names attached to the pictures are not always reliable). Ante-chamber: 2. *Jac. da Ponte*, Senators kneeling before the Madonna; 38. *Girol. dal Toso*, Madonna with SS. Catharine and Apollonia. The cabinets contain ancient terracottas and bronzes, medieval coins, etc., and the shoes worn by the Doge of Venice on the occasion of his nuptials with the sea (p. 220). — I. Room: *Titian* (or rather by an imitator), 37. Marriage of St. Catharine; 48, and 8. Madonna with Christ. — II. Room: 54. *Cima da Conegliano*, Madonna with St. Jerome and John the Baptist (May, 1489); 57. *Campagnola*, Holy Family in a landscape; 15. *School of Bellini* (with a spurious inscription), Madonna; 28. *Marco Palmezzano*, Pietà. — III. Room: 14. *Cima da Conegliano* (or *Andr. del Castagno?*), Angel of the Last Judgment; 1. *German School*, Crucifixion (comp. No. 315 in the Academy at Venice); 2. *Bernardino da Murano*, Madonna enthroned and four saints. — IV. Room: *Bart. Montagna*, 2. Madonna enthroned, with four saints and three angels; 3. Nativity of Christ; 8. Presentation in the temple; 18. Madonna enthroned, with St. Jerome and John the Baptist; 20. *Buonconsiglio*, Pietà. — V. Room. Portraits: 7. by *Gentile Bellini*; 24. by *Vitt. Carpaccio*. — The following rooms contain engravings. — Returning to the ante-room, we may now visit two rooms with pictures of inferior value, then two rooms with coins, and one room with drawings and reminiscences of Palladio. — The Natural History Collection contains some fine fossils: a fish, a palm, a crocodile, etc., most of them found in the neighbourhood of Vicenza.

In the vicinity is the \***Teatro Olimpico** (Pl. 51; E, 3; fee 1/2 fr.), designed by Palladio, but not completed till 1584, after his death. It was inaugurated by the performance of the 'Œdipus Tyrannus' of Sophocles. Palladio is said to have adhered to the directions given by Vitruvius with regard to the construction of ancient theatres, but the result differs materially from what would have been anticipated. The perspective of the stage is very remarkable; it is closed by a façade adorned with statues, through three doors in which a glimpse of the distant landscape is obtained. The original orchestra in front of the stage is 5 ft. below the present wooden floor.

Besides the above mentioned, the following structures of Palladio may also be noticed: *Palazzo Porto-Barbarano* (Pl. 34; D, 3), *Tiene* (Pl. 48; D, 3), *Valmaramo* (Pl. 49; D, 3), *Porto Colleoni* (Pl. 45), and the *Rotonda* (see below).

The church of **S. Corona** (Pl. 12; E, 3), a brick edifice with plain Lombard façade, contains a large \*Baptism of Christ by *G. Bellini* (3rd altar to the left), an Adoration of the Magi by *P. Veronese*, and a handsome monument in a chapel to the right of the choir. — **S. Lorenzo** (Pl. 19; C, 3), in the Contrada di S. Lorenzo, has a Gothic façade which deserves notice, and contains the tomb of *B. Montagna* (p. 196), by whom the high altar-piece, representing SS. Lorenzo and Vincenzo, was painted. — **S. Stefano** (Pl. 29; D, 3) contains, over the 3rd altar to the left, a large

\*altar-piece by *Palma Vecchio*, the Madonna with SS. Lucia and Vincent.

A walk to the pilgrimage-church of Madonna del Monte on the MONTE BERICO is recommended in the morning before the heat of the day, or in the afternoon when the arcades afford shade. The route is either through the Porta S. Giuseppe (before passing through which the \*Ponte S. Michele, Pl. D, E, 4, crossing the Retrone, by Palladio, is seen on the right), or immediately to the right from the railway-station, past the *Villa Karolyi* (Pl. D, E, 5) and across the railway, to the arcade leading to the church, a passage resting on 180 pillars, and 715 yds. in length, which was sharply contested in 1848 by Italian irregular troops, who had fortified the hill with its villas, and the Austrians. To the left, beyond a bend in the arcade, a view is obtained of Palladio's Villa Rotonda. The church of the **Madonna del Monte** (Pl. 24; D, 6, 7) is in the form of a Greek cross with a dome. The present left transept was the original church, erected in 1428, and adorned with pictures by *Montagna*. The old refectory of the monastery (shown by the sacristan) contains the Banquet of Gregory the Great by *Paolo Veronese*, which was entirely torn to pieces in 1848, but has been restored with the aid of the copy in the Pinacoteca. Behind the church is a monument to those who fell here in 1848; to the right an *Italia Liberata* dedicated to them by the municipio of Vicenza. Pleasant view hence (tolerable tavern).

On the hill of S. Sebastiano, at the E. base of Monte Berico (not visible from the road thither), 1½ M. from the town, is situated the celebrated \***Rotonda**, or *Villa Rotonda Palladiana* (Pl. G, 7) of the Marchesi Capra, a square building with an Ionic colonnade, surmounted by a pediment on each of the four sides. In the centre is a circular hall with a dome.

The *Cimetero* (Pl. F, 1) contains the grave of Palladio (d. 1580).

The chalybeate *Baths of Recoaro* (Inn of Domenico Trettenero), about 25 M. N.W. of Vicenza (by carr. in 4 hrs.; carr. with one horse 12, with two horses 20 fr.), and 10 M. to the W. of Schio, are picturesquely situated and much frequented, especially in July and August.

A BRANCH-LINE, recently opened, runs from Vicenza to the N. to *Malo*, *Schio* (22 M.; a wool manufacturing place), and *Tiene*. From Schio to Roveredo, see p. 49; Recoaro, to the left of the road, see above.

*Poiana* is the only station between Vicenza and Padua. Country flat. To the S. in the distance, the Monti Euganei (p. 263).

49 M. *Padua*, see below.

To the left, as the train proceeds, the Tyrolese Alps are perceived in the distance. Near stat. *Ponte di Brenta* the line crosses the *Brenta*; at stat. *Dolo* a lofty, slender campanile; at (61 M.) stat. *Marano* an arm of the Brenta is crossed. From (66 M.) *Mestre* the line to Trieste by Udine diverges to the N. (R. 37). *Venice*, with its dark blue line of towers and churches rising from the sea, now gradually comes into view. The islands with their groups of






# PADOVA.

I:22.500  
 0 100 200 300 400 500  
 Km 1/2 1 1 1/2 2

## Chiese Principali

|    |                                      |        |                        |      |
|----|--------------------------------------|--------|------------------------|------|
| 1  | S. Antonio                           | D.4.   | 13 S. Francesco        | E.4. |
| 2  | S. Annunziati<br>(Madonna dell'Arca) | G.4.   | 14 S. Gaetano          | F.4. |
| 3  | Battistero                           | E.2.   | 15 S. Giorgio          | D.4. |
| 4  | S. Benedetto                         | F.1.   | 16 Giustina            | C.4. |
| 5  | S. Cassiano                          | E.3.   | 17 S. Lucia            | E.3. |
| 6  | S.M. del Carmine                     | G.3.   | 18 S. Maria in Fauvo   | D.3. |
| 7  | S. Caterina                          | F.5.   | 19 S. Massimo          | E.7. |
| 8  | S. Croce                             | A.2.3. | 20 S. Michele          | D.2. |
| 9  | Cappuccini                           | A.2.   | 21 Ogni-Santi          | F.7. |
| 10 | Dimesse                              | C.2.   | 22 i Servi di S. Maria | E.3. |
| 11 | Duomo                                | E.2.   | 23 S. Sofia            | F.5. |
| 12 | Eremitani                            | F.4.   | 24 Scuola del Carmine  | G.3. |
|    |                                      |        | 25 " " Santo           | D.4. |



**Alberghi:**

- a. Stella d'Oro F.3.
- b. Croce d'Oro F.4.
- c. Aquila Nera F.3.
- d. Aquila d'Oro D.4.
- e. Caffè Pedrocchi E.F.3.

- 26 Arena G.4.
- 27 Biblioteca dell'Università E.2.
- 28 Caffè Pedrocchi E.3.
- 29 Casa degli Invalidi C.4.
- 30 Caserme D.I. F.1.B.4.
- 31 Delegazione E.4.
- 32 Orto Botanico C.4.
- 33 " Agrario C.3.
- 34 Ospitale Civile D.E.5.
- 35 " militare G.H.2.
- 36 Polizia E.F.2.
- 37 Pal. della Ragione E.3.
- 38 " del Capitano F.2.3.
- 39 " del Podesta (Chimico) E.3.
- 40 delle Logge C.3.
- 41 Seminario D.3.
- 42 La Specola D.2.
- 43 Teatro Nuovo F.2.
- 44 " Concordi F.3.
- 45 " Diurno (Garibaldi) E.A.
- 46 S. Lucia F.3.
- 47 Università E.4.
- 48 Uffizio della Posta E.F.4.
- 49 Pinacoteca, Museo, Bibl. com. D.4.



houses appear to float in the water. The line passes *Fort Malghera* and two large barracks on the left, and reaches the immense *Bridge*, (222 arches, length  $2\frac{1}{3}$  M., breadth 28 ft.), by which the train crosses the *Lagune* in 8 min. and reaches the station of ( $71\frac{1}{2}$  M.) *Venice* (see p. 204).

### 35. Padua, Ital. *Padova*, Lat. *Patavium*.

**Hotels.** \*HÔTEL FANTI STELLA D'ORO (Pl. a), in the Piazza dei Noti, now Garibaldi, R. from 3, B.  $1\frac{1}{2}$ , D. 5, L. and A.  $1\frac{3}{4}$  fr.; \*CROCE D'ORO (Pl. b), in the Piazza Biade, now Cavour, with baths, R. and L.  $2\frac{1}{2}$  fr., good cuisine, and moderate charges; AQUILA NERA (Pl. c) in the same piazza and belonging to the same proprietor, opposite Café Pedrocchi; DUE CROCI BIANCHE, opposite S. Antonio; ALBERGO DEL SOLE D'ORO, Via S. Matteo 1150, to the E. of the Via S. Fermo (Pl. F, 3), unpretending.

**Cafés.** \**Pedrocchi* (Pl. 28; E, F, 4), opposite the University, an imposing edifice with halls and columns of marble; \**Vittoria*, in the Piazza Unità d'Italia (or de' Signori). — **Restaurants.** *Gasparotto*, at the back of the Café Pedrocchi; *Birreria di Franc. Stoppato*, Via Eremitani.

**Cabs.** \**Broughams* are those with one horse: to or from the station 1 fr., luggage 40 c.,  $\frac{1}{2}$  hr.  $1\frac{1}{2}$  fr., 1 hr. 2 fr., drive in the town 50 c., at night 25 c. more. *Omnibuses* from the hotels meet each train.

**Sights.** The following walk is recommended. Proceed straight through the Porta Codalunga (Pl. G, H, 3), then turn to the left past the church of *I Carmini* (\**Scuola* adjacent) to the Ponte Molino and the Strada Maggiore, follow the latter to the Piazza de' Signori (or Unità d'Italia), turn into the Piazza dei Frutti to the left, pass through the Palazzo della Ragione to the Piazza delle Erbe, see the Café Pedrocchi on the left, turn to the right to the Strada di S. Lorenzo and (where there is a direction 'al Santo') again to the right into the Selciato di S. Antonio leading to the \**Santo* (*Scuola*, S. Giorgio, Museo Civico); then back to the Café Pedrocchi, pass through it, and cross the Piazza Biade and Piazza Noti to the right to the \**Eremitani* and \**S. Annunziata*.

*Padua*, the capital of a province, with 44,600 inhab., situated on the *Bacchiglione* which flows through it in several branches, is a quiet place, occupying an extensive area. Its narrow streets and arcades are interspersed with spacious gardens. The town is now a place of some commercial importance.

Padua traces its origin to Antenor, the mythical King of Troy, and brother of Priam, and in the reign of Augustus was the wealthiest town in Upper Italy. At a later period all the ancient monuments were destroyed during the immigration of the barbarian hordes. In the middle ages the town took the part of the Guelphs, and in 1318 appointed *Jacopo da Carrara* to the Signoria. The princes of this family were much harassed by the princes of Verona and the republic of Venice, and were at length obliged to succumb in 1405, when the town was annexed to Venetia. The *University*, founded by the Emperor Frederick II. in 1238, rendered Padua a very famous seat of learning throughout the whole of the middle ages.

In the HISTORY OF ART Padua is also a place of importance, its reputation as the great focus of Italian science having attracted artists from many other places. Thus the Florentine masters *Giotto*, *Donatello*, *F. Lippi*, and *Uccelli*, found abundant occupation here. The school of art founded here by *Squarcione* in the first half of the 15th cent. exhibits a strange bias towards scholastic elements. Squarcione, though not himself an artist, having made a valuable collection of works of art during his travels, caused a number of young artists to make drawings from these models.



The greatest Paduan master was *Andrea Mantegna* (p. 191), and the school exercised no inconsiderable influence on that of Venice. The austere style peculiar to the Paduan pictures is perhaps due to the doctrinal mode in which the artists were instructed, and to their predilection for richness of decoration, for which Squarcione's collection doubtless supplied abundant models.

\***S. Antonio** (Pl. 1; D, 4), the Basilica of St. Anthony of Padua (d. 1231; a contemporary of St. Francis of Assisi), commonly known as '*Il Santo*', is supposed to have been designed by Niccolò Pisano in 1237, but was not begun till 1256. The principal part of the church was completed in 1307, the remainder not before 1475 (when the domes were raised); the whole was restored in 1749 after a fire. This vast structure with its seven domes is larger than S. Marco at Venice. Over the portal of the façade, which is 117 ft. in width, stands a statue of the saint; in the lunette Madonna with SS. Bernardino and Antonio, a fresco by *Mantegna*. The church is 100 yds. in length, 49 yds. in width across the transepts, and 123 ft. high in the centre. The nave and aisles are supported by twelve pillars; the semicircular choir contains eight clustered columns and a series of eight chapels; at the back of the choir is the Santuario, in the 'baroque' style, containing the treasury of St. Antony.

The **Interior**, now whitewashed, was probably once covered with frescoes.

At the entrance, in the nave on the right and left, are two handsome benetiers, with statuettes of St. John the Baptist and Christ, dating from the beginning of the 16th cent.

**RIGHT AISLE.** By the 1st pillar a <sup>2</sup>Madonna in Trono with SS. Peter, Paul, Bernard, and Anthony, an altar-piece by *Antonio Roselli* of Bergamo.

— **1st CHAPEL:** Altar with reliefs in bronze by *Donatello*, representing the miracles of St. Anthony; on the left the sarcophagus of General Gattamelata (p. 201), and on the right, that of his son.

**RIGHT TRANSEPT.** <sup>2</sup>*Cappella S. Felice*, with frescoes from the history of Christ and St. James, by *Allighieri da Zevio* and *Jac. d'Avanzo*, painted in 1376, and restored in 1773, also architecturally interesting.

**LEFT TRANSEPT.** <sup>3</sup>*Cappella del Santo*, designed by *Sansovino*; the façade has four columns and two elegant corner pillars adorned with reliefs by *Matteo* and *Tommaso Garri*; between the five arches are the Evangelists. The walls are embellished with nine <sup>4</sup>relics of the 16th cent., representing scenes from the life of St. Anthony: (beginning to the left of the altar) <sup>1</sup> Ordination of St. Anthony, by *Antonio Minelli* (1512); <sup>2</sup> Resuscitation of a murdered woman, by *Giovanni Maria Padovano*; <sup>3</sup> Resuscitation of a youth, by *Girolamo Campagna*; <sup>4</sup> A suicide surrounded by women, by *Sansovino*; <sup>5</sup> Resuscitation of a child, begun by *Dunese Cattaneo*, and completed by *Campagna*; <sup>6</sup> *Tullio Lombardo*, Discovery of a stone in the corpse of a miser instead of a heart (1525); <sup>7</sup> *Tullio Lombardo*, Cure of a broken leg; <sup>8</sup> Miracle with a glass, begun by *Padovano*, and finished by *Stella*; <sup>9</sup> St. Anthony causes a child to bear testimony in favour of its mother, by *Antonio Lombardo*. — The bones of the saint repose beneath the altar, which is also adorned with many votive tablets. Two magnificent silver candelabra, borne by angels in marble. — On the N. side of the choir is the *Cappella del B. Luca Belludi*, a pupil of S. Anthony, with frescoes representing the history of St. Philip and St. James the Less, painted by *Giov. and Ant. Padovano* in 1382, and restored in 1786; the walls are covered with numerous votive paintings.

**LEFT AISLE.** Large monument of the Venetian Admiral *Caterino Cornelio* (d. 1674), with two figures as supporters, two prisoners in fetters,

and the life-size statue of the admiral by *Giusto le Curti*; \*Monument of *Antonio de' Roycellis* (d. 1466), of an architectural character; by the last pillar (1st from the W. portal) the monument of Count *Stico*; opposite to it is the last altar, that of St. Stanislaus, with a vault which once belonged to the kingdom of Poland; adjacent to it is a relief by *Luigi Ferrari* to the memory of the Princess *Jablonowska* (d. 1846).

In the CHURCH are twelve reliefs in bronze, representing scenes from the Old Testament, most of them executed by *Vellano*, a pupil of Donatello, at the end of the 15th cent. The features of the full-length figure of St. Anthony are said to be faithfully represented. The reliefs on the altar and the symbols of the four evangelists on the right and left are by *Donatello*. Adjacent to the altar is a bronze \*Candelabrum, 11½ ft. in height, by *Andrea Riccio*, adorned with a variety of Christian and heathen representations (1507). The Crucifix in bronze, with the Virgin and the tutelary saints of Padua, is by *Donatello*; the marble work is attributed to *Girolamo Campagna*.

NAVE. By the 2nd pillar on the left the \*Monument of *Alessandro Contarini* (d. 1553), General of the republic of Venice, with six slaves as supporters. By the opposite pillar (2nd on the right) is the simple and chaste monument of *Cardinal Bembo* (d. 1547); by the 4th pillar on the left the monument of the Venetian Admiral *Hieronymus Michael* (d. 1557).

The CLOISTERS, entered from the S. aisle (several monuments and frescoes in the style of Giotto in the passage), with their wide and lofty pointed arches, contain a number of ancient tombstones.

The SANCTUARY, added to the church in 1690, contains a valuable collection of admirable \**Goldsmith's Work* of the 15th and 16th centuries, including the marshal's baton of Gattamelata, a reliquary with the tongue of St. Anthony, a Gothic censer, and a credence plate.

The \***Scuola del Santo** (Pl. 25; D. 4), adjoining the church, the assembly-hall of the brotherhood of St. Anthony, is adorned with seventeen frescoes representing, like those in the Cappella del Santo (p. 200), scenes from the life of the saint. Written catalogue for the use of visitors; best light in the afternoon; fee ½ fr.

By early Paduan masters Nos. 4, 8, and 10; by *Domenico Campagnola*, Nos. 2, 3, 9, and 17; by *Titian* in his early period (1500-20), No. 1. St. Anthony giving speech to a child; 11. The saint saves a woman who is threatened with death by her jealous husband; 12. Healing of a youth. The rest are painted by pupils of *Titian*.

The ancient **Cappella S. Giorgio**, adjacent, contains twenty-one admirable frescoes of 1377 by *Jacopo d'Avanzo* and *Allighieri*, discovered in 1837 by E. Förster.

To the right, below, is the legend of St. Lucia, above it the legend of St. Catharine; to the left, above and below, the legend of St. George. Altar-wall: Crucifixion, Coronation of the Virgin. Wall of the door: Flight into Egypt, Adoration of the Magi, Nativity. Afternoon light most favourable.

In front of the church is the equestrian \**Statue of Erasmo da Narni*, surnamed *Gattamelata*, commander of the army of the Republic of Venice in 1438-41, cast in bronze by *Donatello*, the first great specimen of bronze-casting of the modern period of Italian art, erected in 1443.

To the right of the church of S. Antonio, established in the S.W. cloisters of the suppressed monastery, is the **Museo Civico** (Pl. 30; D. 4), containing the civic library, a collection of coins, terracottas, bronzes, etc., and the *Pinacoteca* (½ fr.).

*Bonifazio*, Madonna and Child with saints; *Lov. Lotto* (?), same subject; \**Basaiti*, Madonna and saints; *Salv. Rosa*, Warriors; *Titian* (?),

Christ, Mary, and apostles; *L. Bassano*, The Doge Marcantonio Memmo; *Tiepolo*, S. Patrizio healing a lunatic; *Squarcione*, Altar-piece in three sections; *Jac. Bellini*, Christ in purgatory; *Marco Palmezzano da Forlì*, Madonna and Child with John the Baptist; *Ant. and Bart. da Murano*, Altar-piece in 12 sections; *Girolamo da Santa Croce*, Entombment; *Paolo Veronese*, Christ on the Cross; *Garofalo*, Madonna and Child, with Elizabeth, Zacharias, and the young John; *Mantegna*, Warriors; *Romano*, Madonna and two saints; by the same, Last Supper; by the same, Madonna enthroned with saints and angels singing (the finest picture in the collection).

\***Eremitani** (Pl. 12; F, 4), an Augustinian church of the middle of the 13th cent., judiciously restored of late, with painted vaulting of wood, is a very long building, destitute of aisles, columns, and pillars.

On the right and left are two old monuments of Princes of Carrara, the ancient lords of Padua, in a style peculiar to this town. — The walls of the CHOIR are covered with indifferent frescoes by *Guariento* (beginning of 15th cent.), representing scenes from the history of the Augustinian Order.

The **CAPPELLA S. JACOPO E CRISTOFORO**, adjoining the right transept, is embellished with celebrated frescoes, forming one of the finest existing specimens of Upper Italian art. Although now considerably damaged, these pictures are still very attractive, while their decorative parts show that the *School of Squarcione*, from which they emanated, was indebted for many suggestions to its study of the antique. The Evangelists on the ceiling are the poorest, and probably the earliest part of the work. The four upper sections on the wall on the right are also by inferior artists: the St. Christopher with the Infant Christ is by *Bono*; the two highest scenes, representing St. James as a worker of miracles, and St. James before the king, are by an unknown master (*Zoppo?*); the adoration of the giant saint (central section on the right) is by *Asuino da Forlì*. The paintings on the wall and vaulting of the recesses of the choir, are by *Niccolò Pizzolo*, an able master of Padua, who died young. By far the most important of all these works are the pictures with which **ANDREA MANTEGNA** completed the cycle in the second half of the 15th cent. The left wall presents to us the life of St. James from his calling to his execution. The lower scenes exhibit greater ability and maturity than the upper, so that we can almost trace the master's progress step by step. The Execution and Burial of St. Christopher, the last pictures on the left wall, also by *Mantegna*, are sadly injured. — The large altar-relief of the Madonna and saints in terracotta, by *Giov. da Pisa*, a pupil of Donatello who worked for a considerable time at Padua, has visibly influenced the painters of the frescoes.

The chapel to the right of the high altar contains a Coronation of Mary of the school of *Giotto*.

The SACRISTY (entrance to the left of the choir) contains an altar-piece by *Guido Reni* (covered), representing John the Baptist.

On the N. side of the Piazza in front of the church is the entrance (if closed, ring at the large wooden gate; fee 1/2 fr.) to the \***Madonna dell' Arena** (*Annunziata*, Pl. 2; G, 4), situated in an oval garden which shows the outlines of an ancient amphitheatre. The chapel was erected by *Scrovegno*, a Paduan architect, in 1303, and in 1304 its walls were completely covered with a series of \*frescoes by *Giotto*, most of which are well preserved (restored by Botti). Morning light is the most favourable.

These frescoes represent the HISTORY OF THE VIRGIN AND CHRIST. The series begins in the left corner of the right side, in the uppermost row, and is continued by the uppermost row to the left, the middle row to the right, the middle row to the left, the lowest row to the right,

and the lowest row to the left; below are allegorical figures; in the choir the Coronation of the Virgin and saints, by a follower of Giotto. On the W. wall is a single painting, grandly conceived, representing the LAST JUDGMENT, supposed to have been suggested by Dante, when on a visit to his friend Giotto. (Photographs from the originals may be purchased of Naya at Venice, 3 fr. each, see p. 207.) — At the back of the altar is the monument of the founder of the church, *Giovanni Pisano*, 1321.

Near the Porta Codalunga, in the vicinity, is the church of **I Carmini** (Pl. 6; G, 3), with a dome and large choir with six chapels on each side, and an unfinished façade. — In the adjacent open space rises a monument to *Petrarch*, erected by the town on 18th June, 1874, the 500th anniversary of his death.

On the right is the \**Scuola del Carmine* (Pl. 24; G, 3; now a baptistery), with frescoes from the lives of SS. Joachim, Anna, Mary, and Christ, one of them by *Titian* (of his earliest period).

Left, \**Titian*, Joachim and Anna (a shepherd kneeling on the right); *Girolamo da Santa Croce*, Birth of Mary. Presentation in the Temple, Purification, and Spozalizio; the others by Paduan masters. \*Altar-piece, Madonna and Child in an attitude of benediction, by *Palma Vecchio*.

The **Cathedral** (Pl. 11; E, 2), dating from the latter half of the 16th cent., with a plain façade, is uninteresting. The *Baptistery* (Pl. 3; E, 2), adjoining it on the N., a brick structure of the 12th cent., is adorned with frescoes of 1380 by *Giov.* and *Ant.*, or by *Giusto Padovano*.

The **Palazzo della Ragione** (Pl. 37; E, 3), now the *Municipio*, situated between the Piazza delle Erbe and the Piazza de' Frutti, a 'Juris Basilica' as the inscription records, was erected in the 11th cent. and remodelled in 1420. It is celebrated for its great *Hall*, with vaulted wooden ceiling, one of the largest in the world, 91 yds. in length, 30 yds. in breadth, and 78 ft. in height.

This hall contains a large wooden model of a horse by *Donatello*, which has given rise to various conjectures, but was probably used by the artist as a model for the horse in the monument of Gattamelata (it closely resembles the third horse to the right on St. Mark's at Venice, p. 215, which was probably the prototype). Behind the horse is the tombstone of T. Livius Halys, a freedman of the family of the historian Livy, who is believed to have been born at Abano (p. 263). The walls are adorned with about 400 pictures in fresco, painted soon after 1420 by *Gior. Miretto* and others, representing the influence of the constellations and the seasons on mankind (custodian 1/2 fr.).

Under the loggia towards the Piazza dei Frutti, and that towards the Piazza delle Erbe, are Roman antiquities, chiefly inscriptions.

The *Palazzo del Podestà* (Pl. 39; E, 3) in the Piazza delle Erbe, the *Pal. del Capitaneo* (Pl. 38; E, 2, 3) with a clock-tower, in the Piazza de' Signori (now the Piazza Unità d'Italia), and the *Pal. Giustiniani* in the Via del Santo, to the E. of the church of S. Antonio, also merit inspection.

The **Loggia del Consiglio**, or *Gran Guardia*, in the Piazza de' Signori (Pl. E, 3), by *Biagio Rossetti*, is a very elegant example of the early Renaissance style, possessing a deep vestibule with an open arcade above a broad and lofty flight of steps.

The **University** (Pl. 47; E, 4), opposite the Café Pedrocchi,

is established in a building called '*Il Bò*', from a tavern which once existed in the vicinity with the sign of the ox. Below the handsome colonnades in the court, erected in 1552 by *Jac. Sansovino*, are numerous inscriptions and armorial bearings of distinguished '*cives academici*'.

Padua has also dedicated a number of monuments to the '*auditores Patavini*', or students of the university, who distinguished themselves in after-life. A double series of statues adorn the **\*Prato della Valle** (Pl. C. 3, 4), now called the *Piazza Vittorio Emanuele II.*, originally a grassy dale, now a promenade. In the inner row to the left, No. 74. *Steph. Bathori*, 75. *John Sobieski* 'qui Patav. academ. alumnus ingenio, patriam rex etc. illustr.'; in the external row *Tasso*, *Ariosto*, *Petrarch*, *Galileo*. A few of these statues only possess artistic value, such as those of *Poteni* and *Capello* by Canova. This spacious Piazza presents a busy scene at the time of the fair (*fiera*), which begins on the festival of St. Anthony (13th June).

Opposite to the Prato, to the N. W., in front of the Gothic arcades of the *Palazzo della Loggia* (Pl. 40), a modern structure of brick and stone, are the marble *Statues of Dante* and *Giotto*, by Vincenzo Vela. Inscriptions: 'A Dante poeta massimo di patria concordia propugnatore festeggiando Italia il 6 centenario dal suo natale Padova gloriosa di sna dimora p. 1865', and, 'a Giotto per lo studio del vero rinovatore della pittura amico di Dante lodato nel sacro poema Padova da snoi affreschi illustrata p. 1865'.

To the S. E. of the Prato is situated the church of **\*S. Giustina** (Pl. 16; C, 4), an edifice of strikingly noble and imposing proportions, especially in the interior, completed in 1549 by *Andrea Riccio* or *Brioso*. It possesses a nave with two aisles, four domes, and an unadorned façade of brick, approached by a handsome flight of twelve steps, of the entire breadth of the structure.

The church is paved with black, yellow, and red marble. In the left transept is the sarcophagus of St. Luke, in the right transept that of St. Matthew. Over the high altar, which contains the tomb of St. Justina, is the 'Martyrdom of St. Justina, by *Paolo Veronese*. Magnificently carved Choir-stalls from drawings of *Campagnola* (1552), in 50 different sections, each representing a subject from the New Testament above, and one from the Old below. In the chapel on the right of the choir is represented the Virgin with the body of Christ, at the sides John and Mary Magdalene, a large group in marble by *Parodi* (17th cent.). The old choir, the sole remnant of the original church, also possesses fine carved stalls.

In the vicinity is the *Botanic Garden* (Pl. 32; C, 4), the oldest in Europe, well stocked with trees peculiar to the south.

EXCURSION to the *Euganean Hills*, see p. 263.

### 36. Venice, Italian *Venezia*.

**Arrival.** The RAILWAY STATION is on the N.W. side of the town, at the end of the Canal Grande (Pl. B, C, 2; the *Agenzia di Città*, or town office, is in the Palace of the Doges, near the Ponte della Paglia, comp.





# VENEZIA. VENEDIG.



- |                                    |      |                               |        |                            |          |
|------------------------------------|------|-------------------------------|--------|----------------------------|----------|
| 1 Accademia delle Belle Arti       | D.5. | 14 S. Giovanni Grisostomo     | F.3.   | 40 Giardini Papadopoli     | C.3.     |
| 2 Archivio Centrale di Frari       | D.3. | 15 S. " e Paolo               | F.6.3. | 41 Ospedale Civile         | F.G.2.3. |
| 3 Arsenal (Porta d'Ingresso)       | H.4. | 16 S. Giuliano                | F.4.   | 42 Balbi                   | D.4.     |
| 4 Campanile                        | F.4. | 17 S. Marco (Cattedrale)      | F.4.   | 43 Barbarigo               | D.3.4.   |
| <b>Chiese</b>                      |      |                               |        |                            |          |
| 5 S. Apostoli                      | F.2. | 18 S. Maria Formosa           | F.3.   | 44 Battagia                | D.2.     |
| 6 S. Biagio                        | H.4. | 19 " Mater Domini             | DE.3.  | 45 Bembo                   | E.3.     |
| 7 I. Camini                        | C.4. | 20 " dei Miracoli             | F.3.   | 46 Bernardo                | DE.3.    |
| 8 S. Pantino                       | E.4. | 21 " dell'Orto                | E.1.   | 47 Casa ferro              | E.5.     |
| 9 S. Francesco della Vigna         | G.3. | 22 " della Salute             | E.5.   | 48 Ca-d'oro                | E.2.     |
| 10 I. Frari (S. Maria Gloriosa)    | D.3. | 23 " Tobenigo                 | E.4.   | 49 Carverlinghi            | E.3.     |
| 11 I. Gesuiti                      | F.2. | 24 S. Moisè                   | E.F.4. | 50 Cavalli                 | D.4.     |
| 12 S. Giorgio Maggiore             | G.5. | 25 S. Nicolò da Tolentino     | C.3.   | 51 Contarini dei Scritti   | D.4.     |
| 13 " degli Schiavoni               | G.3. | 26 S. Pantaleone              | D.4.   | 52 " Fasan                 | D.4.     |
| 13 <sup>a</sup> S. Cassiano        | E.3. | 27 S. Pietro di Castello      | L.4.   | 53 " Figure                | D.4.     |
| 13 <sup>b</sup> S. Giac. di Rialto | E.3. | 28 Il Redentore               | E.6.   | 54 Corner                  | E.5.     |
| 13 <sup>c</sup> S. Orsola-Bergrato | G.4. | 29 S. Rocco                   | D.3.   | 55 Corner della Regina     | E.2.     |
|                                    |      | 30 S. Salvatore               | F.3.   | 56 Corner Spinelli         | E.4.     |
|                                    |      | 31 Oli Scalzi                 | C.2.   | 57 Corner (Museo civico)   | D.2.     |
|                                    |      | 32 Scuola dell'Angelo Custode | F.2.   | 58 Dandolo                 | E.3.     |
|                                    |      | 33 S. Sebastiano              | C.4.   | 59 Dario Angarini          | E.5.     |
|                                    |      | 34 S. Simone piccolo          | C.2.   | 60 Ducale                  | F.4.     |
|                                    |      | 35 S. Stefano                 | E.4.   | 61 Emo Treves              | E.4.     |
|                                    |      | 36 S. Zaccaria                | G.4.   | 62 Fini                    | E.4.     |
|                                    |      | 37 Dogana di Mare             | E.5.   | 63 Fondaco de Tedeschi     | F.3.     |
|                                    |      | 38 Direzione di Polizia       | G.3.   | 64 Fondaco de Turchi       | D.2.     |
|                                    |      |                               |        | 65 Foscari                 | E.3.     |
|                                    |      |                               |        | 66 Foscari                 | D.4.     |
|                                    |      |                               |        | 67 Giannelli               | E.2.     |
|                                    |      |                               |        | 68 Giustiniani             | D.4.     |
|                                    |      |                               |        | 69 Giustiniani Lora        | D.4.     |
|                                    |      |                               |        | 70 Grimani (S. Toma)       | D.1.     |
|                                    |      |                               |        | 71 Grimani della Vida      | E.2.     |
|                                    |      |                               |        | 72 Grimani (S. M. Formosa) | F.3.     |

- |                               |      |
|-------------------------------|------|
| <b>Alberghi</b>               |      |
| a Grand Hotel Royal (Danieli) | F.4. |
| b Europa                      | F.4. |
| c Britannia                   | E.4. |
| d Belle Vue (Isenghi)         | F.4. |
| e S. Marco                    | F.4. |
| f Lana                        | F.4. |
| g Vittoria                    | E.4. |
| h Italia                      | E.4. |
| i Vapore                      | F.4. |
| k Gallo                       | F.4. |
| l Otta di Monaco              | F.4. |
| m Bauer                       | E.4. |
| n Hotel garni (all'Orologio)  | F.4. |
| o Grand Hotel                 | E.5. |
| p Aurora                      | G.4. |

- |                                     |        |
|-------------------------------------|--------|
| 72 Grassi                           | D.4.   |
| 73 Labia                            | D.2.   |
| 74 Loredan                          | E.3.   |
| 75 Maurin                           | D.2.   |
| 76 Margutti Vabmarana               | E.2.3. |
| 77 Mann                             | E.3.   |
| 78 Manzoni Angarini                 | D.5.   |
| 79 Michieli delle Colonne           | E.2.   |
| 80 Mocenigo                         | D.4.   |
| 81 Mocenigo (Byron)                 | D.4.   |
| 82 Moro-Lin                         | D.4.   |
| 83 Persico                          | D.4.   |
| 84 Pesaro                           | E.2.   |
| 85 Pisani                           | D.4.   |
| 86 Reale                            | F.4.   |
| 87 Remer                            | E.2.   |
| 88 Reasonico                        | D.4.   |
| 89 Sacredo                          | E.2.   |
| 90 Nepolo Stürmer                   | E.3.   |
| 91 " Eucelli                        | E.4.   |
| 92 Nepolo                           | D.4.   |
| 93 Tron                             | D.2.   |
| 94 Venetianin Calerghi              | D.2.   |
| 95 Zichlsterhaxi                    | D.5.   |
| 96 Posta                            | E.4.   |
| 97 Prigioni crim. e Ponte dei Sosp. | F.4.   |
| 98 Scuola di S. Rocco               | D.3.   |
| 99 Seminario Patriarcale            | E.5.   |
| <b>Teatro</b>                       |        |
| 100 La Fenice                       | E.4.   |
| 101 Apollo                          | E.3.   |
| 102 Rossini/Gallo                   | E.4.   |
| 103 Malibran                        | E.3.   |
| 104 Camply                          | D.4.   |
| 105 Zecca                           | F.4.   |
| 106 Ufficio del Disgrato            | E.2.   |



Introd. vii). — Good order is maintained at the station. An official at the egress assigns a gondola to the traveller on being told his destination. An ample supply of gondolas and 'Omnibus-boats' is always in waiting; but the latter are not recommended, being slow, often crowded, and affording no view. GONDOLA from the station to any part of the city 1 fr., each box 15 c.; with two rowers double these charges. A second generally proffers his services, but may be dismissed with the words 'basta uno!' — Gondola tariff for those who arrive by sea, see p. 206. — OMNIBUS BOATS ply, on the arrival of every train, from the station to the *Riva del Carbonè* (near Ponte Rialto) and the *Piazzetta*. Fare 25 c., gratuity 5 c., each heavier article of luggage 15 c.; the porter belonging to the boat, who conveys luggage to the hotel, also expects a fee. Omnibus boats to the station (in 20 min.) start from the *Molo*, E. of the *Piazzetta*,  $\frac{3}{4}$  hr. before the departure of each train (their station is by the first bridge, the *Ponte della Paglia*, close to the *Bridge of Sighs*). — Small café at the station.

**Hotels** (table-d'hôte at 5 p.m. at all). GRAND HÔTEL ROYAL (DANIELI, Pl. a), in the old *Palazzo Bernardi*, well situated, at the beginning of the *Riva degli Schiavoni*, E. of the Palace of the Doges, with the dépendance *Beaurivage*, also on the *Riva degli Schiavoni*. \*EUROPA (Pl. b), in the former *Palazzo Giustiniani*, on the Grand Canal, opposite the Dogana di Mare and near the Piazza of St. Mark. Both expensive. HÔTEL BRITANNIA (Pl. c); formerly 'Hôtel de la Ville', in the *Palazzo Zucchelli*, on the Grand Canal, opposite S. Maria della Salute. \*GRAND HÔTEL VICTORIA (Pl. g), R. 3, D. 5, B.  $1\frac{1}{2}$ , L. and A.  $1\frac{1}{2}$  fr., situation less favourable. GRAND HÔTEL (formerly New-York), in the *Palazzo Ferro* (Pl. 47) and the *Palazzo Fini*, which have recently been united. S. MARCO (Pl. e), in the Piazza of St. Mark, in the old Procurazie, R. 3-4, D. 4-5 fr.; \*HÔTEL BELLEVUE (Pl. d), N. side of the Piazza of St. Mark, R. 2 fr. and upwards, B. 1, D. 4-5 fr.; \*ITALIA (Pl. h), S. Moisé, with one side facing the Canal Grande, R. from 2/2, D. 5, B.  $1\frac{1}{2}$  fr.; \*HÔTEL BAUER (Pl. m), S. Moisé, Calle Lunga, with restaurant, these two last belong to the same proprietors; \*LUNA (Pl. f), opposite the royal garden, close to the S.W. side of the Piazza of St. Mark, similar charges; CITTÀ DI MONACO (Pl. l), on the Canal Grande, not far from the Piazza of St. Mark, D. 4 fr.; ALBERGO ORIENTALE, with the *Restaurant Cappello Nero*, in the Piazza of St. Mark, Procurazie Vecchie, R. from 2 fr.; HÔTEL PENSION SUISSE, on the Canal Grande, opposite S. Maria della Salute; UNIVERSO, in the *Palazzo Brandolin*, Canal Grande, adjoining the academy, R. 3 fr., well spoken of; HÔTEL D'ANGLETERRE (formerly Laguna), *Riva degli Schiavoni*; \*ROMA, S. Moisé. — AURORA (Pl. p) and SANDWIRTH, both on the *Riva degli Schiavoni*, commanding a view, are unpretending but respectable German inns. — VAPORE (Pl. i), in the Merceria, S. GALLO (Pl. k), LEON BIANCO, and CAVALLETO, of which the three last are near the Piazza S. Marco, are tolerable Italian inns with restaurants.

**Hôtels Garnis.** NATIONAL (German) and ANG. FABRIS, both on the *Riva degli Schiavoni*; SCATTI, Calle del Ridotto; ALL' OROLOGIO, in the Merceria, adjoining the clock tower (p. 217); MAD. GRÜNDEL. — \*PENSION ANGLAISE, in the *Palazzo Giustinian Vescovi*, on the Canal Grande, moderate.

**Private Apartments**, advertised by notices on the shutters or in the windows, are easily obtained. The rents of those on the *Grand Canal* and the *Riva degli Schiavoni* are the highest. The *Fondamenta delle Zattere* is a quiet and pleasant situation (e. g. in the Calle del Ridotto, R. 1-2 fr. per day, 30-50 fr. per month). It is usual to pay for one month in advance, before which the tenant is recommended to see that every necessary arrangement is made, '*tutto compreso*'.

Travellers are cautioned against sleeping with open windows on account of the gnats. Mosquito-curtains (*zanzariere*) afford the best protection against these pertinacious intruders. Pastilles ('*fidibus contro le zanzare*'), sold by the chemists, are generally effectual in dispersing them. — *Drinking-water* is bad at Venice; new water-works are projected.

**Restaurants** (*Trattorie*). \*Caffè Quadri, first floor, in the Piazza S.



Marco; *Restaurant on the Lido* (see p. 214); others, where beer is obtainable, see below. In the Italian style: \**S. Gallo* (Pl. k; see above), with an open court; *Cappello Nero*, in the Piazza S. Marco, see above; *Città di Firenze*, good wine, Calle del Ridotto, opposite the Europa; \**Leon Bianco*; \**Cavalletto*, at the back of the Hôtel S. Marco; \**Vapore*; *Bella Venezia*, and others. — The wines of *Cyprus* and *Samos* are among the best at Venice (sold by *Giacomuzzi*, Calle Vallarossa, near the S. W. corner of the Piazza of St. Mark).

**Beer.** \**A. Dreher*, near the Piazza S. Marco, with a good restaurant; \**Bauer and Grünwald* (Hôtel Bauer, see above); and also at the Birrerie near the Campo S. Angelo, S. Polo (pleasant garden), and at many of the cafés.

**Cafés.** In the *Piazza of St. Mark*, S. side: \**Florian*, good ices; *Caffè Svizzero*. N. side: *Degli Specchi*; \**Quadri* (recommended for breakfast); \**Café Giardino Reale*, to the right of the Piazzetta, beautifully situated. After sunset hundreds of chairs and small tables are placed in front of these cafés for the accommodation of customers. — Strangers are often importuned by flower-girls, hawkers, musicians, etc. — The cafés on the *Riva degli Schiaroni* are also much frequented, although less fashionable: *Bricciacco* (good ices), *Alle Nazioni*, etc.

**Boats** take the place of *fiacres* at Venice. The light, old Venetian *Gondola*, with a low black canopy or cabin (*felze*) and black leather seat, accommodates 1-4 pers. They are painted black in conformity with a law passed in the 15th cent. The *Barca*, a modern institution, is a larger craft, open at the sides, covered with coloured material, and accommodating six or more persons. The heavy indented iron prow (*ferro*), resembling a halberd, is partly intended to counterbalance the weight of the rower, and partly as a measure of the height of the bridges, which cannot be passed unless the *ferro*, the highest part of the craft, clears them. The rower himself is hailed as \**Poppe*, from the *poppa* on which he stands.

\**Cavar il Felze* means 'to take off the covering or cabin'. The shouts of the gondoliers on turning a corner are peculiar, e. g. *già è* (boat ahead!), *preme* (pass to the right!), *stali* (pass to the left!), etc.

**Charges.** Gondola for 1-4, or a barca for 1-6 persons, with one rower (*barcajuolo*), according to the tariff of 1872, a copy of which the gondolier is bound to exhibit if desired, for the first hour, or for each trip, *by day or by night*, 1 fr., for each additional hour 50 c. (but a fee is expected in addition to these low fares), for the whole day (of 10 hrs.) 5 fr. To or from the station, see p. 204. From the steamers to the Piazzetta (two rowers required) 40 c., luggage 15 c. For short distances a bargain should be made. For a second rower double the ordinary fare is charged. One, however, suffices for the gondola, and even for the barca if not heavily laden (*basta uno*), unless greater speed than usual is desired. For a longer distance, however, such as to the Lido, two rowers are desirable, and in this case a bargain may be made with the gondolier for a second. — The islands of Murano, S. Lazzaro, and Lido are included in the tariff. — For longer distances the charge per hour and per gondolier is 10 c. more. For public festivities a bargain must be made. Official loiterers who assist passengers to disembark expect a gratuity of a few centimes.

The principal station of the gondolas is by the *Piazzetta* (p. 218; Pl. F. 4). The traveller selects a suitable boat without regarding the importunities of the boatmen, whereupon the owner will soon present himself. If the gondola is hired by the hour, which is the most advantageous mode for sight-seeing, the passenger shows his watch, saying '*all' ora*'. The highest demands are generally made at the Piazzetta and Riva and in the vicinity. It need hardly be observed that the intervention of a commissionaire or a waiter in the hiring of a boat causes the fare to be considerably raised. If any difficulty arises it is best to apply to a policeman (*Guardia municipale*).

The gondoliers are, as a class, respectable and trustworthy, and a small gratuity goes far towards securing their good offices.

*Ferries* (*Traghelli*) across the Grand Canal 15 c., after dusk 8 c., comp.

Plan); from the *Fondamenta Nuove* to Murano, 30 c., and to Mazzorbo (Torcello, p. 245); from the *Fondamenta delle Zattere* to the Giudecca, 15 c.; from the Molo (Piazzetta) to the Giudecca 20 c., to Il Redentore 30 c., to the Punta della Salute 15 c., to S. Giorgio Maggiore 15 c.; from the Molo to the Giardini Pubblici (evening included) 50 c.

**Guides** are to be met with before 9 a.m. or about 8 p.m. in the Piazza of St. Mark. Each hotel generally has its own guide. Parties of visitors are frequently formed by the guides, who undertake to conduct them to all the principal sights of Venice at a charge of 4 fr. each person, which includes gondola-fares, gratuities, etc., but, as the number is usually unlimited, this wholesale system cannot be recommended, the members of the party being entirely deprived of their independence. The traveller, alone, or accompanied by a few friends, will find it far preferable to have a guide at his own disposal. In this case the fee, including all expenses, is about 20 fr. (i.e. 5 fr. for the guide and 15 fr. for gondolas, fees, etc.). The guides are often reluctant to cross to S. Redentore on the Giudecca, but the traveller may insist on their accompanying them.

It must, however, be observed that the aid of the Handbook, coupled with a slight acquaintance with the Italian language, will enable the traveller *entirely to dispense with a guide*. The principal objects of interest should be visited in a definite order, such as that suggested below, and the most direct routes ascertained from the Plan, in order that the proper orders may be given to the gondolier at each stage of the route. Much also can be done on foot with the aid of the Plan. The route from the Piazza di S. Marco to the station is indicated by notices on the street corners.

**Consulates.** *American*, S. Maria del Rosario, *Fondamenta Veurier* 709; *British*, S. Maria del Giglio, Calle Gritti o del Campanile 2439; *French*, S. Stefano, Calle Giustiniano 2891; *German*, S. Benedetto, Pal. Memmo, 3949; also others for all the principal European states.

**Baths** of every description (also for swimming: *galleggiante*) are situated between the Riva degli Schiavoni and the Isola S. Giorgio, but are used during the three summer-months only (bath 1 fr.). Ferry from the Piazzetta to the baths 10 c.; the word '*bagno*' is a sufficient direction to the gondolier. Swimmers (1 fr.) ask at the establishment for a ticket for the '*vasca*' (basin); a separate bath (1½ fr.) is a '*camerino*'; common bath for ladies (*sirene*) 1 fr. 40 c.; separate bath for ladies 3 fr. No gratuities expected. The best time for bathing is about high tide, the water at low tide being shallow and muddy. — The baths on the *Lido* are much pleasanter. In summer a steamboat plies every hour (in the height of the season every half-hour) between the Riva degli Schiavoni and the Lido in 12 min., returning after a halt of ½ hr. (Tickets must be procured before embarking, 30 c.; there and back, including the bath, 1½ fr.) From the landing-place to the baths a walk of 10 min. (omnibus 25 c.). Bath 1 fr. (for ladies to the left, for gentlemen to the right), less to subscribers. Connected with the baths is a favourite '*Café Restaurant*', where a band plays on summer evenings till 10 o'clock. — *Warm Baths* at most of the hotels, and at *Chitarin's* (salt-water), near S. Maria della Salute, 1½-2 fr.

**Booksellers.** *Münster*, Piazza of St. Mark, S.W. corner; *Colombo Coen*, Procurazie Vecchie 139, and at the Hotel New York.

**Photographs:** *Naya & Schöfft*, in the Piazza of St. Mark, views of Venice, from the smallest at about 50 c. to the large and expensive size (28 by 36 inches), copies from drawings 1½, from original pictures 4 fr.; *Ponti*, also in the Piazza of St. Mark.

**Post Office** (*Uffizio della Posta*; Pl. 96; E, 4) to the N. of the Piazza of St. Mark (route indicated by painted notices). *Letter-boxes* in the Piazza of St. Mark, at the Uffizio del Lloyd, etc. — **Telegraph Office** behind the W. end of the Piazza of St. Mark, above the guard-house.

**Steamboats:** To *Trieste* four times weekly, see p. 248; to *Chioggia* (*Società Lagunare*), see p. 245; to *Alexandria* in Egypt, a vessel of the P. & O. Co. once weekly. The offices of these companies are in the Piazzetta, and in the Piazza of St. Mark, under the new Procurazie.

**Theatres** (comp. *Introd. X*). *La Fenice* (Pl. 100), the largest in Venice, is capable of accommodating 3000 spectators; internal arrangements worthy of inspection; performances during the Carnival only, sometimes also in June and July. The following are used throughout the whole year, except in September: *Apollo* (Pl. 101), *Rossini* (Gallo; Pl. 102), and *Camplon* (S. Samuele; Pl. 104). The theatres in Venice are among the best in Italy. *Malibran* (Pl. 103), open-air theatre.

**Shops.** (The recommendations and even the attendance of valets-de-place or boatmen have the effect of greatly increasing the prices; comp. *Introd. X*.) The best are in the *Piazza of St. Mark*, in the *Merceria* (p. 217), and in the *Frezzaria*, entered from the W. end of the *Piazza of St. Mark*, opposite the church. The Venetian pearls and jewellery enjoy a high reputation; bracelets, necklaces, and other ornaments in mosaic, glass, and shells are also well executed here, and are suitable for presents or reminiscences. — The most extensive *Manufactory of Mosaic* is that of the *Compagnia de' Vetri e Musaiici di Venezia e Murano* (formerly *Salviati*) on the Canal Grande, in the Campo S. Vito, not far from S. Maria della Salute. Many of the shopkeepers take two-thirds or even one-half of the price first demanded. — Crystal-wares, *Dalmedico*, *Merceria dell' Orologio*, 218. — Antiquities and objects of art, *Besarel*, Canal Grande, *Traghetto S. Barnaba*; *Guggenheim*, Campo S. Maria del Giglio (Zobenigo), No. 2467, and *Ricchetti* and *Riatti*, both on the Canal Grande. — Venetian lace, *Ruggieri* (near S. Gallo), *Borghesi* (*Merceria*), etc.

**Exhibition of Art** in the Palazzo Mocenigo S. Benedetto, adm. 40 c.

**English Church Service**, Palazzo Contarini degli Scignì, Grand Canal, near the iron bridge. — *Scotch Presbyterian Church* on the Grand Canal, not far from S. Maria della Salute.

The Climate of Venice is tempered by the proximity of the sea and the Lagune. Invalids who intend wintering in Venice should be particular as to a S. aspect. The quietest apartments are to be found in the *Fondamenta delle Zattere* (Pl. C, D, 5). — *Chemist*: Campo S. Luca, 3801. — *Physician*: Dr. Keppler, Campo Sto. Stefano, 2808.

During the Carnival no other city in Italy, Rome excepted, presents so busy and animated a scene as Venice. The *Piazza S. Marco* is then converted into a kind of vast ball-room. Balls also take place in the *Ridotto* and the *Teatro Fenice*.

**Plan of Visit.** A stay of 3-4 days may suffice when time is limited, in which case the following plan is recommended, but it may be extended or modified at discretion.

*Afternoon or Evening* of arrival. In order to gratify their first curiosity, and obtain a general idea of the peculiarities of Venice, travellers are recommended to undertake a preliminary voyage from the *Piazzetta* along the *Grand Canal* (see p. 227) to its extremity (near the railway-station is the church *Degli Scalzi*, see p. 232, which may now be visited on account of its remoteness from the other points of attraction); then under the iron bridge to the *Canal di Mestre*, to the left of which is the Jews' quarter (the *Ghetto*, inhabited by the lowest classes); back hence by the Grand Canal to the *Ponte Rialto*, where the gondola should be quitted. Then walk through the *Merceria* to the *Piazza of St. Mark*. The whole expedition will occupy 2-2½ hrs.

1st Day. \*S. Marco (p. 214); \*\**Palace of the Doges* (p. 218); †*S. Giorgio Maggiore* (p. 242; ascend campanile); †*Redentore* (p. 243); †*S. Sebastiano* (p. 243).

2nd Day. *Pal. Emo Treves* (p. 227); *S. Maria della Salute* (p. 238); \*\**Accademia delle Belle Arti* (p. 223); †*S. Stefano* (p. 238); †*Frari* (p. 235); *Scuola di S. Rocco* (p. 237).

3rd Day. *S. Salvatore* (p. 234); *Pal. Vendramin* (p. 231); *Museo Correr* (p. 230); *Madonna dell' Orlo* (p. 239); *Gesuiti* (p. 239); *S. Maria de' Miracoli* (p. 241).

4th Day. †*S. Zaccaria* (p. 233); *S. Maria Formosa* (p. 233); †*S. Gio-*

*vanni e Paolo* (p. 240); *S. Francesco della Vigna* (p. 241); *Arsenal* (p. 223; open till 3 p.m.); *Giardini Pubblici* (view, p. 244).

Lastly ascend the *Campanile* of S. Marco (p. 217).

Those who make a longer stay may proceed to the *Lido* (sea-baths, p. 244), and make excursions to the N. to *Murano* and *Torcello* (pp. 244, 245; 5 hrs. there and back); to the S. to *Matamocco* and *Chioggia* (p. 245). — Every leisure hour should be devoted to S. Marco and its environs.

Admission is generally obtained to the —

*Churches* from 6 a.m. till 12 or 1 o'clock, after which application must be made to the sacristan (*nonzolo*, fee 50 c.), for whom one of the officious loungers in the neighbourhood may be sent (5 c.).

\* *Academy* (p. 223) daily 10-3; admission on week-days 1 fr., on Sundays and holidays gratis; closed on New Year's Day and Easter Sunday only.

\* *Arsenal* (p. 223), on week-days, 9-3; closed on Sundays and holidays.

\* *Palace of the Doges* (p. 218), on the same days, and at the same hours as the Academy, adm. 1 fr., to the dungeons 40 c. more; guide quite unnecessary; information may be obtained from the custodians.

\* *Museo Correr* (p. 230) Mond., Wed., Sat., 10-4.

*Seminario Patriarcale* (p. 227) daily.

The *Private Palaces* (\* *Vendramin, Emo-Treves, Fini-Wimpfen, Pesaro*) are generally shown between 9 or 10 a.m. and 3 or 4 p.m. When the proprietors are residing in them, application should be made on the day previous to the visit, but this formality is often dispensed with (fee to attendant 1 fr., to porter 25-50 c.).

**History** (comp. p. 181). The modern Venetia was inhabited during the Roman period by the *Veneti*, whose principal towns were Patavium, Altinum, Aquileia, &c. These were successively destroyed, after the fall of the W. Roman Empire, by the hordes of barbarian invaders by whom Italy was now overrun, and their inhabitants took refuge on the islands of the Lagune, founded a new state there, and at an early period carried on a considerable commerce with the Levant. The necessity of a constitutional government was soon felt, and in 697 *Paulucius Anafestus* was elected the first doge. In 819 the doge *Angelus Participotius* transferred the seat of government from Malamocco to Rialto, which he connected with the adjacent islands by means of bridges, thus laying the foundation of the modern city of Venice.

During the following centuries, notwithstanding continual internal dissensions, the might of Venice steadily increased. The foundation of its subsequent greatness, however, was principally laid at the period of the CRUSADES (1097-1271), which the shrewd policy of Venice contrived to turn to its own aggrandizement. In 1177, under the Doge *Sebastiano Ziani*, the celebrated meeting of Emp. Frederick I. with Pope Alexander III. (p. 209) took place at Venice. *Enrico Dandolo* (1192-1205), one of the most valiant of the doges, conquered Constantinople in 1204 with the aid of French crusaders. In consequence of this the Byzantine Empire was divided, and Venice obtained possession of the coast-districts of the Adriatic and Egyptian seas and numerous islands, among which was Candia. Under the successors of Enrico Dandolo the republic underwent severe contests with GENOA, which occasioned the loss of the Venetian conquests in the East, but at length terminated in the total defeat of Genoa in 1352, during the sway of *Andrea Dandolo*. His successor *Marino Falieri* contemplated the overthrow of the aristocratic form of government, but his scheme was discovered, and he was beheaded on 17th April 1355. During the reign of *Andrea Contarini* (1367-82) Padua, Verona, Genoa, Hungary, and Naples formed an alliance against Venice. In 1379 the Genoese took possession of Chioggia, but were surrounded in the Lagune and compelled to surrender, 24th June, 1380. In 1381 the peace was concluded by which Venice lost all its possessions on the mainland.

The republic, however, soon recovered from these reverses. In 1386 *Antonio Venier* (1382-1400) took possession of the island of Corfu, then of

Durazzo, Argos, etc. Under *Michele Steno* (1400-14) the Venetian general *Malatesta* conquered Vicenza, Belluno, Feltre, Verona, and Padua (1405); in 1408 the republic gained possession of Lepanto and Patras, and in 1409 of Guastalla, Casaliniaggiore, and Brescello. In 1421 *Tommaso Mocenigo* waged war successfully against Hungary. In 1416 the Venetian fleet under *Loredan* defeated the Turkish at Gallipoli, and in 1421 subjugated all the towns of the Dalmatian coast, so that Venice was now in possession of the entire coast district from the estuary of the Po as far as the island of Corfu.

Mocenigo's successor was *Francesco Foscari* (1423-57). In 1426 Brescia fell into the hands of the Venetian general *Carmagnola*, but in 1431 his successful career was terminated in consequence of a suspicion of treason, and in 1432 he was executed by order of the Council of Ten. In 1449 the Venetians gained possession of Crema, but were unable to prevent the elevation of Sforza to the dignity of Duke of Milan (1450).

In 1457 Foscari, now enfeebled by old age and domestic affliction, was deposed by the Council of Ten owing to the intrigues of his enemies. Under *Cristoforo Moro* (1462-71) the Morea was conquered by the Turks. In 1480, in consequence of the renunciation of Catharine Cornaro, wife of king James of Cyprus, this island came into the possession of Venice, and in 1483 the republican dominions were farther augmented by the island of Zante.

The close of the 15th cent. may be designated as the culminating point of the glory of Venice. It was now the grand focus of the entire commerce of Europe, numbered 200,000 inhab., and was universally respected and admired. Its annual exports were valued at 10 millions ducats, 4 millions of which were estimated as clear profit. It possessed 300 sea-going vessels with 8000 sailors, and 3000 smaller craft with 17,000 men, as well as a fleet of 45 galleys carrying 11,000 men, who maintained the supremacy of the republic over the Mediterranean. At the beginning of the 16th cent. the power of Venice began to decline. Its commerce was gradually superseded to a great extent by that of the Portuguese, in consequence of the discovery of the new sea-routes to India. The League of Cambray, formed by the Pope, the Emperor, and the kings of France and Arragon against Venice in 1508, and the victory of the French at Agnadello in 1509 occasioned serious losses to the republic. The wars between Emp. Charles V. and Francis I. of France (1521-30) were also very prejudicial to Venice, and its power was still more undermined by the extension of the Osman empire in Europe and Asia. In 1540 Nauplia, the islands of Chios, Paros, and others were lost, and in 1571 Cyprus, notwithstanding its brave defence by *Bragadino*. In the naval battle of Lepanto (1st Oct., 1571) the Venetian fleet greatly distinguished itself. In 1659 the island of Candia was conquered by the Turks. In 1684 the Venetians under *Francesco Morosini* and *Königsmarck* were victorious in the Morea, and conquered Coron, Patras, Corinth, etc.; in 1696 and 1698 they again defeated the Turkish fleets, and by the Peace of Carlowitz in 1709 they retained possession of the Morea; but in 1715 the Turks reconquered the peninsula, and in 1718 were confirmed in their possession by the Peace of Passarowitz.

From this period Venice ceases to occupy a prominent position in the history of Europe. It retained its N. Italian possessions only, observed a strict neutrality in all the contests of its neighbours, and continued to decline in power. On the outbreak of the French Revolution Venice at first strenuously opposed the new principles, on the victorious advance of the French it endeavoured to preserve its neutrality, and repeatedly rejected Buonaparte's proposals of alliance. Irritated by this opposition, the French broke off their negotiations and took possession of the city on 16th May, 1797. The last doge was *Lod. Manin* (1788-97). By the Peace of Campo Formio (1797) Venetia was adjudged to Austria, and by that of Pressburg (1805) to the kingdom of Italy. In 1814 Venice was again declared Austrian, and remained so until 1848, when a revolution broke out, and the citizens endeavoured to re-establish their ancient republican form of government, under the presidency of *Daniele Manin*. Their renewed

independence, however, proved most disastrous and short-lived. The city was torn by internal dissension, and at the same time besieged by the Austrians. After a siege of 15 months it was compelled to capitulate to *Radezky*, in August, 1849, a victory which cost the Austrians upwards of 20,000 soldiers. The war of 1859 did not affect the supremacy of Austria over Venetia, but its re-union with Italy was at length effected by the events of 1866.

In the **History of Art** Venice has shown herself as independent of, and distinct from the mainland, as are her situation and her political history. The sensation of novelty experienced by the traveller who visits Venice for the first time, even after having seen the whole of the rest of Italy, will also be felt by those who begin to study her art. The earliest monuments of Venice at once betray the fact that her greatness was founded on her Oriental commerce. The church of St. Mark is in the **BYZANTINE** style, the oldest mosaics bear a Byzantine impress, and the same type is observable in other branches of art. Even during the period of **GOTHIC ART** the Venetians did not adopt the same forms as the rest of Italy. In the building of their churches several architects from the mainland (including perhaps *Niccolò Pisano*) appear to have been summoned to their aid. Their palaces, which, like those of Upper Italy, generally form the chief examples of Gothic, particularly that of the *Doges*, exhibit a very peculiar character. They usually possess a large entrance colonnade, a loggia on the upper floor with a number of windows close together in the middle, wings, treated rather as spaces for the reception of paintings, and everywhere abundance of decoration and colour. Examples of this style are the *Cà d'Oro*, and the *Palazzo Foscari*. At a later period the **RENAISSANCE ARCHITECTURE**, which did not become naturalised till the end of the 15th cent., was still more zealously cultivated. In point of size the early Renaissance buildings at Venice bear no comparison with those of Tuscany, but are more richly decorated, and the palaces retain the articulation peculiar to the earliest period. At a later date, when art began to decline, the Venetian architecture resisted the influences of bad taste longer than that of Central Italy. Among the most important Venetian architects were several members of the *Lombardi* family, *Jacopo Sansovino* of Florence (1477-1570), *Antonio da Ponte*, and lastly *Andrea Palladio* of Vicenza (1518-1580), who inaugurated a new era, especially in church architecture, by limiting the façade to a single range of massive columns. Palladio's chief successors were *Scamozzi* and *Longhena*.

In the province of **SCULPTURE** the master who designed the statuary on the Palace of the Doges (perhaps *Fil. Calendario*) was the most famous of the middle ages. About the middle of the 15th cent. the growing taste for monumental tombs afforded abundant employment to the sculptors, and from the studios which now sprung up issued the numerous magnificent monuments which still fill the churches of Venice. The names of the *Bregni* or *Rizzi*, of the *Lombardi* (probably not natives), and of *Alessandro Leopardi*, are the most important. At a later period *Jacopo Sansovino* was the leading master here, both as a sculptor and an architect. His works, though often designed chiefly for pictorial effect, are far more pleasing than those of Michael Angelo's school. His pupils were *Girolamo Campagna* and *Alessandro Vittoria* (d. 1607).

The **VENETIAN PAINTERS** did not begin to attract universal attention till the beginning of the 16th cent. In the 14th cent. they were far inferior to those of the other Italian schools, and though Giotto was engaged for a considerable time at the neighbouring Padua, they were unaffected by his influence. In the 15th cent. the most noted masters at Venice were *Giovanni*, also named *Alamannus*, *Antonio*, and *Bartolommeo Vivarini*, who were known as the *Muranese*. An event of great importance, which took place about 1473, was the visit to Venice of *Antonello da Messina*, who introduced painting in oils, the method best adapted for giving full scope to the Venetian love of rich colouring. After the impulse given to the Paduan school by the labours of Squarcione, its style was more or less zealously adopted by the Venetian masters *Carlo Crivelli*, *Jacopo Bellini*, father-in-law of Mantegna, and others. As a master of the pure Venetian

type we must next mention *Giovanni Bellini* (1426-1516; a son of Jacopo, like *Gentile*, 1421-1507), who may be regarded, both in the style of his compositions (such as his 'sacra conversazione', a peaceful and yet expressive group of saints with the Madonna), and his conception of female figures, as the precursor of the glorious prime of Venetian painting. One of his contemporaries was *Vittore Carpaccio* (d. after 1519), a lively pictorial narrator, and to his school belonged *Cima da Conegliano* (who flourished about 1489-1508), *Catena*, and *Marco Marziale*.

The first of the great masters was *Giorgione* (*Barbarelli*, 1477?-1511), but unfortunately few of his works are authenticated (the most important being a Madonna with SS. Francis and Liberale, at Castelfranco, a portrait at Rovigo, and a landscape in the Manfrin Gallery). The peculiar glow of his colouring, an attribute which seems rather to be natural to him than acquired from others, imparts even to his isolated half-figures an unwonted life and poetical charm. The first artist who fully developed that type of female beauty in which a simple and natural enjoyment of life is so admirably expressed, was *Jacopo Palma* (*Vecchio*, 1480-1528). Surpassing all his fellows in reputation, in fertility, and in the length of his career, next comes the great *TIZIANO VECCELLO* (1477-1575). His finest frescoes are in the Scuola del Santo and Scuola del Carmine at Padua, and though most of his oil-paintings are distributed throughout the galleries of Europe, several of his most striking works, especially in the province of religious composition, are still preserved at Venice.

Such was the vitality and vigour, and so great the resources of the Venetian School at this period, that even masters of secondary importance frequently produced works of almost unrivalled excellence. Those who chiefly call for notice are *Sebastiano del Piombo* (1485-1547), who was afterwards influenced by the fascinating proximity of Michael Angelo, *Rocco Marconi*, *Lorenzo Lotto*, *Bonifazio*, *Giovanni Antonio* (*da*) *Pordenone* (d. in 1539), whose carnation tints are unsurpassed, and *Paris Bordone* (1500-70), whose portraits rival those of Titian. A prominent master of a somewhat younger generation was *Jacopo Tintoretto* (*Robusti*, 1512-94), who squandered his eminent abilities on superficial works, and in his eagerness for effect threw away the rich golden tints which formed a distinctive characteristic of his school. *Paolo Caliari*, surnamed *Veronese*, (1528-86), on the other hand, though more material in his conceptions, and frequently confining himself to mere representations of actual life, was a faithful adherent to the traditions of his predecessors. Among the last masters of note were the *Bassano's*, *Palma Giovane*, and *Padovanino*, after whose time the Venetian school became extinct. In the 18th cent., however, we must mention *Tiepolo* (d. 1770), a spirited decorative painter. *Antonio Canale*, an architectural painter, and his pupil *Canaletto* (properly *Bern. Belotto*), who were much admired by their contemporaries.

*Venice*, situated in 45° 25' N. latitude, lies 2½ M. from the main land in the *Lagune*, a shallow part of the Adriatic about 25 M. in length and 9 M. in width. The 15,000 houses and palaces of Venice are situated on three large and 114 small islands, formed by 150 canals, connected by 378 bridges (most of them of stone), and altogether about 7 M. in circumference. The population which had dwindled from 200,000 to 96,000 after its dissolution as an independent state (1797), amounts now to 128,000, of whom, however, one-fourth are paupers. Its trade has again been on the increase since the middle of the century, and Venice is now one of the greatest seaports on the Adriatic.

The lagune are protected from the open sea by long sand-hills (*lidi*), which again are strengthened by means of bulwarks (*murazzi*)

of solid masonry, averaging 30 ft. in height and 40-50 ft. in width. On the side next the Lagoon the Murazzi are perpendicular, while towards the sea they descend in four terraces. The Murazzi on the Lido from *Palestrina* to *Chioggia* (p. 245) date from the last period of the republic. The *Diga of Malamocco*, a pier which extends for a distance of  $1\frac{1}{4}$  M. into the open sea, was constructed by the Austrian government after 1825, in order to prevent the harbour from becoming choked with mud. The Lagoons are connected with the open sea by means of four entrances, of which those of the *Lido* and *Malamocco* alone are available for vessels of heavy tonnage. The steamers usually enter by the *Porto di Lido*, but in stormy weather occasionally by that of *Malamocco*.

The Lagoons are called either '*lagune vive*', or '*lagune morte*', about one half of them belonging to each class. In the former the tide rises and falls about 2 ft.; the latter, shallower, and situated nearer the mainland, are unaffected by the tide. Venice is situated in the '*laguna viva*'. At high water innumerable stakes, protruding from the water in groups of the most varied form, mark the situation and shape of the low sand-islands which surround the city on every side, forming a complicated network of navigable channels, most of them accessible to small boats only.

Most of the houses rise immediately from the canals (*rii*), or are separated from them by narrow streets only, here called (as in Spain) *calli* (sing. *il calle*), and paved with broad slabs of stone, or sometimes with brick or asphalt. These lanes form a labyrinth from which the stranger will frequently find it difficult to extricate himself; none, however, but walkers can form an adequate acquaintance with the picturesque nooks of the city and the characteristics of its inhabitants. The following description is so arranged that many of the sights can be visited on foot, but all the principal buildings may also be visited by boat. Gondolatravelling is very pleasant, and is of course far preferable to walking for expeditions of any length.

The **\*\*Piazza of St. Mark**, usually called '*La Piazza*' (the other small open spaces being '*campi*'), is a square paved with blocks of trachyte and marble, 192 yds. in length, and on the W. side 61, and on the E. 90 yds. in breadth. On three sides it is enclosed by imposing structures, which appear to form one vast marble palace, blackened by age and exposure to the weather; on the E. it is bounded by the Church of St. Mark and the *Piazzetta* (p. 218). These palaces were once the residence of the 'procurators', the highest officials of the republic, whence their appellation of **Procurazie**: N. the *Procurazie Vecchie*, erected at the close of the 15th cent. by *Bartolommeo Buon*; S. the *Procurazie Nuove*, begun by *Scamozzi* in 1584, now the *Palazzo Reale*, containing handsome modern apartments and several good pictures (entrance under the New *Procurazie*; custodian 1 fr. for 1-3 pers.); the modern edifice on



the W., called the *Atrio*, or *Nuova Fabbrica*, was erected under Napoleon in 1810 on the site of the former church of S. Geminiano. The ground-floors of these structures consist of arcades, in which the cafés and shops mentioned at pp. 206, 208 are established. — The Piazza of St. Mark is the grand focus of attraction at Venice. On summer evenings, after sunset, all who desire to enjoy fresh air congregate here, and the prince, as well as the humblest citizen, may be seen enjoying his sorbetto in front of the cafés. The scene is most animated towards 8 p. m., especially on the evenings when the military band plays (Sundays, and generally on Tuesdays and Thursdays also, 8-10 o'clock), when the Piazza is sometimes thronged until after midnight. On other evenings the crowd disperses about 10 o'clock. In winter the band plays on the same days, 2-4 p. m., and the Piazza is then a fashionable promenade. Early in the morning a few visitors to the cafés may be seen sipping their coffee, but these are rarely natives of Venice. The Venetians themselves are seldom visible at a very early hour, and the Piazza is comparatively deserted except at the hours just mentioned. The Piazza with its adjuncts (the Procurazie, St. Mark's, the Palace of the Doges, Piazzetta, and Lagune) presents a strikingly imposing appearance by moonlight.

A large flock of PIGEONS resorts daily to the Piazza at 2 p. m. to be fed at the expense of the city. According to tradition, Admiral Dandolo, while besieging Candia at the beginning of the 13th cent., received intelligence from the island by means of carrier-pigeons, which greatly facilitated its conquest. He then despatched the birds to Venice with the news of his success, and since that period their descendants have been carefully tended and highly revered by the citizens. They nestle in the nooks and crannies of the surrounding buildings, and are generally seen in great numbers in the evening, perched on the façade of St. Mark's.

The three lofty *Flagstaffs* (*Pili*) of cedar in front of the church, rising from pedestals resembling candelabra, executed in 1505, once bore the banners of the kingdoms of Cyprus, Candia, and the Morca, to commemorate their subjugation by the republic. On Sundays and festivals the Italian colours are now hoisted here.

\*\*S. Marco (Pl. 17; E, 4), the Church of St. Mark, the tutelary saint of Venice, whose remains are said to have been brought by Venetian citizens from Alexandria in 828, was erected in 976-1071 in the Romanesque-Byzantine style peculiar to Venice, and decorated with lavish and almost Oriental magnificence during subsequent centuries. The façade received some additions in the Gothic style in the 14th cent. The form of the edifice is that of a Greek cross (with equal arms), covered by a Byzantine dome in the centre and one at the extremity of each arm. Around the W. and part of the N. transept is a vestibule covered by a series of smaller domes. Externally and internally the church is adorned with five hundred columns of marble, the capitals of which present an exuberant variety of styles. The most remarkable are eight detached columns in the vestibule—four at each of the lateral portals on the

W. side, with peacocks and lions. The mosaics cover an area of 45,790 sq. ft., and the interior is also profusely decorated with gilding, bronze, and Oriental marble. The aggregate effect is highly picturesque and fantastic. The mosaics, some of which are said to have been executed as far back as the 10th cent., belong chiefly to the 12th and 16th centuries, and afford interesting evidence of the aptitude of the earliest Venetians for pictorial composition. — Since 1807 St. Mark's has been the cathedral of Venice, a dignity which formerly belonged to S. Pietro di Castello (p. 244).

Over the principal portal are Four Horses in gilded bronze, 5 ft. in height, which were long supposed to be the work of a Greek master (*Lusippus*), but are now believed to be of Roman workmanship, probably of the time of Nero. They are finely executed, and are especially valuable as the sole existing specimen of an ancient quadriga preserved intact. They probably once adorned the triumphal arch of Nero, and afterwards that of Trajan. Constantine caused them to be conveyed to Constantinople, whence the Doge Dandolo brought them to Venice in 1201. In 1797 they were carried by Napoleon I. to Paris, where they afterwards occupied the summit of the triumphal arch in the Place du Carrousel. In 1815 they were brought back to Venice by the Emp. Francis and restored to their former position.

FAÇADE. *Mosaics* in the arches, best surveyed from the steps of the flagstaffs. *Below*, over the principal entrance, the Last Judgment, executed in 1836, on the right the Embarkation of the body of St. Mark at Alexandria, its Disembarkation at Venice, both executed in 1660; on the left the Veneration of the saint, of 1728, and the Church of St. Mark into which the relics are conveyed, of the 13th century. — Above are the four horses in front of the great arched window, on the left and right are four mosaics of the 17th cent., Descent from the Cross, Christ in Hell, Resurrection, Ascension.

ENTRANCE HALL (*Atrio*), the whole breadth of the church: the vaulting consists entirely of MOSAIC, of which the *older* portion (12th cent.) represents Old Testament subjects, beginning on the right: 1st Dome, Creation of the World, and Fall of Man; in the following arch the Deluge; 2nd Dome, over the entrance to the church, St. Mark, executed in 1545 from a design by Titian. — The three *red slabs* commemorate the reconciliation between the Emp. Fred. Barbarossa and Pope Alexander III., which was effected here on 23rd July, 1177, through the mediation of the Doge Seb. Ziani. According to an old tradition the emperor kneeling before the pope said, '*non tibi sed Petro*', to which the pope replied, '*et mihi et Petro*'. — In the next arch, Noah, and the Building of the tower of Babel; 3rd Dome, History of Abraham; 4th (corner) Dome, Joseph's dream, Joseph sold by his brethren, and Jacob's lament; 5th and 6th Domes, Joseph in Egypt; 7th Dome, History of Moses.

INTERIOR, 86 yds. in length, 70 yds. in width, with five domes and an apse. The large *Entrance Doors* are of bronze, that on the right in the Byzantine style, and that in the centre of the 12th cent. Above the latter, *Mosaics*: Christ, Mary, and St. Mark; in the three domes of the nave are represented God with David, Solomon and the prophets, the Ascension of Christ, the Descent of the Holy Ghost, and the Holy Trinity. The beautiful stone mosaic *Pavement* of the 12th cent. is smooth and slippery, and very uneven at places from having settled. By the screen, on the right and left of the approach to the high altar, are two *Pulpits* in coloured marble, each placed on seven columns in accordance with the ancient custom. On the *Screen* are fourteen statues in marble (of 1393), representing St. Mark, Mary, and the twelve Apostles, with a bronze Crucifix. — The LEFT TRANSEPT contains two handsome bronze *Candelabra* of 1520; above, on the left, a *Mosaic* of 1542, representing the genealogy of Mary; adjoining it are some remarkably fine Byzantine mosaics. — The RIGHT TRANSEPT also contains two bronze *Candelabra*, of the end of the 16th cent.

On the arched *Parapet* on each side of the *Choir* are three reliefs in bronze, by *Sansovino* (d. 1570), representing events from the life of St. Mark. On the parapet of the *Stalls* are the four Evangelists in bronze, by *Sansovino*, and four Fathers of the church, by *Catiari* (1614).

The *High Altar* (*Allare Maggiore*) stands beneath a canopy of verde antico, borne by four columns of marble (with reliefs of the 11th cent.). The *Pala d'Oro*, enamelled work with jewels, wrought on plates of gold and silver, executed at Constantinople in 1105, constitutes the altar-piece, which is uncovered on high festivals only, or, at other times, for a fee of 6 fr. (It was originally intended to embellish the *front* of the altar.) Under the high altar repose the relics of St. Mark, as the marble slab at the back records. — Behind the high altar is a second altar with four spiral columns of alabaster, of which the two white ones in the middle are semi-transparent, and are said to have once belonged to the Temple of Solomon.

The *SACRISTY* (*Sagrestia*), to the left, contains some fine mosaics on the vaulting; cabinets with inlaid work of 1523; on the door leading from the high altar, reliefs in bronze by *Sansovino* (1556); to the right of the handle is the portrait-head of the maker of the door; in the right corner the head of Titian. Entrance to the Crypt, see below.

To the right of the high altar: *CAPPELLA DI S. CLEMENTE*, with altar-relief of the 16th cent., representing SS. Nicholas, James, and Andrew, and the Doge Andr. Gritti.

In the right aisle, close to the principal entrance, is the *BATTISTERO*, in the centre of which is a large bronze font of 1545; above it is John the Baptist. Also the monument of the Doge And. Dandolo (d. 1354). The stone over the altar is from Mt. Tabor. To the left of the altar the head of John the Baptist, of the 15th cent.; below it is the stone on which he is said to have been beheaded. — From the Baptistery we enter the *CAPPELLA ZENO*, containing the handsome monument of Cardinal Giambattista Zeno (d. 1501), wrought entirely in bronze; on the sarcophagus is the figure of the cardinal, over life-size; below are the six Virtues. The altar and canopy are also cast in bronze, with the exception of the frieze and the bases of the columns. Over the altar are groups in bronze, of the Madonna, St. Peter, and John the Baptist; on the altar itself a relief of the Resurrection. To the right and left two lions in coloured marble.

In the right transept is the entrance to the *Treasury* (*Tesoro di S. Marco*, open on Mondays and Fridays 12½-2 o'clock, except on festivals), containing candelabra by Benvenuto Cellini; cover of the books of the Gospels from the church of St. Sophia at Constantinople, decorated with gold and jewels; a crystal vase with the 'Blood of the Saviour'; a silver column with a fragment of the 'True Cross'; a cup of agate with a portion of the 'skull of St. John'; the sword of the Doge Morosini; cuneiform writings from Persepolis; an episcopal throne of the 7th cent., said to be that of St. Mark; and a number of other curiosities.

The *CRYPT*, freed from water and restored in 1868 (but still often under water), also deserves a visit; open 12-2 o'clock, entrance by the first door to the right in the Sacristy (see above); at other hours it is shown by the sacristan. To the right a well executed Christ in relief by *Sansovino*.

A walk (sacristan ½ fr.) round the *GALLERY* inside the church is strongly recommended in order that the mosaics may be more closely inspected. The ascent is from a door to the right in the principal portal, which the sacristan opens. The gallery on the outside of the church should then be visited for the sake of examining the bronze horses.

On the N. side of St. Mark's, under the arch of the transept, is a marble sarcophagus borne by lions, executed by Borrò, and containing the remains of *Damiele Manin*, the president of the republic in 1848, which were brought from Paris in 1868. — On the

wall here are placed numerous ancient Byzantine reliefs in marble (Madonna, etc.), brought from the East by Venetians.

On the S. side of the church (comp. p. 218) are two short square \**Columns*, inscribed with Greek characters, brought hither in 1256 from the church of St. Saba at Ptolemais which was destroyed by the Venetians. From the *Pietra del Bando*, a block of porphyry at the S.W. corner, the decrees of the republic were anciently promulgated. Two curious *Reliefs* in porphyry are immured by the entrance to the Palace of the Doges, representing two pairs of knightly and armed figures embracing each other. They are said also to have been brought from Ptolemais, and have given rise to a great variety of conjectures, the most recent being that they represent four emperors of Byzantium of the 11th cent., and once adorned the pedestal of an equestrian statue.

Opposite St. Mark's, to the S.W., rises the isolated square \**Campanile* (*Il Campanile di S. Marco*), 322 ft. in height, which is always open to the public (doorkeeper 10 c. on entering). It was founded in 911, restored in 1510, and finally completed in 1591, the upper part and the spire having been constructed by *Bartolommeo Buon*. The ascent by a winding inclined plane of 38 bends, and finally by a few steps, is easy and well-lighted. The watchman at the summit is provided with a telescope and opens the door to the second gallery for a trifling gratuity. The \*view comprises the city, the Lagune (comp. p. 212), the Alps, and part of the Adriatic; W. the Monti Enganei near Padua (p. 263), rising above the Lagune; E. in clear weather the Istrian Mts., rising above the Adriatic, a magnificent spectacle towards sunset. The ascent of the campanile is recommended to the traveller, both for a preliminary survey, and as an appropriate termination to his visit to Venice. — The \**Bronze Doors* of the *Loggella*, or vestibule (erected by *Sansovino* in 1540), on the E. side of the campanile, cast in 1750, deserve inspection. This chamber once served as a waiting-room for the procurators, whose office it was, during the sessions of the great Council, to command the guards. It is now used for public auctions and 'tombola' (lottery) drawings. The bronze statues of Peace, Apollo, Mercury, and Pallas, and the reliefs on the coping are by *Sansovino*.

The **Clock Tower** (*La Torre dell' Orologio*), on the opposite side, at the E. end of the old Procurazie, erected by *Pietro Lombardo* in 1496, rises over a gateway, resembling a triumphal arch, restored in 1859. On the platform are two Vulcans in bronze, who strike the hours on a bell. The custodian of the clock, who lives in the building, shows and explains the mechanism (fee 1/2 fr.). The entrance is under the archway to the left, where it is indicated by a notice. The *Merceria* (p. 208), the principal commercial street of Venice, quits the Piazza of St. Mark here, and leads to the *Ponte Rialto* (p. 230).

From the S.E. corner of the Piazza of St. Mark to the Lagnne, extends the **\*Piazzetta** (Pl. F, 4), which is bounded on the W. by the former Library, and on the E. by the Palace of the Doges.

The **\*Library** (*Antica Libreria di S. Marco*), which now belongs to the royal palace, begun by *Samsonino* in 1536, is a magnificent structure of the 16th cent., and one of the finest secular edifices in Italy. — In the direction of the Lagnne are two *Granite Columns*, brought by the Doge Michiel from Syria in 1120, and erected here in 1180; one of them bears the Winged Lion of St. Mark, the emblem of the tutelary saint of Venice; the other is surmounted by St. Theodore on a crocodile, the patron of the ancient republic, placed there in 1329. This used to be the place of execution, and is now the headquarters of the gondoliers (comp. p. 206). On the Lagnne, between the Library and the *Royal Garden*, is situated the *Zecca* or *Mint*, which was also built by Sansovino in 1536.

The **\*\*Palace of the Doges** (*Palazzo Ducale*, Pl. 60), the W. side of which, 82 yds. in length, looks towards the Piazzetta, and the S. side, 78 yds. in length, towards the Molo, was founded in 800, afterwards destroyed five times, and as often re-erected in a style of greater magnificence than before. The present sumptuous structure, in the Venetian-Gothic style, was begun about 1350 by *Filippo Calendario*, but was not completed till 1442. The whole building is undergoing restoration. On the W. and on the S. side the palace is flanked by two colonnades of 107 columns (36 below, 71 above), one above the other, with pointed vaulting. The mouldings of the upper colonnade, '*La Loggia*', are remarkable for their richness. From between the two columns of red marble (9th and 10th from the principal portal) in the Loggia, the Republic anciently caused its sentences of death to be published. The capitals of the short columns below are richly decorated with foliage, figures of men and animals, etc. On the corner-pillar by the portal are interesting representations of Numa Pompilius, Scipio, the Emperor Trajan judging the cause of a woman, and of Justice, with inscriptions. Above these is a group representing the Judgment of Solomon. At the corner towards the Lagnne, Adam and Eve. (Porphry-reliefs on the corners to the left, see p. 217.) The fine Portal adjoining St. Mark's, constructed of marble of different colours in 1439, in the Gothic style with a Renaissance tendency, and recently restored, is called the *Porta della Carta*, from the placards formerly exhibited here to announce the decrees of the republic. Justice is represented in the tympanum.

The **\*COURT**, begun at the close of the 15th cent. by *Antonio Bregno* and *Antonio Scarpagnino*, but only partially completed, has an admirable finished façade on the E. side. The unsymmetrical form of the court was probably rendered necessary by the previous existence of surrounding buildings. Within one of the

highest windows to the left was the prison of the poet Count Silvio Pellico in 1822, before he was conveyed to the Spielberg at Brünn. In the centre of the court are two *Cistern-fronts* in bronze. To the right on the façade of the *Clock Tower*, is a statue of the Venetian general Duke Francis Maria I. of Urbino (d. 1625). The other statues are antique, but freely restored. The charming small façade farther E., perhaps the best, is by *Guglielmo Bergamusco* (1520).

The \**Scala dei Giganti*, the flight of steps by which the palace is entered, derives its name from the colossal statues of Mars and Neptune at the top, executed by *Sansovino* in 1554. It was on the highest landing of these steps that the coronation of the doges used to take place. Opposite the landing are statues of Adam and Eve, by *Antonio Rizzo* (1462).

The \*INTERIOR of the Ducal Palace (admission, see p. 209) also forms a noble specimen of Venetian art. Had not the fire in 1577 destroyed so many paintings, we should have been able here to trace the whole progress of Venetian art during its golden era. The earliest Venetian painters devoted their energies to the church of St. Mark, but the great masters of the 15th and 16th cent. were chiefly occupied in embellishing the Palace of the Doges. Their works having unfortunately perished, the edifice now forms a museum of later masters only, such as *Tintoretto*, *Panna Giovane*, and *Paolo Veronese*, but, nevertheless, it still presents a brilliant and most attractive array of the Venetian painters, so far as their energies were enlisted in the service of the state.

We ascend the *Scala dei Giganti*. Around the upper colonnade are placed the busts of a number of Venetian scholars, artists, and doges. The first staircase is the richly decorated *Scala d'Oro*, constructed by Sansovino and completed in 1577, which was once accessible to those only whose names were entered as Nobili in the Golden Book. By this staircase we ascend on week-days (admission 1 fr., payable at the first landing) direct to the second or upper story, where we enter the Atrio Quadrato. In this case we first visit the apartments described at p. 221, and afterwards descend to the first or middle story.

The next staircase, the *Scala dei Censori*, which forms the entrance to the apartments on Sundays and festivals, first leads to the FIRST FLOOR, which contains the *Library* (on the left; p. 221), the *Sala del Maggior Consiglio* (in a straight direction; see below), and the *Archaeological Museum* (on the right; p. 221).

1. \**Sala del Maggior Consiglio* (door generally open; if not, ring). In this large hall (55 yds. long, 26 yds. broad, 47 ft. high), the Nobili, whose names were entered in the 'Golden Book', and who constituted the highest authority in the Republic, formerly sat. In 1848-49 the deputies under the Dictator Manin also assembled here. On the frieze are the portraits of 76 doges, beginning with Angelo Partecipocio (d. 827); on the walls 21 large pictures by *Bassano*, *Paolo Veronese*, *Tintoretto*, etc., painted to commemorate the achievements of the Republic. On the E.

wall *Jac. Tintoretto's Paradise*, said to be the largest oil-painting in the world, containing a perplexing multitude of figures. — The HISTORICAL PICTURES consist of two series. The first illustrates in a somewhat boastful style the life of the Doge *Sebastiano Ziani* (1173-79), who accorded an asylum to Pope Alexander III. when at variance with the Emperor Frederick Barbarossa, and (in league with the towns of Lombardy) resisted the imperial demands. The second series depicts the exploits of the Doge *Enrico Dandolo* (p. 209).

The first series begins on the upper part of the wall to the right of the entrance, and runs to the left in the direction of the opposite end of the rooms: 1. Meeting of Pope Alexander III. and the Doge Ziani at the Monastery della Carità, and — 2. Parting audience of the ambassadors of the Pope and the Doge on their departure for Parma, both by *pupils of Paolo Veronese*; 3. (over the window) Presentation of the consecrated candle, by *Leandro Bassano*; 4. Ambassadors of the Pope and the Doge presenting to Fred. Barbarossa at Pavia a petition for a cessation of hostilities, by *Jacopo Tintoretto*; 5. The Pope presenting a sword to the Doge, by *Franc. Bassano*; 6. (over the window) Departure of the Doge with the papal benediction, by *Paolo Fiammingo*; 7. Battle of Salvore (Pirano), defeat of the Imperial fleet, and capture of Otho, 1177, by *Dom. Tintoretto*; 8. (above the door) The Doge presenting the son of the Emperor to the Pope, by *Andrea Vicentino*; 9. Pope Alexander grants permission to the captive Otho to repair to his father in order to negotiate a peace, by *Palma Giovane*; 10. Fred. Barbarossa kneeling before the Pope (p. 215), by *Federigo Zuccheri*; 11. (over the door) Conclusion of peace between the Pope, the Doge, and the Emperor, at Ancona, by *Girolamo Gambarato*; 12. The Pope presents gifts to the Doge, including the ring, the symbol of supremacy with which the Doge annually 'wedded the Adriatic', 1177, by *Giulio dal Moro*.

The cycle of pictures in honour of the Doge Dandolo also begins on the entrance wall, to which we return after having inspected the first series. They run from left to right as follows: 1. The Doge and French Crusaders swear an oath of alliance at St. Mark's in 1201, for the purpose of liberating the Holy Land, by *Giov. Le Clerc*; 2. Storming of Zara in 1202, by *Andrea Vicentino*; 3. Surrender of Zara to the Crusaders in 1202, by *Dom. Tintoretto* (placed over the door to a balcony, which affords a fine view of the Lagoon and the islands of S. Giorgio and Giudecca); 4. Alexius, son of the dethroned Greek Emp. Isaac Angelus, invoking the aid of the Venetians in behalf of his father in 1202, by *Andrea Vicentino*; 5. Taking of Constantinople by the Venetians and French, 1204, by *Dom. Tintoretto*; 6. Second taking of Constantinople, 1204, by *Dom. Tintoretto*; 7. Count Baldwin of Flanders elected Greek Emp. in the church of St. Sophia, 1204, by *Andr. Vicentino*; 8. Coronation of Baldwin by the Doge Enrico Dandolo, 1204, by *Aliense*. (Above this, a black tablet on the frieze among the portraits of the Doges bears the inscription: *Hic est locus Marini Falethri decapitati pro criminibus*; comp. p. 209.) — Lastly, as an additional picture: 9. Return of the Doge Andr. Contarini from the victory over the Genoese fleet near Chioggia, 1378, by *Paolo Veronese*. — The ceiling paintings, which also represent battles fought by the Venetians, are by *Paolo Veronese*, *Bassano*, *Jac. Tintoretto*, and *Palma Giovane*; the Fauc of Venice (next to the entrance) is by *Paolo Veronese*.

The CORRIDOR contains a bust of the Emp. Francis. — *The Sala dello Scutinio*, or *Voting Hall*, is decorated similarly to the preceding saloon. On the frieze are the portraits of 39 doges, down to Lodovico Manin (1797). *On the wall of the entrance*: Last Judgment, by *Palma Giovane*. *On the left wall*, towards the Piazzetta: 1. Victory of the Venetians over King Roger of Sicily in 1148; 2. Subjugation of Tyre under Domenico Michieli in 1125; 3. (over the door to the balcony, which affords a good survey of Sansovino's library) Victory of Dom. Michieli over the Turks at Jaffa in 1123; 4. Victory in the lagoons over Pepin, son of Charlemagne, in 811; 5. Siege of Venice by Pepin in 809. — *Opposite the entrance*: Monument to the Doge Francesco Morosini 'Peloponnesiacus', who in 1684-90 conquered the Morea and Athens (p. 210). — *On the right wall*: 6. Lazzaro Mocenigo conquers the Turks near the Dardanelles in 1657; 7. (over the

window towards the court): Destruction of Margaritino in 1571; 8. Battle of Lepanto, in the same year; 9. (over the second window) Conquest of Cattaro in Dalmatia during the war against Genoa in 1378; 10. Re-capture of Zara in 1346. — On the *ceiling* several other scenes from the history of the Republic.

The celebrated **Library of St. Mark**, containing many rare MSS., and the valuable and extensive *Collection of Coins* are open to the public on Wed. at 2.45 p.m. only. The visitor should ask to be shown the *“Breviario Grimani*, embellished with 110 miniatures, some of which are attributed to *Menting*, an important work of the Flemish school of the end of the 15th cent. The library is open daily for purposes of study, 9-3, but closed on Sundays and festivals, and during October.

II. The **Archæological Museum**, established in 1846 in the apartments in which the doges resided till the close of the 16th cent., contains ancient sculptures in marble, of Greek and Roman origin, most of which were brought home as booty by the Venetians from their various campaigns.

I. Room: 90. Colossal Minerva; \*85. Bacchus and a satyr; \*80. Apollo reposing, perhaps once accompanied by a second figure, as the preceding group would seem to indicate; \*51, 56. Muses from the Amphitheatre of Pola; 46. Dancing Silenus; 35. Cupid bending his bow; 32. Boy with a goose, a fountain-figure; 29. Venus and Cupid.

II. Room: 169. Hermaphrodite, fragment of a spirited group; \*148. Ganymede, robbed by the eagle, freely restored; \*153. Gaul sinking from exhaustion; \*145. Dead Gaul lying on his shield; \*144. Gaul, in his last desperate struggle; these three resemble the Dying Gladiator in the Capitol at Rome and similar statues at Naples, and probably belonged to the groups dedicated to the Acropolis of Athens by Attalus, King of Pergamos, about B.C. 239. after his victory at Sardes in Asia Minor over the invading Gauls; 138. Leda with the swan; 113, 187. Two comic masks; 102. Replica of the Cupid, bending his bow, of Praxiteles, in Parian marble. — The chimney-piece dates from the end of the 15th cent.

III. Room: old maps; among them the celebrated *“Map of the World by the Camaldulensian monk Fra Mauro, 1457-59; six tablets of carved wood by Haji Mehemet of Tunis (1559), representing the globe; Plans of Venice of 1500 and 1728.* The next room is entered by a door to the right. — IV. Room: 190. Warrior sacrificing; 195. Fragment of a sarcophagus, rape of Proserpine; 196. Another with the destruction of the children of Niobe; 220. Greek tomb relief; 222. Centaurs fighting, and a female Centaur asleep; 231. Fragment of a Greek frieze, battle of the Greeks and Trojans around the ships; 239. Four-sided base of a candelabrum. We now return to the 3rd room, from which the next is entered to the right. — V. Room: chiefly busts of emperors, the best being 292. Vitellius; 250, 299. Bacchantes.

The **UPPER FLOOR** contains the apartments in which the authorities of the republic once held their meetings, and which are still in a great measure preserved in their ancient splendour. The following description begins by the entrance from the *Scala dei Censori*. (On the upper landing we turn to the left; to the right is the Istituto di Scienze.) — Those who ascend by the *Scala d'Oro* (the staircase used on week-days, comp. p. 219) first enter the Atrio Quadrato, from which they proceed to the Sala delle Quattro Porte, Sala del Senato, and the following rooms, till they reach the Anticollegio, whence they visit the Stanza dei Tre Capi del Consiglio and the remaining rooms in the reverse order from that given below. They then descend from the Sala della Bussola by the *Scala dei Censori* to the first floor.

I. **Sala della Bussola**, once the ante-chamber of the three Inquisitors of the Republic; by the entrance is an opening in the wall, formerly decorated with a lion's head in marble, into the mouth of which (*Bocca di Leone*) documents containing secret information were formerly thrown. This apartment contains two pictures by *Aliense*: on the right, Taking of Brescia, 1426, and on the left, Taking of Bergamo, 1427; chimney-piece by *Sansovino*. — In a straight direction we next enter the —



II. **Sala del Consiglio dei Dieci.** On the wall of the entrance, Pope Alexander III. and the Doge Ziani, the conqueror of Emp. Fred. Barbarossa, by *Bassano*; opposite, the Peace of Bologna, concluded in 1529 between Pope Clement VII. and Emp. Charles V., by *Marco Vecellio*; on the ceiling near the entrance, portraits of an old man and a handsome woman, by *Paolo Veronese*, restored. Large modern ceiling paintings. Fine pulto frieze. — We now retrace our steps through the Sala della Bussola and enter (to the right) the —

III. **Stanza dei Tre Capi del Consiglio**, with ceiling-paintings (an angel driving away the vices) by *Paolo Veronese*; chimney-piece by *Sansovino*; caryatides by *Pietro da Salò*; on the left, Madonna and Child, two saints and a dog as donor, by *Vinc. Catena*. — A passage leads hence to the —

IV. **Atrio Quadrato**, into which the *Scala d'Oro* leads, with a ceiling-painting by *Tintoretto*, representing the Doge Priuli receiving the sword of justice. On the walls eight portraits of senators.

V. **Sala delle Quattro Porte**, restored in 1869; doors designed by *Palladio*, 1575; right, Verona conquered by the Venetians, 1439, by *Gior. Contarini*; the Doge Ant. Grimani kneeling before Religion, by *Titian*; left, the Arrival of Henry III. of France at Venice, by *Andrea Vicentino*; the Doge Cicogna receiving the Persian ambassadors in 1585, by *Carlotto Catiari*. Magnificent ceiling. — Through the door on the right we now enter the —

VI. **Sala del Senato.** Over the throne, Descent from the Cross by *Tintoretto*; on the wall, the Doge Franc. Venier before Venice, the Doge Cicogna in presence of the Saviour, Venetia on the Lion against Europa on the Bull (an allusion to the League of Cambray, see p. 210), all three by *Palma Giordano*; the Doge Pietro Loredano imploring the aid of the Virgin for Venice, by *Tintoretto*. Ceiling-painting: Venice, Queen of the Adriatic, by *Tintoretto*.

Beyond this room (to the right of the throne) is the ANTE-CHAMBER to the chapel of the doges, containing five pictures of little value. — In the Chapel over the altar a Madonna by *Sansovino*. To the left of the altar: *Paris Bordone*, Pietà; <sup>2</sup>*Paolo Veronese*, Forest landscape with accessories; *Cima da Conegliano* (?), Madonna in a landscape; *Düver*, Mocking of Christ; *Giorgione* (?), Christ in Purgatory; <sup>3</sup>*Bonifazio*, Christ teaching (three pictures brought from the Palazzo Reale in 1875); then (to the right of the door), *Titian*, Crossing of the Red Sea. — We return through the Sala del Senato and enter to the right the —

**Sala del Collegio.** Over the door, the Nuptials of St. Catharine (below, the Doge Franc. Donà); to the left of it, Virgin in glory (with the Doge Niccolò da Ponte), Adoration of the Saviour (with the Doge Alvise Mocenigo), all three by *Tintoretto*; over the throne a memorial picture of the Battle of Lepanto, <sup>2</sup>Christ in glory (below, the Doge Venier, Venetians, St. Mark, St. Justina, etc.), both by *Paolo Veronese*; opposite, the Prayer of the Doge Andrea Gritti to the Virgin, by *Tintoretto*. Ceiling-paintings, Neptune and Mars, Faith, Venetia on the globe with Justice and Peace, all by *Paolo Veronese*.

**Anticollegio:** left, <sup>2</sup>Rape of Europa, by *Paolo Veronese*; Jacob's return to Canaan, by *Bassano*; Forge of Vulcan, Mercury with the Graces, opposite to it Minerva driving back Mars, and Ariadne and Bacchus, all four by *Tintoretto*. Ceiling-painting, Venetia enthroned, by *Paolo Veronese*, much damaged.

The handsome E. side of the Palace of the Doges towards the canal, which presents a more harmonious appearance than the W. side, and has a basement of faceted stone, is connected with the *Carceri* or *Prigioni*, constructed in 1512-97 by Giov. da Ponte, by means of the lofty **Bridge of Sighs** (*Ponte dei Sospiri*; Pl. 97). The *Piombi*, or prisons under the leaden roof of the Palace, were destroyed in 1797; the *Pozzi*, or half-ruined dungeons on the farther side of the narrow canal on the E. side of the Palace.

have been disused since the beginning of the 17th cent. These once dreaded prisons contain absolutely nothing to interest the traveller beyond the historical associations (entrance from the upper story of the Palace of the Doges; see also p. 209). A good survey of the Bridge of Sighs is obtained from the *Ponte della Paglia*, which connects the Molo with the adjacent —

**Riva degli Schiavoni** (Pl. F, G, 4), a quay paved with unpolished slabs of marble, and presenting a busy scene. Sailors of all nations, from the vessels which lie in the vicinity, and numerous idlers, are seen lounging here or congregated at the cafés. From the Riva a view is obtained of the *Giardini Pubblici* (p. 244), situated on the prolongation of the Riva at the S.E. end of the city. If we diverge from the Riva to the left, by the church of *S. Biagio* (Pl. 6), and skirt the broad canal, we soon reach the entrance gate of the —

**\*Arsenal** (Pl. 3; H, 4; admission daily, 9-3, except on Sundays and festivals, on presenting a visiting-card), which at the time of the Republic employed 16,000 workmen, but now 2000 only. The decline of Venice is nowhere so apparent as here. At the outer entrance (handsome gateway of 1460) are the four antique lions, brought here in 1687 from the Piræus; the large one on the left, the body of which is covered with inscriptions no longer legible, is conjectured once to have stood on the battle-field of Marathon.

INTERIOR. On the external wall of the magazine is a monument of Count Schulenburg, a general of the Republic (d. 1747). The *Collection of Weapons*, a great part of which the Austrians carried off in 1866, contains the remains of the *Bucintoro*, a vessel destroyed by the French, from which the Doge was wont annually on Ascension Day to throw the ring (p. 220) into the Adriatic, which he thus symbolically wedded. Here, too, is a marble monument to Admiral Angelo Emo (d. 1792) by *Canova*: opposite to it the suit of armour of Henry IV. of France, presented to the Republic; several trophies of historical interest, banners from the battle of Lepanto, armour of former doges, revolvers and breech-loaders of a primitive description of the 16th cent., a finely executed culverin of steel, adorned with reliefs, instruments of torture, iron helmet of Attila, king of the Huns, model of an ancient Venetian vessel, model of the piles on which Venice is to a great extent built, bust of Napoleon of 1805.

The extensive wharves and workshops are now comparatively deserted. The state-barge used by Victor Emmanuel in 1866 is also shown (additional fee).

The **\*\*Accademia delle Belle Arti** (Pl. 1; D, 5), in the suppressed *Scuola della Carità*, the assembly-hall of this brotherhood, on the Grand Canal, opposite the S. extremity of the iron bridge (p. 228) and  $\frac{1}{2}$  M. from the Piazza of St. Mark, may easily be reached on foot (comp. p. 237). The entrance is in the cloisters, to the left, whence we ascend to the first floor. (Admission, see p. 209.) Permission to copy is easily obtained at the office. The numbers over the doors apply in each case to the next room. — Catalogue, 1 fr.

The gallery contains almost exclusively pictures by Venetian masters. The general public will be most interested in the works of the time of *Bellini* and the following period, as well as in the historical

pictures by *Gentile Bellini* and *Carpaccio* in the XVI. room, exhibiting a lifelike picture of ancient Venice, the brilliant colours of which cause us to forget the poverty of the execution and want of inspiration which characterise the individual figures as well as the groups. It is instructive to compare these paintings with the manner in which Florentine artists of the same epoch arranged their groups and described historical events. Attention must be drawn to the numerous pictures of *Giovanni Bellini* (Nos. 38, 94, and others), representing the assemblage of saints surrounding the throne of the Madonna ('*sacra conversazione*'), to the beauty of the nude figures, and to the powerful and imposing, though not very saint-like male figures. A picture by *Boccaccino da Cremona* (No. 132), a little known master of the earlier school, is one of the best of that period. *Giorgione's Storm at sea* (No. 37) is of doubtful authenticity, and moreover much damaged. *Palma Vecchio* is not represented here by his best works. On the other hand *Rocco Marconi's* Descent from the Cross (No. 405) is one of his finest works. *Titian's* master-piece, the Assumption of the Virgin (No. 24), requires no comment; the glowing rapture of the apostles, the jubilant delight of the angels, the beaming bliss of the Madonna, the magnificence of the colouring, cannot fail to strike the eye of every beholder. The gallery comprises the earliest known work of this master, and his last uncompleted creation: the Visitation, and the Descent from the Cross. The Presentation in the temple (No. 487) is very attractive owing to the spirited character of the grouping, and the beauty of the individual figures. *Bonifazio's* wealth of colour is displayed in the Adoration of the Magi (No. 57), and in the History of the rich man (No. 500). The Miracle of St. Mark (No. 45) by *Tintoretto*, and the Supper in the house of Levi (No. 517), are specially interesting.

Beyond the CORRIDOR, which contains numerous architectural drawings, we pass the 5th and 6th saloons (see p. 22) on the left, and a room without a number on the right, and in a straight direction enter the —

SALA I, DEGLI ANTICHI DIPINTI. Ancient pictures, the handsome original frames of which should be noticed. 1. *Bart. Vivarini*, Mary and four saints, painted in 1464; 4, 6 (belonging to each other), *Marco Basaiti*, St. James and St. Anthony; 5. *Lorenzo Veneziano* and *Franc. Bissolo*, Altarpiece in sections, in the centre the Annunciation, above it God the Father (1358); 8. *Giovanni* and *Antonio da Murano*, Coronation of the Virgin in an assembly of saints, in the centre 'putti' with instruments of torture (1440); 10. *Bartolommeo Vivarini*, St. Matthew (1490); 11. *Vincenzo Catena*, St. Augustine; 14. *Bart. Vivarini*, St. Barbara; 18. *Aloiso Vivarini*, St. Anthony; 21. *Bartolommeo Vivarini*, Sta. Clara; \*23. *Giovanni d'Alemagna* and *Antonio da Murano*, Madonna enthroned, with four Fathers of the church (1446), interesting also on account of the peculiar architecture.

SALA II, DELL' ASSUNTA, the ceiling richly gilded, in the lunettes portraits of painters of the Venetian school, painted in 1849-55, the light unfavourable (the visitor requires to shade his eyes from the glare of the windows). Opposite the staircase: \*24. *Titian*, Assumption (*Assunta*). Farther on, to the right: 25. *Tintoretto*, The Fall of man; \*31. *Marco Basaiti*, Call of the sons of Zebedee (James and John) (1510); 32. *Tintoretto*, Madonna and Child, with three senators; 33. *Titian*, Entombment, his last picture, with which he was engaged at the time of his death, in his 99th year, completed by *Palma Giovane*, as the inscription records; 34. *Bonifazio*, SS. Anthony and Mark; 35. *Titian*, Assumption, his first picture (a comparison of Nos. 35, 24, and 33 is very interesting); 36. *Tintoretto*, Resurrection, and three senators; 37. *Giorgione* (or *Palma Vecchio*), Storm at sea; \*38. *Gior. Bellini*, Madonna enthroned in a richly decorated niche, with (l.) St. Francis, Job, St. John, and (r.) SS. Sebastian, Dominique, and Louis, and three angels on the steps of the throne; this is one of the master's finest works, and is still in its original frame; 39. *Palma Giovane*, Vision from the Apocalypse; 40. *Palma Giov.*, The three horsemen of the Apocalypse; \*45. *Tintoretto*, St. Mark releasing a condemned slave; 47. *Padovanino*, Marriage of Cana; 49. *Bonifazio*, St. Francis and the apostle Paul; 50. *Bonifazio*, The adulteress before Christ; 51. *Tintoretto*,

Portrait of the Doge Luigi Mocenigo; 52. *Catena*, Scourging of Christ; 53. *Tintoretto*, Madonna and Child, with SS. Joseph, Mark, and Jerome, and the portrait of the doge; 54. *Paolo Veronese*, Virgin in glory, below is St. Dominicus, distributing crowns of roses to the pope, emperor and king, doges, cardinals, etc. (difficult to see); 55. *Bonifazio*, Solomon's judgment (1533); 57. *Bonifazio*, Adoration of the Magi; 59. *Palma Vecchio*, Assumption; 60. *Rocco Marconi*, Christ, Peter, and John; 62. *Paolo Veronese*, Scourging of St. Christina; 63. *Tintoretto*, Death of Abel.

SALA III. (adjoining the Assunta on the right): Marble bust of *Giov. Bellini*. Late Venetian masters of no great merit. The following are temporarily placed here: *Cima da Conegliano*, Tobias and the angel; *Vittore Carpaccio* (according to Mr. Crowe; formerly attributed to *Giovanni Bellini*), The Supper at Emmaus, from S. Salvatore (p. 234). The ceiling paintings are by *Tintoretto*.

SALA IV. (to the left, up the staircase), academic assembly-hall, with numerous old drawings, among which those by *Leonardo da Vinci* are particularly interesting; several relics, and an urn containing the right hand of Canova. If we proceed in a straight direction, we next reach the 17th Room, and beyond it the 20th, the 19th, the 18th, and then the 16th, 15th, etc. in inverted order. Our description, however, follows the numbering of the rooms, in accordance with which the pictures are also arranged.

SALA V. (entrance, see p. 224), PINACOTECA CONTARINI, presented in 1843 by Count Contarini: left, 84. *Palma Vecchio*, Christ and the widow of Nain; 94. *Giov. Bellini*, Madonna, painted in 1487; 96. *Marco Marziale*, Supper at Emmaus (1506); 101. *Giov. Bellini*, Madonna; 107. *Sassoferrato*, St. Cecilia; 110. *Andrea Cordegliahi* (or perhaps *Portenone*), Madonna with St. Catharine and St. John; 117. *Pierfrancesco Bissoto*, Body of Christ moured over by angels; 124. *Vinc. Catena*, Madonna with John the Baptist and St. Jerome; 125. *Cima da Conegliano*, Madonna with John the Baptist and St. Peter; 132. *Boccaccio da Cremona*, Madonna and saints; 133. *Polidoro Veneziano*, Madonna and Child, with John the Baptist and an angel; 151. *Jacques Callot*, Market at Impruneta near Florence, a large picture with numerous figures and groups; 164. *Callot*, Pont Neuf at Paris (these two doubtful).

SALA VI, GABINETTO CONTARINI, containing 66 small pictures: Nos. 229, 230, 231, 241, 242, 243, all by *Pietro Longhi*, are interesting as affording samples of the Venetian costumes and habits of last century. Also: 191. *Antonio Badile*, The Samaritan woman at the well; 231-233. *Giov. Bellini*, Allegories. The series of pictures attributed to *Callot* are probably copies. In the centre, Dædalus and Icarus, executed by Canova when 21 years of age.

SALA VII. contains groups of Ethiopian slaves in ebony, bearing Japanese vases, executed about the middle of last century, and other sculptures. — We return through the gallery to the entrance, turn to the right, and by the first door on the right enter the —

SALA VIII., which contains pictures from the Manfrin Gallery (p. 232): 250. *Antonello da Messina*, Portrait; 198. *Savoldo*, Two hermits; 259. *Niccolò di Pietro*, Madonna enthroned (1394); 261. *Moretto*, St. Peter; 264. *Antonello da Messina*, Christ scourged; 269. *Isaac van Ostade*, Snow-clad landscape; 270. Portrait of an old woman, mother of Titian (?); 272. *Marescalco*, Three saints; 273. *Mantegna*, St. George; 274. *Jan Steen*, Genre-picture (1660).

SALA IX. (long corridor): 280, 281. *Hondekoeter*, Hen and chickens, Victorious cock; 295. *Tintoretto*, Portrait of Antonio Capello; 298. *Michelangelo Caravaggio*, Chess-players; 301. *Titian* (?), The master's mother; 306. *Tinetti*, Portrait; 312. *Lorenzo Canovizio*, Christ in the house of the Maries; 313. *Bellini*, Madonna; 315. *Corn. Engelbrechtsen*, Crucifixion; 318. *Greg. Schiavone*, Madonna; 319. *Titian*, Portrait of Jacopo Soranzo; 324. *Portenone*, Angels among clouds; 326. *Bonifazio*, Madonna and saints; 332. *Girolamo Santacroce*, Madonna and Child with saints; 337. *Bissoto*, Madonna and four saints; 338. *Miereveldt*, Portrait of a general; 349. *Antonello da Messina*, Madonna; 350. *Titian*, Portrait of Priamo da Lezze;

352. *Tommaso da Modena*, St. Catharine (1351). On the opposite wall: 356. *Antonello da Messina*, Madonna. — We now pass through the first door and turn to the left into the —

SALA X.: 361. *Montagna*, Madonna and saints; 365. *Andrea Schiavone*, Madonna and Child with the infant John and three saints; \*366. *Titian*, John the Baptist in the wilderness; 367. *Bassano*, Holy Family; 368. *Bonifazio*, Adoration of the Magi; \*372. *G. Bellini*, Madonna and the Child asleep.

SALA XI. and XII. chiefly contain early Italian masters of the 13th and 14th centuries, interesting to the student of art.

SALA XIII. PINACOTECA RENIER (presented in 1850 by the widow of Count Bernard Renier): *Francesco Vecellio* (brother of Titian), Madonna and Child with John the Baptist; 421. *Cima da Conegliano*, Madonna and Child; \*424. *Giov. Bellini*, Madonna with St. Paul and St. George; 425. *Tintoretto*, The adulteress before Christ; \*429. *Cima*, Entombment; 432. *School of L. da Vinci*, Jesus and the scribes; \*436. *Giov. Bellini*, Mary, Magdalene, and Catharine.

SALA XIV.: \*446. *L. Bassano*, Adoration of the Shepherds; \*452. *Garofalo*, Madonna transfigured and four saints (1518); \*456. *Cima*, Christ with SS. Thomas and Magnus; 464. *Tintoretto*, Senator; 465. *Titian*, Portrait of Antonio Capello (1523; see also above).

SALA XV.: *Canova's* original model of the group of Hercules and Ly-chas; 473. *Pietro da Cortona*, Daniel in the lions' den; 481. *Padovanino*, Descent of the Holy Ghost; 486. *Pordenone*, Madonna of Carmel and saints; \*487. *Titian*, Presentation in the Temple; 488. *Vittore Carpaccio*, Circumcision (1510); 489. *Paolo Veronese*, Salutation; \*490. *Pordenone*, S. Lorenzo Giustiniani, John the Baptist, SS. Francis and Augustine, and three other figures; \*492. *Paris Bordone*, The fisherman presenting the doge with the ring received from St. Mark; 493. *Carlo Caliari*, Raising of Lazarus; 494. *L. Bassano*, Same subject; 495. *Rocco Marconi*, Descent from the Cross; \*500. *Bonifazio*, Banquet of Dives; 503. *Tintoretto*, Madonna and Child with four senators; 505. *Bonifazio*, Saviour and saints (1530); 516. *Bonifazio*, Christ and the apostles; \*519. *Paolo Veronese*, Madonna and saints; 524. *Bonifazio*, Slaughter of the Innocents.

SALA XVI.: 529. *Gentile Bellini*, Miraculous finding of a fragment of the 'True Cross' in the canal, originally painted, like the two other large pictures on canvass, Nos. 543 and 555, for the Scuola di S. Giovanni Evang. (1500), where a relic of the Cross was formerly revered; the walls were hung with these pictures in the same way as with tapestry, a circumstance which accounts for many peculiarities in the composition. 533, 537, 539, 542, 544, 546, 549, 552, 554, 560. \**Vittore Carpaccio*, History of St. Ursula, painted in 1475-1515 in ten large pictures, an almost too simple narration of the legend, but interesting on account of the admirable perspective and faithful rendering of real life. 534. *Marco Basaiti*, Jesus on the Mt. of Olives; 543. *Gentile Bellini*, Miraculous cure in the interior of a house; 545. *Lazzaro Sebastiano*, Antonio Riccio congratulated by his friends; \*547. *Paolo Veronese*, Jesus in the house of Levi (1572); \*555. *Gentile Bellini*, Procession in the Piazza of St. Mark, painted in 1496 (showing the appearance of the Piazza at that date, differing materially from its present form); 559. *Carpaccio*, Martyrdom of the 10,000 Christians on Mt. Ararat, painted in 1515; 561. *Aloiso Vivarini*, Madonna and saints; 564. *Carpaccio*, Healing of a lunatic, with the old Rialto bridge in the background.

SALA XVII.: 572. *Bonifazio*, Adoration of the Magi; 575. *Tintoretto*, Two senators; 582. *Cima*, Madonna and saints; 586. *Bonifazio*, Temptation of SS. Benedict and Sebastian; \*593. *Palma Vecchio*, Peter and saints.

SALA XVIII.: Modern pictures by professors and pupils of the Academy.

SALA XIX.: Pictures from 1700 downwards, most of them mediocre: 644. *Canaletto*, Architectural piece; 656, 661. *Carriera*, Portraits in chalks.

SALA XX.: Modern pictures.

To the left is the 4th saloon (p. 223) through which the visitor may now pass and descend by a staircase to the Sala dell' Assunta.

The **\*\*Canal Grande** ('*Canalazzo*'), the main artery of the traffic of Venice, nearly 2 M. in length, and 33-66 yds. in width, intersects the city from N.W. to S.E., dividing it into two unequal parts, and resembling an inverted *S* in shape. The Canal Grande occupies the same position at Venice as the Corso at Rome, the Toledo at Naples, or the Boulevards at Paris. Numerous gondolas and other craft are seen here gliding in every direction, but little or no commercial traffic is carried on, as the water is too shallow for sea-going vessels. Handsome houses and magnificent palaces rise on its banks, for it is the street of the Nobili, the ancient aristocracy of Venice. A trip on the canal is extremely interesting; the distance from the Piazzetta to the station may be traversed in less than  $\frac{1}{2}$  hr., but  $\frac{3}{4}$ -1 hr. at least should be devoted to it in order to obtain a glimpse at the principal palaces in passing. The gondolier points out the most important edifices. The posts (*pali*) were formerly the distinguishing marks of the palaces of the nobles, and are still so to some extent, being painted with the heraldic colours of their proprietors. The following, beginning from the Piazzetta, are the most striking.

*Left.*

*Dogana di Mare* (Pl. 37), the principal custom-house, erected by Benoni in 1682; the vane surmounting the large gilded ball on the summit of the tower is a gilded Fortuna.

**Seminario Patriarcale** (Pl. 99), containing a collection of statues, architectural fragments, etc., most of them from secularised churches and monasteries of Venice, a collection of coins, a library, and the small *Gallery Manfredini* (open daily).

To the left, 'Madonna and Child with a saint and an angel with a lyre, attributed to *Leonardo da Vinci*; two small pictures, Christ and Mary Magdalene, and the Samaritan woman, probably by *Filippino Lippi*.

*S. Maria della Salute*, see p. 238.

*Pal. Dario-Angarani* (Pl. 59), in the style of the Lombardi (15th cent.).

*Pal. Venier*, a grand building, but the ground-floor only completed.

*Right.*

*Palazzo Giustiniani*, now the *Hôtel Europa* (Pl. b), in the pointed style of the 15th cent.

*Pal. Emo-Treves* (Pl. 61); in one of the apartments is a \*group of Hector and Ajax, over life-size, Canova's last work (fee 1 fr.).

*Pal. Tiepolo-Zucchelli* (Pl. 91), now *Hôtel Britannia*.

*Pal. Contarini*, 15th cent.

\**Pal. Contarini-Fasan*, restored in 1857, and —

*Pal. Ferro* (Pl. 47), now the *Grand Hôtel* (New York), both

*Left.*

*Pal. Da Mula*, pointed style of the 15th cent.

*Pal. Zichy-Esterházy* (Pl. 95).

*Pal. Manzoni-Angarani* (Pl. 78), of the period of the Lombardi (15th cent.), formerly an edifice of great magnificence, and the sole palace which stood in a feudal relation to the republic, now in a dilapidated condition (undergoing restoration).

IRON BRIDGE, constructed in 1854 (toll 2 c.).

*Campo della Carità.*

*Accademia delle Belle Arti* (Pl. 1), see p. 223.

**Palazzi Contarini degli Scignini** (Pl. 51), one of the 16th, the other of the 15th cent., erected by *Scamozzi* (the picture-gallery formerly here has been presented to the Academy, see p. 225).

*Pal. dell' Ambasciatore*, 15th cent.

\***Pal. Rezzonico** (Pl. 88), a spacious structure of the 17th and 18th cent., erected by *Longhena* and *Massari*.

Two *Pal. Giustiniani* (Pl. 68), in the pointed style.

\***Pal. Foscari** (Pl. 66), in the pointed style of the 15th cent., a handsome structure, situated at the point where the Canal turns to the E., containing the *Scuola Superiore di Commercio*.

*Pal. Balbi* (Pl. 42), a Renaissance structure, erected by *Aless. Vittoria*, a pupil of *Sansovino*. This part of the Canal, and especially the two palaces, are a favourite subject with artists.

*Right.*

handsome structures in the pointed style of the 14th cent.

*Pal. Fini-Wimpffen*, now incorporated with the Grand Hôtel.

\***Pal. Corner della Cà Grande** (Pl. 54), erected by *Jac. Sansovino* in 1532, with spacious inner court, now the seat of the prefecture.

*Pal. Barbaro*, 14th century.

\**Pal. Cavalli* (Pl. 50), the property of the Duke of Bordeaux, in the pointed style of the 15th cent., with fine windows.

Church of *S. Vitale*.

*Campo S. Vitale.*

*Pal. Giustinian-Lolin* (Pl. 69), of the 17th cent., the property of the Duchess of Parma.

*Pal. Malipiero*, Renaissance.

*Pal. Grassi* (Pl. 72), of the 18th cent., now the property of Baron Sina.

*Pal. Moro-Lm* (Pl. 82), 17th cent., erected by *Mazzoni*.

*Pal. Mocenigo* (Pl. 81), three contiguous palaces, that in the centre occupied by Lord Byron in 1818; that on the N. (Pl. 80)

## Left.

*Pal. Grimani* (Pl. 70) in the early Renaissance style.

*Pal. Persico* (Pl. 83).

*Pal. Tiepolo* (Pl. 92), beginning of 16th century.

\**Pal. Pisani a S. Paolo* (Pl. 85), in the pointed style of the 14th cent. The celebrated picture of Darius and Alexander, by Paolo Veronese, formerly here, is now in England.

*Pal. Barbarigo della Terrazza* (Pl. 43) was once celebrated for its picture-gallery, which became the property of the Emp. of Russia in 1850.

*Pal. Grimani*, erected by one of the Lombardi in the Renaissance style.

*Pal. Bernardo* (Pl. 46), in the pointed style.

\**Pal. Tiepolo-Stürmer* (Pl. 90), in the Renaissance style.

*Pal. Pisani-Moretta*, pointed style.

## Right.

contains the Exhibition of Art mentioned p. 208 (with *Titian's* picture, *The Saviour's Blessing*).

\**Pal. Conlarini delle Figure* (Pl. 53), in the early Renaissance style, 1504-64, with shields and trophies suspended from the walls.

\**Pal. Corner Spinelli* (Pl. 56), early Renaissance, in the style of the Lombardi.

*Pal. Cavalli*, in the pointed style of the 15th cent.

\**Pal. Grimani* (P. 70), a Renaissance edifice, chef d'œuvre of *Michele Sammicheli*, middle of the 16th cent., now the Corte d'Appello.

\**Pal. Farsetti* (Pl. 65, originally *Dandolo*), in the Venetian style of the 12th cent., with an admixture of Byzantine and Moorish features, now occupied by the municipal offices (*Municipio*).

\**Pal. Loredan* (Pl. 74), coeval with the last, with coloured incrustation, was once the residence of king Peter Lusignan of Cyprus, husband of Catharine Cornaro (comp. *Pal. Corner*, p. 231), whose armorial bearings are seen on different parts of the edifice; now occupied by municipal offices.



*Left.**Right.*

*Pal. Dandolo* (Pl. 58), early Gothic, once the unpretending residence of the celebrated Doge Enrico Dandolo (p. 220; small café on the ground-floor).

\**Pal. Bembo* (Pl. 45), in the pointed style of the 14th cent.

*Pal. Manin* (Pl. 77), with façade by *Jac. Sansovino*, 16th cent., was the property of the last Doge Lod. Manin, who on the approach of the French in May, 1797, resigned his office; it is now the *Banca Nazionale*.

The \***Ponte di Rialto** (i.e. 'di rivo alto'; Pl. E, 3), built in 1588-91 by *Antonio da Ponte*, 158 ft. long, 46 ft. wide, consists of a single marble arch of 74 ft. span and 32 ft. in height, resting on 12,000 piles. It is situated midway between the *Dogana di Mare* and the railway-station, and down to 1854 (p. 228) was the sole connecting link between the E. and W. quarters of Venice. On the right bank, near the bridge, is the *Fish Market*, abundantly supplied on Fridays. On the left is the *Fruit and Vegetable Market*, where excellent fruit may generally be purchased in the morning. On the left bank are also situated the *Fabbriche Vecchie*, erected by Scarpagnino in 1520, and the *Fabbriche Nuove*, built by Sansovino in 1555, as offices and warehouses for the republic. A new edifice in a similar style, adjoining the Canal at the back of the *Pal. de' Camerlenghi*, contains municipal offices. — Description of the quarter near the *Ponte Rialto*, see p. 235.

*Left.**Right.*

*Pal. de' Camerlenghi* (Pl. 49), in the early Renaissance style of 1525, once the residence of the republican chamberlains or officers of finance, was erected by *Guglielmo Bergamasco*.

*Erberia*, vegetable market (p. 235).

*Pescheria*, fish-market.

*Fondaco de' Tedeschi* (Pl. 63), an early Renaissance structure (1506), erected by an unknown master, was once a depôt of the wares of German merchants. It was originally decorated externally with paintings by Titian and his pupils, of which few vestiges now remain. The building is now used as a custom-house (*Dogana*).

*Corte del Remer*, 13th cent.

*Pal. Mangilli-Valmarana* (Pl. 76), built by Visentino.

*Cà da Mosto*, 12th cent.

## Left.

**Pal. Corner della Regina** (Pl. 55) was erected by *Rossi* in 1724, on the site of the house in which *Catharine Cornaro*, Queen of Cyprus, was born; it is now a 'monte di pietà' or pawn-office.

\***Pal. Pesaro** (Pl. 84), a Renaissance edifice of the 17th cent. by *Longhena* (accessible daily 9-4 o'clock, attendant 1 fr., porter 20 c.), contains a series of sumptuous apartments adorned with pictures of no great value.

Church of *S. Eustachio* ('*S. Stae*').

*Pal. Tron* (Pl. 93), 16th cent.

*Pal. Battagia* (Pl. 44), erected by *Longhena*.

\***Fondaco de' Turchi** (Pl. 64), Romanesque style of the 10th cent., once (after 1621) a Turkish depôt, has now been restored in the original style.

**Civico Museo Correr** (Pl. 57), open Mond., Wed., and Sat., 10-4 o'clock.

The GROUND FLOOR contains ancient and modern sculptures in marble, among them a fine antique draped statue. FIRST FLOOR: pictures and drawings by old masters, bronzes, carved wood and ivory, coins, etc.; also a large bird's eye view of Venice, carved in wood by *Dürer* (?) in 1500; mementoes of *Canova*, modern statues (*Hagar*, by *Lucardi*). The following pictures deserve mention: *Gent. Bellini*, *Franc. Foscari*; *Mantegna*, *Transfiguration*; *Giov. Bellini*, *Mocenigo*; *Leonardo da Vinci*, *Cæsar Borgia*; *Carpaccio*, two Venetian ladies; 127-139. *Piet. Longhi*, Pictures characteristic of Venice; several German and Dutch masters; *Aless. Longhi*, *Goldoni*; *P. Veronese*, Sketch of the Marriage of *Cana* (in the Louvre). — The SECOND FLOOR contains an in-

## Right.

*Pal. Michieli dalle Colonne* (Pl. 79), 17th cent.

*Pal. Sagredo*, pointed style of the 14th cent.

\***Cà d'Oro** (Pl. 48), 'the golden house', on account of its rich ornamentation, is the most elegant of the palaces in the pointed style of the 14th cent. (p. 211).

*Pal. Fontana*, late Renaissance.

*Pal. Grimani della Vida* (Pl. 71), 16th cent., erected by *Sanmicheli*.

*Pal. Erizzo*, in the pointed style of the 15th cent.

\***Pal. Vendramin Calergi** (Pl. 94), early Renaissance style, erected in 1481 by *Pietro Lombardo*, one of the finest palaces on the Canal Grande, and well worthy of a visit, is the property of the Duke of *Bordeaux*. Motto on the exterior, '*non nobis*'. The interior is magnificently fitted up, particularly a room to the right of the reception room, with leather tapestry and a fine painted frieze by *Palma Giovane*, representing the *Triumph of Cæsar*. It also contains some fine paintings by *Palma Giovane*, *Tintoretto*, and *Bordone*, and modern works (accessible daily, porter 25 c., attendant 1 fr.). There are also two rooms containing pictures for sale.

Church of *S. Marcuola*.

Church of *S. Geremia*.

*Pal. Labia* (Pl. 73), 17th century, at the union of the *Canal Grande* with the *Canal Grande*.

*Left.*

significant zoological collection and valueless pictures.

*Right.*

Near it, immediately beyond the bridge (*Ponte di Cannaregio*) is (1.) the **Pal. Manfrin** (Pl. 75), containing a picture-gallery, the best works of which were sold in 1856. It still contains about 200 pictures, some of them valuable, in seven rooms: *Luca Giordano*, *Madonna and Child with two saints*, and the donor between them; *Bernardo da Milano* (?), *Madonna enthroned*; *Bonifazio*, *Allegory*; *Girolamo da Santa Croce*, *Adoration of the Magi*; 74. Good old copy of Titian's *Entombment in the Louvre*; *Raphael* (?), *Noah entering the ark*; *Filippino Lippi*, *Madonna and Child*. All for sale (admission daily 10-3, 1/2 fr.).

*Pal. Frangini*, Renaissance, with façade curiously terminated by a half-column.

\***Gli Scalzi** (Pl. 31), is the sumptuous, picturesque church of the order of bare-footed monks, immediately to the E. of the railway-station, erected in 1649-89, and affords an excellent sample of the decorative style of the 17th cent. It was greatly damaged by the bombardment of 1849, but was restored in 1860. Behind the high altar a *Madonna* by *Bellini*.

NEW IRON-BRIDGE, completed in 1858 (toll 5 c.).

**S. Simeone Piccolo** (Pl. 34), opposite the railway-station, W. of the iron bridge, erected 1718-38, with a portal resting on columns, is surmounted by a dome in imitation of the Pantheon at Rome. — Adjacent is a house with a painted façade in good preservation.

*Stazione della Strada Ferrata* (Rail. Station); omnibus-boats, etc., see pp. 204. 205.

To the left, near the point where the Canal turns to the N.W., is situated the well-kept *Giardino Papadopoli* (Pl. 40; permesso to be obtained at the Pal. Papadopoli, Marina). On the N. side of the railway-station is the *Botanical Garden, Orto Botanico* (Pl. C, 2), the cacti in which are said to be the largest in Europe.

In the following description of the churches and other sights at Venice the PIAZZA OF ST. MARK is taken as a starting-point (comp. also p. 213).

Skirting the N. side of the church of St. Mark, proceeding to the E. of the small piazza in which rises the monument of Manin (p. 216), and passing the *Pat. Patriarcale* on the right, we observe opposite us the *Pal. Trevisani*, or *Bianca Capello*, built in the style of the Lombardi about 1500. We cross the bridge (fine view of the back of the palace of the doges and of the Bridge of Sighs), and traverse two small piazzas to the Campo and the church of —

\***S. Zaccaria** (Pl. 36; G, 4), erected in 1457-1515 in the round-arch style, supported by six Corinthian columns, and possessing a remarkable and somewhat discordant façade. The recess of the high altar is in the Gothic style. Over the entrance the statue of St. Zacharias by *Aless. Vittoria*.

The walls of the NAVE are covered with large pictures, all of them, except those over the altars, representing memorable events in the history of the church. To the left of the entrance, over the benitier, a statuette of John the Baptist by *Al. Vittoria*. The third arcade on the right leads to the CORO DELLE MONACHE (choir of the nuns): Enthroned Madonna and saints, on the wall to the right, by *Palma Vecchio* (?); over the door, Nativity of John the Baptist, by *Tintoretto*. In the CAPPELLA DI S. TARASIO (2nd on the right), three gilded altars in carved wood, of 1443-44, with old Italian pictures by the *Vivarini* of Murano. Here, too, is the entrance to the CRYPT, belonging to the original church, which was burned down in 1105. — Third altar in the choir, Circumcision, by *Giovanni Bellini*. In the left aisle, the tombstone of *Alessandro Vittoria* (d. 1605), with a bust by the master himself, '*qui vivens vivos duxit e marmore vultus*'. 2nd altar (l.), Madonna enthroned and four saints, by *Gior. Bellini*. This picture was taken to Paris by the French in 1797, but restored in 1815.

We now retrace our steps, and proceed from the first Campo direct to the bridge of the Rio della Paglia to the left (N.), traverse the Calle della Chiesa, cross the *Ponte Storto*, follow the Ruga Giuffa to the left (on the right is the Gothic *Arco Bon*, with rich ornamentation), and thus reach the considerable CAMPO S. MARIA FORMOSA (Pl. F, 3), in which is situated —

**S. Maria Formosa** (Pl. 18), erected in 1492, a cruciform church covered with a dome, and with smaller domes over the sections of the aisles.

INTERIOR. 1st Altar on the right: *Palma Vecchio*, St. Barbara and four saints, with a Pietà and four lateral pictures above; 2nd Altar: *Bart. Vivarini*, Mary, Anna, and St. Joachim; 3rd Altar: *Palma Giovane*, Descent from the Cross. S. Transept: *L. Bassano*, Last Supper. Choir: modern frescoes by *Pooletti* (1844). — A chapel, to which a staircase ascends (shown by the sacristan), contains (l.) a Madonna and Child by *Sassoferrato*.

Passing to the right of the church and skirting the canal, we observe beyond the bridge the picturesque *Porta del Paradiso*. We then cross the Ponte Ruga Giuffa and proceed past the *Pal. Querini* (now a girls' school) to the **Pal. Grimani** (Pl. 71a), erected in the 16th cent. under the influence of *Pietro Lombardo*, containing in its court an antique colossal \*Statue of Marcus Agrippa, brought, as it is supposed, from the Pantheon at Rome.

The opposite statue of Augustus is inferior, and only partly ancient. — The *Pal. Malipiero* in the Campo S. Maria Formosa also dates from the beginning of the 16th century.

The street opposite the church leads direct to the church of S. Giuliano and to the **Merceria** (Pl. F, 4, 3), the principal business street of Venice, containing the best shops after those of the Piazza of St. Mark. From the latter the Merceria is reached by passing under the clock-tower (p. 217). The first short street to the right leads to —

**S. Giuliano** ('*San Zulians*', Pl. 16; F, 3, 4), erected by *Sansovino* in 1553. The bronze statue of the founder, Thomas of Ravenna, in a sitting posture, is by the same master.

INTERIOR. 1st Altar to the left: *Boccaccino da Cremona*, Madonna and four saints; in the chapel to the left of the high altar is *Girolamo Campagna's* Dying Christ supported by angels, a relief in marble; *Puolo Veronese*, Last Supper. Above the high-altar: *Santa Croce*, Coronation of the Virgin.

Returning to the Merceria, we soon observe the lofty choir of S. Salvatore appearing between the houses. The entrance to the church is in the Campo of the same name.

\***S. Salvatore** (Pl. 30; F, 4), completed in 1534 (façade 1663), surmounted by three flat domes resting on circular vaulting, is one of the finest churches in Venice in this style. It is at present undergoing restoration (pictures in the Academy, p. 225).

RIGHT AISLE. Between the 1st and 2nd altars the monument of Proc. Andrea Dolfinò (d. 1602) and his wife; between the 2nd and 3rd, that of the Doge Franc. Venier (d. 1556), an architectural monument by *Sansovino*; over the 3rd altar (also by *Sansovino*) an Annunciation by *Titian*. — TRANSEPT. On the right the monument of Catharine Cornaro (d. 1510), Queen of Cyprus, who abdicated in 1489 in favour of Venice. — CHOR. Transfiguration, high altar-piece by *Titian*; behind it an altar-piece chased in silver, with 27 scriptural representations, executed about 1290. — In the Chapel on the left, Christ at Emmaus, by *Vitt. Carpaccio*. — LEFT AISLE. Monument of three cardinals of the Cornaro family. — Over the altar to the left of the organ, statue of St. Jerome, by *Tullio Lombardo*. Lofty architectural monument of the doges Girolamo (d. 1567) and Lorenzo Priuli (d. 1559), with gilded recumbent figures of the brothers.

Then to the right (N.) (the street to the left leads through the busy *Calle dei Fabbri* back to the Piazza of St. Mark) to the *Campo S. Bartolommeo* (the church of that name is uninteresting); to the left is the *Ponte di Rialto* (p. 230). We cross the piazza in a straight direction, pass the *Fonduco dei Tedeschi* (Pl. 63; F, 3; p. 230) on the left, and reach, on the right —

**S. Giovanni Crisostomo** (Pl. 14; F, 3), erected in the Renaissance style in 1483 by *Moro Lombardo* and *Sebastiano da Lugano*.

1st Altar on the right, *Gion. Bellini*, three saints; high altar, *Seb del Piombo*, St. Chrysostom with SS. Augustine, John the Baptist, Liberale, Catharine, Agnes, and Magdalene, one of the master's first important works; base of the altar, Entombment, a relief by an unknown master. Altar to the left, Coronation of the Virgin, and the 12 Apostles, reliefs by *Tullio Lombardo*.

At the back of the church is the *Teatro Malibran* (Pl. 103); then farther on, beyond the second bridge, the church of —

**Santi Apostoli** (Pl. 5; F, 2), erected in 1672, containing the

*Cappella Corner*, which belonged to an earlier church, and was erected by *Guglielmo Bergamasco* in the 16th cent., with two monuments of the *Corner* family. To the right in the choir: *Cesare da Conegliano*, Last Supper; left, *Paolo Veronese*, Fall of *Manna*.

Opposite is the *Scuola dell' Angelo Custode* (Pl. 32; German Prot. church). — To the N.W. of the *Campo SS. Apostoli* runs the new *Corso Vittorio Emanuele* (Pl. E, 2), the broadest street in Venice, by which we may proceed past the church of *S. Felice* to the *Palazzo Giovanelli* (p. 239).

We now proceed to the S. to the *RIALTO BRIDGE* (Pl. E, 3; p. 230). Immediately beyond it, on the right, is the church of —

**S. Giacometto di Rialto** (Pl. 13c; E. 3), which is said to have been erected in 520 (?), a short basilica with a dome over the cross, the most ancient example of this style at Venice. The *Fabbriche Nuove* and *Vecchie* are situated here (p. 230). On the farther side of the *Vegetable Market* (p. 230) is a short column of Egyptian granite, to which a flight of steps ascends, borne by a kneeling figure, '*Il Gobbo di Rialto*'. From this column the laws of the Republic were anciently promulgated.

Next in a straight direction, past the *Beccherie*, or slaughter-houses, to the church of *S. CASSIANO* (Pl. 13 b; E, 3), of 1611; 1st altar on the right, \**Palma Vecchio*. John the Baptist and four saints; 3rd altar on the right, *Leandro Bassano*. Salutation. — Still farther on is the church of *S. MARIA MATER DOMINI* (Pl. 19; D, E, 3), begun by *P. Lombardo*, and completed by *Sansovino*. Over the 2nd altar to the right: *Vinc. Catena*, Glorification of *St. Christina*; on the left, *Bonifacio*. Last Supper.

The traveller who wishes to proceed direct to the *Frari*, turns, on leaving *S. Giacometto*, to the W. into the *Ruga Vecchia*, in which, on the left (gateway adjoining the *campanile*), is **S. Giovanni Elemosinario**, erected in 1527 by *Scarpagnino*. Bay on the right, altar-piece by *Pordenone*, SS. *Sebastian*, *Rochus*, and *Catharine*; \*high altar-piece by *Titian*, S. *Giovanni Elemosinario*; left, *Marco Vecellio*, *Doge* giving alms.

We follow the same street, and cross the *Campo S. Apollinare* to the *Campo S. Polo* (in the neighbouring *Rio di S. Polo* is the *Pal. Corner-Mocenigo*, with a good façade by *Sammicheli*). Passing between the church and the ancient *campanile* of the 14th cent., we take the second side-street to the right, and then the fourth to the left, leading to the former church of the *Franciscans*, or the —

\*\***Frari** (*S. Maria Gloriosa dei Frari*, Pl. 10; D, 3), a cruciform church, one of the largest and most beautiful at Venice, in the Gothic style with the peculiar Italian modifications (twelve circular buttresses), erected about the middle of the 13th cent., and completed before 1338 by *Niccolò Pisano*. It contains numerous monuments, sculptures, and pictures, and like *S. Giovanni e Paolo*

(p. 240) is the last resting-place of many eminent men. The rounded terminations of the façade are obviously much later than the church itself.

**RIGHT AISLE.** Adjoining the 1st altar the Monument of Titian (d. 1576), erected by Emp. Ferd. I., completed by *Luigi* and *Pietro Zandomenighi* in 1852. In the centre, above the dedication 'Titiano Ferdinandus I. 1852', between four columns Titian sitting by an angel and uncovering the statue of Sais; on the columns are figures representing Sculpture, Architecture, Painting, and Wood-carving. On the wall are-reliefs of the three most celebrated pictures of Titian, the Assumption (p. 224), Martyrdom of St. Peter (p. 240), and Martyrdom of St. Lawrence (p. 210); above, left and right of the vaulting, Entombment and Annunciation, his last and first pictures; above these the lion of St. Mark. Below are two figures with tablets: 'Eques et comes Titianus sit. Carolus V. 1553', and 'Titiano monumentum erectum sit. Ferdinandus I. 1839'. — Over the 2nd altar: *Salviati*, Presentation of Mary in the temple; adjacent, the monument of Almerico d'Este of Modena, a general of the Republic (d. 1660), with a statue; 3rd altar, St. Jerome, a statue by *Alessandro Vittoria*, said to possess the features and figure of Titian when in his 98th year.

**RIGHT TRANSEPT.** Monument of Jacopo Marcello (d. 1484), a sarcophagus borne by three male figures; altar-piece in four sections by *Bart. Vivarini*. Over the door of the sacristy the monument of Benedetto Pesaro (d. 1503). — In the SACRISTY, opposite the door, a shrine with reliefs in marble of the 17th cent.; altar-piece, a Madonna and saints, by *Giov. Bellini*. — In the church, to the left of the entrance to the sacristy, the monument of Paolo Savelli (d. 1405), with an equestrian statue.

**CHOIR CHAPELS.** 2nd Chapel on the right: on the right, the monument of Duccio degli Alberti, on the left, that of an unknown warrior, both of the 14th cent. — Choir: (r.) mausoleum of the Doge Franc. Foscarini (d. 1457), (l.) that of the Doge Nicolò Tron (d. 1473), both by *Ant. Rizzo*. — Chapels on the left: 1st, altar-piece, Madonna and saints, by *Bern. Licinio da Portenone*; 2nd, (r.) monument of Melch. Trevisano (d. 1500), the altar in coloured and gilded carved wood, in the centre John the Baptist in wood, by *Donatello*; 3rd, altar-piece, St. Ambrose and saints, by *Vivarini* and *Marco Basaiti*; right, St. Ambrose on horseback expelling the Arians, by *Giov. Contarini*.

**LEFT TRANSEPT.** Altar-piece in 3 sections, St. Mark with saints (1474), by *Bart. Vivarini*.

**LEFT AISLE.** *Baptistery*: altar in marble, St. Peter, Mary, and eight saints, of the 15th cent.; over the font a statue of John the Baptist, by *Sansovino*. Farther on: Tomb of Jac. Pesaro (d. 1547); altar-piece, Madonna with saints and members of the Pesaro family, by *Titian*, who has introduced a portrait of himself as Joseph; Monument of the Doge Giov. Pesaro (d. 1669), of a rich architectural character, occupying the entire wall, with unpleasing figures of negroes as bearers, by *Longhena*.

Mausoleum of Canova (d. 1822), '*principis sculptorum aetatis suae*', erected in 1827 from the master's own design for Titian's monument, executed by Canova's pupils *Martini*, *Ferrari*, *Fabris*, and others. — By the W. portal the sarcophagus of Pietro Bernardo (d. 1538), by *Al. Vittoria*.

In the NAVE a high parapet of marble, covered with two series of reliefs, separates the seats of the monks from the rest of the church. Elegantly carved stalls, by *Marco da Vicenza*, 1468, semi-Gothic in style. A pleasing glimpse of the apse is obtained through the screen.

The adjacent monastery contains the *Archives* (Pl. 2), one of the most magnificent collections of the kind in the world, which comprise about 14 million documents, the earliest dating from 883, deposited in 298 different apartments.

Beyond the archives is the church of **S. Rocco** (Pl. 29; D, 3), dating from 1490 and 1725, and like the adjacent Scuola di S. Rocco containing numerous pictures by *Tintoretto*.

On the right, the Annunciation, beyond it the Pool of Bethesda, and above the latter St. Rochus in the wilderness. Chapel to the right of the choir: *Titian*, Christ dragged to Golgotha. In the choir, to the right, St. Rochus in the hospital, to the left, Holy Martyrs by *Tintoretto*. On the left side of the church, *Pordenone*(?). Expulsion of the money-changers from the Temple, above it St. Rochus and St. Martin.

The very interesting \***Scuola di S. Rocco** (Pl. 98; D, 3), begun in 1517, and containing the council-halls of the brotherhood, possesses a magnificent façade, and handsome old staircase and hall (open daily, 9-4, custodian 1/2 fr.; good light necessary).

The ground-floor, staircase, and first floor, on the ceilings, as well as on the walls, are adorned with pictures by *Tintoretto*; on the staircase an Annunciation by *Titian*. At the top, on the left, is a small room containing *Tintoretto's* master-piece, a large Crucifixion of 1565. Opposite is an *Ecce Homo* by *Titian*. The bronze doors in front of the altar in the principal hall, are by *Gius. Filiberti* of Florence, 1756.

The low gateway adjoining the Scuola leads to the church of **S. Pantaleone** (Pl. 26; D, 4), erected in 1668-75. The chapel to the left of the high altar contains (r.) a \*Coronation of the Virgin by *Giovanni* and *Antonio da Murano*, painted in 1444; also an \*Entombment in high relief, of the same date.

Crossing the bridge, and traversing the long *Campo S. Margherita* (Pl. C, 4), we reach —

**S. Maria del Carmine** (Pl. 7; C, 4), generally known as *I Carmini*, which was consecrated in 1348, and restored in the 17th cent. Over the 2nd altar on the right, \**Cima da Conegliano*, Adoration of the shepherds and saints; 2nd altar on the left, \**Lorenzo Lotto*, St. Nicholas with three angels and two saints on clouds. — To the left of the egress of the church are the cloisters of the former monastery of the Carmini, with a basrelief over the entrance, by *Arduino*, 1340. — On the right is the *Scuola dei Carmini*, of the 17th cent., with paintings by Tiepolo and others.

We may either return hence to the Piazza of St. Mark by gondola (1 fr.), or proceed to S. Sebastiano (Pl. 33; C, 4; p. 243), crossing the bridge to the S., and then taking the first cross-street (*Calle Lunga*) to the right.

The passage in the S.W. corner of the PIAZZA OF ST. MARK leads to the *Calle S. Moisè*. To the left is the church of *S. Moisè* (Pl. 24; E, F, 4), with an over-decorated façade. We then cross two bridges to the church of —

**S. Maria Zobenigo** (Pl. 23; E, 4), erected in 1680 by the Barbaro family ('barbaro monumento del decadimento dell' arte', as it has been called). The niches of the façade contain statues of members of the family. At the base of the lower row of columns are plans of Zara, Candia, Padua, Rome, Corfu, and Spalato, hewn in the stone; on the bases of the columns are representations of naval battles. This curious façade is the only part of the church worthy of note.

Leaving this church, we cross the *Campo S. Maurizio*, where the



small church of that name is situated, to the larger *Campo S. Stefano* (Pl. E, D, 4). On the right rises —

\***S. Stefano** (Pl. 35; E, 4), a Gothic church of the 14th cent., with an elegant façade in brick, good window mouldings in terracotta, and a peculiarly constructed vaulting of wood, restored in the ancient style, imparting a very pleasing appearance to the interior.

ENTRANCE-WALL, above the principal door, equestrian statue of Dom. Contarini, middle of 17th cent.; adjacent, (L.) the \*Tomb of the physician Jacopo Suriano (d. 1511). On the PAVEMENT of the nave is the large tombstone of the Doge Francesco Morosini 'Peloponnesiacci' (d. 1694), with the cap and baton of office in bronze. — Adjacent to the SACRISTY in the right aisle a Madonna with saints, a relief in bronze of the 16th cent.; in the sacristy small marble statues of John the Baptist and St. Antony by *Pietro Lombardo*; on the right Madonna and saints by *Palma Vecchio*. — CHOIR. On the lateral walls statues of the twelve Apostles and four saints, and reliefs of the four Evangelists and two Fathers of the church. In front of the high altar two candelabra in bronze, on marble pedestals, by *Al. Vittoria*, 1577; behind it, choir-stalls carved and inlaid. — 3rd altar (L.) statues of St. Jerome and St. Paul by *Pietro Lombardo*.

Adjoining the church on the left is a handsome \**Monastery Court*, restored in 1532, and once adorned with frescoes by *Pordezone*, of which there are remains on the S. and E. wall over the colonnade (four saints on the E. wall, particularly those to the left, very good); below the windows 'putti', the subjects on the S. side being from the Old Testament. — Crossing the court, we reach the *Campo S. Angelo* (Pl. E, 4), with a monument of Paleocapa, the minister, and to the left the *Pal. Grimani* (p. 229). Farther to the E., near the *Teatro Rossini* (Pl. 102), is a large new piazza adorned with a *Monument of Manin* (p. 216) in bronze.

To the left in the *Campo S. Stefano* is the *Pal. Morosini*. In the vicinity is the *Pal. Pisani*, in the small and dreary Piazza of that name, with interesting old ships' lanterns and richly adorned maskknobs.

To the S. of the *Campo S. Stefano* is the *Campo S. Vitale* with the church of that name, from which the *Iron Bridge* (p. 228; 2 c.) crosses to the *Campo della Carità*, where the *Academy* is situated (p. 223).

We now proceed towards the E., cross several bridges, and reach —

\***S. Maria della Salute** (Pl. 22; E, 5), a spacious and handsome dome-covered church, at the E. extremity of the Canal Grande, erected in 1631-82 by *Longhena*, a successor of Palladio, in commemoration of the plague in 1630.

CHAPELS ON THE RIGHT: 1. Presentation in the Temple, 2. Assumption, 3. Nativity of the Virgin, all by *Luca Giordano*; in the last CHAPEL ON THE LEFT: Descent of the Holy Ghost, by *Titian*, much darkened by age. The monolithic columns by which the vaulting of the choir is supported are from a Roman temple at Pola in Istria. On the high altar a large candelabrum in bronze by *Andrea Alessandro da Brescia*, of admirable workmanship; the Virgin banishing the demons of the plague, a group in marble by *Le Curt*. On the ceiling eight me-

dallions with portraits of the evangelists and fathers of the church by *Titian*; the large pictures by *Salvati*. — OUTER SACRISTY: Pietà, a relief of the 15th cent., by *Dentone* (?); *Titian*, St. Mark and four saints; *Marco Basaiti*, St. Sebastian. — SACRISTY: by the entrance-door, St. Rochus and other saints, by *Girolamo da Treviso*; on the right and left of the door four Madonnas by *Sassoferrato* (?), *Vivarini*, and *Palma Vecchio*; left wall: *Tintoretto*, Marriage of Cana; Madonna and Child, with four worshippers, an altar-piece 'a tempera' by *Cristoforo da Parma*, 1495. Ceiling-paintings: Cain and Abel, Abraham and Isaac, David and Goliath, by *Titian*.

Adjoining this church are the *Seminario Patriarcale* (p. 227) and the *Dogana di Mare* (p. 227), which lie obliquely opposite the Piazza of St. Mark (traghetto, or ferry, see Plan).

The more remote quarters of the city are most conveniently visited by gondola. Leaving the Canal Grande opposite the Pal. Pesaro (p. 231), we enter the *Rio S. Felice*; here, on the left, is the \*Pal. *Giovanelli* (Pl. 67; E, 2; admission most easily obtained about noon), of the 15th cent., with sumptuously furnished apartments, a handsome ball-room (with family portraits by *Titian* and *Tintoretto*), and a room with modern pictures; in the boudoir, \**Giov. Bellini*, Madonna; \**Titian*, St. Jerome; \**Paris Bordone*, Madonna and saints.

Following the same canal, we pass the *Abbaduzza della Misericordia*, and turn to the left to the church of —

\***S. Maria dell' Orto** ('*Madonna dell' Orto*'; Pl. 21; E, 1), with a beautiful late Gothic \**Façade* erected by *Pietro Lombardo* soon after 1481, and recently restored, and a curious tower. The church contains many good pictures.

RIGHT, 1st altar: \**Cima da Conegliano*, St. John the Baptist with SS. Peter, Mark, Jerome, and Paul. Between the 3rd and 4th altars: Monument of Hieronymus Carraccio (d. 1631) in the baroque style. Adjoining the 4th altar: \**Palma Vecchio*, St. Stephen surrounded by four other saints (formerly in the chapel on the left of the choir). Above the entrance of the sacristy, Virgin and Child, half-figure by *Giovanni de Sanctis*. — IN THE SACRISTY: 28 portraits of Venetian Saints. — CHAPEL ON THE RIGHT of the choir: *Girolamo da S. Croce*, SS. Augustine and Bonaventura; memorial tablet to *Tintoretto* (d. 1594), who is buried here. — IN THE CHOIR, (r.) the Last Judgment, (l.) Adoration of the golden calf, large works by *Tintoretto*. Over the high altar an Annunciation, by *Palma Giovine*, with surrounding pictures by *Tintoretto*. — CHAPEL ON THE LEFT of the choir, altar-piece, a copy from *Pordenone*. — IN THE LEFT AISLE the Capp. Contarini, containing busts of six members of the celebrated family of that name; among them that of the Cardinal (d. 1542), the second on the left, by *Alessandro Vittoria*: Altar-piece by *Tintoretto*, Miracles of St. Agnes; 2nd chapel on the left: (r.) *Tintoretto*, Presentation in the Temple; (l.) *Palma Giovine*, Crucifixion. 4th Chapel, to the left by the entrance: altar-piece by *Bellini*, Madonna (restored); (l.) *Lor. Lotto*, Lamentation over the body of Christ.

We now return along the *Fondamenta Nuove* (Pl. F, G, 2; view of Murano, the cemetery island, and Torcello) to the church of the —

**Gesuiti** (Pl. 11; F, 2), erected in 1715-30 in the 'baroque' style, entirely lined in the interior with marble inlaid with verde antico, and sumptuously decorated like all the churches of this order.

At the HIGH-ALTAR are ten spiral columns of verde antico; in the centre a globe, with God the Father and the Son. The marble mosaic pavement in front of the altar resembles a carpet. The chapel to the right of the high altar contains the monument and statue of Orazio Farnese (d. 1654); in the chapel on the left is the monument of the Doge Pasquale Cicogna (d. 1595); then, in the LEFT TRANSEPT, the Assumption, an altar-piece by *Tintoretto*; 1st chapel on the left of the principal door, the Martyrdom of St. Lawrence, an altar-piece by *Titian*, much darkened by age (seen best 11-12 a. m.).

We next enter the Rio dei Mendicanti (Pl. F, 2, 3), skirt the large *Spedale Civile* (Pl. 41), and reach —

\***S. Giovanni e Paolo** ('*S. Zanipòlo*'; Pl. 15; F, G, 3), begun under *Niccolò Pisano's* influence in 1240, and completed in 1430, a very spacious and magnificent Italian Gothic edifice, supported by ten circular columns, and covered with a dome. This church, next to St. Mark's the most imposing at Venice, contains the burial-vaults of the doges, whose funeral-service was always performed here, and may to some extent be called the Westminster Abbey of Venice.

RIGHT AISLE. In front: Mausoleum of the victorious Doge Pietro Mocenigo (d. 1476), with fifteen statues by the *Lombardi*; the sarcophagus is '*ex hostium manubis*' (from the spoils of his enemies). Between the 1st and 2nd altar, an obelisk to the memory of the painter Melch. Lanza (d. 1674); monument of Marc Antonio Bragadino (d. 1571), who long defended Famagosta in Cyprus against the Turks, and after its surrender was barbarously flayed alive, as the picture above indicates; Altar-piece in six sections by *Bellini*, or *Carpaccio*; monument of the Senator Alb. Michiel (d. 1589). In the chapel: altar-piece, Descent from the Cross, by *Pietro Liberi*. Over the doors the Mausoleum of Bertucci, Silvestro, and Elisabetta Valier with their statues, a rich architectural 'baroque' monument in marble of the 18th cent., embellished with numerous statues and reliefs. In the chapel below the monument, (1.) St. Hyacinth crossing a river dry-shod, by *L. Bassano*. The second door is an egress. The following chapel contains six reliefs in bronze and wood, scenes from the life of St. Dominic, 1720.

RIGHT TRANSEPT. At the corner, St. Augustine, an oil-painting by *Vivarini da Murano* (1473); tomb of General Niccolò Orsini (d. 1509) with equestrian statue; St. Antoninus, an altar-piece by *Lorenzo Lotto*; stained glass designed by *Vivarini* (1473, restored in 1814); altar-piece, Christ, SS. Andrew and Peter, by *Rocco Marconi*. — The chapels on the right and left of the choir, recently restored, contain nothing noteworthy except a monument of 1347.

CHOIR. Tombs of the Doges, (r.) Michele Morosini (d. 1382), in the Gothic style, and Leonardo Loredano (d. 1521), (l.) Andrea Vendramin (d. 1478) (by *Alessandro Leopardò*, perhaps the finest monument at Venice), and Marco Corner (d. 1368), Gothic.

LEFT TRANSEPT. Above, by the entrance to the Chapel of the Rosary, a group in marble by *Antonio Dentone*, of the 15th cent., St. Helena presenting General Vittore Capello with the marshal's baton; over the door the monument of the Doge Antonio Venier (d. 1400). — The adjacent (on the left) *Cappella del Rosario*, founded in 1571 to commemorate the victory of Lepanto, was destroyed by fire in Aug., 1867. Of its former valuable contents nothing remains but the blackened and mutilated fragments of admirable reliefs in marble, representing scenes from the life of the Saviour and the Virgin, executed by *Bonazza*, *Torcetti*, and other masters from 1600 to 1732. At the time of the conflagration the celebrated picture by *Titian*, representing St. Petrus Martyr attacked and murdered in a wood, and a Madonna by *Bellini* had unfortunately been deposited in the chapel during the execution of repairs in the church, and also

became a prey to the flames. — Farther on in the church, Monument of the wife and daughter of the Doge Antonio Venier, 1411; monument, with equestrian statue, of Leonardo da Prato (d. 1511).

LEFT AISLE. On the right and left of the door of the *Sacristy*, admirable wood carving by *Brustolone*. Over the door busts of Titian and the two Palmas, by *Jac. Albarelli*, 17th cent. \*Mausoleum of the Doge Pasquale Malipiero (d. 1462); tombstone of the senator Bonzio (d. 1508), under it statues of St. Thomas by *Antonio Lombardo* and St. Peter the martyr by *Paolo da Milano*; in the niches, (r.) the recumbent effigy of the Doge Michele Steno (d. 1413), formerly painted, (l.) that of Aloiso Trevisan (d. 1528); monument with equestrian statue of General Pompeo Giustiniani; \*monument of the Doge Tommaso Mocenigo (d. 1423), Gothic; monument of the Doge Niccolò Marcello (d. 1474) by *Pietro Lombardo*; 2nd altar, left of the principal entrance, early copy of Titian's martyrdom of St. Peter (see above), presented by King Victor Emmanuel to replace the picture which was destroyed; monument, with equestrian statue, of Orazio Bagliani (d. 1617); over the last altar a statue of St. Jerome by *Aless. Vittoria*; adjoining it, the monument of the Marquis de Chasteler (d. 1825), who distinguished himself in the Tyrolese war in 1809. Mausoleum of the Doge Giov. Mocenigo (d. 1485) by *Tullio Lombardo*. Over the PRINCIPAL ENTRANCE the mausoleum of the Doge Aloiso I. Mocenigo, his wife, and the Doge Giov. Bembo (d. 1618). This whole side, which is very handsomely arranged, belongs to the Mocenigo family, and was constructed by *Tullio Lombardo*.

Adjoining S. Giovanni e Paolo is the rich Façade (of 1485) of the \**Scuola di S. Marco* (Pl. 41; F, 3), erected by the *Lombardi*, with singular reliefs in perspective, two lions, and the achievements of St. Mark. In the interior the lower hall only is preserved. The building has been used as a hospital since 1815 (50 rooms, for 600 patients). The large sickroom has a magnificent ceiling. Connected with it is the old chapel of S. Maria della Pace, which once contained Marino Falieri's tomb (p. 220). — To the S., on a lofty and elegant pedestal of marble, rises the equestrian \**Statue of Bart. Colleoni* (d. 1475, buried at Bergamo, p. 168), general of the republic, modelled by *Andr. Verrocchio* (his last work), cast in bronze by *Aless. Leopardo*.

We now proceed through the *Rio di Marina* to the church of —

\**S. Maria dei Miracoli* (*Madonna d. M.*; Pl. 20; F, 3), a small, early Renaissance structure, erected in 1480, under the influence of *Pietro Lombardo*, and entirely covered on the façade and in the interior with valuable marble. The quadrangular choir with a dome, twelve steps higher than the nave, is peculiar (below it is the sacristy). On the right and left are ambos, or lecterns where the epistles and gospels are read, as in the ancient Christian churches. The \*decorations are by *Pietro Lombardo*. The coffered barrel-vaulting is sumptuously painted and gilded. The church is not expected to be re-opened till 1879, but the façade and the side next the canal are well worthy of a visit.

We now return through the *Rio di S. Giovanni Laterano*, S. Lorenzo, and Fontego, to —

*S. Francesco della Vigna* (Pl. 9; G, 3), the interior of which was constructed in 1534 by *Sansovino*, the façade by *Andr. Palladio* in 1568-72.

At the entrance a holy water vessel with St. John the Baptist and St. Francis, statues in bronze by *Vittoria*. 1st Chapel on the right, Last Supper, by *Franc. Santacroce*; 3rd chapel encrusted with coloured marble, property of the Contarini family; 4th chapel, Resurrection, by *Paolo Veronese*. RIGHT TRANSEPT, Enthroned Madonna, by *Fra Antonio da Negroponte*. To the left of the high altar is the *Cappella Giustiniani*, the altar entirely covered with reliefs in marble, a work of the 15th cent.; Last Judgment below; above (as an altar-piece), St. Jerome and four saints; over them Madonna and angels; at the sides of the chapel twelve prophets and the four Evangelists; higher up, the history of Jesus in eighteen sections; below, on the altar, the history of St. Jerome in three sections. — In the chapel of the cloisters adjacent to the N., a Madonna and four saints, by *Giov. Bellini*. — Over the pulpit, God the Father and Christ, by *Girolamo Santacroce*, modernised. In the 5th chapel to the left (at the principal door), a Madonna and four saints, by *Paolo Veronese*; 3rd chapel, fitted up with white marble, containing busts of the Patriarch and the Doge Sagredo, erected in 1743; over the altar the statue of S. Gerardo.

A little to the S. in the Rio della Pietà is the church of **S. Giorgio degli Schiavoni** (Pl. 13a; G. 3), with a good Renaissance façade of 1551, a low wooden ceiling, and pictures by *Carpaccio*. on the right, three scenes from the life of St. Jerome, on the left, three from the life of St. George; altar-piece, St. Tryphon and St. Matthew; in an adjoining room, on the right, a Madonna by *Vinc. Catena*. — Farther S. we next come to the church of *S. Antonino*. where we cross the bridge to the right to —

**S. Giorgio dei Greci** (Pl. 13a; G. 4), with an elegant campanile of the 16th cent., and an ikonostasis adorned with gorgeous Byzantine mosaics. The head of Christ in the dome is said to have been designed by Titian. — Returning to S. Antonino, and again pursuing a S. direction, we soon reach —

**S. Giorgio in Bragora** (Pl. 13d; G. 4), a church of early origin, but entirely restored at the beginning of the 18th cent.

1st CHAPEL on the right: *Aloiso Virarini* (according to Mr. Crowe; usually attributed to *Giov. Bellini*), Madonna and Child; *Bissolo* (or *Ant. Virarini*), St. Andrew with Ss. Jerome and Martin, the latter on horseback; *Paris Bordone*, Last Supper. — On the pillar before the chapel of the choir: *Cima da Conegliano*, Constantine and St. Helena by the side of the Cross, 1502. At the back of the high-altar: *Cima da Conegliano*, Baptism of Christ, 1494. On the pillar to the left, *L. Virarini*, Resurrection; *Bart. Vivacini*, Madonna with St. Andrew and John the Baptist; under it, *Cima da Conegliano*, Finding of the Cross, originally a predella of the above named picture.

We may now proceed towards the E., past *S. Martino* (erected by Sansovino in 1540; font with four kneeling angels by Tullio Lombardo, 1484; Last Supper by *Girolamo da Santacroce*, 1549) to the entrance to the arsenal (Pl. 3; H. 4: see p. 223); or to the S. to the Riva degli Schiavoni (p. 223).

Opposite the Piazzetta, on an island fortified in 1848, is situated —

\***S. Giorgio Maggiore** (Pl. 12; G. 5), belonging to the adjacent suppressed Benedictine monastery, a cruciform church with a dome, and apses terminating the transepts, begun by *Palladio* in 1560.

INTERIOR. Over the door a portrait of Pope Pius VII., who was elected by a conclave of Cardinals held here on 14th March. 1800. To the right, the monument of Lorenzo Venier (d. 1667). Over the 1st altar, Nativity, by *Bassano*; 2nd, Crucifix in wood, by *Michelozzo*; 3rd altar, Martyrdom of SS. Cosmas and Damianus and their companions; 4th altar, Coronation of the Virgin, the two last by *Tintoretto*; 5th altar, Adoration of the Madonna, by *Rizzi*. — CHOIR: (r.) Last Supper, (l.) Rain of Manna, both by *Tintoretto*; on the high altar a group in bronze by *Girolamo Campagna*, representing God the Father on a gilded globe borne by the four Evangelists, beside them two angels; two candelabra in bronze by *Nicoletto Roccatagliata* (1597); the 48 choir-stalls, admirably carved in wood in the 17th cent. by *Alberto de Brule* of Flanders, represent scenes from the life of St. Benedict. — In the CORRIDOR, to the right of the choir, the mausoleum of the Doge Domenico Michiel (d. 1129), erected in 1637; in a chapel behind it, Descent from the cross by *Tintoretto*. — To the left, farther on in the church, the Resurrection, and the Martyrdom of St. Stephen, both by *Tintoretto*; Virgin and Child, a group over life-size by *Girolamo Campagna*; last altar, Martyrdom of St. Lucia, by *Bassano*; monument of the Doge Marc Antonio Memmo (d. 1615).

A staircase in 32 spiral windings, well lighted and of easy ascent, leads to the summit of the *Campanile* (before ascending, enquire if the door at the top is open), which commands an admirable \*VIEW of the city and the Lagoon.

On the adjoining island of *Giudecca* is situated the church of —

\***Redentore** (Pl. 28; E, 6), erected in 1576 by *Andr. Palladio*, a spacious church with a portal borne by columns, a much vaunted edifice, chiefly interesting in the interior.

ON THE RIGHT: 1st Chapel, Nativity, by *Francesco Bassano*; 2nd, Baptism, *Carletto Catiari*; 3rd, Scourging, *Tintoretto*. ON THE LEFT: 3rd Chapel, Descent from the Cross, *Palma Giov.*; 2nd, Resurrection, *F. Bassano*; 1st, Ascension, *Tintoretto*. In front of the high altar, Christ bearing the Cross, behind it a Descent from the Cross, reliefs in marble by *Massa da Bologna*; the bronze figures by *Campagna*. — The SACRISTY contains three admirable \*Madonnas by *Giovanni Bellini*; that with the sleeping Child is the most richly coloured, but somewhat stiff; that over the door is easier.

The church belonged formerly to the neighbouring Franciscan monastery.

We now cross the *Canale della Giudecca* and skirt the *Fondamenta delle Zattere* (Pl. C, D, 5) to —

\***S. Sebastiano** (Pl. 33; C, 4), containing a number of works by *Paolo Veronese*, and his tomb. It was erected in 1506-18, and restored within the last few years. Admission to the choir, whence some of the pictures are seen to greater advantage. 1-4 o'clock only.

ON THE RIGHT: 1st altar, St. Nicholas, painted by *Titian* in his 86th year; 3rd, \*Madonna with St. John, a group in marble by *Tommaso Lombardo*, 1547; 4th, Christ on the Cross, and the Maries, by *Paolo*; \*Monument of Bishop Livio Podocataro (d. 1559), by *Sansovino*. — CHOIR. Altar-piece, Madonna in glory and four saints, on the wall to the right \*Martyrdom of St. Sebastiano, to the left Martyrdom of SS. Mark and Marcellinus, all three by *Paolo Veronese*. — ORGAN, on the extreme wing, the Purification of Mary, on the inner, the Pool of Bethesda, both by *P. Veronese*; to the left the bust, in front of it the tomb of the master (d. 1588), bearing the inscription: '*Paolo Catiaro Veronensi pictori, naturae aemulo, artis miraculo, superstiti fati, fama victuro.*' — SACRISTY. Ceiling-paintings by *Veronese*, Coronation of the Virgin, on the sides the four Evangelists. Farther

on in the church, the next chapel on the left, Bust of the Procurator Marcantonio Grimani (d. 1565), by *Vittorio*; Madonna and Child with a saint, a small picture by *P. Veronese*; 2nd altar, Baptism of Christ, by the same; ceiling-paintings also by *Paolo*, aided by his brother *Benedetto Catiari*. Beautiful festoons.

In the vicinity is the *Campo di Marte*, or esplanade (Pl. B, 4), a large grassy island surrounded with trees.

At the S.E. extremity of Venice (*Punta della Motta*) are the **Giardini Pubblici** (Pl. I, 5), laid out by Napoleon in 1807, the space having been obtained by the demolition of several monasteries. They are about 300 yds. in length and 100 yds. in width, and are planted with six rows of acacias and sycamores. At the S. end is a small shrubbery, with a small café. The grounds, which are generally almost deserted, afford fine views of the city and Lagoon. On Sundays and Mondays they are much frequented, chiefly by women of the lower classes (gondola thither from the Piazzetta 50 c.). They are approached by the *Via Nuova dei Giardini*, or *Garibaldi* (formerly *Eugenia*), constructed in 1810 by Eugene Beauharnais, viceroy of Italy, by bridging over a canal.

**S. Pietro di Castello** (Pl. 27; 1, 4), a church with a dome, on the island to the N. of the Giardini Pubblici, begun by *Smeraldi* in 1596, is said to have been designed by *Palladio* in 1557. Down to 1807 it was the cathedral of the Patriarch of Venice, when St. Mark's was raised to that dignity by Napoleon I., and the adjoining palace converted into a barrack. Handsome campanile (1474).

The INTERIOR contains few objects of interest. In the chapel of the left transept are two high-reliefs in marble, executed by *Mich. Ongaro* in the 17th cent., representing the consecration by Pope Paul V. of the Patriarch Vendramin as cardinal, and an allegory of death. To the right, beyond the second altar, is a marble throne from Antioch, said to be that of St. Peter.

Nothing will convey to the traveller a better idea of the situation of Venice with its islands, than a visit to the **Lido**, where there are good sea-baths and a restaurant (see p. 207). A small steamer performs the trip in summer in 12 min. (p. 207). A gondola takes  $\frac{1}{2}$  hr.; a second rower had better be engaged, both for speed and for safety in case of the wind rising. The boatmen on the Lido generally make extravagant demands.

Interesting excursion to Murano, on an island about  $1\frac{1}{2}$  M. N. of Venice (omnibus-boat hourly, starting not far from S. Apostoli; Pl. 5; F. 2). Half-way we pass, on the right, the CEMETERY ISLAND (*Cimitero*), with the church of *S. Michele*, built by Moro Lombardo in 1466, with sculptures on its facade, and the pretty Cappella Emiliana, erected by Gugl. Bergamasco in 1530. — **Murano**, with 3400 inhab., originally an independent town, but afterwards dependent on Venice, possesses interesting treasures of art in its churches, dating from its most prosperous period. The CATHEDRAL *S. DONATO*, a vaulted church supported by columns, with transept resting on pillars, almost vies with St. Mark's in the splendour of its interior, its columns of Greek marble, mosaics, etc. An inscription on a marble slab inserted in the mosaic pavement of the church bears the date IIII. Over the side-door on the right a Madonna with saints, by *Lazzaro Sebastiani*. — **S. PIETRO MARITTE** is a simple and

spacious basilica of 1509. Near the door of the sacristy, to the left, is an Assumption by *Marco Basaiti*, in bad preservation, and a Madonna with saints and angels, by *Gior. Bellini* (between the 2nd and 3rd altars on the right). — Murano possesses an extensive manufactory of glass beads, mosaics in glass, crystal, etc. The *Museo* (adm. 40 c.) contains a good collection of these articles.

**Torcello**, situated on an island about 6 M. to the N.E. of Venice (omnibus-boat to Mazzorbo, see p. 207), the ancient *Altinum*, belonging to the town of *Burano* on a neighbouring island (6000 inhab.), is a poor place, consisting of a few small houses only and two well-preserved churches. The CATHEDRAL, S. MARIA, erected in the 7th cent., re-built in 1008, is a basilica in the early Christian style, supported by columns resembling those of Murano. The principal object of interest is the ancient arrangement of the semicircular seats of the priests on the tribuna, rising in steps and commanded by the lofty episcopal throne in the centre. On the W. wall of the interior is a large Mosaic of the 12th cent., representing the Sacrifice of Christ, the Resurrection, Last Judgment, etc., recently restored. In the choir a Madonna and the 12 Apostles in Byzantine mosaic. Below it is an ancient crypt with a font. — An octagonal BAPTISTERY of 1008 adjoins the cathedral. — S. Fosca, dating in its present form from the 12th cent., is externally octagonal (interior intended for a dome, but at present covered with a flat roof). On five sides it is enclosed by an arcade supported by columns (sixteen in number, and four corner-pillars), a structure worthy of the notice of architects.

**S. Lazzaro**, the Armenian Mechitarist monastery on the island of the same name, 2 M. to the S. E. of Venice, contains a considerable Oriental library, and a large printing-office.

**Chioggia**, 18 M. to the S. (steamer in 2 hrs., every afternoon, but on Sundays at 8 a. m.; fare 2 or 1½ fr.; also pleasure-trips occasionally), an ancient town at the end of the lagoons, was founded about the same period as Venice, by which it was soon conquered. During the war with Genoa it was taken by the Genoese (1379), but recovered by the Venetians the following year (comp. p. 209). The inhabitants have always differed materially in language and customs from the other inhabitants of the lagoon-districts. None of the churches are worthy of note. — The *Murazzi* (p. 213) are most conveniently inspected in the course of an excursion to Chioggia.

## 37. From Venice to Trieste.

### a. By Land, viâ Udine.

133 M. RAILWAY. Ordinary trains in 10 hrs. (fares 27 fr. 25, 20 fr. 5 c., 14 fr.); express in 7¾ hrs. (fares 30 fr. 55, 22 fr. 40 c., of which 7 fr. 33, or 5 fr. 88 c.; the amount due for the Austrian part of the journey, is payable in gold). Austrian custom house examination at Cormons. A supply of change is desirable, as cases of dishonesty are not infrequent at the Venice station.

Bridge across the *Lagune*, and *Fort Mulghera*, see p. 199. At *Mestre* the line diverges N. from that to Padua. Stations *Mogliano*, *Preganziolo*; then —

18 M. **Treviso** (*Albergo Reale; Stella d'Oro*), with 23,000 inhab., the capital of a province. The handsome, but unfinished old cathedral of S. PIETRO contains an Annunciation with the kneeling donor, by *Titian*, and an Adoration of the shepherds, the chief work of *Paris Bordone*, who was born here in 1500; the mural paintings are by *Gior. Ant. da Pordenone*. The Gothic church of S. NICCOLÒ contains pictures by *Bellini*, and the Madonna enthroned with saints as an altar-piece by *Fra Marco Pensabene*, commonly attributed to Seb. del Piombo. The *Town Hall* and *Theatre* are



fine edifices. The *Monte di Pietà* (pawn-office) contains a good Entombment by *Pordenone* (according to Mr. Crowe, and not by Giorgione). In the *Piazza dell'Indipendenza* a monument in memory of the liberation of Italy from the Austrian yoke, by *Borrò*, was erected in 1875. At Treviso, as well as in other Venetian towns on the mainland (such as Conegliano, Serravalle, Bassano, and Pordenone), the pictorial decoration of the façades, in various styles, differing both in point of subject (figures, decoration, or mottoes) and of execution (in sgraffito, grisaille, or coloured) are interesting. To these varied artistic efforts the impulse was doubtless given by Squarcione's school at Padua. — The *Villa Manfrini* possesses extensive gardens.

About 15½ M. to the N.W. of Treviso, on the road to Feltre, is situated the *Villa Masér*, erected by *Palladio*, for Marcantonio Barbaro, and adorned with frescoes by *P. Veronese*, which are among the best works of the master. A series of mythological representations and scenes from social life, grandly conceived, are here presented to us, while a number of the illusive figures so frequently used in the art of a late period are introduced. Such are, immediately by the entrance, a girl and a page, who through a half-opened door apparently watch the persons entering. The dining-room with its fantastically painted architecture is adorned with representations of Ceres with her train and Cupids. The ceiling of the great hall is decorated with paintings of the Council of the Gods, and the Feast of the Gods on Mount Olympus. Those who wish to obtain a good idea of a patrician abode of the luxurious 16th cent. should not omit to make this excursion.

For the continuation of the journey from Villa Masér to Possagno and Bassano, and through the Venetian mountains to Trent, comp. pp. 49, 48.

22 M. *Lancenigo*. Beyond (27 M.) *Spresiano* the train crosses the *Piave* and approaches the mountains, which it skirts as far as Sacile. The lofty Friaul Mts. continue in sight as far as Monfalcone on the Carso. — 30 M. *Piave*.

35 M. **Conegliano** (\**Posta*), birthplace of the celebrated painter *Cima* (d. 1517), surnamed *da Conegliano*, is commanded by an extensive and conspicuous castle on an eminence. The *Cathedral* contains an altar-piece by *Cima* (1492). With regard to the painting of the façades, see above.

FROM CONEGLIANO TO BELLUNO a road leads to the N., via *Ceneda*, *S. Croce*, and *Capo di Ponte* (diligence once daily in 6 hrs.).

**Belluno** (1365 ft.; *Due Torri*), capital of a province, with 14,600 inh., situated on a hill between the *Ardo* and the *Piave*, which here unite, presents all the features of a Venetian town. The *Cathedral*, erected by *Palladio*, is the finest of its fourteen churches. It contains several good altar-pieces and an ancient sarcophagus. The massive campanile, 216 ft. in height, commands a beautiful prospect. An old sarcophagus of some artistic merit adorns the small *Piazza* in front of the church of *S. Stefano*. The triumphal arch outside the gate was erected in 1815.

40 M. *Pianzano*. 45½ M. *Sacile*, a town on the *Livenza*, surrounded by walls and fosses, with a handsome palace of the *Podestà*, exhibits traces of its ancient importance. 53½ M. *Pordenone*, probably the *Portus Naonis* of the Romans, was the birthplace of the painter *Giov. Ant. Licinio da Pordenone* (d. 1540). The cathedral contains a *St. Christopher* by him.

Beyond (63 M.) *Casarsa*, the train crosses the broad channel of the *Tagliamento* by an iron bridge,  $\frac{1}{2}$  M. in length. The stony deposits of the stream have raised its bed so considerably that the next stat. *Codroipo* (Imperatore), situated between the *Tagliamento* and the *Corno*, lies 28 ft. below the level of the bottom of the former river.

To the right lies *Passeriano*, at the château of which the preliminaries of peace between France and Austria at the end of last century were adjusted, the treaty being finally concluded on 17th Oct. 1797, at the small village of *Campo Formio*, which also lies to the right of the line. By this treaty the Republic of Venice was dissolved.  $77\frac{1}{2}$  M. *Pasiano Schiavonesco*.

$84\frac{1}{2}$  M. **Udine** (*Italia; Croce di Malta*), formerly the capital of the Austrian province of Friaul, and a place of great importance, is an ancient town with 22,000 inhab., surrounded by walls of considerable antiquity. In the centre is the old town, with walls and fosses. Above it rises the castle, on an eminence, which according to tradition was artificially thrown up by Attila, in order that he might thence survey the conflagration of Aquileia (p. 248). Udine may in some respects be called a miniature Venice, as it presents several points of resemblance to the metropolis to which it was so long subject. It possesses a town-hall (*Palazzo Pubblico*) of 1457, burnt down in 1876, resembling the palace of the doges, two columns like those of the *Piazzetta* of Venice, a campanile with two figures which strike the hours, and a considerable library. The Romanesque *Cathedral* contains a few interesting pictures, and some fine sculpturing in wood and stone. In the *Episcopal Palace* a ceiling-painting by Giovanni da Udine. The *Castle*, now a prison, commands an extensive survey of the Friaul.

*Cividale*, the ancient *Forum Julii*, interesting on account of the numerous Roman antiquities which have been found here (Museum), lies 9 M. to the E. of Udine.

At (90 M.) *Buttrio* the train crosses the *Torre* by a long bridge.  $93\frac{1}{2}$  M. *S. Giovanni Manzano*, the Italian frontier-station (where the luggage of travellers coming from Austria is examined; railway restaurant). The train now crosses the *Natisone*. The small *Indrio* forms the frontier. 97 M. *Cormons* (Austrian custom-house), beyond which the *Isonzo* is crossed.

102 M. **Gorizia**, Germ. *Görz* (*Tre Corone; Hôtel Brandt*, new), the seat of a bishop, with 16,700 inhab., is charmingly situated on the *Isonzo* in a hilly district, and noted for its mild climate. *Cathedral* worthy of notice. In the upper part of the town is the dilapidated castle of the former counts of the place, partly used as a prison. The preserved fruit of Gorizia is highly esteemed.

Charles X. of France (d. 1836) is interred in the chapel of the monastery of *Castagnovizza*, on a height above the town. In the vicinity rises the *Monte Santo*, with a pilgrimage-church, commanding a fine view.

The train next crosses the *Wipbach*, a tributary of the Isonzo. To the left of stat. *Rubbio* is the château of that name. Fine view of the Alps, beyond the Isonzo. Stat. *Sagrado*. *Gradisca* with its church lies on a height to the left. The train now turns towards the S.E. 109 M. *Ronchi*.

115½ M. *Monfalcone* (Leone d'Oro). The train enters the stony wilderness of the Carso (p. 54), and the Adriatic comes in sight on the left. Thus far the Venetian style of church-architecture is prevalent throughout the coast-district, the slender campanile being always separate from the church as in the case of St. Mark's.

*Aquileia*, 18 M. to the W., once a most important Roman colony, and at that period strongly fortified, was the principal bulwark of Italy on the N.E. frontier. The population at the time of Augustus, who frequently visited the town, is computed to have been 100,000. It was then the great centre of the traffic between Italy and the N. and E. of Europe, and supplied the inhabitants of Illyria and Pannonia with grain, oil, and wine, in return for slaves and cattle. The incursions of the Romans into these districts were always undertaken from this point. In 452 Attila, exasperated by the obstinate resistance he encountered here, caused the city to be plundered and destroyed. The sole trace of its ancient glory is the *Cathedral*, erected in 1019-42, once the metropolitan church of the patriarchs of Aquileia. The place is now a poor village with 500 inhab., but interesting on account of the valuable antiquities frequently found in the neighbourhood. The collections in the *Battistero*, adjoining the cathedral, of Count Cassis, and the apothecary *Zantonati*, may be visited. In 1862 a large *Castellum Aquæ* was discovered between *Monastero* and *Aquileia*. One of the principal curiosities is a fine mosaic, with the Rape of Europa.

At *S. Giovanni* the *Timavo*, the *Timavus* of the Romans, which under the name of *Recca* (or *Rjeka*, i.e. river) is lost in the grottoes of the Carso near St. Canzian, re-appears after a subterranean course of 23 M., and falls into the Adriatic 1½ M. lower down. A pond formed by the river is crossed by a bridge. Farther on is *Duino*, with an ancient castle of Prince Hohenlohe.

At (125½ M.) *Nabresina* the line unites with the Vienna and Trieste Railway, and the train runs back a short way on the line just traversed. From this point to (133 M.) *Trieste*, see p. 54.

### b. Sea Voyage to Trieste.

STEAMBOAT (Austrian Lloyd) on Tues., Thurs., and Sat. (same days in the reverse direction) at midnight (during the four winter months at 9 a.m.) corresponding with the express train to Vienna; fare 9 or 6½ fl.. return-ticket, available for a fortnight, 13 or 10 fl. — A steamer of the *Società Peirano, Danovaro & Co.* also plies once weekly, leaving Venice on Sundays at 6 a.m. — Gondolas to or from the steamers, see p. 206.

The navigable channel is indicated by stakes. The small fortified island of *S. Andrea del Lido* commands the entrance to the harbour. Beautiful retrospect of Venice on moonlight nights. As Trieste is approached, a view is obtained of the distant, snow-clad *Julian Alps*, the lighthouse of *Salvore*, *Pirano*, the coast of *Istria* to the S.E., and *Capo d'Istria* in a bay. *Trieste*, see p. 55.

## VI. The Emilia.

The Emilia includes the former duchies of *Parma* and *Modena*, as well as the papal *Romagna*, and is now divided into the eight provinces of *Piacenza*, *Parma*, *Reggio*, *Modena*, *Bologna*, *Ferrara*, *Ravenna*, and *Forlì*, covering an area of 7921 sq. M., with a population of 2,113,828 souls. The dialects spoken here form the third main group of the Gallic languages of Upper Italy, and the nasal sound of the vowels will at once strike the traveller as indicating the original affinity of the people with the French. The Celts seem to have crossed the Alps in several different detachments. After the *Insubri* had conquered the district of Milan, and the *Cenomani* Brescia and Verona, the tribe of the *Boii* crossed the Po in the 5th cent. B.C., and subjugated the Etruscans and Umbrians who were settled to the S. of that river. They chose *Bologna* for their capital, in the name of which is still preserved that of the conquerors. The *Senones* next invaded Italy, and took possession of the coast district to the S. of the Boii, extending nearly to Ancona. It was a horde of these Gauls who destroyed Rome in B.C. 399. About a century later Italy, united under the guidance of Rome, began to reconquer the lost territory. In 283 the Senones were exterminated. In 269 a colony was established at *Ariminum*, which was constituted the strongest frontier fortress in the peninsula, and connected with Rome by the *Via Flaminia*. In 224 the Boii were subjugated, and in planting the colonies of *Placentia* and *Cremona* in 218, Rome extended her frontier as far as the Po. This process of Latinisation was interrupted by the invasion of Hannibal, but vigorously resumed after his defeat; and in 189 *Bologna*, and in 183 *Modena* and *Parma* received Roman colonies. *M. Aemilius Lepidus*, who was consul in B.C. 187, constructed a military road from Rimini to Piacenza, viâ Bologna, Modena, Reggio, and Parma, a distance of 150 M., called the *Via Emilia*, whence the whole district derived the ancient name which it still retains. Down to the time of Cæsar, although the Roman language and customs had spread rapidly here, the district was officially known as the 'Province of Gaul on this side of the Po', and the *Rubicon* formed the frontier of Italy; but in B.C. 43 it was finally united with the latter.

The institutions of antiquity lingered here longer than in any other part of Italy. In 404 the Emperor Honorius transferred his residence to Ravenna, which also continued to be the capital of the Gothic Kings. After the overthrow of Gothic domination by *Belisarius* in 539, Ravenna became the seat of the *Exarchs*, and the Italian centre of the *Eastern Roman Empire*. The *Lombards* afterwards attacked and took possession of it, but it was soon wrested from them by the Franconian king *Pepin*, who is said to have presented the whole exarchate, i.e. the coast district from the Po to Ancona, to the *Romish Church* in 756. At first, however, the real supremacy over the district was held by the Archbishop of Ravenna. The STATES OF THE CHURCH never constituted a uniform whole like those of Milan or Venice. They consisted of a number of towns, principalities, and monasteries, often estranged from the pontifical throne, and not unfrequently in arms against it. The pope appointed cardinals as his legates in the different districts, but their power was limited, as the most important prerogatives were usurped by his subjects. Meanwhile the TOWNS in the Emilia prospered greatly, and became famous as cradles of SCIENCE, notwithstanding the feud between Guelfs and Ghibellines, princes, nobles, and burghers, which raged within and without their walls. *Roman Law*, which after the Germanic invasion had been preserved in several towns and districts, began to be studied scientifically at *Ravenna* in the 11th cent. From the 12th cent. onwards, owing to the unsettled condition of rights, the study became very prevalent, *Bologna* being its great centre, whence a knowledge of Roman Law gradually extended over the other countries of Europe (comp. p. 271).

The POLITICAL HISTORY of these districts during the middle ages records continual struggles for precedence among several rival powers. As long as the power of the emperors was in the ascendant, they kept the

pretensions of the popes in check. During the exile of the popes at Avignon, the dismemberment of the papal dominions seemed imminent, but after protracted combats was prevented by *Cardinal d'Albornoz*, a valiant Spaniard, who was sent to Italy by *Innocent IV.* in 1353. Even those princes, however, who consented to acknowledge the papal supremacy, still continued practically independent. *Alexander VI.*, who was elected pope in 1492, and his son *Cesare Borgia* at length put an end to this insubordination; they extirpated the dynasties of the Romagna with fire and sword, and from that period the papal feuds began to be gradually converted into a state in the modern sense. Under *Julius II.* and *Leo X.* the papal supremacy was farther extended to Modena, Parma, and Piacenza. In 1545 *Paul III.* *Farnese* invested *Pier Luigi*, his natural son, with the two last as a duchy, which, on the extinction of the *Farnese* in 1731, came into the possession of the Spanish *Bourbons*. In Modena and Reggio, the house of *Este* maintained its supremacy in spite of the papal pretensions, while Ferrara in 1597 was incorporated with the states of the church.

The whole of the existing institutions were at length overthrown by the French Revolution. NAPOLEON united Parma to France, and annexed Modena and the Romagna to his kingdom of Italy. 'At that time,' writes *Cesare Balbo*, 'Italy was doubtless entirely subjugated by a foreign power, but no period of subjection had ever been so cheerful, so active, perhaps useful, and even great and glorious, as this. The foreign yoke was, moreover, the less ignominious, as it was imposed on Italy in common with one half of the rest of Europe, by a man so great and so marvellously enterprising, and one who by birth, and certainly in character and name, was himself an Italian. The country had not achieved independence, but the hope of it had never been so near realisation; the people were not yet free, but they enjoyed equality, an advantage regarded by many as equivalent to liberty. The name of Italy now began to be honoured and loved, and the country to be spoken of as a united whole, while the petty municipal and provincial jealousies, which had become deeply rooted in the course of centuries, began gradually to disappear.' On the fall of Napoleon the AUSTRIANS obtained supremacy over these districts. Parma was awarded to *Marie Louise*, and Modena to *Archduke Francis*, the heir of the last *Este* (who died in 1803 with the title of Duke of Breisgau). The worst lot befel the Romagna, in spite of the entreaty addressed by its ambassadors at the Congress of Vienna, rather to hand over their country to an 'infernal than to the papal government'. By an edict of 15th August 1814, no fewer than 1824 dissolved monasteries, and 612 nunneries were re-erected in the STATES OF THE CHURCH. The Code Napoleon was abolished, and the ecclesiastical administration, as organised by *Sixtus V.* in 1590, re-established. The four northernmost provinces, Bologna, Ferrara, Ravenna, and Forli, were governed by a cardinal with the title of *Legate* (whence these districts were called legations), whose sway was arbitrary and despotic in the extreme. The courts of justice and all the chief magistracies were administered by priests, and never probably had a government earned for itself such a fund of hatred from its subjects. In 1821, 1830, and 1848, the Emilia succeeded in throwing off the yoke of its dukes and legates, but on each occasion the insurrection was crushed by Austrian intervention. The war of 1859 rendered the rising under *Parini* a more successful undertaking, and by the plebiscite of 12th March 1860, the annexation of the Emilia to Piedmont was accomplished.

### 38. From Milan to Bologna, Piacenza, Reggio.


135 M. RAILWAY in 5 $\frac{3}{4}$ -7 hrs. (fares 24 fr. 45, 17 fr. 15, 12 fr. 25 c.). To Piacenza 43 M., in 1 $\frac{1}{2}$ -2 $\frac{1}{2}$  hrs. (fares 7 fr. 80, 5 fr. 50, 3 fr. 90 c.).

*Milan.* see p. 118. At (3 $\frac{1}{2}$  M.) *Regredo* the line to Pavia diverges to the right (see p. 161). 11 M. *Melegnano*, formerly *Marignano*, is a memorable place in the annals of mediæval and modern warfare. Here, on 14th Sept., 1515, Francis I. of France,



# PIACENZA.

1: 20 000  
 0 100 200 300 400 500  
 Metri



- |                           |              |
|---------------------------|--------------|
| 1. Duomo                  | E. 3. 4.     |
| 2. S. Agostino            | D. 4. 5.     |
| 3. S. Antonio             | D. E. 4. 10. |
| 4. S. Francesco il Grande | D. 3. 11.    |
| 5. S. Giovanni in Canale  | C. 3. 12.    |
| 6. S. Maria di Campagna   | A. 2. 13.    |
| 7. S. Maria               | G. 4. 14.    |
| 8. S. Spirito             | B. 2. 15.    |
| 9. S. Sisto               | D. 1. 16.    |
|                           | F. 3.        |
|                           | B. 2.        |
|                           | D. 3.        |
|                           | D. 2. 3.     |
|                           | E. 3.        |
|                           | D. 4.        |
|                           | D. 1. 16.    |
|                           | F. 3. 4.     |
|                           | D. E. 4. 10. |
|                           | D. 3. 11.    |
|                           | C. 3. 12.    |
|                           | A. 2. 13.    |
|                           | G. 4. 14.    |
|                           | B. 2. 15.    |
|                           | D. 1. 16.    |
|                           | F. 3.        |
|                           | B. 2.        |
|                           | D. 3.        |
|                           | D. 2. 3.     |
|                           | E. 3.        |
|                           | D. 4.        |
|                           | D. 1. 16.    |
|                           | F. 3. 4.     |

in his campaign against Milan, defeated the Swiss allies of the city, 7000 of whom fell in the action. In the environs, and especially in the town itself, a sanguinary conflict took place between the French and the Austrians, on 7th June, 1859, resulting in the retreat of the latter. 15½ M. *Tarazzano*. Innumerable cuttings for purposes of irrigation and drainage here intersect the plain.

20½ M. **Lodi** (*Sole; Gambero*), a town with 19,000 inhab. (4½ M. E. of which lies *Lodi Vecchio*, the ancient Roman colony of *Laus Pompeia*). was one of the bitterest enemies of Milan in the middle ages. It is celebrated as the scene of Napoleon's storming of the bridge over the Adda, 10th May, 1796. Excellent Parmesan cheese is made in the neighbourhood. The *Cathedral* contains an ancient relief of the Last Supper. The Renaissance church of \**Incoronata*, erected by Bramante in 1476, is adorned with frescoes by Calisto Piazza da Lodi, a pupil of Titian.

28 M. *Secugnago*; 32½ M. *Casalpusterleno* (branch-line to Pavia and Cremona, see p. 164); 35½ M. *Codogno*; 38 M. *S. Stefano*.

43 M. **Piacenza**. — *CROCE BIANCA* (Pl. c; D, 2), in the Strada al Dazio Vecchio; *S. MARCO* (Pl. a; D, 2), Strada S. Marco; *ITALIA* (Pl. b; D, 3), Strada del Guasto.

*Café Battaglia*, in the Piazza; *Café Grande*, in the Strada di S. Raimondo, a little to the S. of the Piazza.

*Cab* with one horse ½ fr., with two horses 75 c.; at night 75 c. or 1 fr. 10 c.; each box 25 c.

*Piacenza*, French *Plaisance*, the capital of a province, with 34,000 inhab., and an episcopal see, lies on the S. bank of the Po, which is crossed by an iron bridge. The streets are broad and dull, but there are several interesting churches.

Piacenza was founded by the Romans, B.C. 219, as *Colonia Placentia*, at the same time with Cremona. In the middle ages it held a high rank in the league of the Lombard towns, and was afterwards frequently the subject of fierce party-struggles between the Scotti, Torriani, and Visconti. In 1488 it was plundered by Francesco Storza, a blow from which it never entirely recovered. In 1545 it finally came into the possession of the Farnese family and was united to Parma.

In the **PIAZZA DE' CAVALLI** (Pl. D, 3) is situated the \**Palazzo del Comune* (Pl. 12), erected at the end of the 13th century. On the ground-floor there is a spacious arcade with five pointed arches; in the upper floor are six rich round-arch windows, above which rise handsome pinnacles. In front of it stand the equestrian *Statues of the Dukes Alessandro and Ranuccio Farnese*, erected 1620-24, by Francesco Mocchi, a pupil of Giovanni da Bologna. Alessandro attained great distinction in the wars in the Netherlands as governor under Philip II. He took Antwerp in 1585, besieged Paris in 1591, and died at Arras in 1592. He was succeeded by his tyrannical son Ranuccio (d. 1622).

*S. Francesco* (Pl. 4), a brick edifice in the Piazza, with Gothic interior, was erected in 1278. In front of it rises a statue to *Romagnosi*, professor of constitutional law at Parma, and editor of



the new Italian penal code (see p. 127): — The principal street (Via Diritta) leads to the E. to the —

\**Cathedral* (Pl. 1; E. 3, 4), a Romanesque-Lombard edifice dating from 1122, with a superstructure of brick added in the 13th cent., containing admirable frescoes by *Guercino* (prophets and sibyls) on the dome, and by *Lodovico Carracci* on the arch of the choir, and pictures by *Procaccini* (in the choir), and by *Andrea* and *Elisabetta Sirani* over the 3rd altar on the right. The crypt is borne by 100 columns. — In the vicinity (take the first side-street to the left on leaving the cathedral) is —

*S. Antonino* (Pl. 3; D, E, 4), formerly the cathedral, dating from 903, 1104, and 1562, with a fine old vestibule, called 'Paradiso' (1350), of curious irregular shape, and a tower borne by eight massive round columns in the interior.

We return to the Piazza by the Via S. Antonino, turn to the right past the *Palazzo Comunale*, and follow the Strada Campagna to the right to the church of —

*S. Maria della Campagna* (Pl. 6; A, 2), said to have been erected by *Bramante*, but disfigured by alterations. It contains some admirable frescoes by *Pordenone* (to the left of the entrance St. Augustine), paintings in the two chapels on the left with small domes, and also in the large dome. Behind the high-altar is a Descent from the Cross, after *Tintoretto*. — We return by the Str. Campagna and turn to the left to the church of —

\**S. Sisto* (Pl. 9; D, 1), the richest in Piacenza, erected in 1499-1511, with an Ionic atrium. About 1518 Raphael painted for this church his master-piece, the Sistine Madonna (Madonna with St. Sixtus and St. Barbara, now at Dresden), which was sold in 1753 to King Augustus III. of Poland for 20,000 ducats and replaced by a copy by *Avanzini* (beginning of 18th cent.). The choir contains pictures by *Camillo Procaccini*, *Palma Giovane*, etc.; also several good intarsias and (in the left transept) the monument of Margaret of Austria (d. 1586), daughter of Charles V. and wife of Ottavio Farnese, Duke of Parma, the father of Alessandro Farnese.

A little to the E. of S. Sisto is the *Palazzo Farnese* (Pl. E, 2), erected in a magnificent style by *Vignola* during the reign of Margaret in 1558, one of his first great works. It was never completed, and is now a barrack. — On the S.W. side of the town is the *Cibadel* (Pl. A, B, 3, 4), erected in 1547,

About 24 M. to the S.W., in the valley of the Trebbia, lies the small town of **Bobbio**, once famous for the *Library* which belonged to the monastery founded here by St. Columbanus in 612, but which was dispersed on the dissolution of the abbey. This library contained the palimpsests from which the learned *Angelo Mai* (born at Bergamo in 1782, librarian of the Vatican in 1819, cardinal in 1833, d. at Albano near Rome in 1854) brought to light so many valuable ancient works, among others 'Cicero de Republica' in 1822.

The remains of the ancient town of **Velleia**, which is believed to have been buried by a landslip in the reign of the Emp. Probus (about





278). are also 24 M. from Piacenza. Various antiquities excavated here in 1760-75 are now in the museum at Parma (p. 258). An amphitheatre, temple, forum, etc. have also been discovered. The route to Velleia is by *S. Polo*, *S. Giorgio* on the *Nure*, with a villa of the Scotti erected by *Vignola*, *Rezzano*, and *Badagnano* (where the carriage-road terminates).

The RAILWAY FROM PIACENZA TO BOLOGNA follows the direction of the *Via Emilia*, the road constructed by the Roman Consul M. *Æmilius Lepidus*, B.C. 187, and named after himself (comp. p. 249), several traces of which still exist. The train passes *S. Lazaro*, an ecclesiastical seminary greatly enriched in the 18th cent. by the eminent Cardinal *Alberoni*, who was born at *Fiorenzuola* in 1664 (d. 1752). The church contains his tomb, and pictures by *Procaccini*, *Zuccherò*, etc.

Near (48½ M.) *Ponte Nure* the train crosses the *Nure*, and soon passes *Fontana Fredda*, where *Theodoric the Great* and the Lombard kings once possessed a country-residence. The *Arda* is now crossed. 56½ M. *Fiorenzuola*, a small but thriving place, whence a visit may be paid (rough road via *Castel Arquato*) to the ruins of *Velleia* (see above).

61½ M. *Alseno*. — Then the small town of (65½ M.) **Borgo San Donnino** (*Croce Bianca*; *Angelo*), the ancient *Fidentia Julia*, which received its present name in 387 from *St. Dominicus*, who had suffered martyrdom about a century earlier, under *Maximian*, and to whom the ancient \**Cathedral* is dedicated. This church is one of the finest in N. Italy; the admirable façade (the upper part unfinished) has three lion portals in the Lombard style; and the interior with its round-arch arcades is of symmetrical proportions.

71 M. *Castel Guelfo*, with the *Torre d'Orlambò*, a ruined castle erected by the Ghibelline *Orlando Pallavicino* about 1407, for protection against the Guelph *Ottone Terzi* of Parma. The train crosses the river *Taro* over which the road is carried here by a bridge of twenty arches, constructed in 1816-21 (under *Duchess Marie Louise*, ex-*Empress of the French*), and commanding a charming view of the *Apennines*. The costumes of the peasant-women here are picturesque.

79½ M. *Parma*, see p. 255.

The train crosses the *Enza*, formerly the boundary between the duchies of Parma and Modena, and, beyond (84½ M.) *S. Ilario*, the *Crostolo*.

96½ M. **Reggio**. — ALBERGO DELLA POSTA, in the main street; CAVALLETTO, near the Piazza, R. 1½, A. ½ fr.

Café *Vittorio Emanuele*.

Cab, per drive 80 c., per hour 1½ fr. at night 1 fr. and 2 fr. 20 c. respectively.

*Reggio*, which is also called *Reggio nell'Emilia* to distinguish it from *Reggio* in Calabria, the ancient *Regium Lepidi*, is a town with 21,000 inhab., possessing broad, well-built streets flanked with arcades. *Lodovico Ariosto* (d. 1533), the greatest Italian poet

of the 16th cent., was born here on 8th Sept. 1474 in a house near the Municipio, which is still shown (Pl. 4).

In the PIAZZA MAGGIORE (Pl. C, 3), nearly in the centre of the town, is situated the \**Cathedral* (Pl. 5), erected in the 15th cent., with a Renaissance façade, completed only in the lower part, in which interesting traces of the earlier Romanesque church of the 12th cent. are still observable. At the principal entrance are colossal statues of Adam and Eve by *Clementi* of Reggio (d. 1584), a pupil of Michael Angelo. The other statues on the façade are by his pupils.

The INTERIOR, which has a lofty choir and a crypt, contains several statues and monuments by *Clementi*, the finest being the monument of Ugo Rangoni, Bishop of Reggio, and nuncio of Paul III. at the court of Charles V. (in the chapel to the right of the choir); the monument of Horatius Malegntius is also attributed to him, dating from 1583 (immediately on the right of the entrance). — In the 1st chapel on the left is the tomb of *Clementi*, with his bust, by his pupil *Pacchione* (1588).

On the S. side of the piazza is the *Municipio* (Pl. 18); at the entrance is a marble bust of General Cialdini, who was born here.

Proceeding to the right past the Municipio, and following a broad street to the right, we next reach the church of the \**Madonna della Ghiara* (Pl. 6; A, 3), built in 1597 from a design by Balbi, in the form of a Greek cross covered with a dome.

The INTERIOR is adorned with frescoes in the nave as far as the dome and in the N. aisle by *Luca Ferrari* (1605-54) of Reggio, a pupil of Guido Reni. The altar in the latter, presented by the town in 1621, has an altar-piece by *Guccino*. The frescoes in the choir are by *Tiarini* of Bologna, of the school of the Caracci; the Annunciation at the back of the high altar is by *Carlo Caltari* (brother of Paolo Veronese), and the frescoes in the S. transept are by *Lionello Spada* and others.

Passing through the arches to the right of the cathedral, we reach the PIAZZA MINORE, with the church of *S. Prospero* (Pl. 14; C, 3, 4), re-erected in 1504 by *Gasparo Bisi* on the site of an earlier Lombard edifice, to which the six marble lions of the façade originally belonged. The choir contains damaged frescoes by *Campi* and *Procaccini*, and pictures by *Tiarini*.


The *Madonna della Concezione* (Pl. 7; C, 2) is a handsome modern church near the theatre. — The *Theatre* (Pl. C, 2), the chief boast of Reggio, is a remarkably fine edifice for so small a town.


The *Museum* (Pl. 16; C, 2) contains the natural history collection of the celebrated *Spallanzani*, born at Reggio in 1729 (d. 1799). — The *Library* (Pl. 3; B, 4) contains 56,000 vols., and 1066 MSS.

**Correggio**, 9 M. to the N.E. of Reggio, formerly the capital of a principality belonging to the Duchy of Modena, was the birthplace (in 1494) of the celebrated painter *Antonio Allegri da Correggio*. Old copies of his two earliest works are preserved here.

EXCURSION TO CANOSSA (see small map on the plan of Reggio), 8 hrs. there and back; carriages at the 'stabilimento di vetture' at Reggio near the Albergo della Posta (with one horse 10-15, with two horses 20-25 fr.). The route is by the road to Massa (p. 116), traversing a fertile and picturesque plain, enclosed by hills which at first are sprinkled with villas,







## Chiese

|   |                                      |          |
|---|--------------------------------------|----------|
| 1 | <i>Cattedrale</i>                    | F. 3.    |
|   | 2 <i>Battisterio</i>                 | F. 3.    |
|   | 3 <i>S. Alessandro</i>               | E. 3.    |
|   | 4 <i>S. Andrea</i>                   | E. 4.    |
|   | 5 <i>S.S. Annunziata</i>             | C. D. 4. |
|   | 6 <i>S. Antonio</i>                  | G. 4.    |
|   | 7 <i>Cappuccini (nuove)</i>          | F. 6.    |
| 2 | 8 <i>S. Gristina</i>                 | F. 4.    |
|   | 9 <i>S. Francesco del Prato</i>      | G. 2.    |
|   | 10 <i>S. Giovanni Evangelista</i>    | G. 3.    |
|   | 11 <i>Madonna della Steccata</i>     | E. 3.    |
|   | 12 <i>S. Michele</i>                 | H. 4.    |
|   | 13 <i>S. Paolo (ora S. Ludovico)</i> | F. 2.    |
|   | 14 <i>S. Sepolcro</i>                | H. 4.    |
|   | 15 <i>S. Tommaso</i>                 | F. 5.    |
|   | 16 <i>S.S. Trinità (vecchia)</i>     | F. 2.    |
|   | 17 <i>S. Udarico</i>                 | F. 6.    |

## Palazzi

|   |                               |          |
|---|-------------------------------|----------|
| 4 | 18 <i>P. Ducale (Farnese)</i> | E. 3.    |
|   | 19 <i>del Giardino</i>        | C. I. 2. |
|   | 20 <i>del Comune</i>          | E. 3.    |
|   | 21 <i>della Podesteria</i>    | F. 4.    |

## Istituti pubblici

|   |                                               |          |
|---|-----------------------------------------------|----------|
| 5 | 22 <i>Accademia delle Belle Arti</i>          | D. E. 2. |
|   | 23 <i>Biblioteca</i>                          | D. E. 3. |
|   | 24 <i>Collegio Lalatta (ora Maria Luigia)</i> | H. 4. 5. |
|   | 25 <i>Congregazione delle Carità</i>          | E. 4.    |
|   | 26 <i>Orto Botanico</i>                       | F. 6.    |
| 6 | 27 <i>Seminario</i>                           | F. 3.    |
|   | 28 <i>Tipografia Bodoni</i>                   | D. E. 2. |
|   | 29 <i>Università</i>                          | E. 4.    |
|   | 30 <i>Teatro Farnese</i>                      | E. 2.    |
|   | 31 <i>Nuovo</i>                               | E. 3.    |
| 7 | 32 <i>Posta delle Lettere</i>                 | G. 4.    |





and leading by *Pajanello* and *Vezzano* (on the hills to the right lies *Quattrocastella*, with the ruins of four castles which once belonged to the Countess Matilda of Tuscany, d. 1115) to the small village of *Pecorile* (tavern). The route beyond this point must be continued on horseback or on foot. The path cannot be mistaken. It leads through the village, and then to the right towards the church of *Cusola*, which is left on the hill to the right; at the angle of the hill *Canossa* comes in sight, and the path leads in the direction of the village along the dreary bed of the *Campola*. The walk to the foot of the castle hill takes 1 hr.; we then ascend for 1/2 hr. in the direction of the church of S. Paolo which lies three-quarters of the way up the hill, follow a level path round the castle-rock and at the back of the small village of *Canossa* (poor tavern), and lastly mount to the summit of the rock, which is crowned by the scanty, ivy-clad ruins of the castle of *Canossa*. The castle once belonged to the Countess of Tuscany above mentioned, and was afterwards destroyed by the inhabitants of Reggio in 1255. The Emp. Henry IV. performed penance here in presence of Pope Gregory VII. during three days in 1077. The castle-well contains good water. \*Magnificent view of the Apennines towards the S., with the well preserved castle of *Rossena* in the foreground, and of the vast plain of the Po towards the N., with Parma, Reggio, and Modena.

104 M. *Rubiera*. The *Secchia* is then crossed.

111 1/2 M. *Modena*, see p. 260.

The train continues to follow the direction of the Via *Æmilia* and crosses the *Panaro* near *S. Ambrogio*. — 119 M. *Castelfranco*, a small town, supposed to be the *Forum Gallorum* where Antony was defeated by Octavian and Hirtius, B.C. 43. Near (124 M.) *Samoggia* and *Lavino* the train crosses the rivers of these names, and then the narrow *Reno*, the ancient *Rhenus*, or *Annis Bononiensis*. As Bologna is approached the country is open and richly clothed with vegetation; the *Monte della Guardia* (p. 284) is a conspicuous point.

135 M. *Bologna* (\*Rail. Restaurant), see p. 270.

### 39. Parma.

**Hotels.** \**CROCE BIANCA*, in the Piazza Grande; *POSTA*, Strada Maestra S. Michele 101, R. 2, L. 1/2, omnibus 3/4 fr.; *ITALIA*, Via S. Lucia, near the cathedral; *LEONE D'ORO*, in the Corso S. Michele.

*Caf  Carour*, Via S. Lucia.

*Cab* to or from the station 1 fr., two-horse 1 fr. 60 c.; at night 1 1/2 or 2 fr.; per hour 1 fr. 60 c. or 2 fr. — Omnibus 40 or 50 c., trunk 20 c.

*Parma*, situated on the river *Parma*, a small tributary of the Po, the capital of a province (formerly a duchy), is a town of entirely modern appearance, but of very ancient origin, with broad streets, and many spacious, neglected-looking buildings, numbering 45,000 inhab. It possesses a university founded in 1599, and the silk and felt-hat manufactories are important.

Parma was founded by the Etruscans, afterwards conquered by the Gauls, and at a later period by the Romans, and in B.C. 183 was erected into a Roman colony at the same time with *Mufina* (Modena). It was subsequently extended by Augustus, and called *Colonia Julia Augusta Parma*. Both in ancient and modern times its woollen manufactories have rendered it a place of some consequence. It participated in the general development of the towns of Upper Italy, zealously espoused the cause of the Guelphs, and in 1245 was long unsuccessfully besieged by Emp. Freder-

ick II. In 1303 *Ghiberto da Correggio* obtained possession of the supreme power. In 1341, after various vicissitudes, Parma came into the hands of the *Visconti*, and from that period down to 1512 was generally united with the Duchy of Milan. In 1545, after it had been annexed to the States of the Church, it was presented by *Pope Paul III.*, with Piacenza, to his infamous son *Pier Luigi Farnese*. This prince was assassinated in 1557, and was succeeded by eight dukes of his family, after which the male line became extinct in 1731. *Elizabeth*, the daughter and sole heiress of Duke Odoardo II., was married to King *Philip V. of Spain*, and by the quadruple alliance concluded at London in 1718, the succession was secured to their son *Charles*, who, however, ascended the throne of Naples in 1734, and deprived Parma of many treasures of art which now grace the national museum at Naples. By the Peace of Aix-la-Capelle in 1748 the duchy was ceded by Austria to his younger brother *Philip*; in 1807 it was annexed to France, and in 1815 awarded to *Marie Louise*, who ruled better than the Italian princes, and benefited the country by the construction of roads. In 1847, after her death, it came into the possession of the Bourbons, who had hitherto been indemnified with Lucca. *Charles II.* was banished, in 1848 *Charles III.* was assassinated in the open street, and in 1859 his widow withdrew along with the Austrian garrison. The Duchy covered an area of 2216 sq. M. and had a population of about half-a-million souls.

Parma owes its importance in the HISTORY OF ART to *Antonio Allegri of Correggio* (p. 254), who lived here in a quiet and modest style, and died early. It was not till a later period, when he was followed by the *Caracci*, that his merits were duly appreciated (characteristics, see p. lxx). The best known of his pupils is *Francesco Mazzola*, surnamed *Parmegianino* (1503-40), an excellent portrait painter, and a native of Parma.

The ancient *Via Emilia* (p. 249) intersects the town, from the *Porta S. Michèle* to the *Porta S. Croce*, crossing the \*PIAZZA GRANDE (Pl. E, F, 4), in which rises the *Palazzo del Comune*, or *del Governore* (Pl. 20, E, 3). In front of this edifice is a Statue of Correggio, erected in 1872. — A little to the N. rises the —

\**Cathedral (Il Duomo; Pl. I; F, 3)*, an admirable example of the Lombard-Romanesque style, begun in 1117, but not completed till the 13th cent. It is a cruciform building covered with a dome, with somewhat raised choir above a crypt, and a broad façade with a triple columnar gallery. The three portals are embellished with two huge lions and four of smaller size, executed in 1281 by *Bono da Bisone*, and sculptures by *Bianchino*, 1493.

The INTERIOR, consisting of nave and aisles, rests on fourteen articulated pillars, above which runs a fine triforium. The vaulting of the nave was painted by *Girolamo Mazzola*. 3rd chapel on the right, a Descent from the Cross in relief by *Benedetto Antelami* (1178); 4th chapel, frescoes of the 15th cent.; 5th chapel, frescoes by *Rondani*, a pupil of Correggio. To the right of the steps to the choir is the *Cappella S. Agata* with an altar-piece by *Gatti*, and on the right a bust of Petrarch, who was archdean of the cathedral, a work of 1713. The octagonal DOME is adorned with an Assumption by *Correggio* (see above), to whom Parma is chiefly indebted for its importance in the history of art; this was one of the last (1526-30) great works of the master, but has unfortunately been much injured by damp. The figures and groups of angels are especially admired. Noon is the best hour for inspecting the painting. Persons not liable to dizziness may ascend into the dome to examine the painting more closely, but no great advantage is thus gained. (Copies in the picture-gallery, see p. 242.) To the right, above the tribune are portraits of Correggio and his family. In the CHOIR, David and St. Cecilia, by *Camillo Procaccini*, and good half Gothic stalls by *Cristoforo Lendenari* (1473). — The CHURCH, a spacious cruciform structure with thirty-eight columns, contains monuments of

(r.) the Canon Montini (1507), the jurist Prati farther on, by *Clementi* (1542), and of Bernardo degli Uberti. Principal altar also by *Clementi*. 5th Chapel to the left of the entrance, frescoes of the 14th cent., on the left History of St. Peter, on the right SS. Sebastian and Catharine. — The SACRISTY also contains frescoes of the same period, and intarsias by *Lucchino Bianco*.

The \***Baptistry** (*Battistero*; Pl. 2; F, 3), constructed of white marble darkened by age, externally octagonal, with four round-arched portals, and consisting of six stories with colonnades, and a flat roof surmounted by eight turrets, was designed by *Benedetto Antelami*, and erected in 1196-1270. Around nearly the whole exterior of the building runs a series of medallions, representing various animals of symbolical import. The portals are adorned with the following scriptural subjects: —

At the N. Portal (towards the Piazza), above, is the Nativity of Christ; then the History of John the Baptist; on the door-posts are genealogical trees of Jacob and of Jesse. — At the W. Portal, above, a curious representation of the Last Judgment. On the door-posts to the left, Christ performing works of mercy; on the right, the six ages of man. — On the S. side is an Allegory of Death from the biblical romance of Barlaam and Josaphat. All these are probably by *Benedetto Antelami*, whose name appears as the master from the inscription on the portal.

The INTERIOR (closed; key in the house opposite the S. entrance) is sixteen-sided, with niches below and two galleries above, and graceful columns on the walls. The sculptures have only been partly completed. The old frescoes in the dome (13th-14th cent.) represent the history of John the Baptist and prophets, with a number of saints below. The whole population of Parma since 1216 is said to have been baptised here. The font dates from 1291. Altar-piece by *Filippo Mazzola* (15th cent.).

At the back of the cathedral is situated the church of —

\***S. Giovanni Evangelista** (Pl. 10; G, 3), belonging to an ancient Benedictine monastery, which has been recently restored. This elegant cruciform structure, covered with a dome, with aisles and two series of chapels, was erected in 1510 by *Bernardino Zaccagni* (not Bramante).

INTERIOR. In the two first chapels on the left, "frescoes by *Parneggiano* (SS. Lucia and Apollonia, two deacons, S. Giorgio and S. Agata); in the 1st chapel on the right, a handsome monument of the Countess Sanvitale-Montenuovo; in the 2nd a \*Nativity, by *Giacomo Francia*, 1519. The sombre DOME is adorned with "Frescoes by *Correggio*, representing Christ in glory, surrounded by apostles and angels, painted in 1520-24 (the best time to see them is at noon or 4 p.m.; copies in the picture-gallery, see p. 258). The half-dome of the *Choir* containing a Coronation of Mary by *Correggio* was removed in 1584 (the original of the principal group is in the Library, p. 259; copies of other parts of this great composition by Ann. and Ag. Caracci are in the picture-gallery, see p. 258). The new dome of the choir was adorned with a copy of the complete work by *Cesare Aretusi*. The handsome choir-stalls are by Zucchi and Testa. In the archway of the door of the sacristy (N. transept) \*S. Giovanni by *Correggio*. — The picturesque monastery-courts (to the left of the church) are not now accessible. Among the guests who have been entertained in the monastery were King Charles Emmanuel, when a fugitive in 1798, Pope Pius VI. as a prisoner of the French in 1799, and Pope Pius VII. in 1805.

The \***Madonna della Steccata** (Pl. 11; E, 3), an imitation of St. Peter's (a Greek cross with rounded ends), designed by *Bernardino Zaccagni* in 1521, is situated in the street leading from the principal piazza to the (formerly) ducal palace.

INTERIOR. The corner-chapel to the left of the entrance contains a Madonna of the school of *Fil. Mazzola* (earlier than Correggio). In the corner-chapel between the choir and the S. transept, monuments (r.) of Duke Ottavio Farnese and (l.) of Sforzino Sforza, the latter by *Gior. Franc. da Grado*, 1529. The archway of the choir is adorned with frescoes by *Parmeggianino*, the tribune with frescoes by *Anselmi*. Corner-chapel on the right of the choir: monument of Guido da Correggio, by *G. F. da Grado*: the 1st chapel on the right contains the monument of Beltrando Rossi, probably also by *da Grado*.

In the PIAZZA DI CORTE (Pl. E. 3) is the *Palazzo Ducale* (Pl. 18), now the seat of the Prefettura.

To the N.E. of the Palazzo Ducale, which is passed on the right, is the \**Palazzo della Pilotta* (Pl. E. 2), an extensive block of buildings, begun in 1597 by the *Farnese*, but never completed, containing a very valuable collection of antiquities and pictures, as well as a considerable library (cross the court and ascend a broad flight of steps to the left): open daily 9-4, adm. 1 fr.; on Sund. and festivals 10-2, gratis.

In the half-story is the *Museo di Antichità*, containing Roman antiquities, chiefly from the excavations of Velleia (p. 253) begun by Philip Bourbon in 1760. I. Room. Late bronzes. The cabinets contain coins. — II. Room. Bronzes: Apollo; Bacchus; head of a child; Hadrian in gilded bronze; drunken Hercules, a bronze statuette; the *Tabula Alimentaria* of Trajan, containing directions for the maintenance of poor children; terracottas, ancient and mediæval coins, golden trinkets of the later imperial epoch. — III. Room. Architectural fragments from the excavations (1844) in the ancient theatre of Parma; Head of Oceanus in alabaster; Mosaic with figures over the door. — IV. Room. To the left of the door, a good torso of a youth; Zeus; four draped female statues (among them Livia); torso in basalt; L. Verus (all these from Velleia); bust of Marie Louise by *Canova*. A corridor to the left of the 3rd room contains a few Egyptian antiquities. Adjacent is the — V. Room, containing vases (Peleus and Thetis, Bellerophon and the Chimæra, Theft of the Tripod). — VI. Room. Valuable collection of relics of the prehistoric flint and bronze periods. — A staircase descends from the first room to an apartment containing Roman inscriptions, some of them of Christian origin, arranged according to the places where they were found.

The *Picture Gallery* is on the first floor. I. Room: nothing worthy of note. — II. Room. On the left, \*31. Madonna della Scala (formerly in the church della Scala), a celebrated picture by *Correggio*, unfortunately much damaged; 44. *Francesco Mazzola*, surnamed *Parmeggianino*, Nuptials of the Virgin; 74. *Girolamo Mazzola*, Holy Family; 45. *Avaldi*, Annunciation; 62. Copy of *Parmeggianino's* Madonna del Collo Lungo in the Pitti Palace (p. 377); others by *Anselmi*, *Rondani*, etc. — III. Room or Rotunda. Paintings by modern artists, and two colossal statues of Hercules and Bacchus in basalt, found in the imperial palaces at Rome. — LARGE SALOON. Over the entrance, on the right and left, Nos. 118 and 149, and at the opposite end Nos. 209-212. Copies of *Correggio's* Coronation of Mary (in S. Giovanni, p. 257), by *Annibale* and *Agostino Caracci*. By the entrance, on the left, below: 115. *Spagnoletto*, Twelve Apostles; then, on the right, farther on, \*123. *Fr. Francia*, Descent from the Cross, and 130. Enthroned Madonna, 1515; 154. *Lod. Caracci*, Entombment of Mary; 158. *Fra Paolo da Pistoja*, Adoration of the Magi; \*180. *Giov. Bellini*, Christ as a boy with the Scriptures; 128. *Titian*, Christ bearing the Cross. Statue of Marie Louise in a sitting posture, in marble, by *Canova*. On the left, 213. *Tintoretto*, Ascension; \*216. *Tiepolo*, Heresy conquered by Religion; 217. *Giovanni da S. Giovanni*, A merry party. The door to the left at the upper end of the room leads to the studio of *Toschi*, the engraver (d. 1854), which contains admirable engravings from

Correggio, Raphael, etc. — A small door at the beginning of the Large Saloon, to the left, leads to the rooms containing the best pictures in the collection: — XI. Room. Landscapes. — X. Room. Portraits (*Seb. del Piombo*, Pope Clement VII.; *Holbein*, Portrait). — IX. Room. \*350. *Correggio*, Madonna della Scodella. — VIII. Room. 636-632. *Toschi*, Drawings from Correggio. Bust in plaster of the famous engraver. — VII. Room. \*351. *Correggio*, Madonna di S. Girolamo. — The adjoining corridor contains \*WATER COLOUR COPIES from Correggio by *Toschi* and his pupils. — VI. Room. 355. *Holbein*, Portrait of Erasmus of Rotterdam; \*353. *Correggio*, Martyrdom of Placidus and Flavia; \*360. \*361. *Cima da Conegliano*, Madonnas; 362. *Leonardo da Vinci*, Head; \*352. *Correggio*, Descent from the Cross. — V. Room. 378. *Van der Helst*, Portrait; \*371. *Giulio Romano* (after a sketch by Raphael, in the Louvre), Christ in glory, with the Madonna, SS. John, Paul, and Catharine; 369. *Garofalo*, Madonna among clouds; 364. *Murillo*, Job. — The IV. and III. Rooms contain works of the 14th and 15th centuries.

The door opposite the picture-gallery in the same story leads to the **Library** (Pl. 23), containing 80,000 vols. and 4000 MSS.; several of the latter are of Oriental origin, amongst them the Koran which the Emp. Leopold I. found in 1683 in the tent of the grand vizier Cara Mustapha after the raising of the siege of Vienna; the 'livre d'heures' (prayer-book) of Henry II.; a Dante written by Petrarch in 1370; a letter of Luther; Byzantine and Jewish miniatures; the original fresco of *Correggio's* Coronation of Mary from S. Giovanni (p. 257); a room with frescoes from the 'Divine Comedy' by *Franc. Scaramuzza*, now the director of the academy, completed in 1857.

The dilapidated **Teatro Farnese**, also situated here (keys kept by the custodian of the picture-gallery, fee 30 c.), was erected in 1618-28 by Duke Ranuccio Farnese. — The (formerly) ducal *Tipografia* (Pl. 28), founded by *Bodoni* in 1766, is celebrated for its admirable printing.

The custodians of the picture-gallery also keep the keys (fee 50 c.) of the —

\***Convento di S. Paolo** (Pl. 13; F. 2), formerly a Benedictine nunnery, now a school, an insignificant building, containing charming \*Frescoes by *Correggio* in the *Camera di S. Paolo*, which was thus decorated by order of the abbess Giovanna da Piacenza in 1519 (the best preserved works of the master): over the chimney-piece Diana, on the ceiling Cupids and emblems of the chase (the celebrated 'Putti del Correggio'), on the frieze the Graces, Fortuna, Adonis, etc. The most favourable light is in sunny weather, 10-12 a. m. The adjacent room is adorned with paintings by *Al. Araldi* (d. 1528). — The monastery church (*Cappella Reale, S. Lodovico*) contains the monument of Count Neipperg (d. 1829), the husband of the empress Marie Louise of France, and afterwards Duchess of Parma, by *Bartolini* of Florence.

To the S. of the Piazza Grande rises the **University** (Pl. 29; E, 4), possessing faculties of jurisprudence, medicine, and mathematics and natural science. The students number about 400. The palæontological department of the natural history museum is worthy of inspection. Director, Professor P. Strobel.

Quitting the museum and crossing the small river *Parma* by the *Ponte Verde*, we soon reach the (formerly) *Ducal Garden* (closed at 7 p. m.), at the N. end of which is the **Palazzo del Giardino** (Pl. 19; C, 1. 2). erected by Ottavio Farnese, and adorned with

numerous frescoes. One of the apartments contains the Rape of Europa, the Triumph of Venus, the Marriage of Peleus and Thetis, etc., by *Agostino Caracci*. (The palace is now a military school and inaccessible.)

The garden adjoins the *Stradone*, a promenade encircling the town, and laid out on the site of the former fortifications.

## 40. Modena.

**Hotels.** ALBERGO REALE (Pl. a), in the Corso Via Emilia; ALBERGO S. MARCO (Pl. b), Via Posta Vecchia, commercial; ITALIA, near the Piazza Reale; MONDATORA (Pl. c); LEOPARDO (Pl. d).

*Caffè Nazionale*, Corso Via Emilia, opposite the Dogana (Pl. 25). — *Beer* at the *Birreria Testi*, on the W. ramparts, between the Porta S. Agostino and Balvardo di S. Francesco.

*Cab* with one horse 70, with two 90 c. per drive, at night 1 fr. or 1 fr. 20 c.; per hour 1 fr. 10 or 1 fr. 70 c., at night 1 fr. 40 c. or 2 fr.; each additional half-hour 50 or 80 c.

*Modèna*, a town with 30,800 inhab., situated in a fertile plain between the *Secchia* and the *Panaro*, formerly the capital of the duchy of that name, and now that of the province of Emilia, possesses broad streets, spacious arcades, a university, and an academy of art.

Modena, the ancient *Matina*, in the dominions of the Gallic Boii, became a Roman colony in B.C. 183, and, being situated on the high road from Rome to Mediolanum (Milan), was a place of some importance. After the murder of Cæsar, Brutus was besieged here by Antony for four months, Dec. 44 to April 43 B.C. (*Bellum Mutinense*); but the latter was defeated by Octavian with the consuls Pansa and Iirius, and compelled to raise the siege. — In the middle ages Modena belonged to the estates of the Countess Matilda, but eventually obtained its independence and became the scene of violent conflicts between the Guelphs and Ghibellines. In 1288 *Obizzo d'Este* gained possession of the supreme power, which his descendants continued to enjoy (see p. 266). — On the death of Alphonso II., without issue (1597), the states of Modena and Reggio (but not that of Ferrara) fell to his kinsman *Cesare d'Este* (1598), husband of Virginia de' Medici, daughter of Grand-duke Cosmo I. of Florence. *Hercules III.* (d. 1803), who by the Peace of Luneville lost Modena in 1801, was the last of the family of Este. Through his daughter *Beatrice*, who married Archduke Ferdinand, the duchy came into the possession of the younger branch of the House of Austria in 1814. The insurrections of 1848 and 1851 were quelled with cruel severity. Francis V., the last duke, quitted his dominions in 1859 and went over to the Austrians.

A speciality of Modena with regard to art history, was the sculpturing of TERRACOTTAS, the aim of the artists being to represent dramatic groups rather in accordance with pictorial than plastic principles, and therefore calculated only for being exhibited in niches. This branch of art was first fully developed by the strongly realistic master *Guido Mazzoni*, some of whose works may be inspected in the crypt of the cathedral (see below), and in S. Giovanni Decollato (Pl. 7). The art was next practised in a more refined style by *Antonio Begarelli* (d. 1565), who rejected the aid of painting, and brought it to the utmost perfection of which it seems capable.

The \**Cathedral* (Pl. 1; D, 5), begun in the Romanesque style in 1099 by *Lanfranco*, consecrated in 1184, has a superstructure of later date. The façade is relieved by a large rose window and a simple colonnade (three arches resting on columns in the wall





### Chiese


- |                             |       |
|-----------------------------|-------|
| 1 Duomo                     | D.5   |
| 2 Campanile o Ghirlandina   | D.5   |
| 3 Agostino (ora S. Michele) | B.C.4 |
| 4 S. Bartolommeo            | D.6   |
| 5 S. Domenico               | E.3   |
| 6 S. Francesco              | C.6   |
| 7 S. Giovanni decollato     | D.4   |
| 8 Madonna del Popolo        | F.4   |
| 9 S. Paolo                  | D.6   |
| 10 S. Pietro                | E.7   |
| 11 S. Vincenzo              | E.5   |


### Edifizj ed Istituti pubblici

- |                                         |         |
|-----------------------------------------|---------|
| 12 Accademia delle Belle Arti           | E.3     |
| 13 Orto Botanico                        | G.3.4   |
| 14 Osservatorio Astronomico             | E.F.4   |
| 15 Palazzo Civile                       | E.3.4   |
| 16 Comunale                             | D.5     |
| 17 Arcivescovile                        | D.5     |
| 18 Seminario Vescovile                  | C.6     |
| 19 Università                           | E.5     |
| 20 Scuole Mediche all'Università        | C.3     |
| 21 Teatro Comunale e Società del Casino | F.5     |
| 22 Teatro Aliprandi                     | F.4     |
| 23 Archivio e Giudicature di Mandamento | D.4.5   |
| 24 Banca Nazionale                      | D.6     |
| 25 Dogana                               | E.5     |
| 26 Museo Lapidario                      | B.4     |
| 27 Ospedale civile                      | B.C.3.4 |
| 28 " milit.                             | B.4     |
| 29 Posta                                | E.6     |

### Alberghi

- |              |     |
|--------------|-----|
| a. Ricca     | E.5 |
| b. S. Marco  | D.4 |
| c. Mondatori | D.5 |
| d. Leopardo  | C.4 |







and enclosed by a larger arch), which is continued round the whole building. The portals are adorned with the often recurring marble lions. The rude sculptures of the façade, representing the Creation, and the history of the first men down to Noah, are by *Nicolaus* and *Guilelmus* (about 1099); on the S. side, to the right near the choir, is the history of St. Geminianus, a relief by *Agostino da Firenze*, 1442 (perhaps Agostino di Duccio).

The INTERIOR is low and heavy, but of handsome proportions. The nave and aisles are supported by alternate pillars and columns, over which runs a triforium, and the vaulting is pointed. In the 2nd chapel on the left, a late Gothic altar of terracotta; 3rd chapel, a Coronation of Mary with saints on a gold ground, by *Serafinus de Serafinis*, the oldest extant picture of the school of Modena (1385); 4th chapel, Madonna in clouds, St. Jerome, St. Sebastian, and John the Baptist, by *Dosso Dossi*. By the opposite pillar is the pulpit by *Tommaso di Campione*, 1322; very ancient font, to the right of the approach to the choir, adapted for the purpose from the capital of a column. Choir-stalls by *Cristoforo Lendenari*, 1465; in the choir, on the right, sculptures of the beginning of the 12th cent. by *Nicolaus* and *Guilelmus*, representing the Passion. Above these are early frescoes of St. Christophorus and the Annunciation. By the left entrance to the choir, and on the left side of the choir, are several monuments of the Rangoni family, the best being that (designed by *Giulio Romano*) of Claudio, Count of Castelvetro (d. 1537), husband of Lucrezia, daughter of the celebrated scholar Pico of Mirandola (p. 195); and that of Hercules III. of Este (d. 1803). The lofty crypt, with four lions at the entrance, and supported by thirty slender columns, most of them with Romanesque capitals, the fluted ones in front of the high-altar being antique, contains the tomb of St. Geminianus; the realistic group over the altar on the right, a Madonna and Christ, with a nun, St. Joseph, and a servant, is by *Mazzoni*.

The \*Campanile, or *La Ghirlandina* (Pl. 2), erected in 1224-1319, 335 ft. in height, is one of the finest in N. Italy. It leans slightly towards the back of the cathedral, which is itself slightly out of the perpendicular.

In the campanile is preserved an old *Secchia*, or pitcher, which the Modenese (*Geminiani*) captured from the Bolognese (*Petronii*) at the battle of Rapolino, 15th Nov., 1325. *Alessandro Tassoni* of Modena (1565-1635) has humorously described this incident in his comic epic poem 'La Secchia Rapita' (1616). A monument was erected to him in 1860 in the principal street, behind the cathedral.

**S. Pietro** (Pl. 10; E, 7), at the S. end of the town, is a spacious church with double aisles, a good façade of brick, and cross vaulting, partly in the pointed, and partly in the circular style.

INTERIOR. 2nd Altar on the right, Pieta by *Herri met de Bles*; 3rd altar, Assumption by *Dosso Dossi*; in the chapel to the right of the choir, Mourning for the dead Christ, in terracotta, by *Antonio Begarelli* of Modena (p. 260). Six statues in the nave by the same master. The Madonna and Child in clouds, with four saints below, a group in the S. transept, was begun by Begarelli and completed by his nephew Lodovico. 2nd Altar on the left, Madonna in clouds with two saints by *Giambattista Dossi*.

**S. Francesco** (Pl. 6; C, 6) contains a \*Descent from the Cross (in the chapel to the left of the choir) by *Begarelli*, an imposing composition in terracotta, with thirteen life-size figures.

**S. Agostino**, now *S. Michèle* (Pl. 3; B. C, 4) is uninteresting. The old choir of S. Agostino only is now used as a church. The

body of the church (keys at the Ragioneria of the Ospedale Civico opposite) contains the tombs of the celebrated savants *Carolus Sigonius* (1524-85) and *Lod. Ant. Muratori* (1672-1750) of Modena, the latter chiefly eminent as an historian of Italy, and a Pietà by *Begarelli*.

The *Museo Lupidario* (Pl. 26), in the court to the left of S. Agostino, contains Roman inscriptions and sarcophagi, and in the passage to the left two mediæval monuments of 1312 and 1309 respectively.

The Piazza Muratori in the main street is adorned with a marble statue to the celebrated historian with the inscription: *a Lodovico Antonio Muratori la Patria, 1853.*

The \***Palazzo Reale**, formerly *Ducalè* (Pl. 15; E, 3, 4), at the end of the Corso Vittorio Emanuele, a magnificent edifice with a handsome court, begun under Francis I. in 1634 by the Roman *Bartolommeo Avanzini*, contains a *Picture Gallery* (open daily 10-3, fee 1 fr.; Sundays gratis; entrance at the back of the palace, second floor; catalogue 3 fr.).

II. ROOM: 24. *Simone Avanzi*, Madonna and angels (1370); without a number, *Barnaba da Modena*, Madonna (14th cent.); 30 *Baldovinetti* (?), Adoration of the Child; 33. *Gherardo da Haerlem* (or rather by an early master of the school of Bologna), Crucifixion; 39. *Giac. Francia*, Assumption of the Virgin; 49. *Bonosio Bartolommeo*, Pietà (1483); \*36. *Bianchi Ferreri* (Correggio's teacher), Annunciation; 51. *Bernardino Losco*, Madonna and two saints (1515); 58. *Marco Meloni*, Madonna and two saints (1504). — III. ROOM: \*60. *Correggio*, Ganymede carried off by the eagle (ceiling-painting); 66. *Correggio*, Angels. Then a number of frescoes, comprising nine scenes from the Æneid (transferred to canvas), by *Niccolò dell'Abbate* of Modena (1512-71); by the same master, the octagonal piece No. 107, with singers and musicians. — IV. ROOM: 108-112. Ceiling-paintings by *Tintoretto* from Ovid's *Metamorphoses*; 115-118, by the same master; 117. *Titian*, Portrait of a lady; 140. *Palma Giovane*, Allegory; \*141. *Bonifazio*, Adoration of the Magi; \*143. *Cima da Conegliano*, Descent from the Cross. — V. ROOM: \*149. *Guido Reni*, Christ on the Cross; 163. *Guercino*, St. Peter reading; in the centre the statue of a wounded warrior by *Obbigi*. This room and the 8th contain a number of drawings. — VI. ROOM: 189, 190. *Garofalo*, Madonna and saints; 176. *Dosso Dossi*, Adoration of the Child; 178, 191, 193, by the same master. In the centre a marble statue of Psyche by *Capelli*. — VII. ROOM: 201. *Lodovico Caracci*, Flora; 204. *Annibale Caracci*, Venus; 212. *Caravaggio*, Soldier drinking. — VIII. ROOM: unimportant, and most of the names questionable (among the drawings are the \*Judgment of Paris and the Flight of Helen). — IX. ROOM: 297. Madonna, after *Andrea del Sarto*. — To the left is the (X.) SALA GRANDE: Statue of Francis I. by *Bernini*; two landscapes, without numbers, by *Salvator Rosa*; 341. *Guercino*, Crucifixion of St. Peter; 325, 346. *Tintoretto*, Mythological pictures; 348. *Lionello Spada*, Gipsy woman. — XI. ROOM: 404. *Gasparo Pagano*, Nuptials of St. Catherine. — XII. ROOM: *Nugari*. Copy of Correggio's *La Notte*: *Ezzelin's fall*, by *Mulatesta*, the director of the gallery. — Room to the right (generally closed): \*423. *Palma Vecchio*, Portrait of a lady; \*488. *Pinturicchio*, Madonna and Child; 478. *Holbein* (?), Henry VIII. of England; 490. *Murillo*, Portrait of a Benedictine; 458. *Memling*, St. Christopher, an old copy of the original at Munich; *Bern. Luini*, Infant John; *Giulio Romano*, Study of a head, both without numbers. — Another room contains mediæval curiosities and other objects, among them a fine cabinet attributed to *Benvenuto Cellini*.

On the first floor of the palace is the **Library** (*Biblioteca Estense*), with 90,000 vols. and 3000 MSS. (closed 1st Aug. to 1st Oct.), transferred by Duke Cesare d'Este from Ferrara to Modena in 1598, when Pope Clement VIII. claimed the Duchy of Ferrara as a vacant fief (p. 266). The eminent scholars *Zaccaria*, *Tiraboschi*, *Muratori* (p. 262), and the archæologist *Cavedoni* (d. 1865) were once librarians here. Some of the MSS. are very valuable, e. g. a collection of Provençal poems by Ferrari (1254), Dante with miniatures of the 14th cent., prayer-book of Elcctor Albert of Mayence (d. 1545), with miniatures. The same building also contains the *Cabinet of Coins* and the *Archives*.

The well-kept *Gardens* of the palace, now the *Giardino Pubblico* (Pl. F, 3; closed in rainy weather), as well as the ramparts of the town, afford pleasant walks.

From Modena to Mantua, see R. 33.

*Vignola*, 12½ M. S.E. of Modena, on the *Pavaro*, is situated on an eminence and commands the landscape far and wide. The celebrated *Muratori* (p. 262) and the architect *Giacomo Barozzi da Vignola* were born here.

About the year 1770 Duke Francis III. of Modena constructed a bold and interesting, but now neglected road from Modena to PISTOJA, a distance of 46 M., leading by *Formigine*, *Serra*, *Faullo*, *Pieve a Pelago*, and *Fiumalbo*, at the base of the lofty *Monte Cimone*, where charming views of the Apennines are obtained. A diligence runs daily to Pieve a Pelago. Continuation of the road (to Boscolungo, S. Marcello, etc.), see p. 295. — To the W. of this road, about 10½ M. S.W. of Modena, is situated *Sassuolo*, a small town on the *Secchia*, with a ducal Villa and beautiful park. The *Zibio*, a neighbouring volcanic mountain, is remarkable for its naphtha springs.

## 41. From Padua to Bologna.

77 M. RAILWAY in 3-4 hrs.; fares 14 fr. 85, 10 fr. 70, 7 fr. 60 c.

The line skirts and crosses the navigable *Canale di Battaglia*. — 6 M. *Abano*, a small town, the birthplace of the historian Livy, lies at some distance to the right of the line. In the vicinity are the *Bagni* ('Baths', a well-appointed establishment), the *Aquæ Patavinæ*, or *Fons Aponi*, of the Romans, on the E. slope of the *Monti Euganei*, with warm springs and mud-baths.

The *Monti Euganei*, an isolated volcanic chain of hills rising on the right, 12 M. in length, from N. to S., 6 M. in breadth, from E. to W., contain extensive quarries of trachyte, and afford interesting excursions from Padua. Their culminating point is the *Monte Venda* (1890 ft.), with ruins of a monastery.

8 M. *Montegrotto*. To the left, beyond a long tunnel, near *Battaglia*, is seen the old and well-preserved chateau of *Cattùjo*, the property of the Duke of Modena, adorned with numerous frescoes by *Celotti*. It was erected by the now extinct Venetian family of the *Obizzi*, who, according to an inscription on a family-portrait, claim to have invented the howitzer. The chateau contains valuable collections.

ANTIQUES. Ground-floor. Ante-chamber: inscriptions, large triliteral Roman monument; farther on, a room with inscriptions and architectural fragments. First floor. 1st Room: casts. 2nd R.: early Christian sculptures. Hall: twenty Etruscan cinerary urns with scenes of leave-taking and battles; 9, 17, 19. Death of Neoptolemos at Delphi; 18. Cadmus slaying the dragon; 7. Rape of Helen; to the left, farther on, 35. Torso of a Cupid; 40. Cippus of a tomb; 43. Torso of a satyr. Brazen cinerary urns from the Euganean Mts.; 102. Greek (?) tomb-relief; 100, 115.

Terracottas, Artemis, Selene, and Endymion; 111. Scene from the conquest of Troy, in relief; \*288. Basrelief, Victory (?), the laurel-wreath modern. Terracottas from Etruscan tombs: 479. Mithras; 529. Woman in relief (the swan modern); 5, 9. Minerva; \*545. Statue of Sabina, wife of Hadrian, in a sitting posture; 561. Antinous; 608. Isis, in imitation of the Egyptian style; 656. Cinerary urn in terracotta, formerly painted, with Troilus and Achilles; 1065. Statue of a youth; 1155. Augustus as an augur (the staff modern); 1179. Bearded Dionysus. In the centre, 1196. Statue of a magistrate; 1206. Torso of Hercules. — A room to the right contains a large collection of mediæval relics, weapons, guns, and artillery models. The Oratorio S. Michele, or chapel of the château, contains good early Italian pictures.

11 M. **Battaglia** (*Albergo della Luna*, no fixed charges) possesses warm baths of considerable repute. The principal spring (S. Helena) adjoins the château of Count Wimpffen, the proprietor of the watering-place. — About 3 M. to the S. W. of Battaglia, on the Monti Euganei, is situated *Arquà del Monte*, a small town prettily situated in a valley, and a favourite retreat of *Petrarch*, who lived and died here (1304-74). His monument in front of the church consists of a sarcophagus resting on short columns of red marble, bearing the inscription:

Frigida Francisci lapis hic tegit ossa Petrarce,  
Suscipe virgo parens animam! Satc virgine, parce!  
Fessaque nam terris celi requiescat in arce.

On the top is a bust of *Petrarch*, dating from 1547. His house in the upper part of the town, with painted wooden ceilings and faded frescoes in allusion to his poems, contains a few reminiscences of its former illustrious owner.

14½ M. *Monselice*, a town at the base of the Monti Euganei, has remains of fortified walls and a ruined castle. To Arquà and Este a drive of 3 hrs.


18 M. *Stat. Este*. The town, the *Ateste* of Tacitus according to ancient inscriptions, lies 3¾ M. to the N., on the road which here diverges to Mantua. It possesses the extensive, but now ruinous ancestral residence of the House of Este (p. 266), a spacious piazza surrounded with arcades, a *Museo Civico* in the church of S. Francesco (containing several interesting Roman inscriptions), a cathedral of elliptical plan with a lofty choir, and a church of S. Martino with a leaning tower.

Near (19½ M.) *Stanghella* the line crosses the *Gorzone Canal*. The country is fertile, but flat and marshy. Near *Boara* a small new fort is passed and the *Adige* crossed.

27½ M. **Rovigo** (*Cappa d'Oro*; *Corona Ferrea*), on the *Naviglio Adigetto*, an episcopal residence and the capital of a province, belonged to Venice from 1484 downwards. The PALAZZO COMUNALE, near the Piazza Vittorio Emanuele, contains a good picture gallery (including a portrait by *Giorgione*, a Madonna by *Palma Vecchio*, a portrait of King Ferdinand of 1525, by *Holbein*, and works by *Giov. Bellini*, *Paolo Veronese*, *Dosso Dossi*, and *Guido Reni*), and a library of upwards of 70,000 vols. — The two leaning towers belong to a *Castle* erected in the 10th cent. The handsome *Assize Buildings* were erected in 1873.







A B C D E

# Ferrara

1

3

4

5

6


7

8


Piazza  
d'Armi

- Piazza**
- a. del Commercio D4.5
  - b. della Pace D4.
  - c. Municipale D.5.
  - d. dei Pollajoli D4.
  - e. Rocca Guinale CD4.5.
  - f. dell'Oca. C4.
  - g. di S. Giovanni F.3.

1:20000



A B C D E



## Chiese

|                                           |        |
|-------------------------------------------|--------|
| 1. Cattedrale                             | D.5.   |
| 2. S. Andrea                              | F.7.   |
| 3. S. Benedetto                           | C.2.3. |
| 4. Corpus Domini                          | E.6.   |
| 5. S. Cristoforo ( Certosa, Campo Santo ) | E.2.   |
| 6. S. Domenico                            | CD.4.  |
| 7. S. Francesco                           | E.5.   |
| 8. del Gesù                               | DE.4.  |
| 9. S. Giovanni Battista                   | F.3.   |
| 10. S. Girolamo                           | F.6.   |
| 11. S. Maria in vado                      | F.6.   |
| 12. S. Maurelio ( Cappuccini )            | D.2.   |
| 13. S. Paolo                              | D.5.   |
| 14. S. Spirito                            | F.4.   |
| <hr/>                                     |        |
| 15. Accademia Ariostea                    | D.4.   |
| 16. Arcivescovado                         | D.4.5. |
| 17. Castello degli antichi Duchi          | D.4.   |
| 18. Giardino Botanico                     | DE.6.  |
| 19. Palazzo del Municipio                 | D.4.5. |
| 20. " della Ragione                       | D.5.   |
| 21. Seminario                             | D.4.5. |
| 22. Studio Pubblico                       | E.5.6. |
| 23. Teatro Bonaccossi                     | D.5.   |
| 24. " Comunale                            | D.4.   |
| 25. Casa dell'Ariosto                     | CD.2.  |
| 26. Ghetto                                | E.5.   |
| 27. Posta delle Lettere                   | E.4.   |
| 28. " dei Cavalieri                       | D.4.   |
| 29. Ospedale St. Anna                     | E.4.   |
| 30. Ateneo civico                         | D.3.   |
| 31. Monumento Savonarola                  | D.4.   |
| 32. Palazzo Bevilacqua                    | E.3.   |
| 33. " Costabili                           | F.7.   |
| 34. " de' Leoni                           | DE.3.  |
| 35. " Schifunja                           | F.6.   |
| 36. " Zatti                               | F.3.   |



**Adria**, 11 M. from Rivigo, and connected with it by a branch-line, is situated on the *Bianco Canal*, and occupies the site of the very ancient Etruscan town of the same name, whence the Adriatic derives its appellation. The sea has gradually receded from it, and is now 17 M. distant.

32 $\frac{1}{2}$  M. *Arquà*. The line crosses the *Bianco Canal* near the *Bosaro*, and, near —

58 M. *Polesella*, reaches the *Po*, which is here the boundary between Venetia and the Romagna. The left bank of the *Po* is now followed. Stat. *Paviole*; then *S. Maria Maddalena*. The river is then crossed, and the train reaches station *Pontelagoscuro*.

41 $\frac{1}{2}$  M. *Ferrara*, see below.

From Ferrara to Bologna, 29 $\frac{1}{2}$  M., in 1-1 $\frac{1}{2}$  hr. The train crosses the *Cavo Tassone Canal*, which communicates with the *Po di Primaro* immediately to the S. of Ferrara, and traverses flat, well cultivated land (rice-fields). Stations *Poggio Renatico*. *Galliciera*. *S. Pietro in Casale*, and *S. Giorgio*.

From S. Giorgio an excursion may be made to (9 M.) **Cento**, a small town on the *Reno*, the birthplace of the great painter *Giovanni Francesco Barbieri*, surnamed *Guercino da Cento* (1590; d. at Bologna 1666). Several of the churches, particularly those of *S. Biagio* and the *Madonna del Rosario*, contain admirable works by *Guercino*, who was greatly attached to his native town. His house, where he received many illustrious visitors, is still shown. In the centre of the town is his statue by *Galletti*. — Near Cento is situated *Pieve di Cento*, a small town with the pilgrimage-church of *S. Maria Assunta*; the high altar-piece is an *Assumption* by *Guido*.

Next stations *Castel Maggiore* and *Corticella*. The fertility of the soil increases as Bologna is approached.

77 M. *Bologna*, see p. 270.

## 42. Ferrara.

**Hotels.** EUROPA, opposite the post-office; STELLA D'ORO, opposite the castle; at both, R. 2, L. and A. 1 fr.; ALBERGO DELLA COLOMBA, unpretending.

*Cafés* in the Piazza del Commercio, opposite the castle.

*Ferrara* is situated near the ancient *Forum Alieni*, 31 $\frac{1}{2}$  M. S. of the *Po*, in the midst of a fertile, but unhealthy plain. It is the capital of a Delegation, with 28,500 inhab., and possesses broad, deserted streets, mouldering palaces, and other imposing reminiscences of its golden period. It was once a prosperous commercial place, numbering 100,000 inhab., and was the seat of the renowned court of the House of Este.

The family of Este was of Tuscan extraction. *Azzo I.* became Count or MARGRAVE OF ESTE under Emp. Henry III. His eldest son *Welf* (founder of the younger branch of the *Guelphs*) was invested with the Duchy of Bavaria, which had belonged to his grandfather, the last male representative of the elder branch of the *Guelphs*, and his son *Henry the Proud* became the founder of the families of Brunswick and Hanover. *Giulio*, the second son of *Welf*, was the ancestor of the dukes of Ferrara and Modena. *Obizzo III.*, who added Modena and Reggio to his dominions (d. 1352), considerably extended the power of his house, which from an early period was a liberal patron of art and science. In 1452 *Bors-*

received the title of DUKE OF MODENA AND REGGIO from Emp. Frederick III., and that of DUKE OF FERRARA from Pope Paul II. He died in 1471. His brother *Hercules I.* (1471-1505), and the son of the latter, *Alphonso I.* (1505-34), husband of the infamous Lucrezia Borgia, were powerful and influential princes. Cardinal *Hippolytus d'Este*, Archbishop of Milan, brother of Alphonso, was the friend and patron of *Ariosto*. *Hercules II.* (1534-58), son of Alphonso, was the husband of *Renata*, daughter of Louis XII. of France, patroness of the Reformers Calvin and Marot, to whom she accorded an asylum. Having declared herself in favour of the reformed doctrines, she was separated from her husband and children. Her son *Alphonso II.* (1558-97) raised the glory of Ferrara to its culminating point, but with him the family became extinct, his three marriages being childless. He was the patron of the poets *Tasso* and *Guarini* (author of the 'Pastor Fido', born at Ferrara in 1537, died at Venice in 1612). Goethe in his 'Torquato Tasso' has drawn a faithful picture of the court of Ferrara about the year 1575, although a somewhat ideal colouring is given to some of the characters. His description of the attachment of Tasso to *Eleonora* (1537-81), the youngest unmarried sister of the duke, is however not without foundation. *Anna* (1531-1607), one of the sisters, was married to the Duc de Guise, and afterwards to the Duc de Nemours; *Lucrezia* (1534-98), the other sister, was the wife of the Duke of Urbino. Alphonso II. was succeeded by *Cesare d'Este*, descendant of a natural son of Alphonso I., but only as duke of Modena and Reggio, Ferrara and Comacchio having been claimed by Pope Clement VIII. as vacant fiefs. In the history of art and science the renown of the House of Este is immortal.

'Who'er in Italy is known to fame

This lordly House as frequent guest can claim.'

The art of **Painting** was liberally patronised at Ferrara, as at all the other Italian courts, but the Ferrarese painters did not succeed in maintaining full independence. In the 15th cent. they were chiefly influenced by the Paduan school, as in the case of *Cosimo Tura* (1430-1496), whose chief works are the frescoes in the Palazzo Schifanoja (p. 268; painted perhaps with the aid of *Piero della Francesca*). *Lorenzo Costa* (1460-1535), another Ferrarese master, became an adherent of Francia during his residence at Bologna. In the 16th cent. the influence of Raphael and the Venetian painters predominated, the former being apparent in the (works of the skilful *Benvenuto Tiso*, surnamed *Garofalo* (1481-1559) and *Dosso Dossi* (d. 1542), who sometimes displays a taste for fantastic themes, while the colouring of the talented *Lodovico Mazzolino* recalls the Venetian school. The princes of Este, it is well known, were eager collectors of the works of Raphael and Leonardo. *Titian* also occasionally resided at Ferrara, where he painted his 'Cristo della Moneta', now at Dresden.

The \***Castello** (Pl. 17; D, 4), an ancient and picturesque edifice with four towers, situated in the centre of the town, is now occupied by the local authorities and the telegraph-office. The custodian shows several dungeons, and among them one at the base of the 'lion tower', where on 21st May, 1425, the Marquis *Nicholas III.* caused his faithless wife *Parisina Malatesta* and his natural son Hugo, her paramour, to be beheaded. Lord Byron in his poem of 'Parisina' substitutes the name of Azzo for Nicholas as being more metrical. — The *Sala del Consiglio*, and the adjacent *Sala di Napoli* in the building of the prefecture, contains frescoes by *Dosso Dossi*, representing wrestling-matches of the ancient palestra. The *Sala dell' Aurora*, with frescoes by the same master, contains a fine \*frieze with children (said to be Eleonora's room).

Between the castle and the cathedral rises a monument by Galetti to *Girolamo Savonarola* (Pl. 31), who was born at Ferrara

on 21st Feb. 1452 ('in tempi corrotti e servili dei vizi e dei tiranni flagellatore'; p. 329). It was unveiled in 1875, on the occasion of the Ariosto festival. — On the right, farther on, is the *Palazzo del Municipio* (Pl. 19), the oldest residence of the Este family, much altered during the last century.

The \***Cathedral** (*S. Giorgio*; Pl. 1; D, 5) has an imposing façade with three series of round arches, one above the other, an admirable example of the Lombard style. The lower part of the front and the lateral façades date from 1135; the upper part is of the 13th cent., the sculptures of the 13th and 14th. The projecting portal, enriched with sculptures and four lions, was added at a later period; the reliefs, however, are of an earlier date.

The INTERIOR, with its aisles and double transept, has been entirely, but not unpleasingly modernised. In the 2nd TRANSEPT on the right: St. Peter and St. Paul by *Garofalo*, Martyrdom of St. Lawrence by *Guercino*. Crucifix and four figures in bronze by *Niccolò Baronzelli*; terracotta figures of Christ and the apostles in both transepts by *Alfonso Lombardi*. — In the CHOR, to the right, Annunciation, to the left St. George, by *Tura*; above, Last Judgment, by *Bastianino*. 3rd Chapel on the left, Madonna enthroned with saints, by *Garofalo*. On the right and left of the principal door, SS. Peter and Paul, in fresco, by the same master (repainted).

At the S. corner of the cathedral rises a lofty and handsome *Campanile* in four massive stories, erected in the Renaissance style under Ercole II. Opposite to it is the *Pal. della Ragione*, a Gothic brick building with restored façade, erected in 1315-26, restored in 1840, and still containing the courts of justice.

*S. Paolo* (Pl. 13) contains pictures by *Bonone* and *Scarsellino*, and the tomb of *Ant. Montecatino*, the friend and minister of Alphonso II.

The **Studio Pubblico**, or *University* (Pl. 22; E, 5, 6), a school of medicine, mathematics, and jurisprudence, contains a valuable collection of coins, and Greek and Latin inscriptions (in the court several early Christian sarcophagi, and one of Roman origin), and a *Library* of 100,000 vols. and 1100 MSS.

Among the latter are several cantos of the 'Orlando Furioso' in *Ariosto's* handwriting, with numerous corrections, and a copy of *Tasso's* 'Gerusalemme Liberata', also with corrections; letters and poems written by *Tasso* in prison; *Guarini's* MS. of the 'Pastor Fido': a number of choir-books of the 13th-16th cent. with beautiful miniatures. Among the printed books are fifty-two old editions of *Ariosto*. His monument was brought here from *S. Benedetto* (p. 269) in 1801.

**S. Francesco** (Pl. 7; E, 5), erected in 1498 by *Pietro Benvenuti*, is entirely covered with domes, and each aisle is flanked with chapels. 1st Chapel on the left, frescoes by *Garofalo*, the Donors and the Kiss of Judas. The other pictures are copies, of which the originals are preserved in the Pinacoteca. The church contains monuments of the family of Este and that of *Giambattista Pigna*, the secretary of Alphonso II. and rival of *Tasso* (a simple slab, outside, to the right of the entrance). A famous echo here (under the second dome in the nave) answers sixteen times if awakened with due energy.

*S. Maria in Vado* (Pl. 11; F, 6), one of the oldest churches at Ferrara, but altered after 1475 by *Biagio Rossetti* and *Bartolommeo Tristani*, consists of a nave divided into three parts, with a flat ceiling resting on ten columns, and surmounted by a dome supported by buttresses. It contains frescoes by *Bononi*.

At the back of the church, No. 23, *Strada della Scandiana*, is the **Palazzo Schifanoja** (Pl. 35; F, 6), once a chateau of the Este, and now containing a deaf and dumb institution. It was begun by *Alberto d'Este* in 1391, and completed by *Borso* in 1469. Over the handsome portal is the unicorn from *Borso's* armorial bearings. The principal saloon contains \*Frescoes by *Cosimo Tura*, *Lorenzo Costa* (?), and others, discovered in 1840 under the whitewash, representing the twelve months of the year, the signs of the zodiac, and scenes from the life of *Borso*.

To the S. of *S. Maria in Vado*, in the *Corso Porta Romana*, is the *Palazzo Costabili* (Pl. 33; F, 7), sometimes called *Palazzo Scrofa*, after its former proprietors, or *Palazzo Beltrame* from the family to which it now belongs. It was erected in 1502, but is uncompleted. Handsome court.

The N. QUARTER of the town, or 'Addizione Erculea', erected by *Hercules I.* in the 14th cent., is traversed by two main streets, the *Corso Vittorio Emanuele* and the *Corso di Porta Po* and *di Porta Mare*. At their intersection (Pl. D, E, 3) are situated four handsome palaces, the finest of which are the *Palazzo Prosperi*, or *de' Leoni* (Pl. 34), with admirable ornamentation, and the —

\***Palazzo de' Diamanti** (Pl. 30; D, 3), so called from the peculiar facets of the stones with which the building is covered, a handsome early Renaissance structure, erected for *Sigismondo d'Este* by *Biagio Rossetti*, and completed in 1567. It contains the *Ateneo Civico* and the *Civic Picture Gallery*, most of the works in which have been collected from suppressed churches. (Open daily 10-3; ring on the left at the entrance; fees prohibited.) *Garofalo* and *Dosso Dossi* are particularly well represented. Good catalogue, 50 c.

I. ROOM. \*95. *Rocco Marconi* (not *Palma Vecchio*), The Tribute-money; by the window, \**Garofalo*, Crucifixion and Resurrection; 97. *Panelli*, (master of *Garofalo*), St. Paul, a fresco: 120. *Tintoretto*, Madonna del Rosario. — II. ROOM. *Panelli*. 99. St. Andrew; 98. Annunciation; 100. St. Augustine; \*101, 102. Annunciation; 28. *Lor. Costa*, Madonna enthroned, with SS. Petronius and Jerome. — III. ROOM (1.): 27. *Franc. Costa*, Condemnation, and 26. Beheading of St. Maurelius; \*122. *Cosimo Tura*, St. Jerome; 123. *Tura*, Pieta in a landscape; \*60. *Garofalo*, Mass of St. Nicholas of Tolentino; 94. *Perugino*, Drawing; \*121. *Tura*, St. Jerome. — The IV. ROOM, now undergoing restoration, is to be re-opened during the present year. — V. ROOM. *Ercole Grandi*, *Carpi*, *Falzagalloni*, and others. — VI. ROOM. 45. *Dosso Dossi*, St. John inspired for the Apocalypse; 63. *Garofalo*, Madonna del Pilastro; 93. *Ortolano* (a contemporary of *Garofalo*), Adoration of the Child; \*64. *Garofalo*, Adoration of the Magi, with a carnation painted in the foreground by way of signature, 1537; 103. *Panelli*, Salutation of Mary; 88. *Mazzolino*, Adoration of the Child; 65. *Garofalo*, Christ on the Mount of Olives. — VII. ROOM. 66. (over the door) *Garofalo*,

*falo*, Return of the Holy Family to Egypt; 67. *Garofalo*, Madonna among clouds, with saints and donors below. 1514; 37. *Vitt. Carpaccio*, Death of Mary; 68. *Garofalo*, Slaughter of the Innocents. — VIII. Room. 46. *Dosso Dossi*, Annunciation (an early work); 124. *Timoteo della Vite (?)*, Assumption of the Egyptian Mary. — IX. Room. 71. *Garofalo*, Madonna del Riposo; 72. *Garofalo*, Raising of Lazarus; 73. *Garofalo*, Finding of the Cross; 47. *Dosso Dossi*, Madonna with SS. Augustine and Sebastian on the left, and SS. Ambrose and George on the right, one of the master's finest works. — X. Room (to the right of the entrance): Modern pictures.

In the Corso di Porta Po, a little farther to the W., is the church of **S. Benedetto** (Pl. 3; C, 2, 3), erected in 1496-1553 by *Giambattista* and *Alberto Tristanti*, consisting of nave and aisles supported by pillars, and flanked with chapels. The circular vaulting is interrupted by domes. The monument of Ariosto was originally here (see below). The old monastery, now a barrack (keys at the Palazzo Comunale, not always easily obtained), is adorned with frescoes by *Scarsellino* and *Dosso Dossi*; that of the ante-chamber of the refectory represents Paradise, with saints and angels, among whom Ariosto caused himself to be painted.

The simple *House of Ariosto* (Pl. 25; C, D, 2), which he erected for himself and occupied during the latter part of his life, Via dell' Ariosto No. 67, has been the property of the town since 1811. It bears the inscription, composed by the poet himself:

'Parva, sed apta mihi, sed nulli obnoxia, sed non  
Sordida. parva meo sed tamen aere domus.'

A few reminiscences of Ariosto are shown in the interior.

While the poet was studying law, which however he soon exchanged for poetry, he resided in the *Casa degli Ariosti*, near the church of S. Maria di Bocche, but quitted it on his father's death.

A *Statue of Ariosto* by Franc. Vidoni, on a lofty column in the Piazza Ariosteana (Pl. E, F, 3), was placed there in 1833. In the 15th cent. the column was erected as a monument to Hercules I., and in 1810-14 bore a statue of Napoleon. On the S. side of the piazza is the *Palazzo Zatti* (Pl. 36), and on the W. side the *Palazzo Bevilacqua* (Pl. 32).

The church of **S. Cristoforo** (Pl. 5; E, F, 2) in the Campo Santo, which was formerly a Carthusian monastery, a handsome Renaissance building, was erected in 1498-1553. The cemetery contains several tasteful modern monuments.

The *Hospital of St. Anna* (entrance in the Strada della Giovecca, next door to the Europa; Pl. 29; E. 4) is interesting as the place where *Tasso* was kept in confinement for seven years (from 1579) by order of Alphonso II. He is supposed to have incurred the displeasure of his patron by his passion for the Princess Leonora, the sister of Alphonso, or to have suffered from periodical attacks of insanity. A dungeon is shown in which he is said to have been incarcerated, with the names of Byron and other poets written on the walls. — Adjoining the hospital is the *Casino dei Negozianti*, formerly *Palazzo Roverella*, erected in 1508, with a fine façade.

In the church of **S. Giorgio**, outside the Porta Romana (Pl. F, 8), Pope Eugene IV. opened the Council convened in 1438 with a view to effect a union of the Greek and Roman churches, in the presence of the Greek Emp. John Palæologus. This locality being considered unhealthy, the seat of the Council was afterwards transferred to Florence.



## 43. Bologna.

**Hotels.** \*HÔTEL BRUN and PENSION SUISSE (Pl. a), in the Palazzo Malvasia (good survey of the town from the loggia), Strada Ugobassi, formerly S. Felice. R. 3 fr. and upwards. B. 1 $\frac{3}{4}$ , A. 1, L. 3 $\frac{1}{4}$ , D. 1 $\frac{1}{2}$ , omnibus 1 fr.; S. MARCO (Pl. b), same charges; ALBERGO BOLOGNA (formerly Tre Mori); \*PELEGRINO (Pl. c), R. 2 $\frac{1}{2}$ , L. and A. 1, omnibus 1 $\frac{1}{2}$  fr. (all these hotels are in the Strada Ugobassi); HÔTEL D'ITALIE, Portico delle Gabelle Vecchie, well spoken of. — ALBERGO DE' TRE RE, and QUATTRO PELLEGRINI, both in the Mercato di Mezzo; COMMERCIO, Via di Petra Fitta. — AQUILA, in the Calca Vinazzi, a side street of the Strada Ugobassi; BELLA VENEZIA, Mercato di Mezzo; CANNON D'ORO, corner of Via Porta Nova and Via Gombruti, R. 1 $\frac{1}{4}$ -2 fr.

**Restaurants.** \**Ristoratore Felsineo*, Mercato di Mezzo 79, near the Piazza Vitt. Emanuele, on the 1st floor, D. 3-4 fr.; *Stelloni*, Mercato di Mezzo 81, 1st floor, new; \**Caffè del Corso*, Strada S. Stefano; also at most of the hotels. (The '*Mortadella*', or Bologna sausage, and the '*Cervellato*', which is eaten in winter, are much esteemed by the natives.)

**Cafés.** The most frequented are in the arcades near the Palazzo Pubblico, and in the streets to the S. of S. Petronio, most of them sombre and uninviting. *Paraglione*, in the Piazza to the back of S. Petronio, to the S.; *Majani* (confectioner); \**delle Scienze*, Via Miola; *del Commercio*, opposite Hôtel Brun; \**del Corso* (see above). — **Beer** at the following *Birrerie*, which are also restaurants: \**Hoffmeister*, opposite the choir of S. Petronio, in the Piazza della Pace, Via de' Libri; *Nevani* in the side arcade of the Piazza to the E. of S. Petronio; \**Milano*, Via Miola, adjacent to the Caffè delle Scienze; *Brewery* on the S.W. side of the Piazza d'Armi (to which an omnibus runs every evening from the Piazza Petronio), and others.

**Railway Station** outside the *Porta Galliera*, N.W. of the Montagnola (Pl. G, 1). Railway to Ferrara, see R. 41; to Ravenna, see R. 44; to Florence, see R. 45; to Piacenza, see R. 36; to Ancona, etc., see *Baedeker's Central Italy*.

**Post Office** in a wing of the Palazzo Pubblico (Pl. 45), opposite the Palazzo del Podestà. — **Telegraph Office** on the first floor of the Palazzo Pubblico.

**Cabs.** Per drive, within the town, 3 $\frac{1}{4}$  fr.; first half-hour 1 fr., whole hour and each following hour 1 $\frac{1}{2}$  fr.; to or from the station, with or without luggage, 1 fr.; two horses 50 c. more. To S. Michele in Bosco, for the first hour 21 z, each additional 1 $\frac{1}{2}$  hr. 3 $\frac{1}{4}$  fr.; with two horses 3 or 1 $\frac{1}{2}$  fr. After 10 p.m., or in winter after 9 p.m., 50 c. more in each case.

**Baths.** *Bagni al Torresotto*, Strada Castiglione; *alla Carità*, Strada Ugobassi.


**Theatres.** *Teatro del Comune* (Pl. 72), the largest, erected by Bibiena in 1756 on the site of the Palazzo Bentivoglio; *Contavalli* (Pl. 73), established in 1814 in the former church of the Carmelites; *del Corso* (Pl. 74); *Teatro Brunetti*, in a side-street of the Strada Castiglione; *Arena del Sole*, Via de' Malcontenti, near the Montagnola, open-air theatre. — The favourite *Giuoco di Pallone*, or ball-game, always attracts spectators; a large space (Pl. 76; G, 2) in the Promenade Montagnola (p. 283) is fitted up for the purpose, and should be visited (bills are posted up to announce the names of the parties to the matches about to be played).

**Shops.** The best are in the arcades near the Palazzo Pubblico. — **Booksellers.** *Zanichelli* (also photographs), under the arcades, to the E. of S. Petronio. *Serra*, Palazzo Tanari, Via Galliera (Pl. 67), dealer in old books, curiosities, and pictures.

The situation of Bologna is considered healthy, although the summer is often very hot and the winter keen. The town is sometimes called '*Bologna la grassa*', owing to its reputation for wealth and good-living. The neighbourhood produces tolerable wines and excellent fruit. The grapes are delicious; the yellow *Uva Paradisa* is a kind which may be kept a considerable time. — The once favourite lap-dogs of Bologna are







Stazione della Strada ferrata

# Bologna.

Pubblica

H I K

Monte S. Giacomo  
Giardini  
Pubblici

Strada di Porta Mascarella  
Circovallazione



Porta S. Donato

Piazza S. Stefano  
Piazza S. Maria  
Piazza S. Vitale

Porta S. Vitale

Porta Maggiore

Porta Castiglione

Porta S. Stefano

F

G

H

7

6

5

4

3

2

1



now almost extinct. Soap, macaroni, and liqueurs ('bebita') are among the most esteemed commodities of the place.

**Principal Attractions:** Piazza Vitt. Emanuele with the Pal. Pubblico and del Podestà, \*S. Petronio, \*S. Domenico, \*S. Stefano, S. Giacomo Maggiore, S. Cecilia, \*Accademia delle Belle Arti, the Leaning Towers, Loggia de' Mercanti, \*Campo Santo, and, if possible, the \*Madonna di S. Luca for the sake of the view. If time remains, the Archiginnasio, the University, the Palaces Baccicchi, Bevilacqua, Fava, and Zampieri, and the handsome Via Galliera may be visited.

*Bologna*, with 89,100 inhab. (with suburbs 115,900), one of the most ancient and important towns in Italy, the capital of the *Emilia*, is situated in a fertile plain at the base of the Apennines. between the *Reno*, the *Aposa*, and the *Savona*. It possesses 130 churches, 20 monasteries, and a venerable and celebrated university, whence the inscription on old coins '*Bononia docet*'. The narrow streets and lofty arcades, the numerous old palaces, and the venerable churches surmounted by quaint-looking towers, all bear testimony to the peculiar character of the place.

The town was founded by the Etruscans, and named *Felsina*, but was afterwards conquered by the Gallic Boii, and by them called *Bononia*. In the Punic War it espoused the cause of Hannibal, after which, B.C. 190, it was converted into a Roman colony, at the same time as Cremona and Placentia, by the consul C. Lælius, and as such was a place of very great importance. Under the Empire it was even occasionally the residence of the monarchs themselves. It afterwards belonged to the Greek Exarchate, and then to the Lombards and Franks. Charlemagne constituted Bologna a free town (whence its motto '*Libertas*'), and its commerce and prosperity rapidly increased. In 1119 the UNIVERSITY, one of the oldest in the world, was founded, and as a *School of Jurisprudence*, where *Imerius* and other celebrated jurists taught, soon attained a European reputation, and was visited by many thousand students annually. In 1282 the number is said to have attained to nearly 10,000; at the present day there are 400 only. Irnerius introduced the study of the Roman Law, while his successors the *Glossators* devoted their energies to its interpretation. The study of medicine and philosophy was introduced at a later period, and a theological faculty established by Pope Innocent VI. The anatomy of the human frame was first taught here in the 14th cent., and galvanism was discovered here by *Jos. Galvani* in 1789. It is a remarkable fact that the university of Bologna has numbered members of the fair sex among its professors. Thus, in the 14th cent., *Novella d'Andrea*, a lady of great personal attractions, who is said to have been concealed by a curtain during her lectures; at a subsequent period *Leura Bassi* (mathematics and physical science), *Mme. Manzolina* (anatomy), and more recently (1794-1817) *Clotilda Tambroni* (Greek).

Bologna acted a very prominent part in the contests of the Guelphs and Ghibellines, espoused the cause of the former, and allied itself with the Pope against Emp. Frederick II. In a sanguinary encounter at Fossalta, in May, 1249, King *Enzio*, son of the Emperor, was captured by the Bolognese, and kept in confinement by them for the rest of his life (22 years, p. 273). He was the founder of the family of the *Bentivogli*, afterwards so powerful, who after protracted feuds entered into an alliance with the papal throne. During several centuries the town was the scene of the party-struggles of the Bentivogli, Visconti, and other families, until in 1512 Pope *Julius II.* incorporated it with the States of the Church.

In 1515 the interview of Pope Leo X. with Francis I. of France took place at Bologna, and in 1529, 1530, and 1532 those of Clement VII. with Emp. Charles V. Here, too, the Council of Trent held a meeting in 1547. In 1796 Bologna was annexed to the 'Cisalpine Republic' by Napoleon; in 1815 it again became subject to the States of the Church; in 1831 and 1849

revolutions broke out, and in 1859 the town finally united itself to the kingdom of Italy.

In the **History of Art** Bologna did not attain to any distinction till a comparatively late period. In the Gothic era it at length became ambitious of possessing within its walls the largest church in Italy. To this ambition it was indebted for *S. Petronio*, which, had it been completed, would have surpassed in size all the other cathedrals in Italy. Unfortunately, however, it remained a torso, and gave rise to innumerable disputes. The **EARLY RENAISSANCE** style is abundantly represented here. The *Palatial Edifices*, constructed of brick, with their ground floors opening in arcades towards the street, impart a peculiar charm to the town. **SCULPTURE** was chiefly practised by foreign masters. Thus, as early as the 13th cent., pupils of *Niccolò Pisano* were engaged to embellish the tomb of *S. Domenico*; the reliefs on the principal portal of *S. Onofrio* were executed by *Jacopo della Quercia* of Siena, one of the founders of Renaissance sculpture; and even *Michael Angelo*, when a fugitive from Florence after the banishment of the Medici (1494), found occupation in the church of *S. Domenico*. *Tribolo* was likewise employed here. Of the Upper Italian masters, who are well represented at Bologna, *Alfonso Lombardi*, or properly *Cittadella* of Lucca (1488-1537), holds the highest rank. Bologna was also the birthplace of *Propertio de' Rossi* (1490-1530), one of the few women who have devoted themselves to sculpture.

In the province of **PAINTING** the first master who attained more than a local reputation was *Francesco Francia* (1450-1517), the goldsmith, a pupil of Zoppo of Ferrara. In the devotion and gracefulness of his female figures he almost rivals Perugino. His son *Giacomo Francia* was influenced by the Venetian school, while at the same time the school of Raphael gained ground at Bologna. The chief adherents of the latter were *Bartol. Ramenghi*, surnamed *Bagnacavallo* (d. 1542), and *Innocenzo da Imola* (d. 1550?). Bologna attained its greatest importance at the close of the 16th cent. The mannerism into which Italian painting had gradually lapsed, was resisted by the **ECLECTICS**, whose style was mainly introduced by *Lodovico Caracci* (1555-1619). In teaching at his academy he inculcated a thorough mastery of the elements of art, a comprehensive education, and a careful study of the great masters. The school was afterwards carried on by his cousins *Agostino* (1558-1601) and *Annibale Caracci* (1560-1609), the last of whom in particular possessed a refined sense of colour, developed by the study of Correggio. To this school belonged also *Guido Reni* (1574-1642), *Domenichino* (*Domenico Zampieri*; 1581-1641), and *Albani* (1578-1660), who exercised a great influence on Italian art in the 17th cent. and effected a temporary revival of good taste. They afterwards came into collision with the naturalists, chiefly at Rome and Naples, but at Bologna their sway was undisputed.

The **\*Piazza Vittorio Emanuele** (Pl. F, G, 4), formerly *Piazza Maggiore*, in the centre of the town, the mediæval 'forum' of Bologna, is one of the most interesting in Italy. It is adorned with a **Fountain** by *Laureti*; the bronze statue of Neptune, executed by *Giov. da Bologna* (born 1524 at Douay in Flanders) in 1564, is said to weigh 10 tons, and to have cost 70,000 ducats. The smaller part of the Piazza on the N. side is sometimes called *Piazza del Nettuno*.

In this Piazza is situated the **Palazzo Pubblico**, or *del Governo* (Pl. 45; F, 4), formerly *Pal. Apostolico*, begun in 1290, adorned with a Madonna on the façade by *Niccolò dell' Arca* (d. 1494) and a bronze statue of Pope Gregory XIII. (*Buoncompagni* of Bologna) by *Menganti*, which was transformed in 1796 into a statue of St. Petronius. The grand staircase in the interior was designed by

*Bramante* (1509); the galleries and halls are decorated with frescoes; a colossal sitting statue of *Heracles* (in plaster) in the hall of that name, by *Alfonso Lombardi*; in the *Sala Farnese* a statue of *Paul III.*, etc.

In the *VIA DELLE ASSE*, which opens to the S. of the *Palazzo Pubblico*, on the right, is the *Palazzo Marescalchi* (Pl. 63; E, F, 4), erected by *Dom. Tibaldi*, and containing some frescoes by *Lod. Caracci* and *Guido Reni*. — The handsome neighbouring church of *S. SALVATORE* (Pl. 34; E, 4) was built by *Magenta* in 1603. 1st chapel to the left, *Garofalo*, *Zacharias*, *St. John*, and saints; 3rd chapel (l.) *Inn. da Imola*, *Christ* and four saints; left transept, *Tiavini*, *Nativity*. — *S. Francesco* (Pl. 12), now a military magazine, contains a handsome altar of 1388.

Opposite is the *Palazzo del Podestà* (Pl. 44; F, 4), of 1201, with façade of 1485, where the young and poetically gifted King *Enzio* was kept a prisoner by the Bolognese, but was solaced by his attachment to the beautiful *Lucia Vendagoli*, from whom the *Bentivoglio* family is descended. The great hall is called after him *Sala del Re Enzio*. The conclave for the election of *Pope John XXIII.* was held here in 1410. The palace contains the *Civic Archives*, with a number of ancient documents.

The adjoining *Portico de' Banchi*, erected by *Vignola* in 1562, is chiefly used for shops. Opposite to it is —

\**S. Petronio* (Pl. 1), the largest church in the town, begun in emulation of the cathedral of *Florence* in the *Tuscan-Gothic* style in 1390 from a design by *Antonio Vincenzi*, but never completed. The projected length was upwards of 200 yds., and an imposing transept and an octagonal dome rising above the centre between four towers were to be erected. The work was discontinued in 1659, when the nave and aisles as far as the transept only were completed, and they are now terminated by an apse of the breadth of the nave. Length 128 yds., breadth with the chapels 52 yds. The nave is of vast dimensions, and the aisles are flanked with chapels. The church is supported by twelve pillars, and below the pointed vaulting are small round-arch windows. The \*sculptures of the principal entrance are by *Jacopo della Quercia*, 1429; side-doors by *Niccolò Tribolo*, 1525. — Over the principal entrance a bronze statue of *Pope Julius II.* with the keys and a sword in his left hand, by *Michael Angelo*, was placed in 1508, but it was destroyed by the populace three years later, and sold as old metal to the Duke of *Ferrara*, who used it in casting a piece of ordnance ('*Giuliano*').

The Interior is adorned with numerous sculptures and pictures. Most of the chapels are enclosed by handsome marble screens, dating from the 14th, 15th, and 16th centuries. 1st Chapel on the right: altar-piece (*God the Father* with angels) by *Giacomo Francia*; 2nd Chapel (r.) curious old frescoes of the year 1417. 4th Chapel: Old stained glass by *Jacob of Ulm*. 8th Chapel: good inlaid stalls by *Fra Raffaele da Brescia*. 9th Chapel (*di S. Antonio*): Statue of the saint, an early work of *Sansovino*, and the eight Miracles wrought by him, in grisaille, by *Girolamo da Treviso*; fine stained glass from designs by *Pellegrino Tibaldi*. 11th Chapel: Assumption of *Mary*, a high-relief, the lower part by *Niccolò Tribolo*;



the two angels by his pupil *Properzia de' Rossi*; opposite to it is a *Pietà* by *Vincenzo Onofri*. — The sacristy contains pictures of no great value.

Under the canopy of the CHOR, Charles V. was crowned emperor by Pope Clement VII. on 24th Feb., 1530, this being the last occasion on which an emperor was crowned in Italy.

The REVERENDA FABBRICA (workshop), at the end of the N. aisle, contains forty sketches of the unfinished façade, of the 15th-17th cent., by *Palladio*, *Giulio Romano*, *Vignola*, etc., an interesting collection; also a model of the church in wood (the best time for inspecting it is about noon).

N. Aisle: The CAPPELLA BACCIOCCHI (5th from the altar) contains the monument of Princess Elisa Baccocchi (d. 1820), grand-duchess of Tuscany and sister of Napoleon, and of her husband Felix; opposite to it, that of two of her children, groups in marble by the two *Franzoni*. Over the altar a *Madonna* by *Lorenzo Costa*, by whom the stained glass windows were also designed. 7th Chapel: Annunciation in two pictures, and the Twelve Apostles, also by *Costa* (windows probably by him). 8th Chapel, the oldest in the church, consecrated in 1392, contains ancient frescoes: Adoration of the Magi, with Paradise and Hell beneath, recalling Dante's poem; altar with sculptures in marble, and stained glass by *Jacob of Ulm* (?), also worthy of note. Between this and the 3rd chapel are two clocks manufactured by *Fornasini* in 1756, one of which gives the solar, the other the mean time. On the pavement of this aisle is the meridian-line drawn by the celebrated astronomer *Gian. Domenico Cassini* in 1653.

To the S. E. of S. Petronio is situated the \***Archiginnasio Antico** (Pl. 46; F, 5; entrance under the Portici del Pavaglione), erected as a university in 1562 by *Terribilia*, and since the transference of the latter to the Palazzo Cellesi (p. 280) used as a *Biblioteca Comunale* (open daily 10-4, except Sund.; several valuable MSS.). The Logge of the court and of the first floor, contain numerous monuments, adorned with armorial bearings, to the memory of professors of the university (*Muratori*, *Peggi*, *Malpighi*, *Mariani*, etc.), and the arms of the students arranged according to their provinces. On the first floor is the *Museum of Antiquities* (open daily 10-4), connected with the library (*Museo Civico*).

I. Room. Egyptian antiquities. — II. Room. Vases found in Lower Italy, most of them with the usual representations of offerings for the dead; 11. Battle of Codrus with the serpent; 231. Athenian prize-vase with inscription (one of those in which the victors in the athletic sports at Athens received a certain measure of the holy oil). Black vases found at Chiusi (Clusium). Sculptures by the window-wall: \*2061. Head of an athlete, possibly by *Polyclethus*; 2065. Athene; 2075. Relief of Zeus, Hera, and Hebe. In the glass-cabinet interesting vases from *Ægina*; 1585. Fighting cocks, with the name of the sculptor *Nikosthenes*; 1589. Athene, *Dionysus*, *Hercules*; 1584. Genre scene, a cock staked as a wager; 1598. Cloaked figures playing at *Morra*, the guessing game, which is still so popular in Italy. Below, without a number, \**Orcestes*, *Pylades*, and *Electra*. By the wall (l.) vases from Athens; 1377. *Ædipus* and the *Sphinx* (blackened by the burning of the corpse); on the glass cabinet bronzes of the best style; 535. The nine Muses. — III. Room. Vases. \*108. Battle scene; \*84. Battle scene; 104. *Poseidon* and *Amphitrite*; in front of the last are ancient Etruscan ornaments, domestic utensils, etc., from the excavations in the old Necropolis near the *Certosa* (p. 283), which have been carried on since 1869. To the left are tombstones with reliefs. By the window are several early Etruscan tombs. In the centre, under glass, is a bronze vase with representations of processions. — IV. Room. Tombs and tombstones from the same source. — The anatomical lecture-room with statues of the most celebrated professors is also interesting. The roof over the chair is borne by two anatomical figures in wood.

We now proceed to the S. to the **PIAZZA CAVOUR** (Pl. G, 5) in which the new *Banca Nazionale* (Pl. 82), by Cipolla, is situated on the right, and the *Palazzo Guidotti* (Pl. 59) on the left. The latter was rebuilt by *Cor. Monti*, the architect of several other modern buildings in the town. A little farther S. is the **PIAZZA S. DOMENICO** (Pl. F, G, 6), in which is situated the church of —

\***S. Domenico**, formerly *S. Bartolommeo* (Pl. 10), but rededicated to St. Dominicus, who was born in Castile in 1170, and died here in 1221. The church is in the Romanesque style, dating from the 12th cent., but was completely remodelled in the 18th.

**INTERIOR.** 3rd Chapel on the right, on the lower part of the altar a *Madonna* by *Scarsellino da Ferrara*, under glass. — **RIGHT TRANSEPT:** **CHAPEL OF S. DOMENICO**, containing the tomb of the saint, a "sarcophagus" (arca) of white marble dating from 1267, the sarcophagus itself completed, with reliefs from the life of the saint, by pupils of *Niccolò Pisano*; "reliefs in front by *Guglielmo* (some of them perhaps from designs by the master himself), the statues by *Niccolò dell' Arca* (d. 1494), who received his surname from this work, and by *Cortellini*, reliefs on the base by *Alfonso Lombardi* (d. 1537). The kneeling "angel on the left, was until recently regarded as a work of *Michael Angelo* (1494), but the less attractive angel to the right of the spectator is now attributed to him instead of the other. The same great master is also supposed to have executed the drapery of St. Petronius immediately over the sarcophagus with the church in his hand. In the half-dome over the arca, a "transfiguration of the saint, by *Guido Reni*; (r) the saint resuscitating a boy, by *Tiarini*; (l.) the saint burning heretical documents, by *Lionello Spada*; adjoining the choir, on the right *Filippino Lippi*, *Madonna* and saints, 1501. — In the **CHOIR**, magnificent inlaid "stalls" by *Fra Damiano da Bergamo*, 1528-51, among the finest of its kind in Italy. Between the 1st and 2nd chapels on the left of the choir is the monument of 'Hencius Rex', or king *Enzio* (p. 273), frequently restored; in the 2nd chapel (r.) that of *Taddeo Pepoli* by *Jacopo Lanfrani*, 1337; opposite to it a portrait of St. Thomas Aquinas (d. 1274) (much retouched). — **LEFT TRANSEPT:** The **CAPELLA DEL ROSARIO** contains the tombs of *Guido Reni* (d. 1642; to the left a memorial stone; his grave under a slab in the centre) and the talented painteress *Elisabetta Sirani* (died of poison at the age of 26, in 1665). The frame round the altar-piece consists of small paintings by *Guido Reni*, the *Caracci*, *Elisabetta Sirani*, and others. In the vestibule of the side-entrance (to the right in going out) is the monument of the jurist *Alessandro Tartagni*, by *Francesco di Simone* (1477). Opposite is the monument of the *Volta* family, with St. Proculus by *Prospero Clementi* (about 1580).

In the **Piazza S. Domenico** rise two columns with statues of the saint and the *Madonna* and two *Monuments* of the 13th cent., the more important of which, borne by nine columns, was erected in 1207 in honour of *Rolandino Passeggieri*, who distinguished himself in the contests between the town and the Emp. *Fred. Barbarossa* (restored in 1868).

In the vicinity, in the first piazza to the S., is the *Pal. Baccicchi* (Pl. 52; F, 6), with a façade by *Andrea Palladio* and a colonnade by *Bibbiena*. It is now occupied by the *Tribunale*, or law-courts.

To the W. in the *Strada S. Mamolo* is the \**Pal. Bevilacqua-Vincenzi* (Pl. 54; F, 5), ascribed to *Bramantino*, with a superb court, the finest of its style (perhaps by *Gasparo Nadi*, about 1483), but without the usual arcade on the ground-floor. In 1547

the Council of Trent sat here for a short time. — The Via Urbana then leads to the —

**Collegio di Spagna** (Pl. 40; E, 5), at the corner of the Strada Saragozza, founded in 1364 by Cardinal Albornoz, and containing frescoes (damaged) by the *Caracci* and a Madonna (above) by *Bagnacavallo*. The Coronation of Emp. Charles V. at S. Petronio by the latter is covered by whitewash. — A little to the N. is the church of *S. Paolo* (Pl. 31; E, F, 5), erected by Magenta in 1611, with pictures by Lod. Caracci (2nd chapel on the right, Paradise), Guerciuo (in the 4th chapel on the right), and other masters. — Obliquely opposite to it are the *Pal. Zambecari di S. Paolo* (Pl. 69; F, 5), and the suppressed chapel of the *Frati di S. Spirito*, with a charming Renaissance façade, adorned with two rows of pilasters, medallions, and an attica in terracotta.

We now return by the Via S. Mamolo to the Piazza Vitt. Emanuele.

From the N. side of the Piazza del Nettuno (p. 273) the busy *Mercato di Mezzo* (Pl. F, G, 4) leads to the E. to the leaning towers (see below). — In the neighbouring PIAZZA DEL DUOMO (Pl. F, 3, 4) rises the cathedral church of —

**S. Pietro** (Pl. 2), in the 'baroque' style, begun in 1605. It consists of a spacious nave with circular vaulting, the aisles being partly converted into chapels with lofty galleries, and partly into separate apartments. In the chapter-room, St. Peter with the Madonna; above the choir an Annunciation, the last work of *Lod. Caracci*. — Adjoining it on the N.E. is the *Palazzo Arcivescovile* (Pl. 42), with a court constructed by Tibaldi in 1577. — In the vicinity, to the N.W. of S. Pietro, is the small church of the *Madonna di Galliera* (Pl. 20; F, 3), with an interesting, but dilapidated façade of 1470. — Opposite is the *Pal. Fava* (Pl. 57; F, 3), with fine \*frescoes by the *Caracci* from the myths of Jason and Æneas.

We now return to the Mercato di Mezzo, at the E. end of which, nearly in the centre of the town, are the LEANING TOWERS (Pl. G, 4), the most singular structures in Bologna. The **Torre Asinelli** (Pl. 78), erected in 1109 by *Gherardo degli Asinelli*, which looks prodigiously high when seen from the pavement below, is 272 ft. in height and 3 ft. 5 in. out of the perpendicular. A rough staircase of 447 steps leads to the summit, which commands a fine view. The **Torre Garisenda** (Pl. 79), erected in 1110 by *Filippo* and *Ottone Garisendi*, is 138 ft. high only, but is 8½ ft. out of the perpendicular towards the S., and 3 ft. towards the E., and since the last measurement (1772) is said to have settled still more. Dante (*Inferno xxxi.* 136) compares the giant Antæus, who bends towards him, to this tower, 'when a cloud passes over it'. The latter is probably the only one of the many leaning towers

in Italy whose obliquity has been intentional (comp. p. 306), but it was found impossible to complete it.

From the leaning towers five streets radiate to the gates of the same names: the Strada Castiglione, S. Stefano, Maggiore, S. Vitale, and Luigi Zamboni (or S. Donato). To the right at the corner of the Strada S. Stefano and Str. Castiglione is situated the **\*Palazzo della Mercanzia** (Pl. 43; G, 4) or *Loggia de' Mercanti* (Chamber of Commerce), a Gothic structure, said to have been erected in 1294, and restored by the Bentivogli in 1493. The interior is adorned with the armorial bearings of all the jurists who taught law here from 1441 to 1800. — Farther S. in the STRADA CASTIGLIONE is the *Pal. Pepoli* (Pl. 64; G, 5), of 1344, the castellated residence of this once powerful family, with a rich gateway and an imposing court with a colonnade on one side and arched passages on the three others. — Farther on, to the right, rises the handsome new *Cassa di Risparmio* (Pl. 81; G, 5), with arcades on the ground-floor, and handsome wrought iron gratings at the windows; the plan of this palace, as well as of other buildings in the town, was designed by *Giuseppe Mengoni* (p. 123).

On the left in the STRADA S. STEFANO is situated —

**\*Sto. Stefano** (Pl. 36; H, 5), a pile consisting of seven different churches, containing ancient columns and mural paintings, and, according to an inscription still extant (of which there is a copy on the exterior to the left, of 1769), occupying the site of a temple of Isis, having probably been founded in the 5th century. The churches are not all on the same level, the last having been constructed as a crypt below the first. The *first* church, of 1637, contains nothing noteworthy. — A chapel leads thence to the left into the *second* church, **\*S. Sepotero**, originally the *Baptistery*, surrounded by an ambulatory, and erected for its present purpose before the year 1000. In the 12th cent. the tomb of St. Petronius was added in imitation of the Holy Sepulchre at Jerusalem, and a brick column was placed adjacent to each of the antique marble columns. The ambo with the symbols of the evangelists is of the 9th century. Over the altar are frescoes of the 15th cent. by an unknown master. — To the left is situated the *third* church, that of *SS. Pietro e Paolo*, an ancient basilica, in which the last column to the right of the altar has an antique Ionic capital. The altar adjoining the choir on the left is a sarcophagus dating from the 9th cent., and contains the bones of the martyr St. Vitalis (l. 382). Above it, a Madonna with saints by *Lor. Sabbatino* (d. 1577). On the right the sarcophagus of the martyr Agricola (9th cent.), the saint being represented with wings, between a stag and a lion; above it a crucifix by *Simone da Botogna*, surnamed *de' Crocifissi* (14th cent.). — We now return to the second church, whence the first door on the left leads us to the *fourth* church, the *Atrio di Pilato*; in the centre is a font with an inscription mentioning the Lombard king Luit-

prand (d. 744). Chapel on the left, Crucifixion by *Franc. Francia*. To the right of the portal is the *fifth* church (below the first), *della Confessione*, dating from the 11th cent. — The *sixth* church, *della Consolazione*, adjoins the Atrio di Pilato on the right. — Lastly, on the left, rises the *seventh* church, *della Trinità*, resting on pillars, in the centre of which is a series of columns with Byzantine capitals. 3rd Chapel on the right, an Adoration of the Magi in wood (14th cent.). — To the right the handsome cloisters (11th cent.) of the suppressed Celestine monastery.

The Piazza in front of the church contains several handsome Renaissance buildings.

A short side-street to the right now leads to —

**S. Giovanni in Monte** (Pl. 15; H, 5), one of the oldest churches in Bologna, founded by St. Petronius in 433, re-erected in the Gothic style in 1221, and restored in 1824. It consists of a low nave with aisles and a short transept, and a façade and dome of more recent date.

INTERIOR. 1st Chapel on the right, Christ appearing to Mary Magdalene in the garden, by *Giacomo Francia*; 3rd Chapel, St. Joseph on the right, St. Jerome on the left, both by *Guercino*. 7th Chapel, Madonna enthroned with four saints and angels, by *Lorenzo Costa*. In the Choir, Coronation of the Virgin, by *Costa*; stalls by *Paolo Sacca*, 1523; above them, the busts of the twelve apostles in terracotta, by *Alfonso Lombardi*. The N. transept contained Raphael's St. Cecilia down to 1796 (p. 281; the frame by *Formigine* is the original). 6th Chapel on the left, statue of Christ in wood over the altar (15th cent.). 5th Chapel on the left, Call of the sons of Zebedee, by *Cesi*. 2nd Chapel on the left, St. Francis, by *Guercino*.

In the STRADA MAGGIORE (Pl. G, H, I, 4, 5), opposite the Torre Garisenda, at the corner of the Strada S. Vitale is the church of **S. Bartolommeo di Porta Ravennana** (Pl. 3; G, 4), erected in 1653, a gaudy dome-covered church with paintings by *Angelo Colonna*. The 4th altar on the right contains an Annunciation (1632), one of the best works of *Franc. Albani*, and a Nativity, and Flight to Egypt, by the same master. — The opposite Palazzo, with the elegant windows and the date 1496, is said to have been designed by *Franc. Francia*. — Farther on in the Str. Maggiore, on the left, N. 244, is the —

**Pal. Sampieri** (Pl. 70; H, 4), with the inscription '*Galleria Sampieri*' (admission 1/2 fr.), adorned with admirable frescoes from the myth of Hercules by the *Caracci* and *Guercino*. The celebrated old picture-gallery it once contained has been sold. The present collection (good light necessary) consists chiefly of works by pupils of Guido Reni and *Guercino*. Many of the names in the written catalogue are arbitrary.

1st Room: nothing of importance. — 2nd R. Frescoes on the ceiling: Hercules contending with Jupiter; right wall, Ceres seeking Proserpine, by *Lod. Caracci*. Pictures: 46. *Elisabetta Strani*, Putti; 76. *Scarsellino*, Madonna and saints; 134. *Parmeggianino*, Madonna; 123. *Sannachiini*, Holy Family; 73. *Annib. Caracci*, Old woman spinning. — 3rd R. Frescoes on the ceiling: The path to virtue is difficult; right wall, Giant struck by lightning, both by *Annib. Caracci*. Pictures: 147. *Domenichino*, Mater

dolorosa; 164. Olympus. — 4th R. Frescoes on the ceiling: Hercules and Atlas. Wall on the right, Hercules and Cacus with the lion's head, by *Agost. Caracci*. Pictures: 166. *Guido Reni*, Circe; 162, 163. Portraits by *Agost. Caracci*; 152. *Cavedone*, Christ and the tribute-money. — 5th R. Ceiling-painting: Hercules and Antæus, by *Guercino*. Pictures: 242. *Caracci*, Madonna; \*232. *Salvator Rosa*, Storm. — 6th R. Ceiling-painting: \*Genius of strength, by *Guercino*.

The adjoining *House of Rossini* (Pl. 71) was erected by the great composer in 1825, and adorned with inscriptions from Cicero and Virgil (recently marked by a tablet).

**Ai Servi** (*S. Maria ai Servi*; Pl. 35; I, 5), at the corner of the Str. Maggiore and Cartoleria Nuova, erected by *Andrea Manfredi* in 1393, with remarkably thin columns placed very wide apart, is adorned with frescoes (much damaged) on the façade, dating from the 17th cent.

INTERIOR. Over the high altar, completed by *Montorsoli* in 1561: Christ risen from the Dead, and Mary and St. John, below (l.) Adam, (r.) Moses, at the back the portrait of the donor Giulio Bori. Below the organ are small frescoes by *Guido Reni*. 7th altar on the left, Annunciation, by *Innocenzo da Imola*. The place of the 3rd altar on the left is occupied by the monument of Lod. Gozzadini in stucco, by *Giov. Zucchio*. 2nd altar: Christ and Magdalene, by *Fr. Albani*. In the choir, on the right, a terracotta relief, representing the Madonna and SS. Laurence and Eustace with two angels, by *Vincenzo Onofri*, 1503.

**S. Vitale ed Agricola** (Pl. 38; H, 4), in the STRADA S. VITALE, was consecrated in 428 by St. Petronius, and restored in 1872. The large chapel on the left contains an altar-piece (covered) by *Fr. Francia*. Side-frescoes on the right representing the Adoration of the Shepherds by *Fr. Francia*, on the left the Conception by *Bagnacavallo*. — Opposite is the *Palazzo Fantuzzi*, now *Pedrazzi*, built in 1605 from designs by Andrea Marchesi, which contains a superb staircase by P. Canali.

The most northern of the streets radiating from the leaning towers is the STRADA LUIGI ZAMBONI (Pl. H, I, 4, 3) or S. Donato, to the right in which is the handsome *Pal. Malvezzi - Medici* (Pl. 61) by Bart. Triacchini, 1550. Farther on, in the small PIAZZA ROSSINI, which is named after the celebrated composer who attended the neighbouring Liceo Filarmonico (Pl. 41) in 1807-10, is —

\***S. Giacomo Maggiore** (Pl. 13), founded in 1267, consisting of a nave with barrel-vaulting of 1497, with a portico erected in 1483 by *Gasparo Nadi*, and adorned with several excellent pictures.

Over the altar, immediately to the right of the entrance, is the 'Vergine della Cintura', by an early Bolognese master (covered); 3rd Chapel on the right: *Ercote Procaccini*, Conversion of Saul; 5th Chapel, *Passerotti*, Madonna enthroned, with saints and the donor; 7th Chapel, Marriage of St. Catharine, by *Innocenzo da Imola* (1536; the green colour unfortunately faded); 9th Chapel, St. Rochus with an angel, by *Lod. Caracci*; 11th Chapel, erected by *Pellegr. Tibaldi*, the teacher of Caracci, and decorated by him with frescoes. In the CHOIR large paintings of the Resurrection, etc. by *Tommaso Lauretti*. The 3rd chapel in the retro-choir contains a gilded altar with numerous saints; to the left, on the wall, a large painted crucifix by *Simone de' Crocefissi* (1370). The 6th \*CAP. DE' BENTIVOGLI, erected in 1486, contains a \*Madonna, with angels, on the right S. Sebastian, on the left the founder, the best work of *Fr. Francia*, and frescoes by *Lorenzo*

*Costa*, representing the Triumph of life and death, after Petrarch, on the left, and the Bentivogli family on the right (1488); the frescoes above are by *Giacomo Francia*; equestrian statue of Annibale Bentivoglio by *Niccolò dell'Arca* (1458); opposite to it the \*monument of Antonio Bentivoglio (d. 1435) by *Jacopo della Quercia*. The 9th Chapel in the left aisle contains a Presentation in the Temple, by *Orazio Sammachini*.

The sacristan of S. Giacomo also keeps the keys of the adjacent oratory of \***S. Cecilia** (Pl. 6; H, 4), erected in 1481 for Giovanni Bentivoglio. The frescoes by *Fr. Francia* and his pupils represent the legend of St. Valerian and St. Cecilia (Nos. \*1 and 10 by *Fr. Francia*, 2 and 9 by *Costa*, \*3 and 8 by *Giacomo Francia*, 4 by *Chiodarolo*, 5, 6, and 7 by *Aspertini*).

Opposite, on the left side of the street, is the *Pal. Malvezzi-Campeggi* (Pl. 62), by Andrea and Jac. Marchesi, with an interesting court. Adjacent is the *Palazzo Magnani-Guidotti*, by Dom. Tibaldi, 1577, with frescoes in the interior by the Caracci. — Then the *Teatro del Comune* (Pl. 72; H, 3). — On the right we next observe the —

**University** (Pl. 47; I, 3), established since 1803 in the old *Palazzo Cellesi*, with a court by *Triacchini*. After that of Salerno, it is the oldest in Italy, having been founded in 1119, and now possesses a staff of 50 professors and 400 students (comp. p. 271) and a considerable number of scientific institutions (clinical hospital, anatomical theatre, natural history collections, open on Sundays, botanical garden, and observatory). — It also contains a *Museum of Antiquities*, the keys of which are kept by the bidello, or custodian.

*Ante-Chamber*: Roman mile-stones. In the room to the left are inscriptions; on the right and left of the door are fragments of an ancient columbarium. — We now pass through the gate to the right (and begin on the right): four good antique capitals, with earthen and leaden conduits between them. Earthen cinerary urn with the battle of Eteocles and Polyneices (the same scene is repeated six times; the two winged figures are gods of death). \*Five marble figures, probably part of the decoration of a fountain: 1. Venus stooping in the bath; 2. Venus rising from the water (Anadyomene), above it a bakchouse; 3. Satyr with a boy on his shoulder; 4. Torso of a young satyr; 5. Same subject. Between Nos. 2 and 3, torso of a figure in armour. On the right and left of No. 4 are fragments of an Amazon battle in relief. Head in black marble (high relief). End-wall: trilateral \*pedestal of a candelabrum. Left wall: \*corner-brick with Hercules and Dionysus, Zeus, and Hera. Rich cornice. Room on the right: portraits of popes Urban VIII., Innocent III., Boniface VIII., and others. The cabinets contain fine terracottas (some of them found at the Certosa): Victory sacrificing a bull, the drunken Dionysus supported by a satyr boy, etc.; also vases, bronzes (weights in the form of a head, chariots, spoons, lance-points, etc.). End-wall: bronze statuettes, Etruscan mirrors (birth of Athena, Hera with the infant Hercules, etc.); on the left a few Egyptian antiquities.

The extensive **Library** of 100,000 vols. is open daily, 9-3 o'clock, except Sundays. The oldest of the MSS. is that of Lactantius; also letters from Voltaire to Fred. the Great, miniatures, etc. The celebrated linguist *Giuseppe Mezzofanti* (born at Bologna 1776, died at Naples in 1849), professor of Oriental languages at the university, was once librarian here. At the age of 36 he is said to have spoken 18 languages fluently, and at the time of his death no fewer than 42. — The **Archives** comprise a number of ancient documents on papyrus, the *Codex Diplomaticus Bononiensis* in 44 vols., etc.

The **Geological Museum** was established in 1871 in an adjoining building, Via Luigi Zamboni 2530, under the superintendence of Prof. Capellini, who has enriched it with interesting fossils from the neighbourhood of Bologna, minerals from different parts of Europe and America, and a collection of prehistoric anthropological curiosities. — The *Tower* commands a good survey of the town.

We next proceed to the —

\***Accademia delle Belle Arti** (Pl. 39; G, 3), established in the old College of the Jesuits. It contains on the **GROUND-FLOOR** collections of casts and modern works of art; on the **FIRST FLOOR** (1.) a collection of weapons (*Oploteca*), comprising arms captured from the Turks, Venetians, etc., and (r.) a valuable \**Picture Gallery*, or *Pinacoteca*, consisting chiefly of works of the Bolognese School arranged in eight saloons and rooms (open daily from 9-3 or 4, according to the season; admission 1 fr.; on Sundays gratis). Each picture bears the name of the painter.

The visitor imbued with the modern taste for the historical study of art, will find little attraction in the works of the **SEVENTEENTH CENTURY**, which form the chief boast of the gallery. Although it would be unfair to depreciate the undoubted talent and skill of these late masters, their works are unsatisfactory owing to the absence of any definite aim or indication of progress, and from the obvious pains which have been taken to reproduce trite themes in an interesting manner. In the department of fresco painting the works of these Bolognese eclectics (see p. 272) are most numerous at Rome, but they are admirably represented here by a series of oil-paintings. We may first mention several works by *Guido Reni*, the most talented master of this school: No. 133, *Madonna della Pietà*, remarkable for its masterly grouping, which again recurs in No. 136, the *Crucifixion*, and which places these two pictures on a level with the finest works of the 16th cent. in point of composition; No. 135, the *Slaughter of the Innocents*, exceptionally harmonious and dignified in character; No. 139, *St. Andrea Corsini*, an excellent specimen of Guido's powers as a colourist; No. 142, a masterly drawing in chalks for the *Ecce Homo* which was so popular in the 17th cent. The most interesting work of *Lodovico Caracci* is probably No. 45, the *Nativity of St. John*. *Annibale Caracci's* *Madonna and saints* (No. 36) has the merit of stately architectural arrangement. The *Communion of St. Jerome* (No. 34) by *Agostino Caracci* is very inferior to *Domenichino's* treatment of the same subject in the Vatican. *Domenichino's* scenes of martyrdom are far from pleasing, but *Guercino's* *Madonna with the two Carthusian monks* (No. 13) is a devotional picture of profound sentiment. — The gallery also possesses several valuable works of the **EARLIER PERIOD** of Italian art. Thus No. 78, a *Madonna* by *Fr. Francia*, exhibits features of resemblance with *Perugino*, who is represented here by one of his finest works (No. 197, *Madonna and saints*). We also obtain a good survey here of the masters who went over from *Francia's* school to that of *Raphael*: thus, 204. *Timoteo della Vite*, *Mary Magdalene*: 292, 90. *Imocenzo da Imola*, *Madonna and saints*, and *Holy Family*. — The gem of the gallery, however, is *RAPHAEL'S* *ST. CECILIA*, the indelible impression produced by which is doubtless due to the master's unrivalled genius in exalting his figures into the regions of the supernatural, and yet making them human and pleasing. Everything has been maturely considered, the broken instruments, the angels' song, the distribution and graduation of the characters, — and yet the picture appears as simple and natural as if it could not possibly have been arranged otherwise.

**CORRIDOR**: 221. *Giov. Batt. Francia*, *Madonna with the Child, Joseph, and Catharine*; 15. *Guercino*, *John the Baptist*; 39, 40. *Annib. Caracci*, *Annunciation*; 281. *Elisabetta Sirani*, *Mary Magdalene*.

1. Room (reached in a straight direction): 142. *Guido Reni*, *Drawing*



in chalks for the *Ecce Homo*; 82. *Francesco Francia*, Picture in three sections, on the left, the Adoration of the Shepherds, in the centre the Madonna and Child, on the right the Crucifixion in a beautiful landscape; 175. *Elisabetta Sirani*, St. Antony of Padua; 117. *Mazzolino*, Mary and Joseph adoring the Child; 74. *Prospero Fontana*, Entombment. — In the centre: 360. *Niccolò Alunno da Foligno*, Madonna adoring the Child, with the Annunciation on the back, presented by Pius IX. in 1856.

II. ROOM: (r.) 37. *Ann. Caracci*, Madonna with saints; 2. *Albani*, Baptism of Christ; 42. *Lod. Caracci*, Madonna with SS. Dominicus, Francis, Clara, and Mary Magdalene, being portraits of members of the Bargellini family, at whose cost the picture was painted; 206. *Domenichino*, Martyrdom of St. Agnes; 36. *Ann. Caracci*, Madonna with SS. Lewis, Alexis, John the Baptist, Francis, Clara, and Catharine; 35. *Ag. Caracci*, Assumption; 47. *Lod. Caracci*, Conversion of Paul; 183. *Tiarini*, Nuptials of St. Catharine; 34. *Ag. Caracci*, Communion of St. Jerome; 207. *Domenichino*, Madonna del Rosario; 55. *Giacomo Cavedoni*, Madonna in glory with saints.

III. PRINCIPAL ROOM: 198. *Vasari*, Banquet of Gregory I., 1540; 80. *Fr. Francia*, Madonna enthroned, with SS. John the Baptist, Stephen, George, and Augustine; 210. Old copy from *Raphael*. Young St. John (a replica of the same in the Uffizi at Florence); \*152. *Raphael's* St. Cecilia listening to the heavenly music in an ecstatic trance, surrounded by SS. Paul, John, Augustine, and Mary Magdalene. This exquisite picture, the gem of the collection, was painted about the year 1515 for the chapel of the Bentivogli in S. Giovanni in Monte (p. 278). It was at Paris from 1796 to 1815. — 133. *Bagncavallo* (after *Raphael*), Holy Family; 65. *Lorenzo Costa* (so designated), Three saints, 1502; 81. *Fr. Francia*, Madonna adoring the Child, with saints and donors; 371. *Fr. Francia*, Madonna and saints, with the Infant Christ above in the 'mandorla'; \*84. *Giac. Francia*, Madonna and four saints, 1526; 122. *Niccolò da Cremona*, Entombment; \*78. *Francesco Francia*, Madonna and Child, four saints, angels, and the donor (1494); \*197. *P. Perugino*, Madonna in gloria, with the archangel Michael, SS. John, Catharine, and Apollonia; 79. *Fr. Francia*, Madonna with John the Baptist, St. Jerome, and angels; 87. *Giac. Francia*, Madonna and saints, and nuns; 204. *Timoteo della Vite*, Mary Magdalene; 90. *Innocenzo da Imola*, Holy Family and two donors; 85. *Giacomo Francia*, Madonna and saints; 89. *Innocenzo da Imola*, Archangel Michael subduing the dragon.

IV. ROOM: 13. *Guercino*, St. Bruno in the wilderness; \*137. *Guido Reni*, Samson victorious over the Philistines; 12. *Guercino*, William of Aquitaine receiving the robe of the Order of St. Felix; \*136. *Guido Reni*, Crucifixion ('Cristo dei Cappuccini', the high altar of whose church it formerly adorned), one of his finest works; 208. *Domenichino*, Martyrdom of St. Peter; \*134. *Guido Reni*, Madonna della Pietà, below are St. Petronius, Carlo Borromeo, Dominicus, Francis, and Proculus; the picture was painted in 1616 for the Town Council, who rewarded the painter with a valuable gold chain and medal, in addition to his remuneration; 141. *Guido Reni*, Coronation of the Virgin, with four saints below; 140. *Guido Reni*, St. Sebastian; 182. *Tiarini*, Entombment; \*135. *Guido Reni*, Slaughter of the Innocents; 138. *Guido Reni*, Madonna del Rosario, painted on silk in 1630 (as a procession-flag).

In the CORRIDOR: (r.) 61. *Cima da Conegliano*, Madonna; 129. *Giuliano Bugiardini*, St. John in the wilderness; 83. *Fr. Francia*, Christ mourned over by angels; 116. *Parmeggiano*, Madonna and Child with St. Catharine; \*75. *Raphael Mengs*, Portrait of Clement XIII; 392. *Lor. Costa*, Madonna enthroned and two saints (1491); 297. *Aspertini*, Adoration of the Child.

V. ROOM: Altar-pieces of the 14th and 15th cent. by *Vitale* (1320), *Simone da Bologna*, *Jacopo Avanzi*, *Antonio* and *Bartolommeo Vivarini* of Murano (about 1450); 102. Wings of an altar-piece (the latter now in the Brera at Milan, p. 125) by *Giotto*, from the church degli Angioli, with SS. Peter, Paul, the angels Michael and Gabriel, and good predelle; 282. *Hugo van der Goes* (?), Madonna in a garden. In the glass cabinet are some specimens of engraving, by *Franc. Francia*.

VI. ROOM: above the door, 292. *Innocenzo da Imola*, Virgin and Child with saints; 64. *Fr. Cossa*, Madonna with St. Petronius and St. John, 1474.

Traversing the Borgo della Paglia, we next reach the *Pal. Bentivoglio* (Pl. 53; H, 3), erected by this powerful family in the 16th cent. on the site of their ancient mansion which was destroyed under Julius II. — A little to the S.W., in the PIAZZA S. MARTINO (Pl. G, 3), is situated the church of —

**S. Martino Maggiore** (Pl. 26), a Carmelite church of 1313 in the Gothic style.

1st Chapel on the left: Enthroned Madonna with SS. Rochus, Sebastian, and angels by *Francia*; 5th altar on the left, Assumption by *Lor. Costa* (?); 5th altar on the right, Madonna and saints by *Aspertini*; 4th altar on the right, SS. Joachim and Anna by *Giov. Taraschi* (1558); 1st altar on the right, *Girol. Carpi*, Adoration of the Magi.

On the N. side of the town, within the walls, and near the *Porta Galliera* which leads to the station, rises the slight eminence of **La Montagnola** (Pl. G, 1), converted during the first French occupation into a promenade, and now a favourite popular resort. Fine view of the town, with the villas on the spurs of the Apennines in the foreground. The *Giuoco di Pallone* (Pl. 76, p. 271) is situated here. In 1848 the Austrians were attacked here by the Bolognese and compelled to evacuate the town. On the S. is the *Piazza d'Armi*.

About  $\frac{1}{2}$  M. beyond the PORTA S. MAMOLO (Pl. E, 7), on the 2nd road to the right, and near the Casa Minghetti, is situated the church of *S. Maria*, called *Mezzaratta*, containing early Bolognese frescoes of little importance.

Outside the PORTA SARAGOZZA (Pl. C, 5, 6; to the left in the Via Saragozza, is the *Palazzo Albergati*, Pl. 50, by Bald. Peruzzi, 1540),  $\frac{3}{4}$  M. S. of the town, rises \***S. Michele in Bosco** (1437), once an Olivetan monastery (suppressed in 1797), now a royal chateau (*Villa Reale*). In the church are remains of frescoes by *Bagnacavallo* and others. The court is adorned with finely executed \*frescoes by the *Caracci* and their pupils, from the history of St. Benedict and St. Cecilia, but unfortunately much injured. Fine view (cab, see p. 270); attendant 1 fr.

Outside the PORTA S. ISAIA (Pl. B, C, 4), at the W. end of the town, is situated the \***Certosa** (formerly a Carthusian monastery), erected in 1335, and consecrated in 1801 as a *Campo Santo*. The route to it is by the principal road from the gate; after 9 min. a cross indicates the way to the cemetery, which is reached in 5 min. more (custodian  $\frac{1}{2}$ -1 fr.).

A visit to the Campo Santo had better, however, be combined with the ascent of the Madonna di S. Luca, which is reached by following the arcades outside the Porta Saragozza to the point where the new arcades diverging to the right lead to the Campo Santo.

The church contains a few paintings by *Sirani* and others; at the beginning of the cloisters are ancient tombstones from suppressed churches, arranged according to centuries: at the en-

trance 13th cent., then 15th on the right, 14th on the right (including monuments of professors with scenes from their lecture rooms), and 16th on the left; in the arcades modern monuments, most of them in marble. In the centre are the ordinary graves. Among many illustrious names on the former are those of the philologist *Gaspar Garatoni* (d. 1817) and the talented *Clotilda Tambroni* (d. 1817; p. 271); the principal families of the town also possess vaults here. Thus the monument of *Letizia Murat Pepoli* (d. 1859), with a statue of her father King Murat ('propugnatore dell'italica indipendenza'), executed by *Vinc. Vela* in 1855. A rotunda here contains the busts of celebrated professors of the present century, *Mezzofanti*, *Galvani*, *Costa*, *Schiassi*, *Mattei* (teacher of Rossini), etc.

On the *Monte della Guardia*, a fortified eminence outside the Porta Saragozza (Pl. B, C, 5, 6), 2 M. to the S. W. of Bologna (visible from the road to the Campo Santo on the left), rises the handsome pilgrimage-church of the \**Madonna di S. Luca*, erected by *Dotti* in 1731, so called from an ancient picture of the Virgin ascribed to St. Luke, and brought from Constantinople in 1160. Cab to the foot of the hill,  $\frac{3}{4}$  M. from the gate,  $1\frac{1}{2}$  fr.; ascent thence by the arcades  $\frac{1}{2}$  hr. These arcades, consisting of 635 arches (constructed in 1676-1739), form a passage ascending to the church of about 1 M. in length. Remarkably fine view from the summit, extending from the Apennines to the Adriatic, particularly from below the portal of the church and from the new intrenchments. The roof of the church is also an admirable point of view, but the narrow staircase without railings requires a steady head.

#### 44. From Bologna to Ravenna.

52 $\frac{1}{2}$  M. RAILWAY (belonging to the *Ferrovie Meridionale*) in 3 $\frac{1}{2}$  hrs. (fares 9 fr. 50, 6 fr. 70, 3 fr. 80 c.). The train follows the main line to Ancona and Brindisi as far as *Castel Bolognese*, whence Ravenna is reached by a branch-line.

The train follows the direction of the ancient Via *Æmilia* (p. 249), and traverses a fertile plain. To the right in the distance rise the Apennines. — 4 $\frac{1}{2}$  M. *San Lazzaro*; 7 M. *Mirandola*; 10 $\frac{1}{2}$  M. *Quaderna*; 15 M. *Castel S. Pietro*, with a château built by the Bolognese in the 13th cent., on the *Sillaro*.

21 $\frac{1}{2}$  M. *Imola* (*S. Marco*), on the *Santerno*, an ancient town with 11,000 inhab. and the seat of a bishop since 422, was the Roman *Forum Cornelii*, named after its founder L. Cornelius Sulla, but is mentioned by Paulus Diaconus, the Lombard historian of the period of Charlemagne, as *Imolæ*. After many vicissitudes the town was incorporated with the States of the Church by Pope Julius II. in 1509. Imola was the birthplace of St. Petrus Chry-



# RAVENNA


- |                                               |       |
|-----------------------------------------------|-------|
| 1 Accademia di Belle Arti                     | D.5   |
| Chiese                                        |       |
| 2 di S. Agatha                                | D.6   |
| 3 di S. Apollinare nuovo                      | E.4.5 |
| 4 Basilica di S. Gio. Evangelista             | F.4   |
| 5 - - - di S. Vitale                          | C.3   |
| 6 Battistero                                  | C.5   |
| 7 di Classe (Biblioteca)                      | D.6   |
| 8 di S. Croce                                 | C.2   |
| 9 di S. Domenico                              | C.1   |
| 10 Duomo                                      | C.5   |
| 11 di S. Eufemia                              | B.3   |
| 12 di S. Francesco                            | D.5   |
| 13 di Gio. Battista                           | D.3   |
| 14 dei SSi tino e Paolo                       | B.3.1 |
| 15 S. Circolo                                 | C.5   |
| 16 di S. Maddalena                            | D.5   |
| 17 di S. M <sup>te</sup> Maggiore             | C.3   |
| 18 di S. M <sup>te</sup> in Porto             | F.6   |
| 19 di S. M <sup>te</sup> dei Suffragi         | D.4   |
| 20 S. Michele in Affresco                     | D.1   |
| 21 di S. Nirolo                               | D.6   |
| 22 Oratorio di S. M <sup>te</sup> in Cosmedin | E.4   |
| 23 dello Spirito Santo                        | E.3.4 |
| 24 di S. Vittore                              | D.2   |
| 25 Convento di S. Chiara                      | F.5   |
| 26 Mausoleo di Galla Placidia                 | C.2   |
| 27 Monte de pietà                             | D.4   |
| 28 Ospedale Civile                            | E.4   |


## Palazzo

- |                                       |     |
|---------------------------------------|-----|
| 29 Arcivescovile                      | C.5 |
| 30 del Comune                         | D.4 |
| 31 Ginanni                            | C.5 |
| 32 Governativo                        | D.1 |
| 33 Lovatelli                          | D.6 |
| 34 - - - Dal Corno                    | D.6 |
| 35 Rasponi c <sup>te</sup> Ferdinando | D.5 |
| 36 - - - Cav. Giulio                  | C.5 |
| 37 - - - delle Teste                  | C.1 |
| 38 Spreti                             | D.3 |
| 39 di Teodorico                       | E.5 |
| 40 Seminario Arcivescovile            | C.5 |
| 41 Sepolcro di Dante                  | D.5 |
| 42 - - - Isacco Esarca                | C.3 |
| 43 Teatro Comunale Allighieri         | D.1 |
| 44 Torre del pubblico                 | D.3 |

## Alberghi

- |               |     |
|---------------|-----|
| a Spada d'Oro | D.4 |
| b S. Marco    | E.1 |







sologus, archbishop of Ravenna (d. 449), whose tomb is in the cathedral of S. Cassiano, where the remains of the saint of that name also repose. The painter Innocenzo da Imola (Francucci, b. 1506; p. 272), a pupil of Raphael, and the anatomist Vassalva were also natives of Imola. The train then crosses the *Santerno*.

26 M. **Castel Bolognese** (poor restaurant), an ancient stronghold of the Bolognese, constructed in 1380, where the Florentines under Niccolò da Tolentino and Gattamelata were defeated by the Milanese under Piccinino in 1434. — Railway journey hence to Ancona, see *Baedeker's Central Italy*.

The branch-line to Ravenna diverges here to the E., passing *Solarolo*, *Lugo*; 31 M. *Bagnacavallo* (birthplace of the painter Ramenghi, p. 272, who is generally called after his native town), *Russi*, *Godò*. Country flat and well cultivated. — 52½ M. *Ravenna*.

**Ravenna.** — **Hotels.** SPADA D'ORO (Pl. a), Strada del Monte, R. 1½-2 fr.; GRAND' ALBERGO S. MARCO (Pl. b) in the same street, well spoken of; ALBERGO DEI TRE FERRI, by the theatre, unpretending. — *Caffè* in the Piazza Vitt. Emanuele.

**Cabs:** per drive 1, at night 1½ fr., two-horse 1½ or 2 fr.; first hour 1½-2½ fr., each additional ½ hr. 75 c. or 1 fr. 25 c.; beyond the town 2 or 4 fr. per hour.

**Photographs.** *Ricci*, at Byron's house, Strada Porta Sisi 296.

**Steamboat** to Trieste once weekly (Saturd.) in 12 hrs., fare 27½ or 17½ fr.

**Principal Attractions:** Baptistery (p. 287), S. Vitale (p. 290), S. Nazario e Celso (p. 290), S. Maria in Cosmedin (p. 291), S. Apollinare Nuovo (p. 292), S. Apollinare in Classe (p. 293). — Many of the names of the streets have recently been changed, but the inhabitants adhere to the old names, which are accordingly given in our plan, and which are inscribed under the new names in the streets themselves.

*Ravenna*, a town of ancient origin, and formerly the capital of a province, with 19,000 inhab., is situated in the plain between the rivers *Lamone* and *Ronco* (Rom. *Bedesis*), in a somewhat unhealthy locality. The town is 3 M. in circumference, but nearly one-half of the area is occupied by gardens. It was originally a seaport, but is now nearly 6 M. distant from the sea. After the Porto Candiano had become choked up, the *Canale Naviglio* was constructed in 1737, in order to connect Ravenna with the sea. The present harbour of Ravenna is used for the coast-traffic only.

Ravenna is one of the most ancient towns in Italy, but under the Republic was a place of little importance. Augustus constructed the *Portus Classis* and a canal, connected with the Po, round the S. side of the town, and appointed Ravenna the headquarters of the Adriatic fleet. The commerce of the place now improved, and a new quarter was erected between the town and the harbour (*Cæsarea*, a name perpetuated by the ruined church of *S. Lorenzo in Cæsarea*). The harbour, however, having been gradually filled up by the deposits of the Po, *Classis* and *Cæsarea* fell to decay, while Ravenna continued to be the capital of the province *Flaminia*. As early as A. D. 44 Ravenna became an episcopal see, *St. Apollinaris*, a disciple of St. Peter, being the first bishop. The Emp. Honorius transferred his residence hither from Rome in 402 on account of the great strength of the place, and in



438 Ravenna was erected into an archiepiscopal see. After the fall of the Western Empire the town was taken by the Herulian *Odoacer*, king of Italy, and again in 493 by *Theodoric the Great*, king of the Ostrogoths, after which it regained much of its former splendour and was the residence of the Gothic kings till 539. It then became the seat of the exarch or governor of the Eastern Roman, or Greek Emperors, and continued under their sway until 752, when the Lombard *Aistulph* banished Eutychius the last exarch and took possession of the town. Shortly afterwards, however, Ravenna was retaken by *Pepin*, king of the Franks, and handed over to the pope, under whose rule it remained, excepting when his authority was disputed on several occasions by the Guelphs and Ghibellines. In 1275 the *Polenta* family, of whom favourable mention is made by *Dante*, obtained the supreme power. In 1318 Ravenna began to be governed by its own dukes; in 1440 it came into possession of the Venetians, under whom its prosperity materially increased; in 1509 it was conquered by Pope *Julius II.*, and it belonged to the *States of the Church* till the treaty of Tolentino in 1797. It was, however, restored in 1815, but again severed from the papal dominions in 1860.

In the History of **Early Christian Art** of the 5-8th century, Ravenna is the most important place in Italy next to Rome. Being less under the influence of the mighty traditions of the past here than at Rome, art was in a position to develop itself more freely, and even to venture on innovations. The connection of Roman and Byzantine art may best be studied at Ravenna, where the traveller will observe how the capitals of the columns were gradually remodelled, and a new style of ornamentation introduced. Besides the basilicas there are also dome-structures, which form a link between Byzantium and some of the churches of western Europe (such as the cathedral at Aix-la-Chapelle). The ancient BUILDINGS of Ravenna belong to two different periods, the first being that of Honorius and his sister Galla Placidia, 404-450 (*Cathedral, Baptistry, Archiepiscopal Chapel, S. Agata, S. Nazario e Celso, S. Giovanni Battista, and S. Giovanni Evangelista*), and the second a Gothic period from 493 to about 550 (*S. Spirito, S. Maria in Cosmedin, S. Apollinare in Classe, Mausoleum of Theodoric*). The basilicas of Ravenna differ from the Roman in having their porticoes converted into a closed anterior structure, in being destitute of transepts, in possessing columns expressly designed for their object instead of being brought from other buildings, and in showing a consistent use of the round arch with corresponding articulation on the external walls. The campanili moreover are detached and are circular in form. Notwithstanding the alterations of subsequent ages, and the raising of the pavements by several feet, which was rendered necessary by the gradually increasing elevation of the surrounding soil, these noble monuments of triumphant Christianity are profoundly impressive, and their effect is greatly enhanced by the stillness and solitude of the environs. — MOSAIC PAINTING was also extensively practised at Ravenna. The earlier symbolism was gradually abandoned for the historical Christian style, but at the same time the designs became stiff and conventional. The traveller will also have an opportunity here of examining SARCOPHAGI, IVORY CARVING, and other works of the early Christian period, and thus obtain a very comprehensive review of the art products of the centuries preceding the Carolingian era.

*Lord Byron*, who preferred Ravenna to all the other towns of Italy, and was influenced in some measure by his intimacy with the Countess Guiccioli, a member of the Gamba family of Ravenna, spent two years here, during which he wrote several of his finest works, the 'Prophecy of Dante', 'Marino Faliero', the 'Two Foscari', 'Cain', 'Heaven and Earth', and the 'Vision of Judgment'.

The \*PIAZZA MAGGIORE, now *Vittorio Emanuele* (Pl. D, 4), in the centre of the town, which is said to correspond with the ancient Forum Senatorium, is adorned with two lofty columns of granite

erected by the Venetians in 1483, and bearing statues of SS. Apollinaris and Vitalis, with a statue of Pope Clement XII. (1738), and a colonnade of eight columns of granite, supposed to have belonged to a basilica erected or restored by Theodoric. Beyond this Piazza is the —

*Piazzetta dell' Aquila* (Pl. 1; C, 4), with a granite column crowned with an eagle, erected in 1609 to Cardinal Gaetani.

The Strada del Duomo leads hence to the **Cathedral** (Pl. 10; C, 5) of *S. Orso*, or *Basilica Ursiana*, almost entirely rebuilt by Archb. Guiccioli in the 18th cent. on the site of a church of the year 400, and consisting of nave and aisles with transept, surmounted by a dome in the centre, and a round campanile.

INTERIOR. 2nd Chapel on the right: sarcophagus of SS. Exuperantius and Maximianus. In the S. TRANSEPT is the chapel of the Madonna del Sudore, containing the marble sarcophagi of SS. Barbatian (r.) and Reginald (l.) of the 6th century. The HIGH ALTAR contains a marble sarcophagus with the remains of nine bishops of early date; to the right a silver crucifix with figures of the Bishops of Ravenna, executed in the 6th century, and reliefs in the centre of the 16th cent. — In the RETRO-CHOIR, on each side, are several marble slabs with figures of animals, dating from the 6th cent., fragments of an ancient pulpit ('ambo'). — The SACRISTY contains the *Easter Calendar* from 532 to 626 and the *Ivory Throne* of St. Maximian, with bas-reliefs of the 5th and 6th cent. representing John the Baptist in the centre in front, the four Evangelists on the right and left, and the history of Joseph at the sides. The missing tablets are said to have been carried off during the wars of the 16th cent., one of them, of which a poor copy is shown, being now preserved at Florence. In the lunette above the entrance to the sacristy, to the right, \*Elijah in the desert, fed by the angel, a fresco by *Guido Reni*. The chapel of the Holy Sacrament in the N. TRANSEPT contains the \*Falling of the Manna, also by *Guido Reni*; the frescoes on the ceiling, Christ in glory, are by his pupils. In the N. AISLE is the monument of the above-mentioned Archbishop *Guiccioli*.

The \***Baptistery** (Pl. 6; C, 5), *S. Giovanni in Fonte*, or *Battistero degli Ortodossi*, adjoining the cathedral (entrance through the house of the curé, 20 c.), probably also founded by St. Ursus (d. 396), and dedicated to John the Baptist, is an octagonal structure, with two arcades in the interior one above the other. The cupola is decorated with remarkably fine \*mosaics of the 5th cent., the most ancient at Ravenna, representing the Baptism of Christ with the river-god of the Jordan and the twelve Apostles. Under these runs a broad frieze, on which, between the groups of light columns, are represented four altars with the open books of the gospels, and thrones with crosses. The upper arcades of the wall are adorned with figures of prophets, and enrichments in stucco. On the lower section of the wall are admirable mosaics. The large font in white marble is of the 5th century, with the original inscriptions of dedication inside. A niche contains a Bacchic vase. The pavement of the Baptistery is considerably raised. An ancient metal cross on the roof dates from 688.

The **Archiepiscopal Palace** (Pl. 29; C, 5), to the E. of the cathedral, possesses a square vaulted \*Chapel of the 5th cent., preserved in its original condition. The vaulting is adorned with

ancient mosaics representing saints; in the centre, on the groining, \*four angels holding the monogram of Christ; under them the four Evangelists; in the centre of the arches, Christ. The Madonna and two saints over the altar, originally in the cathedral, are of the 11th century. The ante-room contains ancient inscriptions, chiefly of the Christian period, the torso of a magistrate in porphyry, and a relief with children from the temple of Neptune. The episcopal *Archives* comprise about 25,000 documents on parchment.

On the right, at the beginning of the Strada di Classe leading to the Porta S. Mamante, is the **Accademia delle Belle Arti** (Pl. 1; D, 5; open in the forenoon only; ring at the gate, 75 c.).

The interesting PICTURE GALLERY chiefly contains pictures by masters of the place, such as a Crucifixion; Descent from the Cross, and several portraits by *Luca Longhi* (d. 1580); pictures by his son *Francesco*; a Descent from the Cross by *Vasari*; Madonna and saints by *Cotignola*; a large ancient mosaic found near Classe. — On the UPPER FLOOR a collection of casts, among them a bust of St. Apollinaris by *Thorvaldsen*; Tomestone with recumbent statue of Guidarello Guidarelli, 'guerrier Ravennate', by *Baldelli Giacomelli* of Ravenna (about 1490). Several statues from Canova's studio; Endymion, by *Canova*.

In the Strada di Classe, No. 192, is the secularised Camaldulensian Monastery of **Classe** (Pl. 7; D, 6), now occupied by the Academy. The *Biblioteca Comunale* (first floor; admission daily, 10-2, except on Sundays and holidays), founded in 1714 by the Abbate Caneti, contains upwards of 50,000 vols. and 700 MSS.

At the entrance to the library several Roman and Christian inscriptions and sculptures are built into the walls, such as a good female head, the sarcophagus of a child, with interesting representations, perhaps Christian.

Among the MANUSCRIPTS, is the celebrated MS. of *Aristophanes* of the 10th cent., one of *Dante* of 1369, another by Pietro Dante; letters of *Cicero* of the 15th cent.; commentary of *Benvenuto da Imola*; prayer-book of *Mary Stuart* with miniatures; *visitors' book from the tomb of Dante* (p. 289); the wooden coffin which contained the remains of the great poet, found in 1865 in the course of researches instituted on the 6th centenary of his birth; rare editions, such as the *Decretals of Boniface VIII.*, printed by Fust at Strassburg in 1465, and a number of 'editions principes'. There is also a small collection of objects in *ivory, bronzes, and coins* of the popes, the Medici, and the Malatesta, the *golden ornaments* of the helmet of King Odoacer (?), etc. (all shown gratuitously).

The old *Refectory* of the Camaldulensians (shown by the custodian, or by the sacristan of St. Romuald, door to the right opposite the refectory) contains the Marriage at Cana in fresco, by *Luca* and *Francesco Longhi*, and some fine carving on the door. — The altars of the monastery-church of *S. Romualdo* are richly decorated with rare and beautiful marbles; in the 2nd chapel on the left St. Romuald by *Guercino*; 3rd chapel on the left, a beautiful ciborium (with candelabrum and cross from the sacristy) in lapis lazuli, frescoes by *Longhi*.

**S. Niccolò** (Pl. 21; D, 6), built by Archb. Sergius in 760 (closed), contains numerous paintings by the Augustinian monk *Padre Cesare Pronti* and by *Francesco da Cotignola*.

**S. Agata** (Pl. 2; D, 6; entrance in the Via di Porta Sisi,

between Nos. 96 and 97), of the 5th cent., consisting of nave and aisles with a vestibule, contains fine columns of marble. No. 295 in the same street, not far from the Piazza S. Francesco, was once occupied by *Lord Byron* (p. 286), as the memorial tablet records.

**S. Francesco** (Pl. 12; D. 5) is said to have been founded by St. Petrus Chrysologus about the year 450, on the site of a temple of Neptune, but is now entirely modernised.

The INTERIOR consists of nave and aisles, with 22 columns of coloured marble. Unpleasing modern ceiling. At the entrance are several ancient tombstones; on the right that of Ostasio da Polenta of 1396; on the left that of Enrico Alfieri, who died in 1405 as general of the Franciscans. On the right the sarcophagus of the archbishop St. Liberius, of the 5th cent. The Cappella del Crocefisso, the 2nd on the right, contains two columns of Greek marble with capitals and ornamentation by *Pietro Lombardi*.

Adjoining the church is **Dante's Tomb** (Pl. 41; D. 5; closed, keys at the town-hall; but it may be seen through the gate). The poet died at Ravenna, where he enjoyed the protection of Guido da Polenta, on 14th Sept., 1321, at the age of 56, and was interred in the church of S. Francesco. In 1482 Bernardo Bembo, the Venetian governor (father of the celebrated Cardinal Bembo), caused the present mausoleum to be erected from designs by *Pietro Lombardi*, and it was subsequently restored in 1692 and 1780. It is a square structure with a dome, embellished with medallions of Virgil, Brunetto Latini the poet's master, Can Grande della Scala, and Guido da Polenta his patron; opposite the entrance is a half-length relief of Dante, and below it a sarcophagus, a marble urn in which now contains the poet's remains (originally deposited in a wooden coffin, see p. 288). It bears an epitaph attributed to Dante himself: —

*Jura Monarchiae, Superos, Phlegethonta lacusque  
Lustrando cecini, voluerunt fata quousque,  
Sed quia pars cessit melioribus hospita castris,  
Actoremque suum petiit felicior astris,  
Hic claudor Dantes, patriis extorris ab oris,  
Quem genuit parvi Florencia mater amoris.*

The visitors' book formerly kept here, and now preserved at the library (p. 288), contains the following beautiful lines (*Purg.* xi., 100), written by Pope Pius IX. when here on a visit in 1857:

*Non è il mondan rumore altro che un fiato  
Di vento ch'or va quinci ed or va quindi,  
E muta nome, perchè muta lato.*

A marble slab opposite the tomb indicates the site once occupied by the palace of Guido da Polenta.

**S. Michele in Affricisco** (Pl. 20; D. 4), erected in the 6th cent., but now destroyed with the exception of the apse and the clock-tower, still contains fragments of old frescoes.

**S. Domenico** (Pl. 9), a basilica in the vicinity, founded by the exarchs and subsequently restored, is adorned with paintings of **Niccolò Rondinelli** of Ravenna. — Near Porta Adriana is the pictur-

esque little church of *S. Giovanni e Paolo* (Pl. 14; B, 3, 4), with an ancient tower, square below, and round above. An ambo in the interior resembles that in the cathedral (p. 287).

\***S. Vitale** (Pl. 5; C, 3) was erected during the reign of Justinian by Archb. Ecclesius on the spot where St. Vitalis suffered martyrdom, and was consecrated by St. Maximian in 547. It is an imitation of the not much more ancient church of St. Sophia at Constantinople, and served in its turn as a model to Charlemagne for the cathedral of Aix-la-Chapelle. The church is octagonal (37½ yds. in diameter), with a choir, three-sided on the exterior, and round in the interior, added to it on the E. side.

The INTERIOR, unfortunately marred by modern restoration, is divided by eight massive pillars into a central space with a passage around it. Between the pillars are semicircular niches with pairs of columns and arches, in two series, one above the other, over which rises the dome, constructed of earthen vessels. Each of the windows in the dome is divided by a mullion into two round-arched halves. The lower parts of the pillars are still incrustated with their original coating of rare marble ('Africanone'). The pavement has been raised more than 3 ft., and the street is 7 ft. above the former level.

The CHOIR is adorned with admirable *Mosaics*, which are however inferior in style to those of earlier date in the baptistery (p. 287) and to those of S. Maria in Cosmedin (p. 291): Christ enthroned on the globe, angels on both sides; on the right St. Vitalis, and on the left Ecclesius with the church itself. Below, (l.) Emp. Justinian with the bishop Maximian and attendants, and (r.) the Empress Theodora with the ladies of her court, both presenting offerings. On the arch of the choir are represented Jerusalem and Bethlehem. Above, at the sides, (l.) the four Evangelists sitting, and Isaiah and Jeremiah standing, (r.) Moses as a shepherd, above which he is seen removing his sandals at the burning bush; (l.) he receives the Tables of the Law; on the right, in the central scene, an altar with bread and wine; at the sides the blood-sacrifice of Abel and the bloodless offering of Melchisedech. On the left in the centre, a table at which the three angels are entertained by Abraham, Sarah at the door, and sacrifice of Isaac. In the archway busts of Christ (repainted), the Apostles, and SS. Gervasius and Protasius, sons of S. Vitalis. On the right, at the entrance to the choir, an admirable *Greek Relief* from a temple of Neptune, representing his throne with shells, trident, and genii; opposite to it a modern copy (or perhaps also antique). — In the portico of the sacristy a *Roman Relief*, the Apotheosis of the emperor; the goddess Roma is observed sitting on the left; on the star above is Julius Cæsar, with Augustus and Claudius adjacent; on the left, a fragment of a procession with victims, forming part of the same work. Opposite are early Christian reliefs: Daniel in the lions' den, Christ imparting a blessing, and the Raising of Lazarus (7th cent.).

To the N., at the back of the church, is the *Monument of the Exarch Isaac* (Pl. 42; C, 3; d. 641), consisting of a sarcophagus in a small recess with a Greek inscription, erected by his wife Susanna. Adjacent to it are several other ancient inscriptions. On the right a Roman warrior in relief.

The custodian of S. Vitale also keeps the key of —

\***S. Nazario e Celso** (Pl. 26; C, 2), the *Mausoleum of Galla Placidia*, founded about 440 by that Empress, daughter of Theodosius the Great and mother of Valentinian III. The church is in the form of a Latin cross, 49 ft. long, 41 ft. broad, with a dome.

The INTERIOR is adorned with beautiful \**Mosaics*, on a dark blue ground, of the 5th cent.: in the dome the symbols of the four Evangelists; in the four arches eight apostles (or perhaps prophets), between which are doves drinking out of a vase (resembling the celebrated mosaic on the Capitol); under the vaulting of the right and left transept are the other four apostles (?) in gilded mosaic; between them are stags at a spring. Over the door is Christ as a young shepherd; opposite is the triumph of Christian faith, in which Christ (represented here with a beard) is committing to the flames an open book, probably heretical; the adjacent cabinet contains the gospels. — The *Altar*, constructed of transparent Oriental alabaster and intended to be illuminated by inserted lights, was formerly in S. Vitale; behind it is the large marble *Sarcophagus of Galla Placidia* (d. 450), once enriched with plates of silver, in which the Empress was interred in a sitting posture. On the right of this monument is a marble sarcophagus decorated with Christian emblems, containing the remains of the Emp. Honorius, brother of Galla Placidia; on the left that of Constantius III., her second husband (417) and father of Valentinian III.; at the sides of the entrance are two small sarcophagi containing the remains of the tutors of Valentinian and his sister Honoria. These are the only monuments of the emperors of ancient Rome which still remain in their original position.

**S. Giovanni Battista** (Pl. 13; D, 3), with an ancient round tower, erected by Galla Placidia in 438 for her confessor St. Barbatian, was almost entirely remodelled in 1683. The columns of the interior belong to the original church.

To the E. the Strada di Porta Serrata leads to the left through a gate to the Rotonda (p. 292), and to the right to the basilica of —

**S. Spirito** (Pl. 23), or *S. Teodoro*, erected by Theodorice for the Arian bishops, with a vestibule at the W. entrance (portal, 16th cent.), and adorned with fourteen columns of coloured marble in the interior. The sacristan also keeps the key of the adjacent —

\***S. Maria in Cosmedin** (Pl. 22), once an Arian baptistery. The octagonal dome was adorned with \*mosaics in the 6th cent., when it became a Rom. Cath. church. On the dome the Baptism of Christ, on the left, the river-god of the Jordan, surrounded by the twelve Apostles. The walls are covered with half obliterated frescoes of last century. The present pavement is about 7 ft. above the original level. Several Arian crosses are built into the walls of the entrance court on the left side.

**S. Giovanni Evangelista**, or *S. Giovanni della Sagra* (Pl. 4, F, 4; if closed, knock at the door), near the railway-station, erected in 444 by the Empress Galla Placidia in consequence of a vow made during a voyage from Constantinople, has also lost its ancient mosaics, and much of its interest owing to alterations. Above the \*Portal, constructed at the end of the 13th or beginning of 14th cent., are reliefs in allusion to the foundation of the church. Recent excavations have shown that the court in front of the church once formed the atrium of the edifice.

The INTERIOR, with its unpleasing barrel-vaulting, consists of nave and aisles borne by twenty-four antique columns. The vaulting of the 4th chapel is adorned with frescoes of the four Evangelists, with their symbols above them, and the four fathers of the church, SS. Gregory, Ambrose,

Augustine, and Jerome, by *GiOTTO* (who had come to Ravenna on a visit to his friend Dante). In the closed chapel to the left of the choir are some remains of old *Mosaic Pavement*, representing the storm to which Galla Placidia was exposed, on the left, and figures of animals on the right.

\***S. Apollinare Nuovo** (Pl. 3; E, 4, 5), a basilica erected about 500 by Theodoric the Great as an Arian cathedral (*S. Martinus in Coelo aureo*), was afterwards converted (570) by the Archbishop S. Agnello into a Roman Catholic church. It has borne its present name since the 9th cent., when the relics of the saint were transferred hither from Classe.

The INTERIOR contains twenty-four marble columns brought from Constantinople. On the right is an ancient ambo. The walls of the nave are adorned with interesting *Mosaics* of the 6th cent., partly of the Arian, and partly of the Rom. Cath. period, with additions of the 9th cent., afterwards frequently restored: on the left the town of Classis with the sea and ships, twenty-two virgins with the Magi (the upper half arbitrarily restored in 1846); on the right is the city of Ravenna with the church of S. Vitalis and the palace of Theodoric, and twenty-five saints with wreaths approaching Christ enthroned between angels (a group which has also been freely restored). These last mosaics betray a tendency to the showy style of the later period, but the single figures of the teachers of the church above them, between the windows, are executed in a more independent and pleasing manner. Above the windows, on the upper part of the wall, on each side are thirteen interesting compositions from the New Testament. On the left, the sayings and miracles of Christ (without a beard); on the right, the history of the Passion from the Last Supper to the Resurrection (Christ with a beard). The omission of the Crucifixion itself points to the origin of these mosaics at an early period when representations of the kind were abhorred. — In the last chapel on the left, a portrait of Justinian in mosaic, formerly outside the portal, and an ancient episcopal throne. The whole chapel is composed of fragments of ancient edifices.

In the same street, a few paces to the S. of S. Apollinare, are a few scanty remains of a wing of the *Palace of Theodoric* (Pl. 39; E, 5), in which the exarchs and the Lombard kings subsequently resided. These relics consist of a high wall crowned with eight small columns of marble bearing round arches, with a simple gateway below. The columns and treasures of art of this palace were removed to Germany by Charlemagne. To the right of the principal door, in the wall, is a porphyry vessel, probably once a bath, brought here in 1564. The palace itself perhaps stood in the adjacent Strada di Alberoni, excavations in which have brought to light rich mosaic pavements of the 5th cent.

Still farther on, near the Porta Nuova, is **S. Maria in Porto** (Pl. 18; F, 6), erected in 1553 from the remnants of the Basilica S. Lorenzo in Cesarea, consisting of nave and aisles with transept and an octagonal dome, and borne by columns and pillars placed alternately. The choir contains an ancient vase in porphyry. In the N. transept is a very ancient marble figure of the Virgin in the Byzantine style (6th cent.), brought from the church of S. Maria in Porto Fuori.

About  $\frac{1}{4}$  M. from the Porta Serrata is situated the \***Rotonda** (Pl. G, 1), the *Mausoleum of Theodoric the Great*, or *S. Maria della Rotonda*, as it was called after the remains of the emperor

were scattered and the church became a Rom. Catholic place of worship. In order to reach it, we take the road to the right, almost immediately after quitting the gate, and cross the railway, beyond which the tomb is seen to the left, shaded by poplars (key at the house, 30 c.). It was probably erected by Amalasantha, the emperor's daughter (about 530). The substructure is of decagonal shape, and the church is covered with a flat dome of 36 ft. in diameter, consisting of a single huge block of Istrian rock, which is said to weigh 470 tons. The substructure, with its ten arches, is half under water; the upper part is approached by a double staircase of marble, added in 1780. — A pleasant walk may be taken round the walls of the town, and partly upon them, as they are now nearly level with the ground. — Route to the Pineta, see p. 294.

About  $2\frac{1}{2}$  M. from the Porta Nuova is the church of **S. Maria in Porto Fuori**, a basilica with open roof, erected by Bishop Onesti (known as 'Il Peccatore'), in consequence of a vow made during a storm at sea in 1096. The left aisle contains the sarcophagus of the founder, of 1119. The choir and the two adjacent chapels contain ancient *Frescoes* from the life of Mary and the Saviour, erroneously attributed to Giotto, and now much damaged. It is supposed that this spot was formerly the site of the old harbour, and that the massive substructure of the clock-tower belonged to the lighthouse (*faro*). (A visit to this church, which however is of no great interest, and to S. Apollinare may conveniently be combined.)

No traveller should quit Ravenna without visiting the church of *S. Apollinare in Classe*, situated 3 M. from the Porta Nuova (carr. see p. 285). About  $\frac{3}{4}$  M. from the gate a small marble column surmounted by a Greek cross (*La Crocetta*) marks the site of the ancient basilica of *S. Lorenzo in Cesarēa*, the last relic of the venerable town of *Caesarea* (p. 285), which was removed in 1553. About  $\frac{1}{4}$  M. farther, the Ponte Nuovo crosses the united rivers *Ronco* and *Montone*, the confluence of which is seen higher up. (Before the bridge is crossed, a path leads to the left in 20 min. to the church of S. Maria in Porto, the lofty tower of which is seen from a distance.) The road then traverses marshy meadows to —

\***S. Apollinare in Classe**, erected in 534 by *Julianus Argentarius* on the site of a temple of Apollo, consecrated in 549, and restored in 1779. This is the most imposing of the basilicas still existing at Ravenna. It consists of a nave and aisles, with a vestibule at the W. end, and a round campanile. The exterior exhibits traces of an attempt to relieve the surfaces of the walls with pilasters and arches.

The spacious INTERIOR rests on twenty-four cipollino columns, and has an open roof. The *Walls* are adorned with portraits of bishops and archbishops of Ravenna, an unbroken series of 126, from the first bishop St. Apollinaris, who suffered martyrdom in 74 under Vespasian, to the present archbishop. Each aisle contains four marble sarcophagi of archbishops. — The CRYPT, a species of corridor in which the remains of



St. Apollinaris once reposed, is now partially under water. — Above it is the broad flight of steps leading to the 'TRIBUNA' with the high altar. The canopy of the latter is borne by four columns of black and white Oriental marble. The dome of the tribuna is adorned with well-preserved *Mosaics* of the 6th cent.: in the centre a large cross on a blue ground with gilded stars, at the sides Moses and Elias, below whom is St. Apollinaris preaching to his flock; below, on the right, are the sacrifices of Abel and Melchisedech; on the left, Constantine and other Roman emperors, among whom are the four archbishops Ursicinus, St. Ursus, St. Severus, and Ecclesius. — The ARCH of the CHOIR is also embellished with mosaics: in the centre a bust of Christ, at the sides the emblems of the four evangelists, and below them two flocks of sheep hastening to Christ from the towns of Jerusalem and Bethlehem.

The celebrated *Pine-Forest of Ravenna*, or *La Pineta*, probably the most venerable and extensive in Italy, which has been extolled by *Dante*, *Boccaccio*, *Dryden*, *Byron*, and other poets, begins a little beyond the church of S. Apollinare, and extends for many miles along the road to Rimini, as far as *Cervia*. If the traveller prolong his excursion for  $1\frac{1}{2}$  hr. beyond S. Apollinare he may drive through the nearer extremity of the forest. (The whole drive to S. Apollinare, the Pineta, and S. Maria Fuori occupies about 4 hrs.) The Pineta may be still more conveniently visited from the Rotonda by following the road leading thence by the Canal Naviglio to the cemetery ( $1\frac{1}{2}$  M.), which lies within the precincts of the forest.

About 2 M. from Ravenna, on the bank of the Ronco, rises the *Colonna de' Francesi*, a memorial of the victory gained on 11th April, 1512, by the united armies of Louis XII. of France and the Duke of Ferrara (at which the poet Ariosto was present) over the Spanish troops and those of Pope Julius II. At the moment when the victory was decided, the brave *Gaston de Foix* fell, and 20,000 men were left dead on the field.

FROM RAVENNA TO RIMINI there is a good road skirting the coast, but seldom affording a view of the sea, which is concealed by sandhills. It traverses a monotonous, flat district, passing S. Apollinare in Classe, the pine-forest, *Cervia* (a small, regularly built town), *Cesenatico*, *S. Martino*, and *Celle*, altogether 35 M., a drive of  $4\frac{1}{2}$  hrs., recommended to parties of three or four travellers together in preference to the railway (no diligence). Carr. and pair 35-40 fr.; with one horse ('perugino', a kind of gig for one traveller only with luggage) 15-20 fr.

#### 45. From Bologna to Florence.

82 M. RAILWAY in  $4\frac{1}{2}$ -6 hrs. (fares 14 fr. 20, 10 fr. 45, 7 fr. 55 c.). — A boldly constructed line. Fine views of the valleys and ravines of the Apennines (generally to the left), and afterwards of the rich plains of Tuscany.

*Bologna*, see p. 270. The train skirts the slopes of the Monte della Guardia (p. 284), near the *Reno*, which it soon crosses. On an island in the Reno, not far from Bologna, the Second Triumvirate was concerted by Octavian, Antony, and Lepidus, B.C. 43.

$4\frac{1}{2}$  M. *Borgo Panigale*; 6 M. *Casalecchio*, where the valley of the Reno contracts. Here on 26th June, 1402, the army of Giovanni Bentivoglio was defeated by Gian Galeazzo Visconti, and on 21st May, 1511, that of Pope Julius II. under the Duke of Urbino, by the French. — On the left, near (12 M.) *Sasso*, the brook *Setta* falls into the *Reno*, from which a subterranean aqueduct,

constructed by Augustus, leads to Bologna. The restoration of this channel has recently been proposed with a view to supply the town with better water. — 17 M. *Marzabotto*, with the spacious *Villa Aria*. Etruscan antiquities have been frequently found near the neighbouring village of *Misano*. Between this point and Pracchia there are 22 tunnels. At (24½ M.) *Vergato* the valley expands. 29½ M. *Riola*; on the left rise the abrupt peaks of *Monte Ovolo* and *Monte Vigese*; a landslip from the latter destroyed the village of *Vigo* in 1851. On the left bank of the Reno is the modernised castle of *Savignano*, with picturesque environs. 37 M. **Porretta** (\**Albergo Cavour*, unpretending; *Palazzino*, open in summer only), a village of 3000 inhab, with mineral springs and baths, is much frequented in summer. — Beyond Porretta the line enters a narrow and romantic ravine of the Reno, from the sides of which numerous waterfalls are precipitated, particularly in spring, and is then carried by a series of tunnels, cuttings, and viaducts to the culminating point where it crosses the Apennines. — 45½ M. *Pracchia*, the highest point on the line, is 2024 ft. above the sea-level.

A diligence runs twice daily from Pracchia to *S. Marcello* (about 2130 ft.), viâ *Pontepetri*, where it reaches the old Apennine road connecting Florence and Pistoja with Modena (p. 263). The road then continues to ascend (no regular public conveyance), partly by steep windings, to *Boscolungo* (*Pensione di Serrabassa* and *Locanda dell' Abetone*, well spoken of), about 4430 ft. above the sea-level, situated in the midst of a magnificent forest. This place has recently come into notice as a starting-point for numerous excursions: *Monte Majori*, ¾ hr.; *Libro Aperto*, 1½-2 hrs.; *Tre Potenze*, 2 hrs.; *Cimone*, 3-5 hrs.; *Rondinaja*, *Lago Santo*, etc.) and as a pleasant summer resort, and is much patronised by members of the Italian Alpine Club. — Boscolungo lies on the *Passo dell' Abetone*, which once formed the boundary between Modena and Tuscany, about 5½ hours' drive from Pracchia, and 7 hrs. from *Pistoja* (viâ *Pontepetri*, see above). A road also leads to it from *Lucca*, passing the baths (p. 317). *Fiumalbo* (p. 263) is about 9 M. distant.

Beyond Pracchia the train crosses the watershed of the Adriatic and the Tyrrhenian Sea by a tunnel about 1⅔ M. in length, and then enters the valley of the *Ombrone*, which flows towards the S., and is traversed by a lofty viaduct. Between this point and Pistoja there are numerous viaducts and no fewer than 22 tunnels. Beautiful views. — Beyond (54½ M.) *Piteccio* a view is at length revealed of the lovely and populous plains of Tuscany, and of Pistoja far below. The train then passes numerous charming villas.

61 M. *Pistoja* (p. 318). — From Pistoja to Florence, see p. 322.

The OLD ROAD FROM BOLOGNA TO FLORENCE ascends the valley of the *Savena* and passes *S. Rufilo*, *Pianoro*, *Filigare*, and *Pietramala*, which last lies in a bleak district. About ½ hr. to the E. of Pietramala are *I Fucchi*, or the burning mountain (*Monte di Fo*), the flames of which (produced by gas, as proved by Volta) produce a most striking effect, especially at night. Similar, though less imposing, is the *Acqua Buja*, ¼ hr. W. of Pietramala, with inflammable water-bubbles. From Pietramala the road ascends for 1 hr. at the base of *Monte Beni* and the *Sasso di Castro* to *Covigliajo*, at a considerable elevation; then ¼ hr. more to *La Futa*, the culminating point of the route, about 3000 ft. above

the sea-level, occasionally obstructed by snow in winter. We next descend to *Monte Carelli*, beyond which another ridge of the Apennines is traversed, and afterwards into the valley of the *Sieve*, known as the *Val di Mugello*. The road to the right leads to *Barberino* and thence to Prato (and Pistoja), that to the left to Florence. About 2 M. before Cafaggiolo is reached, the road passes *Le Maschere*, now an inn, situated in the midst of most picturesque scenery, and affording views of the Apennines and the extensive valley of the Arno.

*Cafaggiolo*, on the right bank of the Sieve. Then *Fontebuona*, beyond which the road descends rapidly; a little to the left is *Pratolino*, formerly a villa of the grand-dukes, situated in the woods. A castle once erected here by Buontalenti for Francesco de' Medici, son of Cosmo I., for the reception of his mistress Bianca Capello, has long since been destroyed. Almost the sole relic of its former splendour is the colossal stooping statue of Apenninus, 60 ft. in height. The road now descends between villas and gardens, passing Fiesole (p. 388), to Florence, which it enters by the Porta S. Gallo.

---

## VII. Tuscany.

*Tuscany*, which covers an area of 9287 sq. M., and contains 1,967,067 inhab., is divided into eight provinces of very different sizes; viz. *Massa Carrara*, 687 sq. M. in area, an independent duchy down to 1829; *Lucca*, 575 sq. M. in area, independent down to 1847; *Florence*, the largest province, 2267 sq. M. in area; *Leghorn*, the smallest, about 126 sq. M. in area; and *Pisa*, *Arezzo*, *Siena*, and *Grosseto*. The density of the population, too, varies greatly in different parts of the country. In the province of Lucca there are about 431 inhab. to the square mile, in Florence 295, in Siena 127, and in Grosseto not more than 57. With the exception of the coast districts and the valleys, the country is hilly, and intersected by the spurs and ramifications of the *Sub-Apennines*. The N. part, adjoining the *Arno*, is most fertile, the plains and slopes of the hills being richly cultivated. A strong contrast to this smiling region is presented by the marshy coast district below Leghorn, where unalignant fevers have wielded their destructive sway since the depopulation which took place in the middle ages. The soil of the inland hill country is also poor, but some compensation is afforded for this by its copper and other mines. Tuscany, indeed, possesses greater mineral wealth than any other part of Italy, and to this circumstance is due the fact that it was earlier civilised than the rest of the peninsula.

Tuscany still retains the name of its first inhabitants, the *Tusci* or *Etrusci* (Greek *Tyrrhenians*). The excellent iron of Elba and the rich copper mines of Volterra, afforded them materials for establishing thriving industries, the products of which were in demand far and wide at an early period, as for example at Athens and in Germany, where numerous discoveries of ancient Etruscan ironwork have been made. The art of navigation was simultaneously developed. The earliest naval battle in the western part of the Mediterranean handed down by tradition (about B.C. 532), was fought between the Greeks and Etruscans for the possession of Corsica, and resulted in the victory of the latter, who thus obtained supremacy over the sea still known as the Tyrrhenian. The *League of the Etruscan Towns*, which extended from the foot of the Alps to the Bay of Naples, was also instrumental in promoting civilisation, as it was the means of diffusing a knowledge of writing, as well as of the mechanical arts, and to some extent influenced even Latium and Rome itself. The Etruscan Museum at Florence first affords us an opportunity of

becoming acquainted with the artistic products of this ancient people in bronze and earthenware, and obtaining an insight into their gloomy and realistic disposition. At Fiesole our attention will then be directed to the huge stone structures erected by the Etruscans to defend their frontier against the predatory Ligurians of the Apennines. The connection between antiquity and modern times is not very apparent in this part of the country, as the classic soil of Etruria lies somewhat to the S. of the limits prescribed to the present Handbook. None of the twelve great cities which divided among them the supremacy over the whole country lay on the Arno; and the beautiful valleys which now delight the eye of the traveller, being exposed to the continual incursions of the Ligurians, were marshy and desolate down to the 3rd cent. B. C., and did not prosper till the time of the Romans. The history of the ancient Etruscans may nevertheless appropriately be kept in view. If Florence forcibly reminds the visitor at every step that modern Italy owes its noblest aspirations and richest intellectual inheritance to this city and this land, the student of history will be interested in remembering that the same office of disseminating civilisation among their compatriots was performed by the Etruscans two thousand years before the modern development of the country.

The power of the ancient Etruscans attained its zenith in the 6th cent. B.C.; but owing to the want of political coherence in their widely ramified confederation, they were unable permanently to maintain their supremacy. As the whole of N. Italy had been conquered by the Celts, and Campania by the Samnites (in 424), so the Romans and Latins from the lower Tiber gradually encroached on Etruria, and after protracted struggles wrested city after city from the confederation. In the 3rd cent. the entire country thus became subject to the authority of Rome. By the establishment of numerous colonies, and abundant grants of the Roman citizenship, the country was gradually Latinised, and the Etruscan language, which has been handed down to us in several thousand still undeciphered inscriptions, was superseded by Latin. Some of the peculiarities of the Tuscan dialect, such as the slight aspiration of the *c* before *a* (*chasa* for *casa*), are thought to be referable to the old language of the country, but this is matter of mere conjecture. The traveller acquainted with Italian will have little difficulty in understanding the people of the country, as the modern written Italian language (*lingua vulgaris*, *vulgare latinum*, *lingua toscana*) is mainly derived from the dialects of Central Italy, and particularly that of Tuscany. This language is proved to have been used as early as the 10th cent. by the educated classes, as well as Latin, but Dante and the great Tuscan poets and prose writers were the first to give it grammatical regularity and precision. Though closely allied with the popular dialect, it is by no means identical with it.

During the later imperial epoch the country formed the province of *Tuscia*, and was afterwards a Franconian county under the same name. The extensive domains enjoyed by the countess *Matilda*, the friend of Pope Gregory VII., were dismembered after her death (1115), even before which municipal liberty had begun to spring up in the towns. Among the rival communities *Pisa*, owing to its situation, attained the greatest maritime power, and like Milan, Venice, and Genoa, seemed destined to form the centre of a new state. In the 11th, 12th, and 13th centuries it was by far the most important of the Tuscan cities, and while the citizens were commemorating their victories by the erection of imposing buildings, Florence had hardly begun to exist. Florence was first indebted for its progress to the fact that it lay on the great route from the north to Rome, and commanded the passage of the Arno. Under Otho the Great many German knights settled here, and at a later period several noble families traced their origin from German ancestors. The enterprising citizens soon conquered the central and upper part of the valley of the Arno, which the situation of their town enabled them to do, and their arms were afterwards attended with farther successes. 'While the rest of Italy was gradually suffering dismemberment and throwing off the

trammels of its earlier traditions, Florence was still quietly developing her resources, and was thus soon enabled to take possession of the inheritance of the earlier culture achieved by other towns. After her extensive commerce had in a great measure raised her above the narrow aims of her ancient life, she began to suffer, like the rest of Italy, from the dissensions of a number of wild factions, but the more earnest character of the citizens enabled them more effectually to grapple with these difficulties. Florence may be said to resemble a man of unusual strength, whose physical development has been but tardy; and thus it was that she became the mistress of Tuscany'. (Leo). In 1350, among her other acquisitions, Florence gained possession of *Prato*, in 1351 of *Pistoja*, in 1406 of *Pisa*, in 1410 of *Cortona*, and in 1424 of the harbour of *Leghorn*. When at length the free constitutions of the greater part of Italy were superseded by principalities, Florence did not escape the general fate, but the change took place in the most favourable manner possible. Among all the Italian dynasties by far the first in rank was that of the **Medici**, not only owing to their munificent patronage of art and science, but to their prudent administration, their endeavours to improve the lower classes, and their care for agriculture, commerce, and the material interests of their subjects. At a later period their example was followed by the princes of *Lorraine*, and down to the present time Tuscany has enjoyed the enviable lot of being the most enlightened and civilised, and the best governed state in Italy. The fact that Tuscany unreservedly participated in the national aspirations for unity and freedom, and voluntarily recognised the hegemony of a comparatively distant and unsympathetic section of the Italian race, affords the strongest possible evidence of the earnestness of that remarkable revolution which led to the unity of Italy.

In 1530, with the aid of the arms of Emperor Charles V., the dynasty of the **Medici** was firmly established in the sovereignty of Florence. The wise Duke *Cosimo I.* (1537-64) extended his dominions considerably, particularly by the acquisition of *Siena* in 1557, which was ceded to him by the emperor. He abdicated in favour of his son *Francesco* (1564-87), who, instead of the coveted title of King obtained that of Grand Duke (*granduca*) of Florence, in 1569. *Francesco* was succeeded by his brother *Ferdinand I.* (1587-1609), who had previously been a cardinal; *Cosimo II.* (1609-24), the son of the latter, *Ferdinand II.* (1621-70), and *Cosimo III.* (1676-1723) were the next princes. With *Giovanni Gaston*, who died in 1737, the house of **Medici** became extinct. In the wars between Austria and Spain, the two great powers to which Italy was subject, Tuscany formed one of the principal objects of contention, but eventually fell to the share of the former. The emperor annexed the country as a vacant fief, and conferred it on the husband of his daughter *Maria Theresa*, the Duke *Francis Stephen of Lorraine* (1737-65), who by the Peace of *Vienna* (1735) renounced his native principality of *Lorraine* in return. In 1745 he ascended the throne of Austria as *Francis I.*, and in 1763 established Tuscany as an appanage of the second sons of the emperors, in order to prevent its being governed in future as one of the immediate dominions of Austria. He was succeeded in 1765 by the Grand Duke *Leopold*, who reigned on the same enlightened principles as his brother *Joseph II.*, and was an active reformer in the administrative, judicial, educational, and ecclesiastical departments. In consequence of the death of *Joseph II.* in 1790, *Leopold* was summoned to the throne of Austria, and his departure proved a severe loss to the duchy. His son the Grand Duke *Ferdinand III.* was obliged to renounce Tuscany by the Peace of *Lunéville* (1801), for which he received by way of compensation the Archbishopric of *Salzburg*, and afterwards *Würzburg*. Under the name of *Republic*, and afterwards *Kingdom of Etruria*, the country continued to enjoy ostensible independence down to 1807, when it was incorporated with France. In 1814 *Ferdinand II.* was reinstated, and in 1824 was succeeded by his son *Leopold II.*, who was first banished by the revolution of 1849, and finally by that of 1859. By the plebiscite of 15th March 1860, Tuscany was united to the Kingdom of Italy, then in course of formation.



# LIVORNO

1:28 000  
 0 100 200 300 400 500  
 metri



## Chiese :

- 1. Anglicana D.4.
- 2. Armeni D.2.3.
- 3. Duomo (S.Franc. d'Assisi) D.3.
- 4. Madonna DE.3.
- 5. S. Antonio D.3.
- 6. S. Giovanni D.2.
- 7. S. Gailla D.3.
- 8. S.S. Annunziata da' Greci uniti DE.3.
- 9. S. Sebastiano D.3.

## Monumenti:

- 10. Ferdinando I, detto i quattro Mori C.3.
- 11. Ferdinando III E.3.
- 12. Leopoldo II E.2.3.
- Palazzi :
- 13. Comunale D.2.
- 14. ex Reale D.3.
- 15. Larderel E.3.
- 16. Posta E.3.
- 17. Prefettura D.3.
- 18. Spedale dell'Armo D.3.

## Teatri :

- 19. da Florida (S.Marco) DE.2.
- 20. Goldoni DE.4.
- 21. Rossini D.3.
- 22. Tempio arcadico D.3.

## 46. From (*Genoa*) Leghorn to Florence by Pisa and Empoli.

STEAMBOAT FROM GENOA TO LEGHORN daily (*Società Rubattino* on Mon., Wed., and Frid.; *Florio* on Tues.; *Valéry* on Mon. and Thurs.; *Fraissinet* on Mon. and Thurs.) in 9 hrs. (fares 32 fr. 50, 22 fr. 50 c.). Most of the offices are near the quay, where the traveller should take his tickets in person. — Embarkation or landing at *Genoa* 1 fr. for each person with luggage. At *Leghorn* to or from the *Porto Nuovo* 1 fr., or with ordinary luggage 1½ fr.; to or from the *Porto Vecchio* ½ fr., or with luggage 1 fr. (Payment should be made to the official in charge.) — As the voyage is generally performed at night, the passenger loses the charming retrospect of *Genoa*, and afterwards the view of the coast.

In the reverse direction a steamer also plies daily. — Other steamers (of the above mentioned companies) run from *Leghorn* to *Civita Vecchia* and beyond it 4-5 times weekly; to *Naples* direct three times weekly (*Peirano*); to the coast towns and islands of the Tuscan archipelago (*Elba*, *Portoferraio*, *Gorgona*, *Capraia*: *Società Rubattino*), once weekly; to *Bastia* in *Corsica*, once weekly (*Rubattino*); to *Porto Torres* in *Sardinia* once weekly, to *Cagliari* once direct, and once by *Terranuova* (*Rubattino*); to *Tunis* viâ *Cagliari* once weekly (*Rubattino*).

RAILWAY from *Genoa* to *Leghorn* by *Pisa*, see p. 112; from *Leghorn* to *Rome*, see *Baedeker's Central Italy*.

**Leghorn.** — **Hotels.** "VICTORIA & WASHINGTON, on the quay and canal, expensive, R. 3-4 fr. and upwards; "HÔTEL DU NORD, refurbished, *Piazza del Cantiere* 2, R. 3, D. 5, B. 1½ fr.; HÔTEL DE NEW-YORK, *Via Vittorio Emanuele* 19, near the quay; "GRANDE BRETAGNE & PENSION SUISSE, *Via Vittorio Emanuele* 17, also near the quay, externally unattractive, R. and L. 3, D. 4½ fr. — In the *Via Vittorio Emanuele*: GIAPPONE, No. 59; LUNA, No. 42; PERGOLA, Nos. 1, 2; FALCONE, No. 62; all in the Italian style with trattorie. — Those who make a prolonged stay will easily obtain private apartments.

**Cafés.** *Vittoria, Ronzi*, both in the *Piazza d'Armi*; several others in the *Corso Vitt. Eman.* — **Beer:** *Mayer*, *Via Ricasoli* 6 and *Via del Passeggio*; *Kieffer*, *Via Larderel* 27. — **Restaurants:** *Giardinetto, Pergola*, both in the *Via Vitt. Emanuele*; *Ghiacciaio, Piazza d'Armi*.

**Post Office** at the corner of the *Corso Vitt. Emanuele* and *Piazza Carlo Alberto*. — **Telegraph Office**, *Via del Telegrafo* 2.

**Cabs.** To or from the station 1, at night 1½ fr., small articles of luggage 10, box 40 c.; per drive in the town 80 c., at night 1 fr.; outside the town 1 fr. 60 c., at night 2 fr.; night fares are charged between one hour after sunset and 5, or (from 1st Oct. to 31st March) 6 a.m.

**Reading Room.** *Gabinetto Letterario*, *Piazza d'Armi* 30, with foreign newspapers, admission ½ fr.; *Schweizer Verein*, *Via Ceccoli* 2.

**Sea Baths.** *Squarci*, with café, outside the *Porta a Mare*, bath with towels 1 fr.; *Pancaldi*, and *Ferrari & Mayer*, well fitted up, with café and a terrace with view. — **Warm Baths** in the town, *Via della Pace*, *Piazza S. Benedetto* 15, etc.

**Consuls.** American, next door to the *Victoria Hotel*; English (*Mr. Macbean*), *Via della Madonna* 12; German, *Via S. Marco* 3.

**English Church**, resident chaplain.

*Leghorn* (Ital. *Livorno*, French *Livourne*), which was a very insignificant place in the 16th cent. (in 1551 only 749 inhab.), now the capital of a province, and the most important commercial place in Italy after *Genoa*, is indebted for its size and importance to the *Medici*, who invited hither the oppressed and discontented from all parts of the continent, as, for example Roman Catholics from *England*, Jews and Moors from *Spain* and *Portugal*, and merchants from *Marseilles*, who were anxious to escape from the perils of civil



war. Montesquieu consequently calls Leghorn 'the master-piece of the dynasty of the Medici'. — The population, according to the latest census (1871) is 80,914, or, including the suburbs, 97,096 souls (many of whom are Jews), exclusive of a fluctuating sea-faring community of upwards of 3000. The town carries on a brisk trade with the Levant in cotton, wool, and unbleached silk, and with the Black Sea in grain. The most important industries are the manufacture of coral ornaments and of oil.

Leghorn, which is a well built, thoroughly modern place, containing little to detain the traveller, may be explored in a few hours. The *Harbour* is a very busy spot, and extensive new works are now in progress. The inner harbour (*Porto Vecchio*, or *Mediceo*) is too shallow to admit vessels of large tonnage; the *Porto Nuovo* was therefore constructed during the present century, to the W. of the old harbour, and protected from the open sea by a semicircular mole. Picturesque glimpses are obtained hence of the sea with the islands of Elba, Gorgona, and Capraja. An excursion by boat in the harbour will be found pleasant in fine weather (1½ fr. per hr., bargain necessary). By the harbour is the *Statue of the Grand Duke Ferdinand I.* (Pl. 10), by *Giov. dell'Opera*, with four Turkish slaves (*'I quattro Mori'*) in bronze by *Pietro Tacca*. On the pier, which is 500 yds. in length, rises the *Lighthouse* (*Faro* or *Lanterna*; Pl. B, 3), the platform of which affords a good survey of the town, harbour, and sea.

The town possesses well-paved streets and large, handsome squares. It is intersected by canals, and connected by a navigable canal with the *Arno*, the influx of which is 7 M. to the N. The *Corso Vittorio Emanuele*, the principal street (Pl. D, E, 3), contains tempting shops, where objects in coral, scagliolo (an imitation of mosaic), Oriental shawls, etc., may be purchased at reasonable prices. It leads from the harbour to the spacious *Piazza d'Armi* (Pl. D, 3), in which the cathedral, the town-hall, and a small royal palace are situated. It proceeds thence to the *Piazza Carlo Alberto* (Pl. E, 3), adorned with colossal *Statues of Ferdinand III.* (d. 1824) and *Leopold II.*, the last but one, and the last grand-duke of Tuscany respectively. The original inscription on the latter was replaced in 1860 by another to the effect that the 'dinastia Austro-Lorenese si è resa assolutamente incompatibile con l'ordine e la felicità della Toscana'. — The large *Synagogue* (Pl. 22), founded in 1581, dates in its present form from 1603.

**WALKS.** Pleasant grounds to the S., outside the *Porta a Mare*, and along the coast by the road to *Ardenza*; also in the *Giardino dei Bagni* (adm. 50 c.), in the same neighbourhood, where a band plays every evening during the bathing-season (*Caffè*). Farther on are the sea-bathing establishments mentioned at p. 299, and beyond them *Ardenza*, with numerous villas. Comp. Plan B, 4, 5.

## FROM LEGHORN TO FLORENCE.

60½ M. RAILWAY in 2¾-3½ hrs.; fares 10 fr. 55, 7 fr. 20 c., 5 fr. (express 11 fr. 10, and 7 fr. 80 c.); to Pisa, 11 M., in 25 min.; fares 2 fr. 5, 1 fr. 90 c., 1 fr.

The train crosses the Arno Canal and traverses flat meadowland, intersected by canals and occasionally relieved by pines.

11 M. *Pisa*, see p. 302.

The railway next traverses a beautiful and fertile district on the left bank of the Arno, running parallel to the high road. To the left are the *Monti Pisani* (p. 311) with the ruined castle on the Verruca. — 16 M. *Navacchio*; 19½ M. *Cascina* on the Arno, where on the festival of S. Vittorio, 28th July, 1364, the Pisans were defeated by the Florentines. — 24½ M. *Pontedera*, a small town at the confluence of the *Era* and Arno, where the road through the beautiful valley of the *Era* to *Volterra* diverges (diligence, see *Baedeker's Central Italy*).

26 M. *La Rotta*; 31 M. *S. Romano*. — 35 M. *S. Pierino* and **San Miniato dei Tedeschi**; the latter, a small town, raised by Emp. Frederick II. in 1226 to the dignity of seat of the imperial governor, lies to the right on the height. The *Cathedral*, dating from the 10th cent., was remodelled in 1488, and embellished with statues in 1775.

41 M. **Empoli** (*Albergo del Sole*) is a small town in a fertile district. In 1260, after the defeat of the Florentines on the Arbia, the Ghibellines proposed to transfer the seat of government hither and to raze Florence to the ground. This project, however, was strenuously opposed by the heroic *Farinata degli Uberti*, an incident beautifully recorded by Dante in the 10th canto of his *Inferno*. The town is a busy place with old houses and narrow streets, and a *Church* of 1093, containing good pictures by *Lorenzo Monaco*, *S. Botticelli*, *Francesco di Giovanni*, *Cigoli*, and others, and a fine *Baptistry* of 1447.

RAILWAY TO SIENA AND ORVIETO, towards the S., see *Baedeker's Central Italy*.

The train then crosses the small river *Pesa*. On the left, before reaching *Montelupo*, we perceive the *Villa Ambrogiana*, erected by *Ferdinand I.* on the site of an ancient castle of the *Ardinghelli*, and surmounted by towers and pinnacles. 45 M. *Montelupo*; the castle of this place was fortified by the Florentines in 1203 in order to keep in check the hostile *Capraja* on the opposite side. Hence the appellation *Montelupo*, 'mountain of the wolf', which was desirous of devouring the goat (*capra*).

The train now crosses the Arno, and slowly winds through the defile of the *Gonfolina*, through which the Arno flows. The heights are clad with rock-pines, below which is quarried the *pietra serena*, a kind of sandstone frequently employed in the construction of the palaces of Florence. At the extremity of the *Gonfolina* the line crosses the *Ombrone*, which falls into the Arno, and traverses a

vine-clad district to (52 M.) the old borough of *Signa*, with its grey towers and pinnacles, founded in 1377 by the Florentines to command the road at this point. This place, as well as the opposite village of *Lastra*, is noted for its straw-plait. — Near (54 M.) *S. Donnino* is *Brozzi*, with numerous villas which proclaim the proximity of the capital. The train now approaches the *Cascine*, the park of Florence, and enters the station near *S. Maria Novella*. 60½ M. *Florence*, see p. 323.

#### 47. Pisa.

**Arrival.** The *Station* (see lower side of Plan) is on the S. side of the town, and on the left bank of the Arno. Travellers intending to visit the cathedral and its environs only, leave their luggage at the station, and, disregarding the importunities of the bystanders (guide quite unnecessary), proceed on foot, or by fiacre (1 fr.) to the *Piazza del Duomo* (shortest route across the new *Ponte Solferino*).

**Hotels.** *Near the Station:* \**LA MINERVA*, with garden, R. 3, B. 1½, A. ¾ fr.; *HÔTEL DE LONDRES*, at the corner of *Via S. Antonio* and *Via S. Cassiano*, with a large garden, expensive. *WASHINGTON*, R. 2, A. ½ fr., and *HÔTEL DE LA VILLE*, R. 2½, A. ½ fr., both with trattorie, less pretending. — *On the Lung-Arno, N. side:* \**GRAN BRETAGNA* (Pl. e), near the new *Ponte Solferino*, halfway between the station and the *Piazza del Duomo*, expensive; *GRAND HÔTEL LUNGARNO* (Pl. a; formerly *Peverada*), R. and L. 4, D. 3, B. 1½ fr.; \**HÔTEL ROYAL VICTORIA* (Pl. b), these two also of the first class, near the *Ponte di Mezzo*. — *EUROPA* (Pl. f), *Lung-Arno Mediceo* 1, commercial; *ROMA*, *Via Vittorio Emanuele*, R. 1½-3 fr.; *NETTUNO* with \**Trattoria*, in the *Lung-Arno Regio*; *LA PERGOLA*, *Via del Borgo*, near the *Ponte di Mezzo*, small. — \**PENSION of Sofia Ludwig*, *Palazzo Bagnoni*, *Lung-Arno Mediceo*, about 8 fr. per day.

**Restaurants.** \**Railway Restaurant*; also at the *Nettuno*, and most of the other hotels.

**Cafés.** *Ciardelli*, *Burchi*, *Ussero*, all in the *Lung-Arno, N. side*.

**Cabs.** *With one horse:* to or from the station 1 fr., trunk according to size 10-30 c.; per drive in the town 80 c.; first ½ hr. 1 fr., each additional ½ hr. 70 c. Outside the town (within a distance of 2 M.), per drive 1 fr. 60 c., first ½ hr. 1 fr. 40 c., each additional ½ hr. 80 c.; at night 20 c. more for each ½ hr. *With two horses*, one-third more.

**Post Office** (Pl. 51) on the left bank of the river, below the *Ponte di Mezzo*.

**Physicians.** *Drs. Feroci* and *Fedeli*.

**Photographers.** *Huguet & Van Lint*, *Lung-Arno Reale*.

**Baths.** *Bagni Ceccherini*, *Lung-Arno, N. side*, near *Ponte Mare*.

**English Church Service** in winter and spring.

The *Casino dei Nobili*, to which strangers provided with an introduction are admitted, contains Italian and French newspapers. Balls and concerts in winter.

The *Climate* is mild and humid, and Pisa is a well known wintering place for patients suffering from asthma, pneumonia, pleurisy, and other pulmonary complaints. The mean winter temperature is about 4½° lower than that of the Riviera, and during the five winter months there are on an average 62 days of rain, and one of snow. The best apartments are on the N. side of the *Lung-Arno*, that part of which between the *Ponte di Mezzo* and the *Ponte Solferino*, called *Lung-Arno Reale*, is the sunniest. The *Lung-Arno Mediceo* is less favorably situated. The rents of furnished rooms are highest in October, after which they gradually fall. The average rent of a single room is 2-2½ fr. per day, but many landlords decline to let their rooms except for the whole



Stradone delle Cascate

1  
2  
3  
4  
5  
6  
7



- Alberghi**
- a Poverada D.4
  - b Vittoria D.4
  - e Gran Bretagna C.5
  - f Europa E.4
  - l. Piazza delle Vetto  
raglie D.4



# PISA.

- 1 Accademia di Belle Arti D.3  
 2 Antica Fortezza F.7  
 3 Arcivescovato C.1  
 4 Bogno di Serone D.1  
 5 (Cabinetto Patologico }  
 Sprdali Riuniti } B.2  
 6 Clinica Fisica C.3  
 7 Collegio e Seminario. E.1

## Conventi di Fratri

- 8 S. Antonio C.D.7  
 9 il Carmine D.6  
 10 S. Francesco E.F.3  
 11 S. Niccola C.4  
 12 S. Torpè D.1

## Chiese


- 13 S. Andrea F.E.4  
 14 S. Appollonia D.2  
 15 Battistero B.1  
 16 Campo santo B.1  
 17 S. Caterina E.2  
 18 Cavalieri di S. Stefano D.3  
 19 S. Cecilia E.3  
 20 S. Cosimo e Damiano C.5  
 21 S. Cristina D.4.5  
 22 Duomo e Campanile B.1  
 23 S. Erediano D.3  
 24 Inglese B.5  
 25 S. Maddalena D.5  
 26 S. Maria della Spina C.5  
 27 S. Maria F.4  
 28 S. Martino E.6  
 29 S. Michele E.4  
 30 S. Paolo all'Orto E.3  
 31 S. Paolo à Ripa d'Orto B.6  
 32 S. Pierino E.4  
 33 S. Ranierino B.C.1  
 34 S. Sebastiano D.5  
 35 S. Sepolcro E.5  
 36 S. Sisto C.3  
 37 Giardino botanico, Storia Naturale } C.3  
 38 Liceo, Giannasio E.1  
 39 Municipio, Dogana } D.5  

### Monasteri

 40 S. Anna D.2  
 41 S. Benedetto B.6  
 42 Le Cappuccine E.6  
 43 S. Chiara B.2  
 44 S. Domenico D.7  
 45 S. Matteo F.4.5  
 46 S. Silvestro G.5  

### Palazzo

 47 alla Giornata C.D.1  
 48 Pretorio E.5  
 49 Reale C.4  
 50 Vitelli C.4  
 51 Posta delle Lettere D.4.5  
 52 Teatro Duomo C.1  
 53 dei Rivaranti C.1  
 54 Torre della Fame D.2.3  
 55 Guelfa e Ghibl. A.6  
 56 Tronelli C.2  
 57 Ufficio de' Fossi D.5  
 58 Università e Biblioteca C.D.1





winter. Living at an hotel is of course more expensive (pension 9-12 fr. per day), but the visitor is more independent. The best situated hotels are the Lungarno, the Vittoria, and the Gran Bretagna. As the Lungarno is the chief centre of society in winter, invalids are recommended not to take rooms at a distance from it.

*Pisa*, a quiet town with 25,000 inhab. (incl. suburbs 50,000), the capital of a province, is situated 6 M. from the sea, on both banks of the *Arno*. It was the *Pisae* of the ancients, and once lay at the confluence of the Arnus and Auser (*Serchio*), which last now has an estuary of its own.

*Pisa* became a Roman colony in B.C. 180. Augustus gave it the name of *Colonia Julia Pisana*, and Hadrian and Antoninus Pius erected temples, theatres, and triumphal arches here. At that period the town must have been a place of considerable importance, but all its ancient monuments, with the exception of a few scanty relics (p. 311) have disappeared. At the beginning of the 11th cent. *Pisa* attained the rank of one of the greatest commercial and seafaring towns on the Mediterranean, and became a rival of Venice and Genoa. It was chiefly indebted for its power to the zeal with which it took the lead in the wars against the Infidels. In 1025 the Pisans expelled the Saracens from Sardinia and took permanent possession of the island. In 1030 and 1089 they again defeated the Saracens at Tunis, and in 1063 destroyed their fleet near Palermo. In 1114 they conquered the Balearic Islands, and soon afterwards took a prominent part in the Crusades. In the 12th and 13th centuries their power had reached its zenith; their trade extended over the entire Mediterranean, and their supremacy embraced the Italian islands and the whole of the coast from La Spezia to Civit  Vecchia. In the intestine wars of the peninsula *Pisa* was the most powerful adherent of the Ghibellines, and therefore sustained a severe shock through the downfall of the Hohenstaufen. The protracted wars which the citizens carried on with Genoa led to their disastrous defeat at Meloria near Leghorn on 6th Aug. 1284 (p. 84), and the peace concluded in 1300 compelled them to evacuate Corsica and other possessions. In 1320 the pope invested the kings of Arragon with Sardinia, and *Pisa* was thus deprived of this important island also. The city was farther weakened by internal dissensions, and fell a victim to the ambition of the condottieri. In 1406 it was sold to Florence, but on the arrival of Charles VIII. endeavoured to shake off the yoke of its arrogant neighbour. In 1509, however, it was besieged and again occupied by the Florentines, to whom it thenceforth continued subject.

In the **History of Art** *Pisa* occupied an important position at an early period, but was obliged to yield up its artistic precedence earlier than its political to the more fortunate Florence. The progress of art at *Pisa* was more rapid than in the rest of Tuscany, owing perhaps to the influence of its numerous and handsome ancient monuments, as Roman forms repeatedly recur in the buildings. With the foundation of the CATHEDRAL of *Pisa* began the dawn of medi val Italian art. This church is in the old basilica style, but with the not unimportant innovation of having a dome over the centre of the cross. The magnificent building operations of the Pisans continued throughout the whole of the 12th cent., and terminated with the erection of the charming church of S. Maria della Spina (1230), and that of S. Caterina (1253). In the 13th cent. *Pisa* was also important as a cradle of SCULPTURE, and gave birth to *Niccol  Pisano*, a precursor of the Renaissance. Under what influences *Niccol * was trained is uncertain, but there is a marked difference between his works with their somewhat antique cast, and those of his Pisan predecessors (such as the bronze door of the cathedral by *Bonannus*). His successors *Giovanni* and *Andrea Pisano* adhered to his style, or at least to the spirited character of his designs. *Pisa* also boasted of possessing PAINTERS at an early period. The name of *Giunta Pisano* (first half of the 12th cent.), for example, was known far beyond the limits of the town, but his works are uninteresting, except to the student of art.



The fact that *Cimabue* was invited from Florence to embellish the apse of the cathedral, indicates the decline of native art, the development of which appears to have ceased entirely in the 14th cent. The execution of the frescoes in the Campo Santo was committed exclusively to foreign artists, not indeed to Giotto himself, as Vasari asserts, but to his pupils and to Sieneese masters. *Buffalmacco*, the jester among the Italian painters, who is not a merely mythical personage, as has been supposed, is said to have assisted in executing the frescoes in the Campo Santo, but to what extent is unknown. In the 15th cent. *Benozzo Gozzoli* (1420-97) of Florence, a pupil of Fra Angelico, spent 16 years at Pisa, where the Campo Santo is graced by his most important work.

The busiest part of the town and chief resort of visitors is the **Lung' Arno**, a broad and handsome quay extending along both banks of the river, throughout the whole length of the town. On the N. and more sheltered side, and particularly on the Lung-Arno Regio or Reale (Pl. C, D, 4), are situated the principal hotels and cafés. The far-famed illumination here (*La Luminara*) takes place on 17th June, every three years, and the Carnival is also celebrated here. The Lung-Arno, with its prolongation outside the Porta alle Spiagge (*Passeggiata Nuova*), is much frequented in the evening. Churches and buildings in the Lung-Arno worthy of note, see p. 311. — The river is crossed by three bridges, besides the railway-bridge. That in the centre is the *Ponte di Mezzo* (Pl. D, E, 4); above it is the *Ponte alla Fortezza* (Pl. F, 5); and below it the *Ponte Solferino* (Pl. B, C, 5), completed in 1875, and forming the shortest route between the railway station and the Piazza del Duomo.

The chief boast of Pisa is the \*\*PIAZZA DEL DUOMO (Pl. B, 1), to which every visitor first directs his steps. The *Cathedral*, the *Leaning Tower*, the *Baptistery*, and the *Campo Santo* situated here, form a group of buildings without parallel, especially as it is situated beyond the precincts of the town and therefore removed from its disturbing influences.

The \*\**Cathedral* (Pl. 22), erected after the great naval victory of the Pisans near Palermo (1063) by *Busketus* and *Rainaldus* in the Tuscan style, and consecrated by Pope Gelasius II. in 1118, is a basilica with nave and double aisles, and transept flanked with aisles, 104 yds. in length, and 35½ yds. in breadth in the interior, and covered with an elliptical dome over the centre. This remarkably perfect edifice is constructed entirely of white marble, with black and coloured ornamentation. The most magnificent part is the façade, which in the lower story is adorned with columns and arches attached to the wall, and in the upper parts with four open galleries, gradually diminishing in length. The choir is also imposing. The ancient *bronze-gates* were replaced in 1602 by the present doors, with representations of scriptural subjects, executed by *Mocchi*, *Tacca*, *Mora*, and others, from designs by *Giovanni da Bologna*. The only one of the old doors now existing is the *Crociera di S. Ranieri* in the S. aisle, by *Bonannus* (12th cent.), representing 24 scriptural scenes.

The **Interior** (usually entered by the last mentioned door on the E. side, opposite the Campanile) is borne by 68 ancient Roman and Greek columns captured by the Pisans in war. (The capitals are now covered with stucco.) The nave has a flat coffered ceiling, richly gilded, the aisles are vaulted, and above them run triforia which cross the transept to the choir. On 15th Oct., 1596, the dome and the whole church, with the exception of the choir, were seriously injured by fire, but were subsequently restored. Many traces of the restoration are observable in the interior.

**NAVE.** Most of the tombstones formerly here have been removed to the Campo Santo. A few still remain by the W. WALL, on the right and left of the principal entrance, among them that of Archb. Rinuccini (d. 1582), by *Tacca*, and that of Archb. Giuliano de' Medici (d. 1660). On the pillar to the right of the door an old fresco of Christ and the Maries by *Bernardo Falconi*. The designs of the twelve altars are attributed to *Mich. Angelo*, the execution to *Stagi da Pietra Santa*. The large altar-pieces are by *Lomi*, *Allori*, *Passignano*, *Salimbeni*, and other masters of the 16th cent.; the intervening pictures are of the 17th and 18th centuries. — **PULPIT** adorned with lions and evangelists by *Niccolò Pisano*. The swaying of the bronze lamp which hangs in the nave is said first to have suggested to Galileo the idea of the pendulum. On the last pillar of the nave on the right, St. Agnes, by *And. del Sarto*. Opposite is a Madonna by *Perino del Vaga*.

**RIGHT TRANSEPT:** 1st altar on the right, Madonna, by *Perino del Vaga* and *Sogliani*. Above the *Cappella di S. Ranieri*, which contains a sarcophagus by *Foggini*, is a Madonna in mosaic, by a follower of Cimabue; the relief on the niche and the statues by *Francesco Mosca* (about 1600). A niche adjoining the chapel on the right contains an ancient statue of Mars, commonly revered as St. Ephesus. The Madonna and Child which adorn the basin for holy water at the entrance were designed by *Michael Angelo*.

The **CHOIR** contains finely carved stalls, with apostles, landscapes, animals, etc., attributed to *Giuliano da Majano*. The two angels in bronze on the right and left are by *Giovanni da Bologna*. The high altar, overlaid with marble and lapis lazuli, dating from 1774, was restored in 1825. Above it, Christ on the Cross, by *Giovanni da Bologna*. The two episcopal thrones are by *Giov. Batt. Cervellesi* (1536), the six reliefs by masters of the school of Giovanni Pisano. On the arch of the choir, angels by *Dom. Ghirlandajo*, unfortunately much retouched. The mosaics in the dome (Christ between Mary and St. John) are by *Cimabue* (begun about 1302). Of the pictures in the choir, SS. Margaret and Catharine on the right in front of the high altar, and SS. Peter and John on the left, by *And. del Sarto*, are worthy of inspection; beyond the high altar, Abraham's Sacrifice, and Entombment by *Sodoma*; the four Evangelists by *Beccafumi*. The capitals of the two porphyry columns on the right and left, with figures of children, are by *Stagi*, the designs being attributed to Michael Angelo.

**LEFT TRANSEPT.** Over the *Cappella del SS. Sacramento*, the Annunciation in mosaic by a follower of Cimabue. The altar, richly decorated with silver by *Foggini*, was presented by Cosmo III.; behind it, Adam and Eve, a basrelief by *Mosca*, by whom the other statues were also executed.

The **\*Baptistery** (Pl. 15; *Battistero*), begun in 1153 by *Diotisalvi*, but according to the inscriptions not completed till 1278, and with Gothic additions of the 14th cent., is also entirely of marble. It is a beautiful circular structure (33½ yds. in diameter), surrounded by half-columns below, and a gallery of smaller detached columns above, and covered with a conical dome (190 ft. high, restored in 1856). It has four entrances; at those on the N. and E. are sculptures in marble of the 12th century.

The **INTERIOR** rests on eight columns and four pillars, above which there is a simple triforium (restored); in the centre is a marble octagonal *Font*, admirably adorned with rich sculpture and mosaic, and standing on raised ground, and the famous hexagonal *\*Pulpit*, borne by seven

columns, by *Niccolò Pisano*, 1260; the reliefs (comp. p. 308) on the pulpit are: (1) Annunciation and Nativity; (2) Adoration of the Magi; (3) Presentation in the Temple; (4) Crucifixion; (5) Last Judgment; (6) Allegorical figures; in the corners the apostles. — Fine echo.

The **\*Campanile**, or clock-tower, begun by the architects *Bonannus of Pisa* and *William of Innsbruck* in 1174, and completed by *Tommaso Pisano* in 1350, rises in eight different stories, which like the Baptistery are surrounded with half-columns and six colonnades. Owing to its remarkable oblique position, 13 ft. out of the perpendicular (height 179 ft.), it is usually known as the **Leaning Tower**. The question whether this peculiarity was intentional or accidental has frequently been discussed. The most probable solution is that the foundations settled during the progress of the structure, and that, to remedy the defect as much as possible, an attempt was made to give a vertical position to the upper part. Galileo availed himself of the oblique position of the tower in making his experiments regarding the laws of gravitation. The **\*View** from the platform, embracing the town and environs, the sea to the W., and the mountains to the N.E., is very beautiful; a good staircase of 294 steps leads to the top. Permission is only accorded to a party of not fewer than *three*, but if necessary the custodian (50 c.) will provide a third person (15-20 c.). The tower contains seven bells, the heaviest of which, weighing 6 tons, hangs on the side opposite the overhanging wall of the tower.

The **\*\*Campo Santo** (Pl. 16), or *Burial Ground*, was founded by Archb. Ubaldo, 1188-1200 (open daily from morning till dusk; visitors knock at the door to the left;  $\frac{1}{2}$  fr. to the custodian on leaving). After the loss of the Holy Land the archbishop conveyed 53 ship-loads of earth hither from Mt. Calvary, in order that the dead might repose in holy ground. The structure which surrounds the churchyard was begun in 1278 by order of the senators of the city, and completed in 1283 by *Giovanni Pisano*, in the Gothic-Tuscan style. It is 138 yds. in length, 57 yds. in width, and 48 ft. in height. Externally there are 43 flat arcades resting on 44 pilasters, the capitals adorned with figures. Over one of the two entrances is a marble canopy, with a Madonna by *Giovanni Pisano* (?). In the interior there is a spacious hall, the open, round-arched windows of which, with their beautiful tracery, 62 in number, look upon a green quadrangle. Three chapels adjoin the Campo; the oldest is to the right of the entrance, in the centre of the E. side, with dome of later date. The walls are covered with **\*Frescoes** by painters of the Tuscan school of the 14th and 15th centuries, below which is a collection of Roman, Etruscan, and mediæval sculptures, these last being important links in the history of early Italian sculpture. The tombstones of persons interred here form the pavement.

**Paintings.** To the right of the chapel, on the E. WALL: Ascension, the

doubting Thomas, Resurrection, and Crucifixion, by a follower of Giotto, supposed to be *Buffalmacco*, end of 14th century.

On the S. WALL: "Triumph of Death, represented as filling with horror those who are devoted to earthly joys, but as welcome to the miserable and self-denying (on the left an admirable equestrian group, who on their way to the chase are suddenly reminded by three open coffins of the transitoriness of human pleasures). The "Last Judgment (attitude of the Judge celebrated), attributed by Vasari to *Andrea Orcagna*, and Hell, the next picture, attributed by the same authority to *Bernardo*, Andrea's brother, have been pronounced by modern investigators not to be the works of these masters. — Next is the life (temptations and miracles) of the holy hermits in the Theban wilderness, by *Pietro* and *Ambrogio Lorenzetti* of Siena (about 1340; the two preceding paintings perhaps by the same masters). — Between the two entrances, the life of St. Ranieri, the tutelary saint of Pisa; the three upper scenes (conversion from a worldly life, journey to Palestine, victory over temptation, retirement to a monastery) completed by *Andrea da Firenze* in 1377 (erroneously attributed to Simone Memmi and others); the three lower and better executed scenes (return from Palestine, miracles, death, and removal of his body to the cathedral of Pisa, the last much injured) were painted by *Antonio Veneziano* about 1386. — Then, above, scenes from the life of St. Ephesus (who as a Roman general, fighting against the heathens, receives a flag of victory from the Archangel Michael, but is afterwards condemned and executed); below, scenes from the life of St. Potitus, admirably portrayed by *Spinello Aretino* about 1390, but now almost obliterated. Next, the history of Job, by *Francesco da Volterra* (erroneously attributed to *Giotto*), begun in 1371, a vigorous work, but in bad preservation.

On the W. wall no paintings of importance.

On the N. WALL the history of the Genesis: first the Creation (God the Father holding the world in both hands, "il mappamondo"); then in the upper series, Creation of man, the Fall, Expulsion from Paradise, Cain and Abel. Building of the ark, Deluge, and Noah's Sacrifice, by *Pietro di Puccio* of Orvieto, about 1390 (erroneously attributed to *Buffalmacco*). — The lower series and all the following paintings on the N. wall are by *Benozzo Gozzoli* of Florence, 1469-85, twenty-three "representations from the Old Testament, admirably executed 'a tempera': Noah's vintage and drunkenness (with the '*Vergognosa di Pisa*', or scandalised female spectator), the Curse of Ham, the Tower of Babel (with portraits of celebrities of that period, Cosmo de' Medici, his son Pietro, and his grandsons Lorenzo and Giuliano), the history of Abraham, Isaac, Jacob and Esau, Joseph, Moses and Aaron, Fall of the walls of Jericho, history of David, Solomon and the Queen of Sheba; this last much injured. *Benozzo* himself was interred below the history of Joseph.

**Sculptures and Monuments.** S. SIDE. In the left corner 152, 153. Inscriptions in honour of Caius and Lucius Caesar, grandsons of Augustus. — XI. Roman sarcophagus with the rape of Proserpine, on which is placed a fine head of M. Agrippa in basalt. — V. Early Christian sarcophagus with a representation of the Good Shepherd (2nd or 3rd cent.). — 14. Column with mutilated statue of the Madonna, of the later period of the *School of Giovanni Pisano*. — VIII. Fragment of a sarcophagus with fine Bacchanalian representation. — To the right of the entrance, AA. "Monument of the oculist *Andrea Vacca* (d. 1826) by *Thorvaldsen*, Tobias curing his father's blindness. — 33. Madonna and Child with six saints, below them the history of Christ by *Tommaso Pisano*. CC. Tombstone of Count Algarotti (d. 1764), erected by Frederick the Great. — In front of the last, 47. Caritas, above the four cardinal virtues, by *Giovanni Pisano*.

W. END. 7. Ancient palm frieze with dolphins and tridents. — XI. Large ancient bath, latterly used as a sarcophagus. — 45. "Virgin and Child by *Giovanni Pisano* (mutilated). — 46. Monument of Count della Gherardesca (14th cent.). — Memorial tablets of the Pisans who fell in 1848 in the battles for the independence of Italy. — GG. Monument of the Emp. Henry VII. of Luxembourg, protector of Pisa as a partizan of the Ghibellines (d. 1313 at Buonconvento), of the school of *Giovanni Pisano*,

the apostles on the sarcophagus by *Tino di Camaino*. — In front of it a statue of Giovanni Pisano, by *Salvini*. — On the wall above, the chains of the ancient harbour of Pisa, captured by the Genoese in 1632; parts of them were given to the Florentines, who suspended them at the entrance of the Baptistery at Florence, but were restored to the Pisans in 1848; the second chain was restored to them by the Genoese in 1860. — XII, XIII. Two Roman sarcophagi with Etruscan cinerary urns placed on them. — Bust of Cavour by *Duprè* of Florence. — LL. Sarcophagus of Bishop Ricci (d. 1418), of the earlier Pisan school. — 50. Madonna attributed to *Orcagna*. — 52. On a broken column, a marble vase with fine Bacchanalian representation. — QQ. Tomb of the fabulist Prof. Lor. Pignotti (d. 1812).

N. SIDE. 57. Large Greek relief from a tomb. — XIV. Roman sarcophagus. — 62. Virgin and Child by *Giovanni Pisano*. — 76. Madonna in terracotta by the *Robbia*. — The chapel contains remains of a large fresco from the church del Carmine at Florence, which was destroyed by fire, attributed to *GiOTTO*. — On the left the tombstone of Ligo degli Ammanati (d. 1359). — Farther on, 78. Beautiful head of a young Greek, perhaps Achilles. — 83. Head of Pluto. — XIX. Sarcophagus with Bacchanalian scene, upon it the bust of Isotta of Rimini by *Mino da Fiesole*. — XX. Sarcophagus with the procession of Bacchus. — XXI. Sarcophagus with the myth of Hippolytus and Phædra, from which, according to Vasari, Niccolò Pisano copied several figures for his pulpit; the remains of the Countess Beatrix (d. 1076), mother of the celebrated Matilda, were subsequently deposited here. — XXV. Sarcophagus with children gathering fruit. In the chapel the tombstone of Cardinal Maricotti (d. 1345). — 98. Several Egyptian antiquities. — XXIX. Bacchanalian sarcophagus with the myth of Actæon on the cover. — 135. Sitting statue, supposed to be the Emp. Henry VII., surrounded by four of his counsellors. — XXX. Sarcophagus with the hunt of Meleager. — XXXII. Sarcophagus with a battle of barbarians. — XXXIII. Sarcophagus with a representation of the nine Muses.

E. END. 134. Griffin in bronze with Coptic inscriptions. — Sarcophagus of Ph. Dezio (d. 1535) by *Stagi*. Statue of Leonardo Fibonacci by *G. Paganucci*. — 136. Pedestal with the seven arts, bearing a saint with a pair of scales, by *Giovanni Pisano*. — Monument of Count Mastiani, with the sitting statue of his inconsolable widow, by *Bartolini*, 1842. — Beyond it the large monument of Gregory XIII. (d. 1585). 139, 141. Etruscan altar with rams' heads at the corners. — Monument of the singer Angelica Catalani (d. at Paris 1849), by *Costoli*. — Statue of Niccolò Pisano by *Salvini*. — By the inner wall of the passages are a number of Roman and rude early Christian sarcophagi (e.g. LXXVI. and LXXVII.). — In the open space between the arcades two antique fountain-spouts.

A visit to the Campo Santo by moonlight is very impressive (notice must be given to the custodian previously).

The traveller will hardly care to devote much time to the other works of art at Pisa, but he will be amply rewarded by taking a short walk through the town in order to obtain an idea of the extent to which building enterprise was carried at Pisa in the middle ages.

The central part of ancient Pisa, and the forum of the republic, is now the PIAZZA DEI CAVALIERI (Pl. D, 3), formerly *degli Anziani*, which was remodelled in the 16th and 17th cent. In this piazza rises —

**S. Stefano ai Cavalieri** (Pl. 18), the church of the knights of the Order of St. Stephen, begun from designs by *Vasari* in 1565; interior completed 1596; façade designed by *Buontalenti*. It contains Turkish trophies on the right and left of the door, and ceiling-paintings of the battle of Lepanto (1571) and other victories over the Turks, by *Cristoforo Allori*, *Jacopo da Empoli*, and others.

On the 2nd altar to the left a Nativity by *Alessandro Allori*: 'Quem genuit adoravit', a finely conceived work, 1564. Excellent organ.

The *Palazzo Conventuale dei Cavalieri*, adjoining the church, altered by *Vasari*, is now a school; above the door are busts of six masters of the order; in front of the building a marble *Statue of the Grand-Duke Cosmo*, designed by Giambologna and executed by Francavilla (1596). Opposite to it once stood (down to 1635) the ill-famed 'Tower of Hunger', properly *Torre dei Gualandi alle Sette Vie*, in which Archb. *Ruggieri degli Ubaldini* caused Count *Ugolino dei Gherardeschi* with his sons and nephews to be starved to death in 1288 as a punishment for treason, as described by Dante in the 33rd canto of his *Inferno*.

The neighbouring church of **S. Sisto** (Pl. 36; C, 3) was erected by the Pisans to commemorate several of their victories on the day of S. Sisto, 6th Aug., 1089. It contains a number of ancient columns of marble and granite. The church was frequently used as a place of assembly by the Great Council of Pisa.

On the right, in the VIA S. FREDIANO (No. 972), leading from the Piazza dei Cavalieri to the Arno, is the —

**Accademia delle Belle Arti** (Pl. 1; D, 3), founded by Napoleon, and containing a collection of pictures, chiefly of the earlier Pisan and Florentine schools. The arrangement is completed in a few of the rooms only.

I. ROOM. *Umbrian School*, S. Agnella; *Sodoma*, Madonna enthroned and saints (from the church of S. Maria della Spina); *School of Fra Angelico*, Madonna; *Ambrogio d'Asti*, God the Father and angels; Byzantine Madonna. — II. ROOM. *Beccafumi*, Birth of John the Baptist; *Fra Angelico* (?), Angels; *Tempesti*, Portrait of himself. — III. ROOM. *Zenobio Macchiavelli*, Madonna and four saints; *Giunta Pisano*, Crucifix, interesting on account of the old view it contains of the cathedral and its environs; *Paolo Uccello*, Triumphant procession of an emperor; *Orcagna* (?), Four saints; *Tommaso* (1366), Christ on the Cross, Mary, and the Magdalene; St. Catharine, with a view of the city by a Dutch master of the 15th cent. (wings by a different hand). — IV. ROOM. *Traini*, St. Dominic; *Giottino* (school of Giotto), Annunciation, Crucifixion, and St. Ursula; *Ambrogio d'Asti* (1514), Christ, Madonna, and angels; *Fra Filippo Lippi* (?), Madonna, two angels, and four saints; *Benozzo Gozzoli*, Madonna and four saints; *Deodatus Orlandi* of Pisa, Madonna and four saints (1301); *Barnaba da Modena*, Madonna enthroned (1370); *Cimabue*, Madonna (wings still in the Byzantine style). — Another room contains the sketches of the pictures in the cathedral. — The HALL contains a Coronation of the Madonna by *Gentile da Fabriano* (?). — LAST ROOM. *Benozzo Gozzoli's* cartoon of the 'Queen of Sheba's visit to Solomon' in the Campo Santo; a small Madonna in the style of Andrea del Sarto; several works by *Benozzo Gozzoli* and *Botticelli*; Adoration of the Magi by *Cigoli*.

Farther on are *S. Frediano* (Pl. 23), with ancient columns in the interior, and the University (p. 310).

In the N.E. QUARTER of the town the churches of S. Caterina and S. Francesco deserve notice.

**S. Caterina** (Pl. 17; E, 2), which was erected about 1253, possesses an interesting Pisan façade in the Gothic style.

INTERIOR. To the left of the entrance the monument of Archbishop Simone Saltarelli, by *Nino Pisano*, 1342. Altar-piece (3rd on the left) of

St. Thomas Aquinas, with his glory, by *Francesco Traini*, 1341. In the 1st chapel to the right of the choir, a *Madonna* with SS. Peter and Paul by *Fra Bartolommeo* and *Mariotto Albertinelli*.

The church stands in a pleasant piazza, shaded with plane-trees, and embellished with a *Statue of the Grand Duke Leopold I.* (d. 1792), in Roman garb, by Pampaloni, erected in 1832.

**S. Francesco** (Pl. 10; E, F, 3) contains frescoes in the choir by *Taddeo Gaddi* (1342). Its cloisters are richly embellished with columns dating from the close of the 15th cent. Handsome campanile.

In and near the LUNG-ARNO are several other interesting buildings with which we may terminate our walk. In the Via del Borgo, close to the Ponte di Mezzo (p. 304), rises —

**S. Michele in Borgo** (Pl. 29; E, 4), a church in the Gothic style of the 13th cent., which is said to have been designed by *Niccolò Pisano* (but more probably by his pupil *Fra Guglielmo*), with an ancient crypt, supposed to occupy the site of a heathen temple.

In the Lung-Arno Mediceo (to the E. of the Ponte di Mezzo) is the *Palazzo Lanfranchi* (now *Toscanelli*), attributed to *Michael Angelo*, and occupied by Lord Byron in 1822.

In the Lung-Arno Regio (to the W. of the Ponte di Mezzo) rises the *\*Palazzo Agostini*, a fine Gothic brick edifice of the 15th cent., on the ground-floor of which the Caffè dell' Ussero is now established. — (Opposite to it, on the left bank of the river, is the Loggia de' Banchi; p. 311.)

Farther on is the *Palazzo Lanfreducci* (Pl. 47), now *Uppexinghi*, designed by *Cosimo Pagliani*, with the fragment of a chain over the entrance, with the motto 'alla giornata'. It contains a small collection of pictures (including *Guido Reni's* 'Divine and Earthly Love') which are offered for sale.

To the N. rises **La Sapienza** (Pl. 58; D, 4), or the *University*, a large edifice of 1493, extended in 1543, with a handsome Renaissance court. The *Library* contains 50,000 vols. and several valuable MSS. (including the famous Statuto di Pisa, or fundamental law of the city).

The University, mentioned in history as early as the 12th cent., and extended by Cosmo I. in 1542, is now provided with a staff of about 60 professors, and attended by 600 students. The celebrated *Galileo* was appointed professor of mathematics here in 1610. — Connected with the university are the *Museum of Natural History*, founded in 1590, chiefly illustrative of the ornithology and geology of Tuscany, and the *\*Botanical Garden* (both in the Via S. Maria, Pl. 37; C. 3), one of the oldest in Italy, founded in 1544, remodelled in 1563 by the celebrated *Cesalpino*, and transferred in 1595 to the present site, which was laid out by *Giuseppe Benincasa*.

**S. Nicola** (Pl. 11; C, 4), founded about the year 1000 by Count Hugo of Tuscia as a Benedictine Abbey, has an obliquely placed *Campanile*, which contains an admirable winding staircase ascribed to *Niccolò Pisano*. — The Piazza in front of the church is adorned

with a *Statue of Ferdinand I.*, 1595, by a pupil of Giambologna.

On the LEFT BANK OF THE ARNO is situated —

\***S. Maria della Spina** (Pl. 26; C, 5), so called from a fragment of the veritable 'Crown of Thorns' preserved here, an elegant little church in the French Gothic style, erected in 1230 by the senate and the noble families Gualandi and Gattosi, for sailors about to go to sea. It was enlarged in 1323, and adorned with sculptures by pupils of *Giovanni Pisano* and by *Nino*, the son of *Andrea Pisano* (key kept at the opposite house, No. 22). The church is now undergoing restoration.

Passing the new *Ponte Solferino* (p. 304), we proceed towards the *Porta a Mare*, at the end of the town, near which rises —

\***S. Paolo a Ripa d'Arno** (Pl. 31; B, 6), dating from the 12th or 13th cent., with a fine façade embellished with three rows of columns, the finest at Pisa after that of the cathedral. The interior is adorned with badly preserved frescoes of 1400.

Near the *Ponte di Mezzo* (see above, and p. 304; Pl. D, 4) are situated the *Loggia de' Banchi* (Pl. 39), erected in 1605 by *Buontalenti*, now the corn-exchange, and the handsome *Palazzo del Comune* (Pl. 39; formerly *Gambacorti*). The latter contains the newly arranged *Archivio di Stato*, or the city archives, which occupy ten rooms, and comprise 15,994 parchment charters (one granted by *Frederick Barbarossa* in 1162, one by *Richard Cœur de Lion* in 1192, and others of very early date; catalogue kept by the custodian).

The octagonal church of *S. Sepolcro* (Pl. 35; E, 5), dating from the 12th cent., is now entirely restored. — A house on the *Lung-Arno Galileo*, farther on, bears a tablet recording that the great astronomer *Galileo Galilei* was born there (in 1564, d. 1642).

The only relics of ancient *Pisae* are remains of baths (*Bagni di Nerone*) near *Porta Lucca* (Pl. D, 1). The house where they are to be seen is indicated by an inscription.

**Environ.** Outside the *Porta Nuova*, between the *Maltraverso Canal* and the right bank of the *Arno*, about 1½ M. in the direction of the sea, is situated the *Cascine S. Rossore*, a farm founded by the *Medici*, with fine plantations of pines, now a royal shooting-lodge.

On the coast, about 1½ M. farther, lies *Il Gombo*, an unpretending sea-bathing place, commanding a beautiful view. The poet *Shelley* was drowned here on 7th July, 1822. His friend *Byron* afterwards caused his remains to be burned, and the ashes deposited near the pyramid of *Cestius* at *Rome*.

The *Monti Pisani*, a range of hills to the E., are very picturesque; among them, about 5 M. from the town, in the *Valle dei Calci*, lies *La Certosa*, or the *Carthusian Abbey*, a fine structure of the year 1367, with church and cloisters, restored in 1814. — To the right above it is *La Verruca*, a mountain 1765 ft. above the sea-level, crowned with ruins of a castle of the 15th cent. and commanding a delightful prospect.

About 3 M. S.W. of *Pisa*, on the old post-road to *Leghorn*, to the right of the railway, in the direction of the *Arno* and opposite *S. Rossore*, is situated the ancient basilica of \***S. Pietro in Grado**, erected before the year 1000, containing beautiful antique columns and capitals, occupying the spot, according to tradition, where *St. Peter* first landed in Italy. It was



formerly much frequented as a pilgrimage-church. The faded paintings in the interior are of the 14th cent. The ancient estuary of the Arno, with the harbour of Pisa, must once have been at this spot, before the present coast was formed by alluvial deposits.

#### 48. From Pisa to Florence by Lucca and Pistoja.

61 M. RAILWAY in 4½ hrs.; fares 8 fr. 65, 5 fr. 95, 4 fr. 15 c.

The line intersects the fertile plain between the Arno and Serchio. — 3¾ M. *Bagni di San Giuliano*, at the base of the *Monti Pisani*, known to the ancients as *Aquae Calidae Pisanorum*, are much frequented in summer. *Il Pozzetto* is the warmest spring (104° Fahr.), *Bagno degli Ebrei* the coolest (82°). Many Roman antiquities have been found here.

At (5½ M.) *Rigoli* the line approaches the *Serchio*, and beyond (8 M.) *Ripafratta* describes a complete semicircle round the beautifully formed *Monte S. Giuliano*, which, as Dante says (*Inferno*, xxxiii. 30), prevents the two towns of Pisa and Lucca from seeing each other. — 13 M. *Lucca*.

---

**Lucca.** — °CROCE DI MALTA (Pl. a; C. 2, 3); °L'UNIVERSO (Pl. b; D. 3); CAMPANA, or POSTA (Pl. c; C. 3); ALBERGO & °TRATTORIA CORONA, in the Via Pozzotorelli, near the Piazza Grande.

*Lucca*, formerly the capital of the duchy of that name, with 21,000 inhab. (incl. suburbs, 63,000), is an antiquated place situated in a fertile plain, with well-preserved fortifications, and many interesting churches. '*Lucca l'industriosa*' is noted for its silk factories, a branch of industry introduced from Sicily in the 14th cent., and also for its woollen goods. The Oriental *fez* is largely manufactured here and exported to the Levant. Lucca is one of the pleasantest provincial towns in Italy.

Lucca (Roman *Luca*) was founded at a very remote period. It first belonged to Liguria, afterwards to Etruria, and became an important municipium. In B. C. 56, *Julius Caesar*, who was then governor of Gaul, held a conference here with Pompey and Crassus, with whom he had been associated since B. C. 60, in order to discuss a plan for the administration of the Roman empire for the ensuing five years. The splendour of Lucca at that period is still indicated by the remains of the Roman °*Amphitheatre* near S. Frediano. After the fall of the Roman Empire, Lucca belonged successively to the Goths, Lombards, and Franks, then became a duchy, and in the 12th cent. a republic. The feuds of the Guelphs and Ghibellines impaired the strength of the place so seriously that in 1314 it was compelled to succumb to *Ugguccione della Faggiuola* of Arezzo, the warlike governor of Pisa. Dante resided with his friend Ugguccione at Lucca in 1314, and there became enamoured of the youthful *Gentucca* (*Purgatorio* xxiv. 23), but he does not describe the inhabitants in very flattering terms (*Inferno* xxi. 41). After the expulsion of Ugguccione, Lucca fell in 1325 into the hands of the powerful *Castruccio Castrani degli Interminelli* of Lucca, who was also master of Pisa and Pistoja. On 23rd Sept. 1325 he defeated the Florentines at Altopascio, and in 1327 was nominated imperial governor of Tuscany by Emp. Lewis the Bavarian. On his death in 1328 the power of Lucca declined; its next master was *Martino della Scala*; it subsequently came into the possession of Pisa, but in 1369 purchased its own freedom from Charles IV. for

# LUCCA.

## Chiese:

- 1. Duomo S. Martino B. 3.
- 2. S. Frediano D. 2.
- 3. S. Francesco E. 2.
- 4. S. Giovanni D. 3.
- 5. La Madonna (cappella) C. 1.
- 6. S. Michele D. 2.
- 7. S. Paolo C. 2.
- 8. S. Romano C. 3.
- 9. S. Luce D. 2.
- 10. Palazzo pubblico C. 3.
- 11. Teatro del Giglio D. 3.
- 12. Pifferaio D. 3.


## Monumenti:

- 13. Maria Luisa C. B. 3.
- 14. Bartolacci D. 2. 3.
- 15. Carlo III B. 3.

## Alberghi:

- a. Croce di Malta C. 2. 3.
- b. Universo D. 3.
- c. Campana o Posta C. 3.

1:27000  
 0 100 200 300 400 500 Metri





300,000 fl., and remained independent till the invasion of the French in 1799. In 1805 Napoleon gave Lucca as a principality to his sister *Elisa Bacciocchi*; in 1814 it came into the possession of the dukes of Parma of the house of Bourbon, who in 1847 ceded it to Tuscany.

In the HISTORY OF MEDÆVAL ARCHITECTURE, Lucca, like Pisa, occupied an important position at a very early period. The churches of *S. Frediano* and *S. Michele* were both founded upwards of a thousand years ago, though probably little now remains of the original edifices. The columns in *S. Frediano*, like those of the early Christian basilicas of Rome, are antique. The taste for building, probably stimulated by rivalry with Pisa, was again revived in the 12th cent., when the older churches were altered and restored, doubtless in accordance with Pisan models. — Towards the end of the 15th cent., *Matteo Civitali* (1435-1501), one of the most pleasing sculptors of the early Renaissance, resided, and produced numerous works, at Lucca. His style somewhat resembles the best pictures of that period, and, though full of life, is of a graceful and gentle character, contrasting especially with Donatello. — The pictures of *Fra Bartolommeo* in the cathedral and *S. Romano* (the latter now removed to the Palazzo Pubblico) are also worthy of notice.

Immediately on quitting the station, we perceive within the ramparts, to the right, the handsome —

\**Cathedral of S. Martino* (Pl. 1; D, 3), erected in 1060-70 in the Romanesque style by Bishop *Anselmo Badagio* (afterwards Pope Alexander II.), but afterwards frequently restored, with a sumptuous façade added by *Guidetto* in 1204, and an impressive choir. The vestibule contains sculptures of the beginning of the 13th cent. representing the history of St. Martin. Over the small door is St. Regulus on the right, and a \*Descent from the Cross on the left by *Niccolò Pisano* (? 1233). The church is entered by three doors of carved wood, that in the centre being the finest.

The INTERIOR, in the form of a Latin cross, with nave and aisles 91 yds. in length, transept 39, and nave 28 yds. in width, has a clerestory (with large windows and rich tracery) over the aisles and carried across the transept, which it also intersects longitudinally (transept apparently narrower than projected); and it received various Gothic additions in the 14th cent., especially in the arches of the transept. Above the aisles are galleries. The old frescoes on the vaulting were restored in 1858.

The stained glass in the side windows is modern, those in the choir by *Pandolfo di Ugolino da Pisa*. — 1st Altar on the right, Nativity by *Passignano*; 2nd, Adoration of the Magi, *F. Zuccherò*; 3rd, Last Supper, *Tintoretto*; 4th, Crucifixion, *Passignano*; \*Pulpit by *Matteo Civitali* (1498). — In the SACRISTY a \*Madonna with SS. Clement, Peter, Paul, and Sebastian, with predella by *Dom. Ghirlandajo*. — \**La Croce dei Pisani*, beautifully executed in 1350 by *Bettuccio Baroni*, in silver, gilded, originally belonged to the Pisans, but was carried off by the inhabitants of Lucca (not shown except by special permission, to be procured on the previous day).

The RIGHT TRANSEPT contains the beautiful marble \*monument of *Pietro a Noceto*, secretary of Pope Nicholas V., by *Matteo Civitali* (1472); by the same master, on the wall to the right, is the portrait of Count Domenico Bertini (1479); also in the following CAPPELLA DEL SACRAMENTO (enclosed by a railing) two \*angels in an attitude of adoration and (adjoining the choir) the \*Altar of St. Regulus, with St. Sebastian and John the Baptist and beautiful basreliefs (1484). To the left of the choir the 'ALTAR OF LIBERTY', which Lucca recovered in 1369 from Emp. Charles IV. (inscription: *Christo liberatori atque diviti tutelaribus*), with a Resurrection by *Giambologna* (1579). On the wall St. Petronilla, by *Daniele da Volterra*. In the following CAPPELLA DEL SANTUARIO, a Madonna with SS. Stephen and John by *Fra Bartolommeo* (1509). The decorations of the pilasters are by *Civitali*. — The LEFT TRANSEPT contains the \*Sarcophagus of *Ilaria del Carretto* (d. 1405), by *Jacopo della Quercia*.

In the NAVE is °IL TEMPIETTO, a small octagonal chapel of marble, partially gilded, erected in 1484 by *M. Civitali*, and containing the *Volto Santo di Lucca*, an ancient crucifix in cedar-wood, said by tradition to have been made by *Nicodemus*, and to have been transferred in a miraculous manner from the Holy Land to Lucca in 782. It is shown publicly three times a year only. The embroidery on the red curtain is a faithful copy of the sacred relic behind it. In front of the entrance is suspended a candelabrum of solid gold, 24 lbs. in weight, presented by the inhabitants of Lucca in 1836, when the approach of the cholera was dreaded. On the opposite side a statue of St. Sebastian, also by *Civitali*.

In the LEFT AISLE, 5th altar (from the entrance), Visitation of the Virgin, by *Jacopo Ligozzi*. — Over the 2nd altar, Presentation in the Temple, by *A. Allori*. On the left of the entrance, Descent from the Cross, and St. Nicodemus carving the *Volto Santo*, frescoes by *Cosimo Roselli*. On the pavement of the nave, inlaid work of coloured stones, representing Solomon's Judgment.

At the back of the cathedral is the *Archiepiscopal Palace*, and beyond it the small Gothic chapel of *Sta. Maria della Rosa* (1333).

**S. Giovanni** (Pl. 4; D, 3), near the cathedral, is a basilica of the 12th cent., with aisles and transept. The façade is modern, with the exception of the portal, over which there is a relief of the Madonna with the Apostles of the 12th cent., and groups of animals on the right and left. In the interior the flat coffered ceiling is supported by ten columns, of which the shafts and some of the capitals are probably ancient. In the left aisle a monument to *Giov. Farina* (d. 1847). — Adjoining the left transept is a venerable *Baptistry*, the roof of which was renewed during the Gothic period.

A few paces from this church is the **PIAZZA GRANDE** (Pl. C, D, 3), where a *Monument* by *Bartolini* was erected to the Duchess Marie Louise in 1843, in recognition of the service rendered by her to the town in constructing an aqueduct in 1823-32.

In this piazza is situated the **Palazzo Pubblico** (Pl. 10; C, 3), formerly *Ducalé*, begun in 1578 from designs by *Ammanati*, but still incomplete. On the first floor is a *Picture Gallery* (open daily 10-2, closed on Sundays and festivals).

I. Room: 7. *Guido Reni*, Crucifixion; 20. *Tintoretto*, St. Mark releasing a slave; 22. *Tintoretto*, Portrait; 29. *Borgognone*, Battle; 34. *Marco di Tiziano*, Madonna with Christ and St. Catharine; °39. *Fra Bartolommeo*, Madonna della Misericordia, with portraits of the Moncalieri family, of 1515 (formerly in S. Romano); 44. *Andrea del Sarto*, Holy Family (replica in the Palazzo Pitti); 50. *Ligozzi*, Madonna appearing to S. Dominicus; °59. *Fra Bartolommeo*, God the Father with Mary Magdalene and St. Catharine of Siena. 1509 (formerly in S. Romano); 72. *Sodoma*, Christ. — II. Room: 1. *Domenichino*, Samson; 8. *Bronzino*, Portrait; 13. *Tintoretto*, Portrait. — III. Room: 3. *Beccafumi*, Moderation of Scipio; *Vasari*, 6. St. Eustace; 7. Mary treading serpents under her feet; 8. St. Blaise. — The other rooms contain modern pictures by *Michele Ridolfi* (of Lucca, d. 1853), *Nocchi* (Aurora), *Giovannetti*, *Camuccini*, and others.

Not far from the Piazza Grande (in the Via della Rotonda, the first side-street to the right) is the church of *S. Alessandro*, a simple structure completed before 1080, with fine antique columns. — A little farther on, also in the Via della Rotonda, at the end of the street diverging to the left opposite the 'Croce di Malta' hotel, is situated —

**S. Romano** (Pl. 8; C, 3), which existed as early as the 8th cent., but was remodelled in bad taste in the 17th by *Vincenzo Buonamici*. At the back of the high altar is the monument of St. Romanus, with a Pietà above, and a recumbent figure of the saint below, with painted armour, by *Matteo Civitali*.

We now return to the Piazza Grande, and proceed to the left to the venerable church of —

**S. Michele** (Pl. 6; D, 6), founded in 764 by Teutprandus and his wife Gumpranda, with an over-decorated façade of 1288, rising high above the nave, and surmounted by a figure of the angel with brazen wings. The row of columns on the S. side was added in 1377. 1st Altar on the right: Madonna in Trono by *Fra Filippo Lippi*. — The *Palazzo Pretorio*, in the style of the 15th cent., is also situated in the Piazza S. Michele. — Opposite the S. side of the church rises the statue of *F. Burlamacchi* (d. 1548), by Cambi, erected in 1833.

On the N. side of the town is situated —

\***S. Frediano** (Pl. 2; D, 2), a basilica of the 7th cent., founded by the Lombard kings Bertharic and Cunibert, in honour of St. Frigidianus, an Irishman, who was bishop of Lucca in 560-78. The present façade was erected in the 12th cent. on the site of the former apse; the Ascension in mosaic of the same period with which it is adorned was restored in 1827. The nave was originally flanked with double aisles, the outer of which have been converted into chapels. Most of the 22 columns are ancient.

The **CAPPELLA DI S. AGOSTINO** (2nd to the left) contains two old frescoes by *Amico Aspertini*, a pupil of Francia, judiciously retouched by *Michele Ridolfi*. On the ceiling God the Father, surrounded by angels, prophets, and sibyls; in the lunette to the left the Entombment; below it, to the left, an image of Christ found in the sea (*Volto Santo*, p. 314), drawn by two oxen, to the right St. Augustine, baptised by St. Ambrosius at Milan. In the lunette on the wall, on the right, St. Augustine instructing his pupils, and presenting them with the rules of his order; below, to the left, the Nativity and Adoration of the Magi; on the right, S. Frigidiano miraculously checking an inundation of the sea. — In the **CAPPELLA DEL S. SACRAMENTO** (4th to the left), an altar with a Madonna and four saints in relief by *Jacobus magistri Petri de Senis* (*Jacopo della Quercia*?) (1422). Opposite, over the altar to the right behind the pulpit, is the Coronation of Mary; below are king David and Solomon, St. Anselm, and St. Augustine, by *Francesco Francia* (covered). At the foot of the picture are four scenes from the history of the Augustinian Order. The 2nd chapel on the right from the entrance contains the tomb of St. Zita, the patroness of Lucca, mentioned by Dante (*Inferno* xxi. 28); in the church, in front of the chapel, is the ancient font, with unexplained representations by *Magister Robertus* (1151); by the wall is the more modern font by *Matteo* or his brother *Niccolò Civitali*; at the back of the first, Annunciation, heads of angels, children, and rich garlands by the *della Robbia*. On the wall of the entrance, to the right of the door, a Madonna and Child by *Amico Aspertini*; to the left, the Conception by *Rid. Ghirlandajo*, both *al fresco*.

We now cross the Piazza S. Frediano, which adjoins the church on the E., and turning either to the right or left reach an entrance to the *Piazza del Mercato* (Pl. D, 2), the houses enclosing which are built upon the foundations of a Roman Amphitheatre

dating from the early Imperial period. Two series of the arcades, of 54 arches each, are still visible on the outside; length 135 yds., width 105 yds.; the arena (the present market-place) 87½ by 58 yds. — Remains of an ancient theatre are also shown near the church of *S. Maria di Corte Landini*.

To the E. is situated *S. Francesco* (Pl. 3; E, 2), erected in 1442, containing the monuments of the poet Giov. Guidiccioni (16th cent.) and the celebrated Castruccio Castracani (d. 1328). It is now used as a military magazine.

Among the numerous charitable institutions of Lucca may be mentioned the *Deposito di Mendicizia* (poor-house), established in the Italian-Gothic *Palazzo Borghi*, with a lofty tower, erected in 1413 by *Paolo Guinigi*, chief of one of the most powerful families of Lucca. — Of the *Libraries* the most interesting are the *Archiepiscopal*, containing 20 valuable MSS. and 400 rare editions, the *Library of the Chapter* with about 500 MSS., and the *Biblioteca Reale* with MSS. (including Latin poems of Tasso, written by his own hand) and early specimens of printing. The *Archives* are also very valuable.

A spare hour should be devoted to a \*WALK ON THE RAMPARTS, which afford a succession of pleasant views of the town with its numerous towers, and of the beautiful mountains in the vicinity. In the grounds on the S. side is the monument of *Charles III. of Spain* (Pl. 15; B, 3), erected by his grand-daughter the Duchess Marie Louise, in 1822. A little to the E. of it is a pleasant café (Pl. C, 4).

The ENVIRONS of Lucca are beautiful, and many of the pleasant villas are comfortably furnished for the reception of strangers, but in summer the country is hot and destitute of shade.

The traveller should visit the (3 M.) royal \**Villa di Marlia*, with its beautiful grounds, fine points of view, and fountains, resembling Marly at Paris (whence the name), and with a Greek chapel containing old paintings, etc. (permission must be obtained at Lucca). The road thither leads by the Porta S. Maria (see below).

On the road to Viareggio, about 6 M. to the W., near the *Lake of Massaciuccoli*, are situated the Roman ruins known as the \**Bagni di Nerone*, with beautiful environs. — The *Aqueduct* to the S. of Lucca, with its 459 arches, recalling the Campagna of Rome, is worthy of notice.

About 15½ M. to the N. of Lucca, in a hilly district, lie the BATHS of LUCCA (diligence from June to September several times daily in 2½ hrs., fare 3 fr.; carr. in 2 hrs., fare 15 fr.). We quit the town by the Porta S. Maria (Pl. E, 1). The excellent road was constructed by the Princess Elisa. A road to the right diverges to the Villa Marlia (see above). Farther on we reach the *Serchio*, a stream which is generally very low in summer, but sometimes swells to a violent torrent, and is confined by embankments for a long distance. The road ascends the left bank of the stream, and passes the village of *Moriano*. We now traverse charming hill country, passing the opposite villages of *Val d'Ottavo*, *Diecimo*, and *Borgo a Mozzano*. Immediately above Borgo is the bridge *della Madalena*, which is said to have been built in 1322 by Castruccio; it is sometimes called the *Ponte del Diavolo*, from the peculiarity of its construction, and is hardly practicable for carriages. About 1 M. beyond it the road enters the valley of the *Lima*, another stream which is nearly dry in summer, and which is crossed near *Farnoli* by a suspension bridge

constructed in 1860. Between this point and the baths there are roads on both banks of the river.

The **Bagni di Lucca**, which were known in the middle ages, with springs varying in temperature from 86° to 129° Fahr., consist of several different villages in the valley of the *Lima*, connected by shady walks, and containing 9200 inhab. PONTE A SERRAGLIO, the chief of these villages, which we reach first, is picturesquely situated on the bend of the rivulet, and contains the post-office, and the best hotels, baths, and lodging-houses. (° *Pagnini's Hôtel d'Europe et d'Amérique*, R. 3, D. 4, L. and A. 1½, pension 8 fr.; ° *Pera's Hôtel New York*, and *Grand Hôtel des Bains de Lucques*, formerly Croce di Malta, similar charges; ° *Corona*, unpretending, *Cafés Posta* and *Italia*, in the Piazza del Ponte. *Casino*, with billiard, reading, and ball rooms. *Physicians*, Dr. Giorgi, and Dr. Marchi. *Chemist*, Pellegrini. Shops poor.) Adjoining the Hotel Pagnini on the *Lima*, is the royal casino *Ridotti*. A little farther on, at the entrance to the side valley, is the *Nuovo Ospedale*, built by Prince Demidoff.

Beautiful avenues ascend gradually from the Ponte a Serraglio to the villages of *VILLA* (1 M.; Betti, English chemist), and *BAGNI CALDI* (¾ M.; pleasant apartments; physician, Prof. Carina of Pisa). — To the baths of Lucca belong also the establishments of *Bernabò* (comfortable; named after an inhabitant of Pistoja cured here in the 16th cent.), *Docce Bassi*, and *S. Giovanni*. The quietest and pleasantest apartments are to be hired at the *Bagni alla Villa*.

The valley of the *Lima* is cool and well shaded, chiefly with chestnut trees, and is a healthy summer residence, affording pleasant walks. Beautiful excursions may also be taken among the mountains, such as to the village of *Lugliano*, and to the watch-tower of *Bargilio* (on donkey-back; fatiguing), which on clear days commands an extensive view over land and sea. — *Boscolumgo* (p. 295) may be reached hence in about 6 hrs.

The RAILWAY TO PISTOJA at first traverses the plain to the E.; a little to the S. lies the *Lago di Bientina*. 19 M. *Porcari*; 22 M. *Altopascio*; 25 M. *S. Salvatore*.

27½ M. *Pescia* (Posta), a small town, situated about 1½ M. to the N. on the river of that name, which the railway crosses, in a beautiful district, with silk and paper manufactories. The *Cathedral* of *Pescia* has remains of a façade of 1306 and a fine monument of Baldassare Turrini by *Raffaele da Montelupo*, a pupil of Michael Angelo.

30 M. *Borgo a Bugiano*; 32 M. *Monte Catini*, where Uggucione della Faggiuola (p. 312) defeated the Florentines on 29th Aug., 1315. The warm baths (*Bagni di Monte Catini*) in the vicinity attract many visitors.

The line intersects the rich valley of the *Nievole*. — 33 M. *Pieve a Nievole*; to the right, *Monsummano* on a conical eminence, with warm springs; near it a *Grotto* with hot vapour, discovered in 1852, famous for the cures of rheumatism, gout, and paralysis which it has effected. (The arrangements are very primitive, and patients are therefore recommended to take apartments at *Monte Catini*, 1½ M. distant.) 36½ M. *Serravalle*, which was an important frontier-fortress during the wars between Lucca and Pistoja. — 40½ M. *Pistoja*.



**Pistoja.** — **ALBERGO DI LONDRA & DEL GLOBO**, R. 2½, D. 4 fr., with tolerable trattoria; **REGINA D'INGHILTERRA**; both in the Piazza Cino. — **ALBERGO & TRATTORIA ROSSINI**, Via Cavour, opposite the church of S. Giovanni, unpretending. — *Caffè del Globo*.

Cab with one horse 60, with two horses 80 c. per drive; to or from the station 1 fr.; 1st hour 1 fr. 40 or 1 fr. 70 c., each additional hour 1 fr. or 1 fr. 30 c.

*Pistoja*, an ancient town with 12,000 inhab., is loftily situated in the vicinity of the *Ombrone*, a small tributary of the Arno, in a fertile district. It has broad, well-built streets, and important manufacturing of guns and iron-wares. Pistols are said to have been invented at Pistoja, and thence to derive their name.

Pistoja, the Roman *Pistoria*, near which Catiline was defeated and slain, B. C. 62, was in the middle ages the centre of the fiercest struggles between the Guelphs and Ghibellines. In the year 1300 the *Cancellieri* and *Panciatichi*, or *Black* and *White* parties, mentioned by Dante (*Inferno* xxiv. 143), who afterwards extended their intrigues to Florence and influenced the fortunes of the poet himself, were formed here. Pistoja had to surrender to Florence in 1351. It was the birthplace of the celebrated jurist and poet *Cino*, a contemporary of Dante, and of the satirist *Niccolò Forteguerri* (1674-35), author of the *Ricciardetto*.

In the HISTORY OF ART, Pistoja, which somewhat resembles Florence in miniature, held an important rank in the early part of the middle ages, and was foremost among the Tuscan republics in fostering artistic progress. The older churches, such as the *Cathedral* and *S. Andrea*, exhibit a leaning to the Pisan style, which was extensively in vogue in the 12th cent. At Pistoja we also meet with many of the earliest attempts at sculpture in Tuscany, which are much ruder than contemporaneous German and French works of the same kind, and with several of the names of the oldest artists (*Gruamons* and *Adeodatus*). After the 14th cent. Pistoja became dependent on Florence both politically and in the province of art. The town continued to be wealthy and ambitious enough to patronise artists, but thenceforth those of Florence were always employed. Of the *Goldsmith's Art* we have an important specimen in the silver altar in the Cathedral.

We follow the *Via Cino*, leading from the station and intersecting the *Corso Vittorio Emanuele* at a right angle, as far as the *Piazza Cino*, and turning here to the right into the *Via Cavour*, soon reach the old Romanesque church of —

**S. Giovanni Fuoricivitas** (*Evangelista*; Pl. 1), erected about 1100, with a somewhat overlaid façade adorned in Pisan fashion with rows of columns. Over the side entrance is a relief representing the Eucharist by *Gruamons*, as an inscription on the architrave records (12th cent.).

INTERIOR. On the right is the *Pulpit*, adorned with ten reliefs on the three sides by *Fra Guglielmo*, a pupil of *Niccolò Pisano*, about 1270, the series beginning to the left with the Annunciation, Conception, etc.; in front, the symbols of the evangelists; on the left, a handsome basin for holy water by *Giovanni Pisano*, with figures of the virtues at the four corners. On the right, the *Visitation of Mary*, a life-size group in terracotta, by *Andrea della Robbia*.

Opposite the church is the *Pal. Panciatichi*. — Following the *Via Cavour*, and diverging from it by the *Via S. Matteo*, the third side-street to the left, we reach the *PIAZZA*. On the right rises the —

\***Cathedral of S. Jacopo** (Pl. 2) of the 12th cent., remodelled in the 13th from designs by *Niccolò Pisano* (?), with a tribuna

added in 1599 by *Jacopo Lafri*. In the vestibule are faded frescoes by *Giovanni Cristiani da Pistoja*. Over the principal entrance a



good bas-relief in terracotta (Madonna surrounded by angels) by *Andrea della Robbia*. The barrel-vaulting was adorned with coffering and rich garlands in terracotta by *Luca della Robbia*.

The INTERIOR, sadly marred by alterations, and restored with little taste in 1838-39, consists of nave and aisles borne by sixteen columns and two buttresses. — By the wall of the entrance is the Font, adorned with a large relief (Baptism of Christ) and four smaller ones (History of the Baptist) by *Andrea Ferrucci da Fiesole* (d. 1526). — To the RIGHT of the entrance is the Monument of the jurist and poet *Cino da Pistoja* (d. 1336), by the Siense master *Cinello* (1337). The bas-relief represents *Cino* lecturing to nine pupils, among them *Petrarch*, who afterwards composed a sonnet on his death, exhorting the women to mourn for *Cino* as the poet of love. — To the LEFT of the entrance the Monument of Cardinal *Fortiguerra*, with bust and high reliefs, by *Verrocchio* (1474) and *Lorenzetto*. — The CAPPELLA DEL SACRAMENTO (left of the choir) contains a Madonna with *St. Zeno* by *Lorenzo di Credi* (d. 1513). High relief

bust of Bishop Donato de' Medici by *A. Rossellini* (1475). — Over the HIGH ALTAR a Resurrection by *Angelo Bronzino*. Beautifully inlaid choir stalls. — In the CAPPELLA S. JACOPO (right of the choir) a rich *Silver Altar* executed in the 14th and 15th cent. (covered); in a niche above is a sitting statue of St. James, surrounded by apostles and prophets, wrought in silver, and gilded, by *Simone di Ser Memmo* and other masters, in the middle of the 14th cent.; below is a large silver tableau with wings; in the centre fifteen reliefs of subjects from the New Testament and apostles, by *Andrea di Jacopo d'Ognabene* (1316) of Pistoja; the wings consist of ten reliefs on the left, from the Old and New Testament by *Piero da Firenze* (1357) and on the right from the life of St. James by *Leonardo di Ser Giovanni*, pupil of Orcagna (1331). About 446 lbs. of silver are said to have been used in the execution of this work of art. The frescoes in this chapel are by *Alesso d'Andrea* and *Bonaccorso di Cino* (1347). — The Crypt, borne by six columns, is also modernised.

The campanile was originally a fortified tower, called Torre del Podestà, and still bears the arms of governors of the town. The three series of arches were added in Pisan fashion when the tower was adapted to its present purpose.

Opposite the cathedral is the octagonal \***Battistero** (*San Giovanni Battista*; Pl. 3), erected after 1339 by *Cellino di Nese* in the Italian Gothic style, with a pulpit on the exterior. The large square font (older than the building, and probably dating from 1256) is embellished with richly decorated slabs (others of the same kind on the wall to the right). The principal portal is also worthy of notice.

Adjacent is the \***Palazzo Pretorio** (Pl. 4), formerly *del Podestà*, a building of the 14th cent., now containing the courts of justice. The quadrangle is enclosed by four round arches; the arcades are adorned with numerous painted armorial bearings of the Podestà's, remarkable for their admirable heraldic style, restored in 1844. To the left of the entrance are the stone table and seats of the ancient tribunal, bearing the inscription of 1507:

*Hic locus odit, amat, punit, conservat, honorat,  
Nequitiam, leges, crimina, jura, probos.*

The piazza is adorned with a *Statue of Cardinal Forteguerri* (Pl. 5), erected in 1863. — Opposite the Pal. Pretorio is the *Palazzo del Comune* (Pl. 6; originally degli Anziani), erected in the Italian Gothic style in 1294-1385, with a vestibule. In the interior are frescoes by *Gianicola* and his pupils, and a relief in marble of the school of Verrocchio, 1484, representing \*angels with armorial bearings.

Passing between the cathedral and the Pal. del Comune (by the Via S. Bartolommeo), we next visit the church of *S. Bartolommeo in Pantano* (Pl. 7), a Lombard edifice with open roof, borne by twelve columns, with very varied capitals, and two buttresses. The sculptures on the façade by *Rudolfinus* represent Christ and the Apostles, 1167; pulpit, borne by two lions, and the statue of the sculptor, with eight reliefs from the history of Christ, by *Guido da Como*, 1250. — The Via Porta Guidi to the right leads hence to the —

**Ospedale del Ceppo** (Pl. 9), erected in 1277, and afterwards restored, with a long \*frieze consisting of reliefs in terracotta, coloured and glazed, representing the seven works of mercy, an enthroned Madonna, and four virtues; below, the Annunciation, Madonna in glory, and Conception, in medallions, by *Giovanni, Luca,* and *Girolamo della Robbia*, 1525-35. — We now pass the Ospedale by the Via delle Pape to the left, which leads to a small planted piazza, follow the Via del Carmine to the left, and then the first side-street to the right, to —

**\*S. Andrea** (Pl. 9), a church of the 12th cent., and probably once the cathedral. On the architrave of the entrance are sculptures of 1166, representing the Adoration of the Magi with the inscription: 'Fecit hoc opus Grnamons magister bon. et Adod frater ejus.' (*Grnamons* and *Adeodatus*, 1160; see p. 318). Over the door is a small statue of St. Andrew in *Giov. Pisano's* style.

INTERIOR. The narrow nave and aisles are supported by twelve columns and two pillars. The *Pulpit* with its numerous figures by *Giovanni da Pisa*, 1298-1301, a copy of that executed by his father at Pisa, is a hexagon with reliefs from the Old Testament on five sides: Crucifixion, Last Judgment, Adoration of the Magi, Nativity, Slaughter of the Innocents; below these are six figures of sibyls and prophets borne by seven columns of red marble, a lion and lioness, a human figure, and a winged lion with two eagles.

Turning to the right we enter the Via S. Prospero, and turning again to the right we reach the Piazza S. Francesco with —

**S. Francesco al Prato** (Pl. 10), an Italian Gothic church of 1294, with paintings by *Margaritone* and other masters. The chapter-house is adorned with frescoes of scenes from the life of St. Francis, attributed by Vasari to *Puccio Capanna* (perhaps by *Giovanni Cristiani*, 14th cent.). Keys at the Palazzo del Comune. — We return by the Via Cancellieri (with the *Pal. Cancellieri* on the right) to the Piazza Cino, and proceed by a side-street to the right to —

**S. Maria dell' Umiltà** (Pl. 11), with a bare façade, erected about 1509 by *Ventura Vitoni*, a pupil of Bramante, the dome by *Vasari*. A fine oblong vestibule, adorned with frescoes by *Vasari* relating to the miracle-working Madonna in the church, leads to the handsome octagonal interior, with its elegant Corinthian wall pilasters in several stories, and pictures by *Gerimo* and others.

On the way back to the station is —

**S. Domenico** (Pl. 12), in the Corso Vitt. Emanuele, erected in 1380.

INTERIOR. 2nd Altar on the right: Madonna and Child, *al fresco*, by *Fra Bartolommeo* (?). Right Transept: *Cappella Rospigliosi*, with monuments of the family, and the miracle of S. Carlo Borromeo, by *Jacopo da Empoli*. To the left in the Choir, St. Sebastian by *R. Ghirlandajo*. 2nd Altar on the left, Crucifixion with saints; 3rd Altar on the left, the Virgin and Thomas Aquinas, by *Fra Paolino da Pistoja*. Between the 4th and 6th Altars on the left, monument of the jurist Filippo Lazari (d. 1412), by *Bernardo di Matteo Fiorentino*, 1464. — The Cloisters were decorated with paintings by *Sebastiano Veronese* and others, 1596.

Pistoja possesses two *Libraries*, the *Fabbroniana* (Pl. 13), and the *Fortiguerra* (Pl. 14), founded by two cardinals who were born here..

The *Villa Puccini*, 1 M. to the N., has beautiful gardens and works of art by Pampaloni and others.

RAILWAY FROM PISTOJA TO BOLOGNA, see R. 45.

The RAILWAY TO FLORENCE intersects a rich tract at the base of the Apennines. 44½ M. S. *Piero*. On the left the picturesque castle of *Monte Murto* comes into view, near which the Florentine republicans Baccio Valori and Filippo Strozzi were defeated and taken prisoners by the troops of Cosmo I.

50½ M. **Prato** (*Atbergo del Giardino*; *Café Vestris*; both near the cathedral), a well-built town with 12,000 inhab., on the *Bisenzio*, with beautiful environs, is a manufacturing place, of which straw-plait is one of the staple commodities, and is also noted for its excellent bread. It formerly belonged to Florence, whose fortunes it shared throughout the middle ages. In 1512 it was taken by storm by the Spaniards under Cardona.


In the 15th cent. this small provincial town attracted numerous artists from Florence, so that a visit to it is indispensable to those who desire to be thoroughly acquainted with the EARLY RENAISSANCE style of Florence. An important work by *Donatello* and *Michelozzo*, an extensive composition in the style of *Robbia*, and a superb bronze screen bear testimony to the importance of Prato in the history of Renaissance sculpture. Among the painters of the place were *Filippo* and *Filippino Lippi*, *Botticelli*, and *Fra Diamante*. The church of the *Madonna delle Carceri* at Prato also forms a very striking example of Renaissance architecture. This edifice (erected by *Giuliano da Sangallo*) exhibits the transition from early to high Renaissance, and shows how anxiously the architects of the day directed their attention to the design of a Greek cross covered with a dome.

\*IL DUOMO, begun in the 12th cent., and completed by *Giovanni Pisano* in the 14th, is in the Tuscan Gothic style. On the façade, which dates from 1450, is a pulpit, adorned by *Donatello* and *Michelozzo*, after 1434, with \*bas-reliefs (dancing children). From the pulpit the highly revered *Sacra Cintola*, or 'girdle of the Virgin' preserved in the cathedral, is periodically exhibited to the people. Over the principal entrance a \*Madonna with SS. Stephen and Lawrence in terracotta, by *Andrea della Robbia*.

INTERIOR. Over the PRINCIPAL ENTRANCE the Virgin delivering the girdle to St. Thomas, by *Ridolfo Ghirlandajo*. The CAPPELLA DELLA CINTOLA is adorned with mural paintings by *Agnolo Gaddi* (1395), from the life of the Virgin, and her statue on the altar by *Giovanni Pisano*; handsome bronze *Screen* executed in 1444-61. — In the CHOR, at the back of the high altar, are the 'histories of John the Baptist and St. Stephen by *Fra Filippo Lippi*, the finest work of this master (d. 1469): on the right (above) Birth and Naming of the Baptist; his Withdrawal to the wilderness; and his Preaching; Dance of the daughter of Herodias; by the window, on the right: Beheading of St. John; above it a saint. On the left wall of the choir (above): Birth of St. Stephen, his Ordination and care for the poor; Stoning and Interment (among the admirable portrait figures are Cardinal Carlo de' Medici, and, to the extreme right, the portrait of the painter himself). The continuation of the scene of the Stoning is on the window wall; above it a saint; on the ceiling







# FIRENZE.

## Chiese

|                                          |        |                              |     |
|------------------------------------------|--------|------------------------------|-----|
| 1 S. Ambrogio                            | F 5    | 60 Pal. Berte                | E 5 |
| 2 S. Annunziata                          | F 3    | 61 Buondelmonti              | C 4 |
| 3 S. Apostoli                            | C 4    | 62 Batarlini già Niccolini   | E 4 |
| 4 Badia                                  | D 4    | 63 Capponi                   | F 3 |
| 5 Battistero                             | D 4    | 64 della Comunità            | C 4 |
| 6 S. Carlo Borromeo                      | D 4    | 65 Corsini                   | C 4 |
| 7 S. Croce                               | E 5    | 66 Feroni                    | B 4 |
| 8 Duomo                                  | D 4    | 67 Fontebuoni                | C 4 |
| 9 S. Egidio                              | E 4    | 68 Gherardeschi              | F 4 |
| 10 S. Felice                             | B 5    | 69 Ginori                    | D 3 |
| 11 S. Felicità                           | C 5    | 70 Grazi                     | E 4 |
| 12 S. Firenze                            | D 5    | 71 Dubour-Berte già Guadagni | B 5 |
| 13 S. Frediano                           | B 4    | 72 Guicciardini              | C 5 |
| 14 S. Girolamo                           | C 5    | 73 Incontri                  | E 4 |
| 15 S. Giuseppe                           | E 5, 6 | 74 Nencini                   | F 2 |
| 16 S. Jacopo                             | C 5, 6 | 75 Orlandini                 | D 4 |
| 17 S. Lorenzo                            | D 3    | 76 Panciatichi               | F 4 |
| 18 S. Lucia                              | D 5, 6 | 77 Pazzi                     | E 4 |
| 19 S. Marco                              | F 3    | 78 Corsi già Tornabuoni      | C 4 |
| 20 S. Maria degli Angeli                 | E 4    | 79 Strozzi-Ridolfi           | B 2 |
| 21 in campo                              | E 4    | 80 Pitti                     | C 5 |
| 22 del Carmine                           | B 4    | 80 <sup>a</sup> Rucellai     | C 4 |
| 23 Maddalena                             | F 4    | 81 Pomiatowski               | F 2 |
| 24 Maggiore                              | D 4    | 82 Pucci                     | E 4 |
| 25 Novella                               | C 3    | 83 Riccardi già Nodici       | D 3 |
| 26 de' Ricci                             | D 4    | 84 Strozzi                   | C 4 |
| 27 Misericordia                          | D 4    | 85 Topprigiani               | D 6 |
| 28 S. Niccolò                            | D 6    | 86 degli Uffizi              | D 5 |
| 29 S. Benigno                            | D 5    | 87 Ugucione vecchio          | D 5 |
| 30 Ognissanti                            | C B 3  | 89 Posta                     | D 5 |
| 31 Ors. Michele                          | D 4    | 90 Prefettura                | E 4 |
| 32 S. Simone                             | E 5    | 91 Spedale di Bonifazio      | E 2 |
| 33 S. Spirito                            | B 5    | 92 degli Innocenti           | E 3 |
| 34 S. Stefano                            | D 5    | 93 di S. Lucia               | F 2 |
| 35 S. Trinità                            | C 4    | 94 di S. Maria nuova         | E 4 |
| 36 de' Protestanti                       | F 3    | 95 Statua di Dante           | E 5 |
| 37 Accademia di belle Arti               | E 3    | 96 Archivio Centrale         | D 5 |
| 38 Banca nazionale                       | D 5    |                              |     |
| 39 Bargello                              | D 4, 5 |                              |     |
| 40 Baar                                  | D 4    |                              |     |
| 41 Biblioteca Laurenziana                | D 3    |                              |     |
| 42 Magliabecchiana                       | D 5    |                              |     |
| 43 Marcelliana                           | E 3    |                              |     |
| 44 Riccardiana                           | D E 3  |                              |     |
| 45 Bigallo                               | D 4    |                              |     |
| 46 Casa di Dante                         | D 4    |                              |     |
| 47 Galilei                               | C 5    |                              |     |
| 48 Machiavelli                           | C 5    |                              |     |
| 49 Michel Angelo                         | E 5    |                              |     |
| 50 Collegio degli Scolopi                | D 3    |                              |     |
| 51 Dogana (Casino dei Medici)            | E 3    |                              |     |
| 52 Loggia del Grano                      | D 5    |                              |     |
| 53 Loggia de' Lanzi                      | D 5    |                              |     |
| 54 Museo egiziano                        | D 2, 3 |                              |     |
| 55 di S. Marco                           | E 3    |                              |     |
| Nazionale e Bargello                     |        |                              |     |
| di storia naturale                       | B 5    |                              |     |
| 56 Palazzo Albizi                        | E 4    |                              |     |
| 57 Altoviti (de' Visacci)                | E 4    |                              |     |
| 58 Quaratesi già Pazzi                   | D E 4  |                              |     |
| 59 <sup>a</sup> Antinori già Riccardi    | E 3    |                              |     |
| 59 <sup>b</sup> Del Turco già Borgherini | C 4    |                              |     |
| 59 <sup>c</sup> Gerini già Sergardi      | E 3    |                              |     |

## Teatri

|                                 |     |
|---------------------------------|-----|
| 97 Alfieri                      | E 5 |
| 98 Borgognissanti (Rossini)     | C 4 |
| 99 Goldoni                      | B 5 |
| 100 Nazionale                   | D 4 |
| 101 Niccolini                   | D 4 |
| 102 Nuovo                       | E 4 |
| 103 Paghiano                    | E 5 |
| 104 della Pergola               | E 4 |
| 105 Politeama Vittorio Emanuele | B 2 |
| 106 Principe Umberto            | G 4 |

## Alberghi principali

|                             |       |
|-----------------------------|-------|
| a. Italia                   | B 3   |
| b. Nuova York               | C 4   |
| c. Paris                    | B 3   |
| d. Travers                  | B 2   |
| e. Ford                     | C 4   |
| f. La Ville                 | B 3   |
| g. Rome                     | C 3   |
| h. Europa                   | C 4   |
| i. La Nazionale             | D 3   |
| k. Vittoria                 | A 2   |
| l. Washington               | B C 4 |
| m. Arno                     | C 5   |
| n. Luna                     | D 4   |
| o. Angletterre              | C D 3 |
| p. Boniciani                | C 3   |
| r. Pension Suisse           | C 4   |
| t. Pension Anglo Américaine | B 2   |



Evangelists (best light in the forenoon). On the right is the 'Death of St. Bernard, also by *Filippo Lippi*. The side chapel on the left, and the second on the right, contain frescoes in Giotto's style, but much retouched. — In the S. transept a Statue of the Madonna by *Nino Pisano*. — Handsome round PULPIT, resting on sphinxes and snakes, by *Mino da Fiesole* and *Rossellino*, adorned with admirable reliefs (1473).

The campanile, in the Lombard style, is by *Niccolò di Cecco* (1340).

The Via dei Sarti leads from the cathedral to the PALAZZO COMUNALE, which contains a small picture-gallery on the first floor (fee  $\frac{1}{2}$  fr.).

*Fra Filippo Lippi*. 11. Madonna with St. Thomas, etc., 12. Nativity, 21. Madonna with John the Baptist; 16. *Filippino Lippi*, Madonna with John the Baptist and St. Stephen; 18. *Giovanni da Milano*, Madonna with saints (14th cent.).

The *Palazzo Pretorio* opposite is of the 13th cent.

The \*MADONNA DELLE CARCERI, erected in 1492 by *Giuliano da Sangallo*, is in the form of a Greek cross, with barrel-vaulting and dome, and a fine altar by *Antonio da Sangallo*, brother of the architect. — *S. Domenico*, of the 13th cent., was restored in the 17th. — *S. Francesco* contains mural paintings in the chapter-house by *Niccolò di Pietro Gerini* and *Lorenzo di Niccolò* (14th cent.).

At *Monteferrato*, 3 M. to the N.W. of Prato, are quarries of serpentine, which is known as Verde di Prato, and has been much used in Tuscany for decorative purposes.

54 M. *Calenzano*; 57 M. *Sesto* (to the left the villa of *La Doccia*, p. 387); 59 M. *Castello* (near it *La Petraja*, see p. 387); 60 M. *Rifredi*. — 61 $\frac{1}{2}$  M. *Florence*.

## 49. Florence.

**Arrival.** There are two railway-stations at Florence: 1. STAZIONE CENTRALE (Pl. C, 2, 3) for all the railways (approached from the Piazza della Ferrovia; egress for the northern line in the Via Luigi Alamanni; for the other lines, adjoining the Piazza Ferrovia), where omnibuses from most of the hotels meet every train (1-1 $\frac{1}{2}$  fr.); fiacre 1 fr., at night  $\frac{1}{2}$  fr., each box 50, travelling-bag 25 c., triding gratuitly to railway porter. Travelers arriving in the evening should secure a cab in good time, as there is often a scarcity of conveyances. — 2. STAZIONE PORTA CROCE (Pl. G, 4) on the E. side of the town; too far from the middle of the town for most travellers.

**Hotels.** — On the *Lung' Arno*, best situation, from W. to E.: \*GRAND HÔTEL ROYAL DE LA PAIX (Pl. C); HÔTEL DE LA VILLE (Pl. D), both in the Piazza Manin; \*ITALIA (Pl. a, in the Palazzo Murat), principal entrance Borgognissanti 19; \*NEW YORK (Pl. b), Piazza Ponte alla Caraja 1; \*GRAN BRETAGNA, Lung' Arno Acciajoli 8; ARNO (Pl. m), Lung' Arno Acciajoli 4. All these are of the first class: R. 3-4 fr. and upwards, B. 1 $\frac{1}{2}$ , L. and A. 2, D. 4 $\frac{1}{2}$ -5, omnibus 1 $\frac{1}{2}$  fr.; pension, according to bargain, 10 fr. and upwards. — On a somewhat smaller scale, and a degree less expensive: HÔTEL WASHINGTON (Pl. l), Lung' Arno 6, well spoken of; HÔTEL DE RUSSIE, Piazza Manin 2, new. — In the new quarter near the Cascine: \*UNIVERSO, Corso Vitt. Emanuele; VITTORIA, Lung' Arno Nuovo 32; \*CORONA D'ITALIA (also a pension), Via Palestro; ANGLO-AMERICAN, Via Garibaldi 7; CORONA D'INGILTERRA, Via Solferino 8, pension 8-10 fr.; CITTÀ DI MONACO (*Stadt München*), Via Montebello 32, R. 2-3, B. 1 $\frac{1}{4}$ , D. 4 fr., L. 60, A. 60 c.; ALLEANZA (with pension), Via Montebello 34; L'UNION, Via della Scala 33, pension 7-8 fr., well spoken of. — In the Via



*Tornabuoni*: <sup>1</sup>HÔTEL DU NORD, No. 8; HÔTEL DE L'EUROPE, Piazza S. Trinità; <sup>2</sup>HÔTEL-PENSION SUISSE (Pl. r), No. 13, R. 2½, D. 4½, B. 1½ fr.; near it, VILLE DE PARIS, with restaurant, Via della Spada 3; PENSION INGLESE, Via del Sole 6; <sup>3</sup>LEONE BIANCO, Via Vigna Nuova, in the Italian style (see p. 325), unpretending, pension 6-7 fr. — *Near the Piazza della Signoria*, between the Cathedral on the N. and the Arno on the S., most of them thoroughly Italian, with trattorie, but conveniently situated: HÔTEL CAVOUR ET PARLEMENT, Via del Proconsolo 5, with table-d'hôte; ROSSINI, formerly *Luna* (Pl. n), Via Condotta; <sup>4</sup>HÔTEL DU PARLEMENT, Via dei Leoni 14, at the back of the Palazzo Vecchio; <sup>5</sup>PORTA ROSSA, R. 2½, A. ¾, L. ¾, pension 7 fr., Via Porta Rossa, between Via Calzajouli and Via Tornabuoni; <sup>6</sup>ALBERGO DI SPAGNA, Via Calzajouli 13. — *Near S. Maria Novella and the Railway-Station*: ROMA (Pl. g), Piazza S. Maria Novella 7; MINERVA, Piazza S. Maria Novella; HÔTEL D'ANGLETERRE, Via Panzani; <sup>7</sup>CITTÀ DI MILANO, Via Cerretani 12, patronised by English visitors, R. 2½-3, L. ¾, D. 4½ fr.; ALBERGO BONCIANI, Via Panzani 23, pension 7 fr.; ISOLE BRITANNICHE, Piazza S. Maria Novella.

**Pensions and Apartments.** RODOLFO, Via della Scala 2, pension 7 fr., well spoken of; MOLINI-BARBENSI, Lung' Arno Guicciardini 15, 8-10 fr.; MAD. LAURENT, Via del Presto 11 (near S. Spirito), 5-6 fr. (also without board); MAD. JENNINGS, Via Maggio 28, 7-8 fr.; MAD. JANDELLI, Piazza Soderini 1, 8 fr.; FR. DÖHLER, Via S. Paolo 4, near the Piazza dell'Indipendenza, furnished rooms; MAD. BACCIONI, on the 3rd floor of the same house; MAD. ROCHAT, Via dei Fossi 16, 2nd floor, pension 6-8 fr., well spoken of; FR. BRUN, Corso Vitt. Eman. 9, 1st floor, furnished rooms, with or without board; MISS EARLE, Palazzo Corsi, Via Tornabuoni; PENSION GIRARD, Via del Campuccio 59 and 61, pension 7 fr.; MAD. BRUNNORO, Via Alfani 74, 1st floor; PERA, Via della Pergola 14 (bis), 6 fr., good cuisine; CASA NARDINI, Borgo SS. Apostoli 17, 2nd floor, lodgings only, unpretending, frequented by artists. — Travellers who make a stay of 10-14 days and upwards will be more independent and may effect a saving if they engage private lodgings; but rooms (indicated by placards) are sometimes difficult to procure in winter, which is the season at Florence. The charges depend of course on the situation. Two furnished rooms cost on an average 50-60 fr. per month, in summer 40-50 fr.; attendance about 5 fr. The pleasantest situation in winter is the sunny side of the *Lung' Arno*. The other quarters of the town on the right side of the Arno (environs of the Cathedral, Via dei Cerretani, Piazza S. Maria Novella, Via Cavour, Piazza dell'Indipendenza, etc.), as well as the Piazza Pitti on the left side, may also be mentioned as healthy and pleasant situations. The quarter of the town on the left bank of the Arno, especially below the Porta S. Frediano, is considered less healthy. In winter it is most important to secure rooms with a southern aspect, which is essential to health and comfort in Italy, where brilliant sunshine so often contrasts with bitterly cold winds. The Lung' Arno is almost deserted in summer on account of the exhalations and the mosquitoes which infest it, and a northern aspect is then preferred. The heat in July and August is oppressive, and for these months quarters should be sought for in one of the numerous villas charmingly situated on the neighbouring heights. Information regarding houses to be let in whole or in part may be obtained at the offices of the commission-agents.

The WATER at Florence is bad, and should not be drunk unless boiled or mixed with wine. The best *soda-water* is manufactured at Borgo S. Croce 7. — *Andreas Mucke*, a good valet-de-place, may be engaged at the Hôtel de la Ville.

**Restaurants**, most frequented at the dinner-hour, 5-7 o'clock, generally closed after 8 o'clock (luncheon, see p. 325): *Doney & Nipoti*, Via Tornabuoni 16, dear (dinner till 6 p. m. only, 7 fr.), with a branch establishment in the Cascine, see p. 387; *Gilli & Letta*, Piazza Signoria, see below; *Victor*, Via Rondinelli 3; *Café d'Italia*, Piazza S. Maria Maggiore, Via Cerretani. — TRATTORIE in the Italian style: *La Toscana*, Via Calzajouli; *Luna* (Pl. n), Via Condotta, see above; *Patria* and *Stella*, in the Via Calzajouli, with a few rooms to let; *Bonciani*, Via

Panzani 23 (p. 324), and in the Viale dei Colli (p. 383; beautiful view); *Antiche Carrozze*, Borgo SS. Apostoli, near the Ponte Vecchio, and *Leone Bianco* (see p. 324), D. at 5 o'clock, both unpretending; *Birreria Cornelio*, with restaurant, see below; *Porta Rossa*, Via Porta Rossa; *Ville de Paris*, Via della Spada 3. — Dinners à la carte (2-4 fr., bread 10, wine 50-80 c.) are more in vogue than tables d'hôte.

**Cafés**, less inviting than in many other Italian towns, a few only with seats in the open air: *Doney* (best coffee, no newspapers), see above; *Café d'Italia*, Piazza S. M. Maggiore, Via Cerretani; *Flora*, Via del Proconsolo; *Bottegone* and *Piccolo Elvetico*, in the Piazza del Duomo; *Risorti*, Via Cavour; *Ferruccio* and *Witat*, both Via Por S. Maria, N. of the Ponte Vecchio. Cup of coffee 15-20c., ice 30c., light Florence beer 50c. per bottle, beefsteak for déjeuner 1 fr., etc. — Visitors to the cafés are frequently importuned by hawkers of photographs, etc., who often sell their wares at one-third or one-half of the price at first demanded, and by the well known *'Floraje'*, or flower-girls.

**Confectioners (Confetturerie)**. *Gilli*, Via Calzajuoli 10, and Via Cerretani, also excellent white bread; *Castelmur*, *Stuppani*, both in the Via Calzajuoli; *Doney*, *Giacosa*, both in the Via Tornabuoni.

**Wines**. Good Italian at *Mellini's*, Via Calzajuoli 11; at the *Fiaschetteria*, next door to the Café Bottegone, at the beginning of the Via Cavour; *Fiaschetteria Michelangelo*, Via del Presto, near Dante's house. A 'fiasco', a straw-covered flask, usually holding three ordinary bottles (table-wine 1½ fr. per fiasco), is usually ordered, but only the quantity actually consumed is paid for. The best Tuscan wines are *Chianti*, *Montepulciano*, etc.

**Beer**. The *Birrerie* are also restaurants: *Gilli & Letta* (also coffee and wine-house), in the Piazza della Signoria, Viennese beer 35 c. per glass; *Birreria Cornelio*, with garden, Piazza de' Buoni, music in the evenings; *Weiss & Mayer*, Via Maggio (brewery), in summer only. *Bavarian Beer*, and Tuscan wines at Borgo SS. Apostoli 6.

**Tobacco**. The *Spaccio Normale* (or government shop), where imported cigars are also sold, is at Via Tornabuoni 16, next door to Doney's.

**Cabs** are stationed in the Piazza S. Trinità, Piazza della Signoria, near the cathedral, etc. The 'tariffa', which each driver is bound to carry, is the same for one-horse and two-horse carriages. The night-fares in summer are from 9 p.m. to 5 a.m., in winter from 7 p.m. to 6 a.m.

|                                                                                    | Day   | Night |
|------------------------------------------------------------------------------------|-------|-------|
| Within, and including the <i>New Boulevards</i> (p. 332), per drive                | — 80  | 1. 30 |
| Within the <i>Cintia Daziaria</i> (line of municipal inposts), for the first ½ hr. | 1. 30 | 1. 60 |
| Each additional ½ hr.                                                              | — 70  | 1 —   |
| Outside the town, first ½ hr.                                                      | 2 —   | 2. 30 |
| Outside the town, each additional ½ hr.                                            | 1 —   | 1. 30 |
| Each box 50, travelling bag 25 c.                                                  |       |       |

**Omnibuses** from the Piazza della Signoria, some also from the Piazza del Duomo, to all the gates of the city 10 c., on Sundays and holidays 15 c.

**Consulates**. *American*, Via Maggio 7; *English*, Via Tornabuoni 14; *German*, Via del Proconsolo 10.

**Post Office** in the Uffizi, open daily from 8 a.m. to 10 p.m. (branch-office at the railway station for letters only, open till 9); six deliveries of letters daily; postage within the city 5 c. — **Telegraph Office** in the Palazzo Riccardi, Via dei Ginori 2. Branch office, Borgognissanti 15 (10-4).

**Physicians** (hour of consultation generally 2-3): *Dr. v. Coelln*, Via del Sole 14, 2nd floor; *Dr. Bergeest*, Via de' Serragli 3, 3rd floor; *Dr. Levier*, Via S. Frediano 16, 2nd floor; *Dr. Wilson*, Via S. Spirito 33; *Dr. Davidson* (homœopathist), Via della Scala 2, 1st floor. — Surgeon: *Fleischmann*, Piazza del Carmine 20. — Oculist: *Dr. Mannhardt*. — Dentists: *Dunn*, Piazza S. Maria Novella; *Stalton*, Lung'Arno Nuovo; *Campani*, Piazza della Signoria.

**Chemists.** English: *Roberts*, Via Tornabuoni 17; *Groves*, Borgo Ognissanti 15. German: *Jausseu*, Via dei Fossi 10 (mineral water depôt; homœopathic dispensary in a separate room). — *Nurses* may be engaged through the chemists.

**Baths.** *Peppini*, Via SS. Apostoli No. 16, near S. Trinità; *Papini*, Via Vigna Nuova 19, and Corso Vitt. Emanuele 17b; also in the Via di Parione 28, at the back of the Palazzo Corsini, and Via Maggio 30.

W. C. (10 c.): Vicolo della Seta (near the Loggia del Mercato Nuovo), Via Calzajoli, Borgo Ognissanti; on the Viale dei Colli, in the Piazzale Michelangelo, and near the Tivoli, see p. 383.

**Booksellers.** *Goodban*, Via Tornabuoni 9, English, German, French, and Italian books, also photographs, and engravings; *Bocca*, Via Cerretani; *Bellini*, Via Tornabuoni; *Württemberg*, chiefly for German literature, Via Tornabuoni; *Brecker*, Via Maggio 15, with circulating library; *Flor & Fiadel*, Lung' Arno Acciajoli 24. — Music and pianos may be hired of *Brizzi & Nicolai*, Via Cerretani; *Bucci*, Piazza Antinori.

**Reading Room.** *Viousseur*, Palazzo Ferroni, Via Tornabuoni, with a circulating library, open 8 a.m. to 10 p.m., admission 50 c., per week 3, per month 7, quarter 14 fr.; *Circolo Filologico* in the Palazzo Ferroni (visitors to which must subscribe for at least six months).

**Circulating Libraries.** *Brecker*, Via Maggio 15, English, Italian, German, and French books; *Vanni*, Via degli Strozzi, Italian and French books.

**Photographs.** *Alinari*, Via Nazionale 8, and Via Tornabuoni (views from I. fr.); *Broggi*, Via Tornabuoni 1; *Brecker*, agent for Sommer's photographs (I. fr. each), Via Maggio 15; *Philpat & Co.*, Borgognissanti 17 (original photographs from the drawings in the Uffizi), etc.

**Shops.** ALABASTER & MARBLE: *Bazzanti*, Lung' Arno Corsini; *Bevucci*, Via Tornabuoni; *Almanconi*, Lung' Arno Guicciardini, also in the Via de' Fossi. — GALVANOPLASTIC CASTS: *G. Pellas*, Via Jacopo da Diacceto 10. — MOSAICS: *Belli*, Lung' Arno Nuovo; *Fratelli Montelatici*, Lung' Arno Corsini, and in the shops on the Ponte Vecchio. — GILDERS (excellent) in the Via de' Fossi. — STRAW HATS: *Porciauti*, Via Tornabuoni; *Nannucci*, Via Porta Rossa. — MILLINERY: *Emilia Bossi*, Via Rondinelli; *Ficchi*, Via Tornabuoni; *Miss Baker*, Via Cavour 26. — A process of polite bargaining will often be found necessary.

**Artists.** PAINTERS: *Boecklin*, Via Lorenzo Magnifico 2; *Cassioi*, Piazza Pinti; *Car. Gordigiani*, Via Nazionale 44; *Couti*, Via Romana 8. — SCULPTORS: *Prof. Fedi*, Via de' Serragli 99; *Prof. Dupré*, Via della Sapienza; *Prof. Fantacchiotti*, Via Pancale 39; *Hildebrand*, in the monastery of S. Francesco di Paola (p. 386); *Ball* (English), outside the Porta Romana.

**Goods-Agent.** *R. Küntzel & Co.* (German), Piazza de' Giuochi 1; *Boucnielli*, near Or San Michele, and others.

**Bankers.** *Du Fresne*, Piazza S. Firenze, Pal. Gondi (p. 352), 1st floor; *Fenzi & Co.*, Piazza della Signoria; *Haskard & Sou*, Piazza S. Gaetano 3, Pal. Antinori; *Morgan & Hooker*, Via Tornabuoni 5; *Freuch* (Engl. Consul), Via Tornabuoni 14; *Eyre & Huntington* (American), Via Maggio 7. — Money-changers: *Pestellini*, Via Cerretani, near the cathedral; also Via Calzajoli 9, and others; comp. p. xi, xii.

**Schools.** Girls: Institution of the German Protestant sisters of Kaiserswerth. — Boys: *Pères de Famille*, Via d'Ardiglione. — Academy of Art for ladies: *Mlle. Fries*, Villa Pellegrina, Lungo il Mugnone, within the Porta S. Gallo. — Teacher of drawing and water-colours: *Roster*, Via Farini. — Teachers of music: *Car. Krauss*, Via Cerretani 10; *Del Bene*, Via Maggio 3. — Teachers of Italian may be enquired for at the chemists', or at the booksellers'.

**English Church**, Via Maglio, behind S. Marco. — *Presbyterian Service*, Lung' Arno Guicciardini 9, where there are also German and French services on Sundays at 10 and 11 a.m. respectively. — *American Episcopal Church*, Piazza del Carmine 11. — *Waldensian Service* (p. 72), on Sundays at 11 a.m. in the Palazzo Salviati, Via de' Serragli.

**Theatres.** *Della Pergola* (Pl. 104), erected in 1638, remodelled in 1857. Via della Pergola 12, for operas and ballet, seats for upwards of

2000 pers., representations during a few months only in the year, adm. 3 fr.; *Pagliano* or *Cherubini* (Pl. 103), Via Ghibellina 81, adm. 1½ fr.; *Niccolini* (Pl. 101), Italian and French comedy, Via Ricasoli 8; *Delle Logge*, generally French comedy, Via dei Neri (Logge del Grano); *Nazionale* (Pl. 100), Via dei Cerchi; *Alfieri* (Pl. 97), Via Pietra Piana; *Rossini* (Pl. 98), formerly *Borgognissanti*; *Principe Umberto* (Pl. 106), Piazza Azeglio; *Arena Nazionale*, Via Nazionale, and several others. — Open-air Theatres: *Goldoni* (Pl. 99); *Politeama* (Pl. 105), Corso Vitt. Emanuele, near the Cascine, operas, ballet, farces, and sometimes a circus.

**Diary.** Churches generally open the whole day, except from 12½ to 2 or 3 p.m. — Admission to the other sights, except on the public holidays, as follows (see also the daily newspapers): —

‡ *Accademia delle Belle Arti*, daily, 9-3, admission 1 fr., Sund. (10-3), and from April to November on Thursd. also gratis (see p. 361).

*Biblioteca Laurenziana*, daily, exc. Sund. and holidays, 9-3, vacation from 1st Oct. to 12th Nov. (p. 367).

*Bibl. Marcelliana*, daily, exc. Sund., 10-2 (p. 365).

*Bibl. Nazionale*, daily, exc. Sund. and festivals, 9-4 (p. 344).

*Bibl. Riccardiana*, daily, exc. Sund., 9-3; vacation from 20th Aug. to 12th Nov. (p. 365).

‡ *Boboli Garden*, open to the public on Sund. and Thursd. afternoons (p. 375).

*Exhibitions of Art at the Società Artistica*, Viale Principe Eugenio, near the Protestant cemetery (Pl. G, 4).

*Galleria Berte*, frequently closed (p. 358).

‡ *Gal. Buonarroti*, Mond., and Thursd., 9-3 (p. 358).

*Gal. Corsini*, Tuesd., Thursd., and Sat., 10-3 (p. 370).

‡ *Gal. Pitti*, Sund. and from April to Nov. on Thursd. also, 11-3, gratis; on other days, 9-3, adm. 1 fr. (p. 375).

‡ *Gal. Strozzi*, Wednesdays (unless a festival) 11-1, closed in summer (p. 372).

‡ *Gal. degli Uffizi*, Sund., and from April to Nov. on Thursd. also, 11-3, gratis; on other days, 9-3, adm. 1 fr. (p. 334).

‡ *S. Lorenzo*, new sacristy and chapel of the princes, daily, 9-3 (Sund. 10, Mond. 12-3), p. 366.

*Museum, Egyptian and Etruscan*, daily, 10-4, adm. 1 fr.; Sund. gratis (p. 372).

‡ *Museo di S. Marco*, 1st Oct. to 31st March 9-3, 1st Apr. to 30th Sept. 10-1; on Sund. gratis, at other times 1 fr. (p. 360).

*Museo Nazionale*, daily 10-4½, 1 fr., on Sund. gratis (p. 352).

*Museo di Storia Naturale*, Tuesd., Thursd., and Sat., 10-4; strangers admitted daily on application (p. 381).

*Ospedale S. Maria Nuova* (pictures), daily, 9-3, Sund. 10-2 (p. 351).

**Chief Attractions:** *Piazza della Signoria* with the *Palazzo Vecchio* and the *Loggia dei Lanzi* (p. 332); *Galleria degli Uffizi* (p. 334); *Piazza del Duomo* with the *Baptistry* and the *Cathedral* (p. 346); the churches of *S. Croce* (p. 355), *S. Lorenzo* (p. 366), *S. Maria Novella* (p. 368), *S. Marco* and the monastery (p. 360); *S. Annunziata* (p. 359); *S. Spirito* (p. 373); then the *Pal. Pitti* with the picture-gallery (p. 375) and the *Boboli Garden* (p. 381); the *Accademia* (p. 361); the *National Museum* (p. 352); the *Views from S. Miniato* (p. 384) and the *Viale dei Colli* (p. 383); from *Bello Sguardo* (p. 386) and from the heights of *Fiesole* (p. 388). — A stay of 4-6 days will not suffice for more than a hasty glimpse at the sights of Florence.

Florence, formerly the capital of the Grand Duchy of Tuscany, and in 1864-70 that of the kingdom of Italy, ranks with Rome, Naples, and Venice as one of the most attractive towns in Italy. While in ancient times Rome was the grand centre of Italian development, Florence has since the middle ages superseded it as the focus of intellectual life. The modern Italian language and liter-

ature have emanated chiefly from Florence, and the fine arts also attained the zenith of their glory here. An amazing profusion of treasures of art, such as no other locality possesses within so narrow limits, reminiscences of a history which has influenced the whole of Europe, perpetuated by numerous and imposing monuments, and lastly the delightful environs of the city combine to render Florence one of the most interesting and attractive places in the world.

'Who can describe the enchanting view of this art-city of Tuscany and the world, Florence, with its surrounding gardens? who paint the distant horizon, from Fiesole smiling at us with its fair towers, to the blue ridge of the Lucchese Mountains standing out against the golden background of the western sky? Here everything betrays the work of generation after generation of ingenious men. Like a water-lily rising on the mirror of the lake, so rests on this lovely ground the still more lovely Florence, with its everlasting works, and its inexhaustible riches. From the bold airy tower of the palace, rising like a slender mast, to Brunelleschi's wondrous dome of the Cathedral, from the old house of the Spini to the Pitti Palace, the most imposing the world has ever seen, from the garden of the Franciscan convent to the beautiful environs of the Cascine, all are full of incomparable grace. Each street of Florence contains a world of art; the walls of the city are the calyx containing the fairest flowers of the human mind; — and this is but the richest gem in the diadem with which the Italian people have adorned the earth.' (Leo).

*Florence*, Italian *Firenze*, formerly *Fiorenza*, from the Latin *Florentia*, justly entitled 'la bella', is situated in 43° 46' N. latitude, and 11° 15' E. longitude, on both banks of the *Arno*, an insignificant river except in rainy weather, in a charming valley of moderate width, picturesquely enclosed by the Apennines, the highest spur of which (*Monte Morello*, about 3000 ft.) rises to the N. On the S. the heights rise more immediately from the river, on the N. they are 3-4 M. distant, while towards the N.W., in the direction of Prato and Pistoja, the valley expands considerably. The sudden transitions of temperature which frequently occur here are trying to persons in delicate health. The pleasantest months are April, May, and the first half of June, September, October and November. In the depth of winter and the early spring bitterly cold winds often prevail, while in July and August the heat is very oppressive. On the whole, however, Florence is considered a healthy place.

In 1864, when Florence supplanted Turin as the capital of Italy, the enterprise of the citizens received a powerful stimulus; and although in 1870 the city was in its turn superseded by Rome, it still appears to enjoy the beneficial effects of its temporary dignity. It has now entirely laid aside its former character of a quiet provincial town, and has rapidly extended its precincts in every direction. As early as the 15th cent. Florence contained 90,000 inhab., in 1859 about 112,000, and now 167,093. The Florentines have ever been noted for the vigour of their reasoning powers and for their pre-eminence in artistic talent; and even at the present day their superiority over the Genoese and the in-

habitants of other towns of Lombardy is apparent from their manners and their dress.

HISTORY. Florence does not lay claim to very great antiquity. It was probably founded by the Romans in the first century B.C., under Sulla, and, as ancient records and some scanty ruins indicate, must at an early period have attained to considerable prosperity, owing to its highly favourable situation. The town was devastated by the incursions of the barbarian hordes during the dark ages, but revived about the beginning of the 11th century. In 1010 the Florentines conquered the ancient town of Fiesole, aided the Pisans in their contests with Lucca and Genoa, and took an active part in the feud which broke out about this period between the *Guelphs* and *Ghibellines*, the town generally supporting the cause of the pope against the imperial party. The most powerful families in the town, such as the *Buondelmonti*, were on the side of the Guelphs, in opposition to whom the *Uberti* for a brief period held the supremacy under Emperor Frederick II. After that monarch's death (1250), however, the Guelphs returned, and in 1283 a species of republic was constituted by the twelve guilds of the citizens, under twelve presidents (*priori*), the nobility being excluded. About the year 1300 the party struggles again burst forth between the same rival families, under the new names of the *Whites* and the *Blacks* (p. 306), in which the Guelphs (*Neri*) were eventually victorious, and the Whites, among whom was the poet Dante Alighieri, banished. King Robert of Naples then sent Count *Walter de Brienne*, Duke of Athens, to Florence as governor, and his authority for a time repressed the civic broils; but in 1343 he was expelled by the people, and a turbulent and lawless period of 70 years ensued, during which the power of the wealthy commercial family of the *Medici* gradually developed itself.

The founder of the Medici dynasty was *Giovanni de' Medici* (d. 1428). His son Cosmo was overthrown by the *Albizzi* in 1433, but returned after an exile of one year, and resumed the reins of government with almost princely magnificence. He employed his wealth liberally in the advancement of art and science, he was the patron of Brunellesco, Donatello, Michelozzo, Masaccio, and Lippi, and he founded the Platonic Academy and the Medici Library. Towards the close of his life he was not undeservedly surnamed *pater patrie* by his subjects. He was succeeded by his son *Pietro* in 1464, and in 1469 by his grandson Lorenzo, surnamed *Il Magnifico*, who, as a statesman, poet, and patron of art and science, attained a very high reputation. Florence now became the great centre of the Renaissance, the object of which was to revive the poetry, the eloquence, and the art and science of antiquity. Contemporaneously with the artists Luca Signorelli, D. Ghirlandajo, and the young Michael Angelo, the brilliant court of the Medici was graced by Landino, Ficino, L. Valla, Pico della Mirandola, and Poliziano, the earliest of modern philologists. The conspiracy of the *Pazzi* (1478), to which Lorenzo's brother *Giuliano* fell a victim, did not avail to undermine the power of this prince, but proved successful against his feeble son *Pietro II.*, who was banished in 1494, with his brothers *Giovanni* (afterwards Pope Leo X.) and *Giuliano*. Their property was confiscated, and Florence was occupied by Charles VIII. of France. *Hieronymus Savonarola*, the celebrated prior of S. Marco, soon afterwards founded his theocratic republic at Florence, but his career was terminated in 1498 by his death at the stake.

The intermediate supremacy of the Gonfaloniere *Pietro Soderini* now followed, but in 1512 the partisans of the Medici compelled him to abdicate, and recalled the brothers *Giuliano* and *Giovanni*. The former soon resigned his authority, the latter became pope, and they were succeeded by *Lorenzo*, a natural son of Pietro II., and the first of the illegitimate line of the Medici. The family was again banished in 1527, but Emp. Charles V., who had married his daughter to *Alessandro de' Medici*, attacked the town and took it in 1530 after a siege of eleven months, during which Michael Angelo, as engineer on the side of the republic, and his brave partisan Ferruccio greatly distinguished themselves. The emperor then appointed

Alessandro hereditary sovereign of Florence. The assassination of the latter, perpetrated by his own cousin Lorenzo, 7th Jan., 1537, did not conduce to the re-establishment of the republic. He was succeeded by *Cosmo I.* (1536-64), who entirely suppressed all political liberty in the city, but to some extent revived the fame of the Medici by his liberal patronage of art of every kind. (He was the founder of the *Accademia delle Belle Arti.*) Modern history, see p. 298.

**Art and Science.** The proud position occupied by Florence in the history of art and science was first established by *Dante Alighieri*, born here in 1265, author of the 'Divine Comedy', and the great founder of the modern Italian language. In 1302 he was banished with his party, and in 1321 died at Ravenna. *Giovanni Boccaccio*, the first expounder of the illustrious Dante, and celebrated for his 'Decamerone', which served as a model for the 'Canterbury Tales' of Chaucer, also lived at Florence. Florence, too, was the chief cradle of the school of the *Humanists* (15th cent.), who aimed at a universal and harmonious development of the personal character, and whose contemplative life was far exalted above every-day realities. This was the home of *Salutati*, *Leonardo Bruni*, and *Marsuppini*, the infidel, whose firmly moulded characters recall the personages of antiquity; it was here that the sources of classic literature were re-discovered by *Niccolò de' Niccoli*, *Traversari*, and other enthusiastic collectors of books; it was here that the Platonic Academy developed the study of the antique into a species of religious worship, and most of the humanists, including *Ficino*, *Poggio*, *Landini*, and *Pico della Mirandola*, who resided here for longer or shorter periods, enjoyed promotion and the highest distinction at Florence. Even after the decline of 'humanism' Florence continued to surpass the rest of Italy in intellectual culture, as the names of *Macchiavelli*, *Varchi*, *Gucciardini*, and *Gabileo* testify.

In the development of the FINE ARTS Florence has played so important a part, that her art history is in many respects nearly coincident with that of the whole of Italy. We therefore refer the reader to our prefatory article on the subject, and shall now merely direct his attention to those points which more specially concern Florence. In the 13th cent., when frequent changes of the constitution, and constantly recurring dissensions of factions, began to take place, and when private citizens for the first time manifested an interest in public life, a general taste for art gradually sprang up at Florence. With characteristic pride the Florentines proceeded to erect their cathedral, which was begun by *Arnolfo del Cambio* (1240-1311), and in the form of their *Palazzo Vecchio*, the restless aspect of their political life is distinctly reflected. The labours of *Cimabue* (1210?-1302?), and particularly those of *Giotto* (1276-1337) at length entitled Florence to be regarded as the headquarters of the Italian painting of the 14th cent., while the journeys undertaken by Giotto from Padua to Naples were the means of rendering his style predominant throughout the peninsula. Among Giotto's most distinguished pupils we may mention *Taddeo* and *Agnolo Gaddi*, *Andrea di Cione* (*Orgagna*, or *Orcagna*), who was also noted as an architect. *Spinello Aretino*, *Giottino*, and *Stefano*. After this school had flourished for nearly a century, the RENAISSANCE began to dawn in the 3rd decade of the 15th cent. While *Brunelleschi* (1379-1416) had adhered to the national traditions in his palatial architecture (*Palazzo Pitti*), he derived numerous suggestions for his churches from a study of the antique, particularly in the execution of details. His successors were *Leon Battista Alberti* (1405-72), *Michelozzo* (1391-1472), *Benedetto da Majano*, and *Cronaca*. Stimulated by the example of the humanists, the artists of this period aimed at versatility, and were not content to confine their labours to one sphere of art; so that we frequently hear of architects who were at the same time sculptors, and sculptors and goldsmiths who were also painters. Among the most distinguished Florentine sculptors of the Renaissance were *Luca della Robbia* (1400-82), who has given his name to the glazed reliefs in terracotta, *Lorenzo Ghiberti* (1378-1455), and above all *Donatello* (1386-1466), who exercised a great influence on the development of Italian sculpture, and is justly regarded as the precursor

of Michael Angelo. The energetic life and strong individuality of his figures are such, that their deficiency in gracefulness is well nigh forgotten. Beside these celebrated sculptors there were many of inferior reputation, who were fully occupied both here and at Rome in the execution of tombstones.

The pioneers of painting in the Renaissance period were *Paolo Uccello* (1397-1475), and *Masaccio* (1401-28), whose immediate successors were *Filippo Lippi*, the monk (1412-69), his son *Filippino Lippi* (1457-1504), and *Alessandro Botticelli* (1447-1510). The chief aims of the school were to master the technical intricacies of the art, to invest each figure with beauty, to arrange the groups harmoniously, and to cultivate a faithful portraiture of real life. The most famous representative of the school was *Domenico Ghirlandajo* (1449-94), whose chief rivals were *Cosimo Rosselli* (1430-1507), *Antonio* and *Piero Pollajuolo* (1441-89?), and *Andrea Verrocchio* (1435-88). In fervency of religious sentiment *Fra Angelico da Fiesole* (1387-1455), by whom *Benozzo Gozzoli* was afterwards influenced (p. 304), stands pre-eminent. The history of *Leonardo da Vinci*, *Michael Angelo Buonarroti*, and *Raphael*, the princes of Italian art, is not permanently associated with Florence, but their residence in this city exercised a material influence on their respective careers. *Leonardo* and *Michael Angelo* may be regarded as belonging to Florence owing to the completion of their studies there, and it was at Florence that *Raphael* supplemented his art education, and shook off the trammels of the Umbrian school. About 1506 the art history of Florence attained its most glorious period. *Leonardo*, *Michael Angelo*, and *Raphael* were then engaged here together, and with them were associated *Lorenzo di Credi* (1459-1537), a master closely allied to *Leonardo*, *Fra Bartolommeo* (1475-1517), an intimate friend of *Raphael*, and the talented colourist *Andrea del Sarto* (1487-1531), while the two last were rivalled by *Albertinelli*, *Franciabigio*, *Pontormo*, and *Ridolfo Ghirlandajo*. The union of the greatest masters at Rome, effected by *Julius II.* and *Leo X.*, at length detracted from the reputation of Florence, and the despotic sway of the Medici tended to check farther development. After the middle of the 16th cent. Florence produced no architecture worthy of note; among the sculptors the vulgar *Baccio Bandinelli* (1493-1560) may be mentioned solely on account of his failures as an imitator of *Michael Angelo*; and the province of painting, although cultivated with more success, now proved destitute of depth and independence. Florence was the chief headquarters of the mannerist imitators of *Michael Angelo*, the most eminent of whom were *Giorgio Vasari*, the well known biographer of artists (1511-74), *Angelo Bronzino*, and *Alessandro Allori*. In the 17th cent. the principal Florentine artists were *Luigi Cardi*, surnamed *Cigoli*, *Cristofano Allori* (1577-1621), *Furini*, and the somewhat insipid *Carlo Dolce* (1616-86). — The most distinguished sculptors of the present day are *Dupré*, the director of the school of sculpture, *Fantacchiotti*, and *Zocchi*, and the most eminent painters are *Stefano Ussi* and *Cassiole*.

Florence is situated on both banks of the *Arno*, but by far the greater part of the city lies on the right bank. On the latter, to the N. of the Ponte Vecchio, at some distance from the river, was situated the Roman town of *Florentia*, which however was extended at an early period in the middle ages to the opposite bank of the *Arno*. The walls of the city, which have recently been almost entirely removed, were constructed at the same time as the cathedral, between 1285 and 1388. The ancient GATES however have been spared, of which the following are the most interesting: *Porta alla Croce* (Pl. G, 5), erected in 1284, with frescoes by *Ghirlandajo*; *Porta S. Gallo* (Pl. F, 2), erected in 1330, once also adorned with frescoes by *Ghirlandajo*; *Porta Romana* (Pl. A, 6), erected in 1328 by *Jacopo Orcagna*; *Porta S. Frediano* (Pl. A, 3);



and *Porta S. Miniato* (Pl. D, 6). The NEW QUARTERS of the town are at the W. end, on the right bank of the Arno, extending as far as the Cascine (p. 363), and containing the best hotels and the residences of most of the English, American, and other visitors. A number of broad new streets (*Viale Vittorio Emanuele*, *Viale Principe Umberto*, *V. Filippo Strozzi*, *V. Principessa Margherita*, *V. Principe Amedeo*, *V. Principe Eugenio*, *V. Carlo Alberto*) have also been built on the site of the old fortifications, to the N. and E. of the *Porta S. Gallo*, extending as far as the Arno, and not yet entirely completed.

BRIDGES. The oldest of the six bridges which connect the banks of the Arno is the *Ponte alle Grazie* (Pl. D, 5, 6), constructed in 1235, the scene of the union effected between the Guelphs and Ghibellines in 1283. The *Ponte Vecchio* (Pl. C, 5; p. 375), which is said to have existed as early as the Roman period, and was reconstructed, after its repeated demolition, by Taddeo Gaddi in 1362, consists of three arches. The *Ponte S. Trinità* (Pl. C, 4; p. 371), was erected soon after 1567 in a substantial and handsome style by Bartolommeo Ammanati. The *Ponte alla Carraja* (Pl. B, C, 4), originally built in 1218, destroyed together with the *Ponte Vecchio* by an inundation in 1333, and restored in 1337, was again erected in 1559 by Ammanati by order of Cosmo I. Besides these, two *Suspension-Bridges* have recently been constructed, one at each end of the town (toll 5 c., carriages 42 c.).

The river is bordered on both sides by broad and handsome quays, called the LUNG' ARNO, of which the different parts are the *Lung' Arno Corsini*, the *Lung' Arno Soderini*, *Lung' Arno Nuovo*, etc. The busiest streets are the *Via Tornabuoni* (Pl. C, 4) and the *Via Catzajuoli* (Pl. D, 4).

The \**Piazza della Signoria* (Pl. D, 4, 5), with the *Palazzo Vecchio* and the *Loggia dei Lanzi*, once the forum of the republic, and the scene of its most momentous transactions, is still the principal centre of business. Savonarola and two other monks of his order, the Italian precursors of the Reformation, were burned at the stake here on 23rd May, 1498.

The \**Palazzo Vecchio* (Pl. 88), originally the seat of the *Signoria*, the government of the republic, subsequently the residence of Cosmo I., and now used as a town-hall, was erected in 1298 by *Arnolfo del Cambio*, and afterwards considerably altered by *Fioracinti*, *Michelozzo*, *Cronaca*, and *Vasari*. The tower, 308 ft. in height, is by Arnolfo. The original inscription over the door 'Jesus Christus Rex Florentini populi s. p. decreto electus' (1527), was altered by Cosmo I. to 'Rex regum et Dominus dominantium'. From 1504 down to 1873 the famous statue of David by *Michael Angelo*, which is now in the Academy (p. 361), stood to the left of the entrance. On the right is *Hercules and Cacus* by *Michael Angelo's* rival *Baccio Bandinetti* (p. 1v). The two insignificant

statues by *Bandinelli* and *Rossi* on each side of the entrance were used as chain-bearers.

The COURT, by *Michelozzo* (1454), contains a Boy with a fish as a fountain figure, by *Verrocchio*, and stucco decorations and frescoes (view of towns which formerly belonged to Austria) executed under the supervision of *Vasari*. At the back are Samson and a Philistine by *Rossi* (the latter being a caricature of Michael Angelo).

**Interior.** On the FIRST FLOOR is the GREAT HALL (*Sala del Consiglio, or dei Cinquecento*), constructed under the direction of Savonarola in 1495, which was to have been decorated with frescoes from the celebrated cartoons of the 'Cavalry Skirmish' by Leonardo, and the 'Bathing Soldiers' by Michael Angelo (1504). The walls and ceiling are now adorned with frescoes representing scenes from the history of the town and the Medici by *Vasari*, *Luca Giordano*, *Ligozzi*, *Cigoli*, and *Passignano*, and with stucco enrichments by *Donatello*. The hall was for a time used for the sittings of the Italian Chamber. To the left of the staircase is the SALA DEI DUGENTO (1411), with ceiling by *Michelozzo*. — On the SECOND FLOOR is the SALA DE' GIGLI, with beautiful door-posts in marble by *Benedetto da Majano*, to whom the intarsias of Dante and Petrarch on the wings of the door are also ascribed. The frescoes are by *Domenico Ghirlandajo* (?) or by *Sebast. Mainardi*. The SALA D'UBIENZA contains frescoes by *Salviati*. Then the CAPPELLA DE' PRIORI S. BERNARDO, with a ceiling painted in imitation of mosaic by *Rid. Ghirlandajo*, and a crucifix over the altar attributed to *Giov. da Bologna*. — Lastly, six rooms which were formerly the PRIVATE APARTMENTS OF THE MEDICI (Sala di Leone X., Cosimo il Vecchio, Lorenzo il Magnifico, Clemente VII., Giovanni delle Bande Nere, and Cosimo I.), adorned with frescoes of the school of *Vasari*. The paintings in the fifth room are of a grotesque character; the sixth contains good frescoes by *Bronzino* (Passage of the Red Sea, and the Brazen Serpent). A room beyond these is adorned with grotesque scenes by *Pocetti*. We now return to the Sala de' Gigli, to the E. of which lies the *Sala delle Carte Geografiche*.

At the N. corner of the edifice is a lion in marble, a modern copy of the original in bronze by *Donatello*, known as *Il Marzocco*, and now preserved in the Museo Nazionale. To the left is the \* *Great Fountain* with Neptune and Tritons, erected by *Bartolommeo Ammanati* under Cosmo I. (1564-75). Adjoining it is the *Equestrian Statue of Cosmo* in bronze, with bas-reliefs, by *Giovanni da Bologna*, 1594. — In the S. angle of the Piazza rises the —

\* **Loggia dei Lanzi** (Pl. 53; D. 5), or more properly *Loggia dei Signori*, an open hall of the kind with which it was usual to provide both the public and private palaces of Florence, in order that the inmates might enjoy the open air, or participate in public demonstrations, without being obliged to descend to the street. This structure was projected in 1356, having perhaps been designed by *Andrea di Cione (Orcagna)*, but was not erected till 1376. *Benci di Cione Dami* and *Simone di Talenti* are said to have been the architects. The style of the architecture shows a falling off from the Gothic, while the sculptures (Faith, Hope, Charity, Temperance, and Fortitude, by *Agnolo Gaddi*, 1383) exhibit an incipient leaning to the Renaissance forms. The present name of the loggia dates from the time of the Grand Duke Cosmo I., when his spearsmen or 'lancers' were posted here as guards.

By the STEPS are two lions; that on the right is antique, the other by *Flaminio Vacca*. — Under the arches, to the right, is the 'Rape of the

Sabines, a group in marble executed by *Giovanni da Bologna* in 1583; on the left *Perseus* with the head of the *Medusa*, in bronze, by *Benvenuto Cellini* (1553), who also executed the statuettes and bas-reliefs of the pedestal; behind it the *Rape of Polyxena*, a large group in marble by *Fedi*, erected in 1866. To the left of the latter, *Judith* and *Holofernes* in bronze, by *Donatello*. In the centre a *Warrior* supporting a dead man, usually supposed to represent *Ajax* with the body of *Patroclus* or *Achilles*, an ancient copy of a Greek work, brought here from Rome in 1570. To the right of it, *Hercules* slaying the centaur *Nessus*, in marble, by *Giov. da Bologna*; by the wall at the back are six large draped female statues, of which the third from the left represents the so-called *Thusnelda*, from *Trajan's Forum* at Rome.

To the left, behind the equestrian statue of *Cosmo*, mentioned at p. 333, is the *\*Palazzo Uguccioni* (Pl. 87), erected in 1550, from designs variously attributed to *Raphael*, *Michael Angelo*, and *Pal-ladio*. — On the W. side of the piazza rises the handsome new *Palazzo Lavisch*, by *Landi* (1871).

Between the *Pal. Vecchio* and the *Loggia de' Lanzi* begins the **Portico degli Uffizi** (Pl. 86; D, 5), erected 1560-74 by *Giorgio Vasari*, the niches of which were adorned with *\*Marble Statues* of celebrated Tuscans in 1842-56. The names of the persons represented and of the respective sculptors are engraved on the bases.

They are as follows, beginning on the left: *Andrea Orcagna* (d. 1368); behind it, on each side of the first door, *Cosmo, 'pater patrie'* (d. 1464), and *Lorenzo 'il Magnifico'* (d. 1492); then *Niccolò Pisano* (d. about 1280); *Giotto* (d. 1334) by *Dupré*, 1854; *Donatello* (d. 1466); *Leon Batt. Alberti* (d. 1472); *Leonardo da Vinci* (d. 1519); *Michael Angelo* (d. 1564); *Dante* (d. 1321); *Petrarch* (d. 1374); *Boccaccio* (d. 1375); *Macchiavelli* (d. 1527), by *Bartolini*, 1846; *Gnicciardini* (historian, d. 1540), *Amerigo Vespucci* (who gave his name to America, d. 1514); *Galileo* (d. 1642); *Pier Antonio Micheli* (botanist, d. 1751); *Franc. Redi* (poet and physician, d. 1698); *Paolo Mascagni* (physiologist, d. 1815); *Andrea Cesalpino* (anatomist, d. 1604); *S. Antonino* (theologist, d. 1459), by *Dupré*, 1854; *Accorso* (jurist, d. 1260); *Guido Aretino* (musician, 11th cent.); and *Benvenuto Cellini* (d. 1571). — In the external niches, towards the Arno, *Francesco Ferrucci* (d. 1530), *Giovanni delle Bande Nere* (d. 1526), *Piero Capponi* (d. 1496), and *Farinata degli Uberti* (d. 1264); above is *Cosmo I.*, by *Giov. da Bologna*, with *Justice* and *Power*, on the side, by *Danti*.

Opposite the first mentioned statues is the *Post Office* (Pl. 96), formerly the *Mint*.

Approaching from the *Piazza della Signoria*, we enter by the second door to the left under this portico, and ascend by a staircase of 126 steps to the *\*Galleria degli Uffizi* (open on Sund., and from April to Nov. on Thursd. also, 11-3, gratis; on other days, 9-3, admission 1 fr.). The gallery originated with the *Medici* collections, to which numerous additions were made by the *Lorraine* family, and it is now one of the best in the world, both in extent and value. A few of the finest objects only in this vast collection are here enumerated. Those who have time for a brief visit only should first walk through the corridors, in order to become acquainted with their topography, and then return to the *\*Tri-buna*, the gem of the whole gallery. Permission to copy is easily obtained by addressing a written application to the directors. The



Thus the predelle (No. 1294) of *Fra Angelico's* frequently copied winged picture of the Madonna and angels (No. 17) are more interesting than the principal picture itself. Among the FLORENTINE works of the 15th cent. we may first mention *Filippo Lippi's* Madonna and two angels (1307), and four works of *Sandro Botticelli*: a round picture of the Madonna (1267 bis), the Adoration of the Magi (1286), so much extolled by Vasari, and, as specimens of other subjects, his Venus (39), and his Calumniation of Apelles (1182). *Filippino Lippi's* Madonna and saints (1268) attract attention owing to its size and clear colouring, and his Adoration of the Magi (1257), with its numerous figures, is interesting on account of the portraits it contains. The best of the early masters was *Domenico Ghirlandajo*, whose beautiful round picture of the Adoration of the Magi (1295), and the Madonna with saints (1297), are remarkable for the excellence of the composition, and the harmony of colouring. The mythological works of *Pier di Cosimo* (21, 28, 38, 1246) betray a taste for fantastic subjects, from which Leonardo himself was not entirely free. A very important work, though unfinished, is *Fra Bartolommeo's* Madonna enthroned (1265), with its masterly grouping. Another very effective picture, notwithstanding its unfinished condition, is *Leonardo's* rich composition of the Adoration of the Magi (1252). The gallery also contains the Visitation of Mary (1269), the master-piece of *Albertinelli*, and several pictures by *Ridolfo Ghirlandajo* (1275, 1277), which show that very able works were produced during the golden era of art even by masters of second-rate importance. *Sodoma's* St. Sebastian (1279) also ranks as one of the finest creations of Italian art. — Among the works of the other Italian Schools the most notable are *Mantegna's* Madonna among the rocks (1025), and among the numerous Venetian works *Titian's* Flora (626), three works by *Giorgione* (621, 630, 631), and a number of portraits.

The collection is also rich in works of northern origin, the better of which, in spite of the proximity of the more studied Italian pictures, maintain their peculiar charm owing to their depth of colouring, and their unsophisticated realism. The finest works of VAN EYCK'S SCHOOL are a small Madonna by *Memling* (703), and an Entombment by *Roger van der Weyden* (795). The Man praying (769) is either by Memling or *Hugo van der Goes*, and the two portraits (749) are variously attributed to the latter and to *Petrus Cristus*. Among the principal GERMAN masters, *Dürer* is represented by a portrait of his father (766), two heads of Apostles (768, 777), and an unattractive Madonna (851). *Holbein's* portrait of Richard Southwell, dating from 1537 (No. 765), is an admirable work, but the portrait of himself, which was originally a slightly coloured charcoal drawing only, has been painted over and much altered. The NETHERLANDS SCHOOL of the 17th cent. is also represented by several excellent works. Among those by *Rubens* are a small picture of Venus and Adonis, with a landscape by *J. Breughel*, the portrait of his first wife (197), and two pictures of scenes from the life of Henry IV. (140, 147). The best of *Rembrandt's* works preserved here are the two portraits of himself (451, 452, the one in the dressing-gown probably alone original), and a small Holy Family (922). The Dutch genre-painters have also enriched the gallery with several important and well preserved works, such as *Ger. Dow's* Apple woman (926), and the Schoolmaster (786), *Fr. Mieris's* Charlatan (854), and the large family portrait (981), *G. Metsu's* Lady and Hunter (972), and *Jan Steen's* Family feast (977). Among the portraits of the painters those by the Netherlands masters unquestionably occupy the highest rank. The modern portraits of the painters placed here show how sadly this branch of art has fallen off since the 17th cent.

#### FIRST VESTIBULE:

Busts of members of the Medici family. Bronze statues of Mars and Silenus, the latter with the infant Bacchus in his arms, a copy of the original at Rome. Various Roman reliefs with representations of processions and sacrifices (almost all the heads modern).

## SECOND VESTIBULE:

Two pillars with trophies in relief; busts of Cybele and Jupiter. A horse, \*two dogs, a \*wild boar, and a torso of Apollo, all antiques.

## E. CORRIDOR,

178 yds. in length, adorned with mythological ceiling-paintings by *Bernardino Poccetti*. On the upper part of the walls are 534 portraits of princes and great men, begun under Cosmo I., and frequently added to. On each side are arranged antique busts, statues, and sarcophagi, above which are pictures. Proceeding to the right from the entrance, and beginning at the end, we observe the following objects:

ANCIENT SCULPTURES IN MARBLE: \*35. Agrippina sitting; 39. Sarcophagus with representations from the life of a Roman (from which Raphael borrowed the sacrificial scene for his tapestry); 38. Hercules slaying Nessus (almost entirely modern); 41, 47, \*48. Busts of Cæsar (with bronze head), Augustus, and Marcus Agrippa; 49. Julia, daughter of Augustus; 52. Athlete; 62. Sarcophagus with the Dioscuri; 71. Portrait of a child (Nero?); 74. Pompona (head and extremities restored in the early Renaissance period); 75. Beautiful statue of an athlete (the 4th of those so designated), a copy of the celebrated Doryphorus of Polyklethus; \*76. Julia, daughter of Titus; 80. Vitellius; 85. Vespasian; 90. Vestal Virgin with portrait features; 103. Plotina, wife of Trajan; 108. Hadrian. Also a collection of Roman sarcophagi: 45. Rape of Proserpine; 56. Hippolytus; 68, 72. Labours of Hercules; 95-105. Hunt of Meleager; 80. Apollo and the Muses; etc.

PICTURES: 1. *Andrea Rico* (d. 1105), Madonna and Child; 2. *Cimabue* (? or rather *School of Giotto*), St. Cecilia; \*6. *Lorenzo Monaco* (erroneously attributed to *Giotto*), Christ on the Mt. of Olives; 7. *Giottino*, Descent from the Cross; 9. *Simone di Martino* and *Lippo Memmi* (of Siena), Annunciation with lateral pictures (10. S. Giulietta, S. S. Ansano); 12. *School of Pietro Lorenzetti* (of Siena), Hermit saints of the wilderness of Thebes; 14. *Agnolo Gaddi*, Annunciation with predella; 15. *Tuscan School of the 15th Cent.*, Coronation of the Virgin; \*17. *Fra Angelico da Fiesole*, Tabernacle with gold ground, on the outer leaves St. Mark and St. Peter, in the centre St. Mark, John the Baptist, and Madonna with the Child, surrounded by angels playing on instruments; 18. *Bicci di Lorenzo*, SS. Cosmas and Damianus (1429); 20. *Lorenzo Monaco*, Adoration of the Magi; 21. *Pier di Cosimo*, Marriage of Persens, Phinens turned into stone on looking at the head of the Medusa; \*24. *Lor. di Credi*, Madonna, worshipping the Child; (no number) *Alessio Baldovinetti*, Annunciation; 27. *Vecchietta* (School of Siena), Madonna and saints; 28. *Pier di Cosimo*, Sacrifice in the temple of Zeus for the liberation of Andromeda; 29. *Paolo Uccelli*, Cavalry battle (1430); 23. *S. Botticelli*, Madonna (ill-preserved); 30. *S. Botticelli* (not *Pollajuolo*), Portrait; 31. *Baldovinetti*, Madonna and saints; 32. *Piero di Cosimo*, Portrait; 34. *Lorenzo di Credi* (?), Portrait; 36. *Luca Signorelli*, Madonna and Child, in the background nude shepherds; 37. *Rodolfo Ghirlandajo* (not *Raffaellino del Garbo*), Madonna with Christ and St. John; 38. *Pier di Cosimo*, Liberation of Andromeda; 39. *Botticelli*, Birth of Venus; 55. *Jacopo da Empoli*, Creation of Adam; 62. *Cigoli*, Magdalene; 64. *Francesco Boschi*, Call of St. Andrew.

## S. CONNECTING PASSAGE,

with similar decorations and contents, among which are the following fine antiques: 125 and 127. Sleep; 129. Sarcophagus with the fall of Phæton; 132. Annus Verus; 138. Thorn-extractor; 137. Round altar with bas-reliefs, representing the Sacrifice of Iphigenia, bearing the name of Cleomenes; 139. Marcus Aurelius; \*141. Pedestal of a candelabrum, the upper part Greek; 144. Lucius Verus; 145. Venus stooping in the bath; 146. Nymph loosening her sandal, restored as a counterpart of No. 138, and called the *Venere della Spina*.

## W. CORRIDOR,

of the same length as that on the E., adorned with frescoes representing the rise of art, and with portraits of celebrated Florentines. At the en-

trance, 155, 156. Statues of Marsyas, antique, both restored (the upper part of No. 156 by Donatello); 167. Albinus (in alabaster); 168. Caracalla; 169. Discobolus, after Myron, erroneously restored; 208. Satyr, freely restored by Michael Angelo; 365. Altered copy of the Laocoon, by *Baccio Bandinelli*. In front of it (no number), Sleeping Cupid in basalt.

Returning hence, and passing through the second door to the left of the entrance, we next reach the octagonal —

\*<sup>o</sup>TRIBUNA,

containing a magnificent and almost unparalleled collection of masterpieces of ancient sculpture and modern painting. The hall was constructed by *Bernardo Buontalenti*; the decorations are by *Bernardino Poccetti*. In the centre are placed five very celebrated marble sculptures: \*Satyr playing on the cymbal, restored by *Michael Angelo*; group of the \*Wrestlers, found with that of the Children of Niobe; \*Medici Venus, found in the 16th cent. in the Villa of Hadrian near Tivoli, brought to Florence in 1680, under Cosmo III., with Greek inscription designating *Cleomenes*, son of Apollodorus, as the master; the \*Grinder, supposed to be a Scythian from the group of Marsyas who is being flayed, found at Rome in the 16th cent.; the \*Apollino, or young Apollo, of the school of *Praxiteles*.

Paintings, beginning on the left: \*1131. *Raphael*, Pope Julius II., a replica of the original in the Pitti Palace (p. 377); 1133. *A. Caracci*, Pan and Bacchante; 1135. *B. Luini*, The daughter of Herodias with the head of the Baptist; \*\*1129. *Raphael*, Madonna and Child with the cardinal (small grey bird with red crest); 1130. *Fra Bartolommeo*, Job; \*1127. *Raphael* (copy?), The young St. John; 1128. *Van Dyck*, Emp. Charles V.; \*1125. *Giuliano Bugiardini* (d. 1554), formerly attributed to *Raphael*, Madonna at the well; 1126. *Fra Bartolommeo*, Isaiah; \*1123. *Sebastiano del Piombo*, Portrait, formerly called the Fornarina, and attributed to *Raphael*; \*1124. *Franc. Francia*, Portrait of Evangelista Scappi. Over the door: 1122. *Perugino*, Madonna with SS. John and Sebastian (1493); \*1120. *Raphael*, Female portrait; \*1121. *Mantegna* (? or, according to Sign. Cavalcaselle probably *Costa* or *Buonsignori*), Elizabeth of Mantua; \*1118. *Correggio*, Repose on the Flight to Egypt; 1119. *Baroccio*, Duke Francis Maria II. of Urbino; 1116. *Titian*, Archbishop of Ragusa (1552); \*1117. *Titian*, Venus; 1114. *Guercino*, Sibyl of Samos; 1115. *Van Dyck*, Jean de Montfort; 1113. *Guido Reni*, Madonna; \*1111. *Mantegna*, Altar-piece, representing the Adoration of the Magi, the Circumcision, and the Resurrection; \*1112. *A. del Sarto*, Madonna with SS. John and Francis; 1110. *Orazio Alfani*, Holy Family; 1109. *Domenichino*, Cardinal Agucchia; 1107. *Daniele da Volterra*, Massacre of the Innocents; 1108. *Titian*, Venus; 1106. *G. Lanfranchi*, St. Peter; 1104. *Spagnoletto*, St. Jerome; 1105. *Schidone*, Holy Family. Over the door: 1145. *Lod. Caracci*, Rebecca and Eleazar; 1144. *Giulio Romano*, Madonna; \*1141. *A. Dürer*, Adoration of the Magi; 1142. *Cranach*, Adam; \*1139. *Michael Angelo*, Holy Family; 1140. *Rubens* (copy?), Venus and Minerva contending for a youth; 1137. *Guercino*, Endymion; 1138. *Cranach*, Eve; \*1134. *Correggio*, Madonna; \*1136. *Paolo Veronese*, Holy Family.

The door to the left (when approached from the corridor) leads from the Tribuna to the —

TUSCAN SCHOOL.

I. SALOON: 1146. *Lor. di Credi*, Annunciation; 1150. *Lor. di Credi*, Christ appearing to Mary Magdalene; 1152. *Fra Bartolommeo*, God the Father (a sketch); 1153. *Ant. Pollajuolo*, Contests of Hercules with Antæus and the Lernean hydra; 1158. *S. Botticelli*, Death of Holophernes; 1156. *S. Botticelli*, Judith; 1157. Portrait, 1159. Head of the Medusa (the latter executed after the time of Vasari), both erroneously attributed to *Leon. da Vinci*; 1161. *Fra Bartolommeo*, Nativity and Circumcision of Christ (about 1500); 1162. *Fra Angelico da Fiesole*, Birth of John the Baptist; 1163. *Lor. di Credi*, Portrait of Verrocchio; \*1167. *Fra Filippo Lippi* (?), Portrait of an old man (fresco); \*1169. *Andrea del Sarto*, Portrait; \*1176.

*A. del Sarto*, Portrait of himself; 1178. *Fra Angelico*, Spozalizio; 1179. *Filippino Lippi*, St. Augustine; 1182. *Sandro Botticelli*, The slander, from the description by Lucian of a picture of Apelles; 1184. *Fra Angelico*, Death of Mary; 1213. *Alessandro Allori*, Christ on the Cross (from a drawing by Michael Angelo); 1217. *Lor. di Credi* (? *Perugino*), Portrait of a youth; 1224. *Giustiano Bugiardini* (not *Ghirlandajo*), Madonna; 1235. *Fra Bartolommeo*, Madonna and Child (unfinished); 1246. *Piero di Cosimo*, Perseus releasing Andromeda; 1248. *Baccio Bandinelli* (the sculptor), Portrait of himself. — II. SALOON: 1250. *Piero di Cosimo*, Conception; \*1252. *Leonardo da Vinci*, Adoration of the Magi (unfinished); 1254. *Andrea del Sarto*, St. James and two children in monks' cowls; 1257. *Filippino Lippi*, Adoration of the Magi, with portraits of the Medici (1496); \*1259. *Albertinelli*, Visit of Mary to Elizabeth; \*1265. *Fra Bartolommeo*, Virgin with the tutelary saints of Florence (unfinished); 1267. *Pontorno*, Portrait of Cosmo de' Medici ('pater patriæ'); 1267bis. *S. Botticelli*, Madonna and Child with four angels; 1268. *Filippino Lippi*, Madonna with saints (1485); 1271. *Bronzino*, Christ in Hades (1552); 1275. *Ridolfo del Ghirlandajo*, St. Zenobius, bishop of Florence, resuscitating a dead child, and 1277. Transference of the remains of St. Zenobius to the cathedral; 1276. *Cigoli*, Martyrdom of St. Stephen; \*1279. *Sodoma*, St. Sebastian; 1280. *Granacci*, Madonna della Cintola (with the girdle); 1284. *Pontorno*, Venus (from a design by Michael Angelo).

\*HALL OF THE ANCIENT MASTERS.

1286. *S. Botticelli*, Adoration of the Magi, with portraits of Cosmo de' Medici, his son Giovanni, and his grandson Giuliano; 1287. *Lorenzo di Credi*, Mary adoring the Child; \*1288. *Leonardo da Vinci*, Annunciation (an early picture of the master; heads inferior to those of his later works); 1289. *S. Botticelli*, Madonna; 1290. *Fra Angelico*, Coronation of the Virgin (generally placed in the preceding room for the use of copyists); \*1291. *Luca Signorelli*, Holy Family; \*1294. *Fra Angelico*, Predella to No. 17, Adoration of the Magi, Preaching of St. Peter, and Martyrdom of St. Mark; 1295. *Dom. Ghirlandajo*, Adoration of the Magi (a replica in the Palazzo Pitti, No. 358); \*1297. *Dom. Ghirlandajo*, Madonna enthroned, a work of the master's best period; 1298. *L. Signorelli*, Predella; 1299. *S. Botticelli*, Virtus; \*1300. *Piero della Francesca*, Portraits of the Duke and Duchess of Urbino (on the back triumphal processions in a landscape); \*1301. *A. Pollajuolo*, SS. Eustace, and Vincent; \*1303. *S. Botticelli*, Madonna; 1305. *Dom. Veneziano*, Madonna and saints; \*1306. *Pollajuolo*, Virtus; \*1307. (over the door) *Fra Filippo Lippi*, Madonna adoring the Child. — We retrace our steps, pass through the Tribuna, and enter the —

VENETIAN AND LOMBARD SCHOOL.

On the right: 1043. *Massari*, Madonna; 1058. *Trevisani*, Holy Family; 1060. *Tintoretto*, Portrait; 1064. *Canaletto*, Palace of the Doges at Venice (badly preserved); 1068. *P. Veronese*, Head as a study; 1074. *Francesco Solimena*, Diana and Calisto; 1077. *Canaletto*, The Grand Canal at Venice; 1078. *Parmegianino*, Portrait; 1095. *Marco Palmazzani* of Forli, Crucifixion; 990. *Albano*, Venus with Cupids; \*995. *Dosso Dossi*, Murder of the Innocents; 998. *Guido Reni*, Madonna with Jesus and John; 1000. *Alessandro Turchi*, Allegory from the baptism of Giovanni Cornaro of Verona; 1002. *Titian* (? or, as Morelli thinks, an early work of *Correggio*), Madonna; 1003. \*1005. *Salvator Rosa*, Landscapes; 1007. *Annibale Caracci*, Madonna; 1012. *Salvator Rosa*, Landscape; 1013. *Luini*, Madonna; 1015. *Paolo Veronese*, Madonna (a sketch); 1019. *Palma Vecchio* (?), Madonna; \*1025. *Mantegna*, Madonna in a rocky landscape; 1029. Adoration of the Magi by an unknown master; 1031. *Caravaggio*, Head of the Medusa; 1037. *Andrea Schiavone* (according to Mr. Crowe, and not *Palma Vecchio*), Jesus at Emmaus; 1038. *Garofalo*, Annunciation.

DUTCH SCHOOL.

On the right: 922. *Rembrandt*, Holy Family (a replica in the Louvre); 928. *Pieter Breughel*, Landscape; 926. *Gerard Dow*, Apple-woman;



934. *Schalken*, Seamstress; 935. *D. van Berghem*, Landscape with cattle; 941. *F. Mieris*, Woman asleep; 945. *Mieris*, Supper; 950. *C. Netscher*, Portraits of the painter and his family; 952. *Mieris*, Wooing; 954. *Mieris*, The drinkers; 955. *Brouwer*, Tavern-scene; 958. *Terburg*, Lady drinking; 960. *Paulyn*, Miser; 964. *C. Netscher*, Cook; 965. *Hemskerck*, Card-players; \*972. *Metsu*, Lady and huntsman; \*976. *F. Mieris*, Portrait of himself; 977. *Jan Steen*, Family feast; \*979. *Rembrandt*, or *Philip Koninck*, Landscape; 978. *Ostade*, Man with lantern; 981. *F. Mieris*, Portrait of the painter and his family (1675); 854. *Mieris*, Quack; 871. *Paul Brill*, View of a château; \*882. *J. Ruysdael*, Landscape with cloudy sky; 885. *Van der Neer*, Landscape; 888. *Slingeland*, Children blowing soap-bubbles; 892. *P. Breughel*, Christ bearing the Cross; 895. Portrait of Emp. Ferdinand I. when a young man, master unknown; 897. *Berkheyden*, Cathedral of Haarlem; 918. *G. Metsu*, Lute-player.

## FLEMISH AND GERMAN SCHOOLS.

I. SALOON. To the right: 812. *Rubens*, Venus and Adonis; 845. *Cranach*, Electors John and Frederick of Saxony; 847. *Cranach*, Luther and Melancthon; 848. *Claude Lorrain*, Landscape; 851. *Dürer*, Madonna; 764. *B. Denner*, Portrait; \*765. *Holbein the Younger*, Richard Southwell; \*766. *Dürer*, Portrait of his father (1490); 768. *Dürer*, The apostle Philip; 769. *Memling*, Man praying; 772. *Adam Elzheimer*, Landscape; \*774. *Claude Lorrain*, Sea-piece with the Villa Medici at Rome; 777. *Dürer*, St. James the Great; 778. *Memling*, St. Benedict; 780. *Roger van der Weyden* (?), Portrait; 783. *Van Dyck*, Madonna; 784. *Holbein*, Zwingli; \*786. *G. Dou*, Schoolmaster; \*793. *Elzheimer*, Landscape with a scene from the myth of Cupid and Psyche; \*795. *Rogier van der Weyden*, Entombment; 799. *Holbein* (?), Sir Thomas More; 800. *Schalken*, Girl with a candle. — In the II. SALOON eight good pictures from the lives of SS. Peter and Paul, by *Johann Schuffelein* of Nuremberg. To the right: 744. *Nic. Frumentii* (perhaps the German Meister Korn), Tabernacle with the Raising of Lazarus; 749. *Petrus Cristus*, Two portraits (the portrait of the woman damaged); \*751. *L. Cranach*, St. George; 761. *Jan Breughel*, Landscape, forming the cover of a green drawing of the \*Crucifixion relieved with white by *A. Dürer* (1505), with a copy in colours by *J. Breughel*; 698. *Van der Goes* (?), Madonna; 700. *Teniers the Younger*, Love-scene; \*703. *Memling*, Madonna; 705. *Teniers the Elder*, Physician; 706. *Teniers the Younger*, St. Peter weeping; 710. *Adr. Stalbert*, Landscape; 738. *Paul Brill*, St. Paul in the wilderness.

## FRENCH SCHOOL.

This saloon contains numerous battle-pieces by *Bourguignon*, *Parrocel*, and *Gagneraux*, and a beautifully inlaid table. To the right: 679. and 689. Portraits of the poet Vittorio Alfieri and the Countess of Albany (b. 1763. d. at Florence 1824), by *Fabre de Montpellier*, with two autographs by Alfieri on the hack; 680. *Nic. Poussin*, Theseus at Troezen; 674. *Larguillière*, Rousseau; 672. *Grimoux*, Young pilgrim; \*667. *Clouet*, Francis I. on horseback; 671. *Watteau*, Garden-scene; 682. *Clouet*, Portrait.

Then to the left in the corridor is the —

## CABINET OF THE GEMS

(when closed, apply to one of the custodians), a saloon borne by four columns of oriental alabaster and four of verde antico, with six cabinets containing upwards of 400 gems and precious stones, once the property of the Medici. The 1st, 3rd, 4th, and 6th cabinets each contain two small columns of agate and rock crystal. In the 1st cabinet on the right a vessel of lapis lazuli; two bas-reliefs in gold on a ground of jasper, by *Giovanni da Bologna*. 2nd: Two goblets of onyx, with the name of Lorenzo de' Medici; \*casket of rock-crystal with 24 scenes from the life of Christ, executed by *Valerio Belli* for Pope Clement VII.; \*portrait of the grand-duke Cosmo III., in Florentine mosaic, of 1619; three bas-reliefs in gold on a ground of jasper, by *Giovanni da Bologna*; two vases of rock-crystal, that on the left quite unfinished. 3rd: Cover of a crystal vase, in enamelled gold, executed for Diana of Poitiers, with her cipher and half-

moons. The glass-cabinets by the window contain cameos of the 17th cent. 4th: Vase of jasper with lid, on which stands the figure of a warrior in gold adorned with diamonds. Venus and Cupid in porphyry, by *Maria da Pescia*. 5th: Basrelief in gold and jewels, representing the Piazza della Signoria, by *Gasparo Mola*. Fantastic vase with a \*Hercules in massive gold upon it, by *Giov. da Bologna*. 6th: Vase of rock-crystal, by *Benvenuto Cellini*. In the centre of the room a table with a view of the old harbour of Leghorn in Florentine mosaic.

° TWO SALOONS OF THE VENETIAN SCHOOL.

I. SALOON. Right: 571. *Giorgione* (? or *Fr. Caroto*), Portrait; 576. *Titian*, Portrait of Sansovino; 583. *Giov. Bellini*, Pietà (unfinished); 584. *Cima da Conegliano*, Madonna; °585. *Pordenone* (?), Portrait; 586. *Moroni*, Portrait; 589. *Paolo Veronese*, Martyrdom of St. Justina (sketch); 596. *P. Veronese*, Esther in presence of Ahasuerus; 595. *Jacopo da Ponte*, surnamed *Bassano*, Portraits of the painter's family; °599, 605. *Titian*, Portraits of the Duke and Duchess of Urbino; 607. *Paris Bordone*, Portrait. — II. SALOON. Right: °609. *Titian*, Battle between Venetians and Imperial troops; 613. *Paris Bordone*, Portrait; 614. *Titian*, Giovanni de' Medici (father of Cosmo I.); 615. *Tintoretto*, Portrait; 616. *Pordenone*, Conversion of S. Paul; 618. Copy of *Titian's* Pesaro Madonna, begun only (p. 236); 619. *Palma Vecchio*, Judith; °621. *Giorgione*, Moses when a child undergoes the fire ordeal; 622. *Giorgione* (?), Maltese knight; 623. *Palma Vecchio*, Madonna with SS. Magdalene, Joseph, and John; °°626. *Titian*, The so-called 'Flora' (*Palma Vecchio's* daughter); 627. Bust, portrait of a bearded man, erroneously ascribed to *Seb. del Piombo*; 628. *Bonifazio*, Last Supper; 630. *Giorgione*, Judgment of Solomon (damaged); °631. *Giorgione*, Madonna receiving the homage of saints in a landscape; °633. *Titian*, Madonna and Child with the youthful St. John and S. Antonio Eremita; 636. *P. Veronese*, Crucifixion; 638. *Tintoretto*, Portrait of Sansovino; 645. *Savoldo*, Transfiguration; 648. *Titian*, Catharina Cornaro, Queen of Cyprus (a copy); °650. *Palma Vecchio* (?), Mathematician.

Two short Corridors lead hence to the Cabinet of Engravings and Drawings (Director, Professor Pini), and the Collection of Coins (the latter not shown without a special permesso).

WOODCUTS, ENGRAVINGS, DRAWINGS (*Passage to the Pitti Palace*).

(The visitor is recommended to pass over this part of the gallery at present, and to visit it when on his way to the Pitti Palace in connection with the other collections. Those who have left their sticks or umbrellas at the entrance to the Uffizi must of course return for them after visiting the Pitti Palace on the other side of the Arno.)

A staircase descends to the I. SALOON, containing early Italian woodcuts (with and without colouring). — II. SALOON: Engravings down to *Marc Antonio*, a *Mantegna* opposite the door worthy of notice (engraving of the picture in the Tribuna). — A staircase descends hence to a long CORRIDOR which leads over the Ponte Vecchio to the Palazzo Pitti, a walk of nearly 10 min. First, parallel with the Arno, left side: Engravings of *Marc Antonio* and his school, then *Corneille Cort* and his pupils; right side (going back), Roman school of the 16th and 17th cent., Tuscan masters of the 16th-18th cent., then N. Italian, German, and Dutch masters down to the present time (each plate bears the name of the painter and engraver). The passage turns to the left over the Ponte Vecchio; on the right and left, and in stands in the middle, is an admirable collection of °DRAWINGS, founded by Cardinal Leopold de' Medici, and afterwards much extended, now numbering about 30,000. All those which are exhibited to view bear the names of the masters. A few of the most important only are here enumerated: Right wall: *School of Giotto* (*Taddeo Gaddi*), *Fra Angelico*, *Luca della Robbia*, *Masaccio*, °*Fra Filippo Lippi* (sketch of the picture No. 1307 in the Uffizi), °*Dom. Ghirlandajo*, *Pollajuolo*, °*Mantegna* (Madonna worshipping, Judith and Holofernes), °*Perugino*, *Garofalo*, °*Leonardo da Vinci* (24 drawings, admirable heads,

lion fighting with a dragon), *Fra Bartolommeo*, *Lorenzo di Credi*, *Raphael* (37 drawings, Entomhment, sketch of the picture No. 1127 in the Trihuna, the Plagne, etc.), *Francia*, *Giulio Romano*, *Sodoma*, *Giovanni Bellini*, *Michael Angelo* (21 drawings, sketch for the monument of Julius II., sketch for the cartoon of the soldiers hathing, etc.), *Sebastiano del Piombo*, *Andrea del Sarto*. On the end-wall, *Correggio* and *Giorgione*. On the left wall (going back): *Bandinelli*, *Titian* (chiefly landscapes), *P. Veronese*, *Tintoretto*, the *Caracci*, etc., down to *Salvator Rosa*. Then *Burgkmayer*, *Swanevelt*, *Velasquez*, *Murillo*, *Poussin*, *Van der Weijden*, *Albert Dürer* (No. 243-64). In the 1st Stand: *Francia*, *Van Dyck*, etc.; 2nd, *Giulio Romano*, *Imoc. da Imola*, *Bagnacavallo*, etc.; 3rd, ornaments of all kinds. — Then follow portraits of the Medici, allegorical pictures by pupils of Vasari, the Triumph of Galathea by *Luca Giordano* in the larger room, embroidered tapestry from the Florentine manufactory; to the left below them, a Descent from the Cross from a picture by Giulio Clovio in the Palazzo Pitti (No. 241); also several pieces of Gobelins from Paris. — We now ascend a short staircase to a collection of sketches in grisaille and small pictures of animals and plants by *Bart. Ligozzi* (below lies the Boholi Garden). — (In order to reach the gallery in the Pitti Palace, p. 376, two more flights of steps have to be ascended.)

#### TWO SALOONS OF THE PAINTERS.

The walls are covered with portraits of the most celebrated painters of all nations from the 15th cent. to the present time, most of them painted by themselves and with their names attached. The I. SALOON contains the old masters; on the wall to the right of the entrance are those of Central Italy (Florentines, Romans, etc.). The most celebrated names here are: *292. Leonardo da Vinci* (not by himself), 288. *Raphael*, 290. *Michael Angelo* (not by himself), *287. Pietro Perugino* (recently discovered not to be the portrait of the painter), 280. *Andrea del Sarto*, *286. Masaccio* (or probably *Filippino Lippi*), 289. *Giulio Romano*. On the wall to the left of the entrance Venetians, Bolognese, etc.: 354. *Giov. Bellini* (probably not a portrait of himself), *384. Titian*, 385. *Paolo Veronese*, 378. *Tintoretto*, 348, 368, 397. The *Caracci*, 396. *Guercino*, 403. *Guido Reni*. On the entrance wall German and Dutch masters: 237. *Quentin Massys*, 434. *Albert Dürer* (1498, replica of the better picture at Madrid), 232. *Holbein*, 228. *Rubens*, 223. *Van Dyck*, 451, 452. *Rembrandt*, 449. *Gerard Dow*. In the centre a large 'Marlie Vase of Greek workmanship, known as 'The Medici Vase', adorned with the Sacrifice of Iphigenia. In a niche opposite the entrance, the statue of *Card. Leopold de' Medici*, the founder of this collection of portraits. — In the II. SALOON, modern masters: *Angelica Kauffmann*, *Mad. le Brun*, *Raphael Mengs*, *Reynolds*, *Overbeck*, *Canova*, *Winterhalter*, *Ingres*, etc.

#### CABINET OF INSCRIPTIONS.

The walls are covered with a number of ancient Greek and Latin inscriptions, most of them from Rome, arranged in twelve classes according to their subjects (the gods and their priests, the consuls, dramas, military events, private affairs, etc.). There are also some fine STATUES: *268. Bacchus* and *Ampelius*; *263. Mercury*; *266. Venus Urania*; *265. Venus Genetrix*; *264. Priestess* (head new). To the left of the door of the next room an interesting relief representing earth, air, and water. On the right a large relief: Departure for the chasc. Also a number of cinerary urns and busts with (sometimes conjectural) inscriptions.

#### CABINET OF THE HERMAPHRODITE.

307. Torso of Bacchus in basalt; 308. Ganymede with the eagle, restored by *Benvenuto Cellini*; 322. Bust of Seneca; 315. Torso of a Faun; above it 331. Victories sacrificing bulls; 318. Head of the dying Alexander; 306. Hermaphrodite reclining on a panther's skin, the legs restored; 316. Antinous; 323. Cupid and Psyche.

A door in this cabinet leads to the —

## CABINET OF THE CAMEOS.

(When closed on Sund. and Thursd., visitors apply to the custodians.)

Cases 1st-4th contain the antique cameos, 5th and 6th the modern; 7th-10th the ancient cut stones (intaglias), 11th and 12th the modern. In the 1st CASE, to the left of the entrance, the cameo No. 3 (red numbers), with the Sacrifice of Antoninus Pius, is remarkable for its size; 7. Cupid riding on a lion, with the name of the artist (Protarchos); 9. Cupid tormenting Psyche; 31. Nereid on a hippocampus. 2ND CASE: 36. Judgment of Paris; 51. Zeus of Dodona; 63. Hercules and Omphale. 3RD CASE: 86. Youthful Augustus; 100, 101. Tiberius. 4TH CASE: 148. Wounded stag; 156. Fall of Phaëton; 162. Bacchus and Ariadne. 7TH CASE (opposite the door): 28. Apollo; \*54. Hercules and Hebe, with the name of the artist Teucros; 73. Satyr and child. 8TH CASE: 101. Mourning Cupid; 145. Apollo. 9TH CASE: 176. Bacchante; 185. Pluto; 190, 191. Leander (?). 10TH CASE: chiefly portrait-heads. 11TH CASE: 4158. (black numbers), Sphinx, the seal of Augustus. 12TH CASE: (modern): \*371. Head of Savonarola; 373. Leo X., etc. — The four next cases contain the collection bequeathed by Sir William Currie to the Uffizi in 1863: 5. Hermaphrodite; 20. Dancing Satyr; 35, 50. Fine heads; ,106. Ajax and Achilles, etc. — Also six works in nicllo (engraving on silver), e.g. Coronation of the Virgin by *Maso Finiguerra*; then ivory carving and miniatures. By the wall opposite the window: Face carved in wood, purporting to have been copied from a cast of Dante's features taken after death, presented in 1865 by the Marchese Torriani. In the corner are fragments of glass from the catacombs bearing early Christian representations.

## SALOON OF BAROCCIO.

By the walls and in the centre four tables of Florentine mosaic. That in the centre, executed in 1613-18 by *Jacopo Antelli*, from *Ligozzo's* design, most interesting. Right: 154, 159. *Bronzino*, Portraits of Panciatichi and his wife; 155. Venetian portrait; 157. *Honthorst*, Infant Jesus adored by angels; 158. *Bronzino*, Descent from the Cross; 162. *Guido Reni*, Sibyl; 163. *Sustermans*, Galileo; 164. *Pourbus*, Portrait; 166. *Soghiani*, Madonna; 169. *Baroccio*, The Virgin interceding with the Saviour (Madonna del Popolo, 1579); 171. *A. Caracci*, Man with an ape on his shoulder; 180. *Rubens* (?), Helena Fourment, his second wife; 188. *Andrea del Sarto* (?), Portrait; 190. *Honthorst*, Adoration of the Shepherds; 191. *Sassoferrato*, Madonna dei Dolori; 192. *Sustermans*, Portrait; 195. *Caravaggio*, The tribute-money; 196. *Van Dyck*, Margaret of Lorraine; \*197. *Rubens*, Elizabeth Brand, his first wife; 203. *Guido Reni*, Bradamante and Fiordaspina (from Ariosto's Orlando Furioso); 210. *Velasquez*, Philip IV. of Spain on horseback (a copy by different hands); 211. *Salaino*, Copy of the Holy Family of Leonardo da Vinci (in the Louvre); 213. *Bugiardini*, Madonna; 216. *Rubens*, Bacchanalian (damaged); 220. *Snyders*, Boar-hunt.

## \* SALOON OF NIOBE,

constructed in 1775, and so named from the seventeen statues of the far-famed ancient \*\*Group of Niobe with her seven sons and seven daughters who were slain by Apollo and Diana, which probably once adorned the pediment of a temple (perhaps of Apollo), the unhappy mother occupying the centre of the group, with her slain and expiring children and their pedagogue on either side. These statues, which appear to have been copied from a work by *Scopas* or *Praxiteles*, were found at Rome outside the Porta S. Paolo in 1583 and placed by Cardinal Ferdinand de' Medici in his villa on the Monte Pincio (now the property of the French Academy), whence they were subsequently transferred to Florence. Opinions differ regarding the proper arrangement of the group, especially as statues belonging to the group were found elsewhere and some of those found at Rome are in duplicate. Then, 259. Replica of the so-called Zeus of Otricoli. Among the paintings are: (r.) 139. *Sustermans*, the Florentine Senate swearing allegiance to the young Grand-duke Ferdinand II.; 140. *Rubens*, Henri IV. at the battle of Ivry; 147. *Rubens*, Entry of

Henri IV. into Paris; 148. *Honthorst*, Supper; 152. *Honthorst*, Fortune-teller.

TWO CABINETS OF ANCIENT BRONZES.

I. CABINET. By the walls, "bronze heads, found in the sea near Leghorn, among them, on the right, Sophocles and Homer; list of the town-council, on a bronze tablet of A.D. 223, from Canossa. On the left: "426. Colossal horse's head; a tripod. II. CABINET. In the centre, "424. Bronze statuette of a naked youth ('L' Idolino'), found at Pesaro, with handsome pedestal by *Desiderio da Settignano* (15th cent.). The cases by the walls contain a number of small bronzes, some of them statuettes, others articles of domestic use, candelabra, lamps, metal mirrors, helmets, spurs, horse-bits, etc.; also Christian anticaglias (diptychon of the consul *Basilus*; 2256. Ivory ring with the Adoration of the Magi, of the 5th cent., in Cabinet xviii., to the left of the door).

GALLERIA FERONI,

(generally closed; visitors apply to the custodian), bequeathed to the city by Sign. Feroni in 1850, and brought from the Palazzo Feroni (Pl. 66) a few years ago. It contains few objects of great merit. On the wall to the right of the entrance: *Teniers the Younger*, Interior of a butcher's shop and tavern; *Carlo Dolci* (?), *Madonna del dito*; \**Carlo Dolci*, Angel with the lily; *Schidone*, *Madonna and Child*.

The first floor of the edifice contains the **Biblioteca Nazionale** (open daily, except on Sundays and festivals, 9-3, entrance by the 8th door from the piazza), which has been formed since 1860 by the union of the grand-ducal *Biblioteca Palatina* formerly in the Pitti Palace, and the still more extensive *Biblioteca Magliabecchiana*. The latter, founded by *Antonio Magliabecchi*, a jeweller of Florence, has been dedicated to the use of the public since 1747. The present library contains about 300,000 vols. and 8000 MSS., comprising the most important works of the literature of other nations. There are also several very rare impressions: the first printed Homer, Florence 1488; Cicero ad Familiares, Venice 1469; Dante, Florence 1481. Every facility is afforded for the use of the library; to the right, at the end of the great reading-saloon, is the room containing the catalogues. — The staircase to the right of the library leads to the \*CENTRAL ARCHIVES OF TUSCANY (Pl. 96; D, 5), arranged by *Bonaini*, one of the most imposing collections of this description (140,000 documents).

To the E. of the Uffizi, and to the S. of the Palazzo Vecchio, at the beginning of the Via de' Neri, is situated the *Loggia del Grano* (Pl. 52), which was erected by Cosmo II., and is adorned with his bust. — To the W. of the Uffizi is the church of *Sto. Stefano* (Pl. 34; D, 5), which is said to have been founded as early as 790. The epithet 'ad portam ferream' is sometimes applied to it from its door studded with large nails. It was here in 1373 that Boccaccio, by desire of the Signoria, publicly explained Dante's Divine Comedy.

The Piazza S. Firenze, the Badia, and the Museo Nazionale, see pp. 352-54; over the Ponte Vecchio to the Palazzo Pitti, see p. 375.

From the Piazza della Signoria the busy VIA DEI CALZAJUOLI (Pl. D, 4) leads towards the N. to the Piazza del Duomo.

The Via di Porta Iossa, the first side-street to the left, leads to the *Mercato Nuovo*, once the market for silks and jewelry, where straw and woollen wares are now sold. The market is adorned with a good copy of the ancient boar in bronze, by *Pietro Tacca*; the arcades are by *Bern. Tasso* (1547). — In the third street diverging to the right from the Via Calzajuoli, on the left side, beyond the first cross-street, is the house in which *Dante* was born (Via S. Martino 2; Pl. 46). It has been recently restored, and provided with a memorial tablet bearing the inscription 'in questa casa degli Alighieri nacque il divino poeta'. (The traveller interested in historical research should observe the numerous memorial-tablets in various parts of the town, recording important events in the annals of Florence.)

In the Via Calzajuoli, on the left, rises the church of \***Or San Michele** (Pl. 31; D, 4), or originally *S. Michele in Orto*, as it was called from a plot of grass in front of it, which was paved in 1284, and flanked with an open colonnade. With a view to embellish the piazza, in which figures of the Madonna and St. Michael were placed under canopies, it was resolved in 1336 to erect a 'Palatium', containing an oratory below, and a corn-exchange above. The work was at length begun in 1350, in the Gothic style, and progressed rapidly under the supervision of *Andrea Orcagna*. The external decoration of the edifice with statues was undertaken by the twelve guilds, whose armorial bearings are placed below the niches.

On the E. side, towards the Via Calzajuoli, (r.) St. Luke, by *Giovanni da Bologna*, 1562 (judges and notaries); \*Christ and St. Thomas, by *Andrea del Verrocchio*, 1483 (guild of the merchants); (l.) John the Baptist, by *Lor. Ghiberti*, 1414 (guild of the weavers of wool). — Then, farther to the left, on the S. side (r.) St. John, by *Baccio da Montelupo*, 1515 (weavers of silk). Beneath the adjacent canopy was formerly placed a Madonna by *Mino da Fiesole* (physicians and apothecaries; removed to the interior of the church, see below), now a \*St. George by *Donatello*, which was originally destined for the vacant niche to the N. (armourers); on the left, St. James, by *Nanni d'Antonio di Banco* (furriers); St. Mark, by *Donatello*, 1453 (joiners). — On the W. façade, (r.) St. Eligius by *Nanni di Banco* (farriers); \*St. Stephen, by *Lorenzo Ghiberti* (wool merchants), (l.) St. Matthew, by *Michelozzo*, 1420 (money changers). — On the N. side (r.) an empty niche, below, a fine relief; then four saints by *Nanni di Banco* (bricklayers, carpenters, smiths, and masons); (l.) St. Philip, by the same (shoemakers); St. Peter, by *Donatello* (butchers). — The coloured medallions in bas-relief above the niches are by *Luca della Robbia*.

In the INTERIOR, which consists of a double nave, divided by two pillars, to the right, the fine \**High Altar (Canopy)*, a celebrated work of *Andrea Orcagna*, in marble and precious stones, with numerous reliefs from sacred history, completed, according to the inscription, in 1359, and erected over the miracle-working image of the Virgin. At the side-altar under the organ, a marble group of the Holy Family, by *Francesco da Sangallo*; N. side, Madonna and Child, by *Mino da Fiesole*.

Opposite (r.) is the *Oratorio of S. Carlo Borromeo* (Pl. 6).

The Via dei Calzajuoli, before its extension, contained the

ancient towers of the *Adimari*, *Medici*, and *Visdomini*. We next reach the (r.) entrance to the *Bazaar* (Pl. 40), and pass a number of shops, etc. — The next street to the left leads to the busy *Mercato Vecchio* (Pl. D, C, 4), the market for meat, vegetables, fish, etc., extending as far as the *Piazza Strozzi* (p. 372). The *Piazza del Mercato* is one of the oldest in the town, and was called by the Lombards 'Forum Regis'. The column erected here to indicate the centre of the town bears a statue of Abundance, by Foggini, which replaces one by Donatello. On the N. side is the *Loggia del Pesce*, by Vasari. — In the vicinity is the *Ghetto*, or Jewish quarter.

The *Via Calzajuoli* is terminated by the *PIAZZA DEL DUOMO* (Pl. D, 4), in which rise the *Cathedral* and the *Baptistery*, and of which the W. part is called the *Piazza di S. Giov. Battista* after the latter edifice.

On the left, at the end of the *Via Calzajuoli*, is the elegant **Bigallo** (Pl. 45), an oratory erected by a follower of Orcagna in 1248 for charitable purposes, now an orphan-asylum. Over the arcades (N.) are three small statues (Virgin and two saints), by *Alberto di Arnoldo*, and two almost obliterated frescoes from the legend of St. Peter the Martyr, 1444. The chapel, now containing the archives of the asylum, contains a Madonna and two angels, by *Alberto di Arnoldo*, 1364. The room of the cashier is adorned with a fresco representing charity, and a view of Florence by *Giottino*, 1342.

Opposite the Bigallo is the \***Battistero** (Pl. 5; D, 4), or church of *S. Giovanni Battista*, an admirable octagonal structure, which was once extolled by Dante ('mio bel S. Giovanni', *Inf.* xix., 17). Several different accounts are given of the origin of the building and the construction of the altar. The local tradition, which recent investigations tend to confirm, is to the effect that the baptistery was erected on the site of a temple of Mars in the early Christian, or even in the Lombard period. As the building was not used as a baptistery till after 1128 (previous to which it had been the principal church of the Florentines), and as it possesses the polygonal form usually employed for chapels of the kind, it is not improbable that it was not erected in the present form till after 1128; and the external decorations in marble would accord with this hypothesis. On the other hand, the embellishment of the interior, with its straight beams and galleries, is of a character unknown in the 12th cent., so that some authorities believe it to have been erected in the 11th cent. It is at all events certain that its builder was well acquainted with ancient forms. The dome, which is 90 ft. in diameter, afforded Brunellesco a model for that of the cathedral. — The three celebrated \*\**Bronze Doors* were added in the 14th and 15th cent.

The **FIRST DOOR**, the oldest of the three, on the S. side, opposite the Bigallo, was completed by *Andrea Pisano* in 1330 after 22 years of labour. The scenes are from the life of St. John. The bronze decorations

at the sides are by *Lorenzo Ghiberti* and his son *Vittorio* (about 1452-62); above is the Beheading of John the Baptist by *Vincenzo Danti*. 1571.

The <sup>2</sup>SECOND DOOR, facing the cathedral, executed by *Lorenzo Ghiberti* (1425-52), is considered a marvel of art. It represents ten different scenes from scripture history: (l.) 1. Creation and Expulsion from Paradise; (r.) 2. Cain slaying his brother and Adam tilling the earth; 3. Noah after the Flood, and his intoxication; 4. Abraham and the angels, and Sacrifice of Isaac; 5. Esau and Jacob; 6. Joseph and his brethren; 7. Promulgation of the Law on Mt. Sinai; 8. The Walls of Jericho; 9. Battle against the Ammonites; 10. The Queen of Sheba. This is the door which Michael Angelo pronounced worthy of forming the entrance to Paradise. The bronze decorations at the sides are also by *Ghiberti*; over the door the <sup>3</sup>Baptism of Christ, by *Andrea Sansovino*, 1529; the angels by *Spinazzi* (18th cent.). The two porphyry columns were presented by the Pisans (in 1200) in recognition of the assistance rendered them by the Florentines against Lucca in the expedition to Majorca in 1117. The chain of the harbour of Pisa, carried off by the Florentines in 1362, was formerly suspended here, but has been recently restored to the Pisans, and is preserved in their Campo Santo (p. 308).

The THIRD DOOR (N.) is also by *Ghiberti* (1403-27). It represents in 28 sections the history of Christ, the Apostles, and Fathers down to St. Augustine. Many rival artists are said to have competed for the honour of undertaking this work, of whom the principal were *Ghiberti*, *Brunellesco* (visitors should compare the works in the Bargello, p. 353), *Jacopo della Fonte*, *Simone da Colle*, and probably also *Donatello*, but the preference was given to *Ghiberti*. Above the door, the <sup>4</sup>Preaching of St. John by *Fr. Rustici*, 1511 (supposed to have been designed by Leonardo da Vinci).

In the Interior of the baptistery, below, are eight niches, each containing two columns of Oriental granite with gilded Corinthian capitals. The choir is probably part of the original building. The statues and pictures are of subordinate importance. The dome and choir-bays are adorned with <sup>5</sup>Mosaics by *Fra Jacopo* (after 1225), *Andrea Tafi* (d. 1320), *Apollonio Greco*, and others (restored by *Baldovinetti*, 1492), which however are not visible except on very bright days. On the pavement are early mosaics, with the zodiac and inscriptions, and niello with ornaments, 1371. The font is enriched with reliefs by an imitator of Orcagna. To the right of the high altar is the tomb of Pope John XXIII. (d. 1419), who was deposed by the Council of Constance; the recumbent bronze statue by *Donatello*, the figure of Faith by *Michelozzo*. On an altar to the right of *Andrea Pisano's* door is a statue of Mary Magdalene in wood, by *Donatello*. — On the festival of St. John there is placed here an altar of massive silver (325 lbs. in weight) with a cross of the same metal (141 lbs.), adorned with bas-reliefs from the life of the Baptist (kept in the Opera del Duomo, p. 350).

Opposite the N. side of the church is a column of speckled marble (cipollino), called the *Colonna di S. Zanobi*, erected in 1330 to commemorate the removal of the relics of St. Zenobius. (From this point through the Borgo S. Lorenzo to S. Lorenzo, see p. 366.)

The <sup>6</sup>CATHEDRAL (Pl. 8; D. 4), *Il Duomo*, or *La Cattedrale di S. Maria del Fiore*, so called from the lily which figures in the arms of Florence, was erected in 1294-1474 on the site of the earlier church of St. Reparata. This imposing example of Italian Gothic was designed by *Arnolfo del Cambio*, who superintended the works down to his death in 1310. He was succeeded by *Giotto* (who acted as architect-in-chief for 33 months), *Francesco Talenti*, and *Alberto di Arnoldo*. The nave and aisles were completed in 1355. The dome, added in 1420-34 by *Filippo Brunellesco*, a masterly structure, sur-



passes in height (300 ft., with the lantern 352 ft.) the domes of St. Peter and the Pantheon at Rome (ascent, see p. 349). The church, 185½ yds. in length, 114 yds. (across the transepts) in breadth, is one of the most admired in Italy. The façade was begun by *Arnolfo*, but in 1332 his successor *Giotto* designed a new and more imposing plan (of which copies still exist, e.g. in the cloisters of S. Marco, 5th lunette from the entrance on the right), and executed one half of it himself. In 1588 this work was removed with a view to replacing it by a new façade designed by *Buontalenti*, *Dosio*, *Cigoli*, and others, but the project was not carried out. The cathedral (like S. Croce, S. Lorenzo, etc.) was thus left without a façade, and was then decorated with frescoes by way of supplying the defect, but these have long since disappeared. In April, 1860, Victor Emmanuel laid the foundation-stone of a new façade, but the work was not begun till the autumn of 1875. The design is by *De Fabris*. — The first part of the coloured ornamentation of the building, which differs from the rest, is due to *Giotto*, and that of the nave is attributed to *Brunellesco*.

The decoration of the second S. door is by *Pietro di Giovanni*, a North-Italian; the Madonna between two angels, in the lunette, is by *Lorenzo di Giovanni d'Ambrogio* (1402). — The corresponding N. Door was executed by *Giovanni d'Ambrogio*, and *Niccolò di Piero Lomberti*, 1408. The admirable bas-relief of the glorified Madonna, over the door, is ascribed to *Nanni d'Antonio di Banco*. The mosaic is by *Domenico Orcagna*, and *Davide Ghirlandajo* (1496).

The Interior, though somewhat bare, is very impressive owing to its grand dimensions. The gallery, which detracts from the effect, was probably a later addition. The choir, instead of being at the end of the church, is appropriately placed under the dome.

On the entrance-wall to the right, an equestrian statue of John Hawkwood (d. 1394), commander of the troops of Gregory XI., by *Paolo Uccello*; to the left, the monument of Nic. Marucci da Tolentino (d. 1434), by *Andrea del Castagno*. Over the principal portal: Coronation of the Virgin in mosaic, by *Gaddo Gaddi*; at the sides frescoes (angels) by *Santi di Tito*, restored in 1842. — The designs for the rose-windows were drawn by *Lor. Ghiberti*; the design of the coloured mosaic pavement is attributed to *Baccio d'Agnolo* and *Francesco da Sangallo*.

RIGHT AISLE. Monument of Filippo Brunellesco, with his portrait in marble, by his pupil *Buggiano*. Monument of Giannozzo Manetti, by *Cinifigi*; (r.) Bust of Giotto by *Benedetto da Majano* (1490): (l.) on the pillar a fine receptacle for holy water by *Arnolfo* or *Giotto*. (r.) Monument of Pietro Farnese (over the door), by *Agnolo Gaddi* and *Pesello* (1395); farther on, King Hezekiah, by *Nanni d'Antonio di Banco*. Bust of the learned Marsilius Ficinus, by *A. Ferrucci* (1521). Over the following door (r.) the Mausoleum of Antonio Orso, Bishop of Florence, by *Tino di Camaino* of Siena, with the figure of the deceased in a sitting posture. By the pillar of the dome, towards the nave, St. Matthew, a statue by *Vincenzo de' Rossi*; opposite to it, St. James, by *Jacopo da Sansovino* (1524).

RIGHT TRANSEPT: (r.) St. Philip, (l.) St. James the Great, by *Giovanni Bandini*. Each of the four side-chapels is adorned with two saints, painted at fresco by *Bicci di Lorenzo* (1427). The stained glass windows are said to have been executed at Lübeck in 1434 by the Florentine *Domenico Livi da Gambassi*, from designs by *Ghiberti*, *P. Uccello*, *A. Gaddi*, and *Donatello*. — Over the door of the SACRISTY a bas-relief (Ascension) by *Luca della Robbia*. In the sacristy, St. Michael by *Lor. di Credi* (1523), and two angels by *Luca della Robbia*.

In the NAVE, E. branch, statues of (r.) St. John and (l.) St. Peter by *Benedetto da Rovezzano*. 1st Chapel: St. Luke, by *Nanni di Banco* (1415); in the 2nd Chapel, St. John, by *Donatello*. Below the altar of the Tribuna is the chapel of St. Zenobius, with a reliquary containing the remains of the saint, in bronze, by *Lorenzo Ghiberti* (1440). Last Supper on a golden ground, painted 'a tempera' by *Giovanni Balducci*. On the right St. Matthew by *Niccolò d'Arezzo*; on the left, St. Mark, by *Bernardo di Pietro Cinghigni* (1416).

The marble screen of the octagonal CHURCH, designed by *Giuliano di Baccio d'Agnolo*, and adorned with bas-reliefs by *Bandinelli* (with the initials B. B. and date 1555) and his pupil *Giovanni dell'Opera*, was erected to replace the original wooden screen of Ghiberti. Behind the high altar an unfinished group (Entombment) by *Michael Angelo*. — The paintings in the octagonal dome, begun in 1572 by *Vasari*, and continued by *Federigo Zuccheri* (prophets, etc.), diminish its impressive effect.

Bronze door of the N. SACRISTY by *Luca della Robbia* and *Maso di Bartolommeo* (1467). Above it a bas-relief in terracotta (Resurrection) by the *Robbia*. The intarsia cabinets in this sacristy were executed from designs by *Finiquerria* and *Baldorinetti*. The "Putti, or figures of children in the cabinets, are by *Donatello*. In this sacristy *Lorenzo de' Medici* sought refuge in 1478, on the outbreak of the conspiracy of the Pazzi, to which his brother Julian fell a victim.

LEFT TRANSEPT. The Tribuna della S. Croce contains statues of St. Andrew and St. Thomas by *Andrea Ferrucci*. In the chapels, frescoes by *Lorenzo di Bicci*. The ten stained glass windows are by *Lor. Ghiberti*. In the centre of the tribune is a round marble slab covered with wooden planks, placed here about the year 1450 by the celebrated mathematician *Paolo Toscanelli* of Florence for the purpose of making solar observations through a corresponding aperture in the lantern. In 1755 *P. Leonardo Ximenes* added a graduated dial in order to admit of more accurate observations, as an inscription on one of the pillars of the dome records.

LEFT AISLE. By the side-door is a \*Portrait of Dante, with a view of Florence and scene from the Divine Comedy, painted on wood by *Domenico di Michelino* in 1465 by command of the republic. Statue of David by *Cinghigni* (1434). Then Arnolfo, with the design for the cathedral, a medallion in high relief by *Bartolini* (1483). \*Statue of Poggio Bracciolini, secretary of state, by *Donatello*, admirably individualised. Bust of the musician Antonio Squarcialupi by *Benedetto da Majano*. On the first pillar, St. Zenobius, a picture by *Orcagna*.

The ASCENT OF THE DOME (p. 348) is very interesting, both for the sake of obtaining an idea of its construction, and for the \*View (more extensive than from the Campanile, see below). Entrance by a door in the right aisle (opened by the sacristan; attendant 1 fr.); easy ascent of 463 steps to the upper gallery, whence the adventurous visitor may clamber up a ladder of 57 steps more to the cross on the summit.

The \*Campanile, or bell-tower, begun by *Giotto* in 1334 and completed after his death (1336) by *Andrea Pisano*, *Fr. Talenti*, and by *Neri di Fioravanti* (who also executed the windows), a square structure in the style of the cathedral, 292 ft. in height, recently restored, is regarded as one of the finest existing works of the kind. It consists of four stories, the lowest of which is richly decorated with reliefs and statues. The windows, which increase in size with the different stories, are enriched with beautiful tracery in the Italian Gothic style. On the W. side are statues of the four Evangelists, the three first of which are by *Donatello* (\*St. Matthew, the finest), and the fourth (St. John) by *Nanni di Bartolo*, surnamed *Rossi* (1420). On the S., four prophets, three of which are by *Andrea Pisano* and the fourth by *Giottino*; on the E.

side are a prophet, and three patriarchs by *Donatello* (Abraham and Isaac), and *Niccolò di Piero Aretino*; on the N. side are four sibyls by *Luca della Robbia* (?) and *Nanni di Bartolo* (?). Below these figures, on the sides of the tower, are bas-reliefs; those on the W. and S. sides having been designed by *Giotto*, those on the E. side by *Andrea Pisano*, and those on the N. by *Luca della Robbia*: the Seven Cardinal Virtues, the Seven Works of Mercy, the Seven Beatitudes, and the Seven Sacraments. In the lower series is represented the development of mankind from the Creation to the climax of Greek science (Creation of Eve, Adam and Eve at work, Dwellers in tents, Astronomer, Rider, Weaving, Navigation, Agriculture, etc.). It is ascended by a good staircase of 414 steps (fee for 1-2 pers. 1 fr.). Beautiful view from the top, embracing the valley in which the city lies, the neighbouring heights, studded with villas and richly cultivated, and the mountains to the N., S., and E. At the summit are seen the pillars on which, according to *Giotto's* plan, it was proposed to raise a spire of 100 ft., but the project was abandoned by *Gaddi*.

Opposite the S. side of the Campanile is the **Church of the Misericordia** (Pl. 27; D, 4), founded in 1244, belonging to the long established order of brothers of charity, who are frequently seen in the streets garbed in their black robes, with cowls covering the head and leaving apertures for the eyes only, while engaged in their missions of mercy. It contains a Madonna and St. Sebastian by *Benedetto da Majano*, the Plague of 1348 by *Lodovico da Cigoli*, and other pictures.

Adjacent to the E. is the *Canonry (Casa dei Canonici)*, erected in 1827 by *Gaetano Baccani*; at the portal are the statues of *Arnolfo del Cambio* and *Fitippo Brunellesco*, both by *Luigi Pampaloni* (1830). — In to the wall of one of the following houses (No. 29) is built the *Sasso di Dante*, a stone on which the great poet is said to have been wont to sit on summer evenings.

The Via Proconsolo then leads to the S. to the Piazza S. Firenze (Museo Nazionale; see p. 352). — In the piazza of the Cathedral, farther on, at the corner of the Via dell' Orivolo, is the *Palazzo Riccardi*, formerly *Guadagni*. — [In the Via Orivolo, immediately to the right, is the handsome new *Bank* by *Cipolla*.]

Opposite the choir is situated the **Opera del Duomo**, which contains the \*silver altar mentioned at p. 347. The principal reliefs with which it is adorned are the Nativity of Christ by *A. Pollajuolo* (below, to the left), and Herod (above, to the right) and the Beheading of John the Baptist (below, to the right), by *Andrea Verrocchio*; in the centre is a statuette of the Baptist, by *Michelozzo*. Here, too, are kept the silver cross, mentioned at p. 347, the lower part of which is by *A. Pollajuolo*, and two tablets with Byzantine representations in enamel.

The Via dei Servi and Annunziata, see p. 359; the Via Ricasoli, the Accademia delle Belle Arti, and S. Marco, see pp. 360-64; the Via Cavour, and the Palazzo Ricardi, see p. 364.

The Via Bufalini (formerly S. Egidio; Pl. E, 4), which lies a little to the E. of the Piazza del Duomo, passes the small piazza of *S. Maria Nuova*, with the church of *S. Egidio* (Pl. 9), the façade of which is embellished with frescoes of the time of Fra Bartolommeo. At the back of the high altar of the church are a Madonna by Luca della Robbia, and a ciborium by Ghiberti. — Opposite the church, on the ground-floor of No. 29, which once contained *Lorenzo Ghiberti's* studio, is exhibited the small picture gallery of the **Ospedale di S. Maria Nuova** (admission daily, 9-3; on Sundays, 10-2).

VESTIBULE: *A. Verrocchio*, Madonna in relief (terracotta). — LARGE ROOM: \*48-50. *Hugo van der Goes* (d. 1485), Adoration of the Child, and four saints; 20. *A. Orcagna*, St. Matthew; 22. *Raffaellino del Garbo*, Madonna and saints. — II. ROOM: \*71. *Fra Bartolommeo*, Last Judgment (damaged; the adjoining copy shows the details); 63. *Sogliani*, Assumption; 65. *Cosimo Rosselli*, Madonna and Christ; 72. *Albertinelli*, Annunciation.

The house at the corner of the Via Bufalini (S. Egidio) and the Via della Pergola, opposite the hospital, was once inhabited by *Galileo*. Adjoining it, in the Via della Pergola, is the house of *Benvenuto Cellini*.

To the S.E. of the Via della Pergola, and parallel to it, runs the Via di Pinti (Pl. F, 4), in which is situated the church of **S. Maria Maddalena de' Pazzi** (Pl. 23). The cloisters in front of the church were designed by *Giuliano da Sangallo*. In the 2nd chapel, on the left, is a Coronation of the Madonna by *Cosimo Rosselli*; in the 4th chapel, two saints, by *Raffaellino del Garbo*. — In the adjacent Via della Colonna, No. 1, is the entrance to the chapter house of the monastery belonging to the church, which contains a large \*Fresco by *Perugino* (Christ on the Cross, date about 1500), and is open on Mond. and Thursd., 12-4. — In the same street, No. 31, is the exhibition of the *Società d'Incoraggiamento delle Belle Arti* (open daily, 10-4; admission 60 c.). — In the Via di Pinti, No. 62, farther N., is the *Palazzo Panciatichi-Ximenes*, erected by Giuliano da Sangallo in 1490, and restored in the 17th cent. by Silvani. It contains a valuable picture gallery.

The Via della Colonna connects the Piazza dell' Annunziata (p. 359) and the new *Piazza d'Azeglio* (Pl. F, 4), which is laid out in promenades. — To the S. of the latter is the church of *S. Ambrogio* (Pl. 1; F, 5).

On the right, 1st chapel, *Cosimo Rosselli*, Madonna with saints and angels; 2nd and 3rd chapels, pictures of the school of *Spinello Aretino*. To the left in the choir, a canopy by *Mino da Fiesole* (1482), and a large fresco by *Cosimo Rosselli*.

The Galleria Buonarroti, see p. 358; S. Croce, see p. 355.

Quitting the Piazza della Signoria (p. 332), we follow the *Via de' Gondi* to the right, which leads us to the PIAZZA S. FIRENZE (Pl. D, 5), with the church of that name. No 1 in this Piazza is the *Palazzo Gondi*, begun in 1490 by Giuliano da Sangallo, and recently completed by Poggi, containing a handsome court. From this point the VIA DEL PROCONSOLO (Pl. D, E, 4) diverges to the Piazza del Duomo.

Immediately on the right in the *Via Proconsolo* rises the *Palazzo del Podestà*, commonly known as \***Il Bargello** (Pl. 39; D, 4, 5), erected about the year 1250 for the *Podestà*, or chief magistrate of Florence, and altered in 1373. This imposing structure, which had been used as a prison since the 16th cent., and was totally disfigured in the interior, was judiciously restored on the occasion of the Dante Exhibition in 1865, and fitted up for the new \***National Museum**, illustrative of the mediæval and modern history of Italian culture and art. Part of the collection, which is still in course of formation, belongs to the state, and part to private individuals, and it is therefore by no means uniformly valuable. It contains several admirable works, such as the Renaissance bronzes formerly in the Uffizi and the *Palazzo Vecchio* (comp. p. xlix, 1). Entrance in the *Via Ghibellina*, daily 10-4, 1 fr.; on Sundays, 11-2½, gratis. No catalogue has yet been published. The most important works are labelled with the masters' names.

We first enter the picturesque COURT, embellished with the armorial bearings of former *Podestà's*, in which lie a number of Gothic architectural fragments. In the centre is *Donatello's Marzocco* from the Piazza della Signoria (p. 332). A second court (closed on Sundays) contains sculptures of the High Renaissance, including grotesque fountain figures.

The GROUND FLOOR contains (to the right) a valuable collection of weapons, comprising an interesting monster cannon in bronze of the 16th cent. with the arms of the Medici. — A handsome flight of steps ascends to the —

**First Floor.** The VESTIBULE contains a bell cast by *Bartolommeo Pisano* in 1228. — I. SALOON. *Vincenzo de' Rossi* (end of 16th cent.), a series of sculptures representing the combats of Hercules; *Donatello*, David; *Vinc. Danti* (d. 1576), Deceit conquered by Honour; \**Michael Angelo's* 'Victory', an old man fettered by a youth, unfinished, perhaps destined for the monument of Julius II. at Rome; by the same master, 'Dying Adonis'; *Giov. da Bologna (Giambologna, d. 1608)*, Virtue triumphant; \**Michael Angelo*, Drunken Bacchus, an early work of the master; *Baccio Bandinelli*, Adam and Eve; *V. Danti*, Grand Duke Cosmo I. On the walls: Ten bas-reliefs of singing and dancing boys and girls, originally intended for the decoration of the organ in the cathedral, by *Luca della Robbia*; four bas-reliefs representing dancing genii, intended for the same purpose, by *Donatello*.

II. SALOON: ancient furniture and crystal, dating from the 16th and 17th cent.

III. SALOON: fine collection of fayence, formerly in the Uffizi; the objects specially worthy of notice are in the glass-cabinets in the middle, many of them from paintings by Raphael, and once the property of the della Rovere family.

IV. SALOON, originally a chapel, but for centuries a dingy prison, adorned with \**Frescoes* by *Giotto*. Opposite us: Paradise, with a "portrait of Dante as a youth: the two heads behind Dante are said to be portraits of Corso Donati and Brunetto Latini; the figure behind the cardinal

(to the left, by the window), a young man in a yellowish robe, is possibly Giotto himself. The work, which was painted about 1302 in allusion to the peace of 1301, has suffered terribly, and has been restored with little care since 1850. when the whitewash which covered it was removed. On the right and left below it, a Madonna and St. Jerome by *Rid. Ghirlandajo*; on the entrance-wall, almost obliterated, the Infernal regions; at the side, the history of St. Maria Egyptiaca and Mary Magdalene, much damaged. This saloon also contains mediæval crosses, goblets, episcopal rings, reliquaries, and an inlaid choir desk.

V. SALOON: carving in ivory (Christ and St. Sebastian, by Giambologna; two triptychs by Andrea Orcagna), statuettes (including a <sup>2</sup>Madonna in the style of Orcagna), etc.; in the centre, cabinets with fine crystal of the 16th cent.; (r.) a very artistic piece of modern wood-carving. (The door to the left in this saloon leads to the second floor, see below.)

VI. SALOON (and the 7th contain): bronzes. In the centre: <sup>\*</sup>*Donatello*, David. By the walls: 19. Portrait head by *Donatello*; 25. Portrait head of a woman, probably from a cast taken after death; anatomical statuettes in wax and bronze by *Luigi Cigoli*; the other statuettes are of the time of *Gior. da Bologna*; a cabinet with <sup>2</sup>bronze statuettes from the antique and Renaissance works; figures of animals, including a dog in relief by *Bent. Cellini*; Apollo, Juno, school of *Giambologna*.

VII. SALOON: In the centre: *Donatello*, a Cupid treading on a snake; <sup>\*</sup>*Giambologna*, a celebrated Mercury; *Andr. Verrocchio*, David. By the walls, to the left of the entrance: Crucifixion, a basrelief (partly gilded), by *Donatello* (?); lid of a box by a Dutch imitator of Michael Angelo; two cabinets with imitations of ancient and Renaissance sculpture; between these a colossal bust of the Grand Duke Cosmo I. in bronze, by *Benvenuto Cellini*; the model in wax and bronze for that master's Perseus (somewhat differing from it; p. 334). is also placed here; *V. Danti*, Raising of the brazen serpent; *Bertoldo* (pupil of Donatello), Ancient battle scene. Among the small adjacent tablets the finest are: 267. Descent from the Cross, after *Donatello*; 271. *Pollajuolo*, Wrestling match. — End Wall: Abraham's Sacrifice by *Lor. Ghiberti*, and the same by *Fil. Brunellesco*, specimens produced in their competition for the execution of the gates of the baptistery (p. 347). Between these, a <sup>\*</sup>Crucifixion. by *Pollajuolo* (?), and a Frieze of children by *Danese*; below, a recumbent figure of *Mariano Soccino* in bronze, by *Lor. Vecchiotta* (d. 1482). In the next frames: 147, 148, 151. Good portraits; above, 186. *Pollajuolo*, Wrestling match. — Window wall: Francis Xavier, Death of Joseph, and St. Theresa, reliefs by *Soldani*. — By the exit: <sup>\*</sup>Bust of Michael Angelo in bronze (once the property of his servant). — We now return through the 5th Saloon and ascend to the —

Second Floor. I. ROOM. On the walls, interesting frescoes by *Andr. del Castagno* (about 1450), transferred to canvas, the finest being eight portrait-figures (Dante, Petrarch, Boccaccio, etc.), formerly in the Villa Pandolfini at Legnaia; a Pietà by *D. Ghirlandajo*; a Fresco by *Giottino*, etc. The glass cabinets contain articles of clothing dating from the 16th and 17th cent., altar-cloths, and ecclesiastical vestments. The two <sup>2</sup>Stained-glass windows, representing the Nativity, and the Adoration of the Magi, the latter with the armorial-bearings of Leo X., from designs by *Luca Signorelli* or one of his pupils (beginning of the 16th cent.), were formerly in the cathedral at Cortona, and have been described by Vasari.

II. ROOM (right): Beautiful terracottas by *Luca della Robbia* and his school; marble statue of the school of *Ghiberti*; to the left, by the windows, two portrait busts by *Ant.* and *Piero Pollajuolo*; furniture of the 16th cent.

III. ROOM. Flemish tapestry of the 17th and 18th cent.; to the left, Bust of St. John, by *Donatello*.

IV. ROOM. In the centre: *Donatello*, John the Baptist; on the walls, to the right of the entrance, <sup>2</sup>*Mino da Fiesole*, Bust of Rinaldo della Luna; *Benedetto da Rovezzano*, five basreliefs in marble, representing the history of S. Giovanni Gualberto, from the monastery of S. Salvi, outside

the Porta Santa Croce; *And. del Verrocchio*, tomb-relief of the wife of Fr. Tornabuoni, who died in her confinement; a beautiful 'angel musician', of the school of *Niccolò Pisano*; Bust of Pietro Mellini, by *Benedetto da Majano* (1474); \*Bust of Matteo Palmieri (1468), by *Antonio Rossellino*. Octagonal busts in relief: Galeazzo (Francesco?) Sforza, and Duke Federico di Montefeltro, master of Urbino. Above, *Pierino da Vinci*, Madonna; *Mino da Fiesole*, Madonna; *Donatello*, Young St. John.

V. Room. In the centre: *Benedetto da Majano*, John the Baptist; *Sansovino*, Bacchus; *Michael Angelo*, Statue of Apollo, about to take an arrow out of his quiver, unfinished; *Bened. da Majano*, Bacchus. On the wall, to the left of the entrance: *Andr. Verrocchio*, Madonna and Child, and a \*Portrait bust; \**Matteo Civitani*, Faith; *Rossellino*, Mary adoring the Child, a large medallion. Below these: *Jacopo della Quercia*, Boys bearing garlands (a frieze from Lucca); *Ant. Rossellino*, John the Baptist. — End wall: *Luca della Robbia*, Crucifixion of St. Peter; *Michael Angelo*, \*Bust of Brutus, a very late work of the master, unfinished (for the reason given in the inscription alluding to the suppression of liberty at Florence); *Michael Angelo*, Holy Family, an unfinished relief; the Martyrdom of St. Andrew, and the Mask of a Satyr are also ascribed to Michael Angelo, and the latter is said to have been executed by him when in his 15th year. Above, on the right and left, are two fine busts of children. — Between the windows: Coronation of an empress, a relief of the 13th cent. (perhaps of Apulian workmanship; the crown and the hands of the bishop restored in plaster), found outside the Porta S. Gallo. — End wall: Bust of Piero de' Medici (1453), by *Mino da Fiesole*, and a \*Relief of the Madonna and Child by the same master. Below these, Leda, erroneously attributed to Michael Angelo. Bust of Nic. Macchiavelli.

From the 4th Room we proceed in a straight direction to the VI. ROOM, which contains a collection of coins from 1200 to 1850, a valuable assortment of seals, and French Gobelines of the time of Louis XIV.

On the opposite side of the Via Proconsolo is the church of **La Badia** (Pl. 4; D, 4, entrance in the passage to the left), founded by Willa, the mother of Margrave Hugo of (Br) ande (n) burg (?), and erected by *Arnolfo del Cambio* about the end of the 13th cent. In 1625 it was altered by *Segaloni* who left nothing of the original edifice except the termination of the choir, and thus destroyed a number of frescoes by Giotto, Masaccio, and others.

The door is by *Benedetto da Ravezzano*, 1495. In the INTERIOR a \*Madonna and saints, by *Mino da Fiesole*; \*Monument of Bernardo Giugni (1466) and to the left that of the Margrave Hugo (1481), both by *Mino da Fiesole*; then, Madonna appearing to St. Bernard by *Filippino Lippi*, 1480. The beautiful wooden ceiling is by *Segaloni*. — The graceful CAMPANILE is also worthy of inspection. — The MONASTERY COURT contains remains of monuments of the old noblesse (with whom this was a favourite church in Dante's time) and unimportant frescoes of the 15th cent.

Following the Via Ghibellina from the Bargello, we reach a building on the right, part of which is occupied by the Teatro Pagliano (Pl. 103). At the entrance to it (No. 83 in the street), a lunette of the first flight of steps is adorned with a *Fresco* of the middle of the 14th cent., representing the 'Expulsion of the Duke of Athens (p. 329) from Florence on the festival of St. Anne, 1343', interesting on account of the view it contains of the Palazzo Vecchio. The lunette, which is closed, is opened on application to the custodian of the theatre (50 c.).

The BORGO DEGLI ALBIZZI (Pl. E, 4), the second parallel street to the N., contains several handsome palaces. At the corner of the

Via del Proconsolo is the *Palazzo non Finito* (Pl. 90), in the rococo style, by Buontalenti, 1592; No. 10, on the opposite side, is the *\*Palazzo Quaratesi* (Pl. 59), by Brunellesco, with a handsome court; the armorial bearings of the Pazzi, to which it once belonged, are by Donatello. Beyond it, on the left, No. 18, is the *Palazzo Altoviti* (Pl. 57), adorned with the busts of sixteen celebrated Florentines ('I Visacci', i.e. 'the caricatures'), 1570. The *Palazzo Albizzi* (Pl. 56) is of the 17th cent.

In the *\*Piazza S. Croce* (Pl. E, 5), one of the largest in Florence, to which many reminiscences from the earlier history of the city attach, rises *\*Dante's Monument* (Pl. 95), by Pazzi, inaugurated with great solemnity on the 600th anniversary of the birth of the great poet (b. 1265), 14th May, 1865, a white marble statue 19 ft. in height, on a pedestal 23 ft. high, the corners of which are adorned with four shield-bearing lions with the names of his four most important works after the *Divina Commedia*: the *Convito*, *Vita Nuova*, *De Vulgari Eloquentia*, *De Monarchia*. Round the pedestal below are the arms of the principal cities of Italy. — To the right is the *Palazzo dell'Antella* (now *del Borgo*), with a façade decorated with frescoes which were executed in 1620 within the short space of 27 days by *Giovanni da S. Giovanni* and other masters. To the W. is the *\*Palazzo Serristori*, by Baccio d'Agnolo.

The church of *\*S. Croce* (Pl. 7; E, 5), a cruciform edifice borne by columns, was begun in 1294, from a design by *Arnolfo del Cambio*, on the site of a church of the Franciscans, completed in 1442, and consecrated by Cardinal Bessarion in presence of Pope Eugene IV. The front alone remained uncompleted, but the old design of *Simone Pollajuolo*, surnamed *Cronaca*, was at length rescued from oblivion, and the foundation-stone of the new façade laid by Pope Pius IX. in 1857. The work was skilfully executed by the architect *Nicolo Matas*, and consecrated in 1863. The tower has also been well restored. Over the central door is a basrelief (*Raising of Christ*), by *Dupré*.

The Interior, consisting of nave and aisles 163 yds. in length, and each 9 yds. in width and 65 ft. in height, with a transept 14 yds. in width, and open roof, rests on 14 octagonal pillars at considerable intervals, and produces an impressive effect, enhanced by its numerous monuments of celebrated men. This church may be called the Pantheon of modern Italy, and its interest is greatly increased by the frescoes of Giotto which were discovered within the last twenty years under the whitewash (hest light in the morning). In 1566 *Giorgio Vasari*, by order of Cosmo I., made several alterations on the altars, which however hardly accord with the simple dignity of the interior and are therefore to be removed.

ENTRANCE WALL. Over the central door is a window filled with stained glass from drawings by *Lorenzo Ghiberti*.

RIGHT AISLE. At the entrance, small honorary monument to *Daniele Manin*, with portrait-bust (his tomb at Venice, p. 216). — On the right, farther on, *\*Tomb of Michael Angelo* whose remains repose below it (d. at Rome, 1564), erected in 1570, the bust by *Battista Lorenzi*, the painting and sculptures by *Giovanni dell'Opera*, *Lorenzi*, and *Valerio Cioli*. — On



the pillar opposite, a Madonna in relief, by *Rossellino*. — Honorary monument to Dante 'onorate l'altissimo poeta!' (interred at Ravenna, p. 289), by *Stefano Ricci*, erected in 1829. — Alfieri (d. 1810), by *C. nova* (erected by his friend the Countess of Albany). — \*Marble pulpit, by the pillar to the left, with five reliefs, and five allegorical figures by *Benedetto da Majano*. — Machiavelli (d. 1527), by *Innocenzo Spinazzi*, erected in 1787, with inscription, 'Tanto nomini nullum par elogium'. — The learned Lanzi (d. 1810). — Bencdetto de' Cavalcanti; above it is a fresco by *Domenico Veneziano*, representing John the Baptist and St. Francis. — Adjacent is an Annunciation, an early relief by *Donatello*. — Leonardo Bruni (d. 1444), surnamed Aretino from his birth-place, by *Bernardo Rossellino*; above it a Madonna, basrelief by *Andr. del Verrocchio* (?). — The naturalist Micheli. — Leopoldo Nobili. — Opposite, in front of the last pillar towards the nave, Vincenzo degli Alberti (minister of Leopold I.), by *Emilio Santarelli*.

**RIGHT TRANSEPT.** At the corner: Monument of Principe Neri Corsini (d. 1859) by *Fantachiotti*. — The CHAPEL OF THE CASTELLANI, or del S. Sacramento (1st on the right) is adorned with frescoes on the right from the life of St. Nicholas and John the Baptist, on the left from that of SS. John and Antony by *Agnolo Gaddi*; on the right and left two monks, life-size, by *della Robbia*; over the altar a crucifix ascribed to *Giotto*; on the left, the \*Monument of the Countess of Albany (d. 1824), widow of the young Pretender, by *Luigi Giovannozzi*, the two angels and bas-relief by *Santarelli*. — Farther on, CAPPELLA BARONZELLI, now Giugni, with frescoes by *Taddeo Gaddi*. Over the altar a Pietà in marble by *Bandinelli*. Altar-piece, \*Coronation of the Virgin, with saints and angels, by *Giotto*. On the right a statue of the Madonna by *Vincenzo Perugino*. Above these is the Madonna della Cintola, a fresco by *Bastiano Mainardi* (a pupil of Dom. Ghirlandajo).

The door of the corridor leading to the sacristy is next reached. To the left, in the corner, is a large crucifix, perhaps by *Cimabue*. At the end of the corridor is the CAPPELLA MEDICI, erected by *Michelozzo* for Cosmo Pater Patriæ, with bas-reliefs by *Luca della Robbia*, and marble ciborium by *Mino da Fiesole*. — The SACRISTY (first door to the left in the corridor) contains frescoes (on the wall to the right, scenes from the Passion, by *Niccolò di Pietro Gerini*), and missals with ancient miniatures. — The CAPPELLA RINUCCINI (separated from the sacristy by an iron railing) is adorned with altar, ceiling, and mural paintings (scenes from the life of Mary Magdalene and Mary) by *Giovanni da Milano* (1379). — (The last door to the right leads to the cloisters; knock at the sacristy-door, the first on the left; the direct entrance to the cloisters is from the Piazza, p. 355.) — The chapel to the right in the church on leaving the corridor, contains frescoes of the *School of Giotto*, representing the Contest of the Archangel Michael. — The 3rd chapel belongs to the Buonaparte family; monument (1.) of Carlotta Buonaparte (d. 1830) and (r.) that of Julia Clary-Buonaparte (d. 1845), by *Bartolini*.

We now come to the chapels of the Peruzzi and the Bardi, containing \*\**Giotto's* principal paintings, which are perhaps the most excellent works of the 14th cent. In the CAPPELLA PERUZZI *Giotto* has portrayed the life of the two St. Johns: (to the left) Zacharias at the altar; Nativity of the Baptist (with a very fine figure of Elizabeth); Dancing of the daughter of Herod, a spirited and graceful figure; (on the right) Vision of the Evangelist in Patmos, from the Apocalypse; Resuscitation of Drnsiana, and Ascension of the Evangelist, whose tomb his disciples find empty. The altar-piece, a Madonna with SS. Rochus and Sebastian, is ascribed to *Andrea del Sarto*. — In the CAPPELLA BARDI (the next) *Giotto* depicts scenes from the life of St. Francis of Assisi: (to the left) He flees from home, and appears before the Sultan; St. Francis appears to St. Anthony at Arles; (on the right) Confirmation of the rules of his order by the Pope; St. Francis blessing Assisi on his deathbed, and his Burial. On the ceiling are figures representing Poverty, Chastity, and Obedience, the three chief virtues of the order, and the saint in glory. — The altar-

piece, a portrait of St. Francis, with eight lateral pictures, is by *Margilone* (13th cent.).

The CHOIR is adorned with frescoes by *Agnolo Gaddi* (middle of the 14th cent.), representing the legend of the Finding of the Cross, and on the ceiling the four Evangelists and saints. The high altar was executed from a design by *Vasari*.

LEFT TRANSEPT. The 3RD CHAPEL contains modern frescoes in the lunette, and oil-paintings at the sides, by *Luigi Sabatelli* and his sons, representing the Miracles of St. Antony, etc. — In the 4TH CHAPEL: frescoes by *Bernardo Daddi*; over the altar Madonna with saints, of the school of *Luca della Robbia*. — The 5TH CHAPEL (S. Silvestro) contains frescoes by *Giottino*, Conversion of the Emp. Constantine and Miracles of St. Sylvester; monument of *Uberto de' Bardi*, with frescoes (Last Judgment and Entombment) by *Giottino* or *Taddeo Gaddi*. — The CAPELLA NICCOLINI, in the N.E. corner of the transept (closed), constructed by *Antonio Dosio*, contains no objects of interest. — In the following CHAPEL: Monument of the architect *Alessandro Galilei*, by *Ticciati*; crucifix by *Donatello* (executed in competition with Brunellesco, see p. 369). — In the side-chapel the monument of Princess *Sophia Czartoryska* (d. 1857) by *Bartolini*, with a copy of *Rossellino's* relief of the Madonna in the Bargello (p. 354). — Farther on, monument of the composer *L. Cherubini* (born at Florence 1760, d. 1842) by *Fantacchiotti*, erected in 1869.

LEFT AISLE. Tomb of the engraver *Raphael Morghen* (d. 1833), by *Fantacchiotti*. On the opposite pillar the monument of the celebrated architect *Leon Battista Alberti*, erected by the last of his family, a group by *Bartolini*, the master's last work, and unfinished. °*Carlo Marzuppi* (d. 1450), by *Desiderio da Settignano*. *Vittorio Fossombroni* (minister, d. 1844), by *Bartolini*. *Angelo Tavanti* (minister, d. 1781). *Giovanni Lami* (d. 1770), by *Spinazzi*. On the pillar a Pietà, painted by *Angelo Bronzino*. Monument of the jurist *Pompeo Signorini* (d. 1812), by *Stefano Ricci*. °*Galileo Galilei* (d. 1642), by *Giulio Foggini*. Adjoining the entrance is the monument of the naturalist *Targioni Tozzetti*. — In the middle of the nave, near the choir, the marble tomb of *John Catrick*, Bishop of Exeter, who died at Florence in 1419 when on an embassy from King *Henry V.* to Pope *Martin V.*

The Cloisters, erected by *Arnolfo del Cambio*, contain old monuments of the *Alamanni*, *Pazzi*, and della *Torre* families, as well as modern works by *Costoli*, *Santarelli*, *Bartolini*, etc.; in the centre God the Father, a statue by *Bandinelli*. On the right is the °*Cappella dei Pazzi*, in the form of a Greek cross with a polygonal flat dome, erected by *Brunellesco*, with a handsome portal of six ancient columns, and terracottas by *Luca della Robbia*, the twelve Apostles and four Evangelists, and a large Last Supper by *Vasari* (1540). — To the left we observe the second row of cloisters, by *Brunellesco*, one of the finest Renaissance works of the kind. Obliquely opposite to it, on the other side of the cloisters, is the old Refectory (entered by the large door), containing a Last Supper attributed by *Vasari* to *Giotto*, and by *Mr. Crowe* to *Taddeo Gaddi*; the Crucifixion, with a genealogical tree of the Franciscans, and the legend of St. Francis, by pupils of *Giotto* (according to *Mr. Crowe*, by *Niccolò di Pietro Gerini*). The Tribunal of the Inquisition, which was abolished by Grand-duke *Peter Leopold*, once held its sittings here. An adjoining room (to which a few steps ascend opposite the door) contains a °Miracle of St. Francis (multiplication of the loaves), a fresco by *Giovanni du S. Giovanni*, with a portrait of the painter. This large apartment is to be adorned with a number of other frescoes. On the floor are at present a Madonna suckling the Child, and an angel from the monastery dei Frati *Ognissanti*, attributed to *Giotto*, but more probably by *Taddeo Gaddi*; the frescoes of the *Porta S. Gallo*, by *Domenico Ghirlandajo*, etc.

The direct entrance to the cloisters and refectory is from the piazza, through a gate adjoining the church.

Leaving the Piazza S. Croce, we proceed to the S. through the *Via de' Benci*, at the end of which, on the right, No. 1, is the *Pa-*

*lazzo Alberti* (once the residence of Leon Batt. Alberti; restored in 1850), and reach the Ponte alle Grazie, see p. 382.

No. 9, in the Via dei Malcontenti, which leads to the N. past S. Croce is the *Palazzo Berte* (Pl. 80; E, 5), which contains a valuable collection of pictures, formerly in the Palazzo Guadagni (p. 374; generally closed). — In the vicinity, at the corner of the Via Buonarroti, Via Ghibellina 64, is the *House of Michael Angelo* (Pl. 49; E, 5). In the 17th cent. a descendant of his family founded here a collection of pictures and antiquities, which the last of the Buonarroti bequeathed to the city. This \**Galleria Buonarroti* merits a visit chiefly on account of the designs and other reminiscences of Michael Angelo (admission, Mond. and Thursd., 9-3, festivals excepted; fee 50 c., catalogue 50 c.).

ANTE-CHAMBER: \*Battle of the Lapithæ and Centaurs, in relief, an early work by *Michael Angelo*. Adjoining it, the arm of a Discus-thrower (ancient) and a predella representing the \*Legend of St. Nicholas by *Pesellino*. Above these are two portraits of Michael Angelo, that on the right by his pupil *Marcello Venusti*, and that on the left a later work, representing Michael Angelo as a young man. — To THE LEFT of the ante-chamber is the *Room of the Drawings*: Immediately to the left is a Head of Cleopatra; then the first design of the monument of the Medici in S. Lorenzo; various studies for the Last Judgment in the Sistine Chapel, and also the first design for that work. In the centre of the end wall, a \*Madonna with the Infant Christ (executed in colours); Architectural sketches, including the first design for the façade of S. Lorenzo. On the tables in the centre are drawings for the construction of the fortress near S. Miniato (p. 383). — To THE RIGHT of the ante-chamber is the — I. ROOM: 57. Statue of Michael Angelo in a sitting posture, executed by *Ant. Novelli*, in 1620; on the walls are eighteen scenes from the great master's life, some of them in colours and others in grisaille, by painters of the 16th and 17th centuries. On the ceiling are similar scenes and allegories by the same artists. Opposite the statue is a large oil-painting of the Madonna and Christ, St. John, and other saints by *Jacopo da Empoli*, of which Michael Angelo is said to have drawn the design. — II. ROOM (chapel): 74. Madonna and Child, a basrelief in marble, by *Michael Angelo*; 77. Same subject, afterwards reproduced in bronze; 73. Cast of the Descendant from the Cross by *Michael Angelo* (? in the Uffizi); 80. Small copy of Michael Angelo's *Pietà* in the cathedral; \*81. Bronze bust of Michael Angelo, by *Ricciarelli*. — III. ROOM (Archives of MSS. of Michael Angelo). The cabinets contain models: IV. 1. David; 3. Hercules slaying *Cacus* (a fragment); 4. Nude woman; V. 10. David, the first design for the statue; autographs of the master. — Adjacent is a small museum of Etruscan and other antiquities.

The Piazza d'Azeglio and S. Maria de' Pazzi, see p. 354.

Leaving the Piazza del Duomo (p. 347) by the VIA DE' SERVI, we pass the handsome *Palazzo Manelli* (*Riccardi*; Pl. 59 a), erected by Buontalenti in 1565, and reach the —

\**Piazza della SS. Annunziata* (Pl. E, 3), embellished with two singular fountains by *Pietro Tacca*, and the equestrian statue of the grand-duke Ferdinand I., by *Giovanni da Bologna* (his last, but not best work; d. in 1608, upwards of 80 years of age), erected in 1608, and cast of metal captured from the Turks. The pedestal was adorned in 1640, in the reign of Ferdinand II.

On the S.W. side of the piazza rises the \***Spedale degli Innocenti**, or *Foundling Hospital* (Pl. 92), erected in 1421 from the designs of *Brunellesco* and his pupil *Francesco della Luna*, with charming infants in swaddling clothes between the arches, by *Luca della Robbia*. Frescoes under the portico by *Pocetti*; the busts of the four Medici, Cosmo I., Francesco I., Ferdinando I., and Cosmo II., by *Sermei*, pupil of Giovanni da Bologna. To the left in the court, over the door leading to the church of S. MARIA DEGLI INNOCENTI, is an \**Annunciation* by *Andrea della Robbia*. The Interior (restored in 1786) contains an altar-piece (covered), the \**Adoration of the Magi*, which, according to Mr. Crowe, is the finest work of *Domenico Ghirlandajo* (1488). — Opposite the Spedale is the hall of the *Servi di S. Maria* brotherhood, erected by *Antonio da Sangallo* (1519), and designed by *Brunellesco*.

The church of \***SS. Annunziata** (*Basilica Parrocchiale e Convento della Santissima Annunziata, Servi di Maria*; Pl. 2; E, F, 3) was founded in 1250, but has since been frequently altered and redecorated. The handsome portico with its three doors is probably by *Antonio da Sangallo*; that on the W. leads to the monastery and the cloisters, that in the centre to the church, the third to the chapel of the Pucci, founded in 1300, and restored in 1615, which contains a St. Sebastian by *Antonio da Pollajuolo* (shown only by special permission of the family). Over the central door a mosaic by *David del Ghirlandajo*, representing the Annunciation.

A kind of ANTERIOR COURT, which is first entered, also erected by *Ant. Sangallo*, and completed by *Caccini* shortly after 1600, is adorned with \**Frescoes* by *Andrea del Sarto* and his pupils. On the right the Assumption, by *Rosso Fiorentino*; \**Visitation*, by *Pontormo*; Nuptials of Mary, by *Franciabigio*; \**Nativity of Mary*, by *Andrea del Sarto*; \**Arrival of the Magi*, by the same master. Farther on, left of the entrance, *Nativity*, by *Alessio Baldovinetti*; *Investiture of S. Filippo*, by *Cosimo Rosselli*; \**S. Filippo giving his garment to a sick man*, by *Andrea del Sarto*; monument and bust of *Andrea*, by *G. Caccini*; \**Gambler struck by lightning*, and *S. Filippo*, by *Andrea del Sarto*; \**Cure of a man possessed of an evil spirit*, \**Death of S. Filippo* and miracles wrought by his robes, both by *Andrea del Sarto*.

The INTERIOR, consisting of nave with transepts and two series of chapels, and covered with a dome, is adorned with a large ceiling-painting of the Assumption by *Ciro Ferri* (1670). Chapels on the *Right*: 1st, frescoes by *Matteo Rosselli*; 4th, on the left the monument of the engraver *Giovita Garavaglia* (d. 1835), by *Lorenzo Nencini*. Over an altar to the left, in the S. transept, a *Pietà* by *Baccio Bandinelli*, who with his wife is buried under it. The large ROTUNDA OF THE CHOIR, designed by *Leon Battista Alberti*, and adorned with frescoes by *Volterrano* (1683) and *Utielli*, is peculiar. To the left at the entrance is the monument of *Angelo Marzi-Medici* by *Francesco Sangallo* (1546). In the 2nd chapel on the right the Nuptials of St. Catharine by *Biliverte*. The 5th chapel contains a crucifix and six reliefs from the Passion by *Giovanni da Bologna* and his pupil *Franca-villa*, with the monument of the former; in the 6th chapel a Resurrection by *Bronzino*; in the 7th a \**Madonna with saints*, by *Pietro Perugino*. In the 1st chapel of the nave, after the choir is quitted: Assumption, by *Pietro Perugino*. In the 3rd chapel, the Last Judgment, copied from *Michael Angelo's* picture in the Sistine by *Alessandro Allori*. Frescoes by the same. The *Cappella della Vergine Annunziata* in the nave to

the left of the entrance, covered with a kind of canopy, erected in 1448 by *Pagno di Capo Portigiani* from *Michelozzo's* design, and sumptuously decorated with silver and gold by subsequent princes (reliefs in silver by *Rigetti*), contains a 'miraculous' and highly revered picture of the Virgin behind the altar, a fresco of the 13th century. Over the altar a bust of the Saviour by *Andrea del Sarto*.

A door in the N. transept leads to the CLOISTERS; over it is a "fresco by *Andrea del Sarto*, the Madonna del Sacco (1525). Below it is the monument of the Falconieri, the founders of the church. On the same side is the entrance to the chapel of the guild of painters (*Cappella di S. Luca*), adorned with paintings by *G. Vasari*, *Pontormo*, and others (keys at the academy, see p. 361).

The Via della Colonna, in which is the church of S. M. Maddalena de' Pazzi, leads hence to the Piazza Azeglio (see p. 351).

To the N. W. of the Piazza dell' Annunziata the Via della Sapienza leads to the PIAZZA S. MARCO (Pl. E, 3), which is adorned with a bronze statue of general *Fanti*, by *Fedi*, erected in 1872. — On the N. side of this piazza rises **S. Marco** (Pl. 19), a church without aisles, with a flat ceiling and a dome over the choir, erected in 1290.

INTERIOR. Over the central door Christ, painted 'a tempera' on a gold ground, by *Giotto*. RIGHT WALL: 1st altar: St. Thomas Aquinas before the Crucified, by *Santi di Tito*. 2nd altar: Madonna with saints, by *Fra Bartolommeo*. 3rd altar: Madonna and two saints, a mosaic of the Roman school. — In the vestibule of the sacristy a statue of the Risen Christ, by *Antonio Novelli*. In the sacristy (erected by *Michelozzo*) a recumbent statue of St. Antoninus in bronze, by *Portigiani*. Annunciation by *Fra Bartolommeo* (?). — Adjoining the choir on the left is the chapel of Prince Stanislaus Poniatowsky (d. 1833). — Then the CHAPEL OF ST. ANTHONY (who was once a monk in this monastery); architecture and statue of the saint by *Giovanni da Bologna*. Frescoes on each side of the entrance with the funeral obsequies of St. Anthony, by *Passignani*. In the picture on the left, members of the Medici family are represented as supporting the Canopy in the procession; statues of SS. Philip, John, Thomas Aquinas, Antonine the Abbot, Eberhard, and Dominic, by *Francavilla*, the bas-reliefs by *Portigiani*; over the altar, Conversion of Matthew by *Poppi* (r.), and Healing of the leper by *Naldini* (l.). — This church contains the tombs of the celebrated scholar *Johannes Picus de Mirandola*, who died in 1494 at the age of 31, and of the equally eminent *Angelus Politianus* (d. 1494), who, having been a monk, was buried in the monastery of S. Marco (between the 2nd and 3rd altars of the left wall).

Adjacent to the church is the entrance to the once far-famed \***Monastery of S. Marco** (Pl. 58; E, 3), now suppressed, and fitted up as the *Museo Fiorentino di S. Marco* (open daily, from 1st Oct. to 31st March, 9-3; from 1st Apr. to 30th Sept., 10-4 o'clock; Sund. gratis, at other times 1 fr.). The building was originally occupied by 'Silvestrine' monks, but was transferred under Cosmo 'pater patriæ' to the Dominicans, who were favoured by the Medicis. In 1436-43 it was restored in a handsome style from designs by *Michelozzo*, and shortly afterwards decorated by *Fra Giovanni Angelico da Fiesole* (b. 1387, d. 1455) with those charming frescoes which to this day are unrivalled in their portrayal of profound and devoted piety. The painter *Fra Bartolommeo della Porta* (1469-1517) and the powerful preacher *Girolamo Savonarola* (burned at the stake in 1498, see p. 329) were also once inmates of this monastery.

The CLOISTERS, which are entered immediately from the street, are partially decorated with frescoes of the 18th cent., but these are far surpassed by the numerous and excellent works of the earlier masters, among which the following deserve special notice: opposite the entrance, \*Christ on the Cross, with St. Dominic; left, over the door to the sacristy, \*St. Peter the Martyr, indicating the rule of silence peculiar to the order by placing his hand on his mouth; over the door to the chapter-house (see below) St. Dominic with the scourge of nine thongs; over the door of the refectory a Pietà; over the entrance to the 'foresteria', or apartments devoted to hospitality, \*Christ as a pilgrim welcomed by two Dominican monks. Over the door Christ with the wound-prints, all by *Fra Angelico*. The second door in the wall opposite the entrance leads to the CHAPTER HOUSE, which contains a large \*Crucifixion, Christ between the thieves, surrounded by a group of twenty saints, all life-size, with busts of seventeen Dominicans below, by *Fra Angelico*. The door in the corner of the cloisters leads to the GREAT REFECTORY, one of the walls of which is adorned with the so-called \*Providenza (the brothers seated at a table and fed by two angels), by *Fra Bartolommeo*, and a Crucifixion. The door next to the chapter-house leads to the second monastery court, in the passage to which, on the right, is the staircase to the upper floor. On the left, before the staircase is reached, is the SMALL REFECTORY, containing a \*Last Supper by *Dom. del Ghirlandajo*.

UPPER FLOOR. The corridor and the adjacent cells are adorned with a succession of frescoes by *Fra Angelico*, and partly by his pupils. In the CORRIDOR: \*Annunciation, Christ on the Cross with St. Dominic, and an Enthroned Madonna with saints. — In the CELLS (the 9th): \*Coronation of the Madonna by Christ. The other cells contain the two Marias at the Sepulchre, Christ opening the gates of Paradise, Transfiguration, Entombment, etc. Opposite the staircase is a cell containing reminiscences of St. Antonine. The last cells on the left side of the passage were once occupied by *Savonarola*, and now contain his portrait by *Fra Bartolommeo*, a copy of an old picture representing his execution (original at the Pal. Corsini, p. 371), autographs, a marble monument erected in 1873, with a relief (*Savonarola* addressing his judges), and his bust. On the right of the staircase is the LIBRARY, the arrangement of which is incomplete. Glass-cases in the middle contain a number of books of the Gospels with miniatures, most of them by *Fra Benedetto*, the brother of Angelico. On the other side of this passage are two CELLS, adjoining those of St. Antonine, and containing three small easel \*Pictures by *Fra Angelico*, which formerly adorned reliquaries in S. Maria Novella, representing an allegory, the Presentation in the Temple, and Christ teaching. The LAST CELL on the right, embellished with an \*Adoration of the Magi, a fresco, by *Fra Angelico*, is said to be that which Cosimo Pater Patria caused to be fitted up for himself, and where he received the Abbot Antonius and *Fra Angelico*. In 1442 Pope Eugene IV. slept here when in Florence for the purpose of consecrating the church of S. Marco. — An adjacent room contains the flags and colours of all the towns and corporations which were represented at the Dante festival in 1865.

The *Accademia della Crusca*, founded in 1582 to maintain the purity of the Italian language, and established in part of this building, is now publishing a large dictionary of the language, and occasionally holds public sittings.

Leaving the Via della Sapienza, and turning to the left into the Via Ricasoli, we reach, beyond No. 54, the entrance to the \*Academy of the Fine Arts (Pl. 37; E, 3; open daily, 9-3, admission 1 fr.; on Sundays, 10-3, and in summer on Thursd., gratis).

This collection contains few pictures to strike the eye or imagination of the amateur, but it is a most important collection for students of the development of Italian art during the 14th-16th centuries. We have the

advantage here of being able to concentrate our attention on the characteristic features of the Italian schools, as this collection is restricted to national productions. The small pictures of *Giotto* (large paintings, Nos. 18-29) and *Fra Angelico's* Life of Christ (small pictures, Nos. 11 and 24) are, however, merely to be regarded as supplementary to the much more important labours of these two great masters in the department of fresco painting. The Last Judgment (small picture, No. 41), and the Descent from the Cross (large picture, 34), afford a good idea of *Fra Angelico's* works. This collection also possesses one of the chief works of *Gentile da Fabriano*, an Umbrian master, closely allied to *Fra Angelico* (Adoration of the Magi, large picture, 32). This work affords distinct evidence of the unity of sentiment which existed between the Schools of the North and South in the 15th cent., notwithstanding their external independence. The collection is chiefly important for the study of the Florentine art of the 15th cent. We may mention as one of *Filippo Lippi's* earliest works the Nativity of Christ (small picture, 26), whereas the Coronation of the Virgin (large picture, 41), with a portrait of himself, belongs to his latest period. In these works the master obviously aims at sensuous beauty in his female forms, he departs from the strictly ecclesiastical style, and borrows various effects from the province of sculpture. The want of repose caused by the desire to introduce technical novelties is very apparent in *Sandro Botticelli's* Coronation of Mary (large picture, 47); and *Verrocchio's* Baptism (large picture, 43) shows the same tendency in a higher degree, distantly recalling *Leonardo's* technical skill and sense of form. *Domenico Ghirlandajo*, another master of this school, was thoroughly conversant with traditional forms, and with their aid he has been enabled to produce majestic and spirited figures, and to unite in them the result of the labour of two generations. His Madonna and angels (old picture, 17) is better preserved than the Nativity of Christ (large picture, 50). A comparison of *Ghirlandajo's* simplicity of style, the outcome of a mature imagination, with the elaborate and exaggerated manner of the old masters, is most instructive. *Lorenzo di Credi's* Nativity (large picture, 51) is not only a carefully executed, but also an impressive picture on account of its beauty of expression and symmetry of composition. Among *Fra Bartolommeo's* pictures, Mary appearing to St. Bernard is particularly worthy of notice (large picture, 66), as it affords an insight into the master's method of painting; his St. Vincent (large picture, 69) is also a fine work. *Mariotto Albertinelli*, who is closely allied to *Fra Bartolommeo*, is well represented by a Madonna (large picture, 72) and a Trinity (large picture, 70); his Annunciation (No. 73) is no longer in its original condition. *Perugino's* pictures are greatly above the average merit of his works; in his Pietà (large picture, 58) an admirable individuality of character is exhibited; his skill as a colourist is shown in his Mount of Olives (53); and his Assumption of the Virgin (55), admirable both in composition and execution, shows the master at the zenith of his power.

The ENTRANCE HALL contains four bas-reliefs in terracotta, by *Luca della Robbia*, and busts of great painters, in plaster. Passing to the right through a room with casts of modern sculptures, we enter the

#### HALL OF THE LARGE PICTURES.

1. Mary Magdalene, 13th cent.; 2. *Cimabue*, Madonna; 3. *Buffalmacco*, St. Humilitas of Faenza, 1316; 4-13. *Giotto* Ten scenes from the life of St. Francis (executed by *Taddeo Gaddi*); 15. *Giotto*, Madonna with angels; 18-29. *Giotto*, Twelve small scenes from the life of Christ; 30. *Don Lorenzo di Firenze*, Annunciation, with SS. Catharine, Antony, Proculus, and Francis. Above: 31. *Niccolò di Pietro Gerini*, Entombment; 32. *Gentile da Fabriano*, Adoration of the Magi, the painter's master-piece, 1423; 34. *Fra Angelico*, Descent from the Cross; 36. *Massaccio*, Madonna with angels; 39. John the Baptist, by a pupil of *Filippino Lippi*; 40. *Filippo Lippi*, Madonna with saints; 41. Coronation of

Mary, with predella, by the same; 43. *Andrea del Verrocchio*, Baptism of Christ, in which the first angel on the left was painted by *Leonardo da Vinci*, a pupil of this master; 46. *Alessandro Botticelli*, Madonna with several saints, and 47. Coronation of the Virgin; \*48. *Pesellino*, SS. Cosmas and Damianus, predella; 49. *S. Botticelli*, St. John in Patmos, predella; 50. *Domenico Ghirlandajo*, Nativity; \*51. *Lorenzo di Credi*, Nativity (his finest work); 52. *Sandro Botticelli*, Madonna and saints; 53. *Pietro Perugino*, Christ on the Mt. of Olives; \*55. *Sandro Botticelli*, Assumption of the Virgin, with SS. Michael, Giovanni Gualberto, Dominicus, and Bernard, brought from Vallombrosa, 1500; 56. *Sandro Botticelli*, Christ on the Cross; 57. Descent from the Cross, the upper half by *Filippino Lippi*, the lower by *Pietro Perugino*; 58. *Perugino*, Pietà; 59. *Andrea del Sarto*, Four saints; 62. Two angels, by the same; 63. History of four saints, by the same; 64. *Fra Bartolommeo* (?), Madonna, al fresco; 65. *Fra Bartolommeo* (?), Madonna with Jesus, St. Catharine, and other saints; 66. Mary appearing to St. Bernard, by the same; 67. *Raffaellino del Garbo*, Resurrection; 68. Dead Christ, Madonna, Mary Magdalene, and other saints, designed by *Fra Bartolommeo*, and painted by his pupil *Fra Paolino da Pistoja*; 69. *Fra Bartolommeo*, St. Vincent; \*70. *Mariotto Albertinelli*, The Trinity; 71. *Fra Paolino da Pistoja*, Madonna presenting St. Thomas with her girdle; \*72. *Mariotto Albertinelli*, Madonna with Jesus and four saints; 73. Annunciation, by the same, 1510; 75. *Francesco Granacci*, Madonna and four saints; 78. *Fra Bartolommeo*, Head of Christ, and four saints (that in the centre supposed to be Savonarola, next to him a Carthusian monk with his finger on his lips); 82. *Fra Bartolommeo*, Christ, and four saints; 86. *Giovanni Antonio Sogliani*, Madonna enthroned; 88. *Angelo Bronzino*, Portrait of Cosmo de' Medici; 89. *Alessandro Allori*, A lady of the Medici family; 90. *Michele di Ridolfo del Ghirlandajo*, The thousand martyrs; 92. *Angelo Bronzino*, The two Maries with the body of Christ; 93. *Alessandro Allori*, Annunciation; 97. *Francesco Morandini*, Crucifixion; 100. *Santi di Tito*, Pietà.

We now return through the Entrance Hall, proceed to the left through the *Library* of the Academy into another vestibule, and thence reach the —

#### HALL OF THE ANCIENT PICTURES,

containing 60 works, most of them by unknown masters of the Tuscan school of the 14th and 15th cent., less interesting than the above to the ordinary visitor. Among them may be mentioned: \*5. *Luca Signorelli*, Mary Magdalene at the foot of the Cross; 11. *Giacomo Francia* (son of Francesco), Madonna with saints; 17. *Dom. Ghirlandajo*, Madonna and four saints; 19, 22. *Fra Angelico*, Two Madonnas; \*24. *S. Botticelli*, The three Graces. In the centre of the saloon are temporarily placed a number of casts destined for the Michael Angelo Museum (p. 364). Adjacent is the —

#### HALL OF THE SMALL PICTURES,

containing 71 works of the 14th-17th cent., most of them excellent: 1. *Luca Signorelli*, Predella, Last Supper, the Mount of Olives, and the Scourging of Christ; 3. Ascension and Annunciation, attributed to *Giotto*; 8. *Fra Angelico*, Miracle wrought by SS. Cosmas and Damianus; \*11, 24. *Fra Angelico*, Life of Christ in 8 pictures and 35 sections; 12. *Fra Filippo Lippi*, Madonna adoring the Child; 13. *Lorenzo di Credi*, Nativity; 16. *Fra Angelico*, History of five martyrs; \*18. *Perugino* (or *Raphael*?), Two portraits of monks; 19. *Fra Angelico*, Six representations from the legends of the saints; 20. *Fra Angelico*, Madonna with the Infant Jesus, above it the Trinity; 25. *A. Verrocchio*, Tobias and three angels; \*26. *Fra Filippo Lippi*, Madonna adoring the Infant Christ; 27. *Carlo Dolce*, Portrait of *Fra Angelico*; 28. *Fra Bartolommeo*, Hieronymus Savonarola in the character of S. Pietro Martire; *Fra Angelico*: 36. Coronation of the Virgin, 37. Crucifixion, 38. Passion, below it the Adoration of the Magi, 40. Entombment, \*41. Last Judgment, with numerous figures, 49. St. Thomas Aquinas with his pupils, 50. Albertus Magnus teaching theology.



## SALA DEI CARTONI.

A number of the original designs of the most celebrated masters are preserved here: 1. *Fra Bartolommeo*, St. Peter; 2. Madonna (della Gatta), copy from *Raphael*; 4. *Fra Bartolommeo*, St. Paul; 5. Madonna, after *Raphael*; 6. *Correggio*, Madonna; 9. Mary Magdalene, 10. St. Jerome, 11. St. Catharine of Siena, all by *Fra Bartolommeo*; 17. *Andrea del Sarto*, Madonna (in the Palazzo Panciatichi, p. 365); 21. Madonna (del velo), after *Raphael*; 18. Madonna, 22. St. Dominicus, by *Fra Bartolommeo*.

THE FIRST FLOOR contains the GALLERIA DEI QUADRI MODERNI (catalogue 20 c.; admission gratis), few of which are worthy of mention. 2nd R.: *C. Vogel*, 9. Scenes from the Divine comedy, 12. Scenes from *Faust*; 10. *Ussi*, Expulsion of the Duke of Athens from Florence. — 3rd R.: *Castagnola*, Filippino Lippi and his mistress; 10. *Bezzuoli*, Entry of Charles VIII. into Florence. — 4th R.: 3. *Marko*, Harvest; 21. *Marko*, Return of Tobias. — 5th R.: 8. *C. Vogel*, Jesus and the little children; 17. *Buzzi*, Reading lesson. — 6th R.: 19. *Marko*, Landscape; 28. *Bezzuoli*, Portrait of Marie Antoinette.

In a straight direction from the entrance (No. 49) a COURT is reached, where several bas-reliefs by *Luca della Robbia* are preserved; cast of a colossal horse's head from the Monte Cavallo in Rome; original model of the Rape of the Sabine women, by *Giovanni da Bologna*; St. Matthew, just begun, by *Michael Angelo*, etc. — Then to the right through a passage with reliefs in plaster, at the end of which is the *Gallery of Statues*, a rich collection of casts of the most celebrated sculptures in Europe. The *Architecture Saloon* contains drawings of important buildings, and in other rooms are sketches, drawings, etc., by modern architects.

In the SECOND COURT stands the celebrated David by *Michael Angelo* (p. 332); the statue is placed under a glass building covered with a dome. This court is also destined for the reception of the 'Michael Angelo Museum', in which a complete collection of casts and photographs of the great master's works is to be exhibited.

The same building (entrance in the Via Alfani) contains the celebrated manufactory of *Florentine Mosaics* (a branch of industry founded in the middle of the 16th cent.), containing a collection of the materials used and of finished works, open daily except Sundays.

The custodian of the Academy also keeps the keys of the **Cloisters of the Recollets**, or barefooted monks (*Chiostrò della Compagnia dello Scalzo*), Via Cavour 69, adorned with admirable frescoes in grisaille from the history of John the Baptist, by *Andrea del Sarto* (the 5th and 6th at the end of the wall on the right were painted from *del Sarto's* designs by *Franciabigio*; the rich ornamentation is by both masters). — Adjacent is the *Casino Mediceo* (No. 63; Pl. 51), erected in 1576 by *Buontalenti*, on the site of the famous Medici gardens, where Lorenzo il Magnifico, and after him Giuliano de' Medici, preserved a great number of the treasures of art which were afterwards transferred by Cosmo I. to the gallery of the Uffizi. — Proceeding farther to the N., we traverse the Via Salvestrina to the left, and enter the Via S. Gallo, No. 74 in which, a corner house, is the \**Palazzo Pandolfini*, now *Nencini* (Pl. 74), designed by *Raphael*, but not erected till ten years after his death.

At the beginning of the VIA CAVOUR is the \***Palazzo Riccardi** (Pl. 83; E, 3), formerly *Medici*, which has been in possession of the government since 1814. It was erected by *Michelozzo* (who was the first to taper the rustica in its different stories) about

1434 under Cosmo Pater Patriæ, and was celebrated as a seat of art and science, where the Greek scholars, who fled from Constantinople on its conquest by the Turks, first met with a hospitable reception. Lorenzo il Magnifico was born here in 1448, as well as his sons Pietro, Giovanni, and Giuliano. The illegitimate Medici, Julius, Hippolytus, and Alexander, subsequently resided here, and this family continued in possession of the palace until it was sold in 1659 by the grand-duke Ferdinand II. to the Marchese Gabriello Riccardi, who extended it considerably, enclosing within its precincts the *Strada del Traditore*, where on 7th Jan., 1537, Duke Alexander was assassinated by Lorenzino de' Medici.

An imposing gateway leads to a VESTIBULE and COURT, where ancient busts, statues, sarcophagi, Greek and Latin inscriptions from Rome, etc. were placed by the Marchese Riccardi in 1719. Four of the frames for inscriptions resembling windows were designed by *Michael Angelo*. — The passage to the SECOND COURT contains ancient busts; the court itself contains a fountain and the statue of Duke Alexander. — Three flights of steps ascend to the UPPER FLOOR, occupied by the Biblioteca Riccardiana and the archives. The *Library*, founded by the Riccardi, and purchased by the state in 1812, comprises 23,000 vols. and 3500 MSS., including several by *Dante*, *Petrarch*, *Macchiavelli*, *Galileo*, ancient diptychs, etc. Admission 9-3 daily, except Sundays (vacation 10th Aug. to 12th Nov.). — The private CHAPEL of the Medici, constructed and decorated by *Michelozzo*, also on the upper floor (shown by the custodian of the Academy, 50 c.; abundant light necessary) is embellished with frescoes by *Benozzo Gozzoli*, representing the journey of the Magi, with numerous portraits of the Medici. In the *Gallery* adjoining the library are frescoes (in honour of the Medici family) and good paintings on the mirrors by *Luca Giordano*, 1683.

On the corner house opposite the Palazzo Riccardi, in the Via Cavour, is a relief of the Madonna by *Desiderio da Settignano*. On the other side, towards the Baptistery, is a similar work by *Donatello*.

In the Via Cavour are also the palaces of the *Panciatichi* (Pl. 76; E, 3), erected by *Carlo Fontana* about 1700, containing one of the best existing copies of Raphael's Madonna of Loreto, the original of which is lost; *Covoni* (formerly *Capponi*, by *G. Silvani*, about 1660); *Pestellini* (formerly *Naldini*); *Poniatowski* (1740; Pl. 81; F, 2), and others. — The *Biblioteca Marucelliana* (Pl. 43; E, 4), founded in 1703 by *Francesco Marucelli* (with catalogue), is also situated in the Via Cavour near S. Marco (open every week-day, 10-2; librarian Pietro Fanfani).

Opposite the palace of the Medici, in the Via delle Cantonelle, is situated the church of *S. Giovannino degli Scolopi* (belonging to the *Padri delle Scuole Pie*; Pl. 50; D, 3), erected in 1352, remodelled in 1580 by *B. Ammanati*, completed in 1661 by *Alfonso Parigi*, and in the possession of the Jesuits from 1557 to 1775. The scientific institutions of the city, comprising a library, observatory, etc., are established here. The church contains frescoes and pictures by *Allori*, *Bronzino*, *Santi di Tito*, etc.

In the PIAZZA S. LORENZO (Pl. D, 3), with the church of that name, is the *Base di S. Lorenzo*, by *Baccio Bandinelli*, adorned

with sculptures (Giovanni delle Bande Nere, father of the first Cosmo, triumphing over his enemies). In 1850 the monument was restored and furnished with the unpleasing and unfinished statue of Giovanni, executed by the same master.

\***S. Lorenzo** (Pl. 17; D, 3), founded in 390, consecrated by St. Ambrose in 393, is one of the most ancient churches in Italy. In 1423 it was burned down, and in 1425 re-erected by the Medici from the designs of *Filippo Brunellesco*, who restored the form of the early Christian basilica, consisting of a nave and aisles terminated by a transept, the nave being covered with a flat ceiling, and the aisles with groined vaulting. He then added chapels resembling niches on each side, and above the cross he placed a dome without a drum. Over the columns (14 in number, and two pillars) he replaced the ancient beams which had been removed in the middle ages, and which now support the projecting arches. — The high altar was consecrated in 1461. The inner wall of the façade is by *Michael Angelo*, who also added the new sacristy (see below), and the Laurentian Library. His design for the outside of the façade (1516) was unfortunately never executed, but is preserved in the Galleria Buonarroti (p. 358). The church has been handsomely restored within the last few years.

At the end of the RIGHT AISLE is the Monument of the painter Benvenuto (d. 1844), by *Thorvaldsen*. Bas-reliefs on the two pulpits by *Donatello* and his pupil *Bertoldo*. — RIGHT TRANSEPT, side chapel on the right, (r.) Nativity, by *Costmo Rosselli*. Over the altar of the chapel a figure of the Virgin, erected in 1856 to commemorate the cessation of the cholera in 1855. Also a marble altar by *Desiderio da Settignano*.

At the foot of the steps leading to the CHOIR is the simple tomb of Cosmo de' Medici, 'Pater Patriæ' (d. 1464). — In the 2nd chapel to the left of the choir the monument of a Countess Moltke Ferrari-Corbelli, by *Dupré*, 1864. — The OLD SACRISTY, erected by *Filippo Brunellesco*, is covered with a polygonal dome; the bronze doors, bas-reliefs, and statues of the four Evangelists (below the dome), are by *Donatello*; fountain probably by *Brunellesco*; Adoration of the Infant Christ, a painting by *Ridolfo Ghirlandajo*; to the left of the entrance, the monument of Giovanni and Pietro de' Medici, by *Andrea del Verrocchio*. In the centre the marble monument of Giovanni Averardo de' Medici and Piccarda Bueri, the parents of Cosmo, by *Donatello*. — In the 2nd chapel, an Annunciation, by *Fra Filippo Lippi*. — In the LEFT AISLE the Martyrdom of St. Lawrence, a large fresco by *Angelo Bronzino*. — The adjoining door leads to the cloisters and the library (see below). In the following chapel, the Martyrdom of St. Peter by *Sogliani*.

To S. Lorenzo belong also the new Sacristy and the Chapel of the Princes, the entrance to which, however, is now in the Piazza della Madonna at the back of the church, nearly opposite the Via Faenza. From the vestibule we ascend a flight of steps to the left, and reach the new sacristy on the left, and the chapel of the princes on the right.

The \*\*NEW SACRISTY (*Sagrestia Nuova*; admission, see p. 327; fee), a quadrangular chapel of admirable proportions, adorned with two series of Corinthian pilasters, one above the other, constructed by *Michael Angelo* in 1523-29, contains the celebrated Monu-

ments of the Medici, executed by *Michael Angelo* by order of Pope Clement VIII (Giulio de' Medici, 1523-34), the master's finest sculpture.

On the right the Mausoleum of Giuliano de' Medici, Duc de Nemours, brother of Pope Leo X. and younger son of Lorenzo il Magnifico (d. 1516). Above is the figure of the duke in a sitting posture; over his tomb are the "Statues of Day and Night, master-pieces of Michael Angelo, the latter especially admired. A contemporary poet, Giovanni Battista Strozzi, wrote upon it the lines:

*La Notte, che tu vedi in sì dolci atti  
Dormire, fu da un Angelo scolpita  
In questo sasso, e perchè dorme ha vita;  
Destata, se no' l' credi, e parleratti.*

Michael Angelo, in allusion to the suppression of political liberty (by Alessandro de' Medici 1530, see p. 329), answered:

*Grato m' è 'l sonno e più l'esser di sasso;  
Mentre che 'l danno e la vergogna dura  
Non veder, non sentir m' è gran ventura;  
Però non mi destar; deh! parla basso!*

Opposite is the statue of Lorenzo de' Medici, Duke of Urbino (d. 1518), grandson of Lorenzo il Magnifico, represented in profound meditation (hence called *il pensiero*); below it his tomb with "Statues of Evening and Dawn (*Crepusculo e Aurora*), also by *Michael Angelo*. Lorenzo was father of Catharine de' Medici, queen of Henry II., and mother of Charles IX. of France, and of Alexander de' Medici, the first duke of Florence, who was assassinated on 7th Jan., 1537, by his cousin Lorenzino. Opposite the altar in the centre, is an unfinished "Madonna, by *Michael Angelo*; on the left, St. Damianus, by *Raffaello da Montelupo*; on the right, the statue of *St. Cosmo*, by *Fra Giovanni Angiolo da Montorsoli*, a pupil of Michael Angelo.

The CHAPEL OF THE PRINCES (*Cappella dei Principi*), the burial-chapel of the grand-dukes of the Medici family, was constructed in 1604 by *Matteo Nigetti*, by order of the grand-duke Ferdinand I. (designed by *Giovanni de' Medici*).

It is octagonal in form, covered by a dome, and gorgeously decorated with marble and valuable "Mosaics in stone. The paintings in the dome (Creation, Fall, Death of Adam, Sacrifice of Noah, Nativity, Death and Resurrection, Last Judgment) are by *Pietro Benvenuti*. In six niches below are the granite sarcophagi of the princes, some of them with gilded bronze statues, from Cosmo I. (d. 1564) to Cosmo III. (d. 1723, whose son Giov. Gaston was the last of the family, d. 1737). On the coping round the chapel are placed the armorial bearings of 16 Tuscan towns in stone-mosaic. — A sum of 22 million lire (about 880,000 £.) was expended by the Medici family from their private resources on the construction and decoration of this chapel.

In the *Cloisters*, which are attributed to *Brunellesco*, immediately adjoining the church, is the entrance to the **Biblioteca Laurenziana** (Pl. 41; D, 3; open daily 9-3, except on Sundays and festivals; vacation 1st Oct. to 12th Nov.; custodian 1/2-1 fr.), a library founded by Cosmo in 1444, and gradually enlarged by the Medici. Its chief treasure consists of about 8000 MSS. of Greek and Latin classical authors. The building was begun in 1524 from the design of *Michael Angelo*, the portico was built by him, and the staircase (which was also designed by Michael Angelo) was completed in 1571 by *Vasari*; the rotunda containing the Biblioteca Delciana, was erected in 1841, from *Pasquale Poccianti's* design.

The wooden ceiling of the Library was executed by *Tasso* and *Carota*, from *Michael Angelo's* designs. The latter also furnished the design for the 88 'plutei' to which the MSS. are attached. Among these is a number of codices of rare value: Virgil of the 4th or 5th cent.; Tacitus, two MSS. of the 10th and 11th cent., the older brought from Germany, and the sole copy containing the first five books of the Annals. The Pandects, of the 6th or 7th cent., carried off from Amalfi by the Pisans in 1135, the oldest existing MS. of this collection, on which the study of Roman Law almost entirely hinges. Most important MS. of Æschylus. Cicero's Epistole ad Familiars, written by Petrarch. Petrarch's Canzone, with portraits of Petrarch and Laura. MSS. and letters of Dante. Decamerone of Boccaccio. MSS. of Alfieri. Document of the Council of Florence, 1439; Codex Amiatinus; Syrian gospels; maps of Ptolemy; miniatures, etc. Catalogues of Oriental MSS. by Lewis Asseman and Bandini, continued by Furia.

To the N. of S. Lorenzo is situated the new *Mercato Centrale* (Pl. D, 3), constructed from a design by Mengoni (p. 123). — The Via Faenza, and the Egyptian and Etruscan Museum, see p. 372.

We now proceed by the Via del Giglio to the **Piazza S. Maria Novella** (Pl. C, 3), where festivals and games were frequently celebrated in former times. The principal of these, instituted in the reign of Cosmo I. in 1563, took place on the eve of the festival of St. John, and consisted of a race of four four-horse chariots, called *Prasina* (green), *Russata* (red), *Veneta* (blue), and *Alba* (white), resembling those of the ancients. Two obelisks of marble of 1608, standing on brazen tortoises, perhaps by Giov. da Bologna, served as goals. — The *Loggia di S. Paolo*, an arcade opposite the church, erected in 1451 from Brunellesco's design, is adorned with terracottas by *Andrea della Robbia*. — The canopy at the corner of the Via della Scala is by *Francesco Fiorentino*, a pupil of Don Lorenzo Monaco (14th cent.).

The church of **\*S. Maria Novella** (Pl. 25; C, 3), begun in 1278 on the site of an earlier edifice, from designs by the Dominican monks *Fra Sisto* and *Fra Ristoro*, and completed in 1357, was furnished with a beautiful marble façade in 1456-70, designed by *Leon Battista Alberti*, who first employed volutes here to connect the nave and aisles. A quadrant and two concentric meridians on the right and left were constructed by *P. Ignazio Danti* in 1572. — The closed pointed arcades ('avelli') of black and white marble which adjoin the church on the right, were originally constructed from designs by *Brunellesco*, but were frequently altered at subsequent periods, and have recently been restored.

The spacious **Interior**, a Latin cross with pointed vaulting, consists of nave and aisles resting on twelve slender pillars, to which chapels were afterwards added by *Vasari* and others. The unequal distances between the pillars, varying from 37 ft. to 49 ft., are an unexplained peculiarity.

**ENTRANCE WALL:** over the central door, a crucifix in the style of *Giotto*; on the right the Trinity with the Virgin and St. John, one of the best works of *Masaccio*. — The altar-pieces in the **RIGHT AISLE** are of the 17th cent.; 6th altar to the right, Resuscitation of a child, by *Ligozzi*. — In the **RIGHT TRANSEPT**, to the right by the steps, is the Gothic monument of the Patriarch Joseph of Constantinople (d. 1440), who died while attend-

ing the great Council of 1439, which was first held at Ferrara in 1438, and afterwards at Florence, with a view to the union of the Western and Eastern churches. Above the monument is a Madonna by *Nino Pisano*. Farther on, the monument of bishop Aliotti (d. 1336) by *Tino di Camaino*. — We now ascend the steps to the CAPELLA RUCELLAI, which contains a large Madonna, one of *Cimabue's* best productions, and a Martyrdom of St. Catharine by *Bugiardini* after a cartoon of Raphael; on the right, Annunciation, by *Neri di Bicci*, and St. Catharine, by a pupil of Ghirlandajo. — Immediately to the right of the choir is the CHAPEL OF FILIPPO STROZZI, with his monument by *Benedetto da Majano*, and frescoes by *Filippino Lippi* (1486), the Miracles and martyrdom of SS. John and Philip.

The CHOIR contains Frescoes by *Domenico Ghirlandajo* (1490), which form that master's most popular work, and are, at the same time, the finest existing specimens of the earlier Florentine art. On the upper part of the wall of the altar is a Coronation of the Madonna; adjoining the windows are SS. Francis and Peter the Martyr, the Annunciation, and John the Baptist, and below all these, Giovanni Tornabuoni and his wife, at whose expense these works were executed. — On the left wall, in seven sections, is represented the life of Mary: Expulsion of Joachim from the Temple, Nativity of Mary (the architecture of the interior beautifully enriched). Presentation in the Temple, and Nuptials, Adoration of the Magi and Massacre of the Innocents, and Her death and Assumption. — The right wall is devoted to the life of John the Baptist. The first scene, Zacharias in the Temple, is celebrated for the number of portraits which are introduced in a remarkably easy and life-like manner. The figures to the right in the foreground are said to be portraits of Francesco Sassetti, Andrea Medici, and Gianfrancesco Ridolfi, three famous merchants, while to the left are Cristoforo Landini, Angelo Poliziano, Marsilio Ficino, and Gentile de' Becchi, distinguished scholars and humanists; the five men at the back, and to the right of Zacharias, are members of the Tornabuoni family; the four figures by the angel are also said to be family portraits. The other scenes are the Visitation, Nativity of John, the Naming of the child, the Baptist preaching repentance (in which the master shows his art in grouping and individualising the figures), Birth of Christ, and Dancing of the daughter of Herod. Several of these paintings are unfortunately nearly obliterated. — The choir-stalls are by *Baccio d'Agnolo*, altered by *Vasari*. At the back of the altar is a slab to the memory of Lionardo Dati by *Ghiberti*.

The CHAPEL to the left of the choir, by *Giuliano da Sangallo*, contains the celebrated wooden crucifix of *Brunellesco*, which gave rise to the rivalry between him and his friend Donatello (p. 357). — The following GADDI CHAPEL, by *Antonio Bosio*, is adorned with the Raising of the daughter of Jairus, by *A. Bronzino*, and bas-reliefs by *Bandini*. — The STROZZI CHAPEL in the left transept, to which steps ascend, contains Frescoes with numerous figures; opposite the entrance the Last Judgment, (1.) Paradise, by *Andrea Orcagna*; Hell (r.), by his brother *Bernardo*; altar-piece, Christ with saints, completed in 1357, by *Andrea*. — The next door, in the corner, leads to the sacristy, the most interesting object in which is a Fountain by *Luca della Robbia*, a magnificent work of its kind. — The altar-pieces in the N. AISLE are of the 17th and 18th cent. — In the NAVE a pulpit by *Buggiano*: stained glass by *Alessandro Fiorentino* (*Botticelli?*), from drawings by *Filippino Lippi*.

On the W. side of the church are the ancient Cloisters, called *il Chiostro Vecchio*, or *Verde*, the older adorned with frescoes by *Orcagna*, the more recent by *Paolo Uccello*, in terra verde (different shades of green; best preserved, the Deluge). — To the right in the cloisters is the CAPELLA DEGLI SPAGNUOLI (best light, 10-12), begun in 1320, with frescoes of *Giotto's* school (erroneously attributed by *Vasari* to *Taddeo Gaddi* and *Simone di Martino*, but, according to Mr. Crowe, probably by *Andrea da Firenze*); on the wall of the altar the Passion, on the ceiling the Resurrection, Ascension, Descent of the Holy Ghost, Christ and the doubting Peter on the water, the last probably by *Antonio Veneziano*. On the E. side (r.) the Church militant and triumphant, the pope and emperor

on the throne, surrounded by their counsellors and illustrious men, such as Petrarch with Laura, Boccaccio, Cimabue, etc. On the W. side (1.) Thomas Aquinas in his professorial capacity, surrounded by angels, prophets, and saints, in his hand an open book; at his feet the discomfited heretics Arius, Sabellius, and Averrhoës. In the niches 28 figures representing virtues and sciences, all perhaps by *Andrea da Firenze*. On the wall of the door, Christ in Hades. — The GREAT CLOISTERS, the largest at Florence, with frescoes by *Cigoli*, *Allori*, *Santi di Tito*, *Pocetti*, and others, are adjacent to the above.

The LABORATORY of the monastery (*Spezeria*, entrance by the large door in the Via della Scala, No. 14; attendant 1/2 fr.), celebrated for the perfumes and liqueurs prepared in it, especially 'Alkermes', a speciality of Florence, flavoured with cinnamon and cloves, contains a room (formerly a chapel) decorated with frescoes of the 14th cent. (the Passion) by *Spinello Aretino*.

The *Railway Station* (Pl. C, 2, 3) is situated near the back of this church.

The Via de' Fossi (Pl. C, 4), leads from the Piazza S. Maria Novella to the *Piazza del Ponte alla Carraja*, then to the right to the broad street of *Borgo Ognissanti*, and, a little farther, to the PIAZZA MANIN (Pl. B, 3), where there are several large hotels. On the W. side of the piazza are the suppressed monastery of the Minorites and the church of *S. Salvatore d' Ognissanti* (Pl. 30), erected in 1554, remodelled in 1627, the façade by *Matteo Nigetti*, with lunette by the *della Robbia*, representing the Coronation of Mary.

The INTERIOR, consisting of a nave and transept with flat ceiling, contains, over the 3rd altar to the right, a Madonna and saints by *Santi di Tito*; between the 2nd and 3rd altar St. Augustine, a fresco, by *A. Botticelli*; opposite to it St. Jerome, a fresco, by *Domenico Ghirlandajo*. A chapel in the left transept approached by steps contains a crucifix by *Giotto*. Opposite is the entrance to the sacristy, which contains a fresco of the Crucified, with angels, monks, and saints, of the school of *Giotto*. — Adjacent is the entrance to the CLOISTERS, in the style of *Michelozzo*, adorned with frescoes by *Giovanni da S. Giovanni* (in the corner obliquely opposite the entrance from the church), *Ligozzi*, and *Ferrucci*. — The old RE-FECTORY is adorned with a large fresco of the 'Last Supper, by *Dom. Ghirlandajo*, 1490.

We now proceed through the Via del Prato and the *Porta al Prato* (Pl. B, 2), turn to the left, and reach the *Cascine* (p. 387); or they may be reached by entering the *Lung' Arno Nuovo* near the Piazza Manin, and either following this street, or the *Corso Vittorio Emanuele*, which passes the Politeama (p. 327) and leads to the *Nuova Barriera* (near the Piazza Vittorio Emanuele, Pl. A, 2).

Turning to the left from the Borgo Ognissanti to the *Ponte S. Trinità*, we perceive, on the left (*Lung' Arno Corsini*, No. 10) the **Palazzo Corsini** (Pl. 65; C, 4), erected, or at least remodelled, in 1656, from designs by *Silvani* and *Ferri* (magnificent staircase by the latter). It contains a valuable *Picture Gallery* (open on Tuesd., Thursd., and Sat., 10-3; entrance at the back, Via di Parione 7; porter 1/2 fr.; catalogues for the use of visitors, but not always trustworthy).

ANTE-ROOM: Two chiaroscuro by *Andrea del Sarto*. — I. ROOM: 5. *Gessi*, Vision of St. Andrew; portraits by *Sustermans* (the finest Nos. 21

and 24), *Van Dyck*, and *Tintoretto* (35). In a straight direction is the — II. Room: Battle-pieces by *Borgognone* (4, 11) and *Salvator Rosa* (6, 8, 31, 33, 39, 41), and sea-pieces by the same master (12, 20). The marble vase, with *Lycurgus* suppressing the *Bacchanalian* thiasus, appears to be spurious. Bronze vase. — III. (LARGE) ROOM: *Madonna and Child*, with *SS. Anna, Joseph*, and the young *Baptist*, and angels' heads above, with the date 1516, from the *Pal. Rinuccini*, attributed to *Raphael*, but probably a copy of the original at *Munich*; 13. *Dolci*, *Madonna* (in crayons); 19, 21. Portraits by *Seybold*; 23. *Giulio Romano*, Copy of the violinist from the *Pal. Sciarra*; 16. *Caravaggio*, Portrait; 39. *Madonna and Child*, after a lost fresco, by *A. del Sarto*; 40. Copy of *Titian's Madonna* in the *Belvedere* at *Vienna*. On the side next the *Arno* — IV. ROOM: A number of *Carlo Dolci's* (7. *Peace*; 40. *Poetry*); 38. Copy of *G. Romano's Madonna and Child* at *Dresden*; 37. *Filippino Lippi* (?), *Madonna and Child*; 28. *S. Botticelli*, *Madonna* with *Christ* and angels; 18. *Luca Signorelli*, *Madonna and saints*; 21. *Fra Bartolommeo and Mariotto Albertinelli*, *Madonna adoring the Child*; 9. *Raphael* (?), Cartoon for the portrait of *Julius II.* in the *Palazzo Pitti*. We now pass through the 5th Room and enter the — VI. ROOM: *S. Sebastiano del Piombo* (?), *Bearing of the Cross*; 22. *Ligozzi*, *Flute player*; 23. *Guido Reni*, *Lucretia*; 25. *Caravaggio*, *Study of a head*; 26. *A. Pollajuolo*, Portrait; 5. Portrait in the style of *Roger v. d. Weyden*. — Turning to the left, we next enter the — VII. ROOM, containing copies from *Salvator Rosa*. — We then pass through two dark rooms into the — X. ROOM, with pictures from *Ariosto's Orlando Furioso* by *Guido Reni*. In the centre, an altar-piece of the 14th cent. — XI. ROOM: 19. View of the *Piazza della Signoria* of 1498, with the burning of *Savonarola*. In the centre a good *Netherlandish* copy of *Michael Angelo's Holy Family* in the *Tribuna* (p. 338), somewhat altered, and with the addition of a landscape. — We return to the hall and to the right enter the — XII. ROOM: 2. *Raffaellino del Garbo* (?), *Holy Family*; 9. *Albertinelli*, *Holy Family*; 33. *School of Perugia*, *Madonna and Child*. — XIII. ROOM: Nothing of importance.

The *Ponte S. Trinità*, see p. 373; the left bank of the *Arno*, see p. 373.

By the *Ponte S. Trinità* is the *Palazzo Fontebuoni* (*Lung' Arno*, No. 2; Pl. 67), formerly *Gianfigliuzzi*, where the dramatist *Alfieri* resided and died (9th Oct., 1803). — At the corner opposite rises the imposing **Palazzo Spini** (Pl. 64; C, 4; now town-hall), once the seat of this family, a structure groundlessly attributed to *Arnolfo del Cambio*.

Opposite is the church of **S. Trinità** (Pl. 35; C, 4), erected about 1250 by *Niccolò Pisano*, but altered by *Buontalenti* in 1570.

The INTERIOR consists of nave and aisles with transept, and is flanked with chapels at the sides and adjoining the high altar. To the right of the central door are altar enrichments by *Benedello da Rovezzano*; to the left, *Mary Magdalene*, a statue in wood by *Desiderio da Settignano*; the 4th Chapel on the right contains the *Annunciation* by the *Camaldulensian* monk *Don Lorenzo*. The "CAPPELLA DE' SASSETTI", the second on the right from the high altar, is adorned with frescoes from the life of *St. Francis* by *Dom. Ghirlandajo*, dating from 1485, and presents a model of consistent ornamentation. The frescoes are in double rows. We begin with the upper row, to the left: 1. *St. Francis* banished from his father's house; 2. *Pope Honorius* confirms the rules of the order; 3. *St. Francis* in presence of the *Sultan*. On the right: 1. *St. Francis* receiving the stigmata; 2. *Resuscitation* of a child of the *Spini* family; 3. *Interment* of the saint. It is interesting to compare the last of these scenes with *Giotto's* rendering of the same subject in *S. Croce* (p. 356). The sibyls on the ceiling are also by *Ghirlandajo*. — Left Aisle: 3rd Chapel, early *Christian sarcophagus*. — In the *Sacristy* is a monument of 1417, in the style of *Donatello*.



In front of the church lies the **PIAZZA S. TRINITÀ**, adorned with a column of granite from the Baths of Caracalla at Rome, erected here in 1563, and furnished with an inscription in honour of the grand-duke Cosmo I. in 1569. On the summit is placed a statue of Justice in porphyry, by *Francesco Ferrucci*, added in 1581. The grand-duke, thinking the figure too slender, caused it to be draped with a robe of bronze. — To the right is the *Hôtel du Nord* (Pl. e), formerly the *Palazzo Bartolini-Salimbeni*, erected by Baccio d'Agnolo in 1520.

Farther on in the busy **VIA TORNABUONI** (Pl. C, 4), with its handsome palaces and tempting shops, is situated the \***Palazzo Strozzi** (Pl. 84), erected in 1489 by *Benedetto da Majano* for the celebrated Filippo Strozzi, and presenting an example of the Florentine palatial style in its most perfect development. It possesses three imposing façades (that towards the *Via Tornabuoni* is 42 yds in width, and 105 ft. in height), constructed in huge 'bossages', and a handsome court added by *Cronaca*. Celebrated cornice by *Cronaca*. The corner lanterns (by *Caparra*), the link-holders, and the rings are among the finest specimens of Italian ironwork of the 15th cent. The upper floor of the edifice contains a *Picture Gallery* of some value (open in winter only, on Wed., 11-4, closed on festivals).

I. ROOM: *Fra Filippo Lippi*, Annunciation. — II. ROOM: Portrait of a Child, *La Puttina di Tiziano*, by *Titian*; portrait of a lady by *Pollajuolo*; portrait of a man by *Botticelli*; large family picture by *Sustermans*; Christ on the Mt. of Olives, *Pinturicchio* (?). — III. LARGE ROOM: Five portraits, that of Filippo Strozzi in the middle by *Bronzino*; Madonna adoring the Child, a round picture by *Lorenzo di Credi* (?); opposite, the same subject by *Andrea del Sarto* (?). — IV. ROOM: Paul III. by *Paolo Veronese*; good portraits; two landscapes by *Salvator Rosa*; Players by *Caravaggio*.

No. 20, in the same street on the right, is the *Palazzo Corsi* (Pl. 78), formerly *Tornabuoni*, originally by Michelozzo, but remodelled in 1840 when the street was widened. — No. 19, on the left, is the *Palazzo Larderel* by *Giov. Ant. Dosio*, a pupil of Baccio d'Agnolo.

In the vicinity, *Via Vigna Nuova* 20, is the **Palazzo Rucellai** (Pl. 80a), erected about 1460 by *Leon Battista Alberti*, who for the first time here employed a combination of rustica and pilasters. The three-arched loggia opposite is also by him. — In the *Via della Spada* is the *Oratorio de' Rucellai* or *S. Pancrazio* (keys at the shoemaker's opposite), which contains an imitation of the Holy sepulchre by *Leon Batt. Alberti*, 1467.

The **VIA FAENZA** (Pl. D; 3, 2), leads from the centre of the city to the fortress of *S. Giovanni Battista*, erected by Cosmo I. in 1534. The suppressed monastery of *S. Onofrio* in this street (No. 57) contains the **Egyptian and Etruscan Museum** (*Museo Egizio ed Etrusco*; Pl. 54; 1, 2), the former having been collected by *Rossellini* in 1828 and 1829, and the latter embracing numerous Etruscan antiquities which had been scattered through-

out different collections down to 1870 (open daily 9-3; admission 1 fr., Sundays gratis).

**Etruscan Collection.** I. ROOM: Black vases from Chiusi, with and without reliefs; on the left, Etruscan tomb from Volsinii with cinerary urns, mural paintings (mythological, e.g. Pluto and Proserpine, and scenes from life), and numerous inscriptions (the custodian lights visitors). — II. ROOM: In the centre the celebrated *François Vase* (named after its finder), unrivalled in size and in the number of subjects with which it is decorated (Calydonian hunt, Return of Theseus from Crete, Battle of Centaurs and Lapithæ, Marriage of Peleus, Achilles and Troilus, etc.), bearing several ancient Greek names, including those of the artists *Klitias* and *Ergotimos*. To the right of the door, and opposite, are Greek vases in the early style (black figures): Judgment of Paris; opposite, Hercules and the Cercopes; then vases in the later style (red figures): Hercules in the Bacchanalian thiasus, Battle of Centaurs and Lapithæ, etc. — III. ROOM: Reliefs and small figures in terracotta, tomb-vases with head and arms (similar objects in the small cabinet to the left). — IV. ROTUNDA: Crystal and trinkets, coins, implements in Bronze and flint. — V. PASSAGE: Etruscan inscriptions. — VI. ROTUNDA: Bronzes, Athena found at Arezzo, Etruscan mirrors, statuettes. — VII. ROOM: In the centre, Chimæra, from Homer's description, with Etruscan inscription on the right leg in front, found at Arezzo. By the walls, Etruscan cinerary urns (bearing the names of the subjects represented, but not always quite correctly). — To the right is the — VIII. ROOM: Ancient armour and bronze vases found at Orvieto; two bronze handles, Perseus and Medusa, Peleus and Thetis; mirror, once the property of the Strozzi. By the window, under glass, a bronze vase with Bacchic reliefs, found near Bolsena. — Traversing the 7th Room in a straight direction, we next enter the — IX. ROOM: Life-size statue of a magistrate ('the orator'), with an Etruscan inscription on the edge of the toga, found by the Trasimene lake. In front of it, a painted Sarcophagus (heroic battles), with an Etruscan inscription. By the walls, cinerary urns similar to those in the 7th Room, and also in the following passage. — The **Egyptian Museum** is next entered. — Turning to the left in the passage we reach the old REFECTORY, containing a large fresco of the Last Supper, dating from 1505, rediscovered in 1845, a work of the school of Perugino, by *Pintoricchio* or *Gerini da Pistoja*, once attributed to Raphael. On the walls a number of representations of the Eucharist by different masters.

**LEFT BANK OF THE ARNO.** About one-fourth part of the city lies on this bank. We cross the **Ponte della Trinità** (Pl. C, 4; pp. 332, 371), adorned with allegorical statues of the four seasons, and proceed in a straight direction to the **VIA MAGGIO** (Pl. C, B, 5), No. 26 in which is the house of *Bimca Capello*, wife of Francis I., and well known for the romantic vicissitudes of her history, erected in 1566.

We next follow the second side-street to the right and reach the piazza and church of **\*S. Spirito** (Pl. 33; B, 5), an edifice in the form of a Latin cross, covered with a dome, and flanked with 38 chapels, designed by *Filippo Brunellesco* in 1446, but not begun until after his death (1470), and finally completed in 1481 after a great fire. The noble proportions of the interior which is borne by 31 Corinthian columns and 4 pillars, render it one of the most attractive structures in Florence. — The Campanile, erected by *Baccio d'Agnolo* (d. 1543), also deserves inspection.

**RIGHT AISLE.** 2nd Chapel: Pietà, a group in marble, after Michael

Angelo (original in S. Peter's at Rome), by *Nanni di Baccio Bigio*. 7th Chapel: Archangel Raphael with Tobias, group by *P. Baratta*. — RIGHT TRANSEPT. 3rd Chapel: Madonna by *Donatello* (covered). 5th Chapel: Madonna with SS. Nicholas and Catharine, by *Filippino Lippi* or his pupil *Raffaellino del Garbo*. 6th Chapel: Madonna appearing to St. Bernhard, an early copy from *Perugino* (original at Munich). — The CHOIR has a screen of marble and bronze; high altar with canopy and statues by *Caccini*, about 1600. At the back of the choir, in the 2nd chapel on the right, a Madonna and four saints on a gold ground, *School of Giotto*; in the following chapel a Madonna and saints by *Botticelli* or *Lorenzo di Credi*. — 5th Chapel: (1.) The adulteress before Christ by *Alessandro Allori*; 7th Chapel, (r.) Madonna enthroned and saints (1505) by *Raffaellino del Garbo* (according to Mr. Crowe). — LEFT AISLE: 1st chapel, Madonna with four saints, copy from *Rid. del Ghirlandajo* (original in Paris). — The SACRISTY, erected by *Giuliano da San Gallo* in 1488, contains a saint healing the sick, by *Allori*. Farther on, St. Anna, Madonna, and saints, by *Ridolfo* or *Domenico Ghirlandajo*. — LEFT TRANSEPT. 2nd chapel from the entrance, statue of Christ, a copy from Michael Angelo (in S. Maria sopra Minerva at Rome), by *Taddeo Landini*.

The FIRST CLOISTERS, erected by *Alfonso Parigi* (entrance by the sacristy, see above), are adorned with frescoes by *Perugino*, *Ulivelli*, *Baldi*, and *Cascetti*, representing saints of the Augustinian order. — The SECOND CLOISTERS are by *Ammanati* (1564), the paintings by *Poccetti*. — The monastery is now a barrack.

In the Piazza S. Spirito (No. 11) rises the handsome *Palazzo Dufour-Berte*, formerly *Guadagni* (Pl. 74), erected by *Cronaca*. — Leaving the piazza by the opposite Via S. Agostino, and then following the Via S. Monaca, we reach the piazza and the former Carmelite church **del Carmine** (Pl. 22; E, 4), consecrated in 1422, burned down in 1771, and re-erected within the following ten years. Among the parts which escaped destruction is the *Brancacci Chapel* in the right transept, embellished in 1423-28 by *Masaccio*, and after him by *Filippino Lippi* with very interesting \*Frescoes from the traditions regarding the Apostles, especially St. Peter (recently restored; best light about 4 p.m.).

Those by *Masaccio* are: on the pillars of the ENTRANCE, above, on the right the Fall, on the left the \*Expulsion from Paradise. LEFT WALL: above, \*Peter taking the piece of money from the fish's mouth; below Raising of Eutychus, and Peter enthroned (the latter finished by Lippi). WALL OF THE ALTAR: above, Peter preaching, and baptising; below, Peter healing the sick, and distributing alms. RIGHT WALL: above, Healing the cripples, and Raising of Tabitha. The following are by *Filippino Lippi*: on the right wall, below, the Crucifixion of Peter, and Peter and Paul before the proconsul; on the entrance pillars, below, on the left Peter in prison, on the right his release (comp. Introduction, p. 1).

The CHOIR of the church contains the tomb of Pietro Soderini, by *Benedetto da Rovezzano*, 1513, restored in 1780. — The CORSINI CHAPEL, to the left in the transept, contains the tomb of St. Andrea Corsini, Bishop of Fiesole, and three large reliefs in marble by *Foggini*, in celebration of the praises of the saint; painting in the dome by *Luca Giordano*. In the sacristy (entered from the right transept) frescoes from the history of St. Urban (discovered in 1858), by *Spinello Aretino*.

The CLOISTERS of the monastery (entrance to the right, adjoining the church, or from the sacristy) contain a \*Madonna with the Child and the four Evangelists, attributed by Mr. Crowe to *Giovanni da Milano*, and remains of early frescoes by *Masaccio*.

The adjacent building, formerly a Carmelite monastery, is now a barrack. — Beyond this the Via del Orto (Pl. A, 4) leads to the Porta S. Frediano (see p. 296).

The **Ponte Vecchio** (Pl. C, 5; p. 332), over which the covered passage mentioned at p. 341 is carried, forms the most direct communication between the Piazza della Signoria and the Uffizi, and the Palazzo Pitti. The bridge is flanked with shops, which have belonged to the goldsmiths since 1593. — It terminates in the VIA GUICCIARDINI (Pl. C, 5), at the end of which, to the left (No. 17), is situated the *Palazzo Guicciardini* (Pl. 72), where the historian Francesco Guicciardini lived from 1482 to 1541; opposite to it, on the right (No. 16), is the house of *Macchiavelli* (Pl. 48).

The **\*Palazzo Pitti** (Pl. 80; B, C, 5), conspicuously situated on an eminence, was designed and begun by *Brunellesco* in 1440, by order of Luca Pitti, the powerful opponent of the Medici, but owing to the decline of his prosperity (after 1466) remained uncompleted. The palace, which somewhat resembles a castle or a prison, is remarkable for its bold simplicity, and the unadorned blocks of stone are hewn smooth at the joints only. The central part, 117 yds. long, 121 ft. high, has a third story. The effectiveness of the building is entirely produced by its fine proportions (comp. p. xlv). In 1550 the palace was sold by a grandson of Luca Pitti to Leonora, wife of the grand-duke Cosmo I. About the year 1568 *Bartolommeo Ammanati* introduced round-arched windows on the ground floor, where the two portals, and the small rectangular windows, at a considerable height from the ground, were originally the only openings. At the same time he began to construct the large court, which is adjoined by a grotto with niches and fountains, and the Boboli Garden beyond them. The wings of the palace were completed in 1620-31. — Since the 16th cent. the Pitti Palace has been the residence of the reigning sovereign, and is now that of Victor Emmanuel when at Florence. The upper floor of the left wing contains the far-famed **\*\*Picture Gallery**, which was formerly the property of Cardinal Leopold and Carlo de' Medici, and of the Grand-duke Ferdinand II.

The Pitti Gallery, which contains about 500 works, may be regarded as an extension of the Tribuna (p. 338) in the Uffizi gallery. No collection in Italy can boast of such an array of master-pieces, interspersed with so few works of subordinate merit. The most conspicuous work of the earlier Florentine period is the round Madonna by *Filippo Lippi* (No. 338). The Adoration of the Magi, by *Dom. Ghirlandajo* (358), is a replica of the picture No. 1295 in the Uffizi. *Filippino Lippi's* Holy Family (347) is of somewhat doubtful authenticity. *Perugino's* Pietà (164), in which the treatment of the landscape deserves notice, is one of his principal works. To *Fra Bartolommeo's* later period belong the Resurrection (159), the Holy Family (256), St. Mark (125), and the Pietà (64), the master's last work, a model of composition, ennobled by depth of sentiment and purity of forms, and certainly one of the most beautiful products of Italian art. *Andrea del Sarto* is admirably represented by an Annunciation (124); by the so-called Disputa (172), a picture without action, but of an imposing and dignified character; John the Baptist (265); a Pietà (58), more dramatically treated than is the master's wont; and the Madonna in clouds with saints (307), all of which show his different excellences, and particularly the soft blending of his colours. — The treasures of the gallery culminate in no fewer than a dozen of RAPHAËL's works. The

exquisite 'Madonna del Granduca' (266), in which a pure type of simple female beauty is but slightly veiled by the religious character of the work, and the 'Madonna della Sedia' (79), a most beautiful work of purely human character, in which intense maternal happiness is expressed by the attitude of the group, both captivate every beholder. The 'Madonna del Baldacchino' (165), on the other hand, painted at different times and certainly not entirely by Raphael's own hand, and the 'Madonna dell' Impannata' (No. 94, being an extension of an originally simpler composition) are of inferior interest. The finest of the portraits is that of Leo X. with the two cardinals (63), in which the delicate and harmonious blending of the four shades of red should be noticed. Whether the portrait of Julius II. (151) exhibited here, or that in the Tribuna is the original, has long been a matter of controversy, but if the two pictures were placed in juxtaposition, the question might perhaps be settled. The portraits of the 'Velata' (245) and the 'Gravida' (229), are now generally admitted to be genuine works of Raphael. The portraits of Angiolo and Maddalena Doni (61, 69), of the master's Florentine period, are of unquestioned authenticity; but those of Inghirami (171) and of Cardinal Bibbiena (158) are not free from doubt. The Vision of Ezekiel (174), which transports us into an entirely different sphere, is a mediæval symbolical subject, treated by Raphael in his own manner. — The Goldsmith (207), once attributed to Leonardo, has long since been allotted to *Lorenzo di Credi*. The Three Fates (113) can hardly claim, even in its composition, to be a work of Michael Angelo. — The Venetian School also occupies an important place in the Pitti Gallery. Thus *Giorgione's* Concert (185), and *Lor. Lotto's* Three ages (157), a work hardly inferior in conception to that of *Giorgione*. Then *Sebastian del Piombò's* St. Agatha (179); *Titian's* portraits of Ippolito de' Medici (201), Philip II. (200), and Aretino (54), his *Bella* (18), and his *Mary Magdalene* (67); *Pordenone's* Holy Conversation (52); *Bonifacio's* Repose in Egypt (89; erroneously attributed to Paris Bordone), and his *Sihyl* (257); *Tintoretto's* Portrait (65), and his *Vulcan with Venus and Cupid* (3). An excellent work of a later period is *Cristofano Allori's* Judith (96). — Among the non-Italian pictures we must mention two landscapes (9, 14), four portraits (85), and the Allegory of War (86) by *Rubens*, and Cardinal Bentivoglio (82), and the Repose in Egypt by *Van Dyck*, two portraits (1660) by *Rembrandt*, and lastly the equestrian portrait of Philip IV. (243), by *Velasquez*.

The ENTRANCE is in the E. angle of the Piazza Pitti, in the colonnade adjoining the entrance to the Boboli garden. (Or we may approach the gallery by the connecting passage from the Uffizi, in which case sticks and umbrellas must be left at the entrance to that building, see p. 341.) The gallery is open on Sundays, and in summer on Thursdays also, 11-3, gratis, and on other days, 9-3, admission 1 fr.; catalogue 3½ fr.

An insignificant staircase (passing on the 1st floor the ingress from the Uffizi; see above) leads to a corridor containing a beautiful vase of porphyry, a copy of that preserved in the museum at Berlin, and a large porcelain vase from Sèvres. This corridor leads to the gallery, which extends through a suite of splendid saloons, adorned with allegorical ceiling-paintings whence their names are derived. They are sumptuously fitted up with marble and mosaic tables and velvet-covered seats, and heated in winter. Each saloon is provided with a list of the pictures it contains. Permission to copy is readily granted, on written application being made to the director.

The six principal saloons are first visited; the entrance was formerly at the opposite extremity, so that the numbers of the pictures, as enumerated below, are now in the reverse order.

## SALOON OF THE ILIAD,

so named from the subject of the frescoes by *Luigi Sabatelli*. It contains four tables of lapis lazuli, granite, and jasper, and four vases of nero antico; in the centre a *Caritas* in marble by *Bartolini*.

To the right of the entrance door: 235. *Rubens*, Holy Family (copy?); above the door, 230. *Parmeggianino*, Madonna with angels (Madonna del collo lungo); \*229. Portrait of a lady, attributed to *Raphael* (known as 'La gravida'; comp. No. 59 in the Apollo saloon); \*228. *Titian*, Head of the Saviour; 227. *Carlo Dolci*, St. Margaret; \*225. *A. del Sarto*, Assumption; 224. *Rid. Ghirlandajo*, Portrait; 223. *Holbein junr.* (?), Portrait; 222. *Giorgione* (?), Portrait of a lady; \*219. *Pietro Perugino*, Mary and John adoring the Child; 218. *Salvator Rosa*, A warrior; 216. *Paolo Veronese*, Daniel Barbaro; 214. *F. Baroccio*, Copy of the Madonna del S. Girolamo, of Correggio; 213. *Carlo Dolci*, Moses; 212. *Bronzino*, Cosmo I.; \*208. *Fra Bartolommeo*, Madonna del Trono; 207. *Leonardo da Vinci* (? or probably by *Lorenzo di Credi*), Portrait of a goldsmith; 206. *Bronzino*, Francesco I. de' Medici; \*201. *Titian*, Ippolito de' Medici; 200. *Titian*, Philip II. of Spain; 198. *Velasquez*, Portrait; 197. *Guido Reni*, Caritas; 196. *Paolo Veronese*, St. Benedict and other saints; 195. *Giacomo Francia*, Portrait; 191. *A. del Sarto*, Assumption of the Virgin (unfinished); 190. *Sustermans*, Portrait of the son of Frederick III. of Denmark; 188. *Salvator Rosa*, Portrait of himself; 186. *Paolo Veronese*, Baptism of Christ; \*\*185. *Giorgione*, 'The Concert.' representing an Augustinian monk who has struck a chord, another monk with a lute, and a youth in a hat and plume listening; 184. *Andrea del Sarto* (?), Portrait of himself.

## SALOON OF SATURN,

Ceiling-painting by *Pietro da Cortona*. To the right of the entrance-door: 182. *Pontorno*, Martyrdom of 40 Saints; 181. *Salvator Rosa*, Portrait of a poet; above the door, 179. *Sebastiano del Piombo*, Martyrdom of St. Agatha, 1520; 178. *Guido Reni*, Cleopatra; 177. *Leonardo Bassano*, Rustic scenes; 176. *Domenichino*, Mary Magdalene; 175. *Albano*, Holy Family; \*174. *Raphael*, Vision of Ezekiel; \*172. *A. del Sarto*, Conference of the Fathers of the Church regarding the doctrine of the Trinity, one of his best oil-paintings; \*171. *Raphael*, Tommaso Fedra Inghirami (a replica in Volterra); 168. *Guercino*, St. Peter; 166. *Ann. Caracci*, Study of a head; 167. *Giulio Romano*, Dance of Apollo and the Muses; \*\*165. *Raphael*, Madonna del Baldacchino (completed by a different hand after 1514, by which the bishop on the right and the angels were probably added, and finally provided with the canopy by *Cassano* about 1700); 164. *Pietro Perugino*, Entombment, 1495; 163. *A. del Sarto*, Annunciation (retouched); 161. *Bonifazio* (according to Mr. Crowe; formerly attributed to *Giorgione*), Finding of Moses; \*160. *Van Dyck*, Virgin; 159. *Fra Bartolommeo*, Risen Christ among the four Evangelists, 1516; \*158. *Raphael*, Cardinal Bibbiena (perhaps a copy of the original at Madrid); \*157. *Lorenzo Lotto*, Three periods of life; 156. *Guercino*, Madonna with the swallow; 154. *Carlo Dolci*, John the Baptist asleep; 152. *Schiavone*, Cain slaying his brother; \*151. *Raphael*, Pope Julius II.; \*150. *Van Dyck*, Charles I. of England and his queen Henrietta of France; 149. *Pontorno*, Portrait of Ippolito de' Medici; 148. *Dosso...Dossi*, Bamboccia; 147. *Giorgione* (?), Nymph pursued by a satyr.

## SALOON OF JUPITER.

Ceiling-painting by *Pietro da Cortona*.

To the right of the entrance: \*140. *L. da Vinci* (? *Raffaellino del Garbo*), Portrait of a lady; \*139. *Rubens*, Holy Family; over the door, 137. *Giov. da S. Giovanni*, Sportsmen returning home; 136. *Paolo Veronese*, The Saviour parting from his mother; 135. *Salvator Rosa*, Battle; 134. *Paolo Veronese*, The women at the Sepulchre; \*133. *Salvator Rosa*, Battle (the figure on the left, above the shield, with the word Sarò, is the painter's portrait); 132. *Crespi*, Holy Family; 131. *Tintoretto*, Vincenzo Zenò; 130. *Bassano*, Portrait of a woman; 129. *Mazzolini*, The adulteress; 128, 127. *Morone*, Portraits; 125. *Fra Bartolommeo*, St. Mark;

124. *Andrea del Sarto*, Annunciation; \*123. *A. del Sarto*, Madonna in glory with four saints; 122. *Garofalo*, Sibyl divulging to Augustus the mystery of the Incarnation; 119. *Sustermans*, Portrait; \*118. *A. del Sarto*, Portraits of himself and his wife (?); 113. The three Fates, groundlessly ascribed to *Michael Angelo*; 112. *Borgognone*, Battle-piece; 111. *Salvator Rosa*, Conspiracy of Catiline; 110. *Titian* (?), Bacchanalian; 109. *Paris Bordone*, Female portrait; 108. *Paolo Veronese*, Portrait. 4th wall: 141. *Rubens*, Nymphs attacked by Satyrs.

## SALOON OF MARS.

Ceiling-painting by *Pietro da Cortona*.

To the right of the entrance: 103. *Guercino*, Moses; 102. *Luini*, Magdalene; over the door, 97. *And. del Sarto*, Annunciation (retouched); \*96. *C. Allori*, Judith; 95. *Allori*, Abraham's Sacrifice; 94. *Raphael*, Holy Family, called Madonna dell' Impannata (not entirely finished by Raphael, or perhaps only from a drawing by him; the St. John is a later addition); 93. *Rubens* (?), St. Francis; 92. *Titian*, Portrait; 91. *Carlo Dolci*, Peter weeping; 90. *Cigoli*, Ecce Homo; \*89. *Paris Bordone* (?), Repose during the Flight to Egypt; 87, 88. *A. del Sarto*, History of Joseph; \*86. *Rubens*, Mars going forth to war; \*85. *Rubens*, Rubens with his brother and (r.) the scholars Lipsius and Grotius; 84. *Palma Vecchio* (?), Holy Family; \*83. *Titian* (? *Tintoretto*), Luigi Cornaro; 82. *Van Dyck*, Cardinal Giulio Bentivoglio; \*81. *A. del Sarto*, Holy Family; 80. *Titian*, Andreas Vesalius (the physician); \*79. *Raphael*, Madonna della Sedia; 78. *Guido Reni*, Peter weeping; 76. *Van der Werff*, Duke of Marlborough. On the 4th wall, 106. Portrait of Galileo, school of *Sustermans*; 104. *Luca Giordano*, Conception.

## SALOON OF APOLLO.

Ceiling-paintings by *Pietro da Cortona* and *Ciro Ferri*.

To the right of the entrance: \*67. *Titian*, Magdalene; 66. *Andrea del Sarto*, Portrait of himself (replica of No. 1176 in the Uffizi); 65. *Tintoretto*, Portrait; 64. *Fra Bartolommeo*, Pietà (said to have been finished by *Bugiardini*); \*63. *Raphael*, Leo X. and the cardinals de' Medici and de' Rossi; 62. *A. del Sarto*, Madonna; \*61. *Raphael*, Angiolo Doni, a friend of the master (Nos. 59 and 61 belonged to the family down to 1758, when they were transferred to Avignon, where they were purchased for the Gallery in 1826 for the sum of 25,000 fr.); \*60. *Rembrandt*, Portrait of himself; \*59. *Raphael*, Portrait of Maddalena Strozzi Doni; \*58. *A. del Sarto*, Descent from the Cross; 57. *Giulio Romano*, Copy of Raphael's Madonna della Lucertola; 56. *Murillo*, Holy Family; \*54. *Titian*, Pietro Aretino; 52. *Pordenone* (?), Holy Family; 51. *Cigoli*, Descent from the Cross; 50. *Guercino*, Peter raising Tabitha; 49. *Tiberio Titi*, Leopoldo de' Medici when a child, 1617; 47. *Guido Reni*, Bacchus; 44. *Giac. Francia*, Portrait; \*42. *P. Perugino*, Mary Magdalene; 41. *Cristofano Allori*, Hospitality of St. Julian; \*40. *Murillo*, Madonna; 39. *Angelo Bronzino*, Holy Family; \*38. *Palma Vecchio* (?), Christ at Emmaus; 37. *Paolo Veronese*, Portrait of his wife; 36. *Girolamo da Carpi*, Archbishop Bartolini Salimbeni; 35. Bishop Girolamo Argentino, school of *Morone*. 4th wall: 71. *Carlo Maratta*, S. Filippo Neri.

## SALOON OF VENUS.

Ceiling-painting by *Pietro da Cortona*.

To the right of the entrance: 24. *Guido Reni*, Portrait of an old man; 21. *Pietro da Cortona*, Saint entranced; \*20. *A. Dürer*, Adam, probably painted at the same time as Eve (No. 1. see below) in 1507, after the master's second stay at Venice; 19. *Ribera*, Martyrdom of St. Bartholomew; to the left of the door, \*18. *Titian* Portrait (La Bella di Tiziano), same head as the Venus in the Tribuna (No. 1117); \*17. *Titian* (? the original is in London, and this is perhaps a copy by *Bonifazio*), Betrothal of St. Catharine; 16. *Rembrandt*, Old man; 15. *Salvator Rosa*, Sea-piece; \*14. *Rubens*, Landscape, with peasants returning from harvest; \*9. *Rubens*, Landscape, Ulysses on the island of the Phæaci; 8. *Guercino*, Apollo and Marsyas; 6. *Bartolommeo Manfredi*, Gipsy; 5. *Garofalo*, St. James; 4.

*Salvator Rosa*, Harbour at sunrise, 3. *Tintoretto*, Cupid, Venus, and Vulcan; 2. *Salvator Rosa*, Falsehood with a mask; \*1. *A. Ditrer*, Eve, counterpart of No. 20.

We return hence to the Saloon of the Iliad, and thence enter the —

#### SALOON OF THE EDUCATION OF JUPITER.

Ceiling-painting by *Catani*.

241. *Clovio*, Descent from the Cross (in water-colours); \*243. *Velasquez*, Philip IV. of Spain; 244. *Fr. Pourbus*, Portrait; \*245. Portrait of a lady, master unknown, probably by *Raphael*; 246. *Garofalo*, Gipsy; \*248. *Tintoretto*, Descent from the Cross; 252. *Claude de Lorraine*, Duc de Guise, probably by an imitator of *Holbein*; 254. *Palma Vecchio* (?), Holy Family; 255. *Van der Helst*, Portrait; \*256. *Fra Bartolommeo*, Holy Family; 257. *Paris Bordone* (?), Sibyl prophecying to Augustus; 259. *Correggio*, Christ (a copy); 262. *Clouet*, Henry II. of France; 264. *Tintoretto*, Resurrection; \*265. *And. del Sarto*, John the Baptist; \*\*266. *Raphael*, 'Madonna del Granduca'; 267, 268. *Paolo Veronese*, Portraits of children; 269. *Paolo Veronese*, Presentation in the Temple; 270. *Carlo Dolci*, Martyrdom of St. Andrew; 277. *Bronzino*, Lucrezia de' Medici; 279. *Bronzino*, Don Garzia de' Medici. — We now turn to the left into the —

#### SALA DELLA STUFA.

The frescoes illustrating the golden, silver, brazen, and iron ages are by *Pietro da Cortona*; ceiling-paintings by *Matteo Rosselli*, 1622. This room contains four small antique statues in marble, and a column of green porphyry, bearing a small porcelain vase with a portrait of Napoleon I., and two statues in bronze (Cain and Abel), copied by *Papi* in 1849 from a marble statue executed by *Dupré* for the Duke of Leuchtenberg.

Returning hence and traversing a passage, we observe on the left a small Bath-room, most tastefully fitted up, with pavement of modern Florentine mosaic, and four small statues of Venus by *Giovanni Insou* and *Salvatore Bongiovanni*.

#### SALOON OF ULYSSES.

Ceiling-painting by *Gaspero Martellini*, representing the return of Odysseus, an allusion to the restoration of the grand-duke Ferdinand III. after the revolution. Handsome cabinet (stipo) of ebony, inlaid with coloured wood and ivory; in the centre a large porcelain vase. — 288. *Carlo Dolci*, Jesus on the Mount of Olives; 289. *Ligozzi*, Madonna appearing to St. Francis; 297. *Paris Bordone*, Pope Paul III.; 304. *Schidone*, Holy Family; 305. *C. Allori*, St. John in the wilderness; 306. *Salvator Rosa*, Landscape; 307. *A. del Sarto*, Madonna and saints; 311. *Titian*, Duke Alphonso I. of Ferrara; 312. *Salvator Rosa*, Landscape on the coast; 313. *Tintoretto*, Madonna; 316. *Carlo Dolci*, Portrait; \*320. *A. Caracci*, Small landscape; 324. *Rubens* (copy?), Duke of Buckingham; 325. *Carlo Dolci*, Madonna and the Infant Jesus, two miniatures; 332. *Gennari*, Madonna and Child.

#### SALOON OF PROMETHEUS,

with paintings by *Giuseppe Colignon*. In the centre a magnificent round table of modern mosaic, executed for the London Exhibition of 1851, but not sent thither, valued at 30,000*l*.

334. *German School*, Portrait; 336. Allegory, by a Venetian; 337. *Scipio Gaetano*, Ferdinand I. de' Medici; \*338. *Fra Filippo Lippi*, Madonna with saints; in the background SS. Joachim and Anna, and the Nativity of Mary; 339. *Tintoretto*, Portrait of a doge; 340. Madonna with two saints after *Perugino* (the original is in Vienna); 341. *School of Pinturicchio*, Adoration of the Magi; 345. *Baldassare Peruzzi*, Holy Family; 346. *F. Zuccheri*, Mary Magdalene, on marble; \*347. *Filippino Lippi*, Holy Family; 348. *Botticelli*, Holy Family; 353. *Botticelli*, Portrait of the 'Beautiful Simonetta', the mistress of Giuliano de' Medici, who died at an early age, and whose praises were sung by the poets Pulci and Poliziano; 354. *L. di Credi*, Holy Family; 355. *Luca Signorelli*, Holy Family; 357. *S. Botticelli*, Holy Family; 358. *Dom. Ghirlandajo*, Adoration of the Magi



(replica of the picture in the Uffizi, No. 1295); 362. *Jacopo Boatteri*, Holy Family; 363. *Garofato*, Holy Family; 365. *Albertinelli*, Holy Family; 369. *Ant. Pollajuolo*, Ecce Homo; 370. Saint looking upwards, perhaps by *Signorelli* (?); 371. *Piero della Francesca* (or, according to Mr. Crowe, *Franc. Buonsignori*); 372. *Andrea del Castagno*, Portrait of a man; 373. *Fra Angelico da Fiesole*, Madonna with saints, a winged picture over the door; 376. *Lorenzo Costa*, Portrait; 377. *Fra Bartolommeo*, Ecce Homo; 379. *J. da Pontormo*, Adoration of the Magi; 384. *A. Pollajuolo*, St. Sebastian; 388. *Filippino Lippi*, Death of Lucretia. — We next proceed to the —

## GALLERIA POCETTI,

which derives its name from the ceiling-paintings by *Bernardino Poccetti*. Two tables of oriental alabaster and one of malachite. Bust of Napoleon I., by *Canova*. — 483. *Polidoro Veneziano*, Adoration of the Child; 484. *Marco Vecellio* (nephew of Titian), Madonna della Misericordia; 490. *Guercino*, St. Sebastian; 494, 495. *Titian*, Portraits. Also a number of miniature portraits, as well as in the following corridor.

Returning to the Prometheus Saloon, we next enter a CORRIDOR, on the walls of which are six marble mosaics, a number of miniature portraits, and valuable drinking cups, objects in ivory, etc.

## SALOON OF JUSTICE.

Ceiling-painting by *Fedi*. In the centre a handsome cabinet, purchased in Germany by Ferdinand II. — 389. *Tintoretto*, A sculptor; 398. *Artemisia Gentileschi*, Judith; 399. *Salviati*, Patience, said to be copied from a composition by Michael Angelo; 400. *M. Hondeloeter*, Poultry; 401. *Sustermans*, The canon Pandolfo Ricasoli; 403. *Bronzino*, Grand-duke Cosmo I.; 404. *Carlo Dolci*, Vittoria della Rovere; 406. *Bonifazio Bembo*, Christ in the Temple; 406. *Carlo Dolci*, St. Dominic praying; 408. *Peter Lely*, Oliver Cromwell (a genuine portrait, sent by the Protector to the grand-duke Ferdinand II.); 409. *Sebastian del Piombo*, Bust of a bearded man.

## SALOON OF FLORA.

Ceiling-paintings by *Marini*. In the centre *Venus* by *Canova*. 415. *Sustermans*, Grand-duke Ferdinand II. de' Medici; 416, 421. *Gaspard Poussin*, Landscapes; 423. *Titian* (?), Adoration of the Shepherds; 430. *Cigoli*, Madonna; 436. *Gaspard Poussin*, Landscape; 437. *Van Dyck*, Repose during the Flight into Egypt; 438. *Ruthard*, Stag attacked by tigers.

SALOON OF THE CHILDREN (*Sala de' Putti*).

Frescoes by *Marini*, decorations by *Rabbujati*. 451. *Rachel Ruysch*, Fruit; 453. *Salvator Rosa*, Landscape, with an allegorical figure of peace burning weapons; 455. *Rachel Ruysch*, Fruit and flowers; 465. *Ruysdael*, Landscape; 470. *Salvator Rosa*, Landscape, with Diogenes throwing away his drinking-cup (*La foresta dei filosoffi*); 474. *Domemichino*, Landscape, with Diana surprised by Acteon; 476. *Andrea del Sarto*, Holy Family; 478. *Van Douwen*, Masquerade; 480. *A. Caracci*, Nymph and satyr, a replica of the picture in the Tribuna, No. 1133.

The ground-floor of the palace contains several rooms with good *Modern Works of Art*, historical pictures by *Bezzuoli* and *Sabatelli*, statues by *Bartolini* (*Carità*), *Ricci* (*Innocence*), etc. (apply for admission to the porter at the entrance), and the *Treasury* (to the left in the second court, open 10-3, fee 1/2 fr.), containing the royal plate, and interesting specimens of ancient and modern goldsmiths' work. In the cases to the left are several works by *Benvenuto Cellini*. To the right a crucifix in bronze by *Giovanni da Bologna*, opposite to it a crucifixion by *Tacca*. Cruet-stand of lapis-lazuli, etc.

The **\*Boboli Garden** (entrance through the Palazzo Pitti, in the left corner; open to the public on Sundays and Thursdays from noon till dusk; comp. Pl. C, 5), at the back of the palace, extends in terraces up the hill. It was laid out by *Tribolo* in 1550, under Cosmo I., and extended by *Buontalenti*, and commands a succession of charming **\*Views of Florence** with its palaces and churches, among which the Palazzo Vecchio, the dome and campanile of the cathedral, and the tower of the Badia are most conspicuous. The long walks, bordered with evergreens, and the terraces, adorned with vases and statues, attract crowds of pleasure-seekers on Sundays.

On entering we first observe, in a straight direction, a Grotto with four statues, modelled by *Michael Angelo* for the monument of Pope Julius II.; in the centre the Rape of Helen, a group by *Vincenzo de' Rossi*. At the entrance to the grotto, Apollo and Ceres, statues by *Bandinelli*. — The MAIN PATH leads straight from the back of the palace to an open space called the *Amphitheatre*, formerly employed for festivities of the court; on the right, a handsome fountain, on the left, an Egyptian obelisk (brought hither from Rome) and an ancient basin of grey granite. We then ascend to the BASIS OF NEPTUNE, adorned with a statue of the god by *Stoldo Lorenzi*; then, higher up, the statue of ABBONDANZA, begun by *Giovanni da Bologna*, and finished by *Tacca*, and erected in 1636 to commemorate the fact that during the general distress occasioned by the war during the reign of Francis II., Tuscany alone revelled in plenty (fine view hence). To the right, in the vicinity, a small casino (30 c.), commanding a charming and uninterrupted **\*View**.

To the W. of the Abbondanza we reach an open grass-plot, also affording a fine view, whence the visitor about to leave the garden may descend direct. We follow a beautiful avenue to the S., adorned with numerous statues (copies of old works, as well as modern originals), and, passing the gardener's house, reach a charming BASIN (*la vasca dell' isolotta*), enlivened by swans and other water-fowl. In the centre, on an island planted with flowers, rises a fountain surmounted by a colossal statue of Oceanus, by *Giovanni da Bologna*. The surrounding walks are chiefly embellished with 'genre' works. A path leads from this basin in a straight direction to a grass-plot with two columns of granite, and thence to the Porta Romana, which however is usually closed; in the vicinity several ancient sarcophagi. To the right of the Oceanus basin a broad path, parallel with the palace, is reached, by which the principal entrance may be regained. Another exit, near a fountain with Bacchus on the lion, leads into the Via Romana. — To the left is the BOTANIC GARDEN, which, on public days, the custodian invites visitors to inspect (fee); a permesso for other days is obtained at the Museo di Storia Naturale.

Above the Boboli garden is the *Fortezza di Belvedere*, constructed in 1590 by *Buontalenti* by command of Ferdinand I. Near it is the closed Porta S. Giorgio.

At Via Romana 19, to the W. of the Pitti Palace, is the **Museum of the Natural Sciences** (*Museo di Fisica e di Storia Naturale*; Pl. 55; B, 5; open Tuesd., Thursd., Sat., 10-3; to strangers daily by permission of the secretary), founded by Leopold I., and greatly augmented at subsequent periods.

The public museum is on the SECOND FLOOR; the mineralogical, geological, and palæontological collections occupy 9, the zoological 13 rooms. There is also an admirable anatomical collection in 12 rooms, consisting chiefly of preparations in wax, by *Clemente Susini* and his successors *Catenzuoli* and *Calamai*.

On the FIRST FLOOR (r.) is situated the *TRIBUNA OF GALILEO*, inaugurated in 1840, on the occasion of the assembly at Florence of the principal scholars of Italy, constructed by *Giuseppe Martelli*, and adorned with paintings by *Giuseppe Bezzuoli*, *Luigi Sabatelli*, etc., illustrating the history of Galileo, Volta, and other naturalists; also a statue of Galileo by *Costoli*, numerous busts of celebrated men, and mosaics in the pavement, designed by *Sabatelli*, and executed by *Giov. Batt. Silvestri*. Along the walls are six cabinets containing instruments from the time of Galileo downwards. There is also an *Observatory* here.

No. 13 in the *Via della Costa* is the house of *Galileo* (Pl. 47; C, 5).

Immediately adjoining the *Ponte alle Grazie* (recently widened; Pl. D; 5, 6; p. 332) is the *Piazza de' Mozzi*, to the right in which rises the *Palazzo Torrigiani* (Pl. 85), containing a valuable picture-gallery on the first floor (generally shown on application to the porter; written catalogues for the use of visitors).

ANTE-CHAMBER: *Luca della Robbia*, Portrait of himself, a fine work in terracotta. — To the left: 1. Room: \*11. *Signorelli*, Portrait of a man in a red cap; *Filippino Lippi (Masaccio ?)*, Portrait; 20. *Pollajuolo (? Baldovinetti)*, Portrait; \*33. *Domenichino*, Landscape with bathers; 1. *Beccafumi*, Madonna; 6. *Lorenzo di Cradi*, Madonna. — To the right: CABINET: 5, 7. *Triumph of David*, by *Pesellino*; 22, 24. *Procession of Argonauts*, and *Starting for the hunt*, by *Paolo Uccelli* (these four being 'cassoni', or lids of chests). To the left of the 1st Room is the — 11. ROOM: \*7. *Madonna and Child*, a 16th cent. copy from *Raphael* (original in the *Bridgewater Gallery*); 3. *Venetian School*, Entombment; \*8, 11, 21, 22. and another picture between the windows, *Filippino Lippi*, *History of Esther*; 13, 23. *Pinturicchio*, Legend; 10. *Andrea del Sarto (?)*, *Holy Family*; 15. *Bronzino*, *Eleonora of Toledo*. — 111. ROOM: 9. *Tintoretto*, *Resurrection*. — On the other side of the ante-chamber (to the right of the entrance) are three rooms with unimportant contents. In the last (IV.) ROOM: 9. *Hobbema*, Landscape; 13. *Teniers*, *Players*; 14, 16. *Cranach (?)*, *St. John and the Infant Christ*. — The secretary also grants permission to visit the beautiful *Giardino Torrigiani*, *Via dei Serragli* (Pl. A, 5).

The small church of *S. Lucia* (Pl. 18) in the adjoining *Via de' Bardi* contains an *Annunciation* by *Fra Filippo Lippi* (1st Altar on the left).

In the LUNG' ARNO SERRISTORI, between the *Ponte alle Grazie* and the *Porta S. Niccolò*, rises the monument of Prince *Demidoff*, to whose philanthropy Florence was much indebted, erected by *Bartolini* in 1870.

Farther on is the church of *S. Niccolò* (Pl. 28; D, 6), founded about the year 1000. At the back of the high altar are four saints by *Gentile da Fabriano*. The sacristy contains a *Madonna della Cintola* by *A. Pollajuolo*, 1450 (lunette); below it a *Madonna* and saints by *Neri di Bicci*. In 1530, after the capitulation of the town to the Medici (p. 383), *Michael Angelo* lay concealed for a time in the tower of this church.

## 50. Environs of Florence.

*Compare Map.* The small numbers, which are marked on it round the town, designate the boundary of the local imposts (*Conti daziaria*): 1. *Barriera di Lung' Arno Nuovo*; 2. *B. delle Cascine*; 3. *B. Pistojese*; 4. *B. S. Donato*; 5. *B. del Mercato*; 6. *B. del Romito*; 7. *B. del Ponte Rosso*; 8. *B. delle Cure*; 9. *B. delle Forbici*; 10. *B. della Fonte all' Erba*;



**CONTORNI.**

1:55.000







Recoboli

Paradiso

Al Prano

Calluzzo

S. Cristoforo

Kilometres

1 2 3 4 5 6 7 8 9 10

1868



11. B. dell' Affrico; 12. B. Settignanese; 13. B. Aretina; 14. B. Ponte di Ferro di S. Niccolò; 15. B. Porta S. Niccolò; 16. B. Porta S. Miniato; 17. B. Porta S. Giorgio; 18. B. Porta Romana; 19. B. Porta S. Frediano.

The heights surrounding Florence afford many charming views of the city and neighbourhood, and some of the edifices erected on them also deserve notice. Those who make some stay at Florence will find ample scope for excursions in every direction. The afternoon is the most favourable time, as the city and environs are often veiled in haze in the forenoon.

(A.) One of the finest promenades in Italy, a hilly road recently constructed from plans by the engineer *Poggio*, called the **\*\*Viale dei Colli**, ascends the heights in windings from the Porta Romana (Pl. A, 6), the S. gate of Florence, leads along the slopes to S. Miniato, and descends in a long curve to the river, where it terminates at the upper Ponte di Ferro, near the Porta S. Niccolò (Pl. F, E, 6). This road, which is 19 yds. wide and nearly  $3\frac{3}{4}$  M. in length, is bordered with beautiful pleasure grounds, containing bays, elms, sycamores, and hedges of roses, over which delightful views are obtained. The road is called the *Viale Macchiavelli* from the Porta Romana to the large circular *Piazzale Galilei*, beyond which it bears the name of *Viale Galilei*. At the beginning of the latter is the *Tivoli* (adm. 1 fr.; restaurant; music in the evening), and farther on is the new *Restaurant Bonciani*. Below S. Miniato the road passes the large **\*Piazzale Michelangelo**, forming a kind of projecting terrace immediately above the Porta S. Niccolò (Pl. E, 6), to which footpaths and roads descend. In the centre of the Piazza rises a bronze copy of Michael Angelo's David (p. 364), the pedestal of which is surrounded by the four day-times (p. 367). Charming **\*\*VIEW** hence of the town and the valley of the Arno (seen to best advantage in the afternoon): to the right, on the hill, lies Fiesole; then the city with S. Croce, the Cathedral, S. Lorenzo, the Palazzo Vecchio, S. Maria Novella, and the Lung' Arno; to the left are the villa-covered heights, the Fortezza del Belvedere, Bello Sguardo, and the Villa Giramonte. — A drive by the Viale dei Colli, from one gate to the other, occupies 1-1½ hr. (carriages, see p. 325; comp. also p. 384).

(B.) **SAN MINIATO**, with its marble façade, on the hill to the S.E. of Florence, is a conspicuous object from many different points. It may be reached by carriage (p. 325) or on foot in less than ½ hr. The route from the Porta S. Niccolò by the Piazzale Michelangelo (see above) cannot be mistaken. A little beyond the gate we reach the Franciscan monastery of **S. Salvatore del Monte**, with a church erected by *Cronaca* in 1504, the simple and chaste proportions of which were deservedly praised by Michael Angelo, who called it 'la bella villanella'. — We now turn to the left towards the gateway of the old fortifications, constructed by Michael Angelo in 1529 as engineer to the republic, and which were defended by him during an eleven months' siege of the city by the



Imperial troops. Visitors knock at the gate, and on leaving give the gate-keeper a few soldi. The church and the whole hill of S. Miniato are now used as a burial-ground (fine views).

The church of \***S. Miniato al Monte**, like the Battistero (p. 346), is one of the few existing examples of the Pisan Florentine style which preceded the Gothic, and was founded by Bishop Hildebrand of Florence in 1013, on the site of an earlier church. It is an edifice of admirable proportions, with nave and aisles, without a transept, and is in many respects a truly classical edifice. The elegantly incrustated façade dates from the 12th, the mosaics with which it is adorned from the 13th cent. The tower was restored by *Baccio d'Agnolo* in 1519.

THE INTERIOR, recently restored, rests on 12 columns (some of them antique) of white, and 4 handsome pillars of greenish grey marble, and has an open roof, tastefully re-decorated in the original style. The choir with its simple apse is raised by a spacious crypt beneath.

AISLES. On the wall on the right, Enthroned Madonna and six saints by *Paolo degli Stefani* (14th cent.); on the left a Madonna with saints and a Crucifixion, of the beginning of the 15th century. In the NAVE, between the flights of steps (16) ascending to the choir, is a chapel constructed in 1446 by Piero de' Medici from a design by *Michelozzo*. Over the altar is the small crucifix which is said to have nodded approvingly to S. Giovanni Gualberto when he forgave the murderer of his brother (p. 391). In the LEFT AISLE is the Chapel of S. Giacomo, constructed by *Antonio Rossellino*, containing the monument of Cardinal Jacopo of Portugal (d. 1459); above the monument a \*Madonna and Child in a medallion held by two angels; on the ceiling the Four virtues by *Luca della Robbia*. — The CRYPT, to which a flight of seven steps descends, does not rest on the four columns and two pillars which are prolonged in the choir above, but on 28 smaller columns of graceful form, some of them ancient. Beneath the altar here is the tomb of S. Miniato. — The front-wall of the crypt, the screen of the choir, the apse, the whole wall of the nave, and the pulpit present beautiful specimens of incrustated marble-work. The upper part of the APSE is adorned with a mosaic of S. Miniato before the Saviour, executed in 1297, recently restored. The five windows under the arches are closed with semi-transparent slabs of marble. Over an altar on the right, the portrait of S. Giovanni Gualberto (see above). — On the S. side of the choir is the SACRISTY (closed), erected in 1387 in the Gothic style, adorned with sixteen frescoes from the life of St. Benedict (his youth, ordination at Subiaco, miracles, etc.) by *Spinello Aretino* (d. 1410). Below them, admirable inlaid work in wood. — The beautiful mosaic pavement (niello, executed, according to an inscription, in 1207) also deserves inspection.

A visit to S. Miniato may be conveniently combined with a drive on the Viale dei Colli. A walk to the Piazzale Michelangelo, S. Salvatore del Monte, S. Miniato, and thence to the Torre del Gallo (see below), and back by the Poggio Imperiale to the Porta Romana (p. 383; Pl. A, 6), will take about 3 hrs. in all.

(C.) POGGIO IMPERIALE. Immediately to the left, outside the Porta Romana (Pl. A, 6), through which the high road to Siena and Rome issues, begins the Viale dei Colli, mentioned at p. 383. To the right of it a fine avenue of lofty cypresses, evergreen oaks, and larches, embellished with a few statues, leads in 20 min. to the **Villa Poggio Imperiale**. It was thus named and almost en-

tirely fitted up by Magdalene of Austria, wife of Cosmo II., and afterwards adorned with various works of art, which were removed in 1860. The handsome edifice is now occupied by the *Instituto della SS. Annunziata*, a girls' school, and is no longer accessible. ¶

The road now divides: that to the *right* leads to Galluzzo and the Certosa (see below); that to the *left* (soon passing a group of houses, following the *Via del Pian Giullari*, and ascending the height, where at a bifurcation of the road, a bye-road in a straight direction is to be followed) leads to the **Torre del Gallo**, so called after a family of that name (or, according to others, from its conspicuous weather-cock), and containing various reminiscences of *Galileo*, who from this tower is said to have made several important astronomical observations. Fine \*Panorama (fee). — S. Miniato is about 1 M. from this point (comp. Map).

The road to the right passes ( $\frac{1}{4}$  hr.) several houses and villas, among which is the **Villa of Galileo**, marked by a bust and inscription, where the great astronomer passed the last years of his life (1631-42), latterly deprived of sight and surrounded by a few faithful friends, and where he was visited by his illustrious contemporary Milton. — A short distance hence, near the church of *S. Margherita a Montici*, stands the villa where *Francesco Guicciardini* wrote his history of Italy. Here too, on 12th Aug., 1530, the Florentines who had been betrayed by their general Malatesta, signed the articles by which the city was surrendered to the Imperial troops and thus became subject to the rule of the Medici. From that event the house derives its name *Villa delle Bugie* ('villa of lies').

(D.) LA CERTOSA IN THE VAL D'EMA is 3 M. distant by the high road from the Porta Romana (Pl. A, 6; carr. 6 fr.; fare via Poggio Imperiale higher). To the right, as the height beyond the gate is ascended, rises the church of *S. Gaggio*; farther on is the village of *Galluzzo*, beyond which the brook *Ema* is soon reached. On an eminence, clothed with cypresses and olive-trees, at the confluence of this brook with the *Greve*, rises the imposing \***Certosa di Val d'Em**a, in appearance resembling a mediæval fortress. The monastery, which is approaching dissolution and contains twelve inmates only, was erected in 1341 by the Florentine *Niccolò Acciajoli*, from a design by *Orcagna*. The porter (1-2 pers., 1 fr.) shows the church, or rather the series of chapels of which it consists, and the monastery with its various cloisters.

CHURCH. Magnificent pavement and fine carved stalls (of 1590); over the altar, Death of St. Bruno, a fresco by *Poccetti*. — \*RIGHT SIDE-CHAPEL, in the form of a Greek cross, erected by *Orcagna*: to the left St. Francis by *Cigoli*; SS. Peter the Martyr, George, Jerome, Francis, two Madonnas, and the \*Trinity, of the *School of Giotto*. A staircase to the left descends to a chapel with the tombs of the *Acciajoli*; monument of the founder *Niccolò* by *Orcagna* (1366); three monumental slabs, that of a \*young warrior by *Donatello*; tombstone of a cardinal of the family by the same, the ornamentation by *Giuliano da San Gallo*. — We then return through the church and enter the CLOISTERS, with stained glass by *Giovanni da Udine*, and a fountain, perhaps by *Brunellesco*. — To the right is the CHAPTER HOUSE: *Mariotto Albertinelli*, Crucifixion (fresco of 1505); opposite, a Madonna and Child by *Perugino* (?); monument of bishop Buonafide by *Giuliano da San Gallo*. — We next enter the monastery garden, which also serves as a burial-ground, and is surrounded by handsome

cloisters. Some of the empty cells, which enclose the building like pinnacles, command picturesque views, especially through the valley of the Ema towards Prato and the Apennines. — At the *Spezeria* of the monastery good Charreuse and various perfumes may be purchased.

(E.) \***Bello Sguardo**, to the S.W. of Florence, is celebrated for the delightful prospect it commands, which the traveller should on no account fail to visit. From Porta Romana (Pl. A, 6) the town-wall must be followed to the right and the second road to the left taken. This first leads to an open space with the small church of *S. Francesco di Paola*, which contains the monument of Benozzo Federighi, bishop of Fiesole, by *Luca della Robbia*. The carriage-road is then followed in a straight direction, and on the height, where it divides, the road to the left is taken (a few paces beyond this point the road to the Monte Oliveto diverges to the right, see below). At the next bifurcation a side-path to the left is followed, which in a few minutes leads to the \*\**Bello Sguardo* (visitors ring; fee 2-3 soldi on leaving). The view embraces Florence, with the Pitti Palace, S. Croce, the Palazzo Vecchio, Or S. Michele, the cathedral, S. Lorenzo, S. Maria Novella, etc.; to the right, on the height, S. Miniato, opposite the spectator lies Fiesole; to the left, the populous valley of the Arno, over which tower the distant Apennines. The view is seen to the best advantage towards sunset. — In the vicinity is the *Villa degli Albizzi*, with a bust of Galileo and an inscription to the memory of that illustrious astronomer, who frequently resided here and cultivated the garden with his own hands.

The road by the first bifurcation mentioned above leads, beyond the Bello Sguardo, to the right to *Monte Oliveto*. — Those who wish to visit the Bello Sguardo from the Porta S. Frediano follow the city-wall to the left and take the first road to the right, leading to the above-mentioned church of S. Francesco.

(F.) **Monte Oliveto**. About  $\frac{1}{3}$  M. beyond the Porta S. Frediano (Pl. A, 3) the 'Via di Monte Oliveto' diverges to the left from the Leghorn road, and reaches the entrance to the garden of the monastery after  $\frac{1}{2}$  M. (a gate marked No. 5; key to obtain access to the point of view, next door, No. 6, 2-3 soldi). A slight eminence here planted with cypresses commands an admirable \*Prospect: N.W. the beautiful valley of Florence, with Prato and Pistoja, enclosed by mountains, over which rises one of the peaks of the marble-mountains of Carrara; N.E. lies Florence, then Fiesole with its numerous villas; E. the Fortezza di Belvedere and S. Miniato; in the background the barren mountain-chain of the Casentino. Towards the S. the view is excluded by the intervening heights. The monastery-buildings are now used as a military hospital.

The *Badia di S. Bartolommeo di Monte Oliveto*, erected in 1334, possesses frescoes by *Poccetti*; in the refectory an Annunciation by *Dom. Ghirlandajo*. — From the suburb of *S. Frediano* a suspension-bridge (5 c.; Pl. A, 2) leads to the *Cuscine*.

(G.) The \***Cascine**, or park of Florence, lies to the W., beginning near the *Barriera Nuova* (in the Piazza Vitt. Emanuele, Pl. A, 2), and is about 2 M. in length, but of moderate breadth, being bounded by the Arno and the Mugnone. It affords delightful and refreshing walks to the traveller fatigued with sight-seeing. The name is derived from a farm to which it once belonged (*cascina*, i. e. dairy). It is a fashionable rendezvous in the afternoon. — Outside the town, immediately to the left, is a small *Caffé*. — About the middle of the Cascine is a large open space (where a military band plays several times a week), surrounded by several country-houses (*Casino delle Cascine*, a café belonging to Doney's, p. 324), a gay and favourite resort towards sunset. Beyond this spot the park is comparatively deserted, and it terminates about 1 M. farther, where the monument of the *Rajah of Holapore*, a young Indian prince, who died at Florence in 1870, and whose body was burnt at this spot, is situated.

On the road to Pistoja, about  $\frac{3}{4}$  M. from the Porta al Prato, is situated the *Villa Demidoff*, founded by the prince of that name (d. 1870), with gardens and hot-houses (visitors not always admitted).

About  $\frac{1}{2}$  M. from the Villa Demidoff, to the right beyond *Ponte a Rifredi* (railway-station, see p. 323), and near the ancient church of *S. Stefano in Pane*, lies the **Villa Careggi**, the property of the grand-dukes down to 1780, and afterwards that of the Orsi family, erected by *Michelozzo* for the first Cosmo, who terminated his brilliant career at this house in 1464. This was also once the seat of the *Platonic Academy* (p. 330). *Lorenzo il Magnifico*, grandson of Cosmo, also died at Careggi (1492). Fine view of the environs. A few frescoes by *Pontorno* and *Bronzino* and a series of portraits are reminiscences of the history of this edifice.

Farther W. is the **Villa della Petraia**, with delightful gardens, erected by *Buontalenti*, and adorned with paintings by *Andrea del Sarto* and *Daniele da Volterra*. The villa, which is now fitted up as a royal residence, is most conveniently reached from the railway-station *Castello* (p. 323). Near it is the *Villa Quarto*, with beautiful gardens, formerly the property of the Medici.

From railway-stat. *Sesto* (p. 323) a visit may be paid to the great porcelain-manufactory *della Doccia*, the property of *Marchese Gimori*, who possesses a villa here. The proprietor has successfully revived the ancient majolica manufacture, and produces excellent copies of Della Robbia work. Visitors are not always admitted.

(H.) **FIESOLE**, on the height to the N. of Florence, is 3 M. distant (omnibus, starting from the vicinity of the Piazza del Duomo, three times daily, 1 fr.; carr. 7-8 fr., see p. 325). We leave the town by the *Porta S. Gallo* (Pl. F, 2), where a *Triumphal Arch* of no artistic merit, erected in 1738, commemorates the entry of the grand-duke Francis II. Outside the gate rises a handsome new

colonnade. — We follow the Viale Militare (Pl. G, 2), cross the Piazza delle Cure, and then ascend the left bank of the *Mugnone* (Via Boccaccio), an insignificant stream, which however in rainy weather sometimes causes great devastation, to the (1 M.) *Villa Palmieri*, the property of the ex-ducal family, the terrace of which crosses the road by a bridge. Boccaccio makes this the residence of the narrators in his Decamerone during the plague in 1348. The road then ascends rapidly between garden-walls, and reaches (1 M.) the church of S. DOMENICO DI FIESOLE, in the former monastery of which *Fra Angelico*, the celebrated painter of saints, lived before his removal to S. Marco at Florence; the choir of the church contains a Madonna with saints, painted by him. (Opposite the church the 'Via della Badia' diverges to the left, see p. 389.) — The road divides here: the old road to the left leads past the *Villa Mozzi*, once a favourite residence of Lorenzo il Magnifico, reaching the height in 20 min.; the new road to the right winds gradually upwards, passing several pretty villas, and finally skirting the S. side of the ancient Etruscan wall of Fiesole. This excellent road is principally indebted for its construction to the *Golden Book* of Fiesole. This venerable volume enjoys the privilege of ennobling those whose names are inscribed on its pages, and, when the Fiesolans were desirous of constructing the road, their 'golden book' distributed its favours extensively among the Florentines and others, in return for a substantial equivalent.

**Fiesole** (*Trattoria l'Aurora*, fine view; *Locanda Firenze*), Lat. *Fæsulæ*, is an ancient Etruscan town, the Cyclopean walls of which are still partially preserved. It was for a long period more powerful than its rival Florence, to the jealousy of which it at last fell a victim in 1010 (p. 329). The town, the seat of a bishop, but now of no importance, contains 2800 inhab., who like most of the natives of this district are engaged in straw-plaiting (purchasers of their wares should as a rule give only half the price demanded).

On the height we enter the spacious PIAZZA OF FIESOLE, and perceive immediately opposite us the *Cathedral*, one of the earliest and simplest examples of the Tuscan style, begun in 1028 by Bishop Jacopo Bavaro, shortly after the destruction of the ancient Fæsulæ by the Florentines, but not completed till much later. It is a basilica of poor exterior, consisting of nave and aisles with a transept, and a spacious crypt beneath the lofty choir.

Over the altar, statues by *Andrea Ferrucci*. The chapel to the right of the choir contains the "monument of Bishop Salutati (d. 1465), by *Mino da Fiesole*, opposite which is a "bas-relief by the same master, representing the Madonna with St. Remigius and St. Leonhard, in the foreground the Infant Christ, and John the Baptist with a beggar. On the entrance-wall, over the door: "St. Romulus, with rich frame by *Luca della Robbia*.

Opposite the cathedral, on the W. side of the piazza are the *Episcopal Palace* and the *Seminary*. — On the E. side of the piazza

is the *Palazzo Pretorio*, of the 13th cent., bearing the arms of the magistrates (podestà); on the ground-floor is the *Museo Fiesolano*, founded in 1874 and containing the yield of recent excavations. Adjacent to it is the venerable church of *S. Maria Primerana*, dating from the 10th cent., containing a tabernacle in terracotta of the school of the *della Robbia*; on the right a portrait head of *Giuliano da San Gallo* by himself.

Beyond the cathedral, and descending the first side street to the right, we come to a well preserved fragment of an *Ancient Etruscan Wall*, situated among modern terrace walls. — The excavations, which have been resumed since 1873, have brought to light important remains of an *Ancient Theatre* (adm.  $\frac{1}{2}$  fr., and a trifling fee). Sixteen tiers of seats, in a semicircle (37 yds. in diameter), are now visible; the stage was open towards the S.

The site of the old Acropolis of Fæsulæ is occupied by a *Franciscan Monastery*, to which the street ascending to the W. opposite the cathedral leads. On the right, a little below the monastery, rises the venerable church of *S. Alessandro*, with 15 antique columns of cipollino, probably occupying the site of a heathen temple. The plateau in front of it commands a beautiful and extensive \*VIEW of the valley of Florence, bounded on the S. by several ranges of hills, on the E. by the mountain-chain of the Casentino, and on the W. by the heights of Monte Albano, beyond which the mountains of Carrara stand prominently forth.

Those who have time should ascend the eminence a little to the E. of Fiesole, which is higher than the Franciscan monastery and commands an uninterrupted panorama.

On the way back we may visit the *Badia di Fiesole*,  $\frac{1}{4}$  M. to the W. of S. Domenico (p. 388), a monastery founded in 1028, occupied first by Benedictine, afterwards by Augustinian monks. It was re-erected by *Brunellesco* in 1462, by order of Cosmo the Elder, and forms a remarkably attractive pile of buildings.

The CHURCH, with a transept, but destitute of aisles, is covered with circular vaulting, and is of noble proportions throughout. The part of the façade which is decorated with black and white marble belongs to the older structure, and is coeval with S. Miniato (p. 384). In the interior are several tombstones of the celebrated families of the Salviati, Marucelli, Doni, etc. — The REFECTORY is adorned with a quaint fresco by *Giovanni da San Giovanni* (d. 1636), representing angels ministering to Christ in the wilderness.

The monastery, which was highly favoured by the Medici, was frequently the residence of members of the 'Platonic Academy'. Picus of Mirandola here worked at his exposition of Genesis. After the suppression of the monastery (1778), the printing-office of the learned *Francesco Inghirami*, where a number of important works were published, was established here. It is now occupied by a farm.

(I.) About  $\frac{3}{4}$  M. from the *Porta alla Croce* (Pl. G, 5), on the left of the high road, beyond the railway to Arezzo, are situated the remains of the monastery of *S. Salvi*, of the order of Vallombrosa, and mentioned as early as 1084, where in 1312 Emp. Henry VII.

established his head-quarters during the siege of Florence. The former refectory contains a well-preserved and finely coloured \*Fresco by *Andrea del Sarto* (1526-27), representing the Last Supper (Christ is about to take a piece of bread to dip in the dish; Judas already has the sop in his hand). The traveller may prolong his walk hence in the valley of the Arno as far as *Compiobbi*, a station on the line from Florence to Arezzo (see below), and return to Florence by the last train.

(K.) VALLOMBROSA. A visit to this celebrated monastery may be accomplished from Florence in one day; it is advisable, however, to start on the previous evening and pass the night at S. Pelago. If the traveller intends to include the Casentino Valley and the monasteries of Camaldoli and Alvernia in the excursion, three days will be required.

The train from Florence to Arezzo should be taken as far as Pontassieve (in 55 min.; fares 2 fr. 15, 1 fr. 50, 1 fr. 5 c.). From the central station near S. Maria Novella the train performs the circuit of the city, and stops at the station near *Porta Croce*, which may be more conveniently situated for some travellers than the principal station. It then skirts the right bank of the Arno. The valley soon contracts. 8 M. *Compiobbi*, a small village, lies in a richly cultivated district, above which rise barren heights.

13 M. *Pontassieve* (*Italia, Vapore*, both very poor inns; carriage to Pelago 5-6 fr.), a small village at the confluence of the *Sieve* and Arno, formerly derived some importance from its situation on the high road leading through the valley of the Sieve and over the Apennines to Forli.

Quitting the railway-station, we follow the broad road to the right, which after a few hundred paces crosses the Sieve. At (3 M.) the point where the road divides for the third time, we descend to the right, and proceed to ( $2\frac{1}{4}$  M.) the village of *Pelago* (\**Locanda al Buon Cuore*, R., B., and D. 5 fr., but previous agreement necessary; mule to Vallombrosa 5 fr.). The road continues practicable for carriages as far as *Paterno* ( $3\frac{3}{4}$  M. from Pelago, one-horse carr. 5 fr.), formerly the monastery-farm, now a royal agricultural institution, or even as far as the village of *Tosi*,  $1\frac{1}{2}$  M. farther. Those who make the excursion in one day need not go by Pelago, but may proceed direct from Pontassieve to Paterno and Tosi. The rugged and stony path ascends hence to the left by a chapel (carriage-road projected), traverses meadows, underwood, and pine forest, and about half-way up the Pratomagno mountain reaches —

**Vallombrosa** (2980 ft.), situated in a shaded and sequestered spot. The monastery was founded about 1050, and the present buildings date from 1637. It was suppressed in 1869, and has since been occupied by the R. *Instituto Forestale*, or forest school. Outside the walls is a small tavern.

The monastery of Vallombrosa was founded by *S. Giovanni Gualberto*, the scion of a wealthy and powerful family of Florence, who after a career of youthful profligacy resolved to devote the remainder of his life to the most austere acts of penance. His brother Hugo having fallen by the knife of an assassin, Gualberto was bound by the customs of the age to follow the bloody law of retaliation. Descending one Good Friday from the church of *S. Miniato* near Florence, accompanied by armed followers, he suddenly encountered the assassin at a narrow part of the road. The latter fell at his feet and implored for mercy. The knight, suddenly moved by a generous impulse, forgave his enemy, and resolved for ever to renounce the world and its passions. He accordingly retired to the cloister of *S. Miniato*; but finding the discipline there too lax, he betook himself to this lonely spot and founded Vallombrosa.

*Il Paradisino*, or *Le Cette*, a smaller cloister situated on a rock,  $\frac{1}{4}$  hr. to the left above the monastery, and now uninhabited, commands an admirable survey of the latter, which lies 266 ft. below, and of the broad valley of the Arno as far as Florence, half of the dome of which is visible behind a hill. The horizon is bounded by the marble-hills of Carrara.

Another good point of view is situated 1 M. to the S. of the monastery. The path leads to the left of the inn, and immediately beyond it passes a spring (to the right below the path), then traverses the wood, and reaches a projecting rock commanding an extensive view of the valley of the Arno.

The ascent of the *Pratomagno* from Vallombrosa occupies 1 hr. (guide 2 fr.). The path traverses dense pine-forest, then dwarfed beech-underwood, and finally green pastures. The view from the summit, which is 5323 ft. above the sealevel, is obstructed on the N. and S. by peaks of equal elevation. To the E. lies the green Casentino Valley, drained by an impetuous brook, the water of which is praised by Dante (*Inf. xxx. 64*), and bounded on the N.E. by the lofty Monte Falterona (where the Arno rises), a buttress of the principal chain of the Apennines; W. the fertile and richly cultivated valley of the Arno stretches as far as the dome of the cathedral of Florence, beyond which the blue Mediterranean is visible in the extreme distance. Above the towers of Florence rise the indented peaks of the mountains of Carrara and other summits, among which the Monte Cimone (6907 ft.), the loftiest of the N. Apennines, is most conspicuous.

From the PRATOMAGNO a steep path descends through woods and ravines ( $\frac{1}{2}$  hr.), skirting the brook *Solano*, traversing green meadows and stony slopes overgrown with thistles, and then underwood of beeches and chestnuts, passing *Cetica* and several other mountain-villages, and leading to the picturesque market-town of *S. Niccolò*, commanded by the ancient fort of that name, and situated at the confluence of the Solano and Arno, where the fertile Casentino expands. The river is crossed by a wooden bridge, beyond which a good road leads to the right, passing the ancient church of *Campaldino*, where in a sanguinary conflict, on 11th June, 1289, Dante distinguished himself by his bravery as a horseman, and aided his Guelph countrymen to crush the might of Arezzo and the Tuscan Ghibellines. The next place of importance is *Poppi* (see below).

(*L.*) **Camaldoli and Alvernia.** An attractive excursion may be undertaken from Vallombrosa to the *Casentino*, or upper valley



of the Arno, a district which affords an insight into the scenery of the Apennines. The carriage-road from Pontassieve (p. 390) to the Casentino crosses the *Consuma Pass*, about 9 M. distant. The expedition is, however, most suitable for pedestrians. From Vallombrosa a bridle-path (guide necessary, 2 fr.) traverses the brow of the hills, affording a succession of fine views, and leading in 2 hrs. to the *Osteria della Consuma*, the inn of a small mountain-village. If a carriage can be procured here, the traveller should drive to Bibbiena (15 M.), or at least to Pratovecchio (10 M.). The road traverses the lonely height of the *Monte Consuma* for 3 M., after which a view of the valley of the Arno is gradually disclosed. About 6 M. farther, near the extensive ruins of the castle of *Romena*, the road divides; that to the left leads to *Pratovecchio*, a short distance farther, and beyond it to *Stia*. From Pratovecchio pedestrians may proceed by *Moggiona* (poor inn) to *Camaldoli* in 3 hrs. The road to the right leads by *Castel S. Niccolò* (p. 391) to **Poppi**, the capital of the valley, situated on a hill rising above the Arno, the old castle of which with its lofty tower, erected in 1274, has long been visible to the traveller. Passing *Ponte a Poppi*, a few houses at the foot of the hill, we next reach **Bibbiena**, 3 M. farther, the birthplace (in 1470) of Bernardo Divizio, afterwards Cardinal Bibbiena, the patron of Raphael. From Bibbiena Camaldoli is reached by *Soci* and *Partina* in 5-6 hrs., and Alvernia by the valley of the *Corsalone* in 2 hrs. The direct footpath between the monasteries may be traversed in 4 hrs. Pedestrians may therefore reach Camaldoli in one day from Vallombrosa by Consuma and Pratovecchio, and on the following day proceed thence by Alvernia to Bibbiena.

The ancient abbey of **Camaldoli** lies in a grassy valley surrounded by forest. It was founded about the year 1000 by St. Romuald, but frequently destroyed by fire and devastated by war, in consequence of which the church was re-erected in 1523, and again in 1772. It has recently been suppressed by the Italian government, like all the other monasteries in Italy. The environs are wild and beautiful. A zigzag path ascends rapidly ( $\frac{3}{4}$  hr.) to the *Sacro Eremo*, a second monastery with hermitages, founded by St. Romuald in 1046. The name of the place is said to be derived from *Campus Maldoli*, in consequence of a certain pious Count Maldolus, the last proprietor, having presented it to his friend St. Romuald. From this spot the reputation of the order for austere discipline, sanctity, and erudition extended throughout the whole of Italy, although the number of their cloisters was never great. Camaldoli, as well as Vallombrosa, lost its valuable library and many treasures of art through the rapacity of the French in 1808. In 1814 the monastery was restored.

The views from the narrow mountain-ridge at the back of Camaldoli, especially from the summit which is not planted with trees, called the *Prato al Soglio*, are very extensive and beautiful. To the N.E. the houses of Forlì may be distinguished, still farther off the site of Ravenna, and in the extreme distance the glittering Adriatic; W. the chain of the Pratomagno and the green dales of Vallombrosa, the lower valley of the Arno as far as the Maremme of Pisa and Leghorn, and beyond them the Mediterranean. The spectator here stands on one of the summits of the 'back-bone of Italy', whence innumerable mountains and valleys, as well as the two different seas, are visible.

The source of the Arno (4250 ft.) on the *Fallerona* may be visited hence, and the excursion may be extended to the summit of the mountain by those who have energy for the ascent. Dante, who in the 14th canto of the *Purgatorio* describes the course of the Arno, accompanying it from its source to Arezzo and Florence with bitter complaints of the swine of the Casentino, the dogs of Arezzo, the wolves of Florence, and the foxes of Pisa, perhaps visited the Monte Fallerona in person. — Travellers generally proceed from Camaldoli to *Alverna* (some times called *La Vernia*), a rough walk of 5-6 hrs. The S. height is ascended as far as the chapel of St. Romuald; then to the right a descent to *Moggiona*, beyond which the path turns to the left, traversing a long and fatiguing succession of gorges and slopes; the path at the base of the mountains is therefore preferable. The market-town of *Soci* in the valley of the *Archiano* is first reached, then the profound valley of the *Corsalone*; beyond it rises a blunted cone, on which the path ascends in windings to a stony plain with marshy meadows. Above this rises the abrupt sandstone mass of the *Vernia*, to a height of 850 ft. On its S.W. slope, one-third of the way up, and 3906 ft. above the sea-level, is seen a wall with small windows, the oldest part of the monastery, built in 1218 by St. Francis of Assisi. The church dates from 1264. In 1472 the monastery was entirely destroyed by fire. Beautiful forests are situated in the vicinity, from the openings in which imposing mountain-views are often enjoyed. One of the grandest points is the *Penna della Vernia*, or ridge of the Vernia, also known simply as *l'Apennino*, 4790 ft. above the sea, 'the rugged rock between the sources of the Tiber and Arno', at it is called by Dante (*Paradiso* ii., 106). To the E. are seen the lofty *Sassi di Simone*, the mountains which bound the Tuscan Romagna in the direction of the republic of San Marino; N.E. the sources of the Tiber are situated behind the *Fumajolo*.

Near the monastery are the *Luoghi Santi*, a number of grottoes and rock-hewn chambers in which St. Francis once lived. The church contains no pictures worthy of mention, but several excellent reliefs in terracotta, especially an 'Annunciation by *Luca della Robbia*.

To the S., not far from the monastery, is situated the ruined castle of *Chiusi*, occupying the site of the ancient *Clusium Novum*, where Ludovico Buonarroti, father of Michael Angelo, once held the office of Podestà. The great master himself was born on 6th March, 1475, at *Caprese*, in the valley of the *Singorna* in the vicinity, but in 1476 his parents removed to *Settignano*, in the vicinity of the quarries.

The traveller is recommended to return from Bibbiena to Florence by Arezzo (diligence daily in 3 hrs.; one-horse carr. 10 fr.). The road follows the left bank of the Arno, passing several small villages, quits the river at *Giovi*, and entering the rich *Val di Chiana* leads to —

**Arezzo** (*Inghilterra; Vittoria*), a town with 11,000 inhab., possessing several interesting churches. That of *S. Francesco* contains frescoes by Piero della Francesca in the choir. *S. Maria della Pieve*, of the 9th cent., has a façade of 1216. The *Cathedral*, in the Italian Gothic style, begun in 1177, is embellished with several well-sculptured monuments. *S. Annunziata*, a Renaissance edifice, was built by *Ant. da Sangallo*. The *Museum*, in the Piazza Grande, containing Etruscan antiquities, and the *Pinacoteca* in the *Badia*, also merit a visit. — Arezzo is a station on the line Florence-Perugia-Rome (railway to Florence in 2½-3½ hrs.; fares 9 fr. 60, 6 fr. 55, 4 fr. 55 c.). Arezzo, and thence to Perugia, etc., see *Baedeker's Central Italy*.

## VIII. Corsica.

STEAMBOATS. — I. FROM MARSEILLES: *Comp. Fraissinet*, once weekly (Frid.), to Ajaccio in 26 hrs., fares 40 and 28 fr.; *Comp. Valéry*, twice weekly (Wed. and Frid.), also to Ajaccio; once weekly (Sund.) to Bastia, in 30 hrs., fares 30 and 20 fr.; once weekly (Tuesd.) alternately to Calvi and Isola Rossa, in 24 hrs. (returning to Marseilles: from Ajaccio on Tuesday, from Bastia on Thursday, and from Calvi or Isola Rossa on Saturday mornings).

II. FROM NICE (same fares as from Marseilles) every Wed. afternoon to Bastia (12 hrs.) or to Ajaccio.

III. FROM LEGHORN: *Società Rubattino*, to Bastia, once weekly in 7 hrs. Also once weekly from Ajaccio to Porto Torres in Sardinia in 7 hrs. Embarcation 1 fr. — *Diligences* run from Ajaccio and Bastia to all the principal places in the island (comp. p. 396).

**Corsica** (French *La Corse*), situated between 43° and 41° 21' N. latitude, 56 M. distant from Italy and 111 M. from France, and separated from Sardinia by the Strait of Bonifacio, which is 9 M. in width, possesses an area of 3386 sq. M., and a population of 258,000 souls (census of 1872). A broad mountain-chain, terminating towards the N. in the Capo Corso, consisting of grey granite and limestone formations, occupies almost the entire island. On the W. it rises abruptly from the sea, forming a number of bold promontories and deeply indented bays. On the E. side, towards Italy, the alluvial deposits have been more abundant, and have formed a level coast of some breadth. The vast height to which the mountains rise within a comparatively small space (e.g. Monte d'Oro 8690 ft., Monte Rotondo 9063 ft.) imparts a wild and imposing character to the scenery. Nine-tenths of the area of the island are uncultivated, while the mountains for the most part are clothed with magnificent forests. The Flora of the island is remarkable for its rare luxuriance and diversity, comprising specimens of almost every species of plant found on the shores of the Mediterranean. The timber of Corsica was highly esteemed by the ancients, and still supplies most of the French and Italian dockyards. Its mineral wealth, however, is far inferior to that of Sardinia.


The character of the natives, notwithstanding the levelling and equalising effects of advancing civilisation, corresponds with the wild aspect of their country, and, at least in the more remote districts, still retains many of those peculiar features described by ancient writers. Their insatiable thirst for revenge (*vendetta*), formerly one of the chief causes of the depopulation of the island, has never been thoroughly eradicated, although the authorities have adopted the most rigorous measures to counteract the evil. The perpetrators of these dark deeds withdraw themselves from the arm of justice and retire as outlaws (*banditi*) to the mountains, where, hunted like wild beasts by a corps of gendarmes constituted for this express purpose, they frequently protract their miserable existence for many years. At the same time this revengeful ferocity is to a certain extent compensated for by bravery, love of freedom, simplicity of manners, and hospitality, virtues which usually characterise a vigorous and primitive race. Their ballads, too, and especially their dirges (*vocéri*), are replete with poetical pathos.

The situation and climate of the island are Italian, as was also its history down to the year 1768. Since the beginning of the present century its union with France has been still more closely cemented by its connection with the family of Napoleon. It now forms the 86th Department, the capital of which is Ajaccio, and is divided into 5 Arrondissements: Ajaccio, Bastia, Calvi, Corte, and Sartene. Italian is still the language of the natives, but French is used for all official purposes, and is spoken by the educated classes.

The great attractions of Corsica are its beautiful scenery and its inter-

# CORSICA

1:1350000





esting historical associations, for it can boast of no antiquities or treasures of art. A visit to the island is now easily accomplished. A week's stay will enable the ordinary traveller to become acquainted with Ajaccio, Corte (ascent of Monte Rotondo), and Bastia. Those who desire a more thorough insight into the resources of the country and the character of the natives will encounter serious difficulties, and should endeavour to obtain introductions to inhabitants of the island.

Corsica, like its sister-island Sardinia, which was peopled by the same race, never attained to a high degree of civilisation in ancient times. The whole island is depicted as having been a wild and impenetrable forest, of very evil reputation. Its possession was nevertheless keenly contested by the great naval powers of ancient times. The Phœceans, banished from Asia by the Persians, founded the town of Alalia (afterwards Aleria) on the E. coast, at the mouth of the Tavignano, B. C. 556. After a great naval battle in 536, however, they were compelled by the allied Etruscans and Carthaginians to abandon their settlement and migrate to Italy, where they founded the town Elea, or Velia, in Lucania. The island then became subject to the Etruscans, and subsequently to the Carthaginians, from whom it was wrested by the Romans in 238. Under Marius and Sulla the colonies of Aleria and Mariana were established on the E. coast, but were both subsequently destroyed. The island was frequently used as a place of banishment, as in the case of the philosopher Seneca, who spent eight years here during the reign of the Emp. Claudius. His account of the country and its inhabitants is by no means flattering, and the Corsicans sometimes declare that 'Seneca era un birbone'. The following lines written by him are to this day partially true:

'Prima est ulcisci lex, altera vivere raptu,  
Tertia mentiri, quarta negare deos'.

After the fall of the Western Empire Corsica frequently changed masters; the Vandals, Byzantines, Ostrogoths, Franks, and Saracens rapidly succeeded each other in its possession. In 1070 the Pisans, and in 1348 the Genoese obtained the supremacy, which the latter retained till the 18th cent. Their oppressive sway, however, gave rise to a long series of conspiracies and insurrections, in many of which a number of remarkable characters and bold adventurers distinguished themselves. Thus Arrigo della Rocca, Vincentello d'Istria, and Giampolo da Leca in the 14th and 15th cent., and Renuccio della Rocca and Sampiero di Bastelica (killed on 17th Jan., 1567) in the 16th century. At length, in 1729, the universal disaffection to Genoa began to assume a more serious aspect, notwithstanding the efforts made by the Republic to stifle it with the aid of German auxiliaries. The last of a long succession of adventurers was a Baron Theodore Neuhof, from Westphalia, who landed on 12th March, 1736, at Aleria, near the mouth of the Tavignano, attended by a number of followers, and provided with warlike equipments. He was shortly afterwards proclaimed king of Corsica, under the title of Theodore I., but his success was short-lived, and he was soon compelled to quit the island, for the Genoese were assisted by the French. Theodore returned twice subsequently to Corsica, but was ultimately compelled to seek an asylum in London, where he died in obscurity in 1756. Meanwhile the Corsicans, under the command (from 1755) of the heroic Pasquale Paoli (born in 1724 at Stretta, a village among the mountains S.W. of Bastia; died in London in 1807), fought so successfully against the Genoese, that the latter lost the whole island with the exception of Bastia. By the Treaty of Compiègne in 1768 Genoa ceded Corsica to the French, who however were still strenuously opposed by Paoli and other leaders, and were unable thoroughly to assert their supremacy until 1774. After the French Revolution Paoli returned from England to Corsica, after an exile of 20 years, and became president of the island. Internal dissensions, however, again springing up, the English were invited by Paoli to his aid, and in 1794, under Hood, conquered the island. In 1796 they were compelled to abandon their conquest, and since that period Corsica has belonged to France.

## Ajaccio.

**Hotels.** \*HOTEL GERMANIA, the only one possessing rooms with a S. aspect; R. 2-6, pension about 7 fr.; HÔTEL DE FRANCE, in the Place Bonaparte; HÔTEL DU NORD and HÔTEL DE L'EUROPE, both in the Cours Napoléon, pension 6 fr. — *Private Apartments* from 40 fr. per month (without attendance). — Several *Cafés* in the Rue du Marché.

**Banker:** *M. Bozzo*, Boulevard Roi Jérôme.

**Carriage** per hour 2, per day 15-20 fr. — *Saddle-horse* 3 fr. per half-day. — *Rowing-boat* to carry 1-10 persons 3 fr. per hour.

**Steamboats** (comp. 394) to Marseilles on Tuesdays at 10 a. m., to Nice every alternate Saturday.

**Diligence** daily to Bastia (p. 401), Sartene, and Vico. Office in the Cours Napoléon. *Post Office* in the same street.

Ajaccio (pronounced Ajassio in French), with 14,500 inhab., was founded by the Genoese in 1492, and made the capital of the island in 1811 by Napoleon, at the request of his mother Letitia. It is most beautifully situated in an extensive bay, which stretches N. to the *Punta della Parata*, near the *Isole Sanguinarie*, and S. to the *Capo di Muro*, whilst the background is formed by imposing mountains, often covered with a snowy mantle until late in the summer. The town presents a somewhat deserted aspect, although great improvements have taken place of late years. The mildness of the climate attracts a number of invalids as winter-residents.

The broad Place and Rue du Marché, one of the principal streets in the town, adorned with a fountain and a marble statue of Napoleon I., leads from the harbour to the *Place Bonaparte* or *Place d'Armes*, sometimes also called *Place du Diamant*. To the right, in the Place du Marché, at the point where the *Boulevard Roi Jérôme* diverges, is situated the *Hôtel de Ville*, with a library on the ground-floor. On the first floor is the \*Reception Hall, adorned with busts and pictures illustrative of the history of the family of Napoleon.

The Rue Fesch, the next street to the right, leads to the *Collège Fesch*, which contains a large collection of pictures (500, most of them copies), casts, a library and collection of minerals, bequeathed to the town by Cardinal Fesch, and augmented by gifts from the late Emperor. The court contains a statue of the cardinal in bronze.

Adjoining the college is the new *Chapelle Impériale*, to which the monuments of Letitia Ramolino, the mother of Napoleon (d. 2nd Feb., 1836, in her palace at Rome), and of Cardinal Fesch (d. at Rome, 1839), her half-brother, have been recently transferred from the cathedral (p. 397).

By the street to the left opposite the fountain, and then by the third transverse street to the right, we reach the small *Place Letitia*, containing the house in which Napoleon was born, with the inscription: '*Napoléon est né dans cette maison le 15 Août 1769*' (the concierge lives opposite, fee 1 fr.). It is preserved in

its original condition, but presents nothing remarkable beyond its historical association.

The family of Buonaparte appears to have emigrated in the 16th cent. from Sarzana in Tuscany, perhaps with the powerful Malaspinas, to Corsica. Messire Francesco Buonaparte, the first member of the family who resided in Corsica, died at Ajaccio in 1567. Napoleon's father, Carlo Maria Buonaparte, born at Ajaccio, 29th March, 1746, was educated at a school founded by Paoli at Corte, and afterwards studied law at Pisa. He then became an advocate at Ajaccio, where he enjoyed considerable popularity, but was soon appointed by Paoli his secretary at Corte. After the disastrous battle of Ponte Nuovo, 9th May, 1769, in consequence of which Corsica lost its independence to France, Carlo fled with his young wife Letitia Ramolino to the Monte Rotondo. He shortly afterwards returned to Ajaccio, where the French General Marbeuf, the conqueror of Corsica, accorded him protection, and where, about two months later, Napoleon was born. In 1777 Carlo was appointed deputy of the nobility for Corsica, and travelled via Florence to Paris. He died at Montpellier in February, 1785. Napoleon, then 16 years of age, having quitted the school at Brienne two years previously, was studying at the École Militaire at Paris. The letter of condolence which he wrote to his mother on the occasion is still extant. During his visits to Ajaccio his favourite retreat was Milelli, a small country-house in the neighbourhood. After the storming of the Bastille in 1789 and the great subsequent crisis, Napoleon with his elder brother Joseph warmly espoused the popular cause at Ajaccio. He then repaired to Marseilles to welcome Paoli on his return from exile, and the latter predicted on this occasion that a great destiny was in store for the youth. In 1791 Napoleon obtained the command of the newly constituted Corsican battalions, and in this capacity practically began his military career. In 1792, Paoli, dissatisfied with the proceedings of Napoleon, sent him to S. Bonifacio, to join the expedition against Sardinia. This, however, proved an utter failure, and on 22nd January, 1793, Napoleon narrowly escaped being slain by insurgents. Shortly afterwards he broke off his connection with Paoli and was compelled to quit Corsica with his family. During the zenith of his power the Emperor evinced little partiality for his native island, which he visited for the last time on 29th September, 1793, on his return from Egypt. During his exile in the island of St. Helena, however, his thoughts appear frequently to have reverted to Corsica. 'What reminiscences Corsica has left to me!' he was frequently heard to exclaim; 'I still think with pleasure of its mountains and its beautiful scenery; I still remember the fragrance which it exhales.' Autommarchi, Napoleon's physician in St. Helena, and the priest Vignale, who performed the last offices of religion, were Corsicans, and shared the fate of their illustrious compatriot.

The *Cathedral*, where Napoleon was baptised on 22nd July, 1771, dates from 1585.

The *Place Bonaparte* (formerly *Diamant*) is adorned with an equestrian *Statue of the Emperor* with his four brothers, in bronze, his gaze turned towards the sea in the direction of France, erected in 1865.

In a side street of the *Place du Marché* is situated the palace of the *Pozzo di Borgo*, one of the most distinguished Corsican families.

*Carlo Andrea Pozzo di Borgo*, born on 8th March, 1768, an early friend of Napoleon, a democrat and adherent of Paoli, afterwards became the Emperor's bitterest enemy. He subsequently became a Russian counsellor of state, and in 1802 was created a count and appointed ambassador, in which capacity he indefatigably devoted his energies to opposing his ambitious countryman. He died at Paris in 1842. His nephew, the heir to his extensive property, afterwards fell a victim to Corsican revenge.



The Cours Napoléon terminates in the high road to Bastia. To the right, outside the gate, is the monument of *General Abbattucci*, a Corsican who fell in 1796, whilst defending the town of Hüningen. This road affords a pleasant and cheerful promenade. Adjoining it is the *Botanic Garden* which merits a visit.

The road on the N. side of the bay, passing the new *Hospice Eugénie*, although destitute of shade, also affords a charming walk. The gardens here contain numerous family burial-places and chapels.

#### From Ajaccio to S. Bonifacio, and to Bastia by the E. Coast.

Carriage-road from Ajaccio to Bonifacio (86½ M.); diligence daily to Sartene, 52½ M. distant.

The fortress of **Bonifacio** (3600 ft.) is picturesquely situated on a prominent and lofty rock. It possesses high and dilapidated houses, of the Pisan and Genoese periods, and narrow, unattractive streets. The principal street is called the *Piazza Doria*. The town was founded in 833 by the Tuscan Marquis Bonifacio, after a naval victory over the Saracens. *Il Torrione*, a large tower of that remote date, is still standing. Bonifacio subsequently came into the possession of the Pisans, then into that of the Genoese, by whom it was treated with marked favour. In return for this partiality this town, as well as Calvi, remained inviolably faithful to Genoa, as was proved in 1420 by its memorable defence against King Alphonso I. of Arragon. In 1541 the Emp. Charles V., on his return from the expedition against Algiers, paid a visit to Bonifacio. The house of Filippo Cataccioli, in which the Emperor lodged, is still pointed out. The town once boasted of 20 churches, of which the cathedral of *S. Maria del Fico*, the handsome Gothic church of *S. Domenico*, with numerous tombstones of knights Templar and Genoese nobles, and the small church of *S. Francesco* (with a spring, the only one which the town possesses) now alone remain.

A stone bench above the Marina of Bonifacio, by the old gate of the fortress, near the small chapel of *S. Rocco*, commands a charming view, especially by evening-light, of the strait which separates Corsica from Sardinia. On the opposite coast the town of *Longo Sardo*, with its lighthouse, is visible; farther distant, a series of watch-towers on the shore may be distinguished; on the left lies the island of *S. Maddalena*. On the coast below Bonifacio are situated three imposing *Grottoes*, which visitors explore by boat.

The distance from BONIFACIO to BASTIA is 106 M. The E. coast of Corsica is somewhat bleak and desolate. The road leads past the bay of *S. Manza* to (16 M.) *Porto Vecchio*, the only good harbour. It was constructed by the Genoese, and is supposed to occupy the site of the ancient *Portus Syracusanorum*. Hence to the mouth of the Tavignano 44½ M., where, near the lake of *Diana*, the ancient town of *Aleria* was situated. Fragments of masonry and vaulting, and remnants of a circus are still to be seen. Coins, vases, and inscriptions have also been found here. The modern Aleria consists of the Genoese castle and a small group of houses only, for this coast, owing to the want of cultivation, is marshy and unhealthy. Here, on 12th March, 1736, the adventurer Neuhof (see p. 395) landed from an English vessel. About 15½ M. farther is *S. Nicolao* (2 M. on this side of which a road diverges to *Cervione*, 2¾ M.). The river *Golo* (p. 399), often nearly dry in summer, is next crossed. In the extensive plain at its mouth, on the left bank, once lay *Mariana*, the Roman colony founded by Marius, the remains of which are visible on the shore, 3 M. from the road. The ruins of a beautiful chapel, and of a church called *La Canonica*, a basilica of noble proportions, in the Pisan style, are situated here.

## From Ajaccio to Bastia.

94 M. DILIGENCE daily in 20 hrs., starting at 11 a.m., and halting for dinner at Vivario at 7 p.m. (dinner at Corte on the return-journey). The service is well performed, and horses are changed frequently. *Fares*: intérieur 16, coupé 24 fr.; 25 kilogrammes (56 lbs.) of luggage free, each additional kilogr. 25 c. — Post-chaise with relays of horses from Ajaccio to Bastia 184 fr. — Omnibuses also run from Corte to Bastia daily, fare 4, coupé 5 fr. The carriages are the same as the diligences, but the horses are less frequently changed.

The road traverses the well cultivated plain of *Campoloro* (*Campo dell' Oro*), which extends to the S. half of the bay of Ajaccio, and is watered by the *Gravone*. The road follows the stream and ascends. The scenery gradually becomes more attractive, magnificent forests clothe the slopes, and several beautiful retrospects are enjoyed. Beyond *Bogognano* (25 M. from Ajaccio) the *Gravone* is quitted, and a mountain, 3672 ft. high, traversed. On the N. towers the *Monte d'Oro*, a few hundred feet lower than *Monte Rotondo* (p. 400), but of more imposing form; on the S. rises the *Monte Renoso*. The road next traverses the great forest of *Vizzavona*, and descends rapidly to the pleasant mountain-village of *Vivario*. It then turns N. and skirts the base of the *Monte Rotondo*, leading through a wooded and well-cultivated tract, past the villages of *Serraggio*, *Capo Vecchio*, and *S. Pietro*, to (52½ M. from Ajaccio) *Corte*, see p. 400. The road next reaches the *Golo*, the principal river of the island, at *Ponte alla Lecciu*, 12½ M. from *Corte*.

A road leads hence to *Calvi*, 46½ M. distant, to which a diligence runs. It proceeds to the E. by *Morosaglia* and *Porta*, and descends to the coast. Several miles higher up lies the district of *Rostino*, or *Morosaglia*, the native place of the Paoli family. A dilapidated cottage is still pointed out, in the hamlet of *Stretta*, as that in which Pasquale Paoli was born in 1724. His father Hyacinth was a physician and poet, and at the same time the leader of the Corsicans; his mother Dionysia Valentina was a native of the neighbouring *Pontenuovo*. Anecdotes of his noble and heroic character are still current in this district; his memory is also perpetuated by a school, established in an old monastery at *Morosaglia* with funds bequeathed by him for the purpose. An apartment in the same monastery was once occupied by Pasquale Paoli as his study, and here his elder brother Clement, once a general, afterwards a monk, died in 1793.

The road to Bastia follows the right bank of the *Golo*, which it crosses at (5 M.) *Pontenuovo*. The *Golo* is followed as far as the point where the road unites with that from *Bonifacio* (p. 398).

A road leads S. from the river to (5 M.) the village of *Vescovato*, situated among mountains and forests of chestnuts, and containing the house of *Pietro Filippini*, the Corsican historian of the 16th cent. His work was republished at *Pisa* in 1827, having been edited by the learned *Gregori* by desire of the Corsican *Pozzo di Borgo*. Here also is situated the château of *Count Matteo Buttafuoco* (now the property of the family of *Marshal Sebastiani*), who when a young French officer invited *Rousseau* to *Vescovato*, in consequence of the following passage in his 'Contrat Social' alluding to the Corsicans: 'The vigour and perseverance with which these brave people have succeeded in gaining and defending their liberty merit for them that some wise man should teach them how to preserve it. I have a certain presentiment that this island will one

day cause astonishment to the whole of Europe'. The latter prediction was fulfilled 20 years after Rousseau's death (1778), although in a very different manner from that which the philosopher had in view.

The road now leads direct to the N.; the coast-district is flat and full of lagoons.

#### Corte and the Monte Rotondo.

**Corte** (*\*Hôtel de l'Europe*), with 5400 inhab., a sous-préfecture and capital of an Arrondissement, lies on the *Tavignano*, surrounded by mountains. It is commanded by a lofty citadel, which rendered it an important and keenly-contested point in the wars of former centuries. A number of Arabian prisoners from Algiers are usually confined in the citadel.

In Paoli's time Corte was the central point of his democratic government. His study, with window-shutters lined with cork, by way of additional precaution, and the council-chambers are still shown at the *Palazzo di Corte*. A university, a printing-office, and a newspaper were also established here by Paoli in 1765. The Corsican parliament of that period held its meetings at the neighbouring Franciscan monastery. Marble-quarries are worked in the vicinity.

The *Place Paoli*, the principal square, is embellished with a bronze statue of the noble-minded patriot with the French (!) inscription: 'Au général Pascal Paoli la Corse reconnaissante, l'an 1854'. In a piazza near the *Hôtel de l'Europe* rises a statue of *General Arrighi de Casanova*, 'Duc de Padoue' (born at Corte in 1779, d. at Paris in 1853), erected in 1868.

The **Monte Rotondo** is most conveniently ascended from Corte. The night after the ascent may be spent in one of the uninviting chalets at the base, or the traveller may prefer to return to Corte the same day, in which case he must be prepared for a journey of 14 hrs. at least, partly on horseback, and partly on foot. Guide and mule about 20 fr. A supply of provisions necessary. The ascent is not easily accomplished except in the summer months. At an early hour the traveller ascends the valley of the wild *Restonica*, which here falls into the *Tavignano* after a course of 35 M. A broad and wooded dale is at first traversed, beyond which the path becomes a mere shepherd's track. Pine and larch forest afford shade, while bleak open tracts and sequestered chalets, some of them 5000 ft. above the sea-level, are also occasionally passed. After a ride of 3 hrs., the *Rota del Dragone*, a grotto in the rocks affording shelter to 200 sheep and goats, recalling Homer's description of the Cave of Polyphemus, is attained. The *Co di Mozzo*, the last shepherds' station, inhabited in summer only, is reached after 2 hrs. more. These rude hovels, beautifully situated on one of the lower buttresses of the Monte Rotondo, afford shelter for the night in case of necessity (milk and cheese only to be had). Then across several rocky ridges in 2 hrs. more to the *Trigione*, the last spur of the Rotondo, a wilderness of blocks

of granite. The crater-shaped, snow-capped summit is visible hence; below it lies the small and clear *Lago di Monte Rotondo*; in the foreground, green pastures. Fields of snow and ice, rising from the lake, must be laboriously traversed (2 hrs.) before the summit (9053 ft.) is attained. A magnificent \*Panorama is here enjoyed. The spectator surveys the greater part of the island; N. the Capo Corso; W. the bays of Porto, Sagona, and Ajaccio; E. the blue Mediterranean, with the islands of Monte Cristo, Pianosa, Capraia, and Elba, and the mainland of Italy; then the white Alpes Maritimes, extending from Toulon and Nice to Genoa. Corsica itself resembles a vast rocky relief-map; its principal mountain-chains, with their rivers and valleys, are distinctly recognisable. Towards the S., however, the view is obstructed by the broad and massive Monte d'Oro. The descent may be made on the side next to the *Lago di Pozzolo*, where the dark rocky pyramid of the *Frate* (monk) rises. Violets and forget-me-not (here popularly called the 'marvellous flower of the mountains') grow abundantly in the rocky clefts on the banks of the lake. The mufpone, the wild horned sheep of Corsica, of a dark brown colour, with silky hair, browses on these lofty summits. The huts of Co di Mozzo may now be regained in 3 hrs., and Corte in 4-5 hrs. more.

### Bastia.

**Hotels.** \*HÔTEL DE L'EUROPE, Rue de l'Intendance; HÔTEL DE FRANCE, well spoken of; HÔTEL D'ITALIE, both in the Boulevard de Paoli. — *Restaurant de la Paix*, in the Boulevard; *Café Univers Guillon*; *Café du Nord*.

*Diligences* daily to Ajaccio, to Luri and Rogliano on the Capo Corso, and to S. Fiorenzo and the Balagna.

Bastia, with 18,000 inhab., the busiest commercial place in the island, and its capital down to 1811, was founded in 1380 by the Genoese and defended by a strong castle (whence the name of the town, signifying 'bastion'). The cathedral of *S. Giovanni Battista* contains several ancient tombs. In *S. Croce* rich decorations in marble. The college which formerly belonged to the Jesuits contains a library of 30,000 vols. and natural history collections. The Place St. Nicholas on the Promenade on the coast is embellished with a marble statue of Napoleon by *Bartolini*, whose fortunes the inscription records.

The old town with the citadel rises above the more modern quarter situated near the harbour. Beautiful walk along the coast towards the N., where a number of easily attained heights afford a variety of fine views of the sea and coast.

### From Bastia to Capo Corso, S. Fiorenzo, and Calvi.

A very pleasant excursion may be made to the long and narrow peninsula in which the *Serra Mts.* rise, culminating in the Monte Alticcione and Monte Stello (5000 ft.), and terminating on the N. in the *Capo Corso* (*Promontorium Sacrum*). Beautiful valleys descend on the E. and W. sides of these mountains. A good road leads along the coast from Bastia,

passing several ancient watch-towers of the Pisans and Genoese, and affording a view of the picturesque islands of Elba, Capraia, and Monte Cristo. At *Brando* there is a *Stalactite Cavern*, surrounded by pleasant gardens. *Luri* possesses a charming valley, watered by several streams, and producing a luxuriant growth of grapes, oranges, and lemons. The *Serra* is then crossed to *Pino* on the W. side, with villas and beautiful gardens. At the end of the promontory, to the N. beyond *Rogliano* and *Ersa*, rises a lighthouse. An ancient, half-ruined circular structure near it is popularly called the 'Tower of Seneca'.

A road leads from Bastia across the *Serra* to the (14 M.) small seaport of *S. Fiorenzo*, charmingly situated on the bay of that name on the W. side of the island, and commanded by a fort. In the neighbouring low ground formerly lay the mediæval town of *Nebbio*, the ruined cathedral of which (*S. Maria Assunta*), of the 12th cent., stands on an eminence. Beyond this the road skirts the sea, crosses the small river *Ostriconi*, and reaches the small, but thriving seaport town of *Isola Rossa*, founded in 1758 by Pasquale Paoli, notwithstanding the war in which he was then engaged with Genoa. Its name is derived from three red cliffs rising from the sea in front of the harbour. The environs are delightful; the view from the *Monte S. Reparata*, surmounted by a deserted church, is finest by evening-light.

The road then leads to *Algajola*, a deserted old town on the coast, with marble quarries in the vicinity. During the Genoese period it was fortified, and formed the central point of the fertile district of *Balagna*. The loftily situated village of *Lumio*, farther on, with its orange-plantations and hedges of cactus, commands a beautiful view of the valley and the town of *Calvi* (43 M. from *S. Fiorenzo*), an important and fortified place during the Genoese period, noted for its faithful adherence to the Republic, and in 1794 bravely defended against the English by the French commandant Casabianca. The natives of the place maintain that Columbus was born here, and that the name still exists. Traces of the English bombardment are still observable. The principal church contains the tombs of the Baglioni family, who bore the surname *Libertà*, from having distinguished themselves in the 15th and 16th cent. The environs of *Calvi* are marshy. Charming view of the bay, with the promontory of *Rivellata*, and of the rocky mountains of *Calenzana*, to the E. of the town.

A diligence runs from *Calvi*, traversing the beautiful and fertile valley of the *Balagna* (where the powerful Malaspina family dwelt for centuries), enclosed by lofty mountains, to *Novella*, the last village, and then through narrow rocky ravines to *Ponte alla Leccia* in the valley of the *Golo*, where the high road from Bastia to Ajaccio is reached.

---

# INDEX.

(The names of artists are printed in *Italics*.)

- Abano** 263.  
**Abbate** 145.  
*Abbate, Niccolò dell'* 191.  
**Abbiategrasso** 157.  
**S. Abbondio** 136. 143. 149.  
**Abetone, Passo dell'** 295.  
**Acqua Buja** 295.  
**Acquanegra** 164.  
**Acqui** 178.  
**Adda, the** 37. 43. 135. etc.  
**Adelsberg** 51.  
*Aedeodatus* 318.  
**Adige, the** 40. 46. 195. etc.  
**Adigetto, Naviglio** 164.  
**Adlitzgraben, the** 51.  
**Adria** 265.  
**Adriatic, the** 55. 248. etc.  
**Æmilia, Via** 249. 253.  
**S. Agäta** 153.  
**Agedincum** 2.  
**S. Agnese** 103.  
**Agno, the** 150.  
*Agnolo, Baccio d'* xlvi.  
**S. Agostino, Borgo** 139.  
**Aiguebelle** 23.  
**Ain, the** 5. 22.  
**Ainay** 6.  
**Airan** 13.  
**Airolo** 31.  
**Aix-en-Provence** 16.  
**Aix-les-Bains** 22.  
**Ajaccio** 394.  
**Alà** 50.  
**Alais** 13.  
*Alamannus* 211.  
**Alasio** 98.  
**Alba** 80.  
**Albano, Franc.** 272.  
**Albaredo, Monte** 73.  
**Albarinc, the** 22.  
**Albeins** 45.  
**Albenga** 97.  
*Alberti, Leon Batt.* xlii. 330.  
*Albertinelli, Mariotto,* xvii. 311. 362.  
**Albesio** 137.  
**Albigaunum** 97.  
**S. Albino** 145.  
**Albissola** 97.  
**Albizzate** 145.  
**Albizzi, Villa** 386.  
**Albogasio** 151.  
**Aleria** 98.  
**Alessandria** 78.  
 — *-Acqui-Savona* 80.  
 — *-Cavallemaggiore* 80.  
**Algaby Gallery, the** 26.  
*Alessi, Galeazzo* xlvi. 85.  
**Algajola** 402.  
*Allori, Crist.* lxi. 331. 376.  
 —, *Alessandro* 331.  
**Aloxe** 4.  
**Alps, the Cottian** 62.  
 —, *the Graian* 74.  
 —, *the Julian* 51.  
 —, *the Maritime* 80. 111.  
**Alpienbach, the** 26.  
**Alpignano** 21.  
**Alseno** 253.  
**Alserio, Lago** 136.  
*Allighieri* xli.  
**Altinum** 245.  
**Altmünster** 4.  
**Altopascio** 317.  
**Altorf** 29.  
**Alvernia** 393.  
**Amberieu** 5. 22.  
**Ambri** 31.  
**Ambrogiana, Villa** 301.  
**S. Ambrogio (near Modena)** 255.  
 — (near *Turin*) 24.  
 — (near *Varese*) 145.  
*Ammanati, Bart.* xlvi.  
**Ampola** 179.  
**Amsteg** 30.  
**Ancy-le-Franc** 2.  
**Andeer** 35.  
**Andermatt** 30.  
**Andes** 191.  
**Andora** 98.  
**St. André, Grotto of** 109.  
 —, *Château* 109.  
**St. Andrea del Lido, Island** 248.  
**Anfo** 180.  
 —, *Rocca d'* 180.  
*Angelico da Fiesole, Fra* li. 331. 361. 362. 388.  
**Angera** 156.  
**Anges, Baie des** 107.  
*Anguisciola, or*  
*Angussola, Sofonisbe* 165.  
**Annone** 78.  
 —, *Lago d'* 136.  
**S. Annunziata, Mouast.** 102.  
**Antibes** 21.  
**Antipolis** 21.  
*Antonello da Messina* 211.  
**Antongina, Villa** 139.  
**S. Antonino** 24.  
**S. Antonio** 43.  
 —, *near Mantua* 190.  
**Antrona Valley** 27.  
**Anzasca Valley** 27.  
**Aosta** 74.  
**Apennines, the** 77. 111. 295. 393. etc.  
**Aposa, the** 271.  
**Aprica** 176.  
 —, *Passo d'* 176.  
**Apuane, Alpi** 114.  
**Aquae Allobrogum or** — *-Gratianae* 22.  
 — *-Patavinæ* 263.  
 — *-Pisanorum* 312.  
 — *-Sextiæ* 16.  
 — *-Statielæ* 78.  
**Aquilaia** 248.  
**Arausio** 9.  
**Arbedo** 85.  
**Arbostora, Monte** 149.  
**Arc, the** 23.  
**Archiano, the** 393.  
**Arco** 48.  
**Arcola** 115.  
**Arcole** 195.  
**Arcore** 134.  
**Arcs, Les** 19.  
**Arda, the** 253.  
**Ardenza** 300.  
**Ardo, the** 246.  
**Arelate** 14.  
**Arena-Po** 77.  
**Arenzano** 97.  
**Arezzo** 393.  
**Argegno** 140.  
**Arles** 14.  
**Armançon, the** 2.  
**Armeno** 159.  
**Arno, the** 301. 312. etc.  
**Arola** 160.  
**Arona** 156.  
 — *-Genoa* 157.

- Arona Milan 157.  
*Arpino, Car. d' ix.*  
 Arquà 265.  
 Arquà del Monte 462.  
 Arquata 79.  
 Ascona 153.  
 Asigliano 175.  
 Aspremont, the 109.  
 Assenza 177.  
 Assina, Val<sup>e</sup> 137.  
 Asso 137.  
 Asta 77.  
 Asti 77.  
 Atoste 264.  
 Atzwang 46.  
 Auer 46.  
 Augusta Praetoria Salas-  
 sorum 74.  
 — Taurinorum 61.  
 Aulun 4.  
 Auxerre 2.  
*Avanzo, Jac. d' xli.*  
 Avenio 9.  
 Avena 115.  
 Averser Rhein, the 35.  
 Avigliana 24.  
 Avignon 9.  
 Avio 50.  
 Avisio, the 47.  
 Axenberg, the 29.  
 Axenstein 29.  
 Azi, Mont d' 23.  
 Bacchiglione, the 195.  
 199.  
 Bacher Mts., the 53.  
 Badagnano 253.  
 Badelwand, the 52.  
 Baden 51.  
 Badia di Fiesole 389.  
 Bagnacavallo 285.  
*Bagnacavallo (Ramunghi)*  
 lix. 272.  
 Bagni 263.  
 Bagni di Bormio 32.  
 — di S. Giuliano 312.  
 — di Lucca 317.  
 Bagnolo 161.  
 Bagueau, Island 19.  
 Balagna 402.  
 Balbianello, Villa (Lake  
 of Como) 140.  
 Baldichieri 77.  
 Baldo, Monte 179.  
 Balerna 146. 147.  
 Balfrin, the 25.  
 Balzola 175.  
*Bambaja* l. 126.  
*Bandinelli, Baccio* 331.  
 Bar 21.  
 Baracca 114.  
 Baradello, Castello 135.  
*Barbarelli, see Giorgione.*  
 Barberino 296.  
*Barbieri, see Guercino.*  
 Barcesine 179.  
 Barcola 58.  
 Bard, Fort 73.  
 Bardolino 180.  
 Bardonnecchia 24.  
 Bärenburg, the 35.  
 Barghe 180.  
 Bargilio 317.  
 Barni 137.  
 Baro, Monte 144.  
 Barrasso 146.  
 S. Bartolommeo, Monte  
 178.  
*Bartolommeo, Fra Ivii.*  
 331. 362. 375.  
 Baselga 48.  
 Bassano 49.  
*Bassano, Jacopo and*  
*Leandro* 212.  
 Bastia 401.  
 Bâtie, Chât. 23.  
 Battaglia 264.  
 —, Canale di 263.  
 Baveno 27. 134.  
*Bazzi, see Sodoma.*  
 Beaucaire 11.  
 Beaulard 24.  
 Beaulieu 110.  
 Beaune 4.  
 Becca di Nona, the 74.  
 Beckenried 29.  
 Bedretto, Val 31.  
*Begarelli Ant. l.* 260.  
 Belbo, the 80.  
 Belfort 4.  
 Belgiojoso 164.  
 Belgirate 27. 156.  
 Bella, Isola 155.  
 Bellagio 140.  
 —, the Punta di 142.  
 Bellano 143.  
 Bellegarde 22.  
*Bellini, Giov. lii.* 125.  
 212. 224.  
 —, *Gentile and Jac. lii.*  
 125. 211. 224.  
 Bellinzago 157.  
 Bellinzona 32.  
 Belluno 246.  
 Belmonte, Villa 142.  
*Belotto, see Canaletto.*  
*Beltraffio (Boltraffio),*  
*Giov. Ant. lxi.*  
 Benacus, Lacus 177.  
 Beni, Monte 295.  
*Benozzo Gozzoli, see*  
*Gozzoli.*  
 Berceau, the 103.  
 Bergamasco 80.  
 Bergamo 167.  
 Bergeggi, Promont. 97.  
 Berico, Monte 198.  
 Berisal 26.  
 Bernabò 317.  
 St. Bernard, the Great  
 74.  
 S. Bernardino 38.  
 S. Bernardino Pass, the  
 37.  
 Bernina, the 43.  
 Berre 816.  
 Bésançon 5.  
 Besenna, Villa 140.  
 Beseno, Castle 49.  
 Bevera, the 110.  
 Beverin, Piz 34.  
 Bezzecca 179.  
 Biacessa 179.  
 S. Biagio, Isola di 178.  
 Bianco Canal, the 265.  
 Biandrone, Lago di 146.  
 Bianchi 175.  
 Biasca 32.  
 Bibbiena 392.  
 Biella 75.  
 Bientina, Lago di 317.  
 Bietschhorn, the 25.  
 Bignone, Monte 100.  
 Binago 145.  
 Binasco 161.  
 Bironico 33.  
 Bisagno, the 84. 95. 112.  
 Bisbino, Monte 139.  
 Bisenzio, the 322.  
 Bissone 147.  
 Bistagno 78.  
 Bizozzero 146.  
 Blaisy-Bas 3.  
 Blegno, Val 32.  
 Blevio 136. 139.  
 Blumau 46.  
 Boara 264.  
 Bobbio 252.  
*Bocaccino da Cremona*  
 B 224.  
 Bodio 32.  
 Boesio, the 146. 153.  
 oghiaco 178.  
 Bogliasco 113.  
 Bogognano 399.  
 Bois-le-Roi 1.  
 Boletto 159.  
 Bolladore 43.  
 Bologna 270.  
 Accademia delle Belle  
 Arti 281.  
 Antiquities, Museum of  
 274. 280.  
 Archives 280.  
 Archiginnasio 274.  
 Banca Nazionale 275.

- Bologna:  
 S. Bartolommeo di Porta Ravegnana 278.  
 Biblioteca Comun. 274.  
 Campo Santo 283.  
 Cassa di Risparmio 277.  
 Cathedral, see S. Pietro.  
 S. Cecilia 280.  
 Certosa 283.  
 Collegio di Spagna 276.  
 S. Domenico 275.  
 S. Francesco 273.  
 Frati di S. Spirito 276.  
 Geolog. Museum 281.  
 S. Giacomo Maggiore 279.  
 S. Giovanni in Monte 278.  
 Giuoco di Pallone 271.  
 Leaning Towers 276.  
 Library 274.  
 —, University 280.  
 Loggia de' Mercanti 277.  
 Madonna di Galliera 276.  
 Madonna di S. Luca 284.  
 S. Maria ai Servi 279.  
 S. Martino Maggiore 283.  
 Mercato di Mezzo 276.  
 Mezzaratta 283.  
 S. Michele in Bosco 283.  
 Montagnola, La 283.  
 Palazzo Albergati 283.  
 — Arcivescovile 276.  
 — Baccocchi 275.  
 — Bentivoglio 283.  
 — Bevilacqua-Vincenzi 275.  
 — Fantuzzi 279.  
 — Fava 276.  
 — del Governo 272.  
 — Guidotti 275.  
 — Magnani-Guidotti 280.  
 — Malvezzi - Campeggi 280.  
 — — Medici 279.  
 — Marescalchi 273.  
 — della Mercanzia 277.  
 — Pedrazzi 279.  
 — Pepoli 277.  
 — del Podestà 273.  
 — Pubblico 272.  
 — Sampieri 278.  
 — Zambecari di S. Paolo 276.  
 S. Paolo 276.  
 S. Petronio 273.  
 Piazza d'Armi 283.  
 — Rossini 279.  
 — Vittorio Emanuele 272.
- Bologna:  
 S. Pietro 276.  
 Pinacoteca 281.  
 Portico de' Bianchi 273.  
 Rossini's House 279.  
 S. Salvatore 273.  
 Servi 279.  
 S. Stefano 277.  
 Theatres 270. 280.  
 Torre Asinelli 276.  
 — Garisenda 276.  
 Tribunale 276.  
 University 280.  
 Villa Reale 283.  
 S. Vitale ed Agricola 279.
- Bologna-Padua 263-65.  
 — -Piacenza-Milan 250-255.  
 — -Pistoja-Florence 294-296.  
 — -Ravenna 284.  
 Bolzaneto 79.  
 Bolzano (Piedmont) 76.  
 Bona, Val 179.  
 Bonaduz 34.  
 Bonannus 303.  
 Bonassola 114.  
 S. Bonifacio 195.  
 — (Corsi.) 398.  
 Bonifazio lx. 125. 212. 224. 376.  
 Bononia 271.  
 Bonvicini, see Moretto.  
 Borbone, the 77.  
 Bordighera 100.  
 Bordone, Paris lx. 212. 245.  
 Borgo S. Agostino 189.  
 — a Bugiano 317.  
 — S. Dalmazzo 111.  
 — San Donnino 253.  
 — Lavezzaro 157.  
 — S. Martino 75.  
 — a Mozzano 316.  
 — Panigale 294.  
 — Sesia 160.  
 — Ticino 157.  
 — di Val Sugana 48.  
 — Vercelli 75.  
 — Vico 139.  
 Borgoforte 194.  
 Borgomanero 76.  
 Borgone 24.  
 Borigli, the 103.  
 Bormida, the 78. 80.  
 Bormio 42.  
 Borroean Islands, the 155.  
 Bosaro 265.  
 Boscolungo 295.  
 Bossèa, Grotto of 80.  
 Botsch, the 53.
- Botticelli, Alessandro lii. 331. 362.  
 Bourg 21.  
 Bourget, Lac du 22.  
 Bourgoigne, Canal de 2.  
 Bouzoise, the 4.  
 Bozen 46.  
 Bozzolo 167.  
 Brà 80.  
 Bracco 114.  
 Bramante xlvii. 120.  
 Brandizzo 75.  
 Brando 402.  
 Branzoli 46.  
 Braulio, the 42.  
 Baus, Col di 110.  
 Brè 150. 179.  
 —, Monte 149.  
 Bregaglia, Val 36.  
 Breggia 139.  
 Breglio 111.  
 Bregni, the 211.  
 Breitenstein 51.  
 Brenner 44.  
 Brennerbad 44.  
 Brennersee, the 44.  
 Brenno, the 32.  
 Breno 176.  
 Brenta, the 48. 49. 198.  
 Brescia 169.  
 Brescia-Cremoua-Pavia 164.  
 — -Tirano 174.  
 Bressana 165.  
 Bressanone 45.  
 Bresse, the 21.  
 Briançon 24. 72.  
 Brianza, the 136.  
 Briccione 159.  
 Brieg 25.  
 Brienno 139.  
 Briona 160.  
 Brione, Monte 179.  
 Briosco (And. Riccio) xlvii. 1.  
 Brissago 153.  
 Bristenstock, the 29.  
 Brixen 45.  
 Brixener Klause, the 45.  
 Brixia 169.  
 Broni 77.  
 Bronzino, Angelo lvii. 331.  
 Broteaux, Les 6.  
 Brou, Church of 22.  
 Brouis, Col di 110.  
 Brozzi 302.  
 Bruck 52.  
 Brühl, the 50.  
 Brunato 139.  
 Brunelleschi, or Brunellesco xlv. 330. 348.  
 Brunn 50.



- Brunna 29.  
 Bruno 80.  
 Bruoy 1.  
 Buco di Vela 48.  
*Buffalmacco* 304.  
 Bufalora, the 38.  
 Buochs 29.  
 —, Lake of 29.  
 Buon Consiglio, Castle 37.  
*Buonconsiglio, Giuv.* 196.  
*Buonvicino, Aless.* 170.  
 Burano 245.  
 Burgeis 41.  
 Burgenstock, the 29.  
 Busalla 79.  
 Bussana 98.  
 Bussoleno 42.  
*Busti*, see *Bambaja*.  
 Busto Arsizio 157.  
 Buttler, the 74.  
 Buttrio 247.  
  
**C**  
 Cabbe 103.  
 Cabbio 38.  
 Cahrole 103.  
 Cadempino 33.  
 Cadenabbia 140.  
 Cadenazzo 32.  
 Cadine 48.  
 Caesarea 285, 293.  
 Caffagiolo 296.  
 Caffaro, the 180.  
 Cairo 78.  
 Calamandran 80.  
 Calanca, Val 38.  
 Calanda, the 34.  
 Calcababbio 165.  
 Calcaccia, the 31.  
 Calci, Valle dei 311.  
 Calde 153.  
 Calderara, Villa 144  
 Caldiero 195.  
 Caldonazzo 48.  
*Calendario, Fl.* 211.  
 Calenzana 402.  
 Calenzano 323.  
*Calviari*, see *Ferouse*.  
 Calliano 49.  
 Calolzio 135.  
 Callignaga 76.  
 Caluso 72.  
 Calvaggione, Mte. 147.  
 Calvi 402.  
 Calvo, Monte 106.  
 Cama 38.  
 Camaldoli 392.  
 Camargne, the 16.  
 Cambiano 77.  
*Cambiano, Luca* 85.  
*Cambio, Arnolfo del* 330.  
 Camerlata 135.  
 Camignone 174.  
 Camnago 135, 137.  
 Camoghè, Monte 33.  
 Camogli 113.  
 Canonica, Val 167.  
*Campagna, Girol.* 211.  
 Campaldino 391.  
 Campi 179.  
 Campo (Lake of Como) 140.  
 — -Dolcino 36.  
 — -Formio 247.  
 Campola, the 255.  
 Campoloro 399.  
 Camporciero, Val di 73.  
 Camporosso 103.  
 Canaria Valley, the 31.  
*Canale, Antonio* 212.  
*Canaleto* 212.  
 Candelo 75.  
 Canelli 180.  
 Cannèro 153.  
 Cannes 20.  
 Cannet 20.  
 Canobbio 153.  
 Canonica, La 398.  
 Canossa 255.  
 Canova 34.  
 Cantalupo 78, 80.  
 St. Canzian 54.  
 Canzo 137.  
 —, Corni di 137.  
 Caorso 166.  
 Capo Corso 402.  
 — S. Croce 98.  
 — d'Istria 58.  
 — Martino 103.  
 — delle Mele 98.  
 — Nero 100.  
 — Vecchio 399.  
 — Verde 98.  
 — Vico 136.  
 Capo di Ponte (near Bel-  
 luno) 246.  
 — (Val Canonica) 176.  
 Capolago 147.  
*Cappuccino, Il* 85.  
 Capraja 301.  
 Caprese 393.  
 Caprino, Monte 150.  
*Caracci, Agostino* lxi.  
 272, 281.  
 —, *Annibale* lxi. 272, 281.  
 —, *Lodovico* 272, 281.  
 Carate 139.  
 Caravaggio 165.  
*Caravaggio, Michael An-  
 gelo da* lxi. 165.  
*Caravaggio, Polidoro*  
 lviii.  
*Cardi, Luigi*, see *Cigoli*.  
 Carelli, Monte 296.  
 Careggi, Villa 387.  
 Carema 72.  
 Careno 140.  
 Carignano 79.  
 Carlo, Mte. 103.  
 Carlotta, Villa 140.  
 Carmagnola 79.  
 Carmelo, Monte 97.  
 Carnian Alps, the 54.  
 Carona 149.  
*Caroto, Gianfr.* lix.  
*Carpaccio, Vittore* 212, 224.  
 Carpentras 9.  
 Carpi 195.  
 Carrara 115.  
 Carrù 80.  
 Carso, the 54.  
 Casalbuttano 165.  
 Casale 75, 78.  
 Casalecchio 294.  
 Casaleto 165.  
 Casalpusterlengo 164, 251.  
 Casarsa 247.  
 Casarza 114.  
 Casciago 146.  
 Cascina 301.  
 Castino, Valley 392.  
 Castino 136.  
 Casneda 153.  
 Casola 255.  
 Cassano 137, 167.  
 St. Cassien 21.  
 Cassina 147.  
 Cassone 180.  
 Castagnola 151.  
 Castagnole 78, 80.  
 Castagnovizza 247.  
 Casteggio 77.  
 Castel Arquato 253.  
 — Bolognese 285.  
 — S. Giovanni 77.  
 — Guelfo 253.  
 — Maggiore 265.  
 — S. Niccolò 392.  
 — S. Pietro 284.  
 Castlefranco (Romagna)  
 255.  
 — (Venetia) 49.  
 Castellaro 103, 164.  
 Castellatsch 35.  
 Castellone 165.  
 Castellotto 180.  
 Castello near Florence  
 323.  
 — near Lecco 144.  
 — (Lago di Garda) 180.  
 Castellucchio 167.  
 Castelnuovo near Ales-  
 sandria 80.  
 — near Peschiera 169.  
 Castiglione d'Olona 146.  
 — (near Sospello) 103, 110.

- Castiglione, Bened.* 85.  
 Castione 32.  
*Catena, Vinc.* 212.  
 Catini, Monte 317.  
 Cattajo, Castle 263.  
 Cava 164.  
 Cava-Manara 165.  
 Cava-Tigozzi 164.  
 Cavallermaggiore 80.  
     112.  
 Cavedine, Val 48.  
 Cavo Tassone, Canal 265.  
 Cazzanore 136.  
 Cecina 178.  
 Celle 97. 294.  
 Cemenelum 108.  
 Ceneda 246.  
 Cenère, Monte 33.  
 Cenis, Mont 24.  
     —, Tunnel 23.  
 Centa, the 98.  
 Centallo 112.  
 Cento 265.  
 Centre, the Canal du 4.  
 Ceppina 43.  
 Ceraino 50.  
 Ceresio, the Lago 147.  
 Ceriale 97.  
 Ceriana 100.  
 Cernobbio 139.  
 Cernusco 134.  
 Cerro 78.  
 Certosa di Pavia 161.  
     — di Pisa 311.  
     — near Bologna 283.  
     — di Val d'Enza 385.  
     — di Val Pésio 111.  
 Ceruso, the 97.  
 Cervara 113.  
 Cervia 294.  
 Cervione 398.  
 Cervo 98.  
 Cesanne 24. 72.  
 Cesenatico 294.  
 Cesson 1.  
 Cetica 391.  
 Cette, Le 391.  
 Ceva 80.  
 Cézy 2.  
 Chablis 2.  
 Chagny 4.  
 Challant, Val de 73.  
 Châlon-sur-Saône 4.  
 St. Chamas 16.  
 Chambave 73.  
 Chambéry 23.  
 Chambre, La 23.  
 Chamousset 23.  
 Champigny 2.  
 Champorcher, Val 73.  
 Charenton 1.  
 Château Neuf (Nice) 109.
- Châtillon (near Aosta) 73.  
     — (Savoy) 22.  
     — (near Sospello) 110.  
 Châtillon-sur-Seine 2.  
 Chaumont 2. 24.  
 Chauve, Mont 106.  
 Cherasco 80.  
 Chevalier, Mont 20.  
 Chiana, Val di 393.  
 Chiasso 146.  
 Chiavari 113.  
 Chiavenna 36.  
     —, the 166.  
 Chiese, the 169. 179.  
 Chignin, Chât. 23.  
 Chignolo 164.  
 Chioggia 245.  
 Chiomonte 24.  
 Chiuro 43.  
 Chiusi 395.  
 Chivasso 75.  
 Chur 33.  
 Churburg, the 41.  
*Cigoli* 331.  
 Cilli 35.  
 Cima 151.  
     —, Villa 139.  
*Cima da Conegliano* 125.  
     212. 246.  
*Cimabue* xxxix. 304. 330.  
 Cimella or  
 Cimiès 108.  
 Cimone 295.  
 Cimone, Monte 263. 391.  
*Cione, Andr.*, see *Orcagna*.  
 Ciotat, La 19.  
 Ciraun 35.  
 Cisano 144. 180.  
 Cismone, the 49.  
 Cittadella 49.  
 Cittiglio 146.  
 Civate 137.  
 Civenna 137.  
 Civasco 160.  
 Cividale 247.  
 Civate 176.  
*Civitali, Matteo* 1.  
 Claro 32.  
 Clastidium 77.  
 Claudia Celleia 53.  
 Clavenna 36.  
 Clusium Novum 393.  
 Clusone, the 72.  
 Co di Mozzo 400.  
 Coccaglio 169.  
 Cocquio 146.  
 Codogno 164. 165. 251.  
 Codroipo 247.  
 Cogoletto 97.  
 Coire 33.  
 Coire-Bellinzona 37.  
     — -Colico 33.
- Coiro 158.  
 Colico 37. 144.  
 Colla, La 100.  
 Colle-Campiglio 145.  
 Collegno 24.  
 Collonges 22.  
 Colma, Col di 160.  
 Colobiano, Villa 139.  
 Cologna 179.  
 S. Colombano, Monte 42.  
 Colombier, the 22.  
 Comabbio, Lago di 146.  
 Comacina, Isola 140.  
 Combes-la-Ville 1.  
 Comerio 146.  
 Como 135.  
     —, the Lake of 137.  
 Compiobbi 390.  
 Condino 179.  
 Condove 24.  
 Conegliano 246.  
*Conegliano*, see *Cima*.  
 Coni 111.  
 Consuma Pass, the 392.  
 Conzei, Val 179.  
 Coppa, the 77.  
 Corbè, Castle 32.  
 Corenno 143.  
 Cormons 247.  
 Cornaggia, Villa 139.  
 Corniale 58.  
 Corniche, Route de la  
     95. 103.  
 Corniglia 114.  
 Cornigliano 96.  
 Cornio, Col di 111.  
 Corno, the 247.  
 Correggio 254.  
*Correggio (Ant. Allegri)*  
     lix. 254. 256.  
 Corsaglia, Valle di 80.  
 Corsalone, the 392.  
 Corsica 394.  
 Corsico 157.  
 Corso, Capo 402.  
 Corte 400.  
 Cortenedolo 176.  
 Cortèno 176.  
 Corteolona 164.  
 Corticella 265.  
 St. Cosme 4.  
*Costa, Lorenzo* 266.  
 Costigliole 80.  
 Cotaiga, Monte 150.  
 Côte d'Or, the 3.  
 Côte Rôtie, La 8.  
 Cottian Alps, the 62.  
 Courmayeur 74.  
 Covelo 49.  
 Cavigliajo 295.  
 Cramosina, La 32.  
 Crau, the Plain of 16.

- Credi, Lorenzo di* 65.  
 331. 362. 376.  
 Crêdo, Tunnel du 22.  
 Crema 165.  
 Cremeo 38.  
 Cremia 143.  
 Cremona 165.  
 Cremona-Brescia 164.  
 — -Milan 165.  
 — -Pavia 164.  
 Cresciano 32.  
 Cresogno 151.  
 Crespano 49.  
 Crestola, Monte 116.  
 Creuzot 4.  
 Crevola 27.  
 Cribiasca, the 31.  
 Cristallo, Monte 41.  
*Crivelli, Carlo* lii. 125. 211.  
 Croce (near Menaggio) 150.  
 — (near Belluno) 246.  
 —, Capo della 78.  
 Crocione, Monte 150.  
 Croisette, Cap de la 21.  
 Croix Rousse, La 5.  
*Cronaca* 330.  
 Crostolo, the 253.  
 Cucciago 135.  
 Cuccione, Castello di 159.  
 Cugnasco 32.  
 Culoz 22.  
 Cuneo 111.  
 Curone, the 77.  
 —, Ponte 77.  
 Curver, Piz 34.  
 Custozza 90.  
 Cuvio, Val 146.  
 Cuzzago 27.  
  
 S. Dalmazzo 111.  
 —, Abbey 111.  
 S. Damiano 77.  
 Daunafirn, the 30.  
*Daniela da Volterra* lvi.  
 Darfo 175.  
 Dazio Grande 31.  
 Dego 78.  
 Deiva 114.  
 Delio, Lago 153.  
 Bertona 76.  
 Dervio 143.  
 Desago 150.  
 Desenzano 169. 177.  
*Desiderio da Settignano* xlix.  
 Desio 135.  
 Devil's Bridge, the 30.  
 Diana 78.  
 —, Lake of 398.  
 Diano Castello 98.  
 — Marina 98.  
 Diavolo, Ponte del 43.  
 Diecimo 316.  
 Dijon 3.  
 S. Dionigio, Proumont. 144.  
 Disgrazia, Monte della 44.  
 Dissântis 34.  
 Divazza 54.  
 Divôria, the 26.  
 Divio 3.  
 Docce Basse 317.  
 Doccia, La, Villa 387.  
 Doire, the 72. 73. etc.  
 Dolce Acqua 101.  
*Dolci, Carlo* 331.  
 Dôle 3.  
 Dolo 198.  
 Domaso 144.  
 Domegliara 50.  
*Domenichino (Dom. Zampieri)* lxi. 272. 281.  
 Domleschg 34.  
 Domo d'Ossola 27.  
 Donat 35.  
*Donatello* xlix. 330.  
 Dongo 143.  
 Donnaz 93.  
 S. Donnino 302.  
 Dora Baltea, the 72. 73. etc.  
 — Riparia, the 24. 62. etc.  
 Dorio 143.  
 Dos Trento 48.  
*Dosso Dossi* 266.  
 Dossobuono 190.  
 Doubs, the 4.  
 Draguignan 19.  
 Drappo 110.  
 Drau, the 53.  
 Drena, Castello di 48.  
 Drò 48.  
 Druentia 11.  
*Duccio* xxxix.  
 Duggia, Val 160.  
 Dinno 248.  
 Durance, the 11. 72.  
  
 Ecluse, Fort de l' 22.  
 Edolo 176.  
 Eggenthal, the 46.  
 Egna 46.  
 St. Egyden 51.  
 Ehrenhausen 53.  
 Einshorn, the 35.  
 Eisak, the 44. 46.  
 Ellero, the 80.  
 Ema, the 385.  
 Emilia, the 249.  
 Empoli 301.  
 Ems 34.  
 Enguiso 179.  
 Enza, the 253.  
 Epierre 23.  
 Eporedia 72.  
 Era, the 301.  
 Erba 137.  
 Ersa 402.  
 Ermitage, the 8.  
 Erstfeld 29.  
 Escarène 110.  
 Esino, Val d' 142.  
 Este 264.  
 —, Villa d' 139.  
 Estérel, Mont d' 20.  
 Etsch, see Adige.  
 Euganean Mts., the 263.  
 Exilles 24.  
 Eza 103. 104.  
  
**Fabrizio, Gentile da** lii.  
 125. 362.  
 Fiesule 88.  
 Faido 31.  
*Falconetto, Giov. Maria* xlvii.  
 Falicon 109.  
 Falterona, Monte 393.  
 Fantiscritti 116.  
 Fara 160.  
 Fardun, Castle 35.  
 Farioglio 80.  
 Fariolo 27. 154.  
 Farnoli 316.  
 Felixdorf 51.  
 Felizzano 78.  
 Felsberg 31.  
 Felsina 271.  
 Fenestrelle 72.  
 Fenis, Castle 74.  
*Ferramola, Floriano* 170.  
 Ferrara 265.  
 — Ariosto, House of 269.  
 —, Statue of 269.  
 Ateneo Civico 268.  
 S. Benedetto 269.  
 Castello 266.  
 Cathedral 267.  
 S. Cristoforo 269.  
 S. Francesco 267.  
 S. Giorgio 267. 269.  
 Hospital of St. Anna 269.  
 S. Maria in Vado 268.  
 Pal. Bevilacqua 269.  
 — Costabili 268.  
 — de' Diamanti 268.  
 — del Municipio 267.  
 — Prosperi (de' Leoni) 268.  
 — della Ragione 267.  
 — Roverella 269.  
 — Schifanoja 268.  
 — Zatti 269.  
 S. Paolo 267.  
 Picture Gallery 268.  
 Savonarola, Monum. of 266.

- Ferrara:**  
 Studio Pubblico 267.  
 Tasso, Prison of 269.  
 University 267.  
*Ferrari, Gaudenzio* 65.  
 130.  
**Ferrera** 164.  
 — Valley, the 35.  
 Fersina, the 48.  
 Fidentia Julia 253.  
 Fiesole 388.  
 Fiesso 31.  
 Figino 149.  
 Filigare 295.  
 Finale 97.  
 Finalmarina 97.  
 Finalpia 97.  
 Finstermunz 40.  
 Fiora 29.  
 S. Fiorenzo 402.  
 Fiorenzuola 253.  
 Firenze 328.  
 Fiumalbo 263.  
 Fiume 54.  
 Fiume Latte 142.  
 Flamboin 2.  
**Florence** 323.  
 Accademia delle Belle  
 Arti 361.  
 — della Crusca 361.  
 S. Ambrogio 351.  
 SS. Annunziata 359.  
 Archives 344.  
 Arrival 323.  
 Artists 326.  
 Badia 345.  
 — S. Bartolommeo 386.  
 — di Fiesole 349.  
 Bank 350.  
 Bankers 326.  
 Bargello 352.  
 Baths 326.  
 Battistero 346.  
 Bazaar 346.  
 Beer 325.  
 Bello Sguardo 386.  
 Biblioteca Laurenziana  
 367.  
 — Marcelliana 365.  
 — Nazionale 344.  
 — Riccardiana 365.  
 Bigallo 346.  
 Boboli Garden, the 381.  
 Booksellers 326.  
 Borgo degli Albizzi  
 355.  
 — Ognissanti 370.  
 Boulevards 332.  
 Brancacci Chapel 374.  
 Bridges 332.  
 Cabs 325.  
 Cafés 325.
- Florence:**  
 Campanile 349.  
 Canoury 350.  
 Cappella de' Pazzi 357.  
 — degli Spagnuoli 369.  
 Carmine, Mad. del 374.  
 Cascine 387.  
 Casino Mediceo 364.  
 Cathedral 347.  
 Certosa di Val d'Ema  
 385.  
 Chemists 325.  
 Colonna di S. Zanobi  
 347.  
 Confectioners 325.  
 Consulates 325.  
 Cosmo's I. Statue 333.  
 S. Croce 355.  
 Dante's House 345.  
 Dante's Statue 355.  
 Demidoff, Monum. of  
 382.  
 Doecia, La 387.  
 S. Domenico di Fiesole  
 388.  
 S. Egidio 351.  
 Egyptian Museum 372.  
 English Church 326.  
 Environs 382.  
 Etruscan Museum 372.  
 Exhibition of Art 351.  
 Fiesole 388.  
 S. Firenze 352.  
 Fortezza di Belvedere  
 381.  
 Foundling Hospital  
 359.  
 S. Francesco di Paola  
 386.  
 Galleria Buonarroti  
 358.  
 — Corsini 370.  
 — Panciatichi 365.  
 — Pitti 375.  
 — Strozzi 372.  
 — Torrigiani 382.  
 — degli Uffizi 331.  
 Galileo, House of 351.  
 Gates 331.  
 Ghetto 346.  
 S. Giovanni Battista  
 346.  
 S. Giovannino degli  
 Scolopi 365.  
 History 329.  
 — of Art 330.  
 Hotels 323.  
 House of Bianca Ca-  
 pello 373.  
 — of Benvenuto Cellini  
 351.  
 — of Dante 345.
- Florence:**  
 House of Galileo 351.  
 382.  
 — — Macchiavelli 375.  
 — — Michael Angelo  
 358.  
 Lieux d'Aisance 326.  
 Loggia dei Lanzi 333.  
 — del Grano 344.  
 — di S. Paolo 368.  
 — del Pesce 346.  
 S. Lorenzo 366.  
 S. Lucia 382.  
 Lung' Arno 332.  
 Madonna del Carmine  
 374.  
 S. Marco 360.  
 —, Monastery 360.  
 S. Margherita a Mon-  
 tici 385.  
 S. Maria del Fiore 347.  
 — degli Innocenti 359.  
 — Maddalena de' Pazzi  
 351.  
 — Novella 368.  
 — Nuova 351.  
 Marzocco, the 333.  
 Medici, Monuments of  
 the 367.  
 Mercato Centrale 368  
 — Nuovo 345.  
 — Vecchio 346.  
 S. Miniato 384.  
 Misericordia 350.  
 Monte Oliveto 386.  
 Mosaics, Manufact. of  
 364.  
 Museo di Storia Natu-  
 rale 381.  
 — di S. Marco 360.  
 — Nazionale 352.  
 S. Niccolò 382.  
 Observatory 382.  
 Ognissanti 370.  
 Omnibuses 325.  
 S. Onofrio 372.  
 Opera del Duomo 350.  
 Or S. Michele 345.  
 Oratorio S. Carlo Bor-  
 romeo 345.  
 — S. Pancrazio 372.  
 — dei Rucellai 372.  
 Ospedale S. Maria  
 Nuova 351.  
 Palazzo Alberti 358.  
 — Albizzi 355.  
 — Altoviti (Visacci)  
 355.  
 — dell' Antella 355.  
 — Bartolini-Salimbeni  
 373.  
 — Berte 358.

- Florence  
 Palazzo del Borgo 355.  
 — dei Canonici 350.  
 — Corsi 372.  
 — Corsini 370.  
 — Covoni 365.  
 — Dufour-Berte 374.  
 — Fontebuoni 371.  
 — Gianfigliuzzi 371.  
 — Gondi 352.  
 — Guadagni 374.  
 — Guicciardini 375.  
 — Larderel 372.  
 — Lavisch 334.  
 — Manelli 358.  
 — Medici 364.  
 — Nencini 364.  
 — non finito 355.  
 — Panciatichi 365.  
 — — Ximenes 351.  
 — Pandolfini 364.  
 — Pestellini 365.  
 — Pitti 375.  
 — del Potestà 352.  
 — Poniatowski 365.  
 — Quaratesi 355.  
 — Riccardi 364.  
 — Riccardi (Guadagni) 350.  
 — Rucellai 372.  
 — Serristori 355.  
 — Spini 371.  
 — Strozzi 372.  
 — Tornabuoni 372.  
 — Torrigiani 382.  
 — Uguccioni 334.  
 — Vecchio 332.  
 Pensions 324.  
 Physicians 325.  
 Photographs 326.  
 Piazza SS. Annunziata 358.  
 — d'Azeglio 351.  
 — S. Croce 355.  
 — del Duomo 346.  
 — S. Lorenzo 365.  
 — Manin 370.  
 — S. Marco 360.  
 — S. Maria Novella 368.  
 — del Mercato 345.  
 — della Signoria 332.  
 — S. Trinità 372.  
 Piazzale Michelangelo 383.  
 Poggio Imperiale 384.  
 Ponte alla Carraja 332.  
 — alle Grazie 332. 382.  
 — S. Trinità 332. 373.  
 — Vecchio 332. 375.  
 Porta S. Gallo 387.  
 Portico degli Uffizi 334.
- Florence:  
 Post Office 325. 334.  
 Private Lodgings 324.  
 Railway Station 370.  
 Rajah of Holapore, Monum. of 387.  
 Reading Rooms 326.  
 Recollets, Cloisters of the 361.  
 Restaurants 324.  
 Sagrestia Nuova 366.  
 S. Salvatore del Monte 383.  
 S. Salvi 389.  
 Sasso di Dante 350.  
 Scalzi, Chiostro dei 364.  
 Schools 326.  
 Servi di Maria 359.  
 Shops 326.  
 Spagnuoli, Capp. degli 369.  
 Spedale degli Innocenti 359.  
 — di S. Maria Nuova 351.  
 S. Spirito 373.  
 S. Stefano 344.  
 Telegraph Office 325.  
 Theatres 326.  
 Tivoli 383.  
 Torre del Gallo 384.  
 Treasury 380.  
 Tribuna del Galileo 328.  
 S. Trinità 371.  
 Uffizi, Galleria degli 334.  
 Viale dei Colli 383.  
 Villa degli Albizzi 386.  
 — delle Bugie 385.  
 — Careggi 387.  
 — Demidoff 387.  
 — della Doccia 387.  
 — of Galileo 385.  
 — Guicciardini 385.  
 — Mozzi 388.  
 — Palmieri 388.  
 — Petraja 387.  
 — Poggio Imperiale 384.  
 — Quarto 387.  
 Wines 325.
- Florence-Bologna 294-296.  
 — Empoli-Pisa-Leghorn 302, 301.  
 — Pistoja-Lucca-Pisa 323-312.  
 — Pontassieve (Arezzo) 390-93.  
 St. Florentin 2.  
 Fiorentina, tower 38.
- Fluelen 29.  
 Fogliardi 145.  
 Fons Aponi 263.  
 Fontainebleau 1.  
 Fontaines 4.  
 Fontana 111.  
 Fontana Fredda 253.  
 Fontebuona 296.  
 Formigine 263.  
 Fornace 150.  
 Fornasette 150.  
 Forum Alieni 265.  
 — Cornelii 284.  
 — Gallorum 255.  
 — Julii 19. 247.  
 — Licini 137.  
 Fossano 112.  
 Fourneaux 23.  
 Fourvières 6.  
 Foux, La 13.  
 Frabosa 80.  
 Fraele, Val 42.  
 Fragenstein, Castle 39.  
 Framura 114.  
*Francesca, Piero della* H. 266.  
 S. Francesco d'Albaro 113.  
*Francia, Franc.* 272. 281.  
 —, *Giac.* 272.  
*Franciabigio* 331.  
 Franzdorf 54.  
 Franzensfeste 45.  
 Franzenshöhe 41.  
 Frati, Isola dei 178.  
 Freienfeld 45.  
 Fréjus 19.  
 —, Col de 23.  
 Fressinone, the 26.  
 Friaul 247.  
 Frodolfo, the 43.  
 Frohnleiten 52.  
 Frolichsburg 41.  
 Fröschnitz, the 51.  
 Frugarölo 78.  
 Fuentes, Castle 37.  
 Fugazze Pass, the 49.  
 Fumajolo, the 393.  
 Fuochi, the 295.  
*Furini, Franc.* 331.  
 Fürstenau, Castle 34.  
 Fürstenburg, Castle 41.  
 Furva, Val 42.  
 Futa, La 295.
- Gaddi, Agnolo* 330.  
 —, *Taddeo* 330.  
 Gaggi, Villa, see Anton-  
 gina.  
 Gaggiano 157.  
 Gaggio 385.  
 Galbiati, Villa 139.

- Galbigo, Monte 151.  
 Gallarate 157.  
 Galleno 176.  
 Gallia Cisalpina 117.  
 Galliera 265.  
 Gallinara, Isola 98.  
 Gallivaggio 36.  
 Galluzzo 386.  
 Gandria 151.  
 Ganterthal, the 26.  
 Gard, Pont du 13.  
 Garda 180.  
 —, Isola di 178.  
 —, Lake of 177.  
 Gardone 178.  
 Gargnano 178.  
 Garlate, Lago di 144.  
*Garofalo* Iviii. 266.  
 Garza, Val 180.  
 Garzeno 143.  
 Gavardo 178.  
 Gavirate 145. 146.  
 Gazza, Monte 48.  
 Gazzada 145.  
 Gazzo 167.  
 Gemonio 146.  
 Generoso, Monte 147.  
 Geneva 5. 22.  
 Genève, Mont 24. 72.  
 Genoa 82.  
 Accademia delle Belle  
 Arti 88.  
 Acqua Sola 94.  
 Albergo dei Poveri 95.  
 S. Ambrogio 87.  
 SS. Annunziata 91.  
 Banca Nazionale 86.  
 — di S. Giorgio 85.  
 Baths 83.  
 Begato, Fort 84.  
 Biblioteca Civica 88.  
 Campo Santo 95.  
 Castellaccio 84.  
 Consulates 83.  
 Darsena 86.  
 Dogana 85.  
 Exchange 86.  
 Fortifications 83.  
 Harbour 85.  
 History 84.  
 — of Art 85.  
 Istituto Tecnico 91.  
 Lighthouse 85.  
 Loggia de' Banchi 86.  
 S. Lorenzo 86.  
 S. Maria in Carignano  
 88.  
 — di Castello 86.  
 S. Matteo 88.  
 Moto Nuovo and Vec-  
 chio 85.  
 Municipio 90.
- Genoa:  
 Palazzo Adorno 90.  
 — Balbi 91.  
 — Balbi-Senarega 92.  
 — Bianco 91.  
 — Brignole-Sale 90.  
 — Cambiaso 89.  
 — Carega 89.  
 — della Casa 89.  
 — Cataldi 89.  
 — Cattaneo 86.  
 — Centurioni 91.  
 — Deferrari 88.  
 — Doria 88.  
 — Doria (Giorgio) 90.  
 — Ducale 87.  
 — Durazzo 93.  
 — Faraggiana 93.  
 — Gambaro 89.  
 — Gropallo 95.  
 — Lomellini 91.  
 — Marcello Durazzo  
 91.  
 — del Municipio 90.  
 — Pallavicini 89.  
 — Parodi 89.  
 — della Prefettura 87.  
 — dei Principi Doria  
 93.  
 — Reale 93.  
 — Rosso 90.  
 — della Scala 91.  
 — dello Scoglietto 94.  
 — Serra 90.  
 — Spinola 89.  
 Passo Nuovo 94.  
 Peirano, Gallery 91.  
 Piazza Acquaverde 93.  
 — Deferrari 88.  
 — Fontane Morose 89.  
 — Vacchero 86.  
 Ponte Carignano 88.  
 Porto Franco 85.  
 Post Office 83.  
 Prefettura 87.  
 Rail. Stations 82.  
 S. Siro 86.  
 Sperone, Fort 84.  
 Statue of Cavour 86.  
 — of Columbus 93.  
 S. Stefano 89.  
 Teatro Carlo Felice 83.  
 88.  
 Terrazzo di Marmo 86.  
 Town Hall 90.  
 University 92.  
 Via Balbi 91.  
 — di Circonvallazione  
 95.  
 — Nuova 89.  
 — Nuovissima 91.  
 — degli Orefici 86.
- Genoa:  
 Villa Mylius 88.  
 — Negro 94.  
 — Pallavicini 96.  
 Zecca 91.  
 Genoa-Leghorn (by sea)  
 299.  
 — Milan 161-65.  
 — Nice 95-104.  
 — Spezia-Pisa 112-16.  
 — Turin 77-80.  
 St. George des Hurlières  
 23.  
 Gère, the 8.  
 St Germain, Chât. 22. 73.  
 S. Germano 75.  
 Germignaga 153.  
 Gersau 29.  
 Geschenen 30.  
 — Reuss, the 30.  
 Gesso, the 111.  
*Ghiberti, Lor.* xlviii. 330.  
 347.  
 Ghiffa 153.  
*Ghirlandajo, Dom.* li.  
 331. 362. 369. 375.  
 —, *Rid.* lvii. 331.  
 S. Giacomo (Bernardino)  
 38.  
 — (near Chiavenna) 36.  
 Giandola 111.  
 Giarole 75.  
 Gignese 158.  
 Ginistrella, Monte 160.  
*Giocondo, Fra* xlv. 183.  
 Gionnero, Montes. Monte  
 Generoso.  
 S. Giorgio 253. 265.  
*Giorgione* lix. 212. 224.  
 376.  
 Giornico 32.  
*Giotto* xxxix. 202. 330.  
 352. 356. 362.  
*Giottino* 330.  
 S. Giovanni the Adria-  
 tic 58. 248.  
 — (Lake of Garda) 180.  
 — (near Nice) 110.  
 —, Castel 77.  
 —, Island (Lake of Como)  
 140.  
 — (Lago Maggiore)  
 154.  
*Giovanni da Murano* 211.  
 S. Giovanni Manzano 247.  
 Giovi 393.  
 —, Galleria dei 79.  
 Gittana 143.  
 Giubiasco 32.  
 Giudicaria 179.  
 S. Ginletta 77.  
 Giulia, Villa 142.

- S. Giuliano 78.  
—, Monte 312.  
S. Giuliano, Bagni di 312.  
S. Giulio, Isola 159.  
Giunella, Monte 178.  
S. Giuseppe, Lago di 72.  
S. Giuseppe di Cairo 78.  
80.  
Glanum 12.  
Gloggnitz 51.  
Glurns 40.  
Gmund 46.  
*Gobbo, il (Cristofano Solari)* 1.  
Gobetta, Cime di 42.  
Godo 285.  
Golfe Jouan 21.  
Golo, the 398. 399.  
Golzano 164.  
Gomagoi 41.  
Gombo, Il 311.  
Gondo 26.  
Gonfolina, the 301.  
Gonzaga 194.  
Gorbio 103.  
Gordola 33.  
Gorgie, Le 24.  
Gorzia 247.  
Gorlago 168.  
Görz 247.  
Gorzone Canal, the 264.  
Göschönen 30.  
Gossensas 45.  
Gösting 52.  
Gotschakogel, the 51.  
St. Gotthard, the 31.  
St. Gotthard Tunnel 28.  
30.  
Gozzano 76.  
*Gozzoli, Benozzo* li. 304.  
307. 331.  
Gradisca 248.  
Graian Alps, the 74.  
Graisivaudan, Valley of 23.  
Grand Paradis, the 71. 72.  
Grappa, Monte 49.  
Grasse 21.  
Grasstein 45.  
Gratwejn 52.  
Graz 52.  
Gravedona 143.  
Gravellona 27.  
Gravone, the 399.  
Grenoble 8.  
Greve, the 385.  
Gries 44. 46.  
Grigna, Monte 143.  
Grignano 55.  
Grigno 48.  
Grimaldi 101.  
Grödenerbach, the 46.  
Grono 38.  
Gropello 145.  
Grosio 43.  
Grosotto 43.  
Grotta, La 179.  
*Gruamons* 318.  
Grumello 168.  
Gschnitzthal, the 44.  
Guardia, Monte 283.  
Guastalla 194.  
Guelfo, Castel 253.  
*Guercino (Barbieri)* lxi. 265.  
Guglielmo, Monte 175.  
Guidizzolo 169.  
Guillotiére, La 5. 6.  
Guinzano 161.  
Gumpoldskirchen 50.  
Guntramsdorf 50.  
**H**  
Haimingen 39.  
Haute-Combe, Abbey 23.  
Heidersee, the 40.  
Heinzenberg, the 34.  
Héricourt 4.  
Hetzendorf 50.  
Hinterrhein 37.  
Hirli, the 35.  
Hoch-Finstermünz 40.  
Hoch-Realt 35.  
Hohenems, Castle 34.  
Hohen-Rhätien, Castle 34.  
St. Honorat 21.  
Hôpitaux, Les 22.  
Hospenthal 31.  
St. Hospice 110.  
Ilrastnig 54.  
Hyeres 19.  
—, the Islands of 19.  
Idria 54.  
Idro 180.  
—, Lago d' 180.  
Il, Château d' 18.  
S. Ilario 253.  
Imola 284.  
*Imola, Innocenzo da* 272.  
281. 285.  
Impero, the 98.  
Imst 39.  
Incino 136.  
Incisa 80.  
Indrio, the 247.  
Inn, the 39. 40.  
Innsbruck 39.  
Intelvi Valley, the 140.  
Intra 154.  
Introbio 143.  
Intschi 30.  
Inverigo 136.  
Iria 77.  
Isel, hill 44.  
Iselle 26.  
Iseo 174.  
—, Lago d' 175.  
Isera 49.  
Isère, the 8. 23.  
Isola 36. 58.  
— Bella 155.  
— S. Biagio 178.  
— del Cantone 79.  
— dei Frati 178.  
— S. Giovanni (Lago Magg.) 154.  
— Madre 155.  
— Rossa 402.  
— dei Pescatori or — Superiore 155.  
Isole Sanguinarie 394.  
Isoletto, Rock 180.  
Isonzo, the 247.  
Ivano, Château 48.  
Ivrea 72.  
Ivry 1.  
**J**  
Jadera 67.  
St. Jean 110.  
St. Jean de Maurienne 23.  
Joigny 2.  
S. Jorio, Passo 143.  
St. Joseph, Monastery 53.  
Jouan, Golfe 20.  
Joviniacum 2.  
Judendorf 52.  
Julian Alps, the 54. 248.  
St. Julien-du-Sault 2.  
Jumeaux, the 73.  
Jura, the 22.  
Justinopolis 58.  
Juvalta, Castle 34.  
**K**  
Kainach, the 53.  
Kalkberg, the 36.  
Kalsdorf 53.  
Kalterer 46.  
Kaltwasser Glacier, the 25.  
Kapfenberg 52.  
Kardaun 46.  
Karst, the 54.  
Katz 34.  
Kaunserthal, the 40.  
Kindberg 52.  
Klamm 51.  
Klausen 45.  
Klein-Stübing 52.  
Klus, the 29.  
Kottingbrunn 51.  
Kranichsfeld 53.  
Kressnitz 54.  
Krieglacb 52.  
Kronburg, Ruins 39.

- Kuntersweg, the 46.  
 Kurtatsch 46.  
 Küssnacht (Lake of Lucerne) 29.  
 Laase 54.  
 Labeck, Castle 53.  
 La Chambre 23.  
 La Colla 100.  
 Lacus Benacus 177.  
   — Ceresius 147.  
   — Larius 138.  
   — Sebinius 175.  
   — Verbanus 152.  
 Ladis 40.  
 La Doccia 387.  
 La Foux 13.  
 Lagarina, Val 49.  
 Lagersberg, the 39.  
 Laglio 139.  
 Lagnasco 112.  
 Lago Inferiore 191.  
   — Maggiore 151.  
   — Santo 295.  
   — Superiore 191.  
 La Grotta 179.  
 Lagune, the 212.  
 Laibach 54.  
 Laibach, the 54.  
 Laignuglia 98.  
 Laisse, the 23.  
 Lambro, the 136.  
 Lamone, the 285.  
 La Motta 177.  
 Lancenigo 246.  
 Landeck 40.  
 Landskron, Castle 52.  
 La Nova 178.  
 Lanza, the 145.  
 La Praz 23.  
 Larius, Lacus 138.  
 La Roche 2.  
 La Rotta 301.  
 La Salute 153.  
 Lasnigo 137.  
 Lastra 302.  
 La Tour 72.  
 La Tourette 109.  
 La Trinité Vittorio 110.  
 La Turr, ruined châ. 35.  
 Lavdegg, Castle 40.  
 Lans Pompeia 251.  
 Lavagna 113.  
 Lavedo, Promontory 140.  
 Laveno 153.  
 Lavenone 180.  
 Lavino 255.  
 Lavis 47.  
 Laxenburg 50.  
 S. Lazzaro, near Bologna 284.  
   — near Piacenza 253.
- S. Lazzaro, near Venice 245.  
 Lazise 180.  
 Lebring 53.  
 Leccia, Ponte alta 399.  
 Lecco 144.  
   —, the Lake of 144.  
 Le Creuzot 4.  
 Ledro, Lago di 179.  
   —, Pieve di 179.  
 Ledro Valley, the 179.  
 Leggia 38.  
 Leghorn 299.  
 Legnano 157.  
 Legnolino, Monte 143.  
 Legnone, Monte 143.  
 Leibnitz 53.  
 Leitha Mts., the 51.  
 Leno, the 49.  
 Leuzuno 179.  
 Leobersdorf 51.  
*Leonardo da Vinci* liii.  
   120. 125. 128. 129. 331.  
*Leopardo, Aless.* l. 211.  
 Le Prese 43.  
 Lerici 115.  
 Lérins, Îles 20.  
 Lesa 27. 156.  
 Le Sarchè 48.  
 Les Arcs 19.  
 Lesce 54.  
 Les Marches 23.  
 Le Tezze 48.  
 Leuk 25.  
 Levanna, Monte 71.  
 Lévant, Île du 19.  
 Levante, Riviera di 112.  
 Levanto 114.  
 Leventina, the 31.  
 Levico 48.  
 Leyment 5.  
 Lezzeno 110.  
*Liberale da Verona* 183.  
*Libri, Girol. dai* 184.  
 Libro Aperto 295.  
 Lichtenberg 41.  
 Lichtenegg 52.  
 Liciniformum 136.  
 Lijona 144.  
 Lieusaint 1.  
 Liguria 81.  
 Lima, the 316.  
 Limite 167.  
 Limone (Lake of Garda) 178.  
   — (Col di Tenda) 111.  
 Limonta 144.  
*Lionardo da Vinci*, see *Leonardo*.  
 Lipizza 58.  
*Lippi, Fra Filippo* li. 322.  
   331. 362.
- Lippi, Filippino* li. 331.  
   375.  
 Liro, the 36.  
 L'Isle-sur-le-Doubs 4.  
 L'Isle-sur-Sorgue 11.  
 Litta, Villa 143.  
 Littai 54.  
 Livenza, the 246.  
 Livorno (Piedmont) 75.  
   — (Tuscany) 299.  
 Lizzana 49.  
 Loano 97.  
 Locarno 152.  
 Locate 161.  
 Lodi 251.  
 Lodrone 180.  
 Lœche 25.  
 Lœtschenthal, the 25.  
 Loing, the 2.  
 Loitsch 54.  
*Lombardi, Alf.* 272.  
   —, the 211.  
 Lombardy 117.  
 Lomellina, the 164.  
 Lomello 164.  
 Lonato 169.  
*Longhena* 211.  
 Lonigo 195.  
 Lons-le-Saulnier 4. 5.  
 Loppio, Lake of 179.  
 S. Lorenzo 58. 98.  
 S. Loretto 175.  
 Lostalio 38.  
*Lotto, Lor.* ix. 212. 376.  
 Loveno 142.  
 Lovère 175.  
 Lovero 43.  
 Lucca 312.  
   —, the Baths of 317.  
 Lucendo, Lake of 31.  
 Lucerne 28.  
   —, the Lake of 28.  
 S. Lucia 50. 169.  
 Lucino 145.  
 Lugano 147.  
   —, the Lake of 147.  
 Lugdunum 5.  
 Lugliano 317.  
 Lugo 285.  
 Luinate 146.  
*Lumi, Bern.* liv. 120. 125.  
 Luino 153.  
 Lumino 38.  
 Lumio 402.  
 Luna 115.  
 Luna Nova 115.  
 Lunai Portus 114.  
 Lunga Sardo 398.  
 Lunigiana, La 115.  
 Lurate 145.  
 Luri 402.  
 Luserna, Torre 72.



- Lyons 5.  
Lysbach, the 72.
- Maccagno** 153.  
**Macon** 4.  
**Macra**, the 112.  
**Madatsch Glacier**, the 41.  
**Maddalena**, La 112.  
—, Island 398.  
**Madeleine**, La 110.  
**Maderaner Thal**, the 30.  
**Maderno** 178.  
**Madesimo**, the 36.  
**Madonna degli Angeli** 111.  
— di Caravaggio 165.  
— della Costa 100.  
— della Guardia 79. 100.  
— di S. Marliano 141.  
— di Montallegro 113.  
— del Monte (near Varese) 135.  
— — (near Vicenza) 198.  
— — (near Ivrea) 72.  
— d'Oropa 75.  
— Pilone 71. 80.  
— del Sasso (Lago Maggiore) 152.  
— — (Lake of Orta) 159.  
— di Tirano 43.  
—, Val 158.  
**Madre**, Isola 155.  
**Madrera**, Val 144.  
**Magadino** 152.  
**Magenta** 76.  
**Magerbach** 39.  
**Maggia**, the 152.  
**Maggiore**, Lago 151.  
**Magliaso** 150.  
**Magnan**, the 107. 110.  
**Magra**, the 115.  
**Magreglio** 137.  
**Maira**, the 36.  
**Majano**, *Bened. da* 330.  
**Majori**, Monte 295.  
**Majoria**, Castle 25.  
**Malagnino** 167.  
**Malain** 3.  
**Malamocco** 213.  
**Malcesine** 180.  
**Malenco**, Val 43.  
**Malero**, the 43.  
**Malghera**, Fort 199.  
**Malgrate** 137. 144.  
**Malgue**, La 19.  
**Malnate** 115.  
**Malo** 198.  
**Malon**, the 75.  
**Mals** 41.  
**St. Mammès** 2.
- Manarola** 114.  
**Mandello** 144.  
**Manerba** 178.  
**Manerbio** 161.  
**Manfrini**, Villa 246.  
**Mantegna**, *Andrea* lii. 125. 191. 200.  
**Mantua** 191.  
**Mantua-Cremona-Milan** 167-65.  
— -Modena 194.  
— -Verona 190.  
**S. Manza** 398.  
**Mapello** 141.  
**Marano** 198.  
**Marburg** 53.  
**Marcaria** 167.  
**S. Marcello** 295.  
**Marches**, Les 23.  
**Marchino**, Villa 149.  
**S. Marco (Simplon)** 26.  
— (Tyrol) 50.  
**Marconi**, *Rocco* 212. 221.  
**Marengo** 76. 78.  
**S. Margherita** 113.  
— a Montici 385.  
**Margorabbia**, the 153.  
**Margreid** 164.  
**St. Marguerite** 20.  
**S. Maria, Monastery (near Claro)** 32.  
— (Stelvio) 41.  
— Assunta 265.  
— delle Grazie 167.  
— Maddalena 265.  
— della Salute 32.  
**Mariana** 398.  
**St. Marie** 16.  
**Marienbergl, Abbey** 41.  
**Marignano** 250.  
**Maritime Alps**, the 80. 111.  
**Markt-Tüffer** 53.  
**Marlia**, Villa 316.  
**Marne**, the 1.  
**Maroggia** 147.  
**Marone** 175.  
**Marseilles** 16.  
**Martigny** 25.  
**St. Marlin**, Pont 72.  
**Martino**, Capo 103.  
**S. Marliano (Lake of Lugano)** 147.  
— (near Rimini) 294.  
— (on the Ticino) 76.  
— (near Verona) 195.  
— d'Albaro, Promontory 88.  
—, **Madonna** di 141.  
—, **Sasso** 141.  
**Martinswand**, the 39.  
**Marzabotto** 295.
- Marziale**, *Marco* 212.  
**Masaccio** li. 331.  
**Maschere**, Le 296.  
**Masein** 34.  
**Masèr**, Villa 246.  
**Masnago** 146.  
**Masolino** 146.  
**Masone** 27.  
**Massa** 116.  
**Massaciuccoli**, Lago di 316.  
**Massilia** 16.  
**Masuccio**, Piz 43.  
**Matarello** 49.  
**Matrei** 44.  
**Matterjoch**, the 73.  
**Mauls** 45.  
**Maures**, Mont. des 19.  
**Maurier**, la 23.  
**S. Maurizio**, Monte 137.  
**Maurizio**, Porto 98.  
**Mazzo** 43.  
*Mazzola, Franc.*, see *Parmeggiano*.  
**Mazzolino**, *Lod.* lix. 266.  
**Mazzoni**, *Guido* l. 260.  
**Meana** 21.  
**Mede** 164.  
**Mediolanum** 120.  
**Meina** 27. 156.  
**Mele**, Capo delle 98.  
**Melegnano** 250.  
**Melide** 147.  
**Mella**, the 164.  
**Melun** 1.  
**Melzi**, Villa 141.  
**Melzo** 167.  
**Menaggio** 142.  
**Mendrisio** 146.  
**Mentone** 101.  
**Merana** 78.  
**Merate** 131.  
**Mesocco** 38.  
—, Val 32. 38.  
**Mesolcina**, Val 38.  
**Mestre** 198. 245.  
**Meursault** 4.  
**Mezz-Isola** 175.  
**Mezzo**, Lago di 191.  
**Mezzo Lombardo** 47.  
— **Tedesco** 47.  
**Mezzola**, Lago di 37.  
**Mezzolago** 179.  
**Miasino** 159.  
*Michael Angelo Buonarroti* liv. 331. 358. 367.  
**St. Michel** 23.  
**St. Michel**, Piz 34.  
**S. Michele** 195.  
— della Chiesa 24.  
— **Lombardo** 47.  
*Michelozzo* 330.

- Migiandone 27.  
 Milan 118.  
   S. Alessandro 131.  
   S. Ambrogio 129.  
   Archivio 124.  
   Arcivescovado 123.  
   Arco del Sempione 133.  
   Arena 133.  
   S. Babila 132.  
   Biblioteca Ambrosiana 127.  
   — Pubblica 124.  
   Brera 124.  
   S. Carlo Borromeo 132.  
   Cassa di Risparmio 124.  
   Castle 133.  
   Cathedral 121.  
   Cavour's Statue 132.  
   S. Celso 131.  
   Cemetery 133.  
   Coins, Coll. of 124.  
   Conservat. of Music 132.  
   Corso Magenta 128.  
   — Porta Venezia 132.  
   — Porta Ticinese 130.  
   — Vittorio Eman. 131.  
   S. Eufemia 131.  
   S. Eustorgio 130.  
   S. Fedele 124.  
   Galleria Vitt. Emanuele 123.  
   — de Cristoforis 132.  
   Giardini Pubblici 132.  
   Leonardo's Last Supper 129.  
   Loggia degli Osii 127.  
   S. Lorenzo 130.  
   S. Maria del Carmine 127.  
   — presso S. Celso 130.  
   — delle Grazie 128.  
   — della Passione 132.  
   — Podone 128.  
   S. Maurizio 128.  
   Monument of Leon. da Vinci 124.  
   Municipio 124.  
   Museo Archeologico 126.  
   Museo Civico 133.  
   S. Nazaro 131.  
   Observatory 124.  
   Ospedale Maggiore 131.  
   Palazzo Borromeo 128.  
   — Ciani 132.  
   — della Città 127.  
   — del Censo 124.  
   — di Giustizia 131.  
   — Litta 128.  
   — Marino 124.
- Milan:  
 Palazzo della Ragione 127.  
 — di Prefettura 132.  
 — Reale 123.  
 — Saporiti 132.  
 — Visconti 130.  
 Piazza d'Armi 133.  
 — del Duomo 121.  
 — de' Mercanti 127.  
 — della Scala 124.  
 Pinacoteca 125.  
 Porta Garibaldi 121.  
 — Lodovica 130.  
 — Ticinese 130.  
 Portico di S. Lorenzo 130.  
 Raphael's Sposalizio 125, 126.  
 S. Satiro 131.  
 Seminary 132.  
 S. Sepolcro 128.  
 S. Stefano 131.  
 Statue of Beccaria 131.  
 — of Carlo Porta 132.  
 — of Cavour 132.  
 — of Leon. da Vinci 124.  
 — of Napoleon I. 124.  
 Teatro della Scala 119, 124.  
 Villa Reale 132.
- Milan-Cremona 165.  
 — -Monza-Como 134, 135.  
 — -Monza-Lecco 134, 135.  
 — -Mortara-Genoa 157.  
 — -Novara-Turin 76, 75.  
 — -Pavia-Voghera 161-165.  
 — -Piacenza-Bologna 250-255.  
 Millesimo 80.  
 Mils 39.  
 Mincio, the 167, 190.  
 S. Miniato 384.  
 — dei Tedeschi 301.  
*Mino da Fiesole* xlix.  
 Miolans 23.  
 Miradolo 164.  
 Miramar, Château 57.  
 Mirandola near Bologna 284.  
 — near Modena 194.  
 Misano 295.  
 Missaglia 134.  
 Mittelberg, the 46.  
 Mitterdorf 52.  
 Mittersee, the 40.  
 Mittewald 45.  
 Mixnitz 52.  
 Modane 23.
- Modena 260.  
 S. Agostino 261.  
 Cathedral 260.  
 S. Francesco 261.  
 Ghirlandina, la 261.  
 Giardino Pubblico 263.  
 Library 263.  
 S. Michele 262.  
 Museo Lapidario 262.  
 Palazzo Reale 262.  
 S. Pietro 261.  
 Pinacoteca (Picture Gallery) 262.  
 Modena-Bologna 255.  
 — -Mantua-Verona 195-190.  
 — -Piacenza-Milan 255-250.  
 Mödling 50.  
 Moesa, the 32, 37.  
 Moesola, Lago 37.  
 Moggiona 392.  
 Mogliano 245.  
 Molgora 135.  
 Moltrasio 139.  
 Momo 76.  
 Monãco 103.  
 Monate, Lago di 146.  
 Moncalièri 77.  
 Monchierro 80.  
 Mondadizza 43.  
 Mondini, Piz 40.  
 Mondovi 80.  
 Moneglia 114.  
 Monfalcone 248.  
 Monguzzo 136.  
 Moniga 178.  
 Monselice 264.  
 Monsummano 317.  
 Montagna 43, 180.  
 — (Heinzenberg) 34.  
*Montagna, Bart.* 196.  
 —, *Benedetto* 196.  
 Montalban, Fort 109.  
 Montallegro, Madonna di 113.  
 Montalto, Castle 72.  
 Montanaro 72.  
 Montario, Castle 195.  
 Montbard 2.  
 Montbéliard 4.  
 Monteboron, Promont. 109.  
 Mont Cenis 24.  
 — Chanve 106.  
 Monte Carlo 103.  
 — Catini 317.  
 — Murlo 322.  
 Montebello (Piedmont) 77.  
 — (near Vicenza) 195.  
 Montecchi 195.

- Montechiaro 78.  
 Monteferrato 323.  
 Montefino 113.  
 Montegrotto 263.  
 Montelinar 9.  
 Montelupo 301.  
 Montereau 2.  
 Monterey 20.  
 Monterone, Monte s.  
 Monte Motterone.  
 Monterosso 114.  
 Monte Rosso 154.  
 Montevecchia 134.  
 Montgeron 1.  
 Monti (near Menton) 103.  
 Monti Pisani 311.  
 Monticelli 166.  
 Montignoso 116.  
 Montjovet 73.  
 —, Dêfile of 73.  
 Montmélian 23.  
 Montone, the 293.  
 Montorfano, the 137.  
 —, Monast. 169.  
*Montorsoli, Gio. Ant.* 88.  
 Montpellier 14.  
 Monza 134.  
 Morbegno 11.  
 Morcole 149.  
 Morello, Monte 328.  
 Moret 2.  
*Moretto* lx. 170.  
 Mori 19. 179.  
 Moriano 316.  
 Morignone 43.  
*Morone, Franc.* 183.  
 Morosaglia 399.  
 Mortara 78. 157.  
 Mortola 101.  
 Motta, La 177.  
 Motta S. Damiano 164.  
 Motterone, Monte 158.  
 Mouchard 3. 5.  
 Mougins 21.  
 Moulins 2.  
 Mozzecane 190.  
 Muggello, Val di 296.  
 Muggia 58.  
 Muggio 117.  
 Mugnone, the 388.  
 Mulhausen 4.  
*Mulinary (Caraccino)* 112.  
 Muotta, the 29.  
 Mur, the 52.  
 Murano 244.  
 Murlo, Monte 322.  
 Muro, Capo di 394.  
 Murz, the 52.  
 Murzanschlag 52.  
 Mustone 178.  
 Musocco 157.
- Musso 143.  
 Mutina 60.  
 Muzzano, Lake of 150.  
 Mylius, Villa 139. 142.  
 Mythen, the 29.  
 Mythenstein, the 29.
- Nabresina 54. 248.  
 Nago 179.  
 Napoule, Golfe de la 20.  
 Narzole 80.  
 Nasen, the 29.  
 Natisone, the 247.  
 Nauders 40.  
 Naudersberg 40.  
 Navacchio 301.  
 Naviglio Adigetto 264.  
 — Grande 76. 120.  
 — della Martesana 120.  
 — di Pavia 120.  
 S. Nazzaro 166.  
 Nebbio 402.  
 Neive 80.  
*Nelli, Ottaviano* lii.  
 Nemasus 12.  
 Nero, Capo 100.  
 Nerone, Bagni di 316.  
 Nervi 113.  
 Nesso 140.  
 Neumarkt 46.  
 Neunkirchen 51.  
 Neustadt 51.  
 Nevers 2. 4.  
 Nicaca 106.  
 Nice 104.  
 Nice-Genoa 104-95.  
 — -Marseilles 21-16.  
 — -Turin 110-12.  
 S. Niccolò (near Piacenza) 77.  
 — (Casentino) 391.  
 S. Nicolao 398.  
 Niclla 80.  
 Nievole, the 317.  
 Nîmes 12.  
 Nivolet, Dent de 23.  
 Nizza 104.  
 Nizza di Monferrato 80.  
 Noli 97.  
 Nolla, the 34.  
 Non, Val di 46. 167.  
 Nonandola 194.  
 Nonsberg, the 116.  
 Notre-Dame de la Garde 18.  
 Noya, La 178.  
 Novara 75. 151.  
 Novella 402.  
 Novi (near Alessandria) 79.  
 — (near Modena) 195.  
 Nuits-sous-Beaune 4.
- Nuits-sous-Ravières 2.  
 Nure, the 167. 253.  
 Nure, Ponte 253.  
 Nus 74.
- Obercilli 53.  
 Oberlaibach 54.  
 Obhladis 40.  
 Odescalchi, Villa, see Raimondi.  
 Oetzthal, the 39.  
 Oggebbio 153.  
*Oggiono, Marco da* 120.  
 Ogliasca 143.  
 Oglio, the 164. 169. 175. etc.  
 Olbia 17.  
 Olcio 144.  
 Oldese 178.  
 Oleggio 157.  
 Olevano 157.  
 Olgiate 135. 145.  
 Olginate, Lago d' 114.  
 Olimpino, Monte 146.  
 Oliveto, Monte 386.  
 Olmeneta 164. 165.  
 Olona, the 120. 145.  
 Oltre 58.  
 Oltrona 145.  
 Ombrone, the 295. 301.  
 Omega 159.  
 Oneglia 98.  
 Onno 144.  
 Optschina 58.  
 Ora 46.  
 Orange 9.  
*Orcagna* 330.  
 Orco, the 75.  
 Orlando, Torre d' 253.  
 Ornavasso 27.  
 Oro, Monte d' 399.  
 Orsera 30.  
 Orso, Colmo dell' 36.  
 Orta 159.  
 —, Lago d' 159.  
 Ortenstein 34.  
 Ortler, the 41.  
 Osogna 32.  
 Ospedaletti 100.  
 Ospedaletto 164. 169.  
 Ossola, Val d' 27.  
 Osteno 151.  
 Ostriconi, the 402.  
 Ottavo, Val d' 316.  
 Ouche, the 3.  
 Oulx 24.  
 Oviglio 80.  
 Ovolo, Monte 295.
- Padernone 48.  
 Padrio, Monte 176.  
 Paese Freddo 43.  
 Padua 199.

- Padua:  
 S. Antonio 200.  
 Baptistery 203.  
 Botanic Garden 204.  
 Carmini 203.  
 Dante's Statue 204.  
 Cathedral 203.  
 Eremitani 202.  
 Gattamelata, Statue of 201.  
 S. Giorgio, Cappella 201.  
 Giotto's Statue 204.  
 S. Giustina 204.  
 Gran Guardia 203.  
 Loggia del Consiglio 203.  
 Madonna dell' Arena 202.  
 Museo Civico 201.  
 Palazzo del Capitaneo 203.  
 — Giustiniani 203.  
 — della Loggia 204.  
 — del Podestà 203.  
 — della Ragione 203.  
 Pinacoteca 201.  
 Prato della Valle 204.  
 Santo, Il 200.  
 Scuola del Carmine 203.  
 — del Santo 201.  
 University 203.  
 Padua-Ferrara-Bologna 263-65.  
 — -Venice 198, 199.  
 — -Verona 198-95.  
*Padovano* 212.  
*Paggi, Giov. Batt.* 85.  
 Paglione or Paillon, the 104, 107.  
 Paina 136.  
 Pajanello 255.  
 Palanzo 136.  
 Palazzolo 169.  
*Palladio, Andrea* xlvii. 196, 211.  
 Pallanza 154.  
 Pallanzeno 27.  
 Pallavicini, Villa 96.  
*Palma Giovane* 212.  
 — *Vecchio* lix. 212, 224.  
 Palmaria 145.  
 Palmieri, Villa 388.  
 Pambio 149.  
 Panaro, the 255, 260, 263.  
 S. Paolo, islet 175.  
 Papia 63.  
 Parabiago 157.  
 Paradisino, Il 391.  
 Parata, Punta della 394.  
 Parè 144.
- Parma 255.  
 Antiquities, Museum of 258.  
 Baptistery 257.  
 Cappella Reale 259.  
 Cathedral 256.  
 Convento di S. Paolo 259.  
 Giardino Ducale 259.  
 S. Giovanni Evangelista 257.  
 Library 259.  
 S. Lodovico 259.  
 Madonna della Steccata 257.  
 Palazzo del Comune 256.  
 — Ducale (Prefettura) 258.  
 — del Giardino 259.  
 — della Pilotta 258.  
 Piazza Grande 256.  
 Picture Gallery 258.  
 Stradone, the 260.  
 Teatro Farnese 259.  
 University 259.  
 Parma, river 255.  
*Parmeggiano* 256.  
 Parolini, Villa 49.  
 Parona 50.  
 Partina 392.  
 Pas-des-Lanciers 16.  
 Pasiano Schiavonesco 247.  
 Paspels 34.  
 Passable, Bay of 110.  
 Passalacqua, Villa 139.  
 Passeriano 247.  
 Pasta, Villa 139.  
 Patavium 199.  
 Paterno 390.  
 Patsch 44.  
 Paulo 263.  
 Pavia 162.  
 — Codogno-Piacenza 165.  
 — -Cremona-Brescia 164.  
 — -Milan 161.  
 — -Valenza-Alessandria 164.  
 — -Voghera (Genoa) 165.  
 Paviolo 265.  
 Payrbach 51.  
 Pazzallo 149.  
 Pecorile 255.  
 Peggau 52.  
 Pegli 96.  
 Pelago 390.  
 Pelestrina 213.  
 Pella 159.  
 Pellino, the 159.  
 Pendolasco 43.
- Peuni, Franc.* lviii.  
 Penzano 137.  
 St. Peray 9.  
 Pergine 48.  
 Peri 50.  
 Pernegg 52.  
 Perosa 72.  
 Perrache 8.  
 Portengo 75.  
*Perugino, Pietro* lii. 281, 362, 375.  
*Peruzzi, Bald.* xlvi.  
 Pesa, the 301.  
 Pescantina 50.  
 Pescatori, Isola dei 155.  
 Peschiera 169, 180.  
 — d'Isèo 175.  
 Pescia 317.  
 Pésio, Val 111.  
 —, Certosa di 111.  
 Pessione 77.  
 St. Peter 54.  
 Petersberg, the 39.  
 Petraja, La 387.  
 Pfannberg, Castle 52.  
 Pfersch-Thal, the 45.  
 Pfunds 40.  
 Pfyv 25.  
 Piacenza 251.  
 — -Bologna 253-55.]  
 — -Codogno-Pavia 165.  
 — -Milan 251.  
 Piadena 167.  
 Pianazzo 36.  
 Pianello 143.  
 Piano, Lago del 151.  
 Piano del Re 100.  
 Piano del Tivano 140.  
 Pianoro 295.  
 Pianzano 246.  
 Piave 246.  
 —, river 246.  
 Piazza, Cima di 42.  
 Piedmont 59.  
 S. Pier d'Àrena 79, 94, 96.  
 S. Pierino 301.  
 S. Piero 322.  
 St. Pierre-d'Albigny 23.  
 Pietole 191.  
 Pietraligure 97.  
 Pietramala 295.  
 Pietra Murata 48.  
 Pietrasanta 116.  
 S. Pietro 176.  
 — in Casale '265.  
 — in Grado 311.  
 Pieve near Pavia 164.  
 — di Cento 265.  
 — S. Giacomo 167.  
 — di Ledro 179.  
 — a Nievole 317.  
 — a Pelve 263.

- Pieve di Sori 113.  
 Pigna 101.  
 Pigna-Andora 98.  
 Pigneron 72.  
 Pilat, Mont S.  
 Pinerolo 72.  
 Pino 153. 402.  
*Pinturicchio, Bern.* lii.  
 Piotta 31.  
 Piottino, Monte 31.  
 Piovere 178.  
 Pioverna, the 143.  
 Pirano 58. 248.  
 Pisa 302.  
   Academy 309.  
   Archives 311.  
   Baptistery 305.  
   Bagni di Nerone 311.  
   Botan. Garden 310.  
   Bridges 304.  
   Campanile 306.  
   Campo Santo 306.  
   Cascine S. Rossore 311.  
   S. Caterina 309.  
   Cathedral 304.  
   Climate 302.  
   S. Francesco 310.  
   S. Frediano 309.  
   Galileo, House of 311.  
   Gombo, Il 311.  
   History of Art 303.  
   Leaning Tower 306.  
   Loggia de' Banchi 311.  
   Luminara, the 304.  
   Lung' Arno 304.  
   S. Maria della Spina 311.  
   S. Michele in Borgo 310.  
   Nat. Hist. Museum 310.  
   S. Nicola 310.  
   Palazzo Agostini 310.  
   — dei Cavalieri 309.  
   — del Comune (Gambacorti) 311.  
   — Lanfranchi-Toscanelli 310.  
   — Lanfreducci-Uppesinghi 310.  
   S. Paolo a Ripa d'Arno 311.  
   Passeggiata Nuova 304.  
   Piazza del Duomo 304.  
   S. Pietro in Grado 311.  
   Sapienza 310.  
   S. Sepolcro 311.  
   S. Sisto 309.  
   Statue of Grand-Duke Cosimo I. 309.  
   — of Ferdinand I. 311.  
   — of Leopold I. 310.  
   Torre dei Gualandi 309.  
   Tower of Hunger 309.  
 Pisa:  
   S. Stefano ai Cavalieri 308.  
   University 310.  
 Pisa-Empoli-Florence 301.  
   — Spezia-Genoa 112-17.  
   — Leghorn 301.  
   — Lucca-Pistoja-Florence 312.  
 Pisa, the Baths of 312.  
*Pisanello, see Pisano, Vittore.*  
 Pisani, Monti 311.  
*Pisano, Andrea* 303.  
   —, *Giovanni* 303.  
   —, *Giunta* 303.  
   —, *Niccolò* xxxviii. 211. 303.  
   —, *Vitt.* (*Pisanello*) 183.  
 Pisogne 175.  
 Pistoja 318.  
 Piteccio 295.  
 Pitzthal, the 39.  
 Piumogna, the 31.  
 Pizzighettone 164.  
 Pizzigone, Monte 160.  
 Pizzo, Monte 167.  
 Pizzo, Villa 139.  
 Pizzocolo, Mte. 178.  
 Plaisance 251.  
 Plan de l'Aiguille 8.  
 Platteinkogl, the 39.  
 Plessur, the 33.  
 Pliniana, Villa 139.  
 Po, the 62. 75. 77. 157 etc.  
 Po di Primaro 265.  
 Poggio 98.  
 Poggio Imperiale, Villa 384.  
 Poggio Renatico 265.  
 Pogliasca 114.  
 Pognana 138.  
 Poiana 198.  
 Poik, the 54.  
 Polcevera, the 79.  
 Poldi, Villa 140.  
 Polesella 265.  
*Pollajuolo, Ant.* and *Piero* 331.  
 Polleggio 32.  
 Pollenzo 80.  
 S. Polo 253.  
 Pölschach 53.  
 Pombia 157.  
 Ponale, Fall of the 179.  
 St. Pons, Monastery 108.  
 Pont d'Ain 22.  
 Pont St. Louis 101.  
 Pont St. Martin 72.  
 Pont des Salassins 73.  
 Pont-de-Veyle 21.  
 Pont-sur-Yonne 2.  
 Pontarlier 3.  
 Pontassieve 390.  
 Ponte di Brenta 198.  
   — Curone 77.  
   — del Diavolo 316.  
   — alla Leccia 399.  
   — S. Marco 169.  
   — Nure 253.  
   — S. Pietro 144.  
   — a Poppi 392.  
   — a Rifredi 387.  
   — a Serraglio 317.  
   — Tresa 150.  
*Ponte, Ant. da* 211.  
 Pontedecimo 179.  
 Pontodera 301.  
 Pontelagoscuro 265.  
 Pontenuovo 399.  
 Pontepetri 295.  
 Pontevico 164.  
 Ponti 78.  
 Pontigny 2.  
 Pontlatzer Brücke, the 48.  
*Pontormo, Jac. da* lviii. 331.  
 Ponzana 75.  
 Poppi 392.  
 Porcari 317.  
 Pordenone 246.  
*Pordenone, Giov. Ant. da* lx. 212. 246. 376.  
 Porlezza 151.  
 Porquerolles 19.  
 Porretta 295.  
 Porta 399.  
 Portcros 19.  
 Portofino 113.  
 Porto Maurizio 98.  
   — Valtravaglia 153.  
   — Vecchio 398.  
   — Venere 115.  
 Portus Classis 285.  
   — Lunae 114.  
   — Naomis 246.  
 Poschiavino, the 43.  
 Poschiavo 43.  
 Possagno 49.  
 Pössnitz 53.  
 Pötschach 51.  
 Pozzolo, Lago di 401.  
 Pozzuolo 76.  
 Prà 96.  
 Pracchia 295.  
 Prad 41.  
 Pragerhof 53.  
 Prato 322.  
 Prato al Soglio 392.  
 Pratolino 296.  
 Pratomagno, the 391.  
 Pratovecchio 392.

- Praz, La 23.  
 Preganziolo 245.  
 Premosello 27.  
 Premstetten 52.  
 Preseglie 180.  
 Prestranek 54.  
*Prete Genovese* 85.  
 Primaro, Po di 265.  
*Primaliccio* 191.  
 Primiero, Val 49.  
 S. Primo, Monte 137. 142.  
 Primolano 49.  
 Prina, Villa 154.  
 Promontorium Sacrum 402.  
 Prosecco 54.  
 Provaglio 174.  
 Prutz 40.  
 Puccini, Villa 322.  
 Puchl 52.  
 Pugieu 22.  
 Puntigam 52.  
 Pusiano 137.  
 —, Lago di 136. 137.  
 Pylimont 22.  
  
 Quaderna 284.  
 Quarsano 140.  
 Quart, Castle 74.  
 Quarto, Villa 387.  
 Quattrocastella 255.  
 St. Quentin 14.  
 Querceta 116.  
*Quercia, Jac. della* 272.  
 Quinto 113.  
  
 Rabenstein, Castle 52.  
 Racconigi 80.  
 Raimondi, Villa 139.  
 Rakek 54.  
 St. Rambert 8.  
 St. Rambert-de-Joux 22.  
*Ramenghi, Bart., see Bagnacavallo.*  
 Rapallo 113.  
 St. Raphael 19.  
*Raphael Santi* xlv. lvi. 125. 281. 331. 375.  
 Raron 25.  
 Ratonneau 16.  
 Raubeneck 51.  
 Rauchenstein 51.  
 Raut-Glacier, the 26.  
 Ravenna 285.  
   Academy 288.  
   St. Agata 288.  
   S. Apollinare in Classe 293.  
   S. Apollinare Nuovo 292.  
   Archives 288.  
  
 Ravenna:  
   Baptistery 287.  
   Biblioteca Comunale 288.  
   Byron's House 289.  
   Cathedral 287.  
   Classe 288.  
   Colonna de' Francesi 294.  
   Crocetta 293.  
   Dante's Tomb 289.  
   S. Domenico 289.  
   S. Francesco 289.  
   S. Giovanni Battista 291.  
   S. Giovanni Evange-  
   lista 291.  
   S. Giovanni e Paolo 290.  
   History of Art 286.  
   Library 288.  
   S. Lorenzo in Cesarea 293.  
   S. Maria in Cosmedin 291.  
   — in Porto 292.  
   — in Porto Fuori 293.  
   — della Rotonda 292.  
   Mausoleum of Galla  
   Placidia 290.  
   — of Theodoric 292.  
   S. Michele in Affricisco 289.  
   S. Nazario e Celso 290.  
   S. Niccolò 288.  
   S. Orso 287.  
   Palace of Theodoric 292.  
   Palazzo Arcivescovile 287.  
   Piazza Maggiore 286.  
   Piazzetta dell' Aquila 287.  
   Pineta, La 294.  
   S. Romualdo 288.  
   Rotonda, the 292.  
   S. Spirito 291.  
   S. Teodoro 291.  
   S. Vitale 290.  
 Raxalp, the 51.  
 Realta 34.  
 Rebbio 145.  
 Recca, the 248.  
 Recco 113.  
 Recoaro 198.  
 Redasco, Piz 42.  
 Reggio 253.  
 Reggiolo 194.  
 Regium Lepidi 253.  
 Regoledo 143.  
 Reichenau 34.  
 Reichenauer Thal 51.  
  
 Reifenstein, Castle 45.  
 S. Remigio, Promont. 154.  
 S. Remo 98.  
 Remouilins 13.  
 St. Remy 12.  
*Reni, Guido Ixi.* 272. 281.  
 Reno, the 255. 265. 271.  
 Renoso, Monte 399.  
 S. Reparata, Monte 402.  
 Resclien 40.  
   — Scheideck, the 40.  
 Resegone, Monte 135. 137.  
 Restonica, the 400.  
 Retrone, the 195.  
 Reuss, the 28. 29.  
 Revoltella, Villa 57.  
 Reyzousse, the 21.  
 Rezzano 253.  
 Rezzata 178.  
 Rezzato 169.  
 Rezzonica, Villa 49.  
 Rezzonico 143.  
 Rhazuns 34.  
 Rhein, the Averser 35.  
   —, Hinter- 34. 31.  
   —, Vorder- 34.  
 Rheinwaldthal, the 35. 37.  
 Rhenus 255.  
 Rhine, the 33. 34. etc.  
 Rhò 76. 157.  
 Rhone, the 6. 8 etc.  
   —, la Perte du 22.  
   —, the Petit 16.  
*Riccio, Andrea (Briosco)*  
   xlvii. 1.  
 Riddes 25.  
 Ried 40.  
 Rietberg 34.  
 Riferdi 323.  
 Rigi, the 29.  
 Riglio, the 167.  
 Rigoli 312.  
 Ringelspitz, the 34.  
 Riola 295.  
 Riomaggiore 114.  
 Ripafratta 312.  
 Ritorto, the 137.  
 Riva (Lake of Como) 37.  
   — (Lake of Garda) 178.  
   — di Palanzo 136.  
   —, Lago di 37.  
 Rivaligure 98.  
 Rivarolo 75. 79.  
 Rivellata, Promont. 402.  
 Riviera, the 32.  
   — di Levante 112.  
   — di Ponente 95.  
 Rivoli 50.  
*Rizzi* 211.  
 Roanne 2.  
*Robbia, Luca della* xlviii.  
   330.

- Robecco 164.  
 Robigliante 111.  
*Robusti, see Tintoretto.*  
 Roccafranca 103.  
 Rocca d'Anfo 180.  
 Roccazione 111.  
 Rocchetta 78.  
 Rocchetta Pass, the 46.  
 S. Rocco 175.  
*Rocco Marconi* 212. 224.  
 Roche Melon, the 24. 71.  
 Roche-Michel, the 24.  
 Rodont Bridge 31.  
 Roffna Gorge, the 35.  
 Rogliano 402.  
 Rognac 16.  
 Rogoredo 161. 250.  
 Rohrbach, the 30.  
 Roja, the 101. 111.  
 Rolo 195.  
 Romagna, the 249.  
 Romagnano 160.  
*Romanino, Girol.* 170.  
 Romano 49.  
 S. Romano 301.  
*Romano, Giulio (Pippi)*  
 xvii. lviii. 191. 194.  
 Romeno 392.  
 Römerbad 53.  
 S. Romolo 100.  
 Roncaglia 167.  
 Ronchi 248.  
 Ronco 153.  
 Ronco, the 285. 293.  
 Rondinaja 295.  
 Rongellen 35.  
 Roppen 39.  
 Roquebrune 103.  
*Rosselli, Cosimo* lii. 331.  
*Rossellino, Ant.* xlix.  
*Rossi, Proserpia de'* 272.  
 Rossillon 22.  
 S. Rossore 311.  
 Rosta 24.  
 Rostino 399.  
 Rothenbrunnen 34.  
 Rotonda, Villa (Brianza)  
 136.  
 — (near Vicenza) 198.  
 Rotondo, Monte 400.  
 Rotta, La 301.  
 Rottoleno 77.  
 Rovenna 139.  
 Roverbella 190.  
 Roveredo (Bernardino)  
 38.  
 (Tyrol) 49.  
 Rovigo 264.  
 Rovio 147.  
 Rubbio 248.  
 Rubiera 255.  
 S. Rufilo 295.
- Russi 285.  
*Rustici, Giov. Fr.* 1.  
 Ruta 113.  
 Rütli, the 29.  
 Rutzbach, the 44.
- Sabbia, Val 180.  
 Sabbio 180.  
 Sabiona 45.  
 Sacile 246.  
 Sacro Monte, the (near  
 Orta) 159.  
 — (near Varallo) 160.  
 Sagor 54.  
 Sagra, La 24.  
 Sagrado 248.  
 Sagro, Monte 116.  
 Sala 140.  
*Salaino, Andrea* liv. 120.  
 Salassins, Pont des 73.  
 Salbertrand 24.  
 Sale 80.  
 Sale Marazzino 175.  
*Salerno, Andr. da* lviii.  
 Salloch 54.  
 Salò 178.  
 Salon 16.  
 Salorino 147.  
 Saluggia 75.  
 Salurn 46.  
 Salussola 75.  
 Salute, La 153.  
 Safuzzo 112.  
 S. Salvatore, near Lucca  
 317.  
 S. Salvatore, Monte 149.  
 S. Salvi 389.  
 Salvore 248.  
*Sammicheli, Mich.* xlvii.  
 183.  
 Samoggia 255.  
 Sampierdarena 94.  
 Sandigliano 75.  
*Sangallo, Ant. da* xlvi.  
 Sanguinarie, Isole 394.  
 Sann, the 53.  
 Sanuazzaro 164.  
 Sanremo 98.  
 Sansobbia, the 97.  
*Sansovino, Andrea* l.  
 —, *Jacopo* xvii. 211.  
 Santerno, the 284.  
 Santhia 75.  
*Santi, Giov.* lvi.  
 Santicolo 176.  
 Santino 154.  
 Santo, Monte 247.  
 Saône, the 4.  
 Saorgio 111.  
 Sarca, the 48.  
 Sarca, Val 48.  
 Sarchè, Le 48.
- Sardagna 49.  
 Sarmato 77.  
 Sarnico 174.  
 Sarnthal, the 46.  
 Saronno 145.  
 Sartirana 157.  
*Sarto, Andr. dell'vii.* 331.  
 375.  
 Sarzana 115.  
 Sarzanella 115.  
 Sassa Plana 34.  
 Sassella 43.  
 Sassina, Val 143.  
 Sasso 294.  
 Sasso di Castro 295.  
 — S. Martino 141.  
 — Rancio, il 143.  
 — del Ferro, the 154.  
 Sassuolo 263.  
 Sau, the 53.  
 Sava 54.  
 Save, the 53.  
 Savena, the 271. 295.  
 Savigliano 112.  
 Savignano 295.  
 Savona 97.  
 —, Santuario di 80.  
 Savoureuse, the 4.  
 Savoy 23.  
 Saxon, Baths of 25.  
 Scale, Monte delle 42.  
*Scamozzi* 211.  
 Scanupia, Monte 48.  
 Scarena 110.  
 Schächenbach, the 29.  
 Schamser Thal, the 35.  
 Schelleberg 45.  
 Sebio 198.  
 Schleglmühl 51.  
 Schuderns 41.  
 Schmirner Thal, the 44.  
 Schneeberg, the 51.  
 Schöllenen, the 30.  
 Schottwien 51.  
 Schwarzau, the 51.  
 Schwyz 29.  
 Scrivia, the 76. 78.  
 Scudelatte 147.  
*Sebastiano del Piombo*  
 lvi. lx. 212. 376.  
 Seben, Monastery 45.  
 Sebenstein, Castle 51.  
 Secchia, the 255. 260.  
 Seckau 53.  
 Secognago 251.  
 Seelisherg 29.  
 Segrino, Lago 136.  
 Segusio 24.  
 Seillon 21.  
 Seitz 53.  
 Sella Lake, the 31.  
 Semedella 58.

- Semmering 51.  
 —, the 51.  
 Sempione 26.  
 Sens 2.  
 Serbelloni, Villa 142.  
 Serchio, the 116. 312.  
 Seregno 135.  
 Sergiana 115.  
 Seriate 168.  
 Serio, the 168.  
 Sermione, Promont. 177.  
 Sernio 43.  
 Serra 263.  
 — di Morignone 43.  
 Serra Mts., the 402.  
 Serraggio 399.  
 Serraglio, Ponte a 317.  
 Serravalle (Apennines)  
   79.  
 — (Tyrol) 50.  
 — (Tuscany) 317.  
 — (Venetia) 246.  
 Serravezza 116.  
 Servola 57.  
 Sesia, the 75. 160.  
 —, Val 160.  
 Sessana 54.  
 Sesto 134. 323.  
*Sesto, Cesare da* 120.  
 Sesto Calende 157.  
 Sestri Levante 113.  
 — Ponente 96.  
 Setta, brook 294.  
 Settignano 393.  
 Settimo 75.  
 Settimo-Vittone 72.  
 Seveso, the 136.  
 Seyssel 22.  
 Siegmundsried 40.  
 Sierre 25.  
 Sieve, the 296.  
 Sigmundskron 46.  
 Signa 301.  
*Signorelli, Luca* lii.  
 Silinen 29.  
 Sill, the 44.  
 Sillaro, the 284.  
 Silz 39.  
 Simone, the Sassi di 393.  
 Sempelu or  
 Simplon 26.  
 — Pass, the 26.  
 Singorna, the 393.  
 Sion 25.  
 Siviano 175.  
 Sizzano 160.  
 Soave, Castle 195.  
 Soazza 38.  
 Soci 392.  
*Sodoma* lviii. 65.  
 Solagna 47.  
 Solano, the 391.
- Solari, Cristofano* l.  
 Solarolo 285.  
 Solbiate 145.  
 Sole, Val di 176.  
 Solero 78.  
 Solferino 169.  
 Soliera 195.  
 Someraro 158.  
 Somma 157.  
 Somma Campagna 169.  
 Sommariva, Villa s. V.  
   Carlotta.  
 Sommazzo 147.  
 Sondalo 43.  
 Sondrio 43.  
 Sopra Villa 136.  
 Soresina 165.  
 Sorgue, the 11.  
 Sorgues 9.  
 Sori 113.  
 Sornico 144.  
 Sospello 110.  
 Souzon, the 3.  
*Speranza, Gior.* 196.  
 Spezia, La 114.  
 Spielfeld 53.  
 Spigno 78.  
*Spinello Aretino* 330.  
 Spinetta 78.  
 Spital 51.  
 Spluga 36.  
 Splügen 36.  
 Splügen Pass, the 36.  
 Spondalunga 42.  
 Spodingig 41.  
 Spertino 97.  
 Sprechenstein, Castle 45.  
 Spresiano 246.  
*Squarcione* 199.  
 Stafflach 44.  
 Staffora, the 77.  
 Stalvedro, Stretto di 31.  
 Stams 39.  
 Stanghella 264.  
 Stanser Horn, the 29.  
 Starkenbach 39.  
 Staziona 177.  
 S. Stefano 98. 251.  
*Stefano* 330.  
 S. Stefano Belbo 80.  
 — in Pane 387.  
 — near Piacenza 251.  
 Steinach 44.  
 Steinbrück 53.  
 Stello, Monte 402.  
 Stelvio 41.  
 Stelvio Pass, the 41.  
 Sterzing 45.  
 Stia 392.  
 Stills 41.  
 Stochades 19.  
 Storo 179.
- Stradella 77.  
 Strambino 72.  
 Strassburg 4.  
 Strassengel, Church of 52.  
 Stresa 155.  
 Stretta 399.  
 Strona, the 27.  
*Strozzi, Bernardo* 85.  
 Stulbaythal, the 44.  
 Stura, the 75. 80. 111.  
   etc.  
 Sturla 113.  
 Succursale di Torino 75.  
 Sugana, Val 48.  
 Suldenthal, the 41.  
 Sulm, the 53.  
 Sulzano 175.  
 Sulzbach Alps, the 53.  
 Sulzberg, the 176.  
 Suna 154.  
 Superga, the 71.  
 Surettahorn, the 36.  
 Susa 24.  
 Susten 25.  
 Suvers 35.  
 Suzzara 194.
- Tabiago 136.  
 Taggia 98.  
 Tagliamento, the 247.  
 Taglioni, Villa 139.  
 Tagstein 34.  
 Tain 8.  
 Talfer, the 46.  
 Taubohorn, the 36.  
 Tanáro, the 77. 80.  
 Tanlay 2.  
 Tanzina, Villa 149.  
 Tarascon 11.  
 Taro, the 253.  
 Tartsch 40.  
 Tassone, Cavo, Canal 265.  
 Tauroeis 17.  
 Tavazzano 251.  
 Taverna, Villa 139.  
 Tavernelle 195.  
 Tavernola, Villa 139.  
 Tavignano, the 400.  
 Tavordo 151.  
 Teglio 43.  
 Telfs 39.  
 Tell's Platte 29.  
 Telvana, Castle 48.  
*Tempesta, Ant.* lx.  
 Tenay 22.  
 Tenda 111.  
 —, Col di 111.  
 Tenno 179.  
 Teplitz 53.  
 S. Tereuzo 115  
 Tergeste 55.  
 Terlago 48.



- TERNITZ 51.  
 Terzo 78.  
 Tesino, the 48.  
 Tessin s. Ticino.  
 Tezze, Le 48.  
 Thalie, the 4.  
 Theodule Pass, the 73.  
 Theresienfeld 51.  
 Thermae Pannonicæ 51.  
 Thomery 1.  
 Thumberg 45.  
 Thuisis 34.  
 Tiarno 179.  
 Ticino, the 31. 152. 157.  
 etc.  
 Ticinum 163.  
 Ticino 198.  
 Tiepolo 212.  
 Tierser Thal 46.  
 Tignale 178.  
 Tiuvavo, the 248.  
 Tinavus 248.  
*Tintoretto, Jac. Ix.* 212.  
 224. 376.  
 Tirano 43.  
 —, Madonna di 43.  
*Tisio, Bev., see Garofalo.*  
 Titan, Ile du 19.  
*Titian Vecellio lix.* 212.  
 224. 376.  
 Tivano, Piano del 140.  
 Toblino, Castle 48.  
 Toblino, Lake of 48.  
 Toccia or  
 Toce s. Tosa.  
 Tonale, Monte 167.  
 Tonnerre 2.  
 Torano, the 116.  
 Torbole 179.  
 Torcello 245.  
 Torno 139.  
 Torrazza di Verolan 75.  
 Torre-Beretti 157. 164.  
 — del Gallo 385.  
 — di Lago 116.  
 — Luserna 72.  
 — d'Orlando 253.  
 — de' Picenardi 167.  
 — di Vezio 142.  
 Torretta 109.  
 Torri 180.  
 Toriggia 139.  
 Tortona 76.  
 Tosa, the 27. 154.  
 Toscolano 178.  
 Töscus 40.  
 Tosi 390.  
 Toulon 19.  
 Tour, La 72.  
 Tourbillon, Castle 25.  
 Tournette, La 109.  
 Tournanche, Val 73.  
 Tournon 8.  
 Tournus 4.  
 Tovo 43.  
 Tradate 146.  
 Trafoi 41.  
 Tramin 46.  
 Trattat, Monte 179.  
 Trautson, Château 44.  
 Tre Croci 146.  
 Trebia, the 77.  
 Trecate 76.  
 Tregolo 136.  
 Treib 29.  
 Tremelone, Island 180.  
 Tremezina, the 140.  
 Tremezzo 140.  
 Tremòla, Val 31.  
 Tremosine 178.  
 Trent 47.  
 Tro Potenze 295.  
 Tresa, the 150.  
 Tresenda 43.  
 Tresero, Piz 42.  
 Treviglio 167.  
 Treviso 245.  
 Trezzo 144.  
*Tribolo* 272.  
 Tridentum 47.  
 Trieste 55.  
 Trifail 54.  
 Trigione, the 400.  
 Trinité, La 110.  
 Trinquetalle 14.  
 Trinsershorn, the 34.  
 Trivella, Castle 111.  
 Trofarello 77. 79.  
 Tronzano 75.  
 Tropæa Augusti 103.  
 Trostburg, Castle 46.  
 Tschingel Glacier, the 25.  
 Tschötsch 45.  
 Tschürgant, the 39.  
 Tuffer, Markt 53.  
*Tura, Cosimo* 266.  
 Turbia 103.  
 Turin 60.  
 Accademia delle Belle  
 Arti 69.  
 — delle Scienze 72.  
 Armoury 63.  
 Arsenal 69.  
 Botanic Garden 70.  
 Campo Santo 71.  
 Capp. del SS. Sudario  
 67.  
 Capuchin Monastery  
 71.  
 Cathedral 67.  
 Cavallo di Marmo 63.  
 Cavour's Monument 67.  
 Cemetery 71.  
 Turin:  
 Consolata, La 68.  
 Corpus Domini 68.  
 Exchange 67.  
 Galleria dell'Industria  
 Subalpina 62.  
 Giardino Pubblico 70.  
 — Reale 64.  
 — della Cittadella 69.  
 — dei Ripari 70.  
 Gran Madre di Dio 70.  
 Industrial Museum 67.  
 Library, Royal 64.  
 —, University 69.  
 S. Massimo 70.  
 Monuments 63. 64. 67.  
 68. 69. 70.  
 Museo Civico 70.  
 Museo Lupatario 69.  
 Museum of Antiquities  
 65.  
 — of Artillery 69.  
 Nat. Hist. Museum 64.  
 Ospedale di S. Giov.  
 Batt. 67.  
 Palazzo dell'Accademia  
 delle Scienze 64.  
 — Carignano 64.  
 — di Città 68.  
 — Madama 62.  
 — Reale 63.  
 Piazza S. Carlo 67.  
 — Carignano 64.  
 — Carlo Alberto 64.  
 — Carlo Emanuele 67.  
 — Carlo Felice 69.  
 — Castello 62.  
 — Savoia 68.  
 Picture Gallery 65.  
 Polytechn. School 70.  
 Porta Palatina 62.  
 Protestant Church 70.  
 Rail. Station 60. 69.  
 S. Spirito 68.  
 SS. Sudario 67.  
 Superga 71.  
 Synagogue 70.  
 Tempio Valdese 70.  
 University 69.  
 Valentino, the 70.  
 Via di Po 62.  
 — Roma 67.  
 Villa della Regina 71.  
 Zoolog. Garden 64.  
 Turin-Alessandria-Pia-  
 cenza 76.  
 — Cuneo 112.  
 — Modane 24. 23.  
 — Novara 75.  
 — Milan 75.  
 — Pinerolo 72.  
 — Aosta 72-74.

Turr, La 35.  
 Turtman 25.  
 Tuscany 296.

*Uccello, Paolo* 331.  
 Uccello, Pizzo 35.  
 Udine 247.  
*Udine, Giov. da* lviii.  
 Umbrail, Piz 42.  
 Unterau 45.  
 Uri, the Bay of 29.  
 Urlo 139.  
 Urner Loch, the 30.  
 Urseren 30.  
 —, the Valley of 30.  
 Usmate 134.  
 Usselle 73.

Vado 97.  
*Vaga, Perino del* lviii.  
 Vaise 6.  
 Val Madonna 158.  
 — d'Ottavo 316.  
 — Rhein 35. 37.  
 — Travaglia 153.  
 Valais, the Canton of 25.  
 Valcarès, Etang the 16.  
 Valdieri, Baths of 111.  
 Valence 9.  
 Valentia 9.  
 St. Valentin auf d. Heide 40.  
 Valenza 75. 158.  
 Valeria, Castle 25.  
 Vallauris 21.  
 Valle 157.  
 Vallecrosia 101.  
 Vallombrosa 390.  
 Valmadonna 75.  
 Valmara, the 152.  
 Valserine Viaduct, the 22.  
 Valstagna 49.  
 Val Tellina, the 43.  
 Valtravaglia 153.  
*Vannucci, see Peruginò.*  
 Vaprio 165.  
 Var, the 21. 108. 110.  
 Vara, the 114.  
 Varallo 160.  
 Varallo-Pombia 157.  
 Varazze 97.  
 Varenna 142.  
 Varese 145.  
 —, Lago di 145.  
 Varignano 179.  
 Varrone, the 143. 179.  
*Vasari, Giorgio* 331.  
 Vassena 144.  
 Vacluse 11.  
*Vecellio, see Titian.*

Vedeggio, the 33.  
 Velasquez, Villa 144.  
 Velleia 252.  
 Venda, Monte 263.  
 Venetia 181.  
**Venice** 204.  
 Accademia delle Belle Arti 223.  
 S. Antonino 242.  
 SS. Apostoli 234.  
 Archaeolog. Museum 221.  
 Archives 236.  
 Arco Bon 233.  
 Arsenal 223.  
 Atrio 214.  
 Banca Nazionale 230.  
 S. Bartolommeo 234.  
 Baths 207.  
 Beccherie 235.  
 Beer 206.  
 S. Biagio 223.  
 Boats 206.  
 Booksellers 207.  
 Botan. Garden 232.  
 Bridge of Sighs 222.  
 Cà da Mosto 230.  
 Cà d'Oro 231.  
 Cafés 206.  
 Campanile of St. Mark 217.  
 Campo di Marte 244.  
 Canal Grande 227.  
 Carmine 237.  
 Carnival, the 208.  
 S. Cassiano 235.  
 Chemist 208.  
 Cemetery Island 244.  
 Climat 208.  
 Clock Tower 217.  
 Colleoni, Statue of 241.  
 Consulates 207.  
 Corso Vitt. Emanuele 235.  
 Corte del Remer 230.  
 Digadi Malamocco 213.  
 Dogana di Mare 227.  
 Doges, Palace of the 218.  
 English Church 208.  
 Erberia 230.  
 S. Eustachio 231.  
 Exhibition of Art 208.  
 Fabbriche Nuove and Vecchie 230.  
 Fish Market 230.  
 Fondaco de' Tedeschi 230.  
 — de' Turchi 231.  
 Fondamenta Nuove 239.  
 — delle Zattere 243.

Venice:  
 S. Francesco della Vigna 241.  
 Frari 235.  
 Frezzaria 208.  
 S. Geremia 231.  
 Gesuiti 239.  
 S. Giacomo di Rialto 235.  
 Giardini Papadapoli 232.  
 — Reale 218.  
 Giardini Pubblici 244.  
 S. Giorgio Maggiore 242.  
 — in Bragora 242.  
 — dei Greci 242.  
 — degli Schiavoni 242.  
 SS. Giovanni e Paolo 240.  
 — Elemosinario 235.  
 — Crisostomo 234.  
 Giudecca, the 243.  
 S. Giuliano 234.  
 Gobbo di Rialto 235.  
 Gondolas 206.  
 Grand Canal 215.  
 History 209.  
 — of Art 211.  
 Hotels 205.  
 Hôtels Garnis 205.  
 Lagune, the 212.  
 S. Lazzaro 245.  
 Library 218. 221.  
 Lido 244.  
 Manin's Tomb 216.  
 — Monument 238.  
 S. Marco 214.  
 S. Marcuola 231.  
 S. Maria Formosa 233.  
 — del Carmine 237.  
 — dei Frari 235.  
 — Mater Domini 235.  
 — de' Miracoli 241.  
 — dell' Orto 239.  
 — della Salute 238.  
 — Zobenigo 237.  
 S. Martino 242.  
 S. Maurizio 238.  
 Merceria, the 234.  
 S. Michele 244.  
 Misericordia, Abbad. 239.  
 S. Moisé 237.  
 Mosaica 208.  
 Municipio 229.  
 Murazzi 213. 245.  
 Museo Civico 231.  
 Nuova Fabbrica 214.  
 Omnibus boats 206.  
 Pal. dell' Ambasciatore 228.

- Venice:
- Palazzo Balbi 228.
  - Barbarigo 229.
  - Barbaro 228.
  - Battaglia 231.
  - Bembo 230.
  - Bernardo 229.
  - Bianca Capello 233.
  - Cà d'Oro 231.
  - de' Camerlinghi 230.
  - Cavalli 228. 229.
  - Contarini 227.
  - Contarini-Fasan 227.
  - Contarini delle Figure 229.
  - Contarini degli Scrigni 228.
  - Corner della Cà Grande 228.
  - Corner-Mocenigo 235.
  - Corner della Regina 231.
  - Corner-Spinelli 229.
  - Correr (Musco Civico) 231.
  - Corte del Remer 230.
  - Da Mula 228.
  - Dandolo 230.
  - Dario-Angarani 227.
  - Ducale (of the Doges) 218.
  - Emo-Treves 227.
  - Erizzo 231.
  - Farsetti 229.
  - Ferro 227.
  - Fini-Wimpffen 228.
  - Fontana 231.
  - Foscarini 228.
  - Frangini 232.
  - Giovanelli 230.
  - Giustiniani 227. 228.
  - Giustinian-Lolin 228.
  - Grassi 228.
  - Grimani 229. 233.
  - — a S. Polo 229.
  - Grimani della Vida 231.
  - Lahia 231.
  - Loredan 229.
  - Malipiero 228. 234.
  - Manfrin 232.
  - Mangilli-Valmarana 230.
  - Manin 230.
  - Manzoni-Angarani 228.
  - Michieli dalle Colonne 231.
- Venice:
- Palazzo Mocenigo 228.
  - Moro-Lin 228.
  - Morosini 238.
  - Mosto (Cà da) 230.
  - Patriarcale 233.
  - Persico 229.
  - Pesaro 231.
  - Pisani 238.
  - — Moreta 229.
  - — a S. Paolo 229.
  - Querini 233.
  - Reale 213.
  - Rezzonico 228.
  - Sagredo 231.
  - Tiepolo-Stürmer 229.
  - Tiepolo-Zucchelli 227.
  - Trevisani 233.
  - Tron 231.
  - Vendramin-Calergi 231.
  - Venier 227.
  - Zichy-Esterhazy 228.
- Palocapa, Monum. of 238.
- S. Pantalone 237.
- Pescheria 230.
- Physician 208.
- Photographs 207.
- Piazza of St. Mark 213.
- Piazzetta, the 218.
- S. Pietro di Castello 244.
- Piomhi, the 222.
- Ponte di Rialto 230.
- della Paglia 223.
- de' Sospiri 222.
- Storto 233.
- Porta del Paradiso 233.
- Post Office 207.
- Pozzi, the 222.
- Prisons 222.
- Private Apartments 205.
- Procurazie 213.
- Prot. Church 235.
- Railway Station 204. 232.
- Redentore 243.
- Restaurants 205.
- Rialto, the 230.
- Riva degli Schiavoni 223.
- S. Rocco 236.
- S. Salvatore 234.
- Scala dei Giganti 219.
- Scalzi 232.
- Scuola di S. Marco 241.
- dei Carmini 237.
- Venice:
- Scuola della Carità 223.
  - di S. Rocco 237.
  - dell'Angelo Custode 235.
  - Sea-baths 207.
  - S. Sebastiano 243.
  - Seminario Patriarcale 227.
  - Shops 208.
  - S. Simeone Piccolo 232.
  - Spedale civile 240.
  - Statue of Colleoni 241.
  - Steamers 207.
  - S. Stefano 238.
  - Telegraph Office 207.
  - Theatres 208. 234. 238.
  - Torre dell'Orologio 217.
  - Traghetti 206.
  - Trattorie 205.
  - Vegetable Market 230. 235.
  - S. Vitale 228.
  - S. Zaccaria 233.
  - Zecca 218.
- Venice-Trieste 245-46.
- Verona 199-95.
- Venere, Porto 115.
- Ventimiglia 101.
- Ventonx, Mont 11.
- Venusti, Marcello Ivi.
- Verbanus, Lacus 152.
- Vercelli 75.
- Verde, Capo 98.
- Verdello 167.
- Vergato 295.
- Vergiate 157.
- Vergnasco 75.
- Vermanagna, the 111.
- Vernazza 114.
- Vernia, the 393.
- Verola Nuova 164.
- Verona 182.
- Amphitheatre 184.
- S. Anastasia 186.
- Arco de' Leoni 187.
- Arena 184.
- S. Bernardino 187.
- Biblioteca Capitolare 186.
- Campo Santo 189.
- Cappella de' Pellegrini 187.
- Casa Mazzanti 185.
- dei Mercanti 185.
- Castello S. Pietro 190.
- Vecchio 186.
- Cathedral 186.
- Cemetery 189.
- Corso Cavour 184.
- Dante's Statue 185.

- Verona:
- S. Fermo Maggiore 187.
  - Giardino Giusti 190.
  - S. Giorgio in Braida 186.
  - S. Giovanni in Fonte 186.
  - Guardia Antica and Nuova 184.
  - History of Art 183.
  - Loggia, la 185.
  - S. Maria Antica 185.
  - in Organo 189.
  - della Scala 188.
  - Municipio 185.
  - Museo Civico 187.
  - Lapidario 184.
  - S. Nazario e Celso 189.
  - Palazzo del Consiglio 185.
  - Bevilacqua 186.
  - Canossa 187.
  - de' Giureconsulti 185.
  - Guastaverza 184.
  - Maffei 185.
  - Pompei 187.
  - Portalupi 187.
  - Tedeschi 188.
  - Pellegrini, Capp. 187.
  - Piazza Brà 184.
  - delle Erbe 184.
  - dei Signori 185.
  - Vittorio Emanuele 184.
  - S. Pietro Martire 186.
  - Ponte delle Navi 187.
  - della Pietra 190.
  - Porta de' Borsari 184.
  - Nuova 183.
  - Palio 187.
  - Stuppa 187.
  - Vescovo 182.
  - Portone della Brà 184.
  - Roman Theatre 190.
  - Teatro Filarmonico 184.
  - Tomb of Juliet 190.
  - Tombs of the Scaligers 185.
  - Town Hall 185.
  - S. Zeno Maggiore 187.
  - Verona-Milan 169-67.
  - Mantua-Modena 190-195.
  - Venice 195-99.
  - Verona, La Chiusa di 50.
  - Veronese, Paolo lx. 183.
  - 212. 219. 243. 246.
  - Verrex 73.
- Verrocchio, Andrea* xlix. 331. 362.
  - Verruca, La 311.
  - Verruca, the (Trent) 48.
  - Verzasca, the 33.
  - Vescovato 399.
  - Vesontio 5.
  - Vespolate 157.
  - Vestone 180.
  - Veyle, the 21.
  - Vezia 33.
  - Vezzano 48. 255.
  - Via Emilia 249. 253.
  - Flaminia 249.
  - Via Mala, the 35.
  - Viareggio 116.
  - Vicenza 195.
  - Vicetia 195.
  - Viège 25.
  - Vienne 8.
  - Vieux-Mont-Ferrand 22.
  - Vigese, Monte 295.
  - Vigevano 157.
  - S. Vigilio 180.
  - Vignola 263.
  - Vigo 295.
  - Vigolo 48.
  - Vigoni, Villa 142.
  - Villa (near Lucca) 317.
  - (near Domo d'Ossola) 27.
  - Villa Martis 24.
  - Villafranca (near Asti) 77.
  - (near Nice) 109.
  - (near Verona) 190.
  - Villamaggiore 161.
  - Villanuova (near Asti) 77.
  - (near Verona) 195.
  - Villa Romano 136.
  - Villastellone 79.
  - Villefranche (near Aosta) 74.
  - (near Nice) 109.
  - Villeneuve St. Georges 1.
  - la-Guiard 2.
  - sur-Yonne 2.
  - Villetta 167.
  - St. Vincent 73.
  - Vintschgau, the 40. 41.
  - Vignola 144.
  - Viso, Monte 71. 111.
  - Visp or
  - Vispach 25.
  - Vite, *Timoteo della* lviii. 281.
  - Vitelli, Val 42.
  - S. Vittore 38.
  - Vittoria 80. 110.
  - Vittoria, Aless.* 121.
- S. Vittorio 110.
  - Vittuone 76.
  - Vitznau 29.
  - Vivarini, Antonio* and *Bart.* lii. 211.
  - Vivario 399.
  - Vizzavona 399.
  - Vobarno 180.
  - Vogelberg, the 37.
  - Voghera 77.
  - Alessandria-Turin 76. 77.
  - Pavia-Milan 165-61.
  - Piacenza 77.
  - Vogogna 27.
  - Volciano 180.
  - Volterra 301.
  - Volterre 145.
  - Voltri 96.
  - Voragine 97.
  - Vöslau 51.
  - Vouache, Mont 22.
  - Vougeot 3.
  - Voujaceut 4.
  - Waggis 29.
  - Waidbruck 46.
  - Waldensian Valleys, the 72.
  - Wartenstein, Castle 51.
  - Wasen 30.
  - Wattingen 30.
  - Weilburg, Chât. 51.
  - Weinzettelwand, the 51.
  - Weisseneck, Castle 53.
  - Weiskugel, the 41.
  - Welfenstein, Castle 45.
  - Wildon, Castle 53.
  - Wilten, Abbey 44.
  - Windgollen, the 29.
  - Wipbach, the 248.
  - Worms s. Bormio.
  - Yères, the 1.
  - Yonne, the 2.
  - Zampieri, see Domesnichino.*
  - Zams 40.
  - Zapporthorn, the 36.
  - Zaule 57.
  - Zenna 152.
  - S. Zeno 164.
  - Zibio, Monte 263.
  - Zillis 35.
  - Zinasco 164.
  - Zirknitzer See, the 54.
  - Zirl 39.
  - Zoagli 113.
  - Zuccaro, Fed.* lx.

Leipzig: Printed by Breitkopf and Härtel.







